


**MECHANICAL FLOOR PLAN**  
SCALE: 1/4" = 1'-0"

- MECHANICAL SYMBOLS**
- (SD) NEW SUPPLY DIFFUSER
  - (RG) NEW RETURN AIR GRILLE
  - EXHAUST GRILLE/FAN
  - REMOTE TEMPERATURE/HUMIDITY SENSORS
  - THERMOSTAT, MOUNTED AT 48" AFF
  - DUCT-MOUNTED SMOKE DETECTOR
  - NEW DUCTWORK
  - 32"x14" SIZE OF RECTANGULAR DUCT
  - 6"Ø SIZE OF ROUND DUCT
  - FLEXIBLE DUCTWORK
  - FLOOR PLAN NOTE DESIGNATION
  - S.A. SUPPLY AIR
  - R.A. RETURN AIR
  - EXH. EXHAUST AIR
  - TRANSITION IN DUCT SIZE
  - ELBOW WITH TURNING VANES
  - MANUAL VOLUME DAMPER
  - MANUAL VOLUME DAMPER
  - SUPPLY AIR DUCT UP/DOWN
  - RETURN AIR DUCT UP/DOWN
  - EXHAUST AIR DUCT UP/DOWN
  - CHANGE IN ELEVATION UP (UP) DOWN (DN) IN DIRECTION OF FLOW
  - RTU-1 SCHEDULED MECHANICAL EQUIPMENT



**DINING ROOM DIFFUSER DETAIL**  
SCALE: NONE

**AIR BALANCE SCHEDULE**

SUPPLY AIR UNIT	OUTSIDE AIRFLOW (CFM)	RETURN AIRFLOW (CFM)	SUPPLY AIRFLOW (CFM)	OA/SA %	EXHAUST AIR UNIT	EXHAUST AIRFLOW (CFM)
DOAS-1	3,300	0	3,300	100.0%	KEF-1	2584
RTU-1	900	3,100	4,000	22.5%	KEF-2	775
					KEF-3	525
					EF-1, EF-2	225
<b>TOTAL</b>	<b>4,200</b>	<b>3,100</b>	<b>7,300</b>	<b>57.5%</b>	<b>TOTAL</b>	<b>4,109</b>
RESULTING BUILDING PRESSURIZATION						91 CFM

THE BUILDING HVAC SYSTEM SHALL BE BALANCED BY NATIONAL TAB HIRED BY THE OWNER. CONTACT Dan Hertenstein - National TAB at: 616-215-1543 - DAN@NATIONALTAB.COM


**OUTDOOR AIR CALCULATIONS**

UNIT	Area (sqft)	OCCUPANCY CLASSIFICATION	Occupant Density #/1000 sqft	People outdoor airflow rate in breathing zone (Rp) cfm/person	Area outdoor airflow rate in breathing zone (Ra) cfm/sqft	Exhaust airflow rate cfm/sqft	Breathing zone outdoor airflow (Vbz) cfm/sqft	Zone air distribution effectiveness (Ez)	Zone outdoor airflow (cfm)	
DOAS-1	884	Dining rooms	10	7.5	0.18		623	0.8	774	
RTU-1	173	Corridors	0	0	0.06		10	0.8	13	
									Total	792


- MECHANICAL PLAN NOTES:**
- LOCATION OF DUCT MOUNTED SMOKE DETECTOR. PROVIDE REMOTE ENUNCIATOR AUDIO/VISUAL. VERIFY LOCATION WITH FIRE MARSHAL PRIOR TO INSTALLATION. REFER TO SPEC SHEET MPO FOR ADDITIONAL INFORMATION.
  - LOCATION OF MANUAL PULL STATION. INSTALL PER THE MANUFACTURERS REQUIREMENTS.
  - LOCATION OF RTU THERMOSTATS. GC TO LABEL EACH THERMOSTAT.
  - LOCATION OF RTU TEMPERATURE AND HUMIDITY SENSORS MOUNTED 7'-0" AFF.
  - ALL KITCHEN DUCTWORK IS INTENDED TO BE ROUTED THROUGH OR BETWEEN TRUSSES. COORDINATE WITH STRUCTURAL ENGINEER AND TRUSS MANUFACTURER FOR TRUSS BLOCKOUT DIMENSIONS.
  - EXHAUST HOOD PROVIDED BY OTHERS. INSTALLED BY THIS CONTRACTOR PER THE MANUFACTURERS INSTRUCTIONS.
  - TRANSITION AND CONNECT 8"x9" GREASE DUCT TO EXHAUST HOOD WITH AS SHOWN. ROUTE DUCT UP AND CONNECT TO EXHAUST FAN. OFFSET AS NECESSARY TO MISS ROOF STRUCTURE, AND TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES, AND 5'-0" FROM PARAPET WALLS. ALL GREASE DUCT IS TO BE INSTALLED WITH DUCT WRAP AS DETAILED AND PER THE MANUFACTURERS REQUIREMENTS FOR 0" CLEARANCE TO COMBUSTIBLES.
  - TRANSITION AND CONNECT 15"x15" GREASE DUCT TO 12"x10" COLLARS ON EXHAUST HOODS. ROUTE DUCT UP AND CONNECT TO EXHAUST FAN. OFFSET AS NECESSARY TO MISS ROOF STRUCTURE, AND TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES, AND 5'-0" FROM PARAPET WALLS. REFER TO DETAIL ON SHEET M2. ALL GREASE DUCT IS TO BE INSTALLED WITH DUCT WRAP AND ACCESS DOORS AS DETAILED AND PER THE MANUFACTURERS REQUIREMENTS.
  - COORDINATE DUCT ROUTING WITH LIGHTING.
  - EXPOSED DUCTWORK SHALL BE OF PAINTLOCK CONSTRUCTION AND PAINTED PER THE DIRECTION OF ARCHITECT.
  - RETURN AIR DUCT LOCATED BETWEEN ROOF TRUSSES. OPEN END OF DUCTWORK TURNED UP TOWARD STRUCTURE WITH A MINIMUM 8" CLEARANCE TO DECK.
  - SUPPORT EXHAUST FAN FROM STRUCTURE AS REQUIRED BY THE MANUFACTURER.
  - COORDINATE WITH STRUCTURAL TO BLOCK OUT JOISTS AS REQUIRED TO RUN DUCT THROUGH STRUCTURE.
  - MOUNT CONDENSING UNIT ON ROOF AS DETAILED AND AS REQUIRED BY THE MANUFACTURER. CONNECT REFRIGERANT PIPING AS REQUIRED BY THE MANUFACTURER. SEE ARCHITECTURAL PLANS FOR MOUNTING DETAIL.
  - RETURN DUCT TO BE ROUTED BETWEEN JOISTS, AS HIGH AS STRUCTURE WILL ALLOW.
  - ROUTE 10"Ø EXHAUST DUCT UP THROUGH ROOF TO ROOF CAP. MAINTAIN 10'-0" CLEARANCE TO ALL OUTDOOR AIR INTAKES.
  - HOOD SHALL BE PROVIDED WITH FACTORY PRE-ENGINEERED PACKAGE AND A PRE-ENGINEERED UL-300 FIRE SUPPRESSION SYSTEM. SEE HOOD DRAWINGS FOR DETAILS.
  - INSTALL CAPTIVE AIR INBE WINDBAND EXTENSION FOR KEF-2 PROVIDED BY KITCHEN EQUIPMENT SUPPLIER.
  - TRANSITION AND CONNECT 10"Ø ALUMINUM DUCT TO CONDENSATE HOOD. ROUTE DUCT UP AND CONNECT TO EXHAUST FAN, OFFSET AS NECESSARY TO MISS ROOF STRUCTURE, AND TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES AND 5' FROM PARAPET WALLS.
  - 4" PVC/CPVC INTAKE AND 4" PVC/CPVC EXHAUST FROM GAS WATER HEATER UP TO ROOF. COMBINE RIGHT BEFORE ROOF PENETRATION WITH CONCENTRIC VENT KIT. WATER HEATER PROVIDED AND INSTALLED BY OTHERS.

**MECHANICAL GENERAL NOTES:**

- COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
- THIS CONTRACTOR SHALL PERFORM ALL WORK INDICATED AND/OR AS REQUIRED FOR THE PROPER INSTALLATION AND OPERATION OF THE MECHANICAL SYSTEMS.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATIONS OF DIFFUSERS.
- INSTALL ALL DUCT, PIPE, ETC. AS HIGH AS POSSIBLE.
- DUCT SIZES SHOWN ARE ACTUAL SHEET METAL SIZES AND INCLUDE A 1/2 INCH ALLOWANCE FOR DUCT LINER WHERE APPLICABLE.
- PROVIDE FLEXIBLE CONNECTION BETWEEN DUCTWORK AND ROOFTOP UNITS, EXHAUST FANS, AND OTHER MOTORIZED EQUIPMENT.
- NO DUCT SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
- ALL EXPOSED DUCT WORK SHALL BE PAINTED. REFER TO ARCHITECTURAL PLANS FOR DETAILS.



**DIFFUSER DETAIL**  
SCALE: NONE



### REMOTE TEMPERATURE AND HUMIDITY SENSOR WIRING

ALL LOW VOLTAGE WIRING FOR THE HVAC SYSTEM IS TO BE PROVIDED AND INSTALLED BY THE HVAC CONTRACTOR.




Figure 1. Field Wiring (150' [46m] or shorter runs)

Wire runs of 150' (46m) or less:

Use two separate shielded cables containing 18AWG minimum, twisted pair conductors with overall shield, Belden type 8760 or 88760 (plenum) or equivalent. Connect both cable shield drain wires as shown in figure 1.

Wire runs over 150 feet (46m):

Use a local, isolated 24VAC transformer such as Lennox cat #18M13 (20VA minimum) to supply power to RH sensor as shown in figure 2. Use one shielded cable containing 20AWG minimum, twisted pair conductors with overall shield. Belden type 8762 or 88760 (plenum) or equivalent.






Figure 2. Field Wiring (150' [46m] or longer runs)

### LENNOX HUMIDITY SENSOR WIRING

FOR GENERAL INFORMATION ONLY. REFER TO THE MANUFACTURERS INSTALLATION INSTRUCTIONS PROVIDED WITH THE EQUIPMENT FOR EXACT INSTALLATION INSTRUCTIONS AND REQUIREMENTS.



### Installation

#### DC Conductors

Distance from Unit to Control	Recommended Wire Size
0 - 150 feet	22 gauge
0 - 45.7 m	0.33 mm <sup>2</sup>
151 - 240 feet	20 gauge
46 - 73.1 m	0.50 mm <sup>2</sup>
241 - 385 feet	18 gauge
73.5 - 117.3 m	0.75 mm <sup>2</sup>
386 - 610 feet	16 gauge
117.7 - 185.9 m	1.3 mm <sup>2</sup>
611 - 970 feet	14 gauge
186.2 - 295.7 m	2.0 mm <sup>2</sup>

Figure 58. Typical field wiring diagrams for electromechanical





Figure 59. ReliaTel™ conventional thermostat field wiring diagrams(a)



(a) Not compatible with VAV units.

Figure 60. ReliaTel™ options module (RTOM board)




Figure 61. ReliaTel™ relative humidity sensor (dehumidification option)





Figure 62. ReliaTel™ relative humidity sensor (field supplied)

### TRANE HUMIDITY SENSOR WIRING

FOR GENERAL INFORMATION ONLY. REFER TO THE MANUFACTURERS INSTALLATION INSTRUCTIONS PROVIDED WITH THE EQUIPMENT FOR EXACT INSTALLATION INSTRUCTIONS AND REQUIREMENTS.

ROOFTOP UNIT SCHEDULE																				
MARK	MFR	MODEL NO.	NOM. TONS	EVAP. CFM	EXT. STATIC P. IN. WG (NOTE 2)	COOLING				HEATING (GAS)		ELECTRICAL			REMARKS					
						TOTAL BTUH	SENS. BTUH	AMB.	EVAP. EAT DB/WB	BTUH INPUT	BTUH OUTPUT	VOLT/Ø/HZ	BLOWER MOTOR	MIN. MCA (AMPS)		MIN. MOCP (AMPS)	MINIMUM OUTDOOR AIR (CFM)	TOTAL WEIGHT (LBS)	IEER	FREON
RTU-1	CARRIER	48HCFD14K2	12.5	5,000	1.0"	151,510	118,530	45	80/67	240	195	208/3/60	3 HP	60	70	400	1715	13.9	R-410a	1,2,3,4,5,6,7,8

- NOTES:**
- PROVIDE DIGITAL CONTROLS, HIGH PERFORMANCE WITH FDD OUTDOOR AIR ECONOMIZER WITH DRY BULB CONTROL, SINGLE ZONE VAV (MSAV), BAROMETRIC RELIEF DAMPER, TIME DELAY ON COMPRESSOR RE-START, CRANKCASE HEATER, BAROMETRIC RELIEF DAMPER, DRAIN PAN OVERFLOW SWITCH, DISCHARGE AIR TEMPERATURE SENSING, HINGED ACCESS DOORS, SMOKE DETECTOR MOUNTED IN RETURN, AND STANDARD COOLING DOWN TO 0°F FOR EACH UNIT. OUTDOOR AIR DAMPER TO FULLY CLOSE VV FAN SHUTDOWN FOR ALL UNITS.
  - EXTERNAL STATIC PRESSURE LISTED REPRESENTS STATIC PRESSURE REQUIRED FOR DUCTWORK AND DIFFUSERS OUTSIDE THE HVAC UNIT COMPLETELY INDEPENDENT OF ANY PRESSURE DROP THROUGH THE HVAC EQUIPMENT INCLUDING BUT NOT LIMITED TO FILTERS, COILS AND ECONOMIZERS. THE FAN AND MOTOR SHALL BE SIZED APPROPRIATELY TO MEET THIS DEFINITION OF EXTERNAL STATIC PRESSURE.
  - PROVIDE COMMERCIAL 7-DAY PROGRAMMABLE HEAT/COOL/AUTO CHANGEOVER THERMOSTAT WITH ECONOMIZER OUTPUT AND REMOTE, TEMPERATURE AND HUMIDITY SENSOR FOR EACH UNIT (HONEYWELL VISION PRO 8000 OR EQUAL), ECONOMIZER/OUTDOOR AIR DAMPER IS TO CLOSE DURING UNOCCUPIED HOURS.
  - PROVIDE 14" HIGH (AT LOWEST POINT) PRE-FABRICATED INSULATED ROOF CURB.
  - PROVIDE HAIL GUARDS FOR EACH UNIT.
  - PROVIDE FACTORY INSTALLED UNIT MOUNTED CIRCUIT BREAKERS.
  - MECHANICAL CONTRACTOR SHALL CLEAN OR PROVIDE ALL NEW MERV 13 FILTERS ON DAY OF TURNOVER.
  - PROVIDE HOT GAS REHEAT FOR HUMIDITY CONTROL (HUMIDITROL)




**GREASE HOOD DETAIL**  
SCALE: NONE

EXHAUST FAN SCHEDULE									
MARK	MFR	MODEL	CFM	EXTERNAL STATIC P. IN. WG.	RPM	ELECTRICAL		FAN TYPE	NOTES
						VOLT/Ø/HZ	PAWR		
EF-1	COOK	GC-160	150	0.25	1099	120/1/60	50.4 W	CEILING EXH.	1
EF-2	↑	GC-146	75	↑	900	↑	30.3 W	↑	1


- NOTES:** 1. PROVIDE CEILING GRILLE, INTEGRAL BACK DRAFT DAMPER, AND ROOF CAP.

DIFFUSER SCHEDULE						
MARK	MFR	MODEL	NECK SIZE	FACE SIZE	FINISH	REMARKS
SD-1	TITUS	TMR	12"Ø	22"Ø	WHITE	FIELD PREP FOR PAINTING
SD-2	↑	TMS/3	10"Ø	24"x24"	↑	↑
SD-3	↑	PAR/3	↑	↑	↑	RETURN - NO DEFLECTOR
SD-4	↑	T35Q4	8"Ø	↑	↑	THERMAL VAV DIFFUSER
SD-5	↑	TMS/3	6"Ø	12"x12"	↑	WITH O.B. DAMPER AND TRM KIT
SD-6	↑	↑	8"Ø	12"x12"	↑	WITH TRM KIT
RG-1	AMER. LOUVER CO.	STRATUS	20"x20"	24"x24"	↑	SEE NOTE 1.
RG-2	TITUS	3BORL	8"x8"	↑	↑	↑
RG-3	↑	PAR/3	10"x22"	12"x24"	↑	↑


- NOTES:** 1. RETURN GRILLE TO BE PLASTIC FILTER RETURN, FILTER TO BE AMERICAN AIR FILTER (AAF) FRONTLINE GREEN 1", WITH AAF AMERIFRAME SIZE 20X20X1.




**ROUND DUCT TAKE OFF DETAIL**  
SCALE: NONE



**RECTANGULAR DUCT TAKE OFF DETAIL**  
SCALE: NONE




**ROOF CONDENSING UNIT MOUNTING DETAIL**  
SCALE: NONE



**DOWNFLOW ROOF TOP UNIT DETAIL**  
SCALE: NONE

**FIRE RATED ENCLOSURE - GREASE DUCTS**

- THERMAL CERAMICS FIREMASTER FASTWRAP XL IS TESTED TO ASTM E2336 AND UL LISTED PER HNK7.G18 TO PROVIDE ZERO CLEARANCE TO COMBUSTIBLES AND TO PROVIDE A 1- OR 2- HOUR ENCLOSURE. THROUGH PENETRATIONS FIRESTOP SYSTEMS ARE TESTED IN ACCORDANCE WITH ASTM E 814 (UL 1479). ICC-ES APPROVAL PER REPRDT ESR 2213 OR ESR 2832.
- COMPLIANT TO THE FOLLOWING CODES:  
NFPA 96  
INTERNATIONAL MECHANICAL CODES  
UNIFORM MECHANICAL CODE  
CALIFORNIA MECHANICAL CODE
- INSULATION APPLIED IN TWO LAYERS WITH TIGHT COMPRESSION JOINT ON BOTH LAYERS AT ALL JOINTS.
- MINIMUM 16 GAUGE CARBON STEEL (OR 18 GAUGE STAINLESS STEEL) RECTANGULAR OR ROUND GREASE EXHAUST DUCT
- INSTALL UL LISTED AND LIQUID TIGHT THERMAL CERAMICS FASTDOOR XL ACCESS DOORS AT ALL CHANGES IN DIRECTION AND AT MINIMUM EVERY 20 FT ON HORIZONTAL RUNS.
- SUPPORT HANGER SYSTEMS DO NOT NEED TO BE WRAPPED PROVIDED THE HANGER RODS ARE MINIMUM OF 3/8 IN. DIAMETER AND SUPPORTS ARE MINIMUM 2 X 2 X 1/8 IN. STEEL ANGLE OR SMACNA EQUIVALENT SUPPORT SYSTEM.
- THERMAL CERAMICS DUCT WRAP SHALL BE INSTALLED DIRECTLY ONTO THE DUCT AND APPLIED FROM THE HOOD CONNECTION TO THE CONNECTION TO THE FAN.
- THERMAL CERAMICS DUCT ENCLOSURE SYSTEM SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS AND UL LISTINGS.



**Morgan ThermalCeramics**  
P.O. Box 923  
Augusta, Georgia 30903-0923  
Phone: (706) 560-4038

**SEQUENCE OF OPERATION**

- THE ROOF TOP UNITS FOR THE BUILDING ARE PROVIDING SPACE CONDITIONING AND PROVIDING MAKE UP AIR FOR THE KITCHEN EXHAUST SYSTEM. THE ROOF TOP UNITS AND KITCHEN EXHAUST FANS ARE INTERLOCKED AND CONTROLLED BY THE CAPTIVE AIR GASLINK SYSTEM
  - PACKAGED ROOFTOP DOAS AND HIGH OUTDOOR AIR UNIT
    - UNIT SHALL CONSIST OF SUPPLY AIR FAN, FILTERS, DX COOLING COIL, GAS-FIRED HEAT SECTION, AND A 7-DAY PROGRAMMABLE THERMOSTAT INTERFACE.
    - DOAS-1
      - OCCUPIED MODE: DURING OCCUPIED MODE, THE UNIT SHALL OPERATE AS A DELEGATE OUTDOOR AIR SUPPLY UNIT PROVIDING 100% CONDITIONED OUTDOOR AIR FOR MAKE UP AIR TO THE KITCHEN EXHAUST HOODS, AND PROVIDING SPACE CONDITIONING IN THE KITCHEN. BASED ON THE ROOFTOP UNITS HOURS OF OCCUPANCY, START THE UNIT AT THE BEGINNING OF OCCUPANCY AND SHUT DOWN THE UNIT AT THE END OF OCCUPANCY (NOTE: OUTSIDE AIR DAMPER WITHIN THE RTU SHALL OPEN AND THEN THE RTU SHALL START). THE UNIT SHALL START EARLIER AS DETERMINED BY THE PROGRAM FOR EARLY WARM-UP OR COOL DOWN. ON A SYSTEM STARTUP, THE RTU FAN SHALL START AND RUN CONTINUOUSLY AND THE INTERNAL FACTORY CONTROLS SHALL BE ENABLED. BASED ON THE SPACE TEMPERATURE SENSOR, THE UNIT SHALL CYCLE THE HEATING/COOLING TO MAINTAIN THE SPACE TEMPERATURE SETPOINT. THE UNIT SHALL ALSO OPERATE WHENEVER ANY ONE OF THE KITCHEN EXHAUST FANS IS OPERATING EITHER BY MANUAL OR AUTOMATIC MEANS AS DIRECTED BY THE GASLINK SYSTEM.
      - HUMIDITY CONTROL: UPON DETECTION OF RELATIVE HUMIDITY ABOVE 55%, THE UNIT SHALL CYCLE INTO DEHUMIDIFICATION MODE AND ENGAGE THE HOT GAS REHEAT COIL TO REMOVE HUMIDITY IF NOT ALREADY IN COOLING.
    - RTU-1
      - OCCUPIED MODE: DURING OCCUPIED MODE, THE UNIT SHALL OPERATE AS A HIGH OUTDOOR AIR SUPPLY UNIT PROVIDING A MIX OF CONDITIONED RECIRCULATED AIR AND OUTDOOR AIR FOR MAKE UP AIR TO THE KITCHEN EXHAUST HOODS, AND PROVIDING SPACE CONDITIONING. BASED ON THE ROOFTOP UNITS HOURS OF OCCUPANCY, START THE UNIT AT THE BEGINNING OF OCCUPANCY AND SHUT DOWN THE UNIT AT THE END OF OCCUPANCY (NOTE: OUTSIDE AIR DAMPER WITHIN THE RTU SHALL OPEN TO THE CFM SCHEDULED TO PROVIDE POSITIVE PRESSURE IN THE BUILDING AND THEN THE RTU SHALL START). THE UNIT SHALL START EARLIER AS DETERMINED BY THE PROGRAM FOR EARLY WARM-UP OR COOL DOWN. ON A SYSTEM STARTUP, THE RTU FAN SHALL START AND RUN CONTINUOUSLY AND THE INTERNAL FACTORY CONTROLS SHALL BE ENABLED. BASED ON THE SPACE TEMPERATURE SENSOR, THE UNIT SHALL CYCLE THE HEATING/COOLING TO MAINTAIN THE SPACE TEMPERATURE SETPOINT. THE UNIT SHALL ALSO OPERATE WHENEVER ANY ONE OF THE KITCHEN EXHAUST FANS IS OPERATING EITHER BY MANUAL OR AUTOMATIC MEANS AS DIRECTED BY THE GASLINK SYSTEM.
      - HUMIDITY CONTROL: UPON DETECTION OF RELATIVE HUMIDITY ABOVE 55%, THE UNIT SHALL CYCLE INTO DEHUMIDIFICATION MODE AND ENGAGE THE HOT GAS REHEAT COIL TO REMOVE HUMIDITY IF NOT ALREADY IN COOLING.
  - DOAS-1 & RTU-1
    - UNOCCUPIED MODE: THE RTU INTERNAL OA DAMPERS SHALL REMAIN CLOSED WHEN THE BUILDING IS NOT OCCUPIED, THE RTU SHALL STOP HEATING/COOLING AND THE FAN SHALL STOP. IF THE SPACE TEMPERATURE FALLS BELOW 60 DEGREES F (ADJUSTABLE), THE UNIT SHALL START AND HEAT UNTIL THE SPACE TEMPERATURE REES ABOVE 65 DEGREE F (ADJUSTABLE), THE UNIT SHALL START AND COOL UNTIL THE SPACE TEMPERATURE IS 60 DEGREE F (ADJUSTABLE) AND THEN SHUTDOWN.
    - ECONOMIZER MODE: WHEN ENTHALPY OF OA IS BELOW 28 BTU/LB, ECONOMIZER MODE SHALL BE ENABLED. ECONOMIZER MODE SHALL LINEARLY MODULATE OUTDOOR AIR CFM FROM MINIMUM OA CFM TO 100% BASED ON ENTHALPY READINGS TO PROVIDE FREE COOLING.
- UPON DETECTION OF SMOKE BY UNIT SMOKE DETECTOR BOTH RTUS SHALL SHUT DOWN AND AN ALARM SHALL BE SENT TO THE FIRE ALARM CONTROL PANEL (WHERE APPLICABLE). LOCAL REMOTE ANNUNCIATORS SHALL ALSO BE ACTIVATED.
- KITCHEN HOOD EXHAUST FAN (KEF-1, KEF-2 AND KEF-3)
  - THE KITCHEN HOOD EXHAUST FAN SHALL BE ENABLED WHEN ANY COOKING APPLIANCE LOCATED UNDER ITS RESPECTIVE HOOD, IS IN USE.
- EF-1 AND EF3
  - EXHAUST FAN SHALL RUN WHEN THE RESTROOM IS OCCUPIED. EC TO WIRE THROUGH LIGHTING CIRCUIT.
- ANSUL SYSTEM ACTIVATION
  - UPON ACTIVATION OF ANSUL SYSTEM, SHUT DOWN DOAS-1 AND DOAS-2. PROVIDE RELAYS CONTACTS, INTERLOCKS, TRANSFORMERS AND ALL ASSOCIATED WIRING TO ACCOMPLISH SEQUENCE.

**CASE Engineering Inc.**  
796 Merri Court  
St. Louis, MO 63106  
CERTIFICATE OF AUTHORITY NO. 1758

**FREDDY'S FROZEN CUSTARD**  
1101 Julian Drive  
LaGrange, KY 40031  
Oldham County

**LK ARCHITECTURE, INC.**  
346 RIVERVIEW,  
WRENTHAM, MA 01923  
F 518 286 0206  
F 518 286 0208  
Architecture - Engineering - Planning - Interior  
Design - Landscape Architecture

Professional Seal:  
STATE OF KENTUCKY  
DARRELL R. CASE  
20334  
REGISTERED PROFESSIONAL ENGINEER  
09-24-2023

**MECHANICAL SCHEDULES**

DATE  
**Dec. 02, 2022**  
03-20-2023  
REVISION

DRAWN BY:  
NM  
CHECKED BY:  
MC  
LK #22330

SHEET NO.  
**M3.0**

MECHANICAL SPECIFICATIONS

- 1. GENERAL PROVISIONS:
A. PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, NECESSARY FOR THE COMPLETE INSTALLATION OF THE PLUMBING AND MECHANICAL SYSTEMS OUTLINED.
B. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE AUTHORITIES.
C. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION OVER THE SITE.
D. ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.
E. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, PIPE, DUCT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNDamaged. ALL Damaged ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERING SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.
F. PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS AS NECESSARY. PATCH AROUND ALL OPENINGS SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.
G. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
2. OPERATION AND MAINTENANCE MANUALS:
A. DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, WIRING DIAGRAMS, CAPACITY, LABELING AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.
B. ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATION AND MAINTENANCE MANUALS.
C. ALL LITERATURE LISTED ABOVE AND ALL PAPERS LISTING WARRANTIES, ETC. SHALL BE BOUND IN A 3-RING BINDER AND LABELED WITH THE PROJECT NAME, ADDRESS, ARCHITECT, ENGINEER, CONTRACTORS, ETC.
3. MANUFACTURERS:
A. MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSTRUED AS LIMITING COMPETITION. ARTICLES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO STRUCTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN, UNLESS NOTED OTHERWISE.
4. MOTORS:
A. PROVIDE THERMAL OVERLOAD PROTECTION FOR EACH MOTOR PROVIDED BY THIS WORK.
5. TESTING, BALANCING, AND CLEANING:
A. ALL PIPING SHALL BE TESTED FOR LEAKS BEFORE BEING CONCEALED IN WALL CONSTRUCTION OR COVERED WITH INSULATION.
B. SEWER AND VENT PIPING SHALL BE HYDROSTATICALLY TESTED WITH NO LESS THAN 10 FEET OF HEAD FOR A PERIOD OF NOT LESS THAN 15 MINUTES, PER THE LOCAL PLUMBING CODE, WITH NO LEAKS.
C. DOMESTIC WATER PIPING SHALL BE HYDROSTATICALLY TESTED AT A PRESSURE OF NOT LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE, BUT NOT LESS THAN 60 PSI, FOR A PERIOD OF NOT LESS THAN 2 HOURS, WITH NO LEAKS.
D. DUCTWORK AND PIPING SHALL BE BALANCED BY QUALIFIED INDEPENDENT BALANCING PERSONNEL WHO HAVE PREVIOUS EXPERIENCE WITH BALANCING PROCEDURES AND ARE CERTIFIED BY THE ASSOCIATED AIR BALANCE COUNCIL (AABC) OR NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB).
1) BALANCING SHALL INCLUDE THE BALANCING OF THE EQUIPMENT AND AIR DISTRIBUTION SYSTEMS TO PROVIDE DESIGN QUANTITIES INDICATED AND VERIFICATION OF PERFORMANCE OF ALL EQUIPMENT AND AUTOMATIC CONTROLS.
2) WITH IN 30 DAYS OF THE COMPLETION OF THE TESTING AND BALANCING WORK, SUBMIT THE TEST AND BALANCING REPORT BEARING THE SIGNATURE OF THE TEST AND BALANCING ENGINEER. THE REPORTS SHALL BE CERTIFIED PROOF THAT THE SYSTEMS HAVE BEEN TESTED, ADJUSTED, AND BALANCED IN ACCORDANCE WITH THE REFERENCED STANDARDS, ARE AN ACCURATE REPRESENTATION OF HOW THE SYSTEMS HAVE BEEN INSTALLED AND ARE OPERATING. REPORTS SHALL BE BOUND IN A VINYL BINDER AND THE BINDER LABELED OR MAY BE AN ELECTRONIC PDF SUBMITTAL.
E. GREASE DUCT SHALL BE TESTED PRIOR TO USE OR CONCEALMENT OF ANY PORTION OF THE GREASE DUCT SYSTEM. DUCTS SHALL BE CONSIDERED TO BE CONCEALED WHEN INSTALLED IN SHAFTS COVERED BY DUCT WRAP INSULATION THAT PREVENTS THE DUCTWORK FROM BEING VISUALLY INSPECTED FROM ALL SIDES. THE PERMIT HOLDER SHALL BE RESPONSIBLE TO PROVIDE THE NECESSARY EQUIPMENT AND PERFORM THE GREASE DUCT LEAKAGE TEST PER NFPA 98 AND ALL LOCAL CODES.
F. BEFORE DOMESTIC WATER PIPING IS PLACED IN SERVICE, ALL DOMESTIC WATER DISTRIBUTION SYSTEMS INCLUDING THOSE FOR COLD WATER AND HOT WATER SYSTEMS, SHALL BE FLUSHED, STERILIZED AND CHLORINATED IN ACCORDANCE WITH HEALTH DEPARTMENT REGULATIONS. THE SYSTEMS SHALL BE THOROUGHLY FLUSHED OF ALL DIRT AND FOREIGN MATTER, THEN FILLED WITH WATER TREATED WITH FREE CHLORINE. DURING THE FLUSHING PROCESS, VALVES AND FITTINGS SHALL BE OPENED SEVERAL TIMES TO ASSURE TREATMENT OF THE ENTIRE SYSTEM. THE TREATED WATER SHALL BE LEFT IN THE SYSTEM FOR 24 HOURS AFTER WHICH TIME THE SYSTEM SHALL BE FLUSHED. IF THE RESIDUAL CHLORINE IS NOT AT LEAST 1.0 PPM, THE FLUSHING SHALL BE REPEATED. AFTER STERILIZATION, SAMPLES OF WATER IN THE SYSTEM SHALL BE APPROVED BY THE BOARD OF HEALTH.
6. PIPING:
A. DOMESTIC COLD, HOT, AND HOT WATER REGULATORING (ABOVEGROUND).
1) TYPE L HARD DRAWN COPPER TUBING, ASTM B-88
a) WROUGHT COPPER SOLDERED FITTINGS, ASTM B78 ALLOY C12200, ANSI B16.22, MSS SP-104.
b) MECHANICAL PRESS COPPER FITTINGS FOR USE IN PLUMBING OR MECHANICAL APPLICATIONS, ASME B16.22, ASME B16.51, OR ASME B16.10. MECHANICAL PRESS COPPER FITTINGS SHALL CONFORM TO ANPNO P3-117 OR ASME B16.51.
2) PEX, HIGH-DENSITY CROSS-LINKED POLYETHYLENE TUBING SHALL BE MANUFACTURED TO THE REQUIREMENTS OF ASTM F2016 AND MEET THE STANDARD GRADE HYDROSTATIC PRESSURE RATINGS FROM PLASTIC PIPE INSTITUTE (API) 44-09.
a) PEX-A AND PEX-B MEETING ANSI/NSF61 AND ANSI/NSF312 STANDARDS FOR POTABLE WATER SAFETY AND LEAD-FREE STANDARDS AND MUST BE MARKED WITH "PPA-G", "NSF-61-G" OR OTHER NSF-APPROVED MARKING. ASTM F2020 FOR USE WITH UNDRINKED WATER.
b) PEX MECHANICAL CRIMP/INSERT OR EXPANSION FITTING ASSEMBLY WITH MANUFACTURER'S INSTRUCTIONS. PIPE SIZES GIVEN ON THE DRAWINGS ARE NOMINAL COPPER PIPE SIZE. INCREASE PEX PIPING SIZE TO EQUAL OR EXCEED COPPER PIPE INSIDE DIAMETER FOR SUPPLY MAINS.
3) VALVES
a) GATE VALVE: JOHAR T-8-301 OR EQUAL, NSF 61-0, ANSI B16.201, ANSI B16.10.
b) GLOBE VALVE: CRANE #1 OR EQUAL.
c) BALL VALVE: JOHAR T-5-1000 OR EQUAL CONTACT LEAD FREE FORGED BRASS BALL VALVE, UL424 CSA 337112 & 337112 FM, NSF 61, CALIFORNIA CODE AB1193-NSF61 ANNEX G APPROVED.
d) BALL VALVE: JOHAR T-1000E OR EQUAL, UL424, FM, CSA, NSF 61-0, MSS SP-110.
B. STORM SEWER, SANITARY SEWER, GREASE WASTE, AND VENTS (UNDERGROUND, INTERIOR TO THE BUILDINGS).
1) ABS SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM: PIPE AND FITTINGS SHALL BE MANUFACTURED FROM ABS COMPOUND WITH A CELL CLASS OF 42222 FOR PIPE AND 32222 FOR FITTINGS AS PER ASTM D 2665 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620. FITTINGS SHALL CONFORM TO ASTM D 2235.
2) PVC SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM: PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 11432 PER ASTM D 4396 FOR PIPE AND 12454 PER ASTM D 1194 FOR FITTINGS AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620. FITTINGS SHALL CONFORM TO ASTM D 2235.
3) PVC SCHEDULE 40 SOLID WALL PIPE AND DRY FITTING SYSTEM: PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 12454 PER ASTM D 1194 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 194. FITTINGS SHALL CONFORM TO ASTM F 194. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564.
4) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 889 AND GSP1 STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO GSP1 STANDARD 310 AND BE CERTIFIED BY NSF INTERNATIONAL.
5) HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
6) COPPER DRY, DRAINAGE TUBE SHALL CONFORM TO ASTM B306, WROUGHT COPPER FITTINGS, ANSI B-16-21.
7) GALVANIZED STEEL PIPE, WITH MALLEABLE IRON, THREADED FITTINGS, DRAINAGE PATTERN FOR SEWERS SHALL CONFORM TO ASTM A 53.
E. CONDENSATE DRAINS & INDIRECT WASTE (ABOVEGROUND).
1) DRY, WROUGHT COPPER, ANSI B-16-21.
2) POLYETHYLENE GLYCOL (PEG) DRY PIPE, SCHEDULE 40, SOLVENT JOINT.
F. REFRIGERANT.
1) ASTM B 260, TYPE ACR, HARD-DRAWN STRAIGHT LENGTHS, AND SOFT-ANNEALED COILS, SEAMLESS COPPER TUBING.
2) WROUGHT COPPER, ANSI B16.22, STREAMLINED PATTERN, FITTINGS, BRAZED JOINTS, AVG A 5.0, CLASSIFICATION BAG-1 (SILVER).
3) TUBING SHALL BE FACTORY CLEANED, READY FOR INSTALLATION, AND HAVE ENDS CAPPED TO PROTECT CLEANLINESS OF PIPE INTERIORS PRIOR TO SHIPPING.
4) SIZE AND INSTALLATION OF PIPE SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
5) ALL PIPE HANGERS AND SUPPORTS SHALL BE STANDARD PRODUCTS OF GRNELL, FEE AND MASON, OR ELGEN. HANGER SPACING SHALL BE IN ACCORDANCE WITH MSS-SP-64.
H. SLEEVES
1) PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK. ALL SLEEVES SHALL BE OF SUFFICIENT SIZE TO PERMIT PIPE MOVEMENT DUE TO EXPANSION AND CONTRACTION AND TO ACCOMMODATE PIPE INSULATION.
2) INTERIOR PARTITIONS: 16 GAUGE GALVANIZED STEEL, PACK BETWEEN PIPE AND SLEEVE WITH FIRE SAFING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.
3) ROOF: PROSET OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WATERPROOF SEAL. COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF WARRANTY.
4) PLUMBING VENTS: FLASH ROOF VENT INTO ROOFING SYSTEM AS REQUIRED BY THE ROOFING CONTRACTOR. ALL PLUMBING VENT TERMINALS SHALL TERMINATE A MINIMUM OF 12" ABOVE ROOF OR EQUAL, TO HEIGHT OF PARAPET, WHICHEVER IS GREATER.
I. PROVIDE CHROME PLATED ESCUTCHEONS ON ALL PIPE ENTERING FINISHED AREAS.
7. INSULATION AND DUCT LINING:
A. ALL INSULATIONS AND ACCESSORIES SHALL HAVE A FIRE HAZARD CLASSIFICATION WITH A FLAME SPREAD RATINGS OF NOT OVER 25, A FUEL CONTRIBUTION RATINGS OF NOT OVER 50, AND A SMOKE DEVELOPED RATINGS OF NOT OVER 50, IN ACCORDANCE WITH NFPA.
B. PIPE INSULATION - ABOVE GRADE:
1) THE PIPING INSULATION USED SHALL HAVE A THERMAL CONDUCTIVITY OF 0.27 Btu Per In/ft^2/ft^2 OR LESS.
2) FIBER-GLASS INSULATION WITH FACTORY APPLIED VAPOR BARRIER, ASU JACKET, FACTORY APPLIED PRESSURE SEALING LONGITUDE LAP JOINT, NO STAPLES, ZESTON REMOLDED PVC FITTING COVERS. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
3) FLEXIBLE CLOSED CELL ELASTOMERIC THERMAL INSULATION, UNSLIT OR PRESLIT WITH PRESSURE SENSITIVE ADHESIVE SYSTEM, GASKET CLOSURE AND VAPOR SEALING, EQUAL TO ARMIFLEX AP ARMIFLEX OR ARMIFLEX 2000.
4) FOR NON CIRCULATING SYSTEMS, THE FIRST 3 FEET OF INLET AND OUTLET PIPING BETWEEN THE TANK AND THE HEAT TRAP (INCLUDING THE HEAT TRAP) MUST BE INSULATED.
5) INSULATION SCHEDULE:
a) DOMESTIC COLD WATER 1/2"
b) DOMESTIC HOT WATER 1-1/2"
c) HOT WATER REGULATORING 1-1/2"
d) CONDENSATE DRAINS INSIDE BUILDINGS 1/2"
e) REFRIGERANT SUCTION 1-1/2" FOR PIPING UP TO 1 1/2"; 4" FOR PIPING 1-1/2" AND LARGER
f) HORIZONTAL STORM PIPE 1/2"
g) HORIZONTAL STORM OVERFLOW PIPE 1/2"
h) ROOF DRAINS INSULATION SHALL BE PROVIDED AT ROOF DRAIN BODY AND A MINIMUM OF 10" OF HORIZONTAL PIPING OR A MINIMUM OF 8" IF COMBINATION OF HORIZONTAL AND VERTICAL STORM PIPING DOWNSTREAM OF ROOF DRAIN BODY.
C. DUCTWORK: ACOUSTICAL INSULATION.
1) DUCT LINING: 2 LB/CF, THICKNESS AS SCHEDULED, AIR STREAM SIDE COATED, INSTALL PER SMACNA STANDARDS.
a) DUCT LINING SCHEDULE:
(1) RECTANGULAR SUPPLY DUCT 1/2" THROUGHOUT THE FIRST 10 FEET OF DUCT.
(2) RETURN AIR DUCT (DINING UNITS ONLY) 1/2" THROUGHOUT THE FIRST 10 FEET OF DUCT.
D. DUCTWORK: THERMAL INSULATION (WHERE CONCEALED ABOVE CEILING).
1) DUCT COVERING: 3/4 LB/CF, FIBERGLASS BLANKET WITH FACTORY APPLIED VAPOR BARRIER AND FACING, THICKNESS AS SCHEDULED, INSTALLATION IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
a) DUCT COVERING SCHEDULE: MINIMUM R-6
(1) ROUND SUPPLY DUCT (ABOVE CEILING) 2"
(2) RECTANGULAR SUPPLY DUCT (ABOVE CEILING) 2"
(3) RETURN AIR DUCT 2"
(4) OUTDOOR AIR / MAKE-UP AIR DUCT 2"
B. GREASE HOOD AND EXHAUST DUCT:
A. HOOD SHALL BE CONSTRUCTED OF 18 GAUGE STEEL OR 20 GAUGE STAINLESS STEEL IN ACCORDANCE WITH NFPA AND LOCAL CODES.
1) GREASE FILTERS SHALL BE UL LISTED ALUMINUM GREASE EXTRACTORS.
2) PROVIDE A COMPLETE AUTOMATIC NET CHEMICAL FIRE EXTINGUISHING SYSTEM FOR THE HOOD AND DUCT AS REQUIRED BY NFPA AND LOCAL CODES. ALL COOKING EQUIPMENT UNDER THE HOOD SHALL BE INTERLOCKED WITH THE SYSTEM, TO SHUTDOWN IN AN ALARM CONDITION.
a) THE GREASE HOOD FIRE SUPPRESSION SYSTEM SHALL BE EQUAL TO AMREX KP SERIES PRE-ENGINEERED, NET CHEMICAL, STORED-PRESSURE TYPE WITH A FIXED NOZZLE AGENT DISTRIBUTION SYSTEM. THE SYSTEM SHALL BE UL LISTED AND TESTED TO UL STANDARD 300.
b) THE SYSTEM SHALL UTILIZE AN AGENT EQUAL TO AMREX KP LIQUID FIRE SUPPRESSANT, A POTASSIUM ACETATE BASED SOLUTION THAT SUPPRESSES COOKING GREASE FIRES, SHALL HAVE A PH OF 9 OR LESS, AND SHALL NOT HARM STAINLESS STEEL SURFACES.
c) THE SYSTEM SHALL BE PROVIDED WITH A MANUAL "DUAL ACTION" TYPE FULL STATION. FULL STATION SHALL BE LOCATED NOT LESS THAN 10 FEET AND A MAXIMUM OF 20 FEET FROM THE GREASE HOOD AND IN THE PATH OF EGRESS. THE MANUAL ACTUATION SHALL REQUIRE A MAXIMUM FORCE OF 40 POUNDS AND A MAXIMUM MOVEMENT OF 14 INCHES TO ACTUATE THE FIRE SUPPRESSION SYSTEM.
d) PROVIDE A GAS SHUT OFF VALVE FOR MOUNTING IN THE GAS PIPE THAT WILL SHUT OFF GAS FLOW TO EQUIPMENT UNDER THE HOOD IN AN ALARM CONDITION. PROVIDE AN ELECTRICAL SWITCH WHICH SHALL BE CAPABLE OF DE-ENERGIZING ALL ELECTRICAL DEVICES AND EQUIPMENT UNDER THE HOOD IN AN ALARM CONDITION.
B. GREASE DUCT SHALL BE CONSTRUCTED OF 16 GAUGE CARBON STEEL OR 18 GAUGE STAINLESS STEEL IN ACCORDANCE WITH NFPA AND LOCAL CODES.
a) JOINTS, SEAMS AND PENETRATIONS OF GREASE DUCTS SHALL BE MADE WITH A CONTINUOUS LIQUID TIGHT WELD OR BRAZE MADE ON THE EXTERNAL SURFACE OF THE DUCT SYSTEM.
b) DUCT JOINTS SHALL BE BUTT JOINTS, WELDED FLANGE JOINTS WITH A MAXIMUM FLANGE DEPTH OF 1/2" OR OVERLAPPING DUCT JOINTS OF EITHER THE TEE OR GROUND TYPE. OVERLAPPING JOINTS SHALL BE INSTALLED TO PREVENT LEDGES AND OBSTRUCTIONS FROM COLLECTING GREASE OR INTERFERING WITH GRAVITY DRAINAGE TO THE INTENDED COLLECTION POINT.
C. SEAL ALL CONCEALED DUCTWORK JOINTS WITH NON-HARDENING, NON-MIGRATING MASTIC SEALANT, AS RECOMMENDED FOR SEALING SEAMS AND JOINTS IN DUCTWORK. OIL BASE CAULKING AND GLAZING COMPOUNDS SHALL NOT BE ACCEPTABLE.
E. DUCT SIZES SHOWN ON THE DRAWINGS ARE SHEETMETAL SIZES, ALLOWANCE FOR DUCT LINER HAS BEEN MADE WHERE APPLICABLE.
F. INSTALLATION OF METAL DUCTWORK:
1) GENERAL: ASSEMBLE AND INSTALL DUCTWORK IN ACCORDANCE WITH RECOGNIZED INDUSTRY PRACTICES WHICH WILL ACHIEVE AIR-TIGHT SYSTEMS (MAXIMUM 5% LEAKAGE), WITH NO OBJECTABLE NOISE, AND CAPABLE OF PERFORMING INDICATED SERVICE. INSTALL EACH RUN WITH MINIMUM NUMBER OF JOINTS. ALIGN DUCTWORK ACCURATELY WITH INTERNAL SURFACES SMOOTH. SUPPORT DUCTS RIGIDLY WITH SUITABLE STRAPS, BRACES, HANGERS AND ANCHORS IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS" LATEST EDITION. DUCT HANGERS SHALL BE HANGERS WITH HOLD DOWNS OF THE TYPE WHICH WILL HOLD TRUE-TO-SHAPE AND TO PREVENT BUCKLING. SUPPORT VERTICAL DUCTS AT EVERY FLOOR.
2) AUXILIARY STEEL: PROVIDE AUXILIARY STEEL AS REQUIRED TO ADEQUATELY SUPPORT DUCTWORK.
3) ROUTING: LOCATE DUCTWORK RUNS, EXCEPT AS OTHERWISE INDICATED, VERTICALLY AND HORIZONTALLY AND AVOID DIAGONAL RUNS WHEREVER POSSIBLE. LOCATE RUNS AS INDICATED BY DIAGRAMS, DETAILS AND NOTATIONS OR, IF NOT OTHERWISE INDICATED, RUN DUCTWORK IN SHORTEST ROUTE WHICH DOES NOT OBSTRUCT USABLE SPACE OR BLOCK ACCESS FOR SERVICING BUILDING AND ITS EQUIPMENT. HOLD DUCTS CLOSE TO WALLS, OVERHEAD CONSTRUCTION, COLUMNS, AND OTHER STRUCTURAL AND PERMANENT ENCLOSURE ELEMENTS OF BUILDING, WHEREVER POSSIBLE IN FINISHED AND OCCUPIED SPACES. CONCEAL DUCTWORK FROM VIEW, BY LOCATING IN MECHANICAL SHAFTS, VERTICAL WALL CONSTRUCTION OR ABOVE SUSPENDED CEILING. DO NOT ENGAGE HORIZONTAL RUNS IN SOLID PARTITIONS, EXCEPT AS SPECIFICALLY SHOWN. COORDINATE LAYOUT WITH SUSPENDED CEILING AND LIGHTING LAYOUTS AND SIMILAR FINISHED WORK.
4) DO NOT ROUTE DUCTWORK THROUGH ELECTRICAL EQUIPMENT SPACES AND ENCLOSURES, UNLESS INDICATED OTHERWISE.
5) PENETRATIONS:
a) WHERE DUCTS PASS THROUGH INTERIOR PARTITIONS OR EXTERIOR WALLS, AND ARE EXPOSED TO VIBRY, CONICAL SPACE BETWEEN OPENINGS AND DUCT OR DUCT INSULATION THIN SHEET METAL FLANGES OF SAME GAUGE AS DUCT. OVERLAP OPENING ON 4 SIDES BY AT LEAST 1-1/2". FASTEN TO DUCT AND WALL.
b) WHERE DUCTS PASS THROUGH FIRE-RATED FLOORS, WALLS, OR PARTITIONS, PROVIDE FIRESTOPPING BETWEEN DUCT AND WALL.
6) COORDINATION: COORDINATE DUCT INSTALLATIONS WITH INSTALLATION OF ACCESSORIES, DAMPERS, COIL FRAMES, EQUIPMENT CONTROLS, AND OTHER ASSOCIATED WORK OF THE DUCTWORK SYSTEM.
7) INSTALLATION: INSTALL METAL DUCTWORK IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS" LATEST EDITION.

MECHANICAL SPECIFICATIONS (CONTINUED)

- 1) ABS SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM: PIPE AND FITTINGS SHALL BE MANUFACTURED FROM ABS COMPOUND WITH A CELL CLASS OF 42222 FOR PIPE AND 32222 FOR FITTINGS AS PER ASTM D 2665 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620. FITTINGS SHALL CONFORM TO ASTM D 2235.
2) PVC SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM: PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 11432 PER ASTM D 4396 FOR PIPE AND 12454 PER ASTM D 1194 FOR FITTINGS AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620. FITTINGS SHALL CONFORM TO ASTM D 2235.
3) PVC SCHEDULE 40 SOLID WALL PIPE AND DRY FITTING SYSTEM: PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 12454 PER ASTM D 1194 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 194. FITTINGS SHALL CONFORM TO ASTM F 194. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564.
4) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 889 AND GSP1 STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO GSP1 STANDARD 310 AND BE CERTIFIED BY NSF INTERNATIONAL.
5) HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
6) COPPER DRY, DRAINAGE TUBE SHALL CONFORM TO ASTM B306, WROUGHT COPPER FITTINGS, ANSI B-16-21.
7) GALVANIZED STEEL PIPE, WITH MALLEABLE IRON, THREADED FITTINGS, DRAINAGE PATTERN FOR SEWERS SHALL CONFORM TO ASTM A 53.
E. CONDENSATE DRAINS & INDIRECT WASTE (ABOVEGROUND).
1) DRY, WROUGHT COPPER, ANSI B-16-21.
2) POLYETHYLENE GLYCOL (PEG) DRY PIPE, SCHEDULE 40, SOLVENT JOINT.
F. REFRIGERANT.
1) ASTM B 260, TYPE ACR, HARD-DRAWN STRAIGHT LENGTHS, AND SOFT-ANNEALED COILS, SEAMLESS COPPER TUBING.
2) WROUGHT COPPER, ANSI B16.22, STREAMLINED PATTERN, FITTINGS, BRAZED JOINTS, AVG A 5.0, CLASSIFICATION BAG-1 (SILVER).
3) TUBING SHALL BE FACTORY CLEANED, READY FOR INSTALLATION, AND HAVE ENDS CAPPED TO PROTECT CLEANLINESS OF PIPE INTERIORS PRIOR TO SHIPPING.
4) SIZE AND INSTALLATION OF PIPE SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
5) ALL PIPE HANGERS AND SUPPORTS SHALL BE STANDARD PRODUCTS OF GRNELL, FEE AND MASON, OR ELGEN. HANGER SPACING SHALL BE IN ACCORDANCE WITH MSS-SP-64.
H. SLEEVES
1) PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK. ALL SLEEVES SHALL BE OF SUFFICIENT SIZE TO PERMIT PIPE MOVEMENT DUE TO EXPANSION AND CONTRACTION AND TO ACCOMMODATE PIPE INSULATION.
2) INTERIOR PARTITIONS: 16 GAUGE GALVANIZED STEEL, PACK BETWEEN PIPE AND SLEEVE WITH FIRE SAFING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.
3) ROOF: PROSET OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WATERPROOF SEAL. COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF WARRANTY.
4) PLUMBING VENTS: FLASH ROOF VENT INTO ROOFING SYSTEM AS REQUIRED BY THE ROOFING CONTRACTOR. ALL PLUMBING VENT TERMINALS SHALL TERMINATE A MINIMUM OF 12" ABOVE ROOF OR EQUAL, TO HEIGHT OF PARAPET, WHICHEVER IS GREATER.
I. PROVIDE CHROME PLATED ESCUTCHEONS ON ALL PIPE ENTERING FINISHED AREAS.
7. INSULATION AND DUCT LINING:
A. ALL INSULATIONS AND ACCESSORIES SHALL HAVE A FIRE HAZARD CLASSIFICATION WITH A FLAME SPREAD RATINGS OF NOT OVER 25, A FUEL CONTRIBUTION RATINGS OF NOT OVER 50, AND A SMOKE DEVELOPED RATINGS OF NOT OVER 50, IN ACCORDANCE WITH NFPA.
B. PIPE INSULATION - ABOVE GRADE:
1) THE PIPING INSULATION USED SHALL HAVE A THERMAL CONDUCTIVITY OF 0.27 Btu Per In/ft^2/ft^2 OR LESS.
2) FIBER-GLASS INSULATION WITH FACTORY APPLIED VAPOR BARRIER, ASU JACKET, FACTORY APPLIED PRESSURE SEALING LONGITUDE LAP JOINT, NO STAPLES, ZESTON REMOLDED PVC FITTING COVERS. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
3) FLEXIBLE CLOSED CELL ELASTOMERIC THERMAL INSULATION, UNSLIT OR PRESLIT WITH PRESSURE SENSITIVE ADHESIVE SYSTEM, GASKET CLOSURE AND VAPOR SEALING, EQUAL TO ARMIFLEX AP ARMIFLEX OR ARMIFLEX 2000.
4) FOR NON CIRCULATING SYSTEMS, THE FIRST 3 FEET OF INLET AND OUTLET PIPING BETWEEN THE TANK AND THE HEAT TRAP (INCLUDING THE HEAT TRAP) MUST BE INSULATED.
5) INSULATION SCHEDULE:
a) DOMESTIC COLD WATER 1/2"
b) DOMESTIC HOT WATER 1-1/2"
c) HOT WATER REGULATORING 1-1/2"
d) CONDENSATE DRAINS INSIDE BUILDINGS 1/2"
e) REFRIGERANT SUCTION 1-1/2" FOR PIPING UP TO 1 1/2"; 4" FOR PIPING 1-1/2" AND LARGER
f) HORIZONTAL STORM PIPE 1/2"
g) HORIZONTAL STORM OVERFLOW PIPE 1/2"
h) ROOF DRAINS INSULATION SHALL BE PROVIDED AT ROOF DRAIN BODY AND A MINIMUM OF 10" OF HORIZONTAL PIPING OR A MINIMUM OF 8" IF COMBINATION OF HORIZONTAL AND VERTICAL STORM PIPING DOWNSTREAM OF ROOF DRAIN BODY.
C. DUCTWORK: ACOUSTICAL INSULATION.
1) DUCT LINING: 2 LB/CF, THICKNESS AS SCHEDULED, AIR STREAM SIDE COATED, INSTALL PER SMACNA STANDARDS.
a) DUCT LINING SCHEDULE:
(1) RECTANGULAR SUPPLY DUCT 1/2" THROUGHOUT THE FIRST 10 FEET OF DUCT.
(2) RETURN AIR DUCT (DINING UNITS ONLY) 1/2" THROUGHOUT THE FIRST 10 FEET OF DUCT.
D. DUCTWORK: THERMAL INSULATION (WHERE CONCEALED ABOVE CEILING).
1) DUCT COVERING: 3/4 LB/CF, FIBERGLASS BLANKET WITH FACTORY APPLIED VAPOR BARRIER AND FACING, THICKNESS AS SCHEDULED, INSTALLATION IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
a) DUCT COVERING SCHEDULE: MINIMUM R-6
(1) ROUND SUPPLY DUCT (ABOVE CEILING) 2"
(2) RECTANGULAR SUPPLY DUCT (ABOVE CEILING) 2"
(3) RETURN AIR DUCT 2"
(4) OUTDOOR AIR / MAKE-UP AIR DUCT 2"
B. GREASE HOOD AND EXHAUST DUCT:
A. HOOD SHALL BE CONSTRUCTED OF 18 GAUGE STEEL OR 20 GAUGE STAINLESS STEEL IN ACCORDANCE WITH NFPA AND LOCAL CODES.
1) GREASE FILTERS SHALL BE UL LISTED ALUMINUM GREASE EXTRACTORS.
2) PROVIDE A COMPLETE AUTOMATIC NET CHEMICAL FIRE EXTINGUISHING SYSTEM FOR THE HOOD AND DUCT AS REQUIRED BY NFPA AND LOCAL CODES. ALL COOKING EQUIPMENT UNDER THE HOOD SHALL BE INTERLOCKED WITH THE SYSTEM, TO SHUTDOWN IN AN ALARM CONDITION.
a) THE GREASE HOOD FIRE SUPPRESSION SYSTEM SHALL BE EQUAL TO AMREX KP SERIES PRE-ENGINEERED, NET CHEMICAL, STORED-PRESSURE TYPE WITH A FIXED NOZZLE AGENT DISTRIBUTION SYSTEM. THE SYSTEM SHALL BE UL LISTED AND TESTED TO UL STANDARD 300.
b) THE SYSTEM SHALL UTILIZE AN AGENT EQUAL TO AMREX KP LIQUID FIRE SUPPRESSANT, A POTASSIUM ACETATE BASED SOLUTION THAT SUPPRESSES COOKING GREASE FIRES, SHALL HAVE A PH OF 9 OR LESS, AND SHALL NOT HARM STAINLESS STEEL SURFACES.
c) THE SYSTEM SHALL BE PROVIDED WITH A MANUAL "DUAL ACTION" TYPE FULL STATION. FULL STATION SHALL BE LOCATED NOT LESS THAN 10 FEET AND A MAXIMUM OF 20 FEET FROM THE GREASE HOOD AND IN THE PATH OF EGRESS. THE MANUAL ACTUATION SHALL REQUIRE A MAXIMUM FORCE OF 40 POUNDS AND A MAXIMUM MOVEMENT OF 14 INCHES TO ACTUATE THE FIRE SUPPRESSION SYSTEM.
d) PROVIDE A GAS SHUT OFF VALVE FOR MOUNTING IN THE GAS PIPE THAT WILL SHUT OFF GAS FLOW TO EQUIPMENT UNDER THE HOOD IN AN ALARM CONDITION. PROVIDE AN ELECTRICAL SWITCH WHICH SHALL BE CAPABLE OF DE-ENERGIZING ALL ELECTRICAL DEVICES AND EQUIPMENT UNDER THE HOOD IN AN ALARM CONDITION.
B. GREASE DUCT SHALL BE CONSTRUCTED OF 16 GAUGE CARBON STEEL OR 18 GAUGE STAINLESS STEEL IN ACCORDANCE WITH NFPA AND LOCAL CODES.
a) JOINTS, SEAMS AND PENETRATIONS OF GREASE DUCTS SHALL BE MADE WITH A CONTINUOUS LIQUID TIGHT WELD OR BRAZE MADE ON THE EXTERNAL SURFACE OF THE DUCT SYSTEM.
b) DUCT JOINTS SHALL BE BUTT JOINTS, WELDED FLANGE JOINTS WITH A MAXIMUM FLANGE DEPTH OF 1/2" OR OVERLAPPING DUCT JOINTS OF EITHER THE TEE OR GROUND TYPE. OVERLAPPING JOINTS SHALL BE INSTALLED TO PREVENT LEDGES AND OBSTRUCTIONS FROM COLLECTING GREASE OR INTERFERING WITH GRAVITY DRAINAGE TO THE INTENDED COLLECTION POINT.
C. SEAL ALL CONCEALED DUCTWORK JOINTS WITH NON-HARDENING, NON-MIGRATING MASTIC SEALANT, AS RECOMMENDED FOR SEALING SEAMS AND JOINTS IN DUCTWORK. OIL BASE CAULKING AND GLAZING COMPOUNDS SHALL NOT BE ACCEPTABLE.
E. DUCT SIZES SHOWN ON THE DRAWINGS ARE SHEETMETAL SIZES, ALLOWANCE FOR DUCT LINER HAS BEEN MADE WHERE APPLICABLE.
F. INSTALLATION OF METAL DUCTWORK:
1) GENERAL: ASSEMBLE AND INSTALL DUCTWORK IN ACCORDANCE WITH RECOGNIZED INDUSTRY PRACTICES WHICH WILL ACHIEVE AIR-TIGHT SYSTEMS (MAXIMUM 5% LEAKAGE), WITH NO OBJECTABLE NOISE, AND CAPABLE OF PERFORMING INDICATED SERVICE. INSTALL EACH RUN WITH MINIMUM NUMBER OF JOINTS. ALIGN DUCTWORK ACCURATELY WITH INTERNAL SURFACES SMOOTH. SUPPORT DUCTS RIGIDLY WITH SUITABLE STRAPS, BRACES, HANGERS AND ANCHORS IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS" LATEST EDITION. DUCT HANGERS SHALL BE HANGERS WITH HOLD DOWNS OF THE TYPE WHICH WILL HOLD TRUE-TO-SHAPE AND TO PREVENT BUCKLING. SUPPORT VERTICAL DUCTS AT EVERY FLOOR.
2) AUXILIARY STEEL: PROVIDE AUXILIARY STEEL AS REQUIRED TO ADEQUATELY SUPPORT DUCTWORK.
3) ROUTING: LOCATE DUCTWORK RUNS, EXCEPT AS OTHERWISE INDICATED, VERTICALLY AND HORIZONTALLY AND AVOID DIAGONAL RUNS WHEREVER POSSIBLE. LOCATE RUNS AS INDICATED BY DIAGRAMS, DETAILS AND NOTATIONS OR, IF NOT OTHERWISE INDICATED, RUN DUCTWORK IN SHORTEST ROUTE WHICH DOES NOT OBSTRUCT USABLE SPACE OR BLOCK ACCESS FOR SERVICING BUILDING AND ITS EQUIPMENT. HOLD DUCTS CLOSE TO WALLS, OVERHEAD CONSTRUCTION, COLUMNS, AND OTHER STRUCTURAL AND PERMANENT ENCLOSURE ELEMENTS OF BUILDING, WHEREVER POSSIBLE IN FINISHED AND OCCUPIED SPACES. CONCEAL DUCTWORK FROM VIEW, BY LOCATING IN MECHANICAL SHAFTS, VERTICAL WALL CONSTRUCTION OR ABOVE SUSPENDED CEILING. DO NOT ENGAGE HORIZONTAL RUNS IN SOLID PARTITIONS, EXCEPT AS SPECIFICALLY SHOWN. COORDINATE LAYOUT WITH SUSPENDED CEILING AND LIGHTING LAYOUTS AND SIMILAR FINISHED WORK.
4) DO NOT ROUTE DUCTWORK THROUGH ELECTRICAL EQUIPMENT SPACES AND ENCLOSURES, UNLESS INDICATED OTHERWISE.
5) PENETRATIONS:
a) WHERE DUCTS PASS THROUGH INTERIOR PARTITIONS OR EXTERIOR WALLS, AND ARE EXPOSED TO VIBRY, CONICAL SPACE BETWEEN OPENINGS AND DUCT OR DUCT INSULATION THIN SHEET METAL FLANGES OF SAME GAUGE AS DUCT. OVERLAP OPENING ON 4 SIDES BY AT LEAST 1-1/2". FASTEN TO DUCT AND WALL.
b) WHERE DUCTS PASS THROUGH FIRE-RATED FLOORS, WALLS, OR PARTITIONS, PROVIDE FIRESTOPPING BETWEEN DUCT AND WALL.
6) COORDINATION: COORDINATE DUCT INSTALLATIONS WITH INSTALLATION OF ACCESSORIES, DAMPERS, COIL FRAMES, EQUIPMENT CONTROLS, AND OTHER ASSOCIATED WORK OF THE DUCTWORK SYSTEM.
7) INSTALLATION: INSTALL METAL DUCTWORK IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS" LATEST EDITION.


MECHANICAL SPECIFICATIONS (CONTINUED)

- c) DUCT TO HOOD CONNECTIONS SHALL BE MADE WITH LISTED AND LABELED DUCT TO HOOD COLLAR CONNECTIONS THAT ARE LABELED PER THE TERMS OF THEIR APPROVAL AND PER THE MANUFACTURERS INSTALLATION INSTRUCTIONS.
d) DUCT TO EXHAUST FAN CONNECTIONS SHALL BE FLANGED AND GASKETED AT THE BASE OF THE FAN FOR VERTICAL DISCHARGE FANS, OR SHALL BE FLANGED, GASKETED AND BOLTED TO THE INLET OF THE FAN FOR SIDE INLET UTILITIES. GASKET SEALING MATERIALS SHALL BE RATED FOR A MINIMUM CONTINUOUS DUTY TEMPERATURE OF 1,500°F.
C. SINGLE WALL ROUND GREASE DUCT:
1. FURNISH SINGLE-WALL, FACTORY BUILT, GREASE DUCT FOR USE WITH TYPE I KITCHEN HOODS, WHICH CONFORMS TO THE REQUIREMENTS OF NFPA-96. PRODUCTS SHALL BE ETL LISTED TO UL-1975 AND CANULS-5662 FOR VENTING AIR AND GREASE VAPORS FROM COMMERCIAL COOKING OPERATIONS AS DESCRIBED IN NFPA-96.
2. THE DUCT WALL SHALL BE CONSTRUCTED OF .036 AND .041 THICK STAINLESS STEEL AND BE AVAILABLE IN DIAMETERS 6" THROUGH 24".
3. ALL SUPPORTS, FAN ADAPTERS, HOOD CONNECTIONS, FITTINGS AND EXPANSION JOINTS REQUIRED TO INSTALL GREASE DUCT SHALL BE INCLUDED.
4. ROOF PENETRATIONS SHALL COMPLY WITH LISTED CLEARANCE TO COMBUSTIBLES, SEE "CLEARANCE TO COMBUSTIBLES" GUIDE FOR DETAILS. THE GREASE DUCT WILL TERMINATE AT THE FAN ADAPTER PLATE, WILL BE FULLY WELDED TO THE FAN ADAPTER PLATE AND THE FAN ADAPTER PLATE WILL BE FASTENED TO THE CURB USING A SUITABLY SIZED FASTENER PROVIDED BY OTHERS; SEE PAGE 12 OF THE "INSTALLATION, OPERATION AND MAINTENANCE MANUAL" FOR DETAILS.
5. GREASE DUCT JOINTS SHALL BE HELD TOGETHER BY MEANS OF FORWED VEE CLAMPS AND SEALED WITH 3M FIRE BARRIER 2200. SCREWS USED TO SECURE THE VEE CLAMPS SHALL BE OF THE HEX-HEAD TYPE WITH FLANGED STOPS AND TAPERED "LEAD IN" THREADS FOR EASY STARTING. NUTS SHALL BE RETAINED BY MEANS OF A FREE-FLOATING CAGE TO ALLOW EASY ALIGNMENT.
6. SINGLE-WALL GREASE DUCT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S "INSTALLATION, OPERATION AND MAINTENANCE MANUAL", ETL LISTING AND STATE AND LOCAL CODES.
7. GREASE DUCT INSTALLED OUTSIDE OF THE BUILDING SHALL BE PROTECTED AGAINST ACCIDENTAL DAMAGE OR VANDALISM.
8. SUPPORT VERTICALLY INSTALLED GREASE DUCT FROM THE BUILDING STRUCTURE USING RIGID STRUCTURAL SUPPORTS. ANCHOR SUPPORTS TO THE STRUCTURE BY WELDING OR BOLTING STEEL EXPANSION ANCHORS OR CONCRETE INSERTS. SUPPORT HORIZONTALLY INSTALLED GREASE DUCT FROM THE BUILDING STRUCTURE USING ABOVE METHOD. 1/2" THREADED ROD AND SADDLES MAY ALSO BE USED FOR THE SUPPORT OF HORIZONTAL GREASE DUCT.
9. FANS SHALL BE SUPPORTED INDEPENDENTLY FROM THE GREASE DUCT SECTIONS. PROTECT GREASE DUCT FROM TWISTING OR MOVEMENT CAUSED BY FAN TORQUE OR VIBRATION.
9. PLUMBING:
A. PROVIDE AN APPROVED WATER HAMMER ARRESTOR FOR EACH PLUMBING FIXTURE SUPPLY AS REQUIRED BY FIXTURE MANUFACTURER.
B. ALL EXPOSED PIPE SHALL BE CHROME PLATED BRASS PIPE, NO FERROUS PIPE.
C. PROVIDE CLEANOUTS AT EACH CHANGE OF DIRECTION AND AT 100 FOOT INTERVALS IN STRAIGHT RUNS.
D. PROVIDE ACCESS PANELS FOR ALL CONCEALED VALVES AND TRAPS.
E. CLEANOUTS:
1) VINYL TILE FLOOR: JR SMITH #4140, OR EQUAL.
2) QUARRY TILE FLOOR: JR SMITH #4200, OR EQUAL.
3) CARPETED FLOOR: JR SMITH #4202, OR EQUAL.
4) UNFINISHED FLOOR: JR SMITH #4202, OR EQUAL.
5) WALL: JR SMITH #4472, OR EQUAL, 24" ABOVE THE FLOOR.
6) GRADE: JR SMITH #4256, OR EQUAL, WITH HEAVY DUTY CAST IRON BODY AND COVER.
F. PROVIDE DIELECTRIC UNIONS WITH APPROPRIATE END CONNECTIONS TO MATCH THE PIPE SYSTEM IN WHICH INSTALLED (BORSEB, POLYMER, OR FLANGED). PROVIDE DIELECTRIC UNIONS ON ALL PIPING CONNECTIONS TO HOT WATER HEATERS AND EXPANSION TANKS.
6. ALL SEWER PIPING LOCATED INSIDE THE BUILDING SHALL BE INSTALLED WITH THE FOLLOWING SLOPES.
1) INSTALL 2-1/2" AND SMALLER PIPE AT 1/4" PER FOOT FALL.
2) INSTALL 4" AND LARGER PIPE AT 1/8" PER FOOT FALL.
H. ALL SEWER PIPING LOCATED EXTERIOR TO THE BUILDING SHALL BE INSTALLED WITH THE FOLLOWING SLOPES.
1) INSTALL 4" AND SMALLER PIPE AT A MINIMUM OF 2% SLOPE.
2) INSTALL 6" AND LARGER PIPE AT A MINIMUM OF 1% SLOPE.
3) INSTALL ALL GREASE WASTE PIPING AT 1/4" PER FOOT FALL.
I. DUCTWORK:
A. ALL DUCTWORK, UNLESS OTHERWISE INDICATED, SHALL BE FABRICATED FROM GALVANIZED SHEET STEEL COMPLYING WITH ASTM A 521, LOCKFORMING QUALITY, WITH 6-90 ZINC COATING IN ACCORDANCE WITH ASTM A 525, AND MILL PHOSPHATIZED FOR EXPOSED LOCATIONS.
B. WHERE DUCTWORK IS INDICATED TO BE EXPOSED TO VIEW IN OCCUPIED SPACES, PROVIDE MATERIALS WHICH ARE FREE FROM VIBRY, IMPERFECTIONS INCLUDING FITTING, SEAM MARKS, ROLLER MARKS, STAINS AND DISCOLORATIONS, AND OTHER IMPERFECTIONS, INCLUDING THOSE WHICH WOULD IMPAIR PAINTING.
C. DUCTWORK, METAL GAUGES, REINFORCING, ETC. SHALL BE CONSTRUCTED IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS", LATEST EDITION FOR A 2 INCH WATER GAUGE STATIC PRESSURE.
1) RECTANGULAR DUCT:
a) ELBOWS, UNLESS INDICATED OTHERWISE SHALL BE CONSTRUCTED WITH CENTERLINE RADIUS OF NOT LESS THAN 1.5 DUCT WIDTH OR SQUARE ELBOW WITH DOUBLE WALL STREAMLINE VANES.
b) RETURN AIR ACOUSTICAL DIAPHRAGMS AND SOUND BOOTS SHALL BE A SQUARE ELBOW WITH NO TURNING VANES.
c) SLOPES FOR TRANSITIONS OR OTHER CHANGES IN DIMENSIONS SHALL BE MINIMUM 1 TO 3.
2) ROUND AND OVAL SPIRAL SEAM DUCT:
a) PROVIDE RADUIS TYPE FITTINGS FABRICATED OF MULTIPLE SECTIONS WITH MAXIMUM 18 DEGREE CHANGE OF DIRECTION PER SECTION. UNLESS SPECIFICALLY INDICATED OTHERWISE, USE 45 DEGREE LATERALS FOR BRANCH TAKEOFF CONNECTIONS. WHERE 90 DEGREE BRANCHES ARE INDICATED PROVIDE CONICAL TYPE TEES.
b) SLOPES FOR TRANSITIONS OR OTHER CHANGES IN DIMENSIONS SHALL BE MINIMUM 1 TO 3.
c) AS AN OPTION, PROVIDE FACTORY-FABRICATED DUCT AND FITTINGS, IN LIEU OF SHOP-FABRICATED DUCT AND FITTINGS.
(1) ELBOWS: ONE PIECE CONSTRUCTION FOR 90 DEGREES AND 45 DEGREE ELBOW 14" AND SMALLER. PROVIDE MULTIPLE SORE CONSTRUCTION FOR LARGER DIAMETERS WITH STANDING SEAM CIRCUMFERENTIAL JOINT.
(2) DIVIDED FLOW FITTINGS: 90 DEGREE TEES, CONSTRUCTED WITH SADDLE TAP SPOT WELDED AND BONDED TO DUCT FITTING BODY.
(3) ROUND LONGITUDINAL SEAM DUCT: USE FOR RISID METAL DUCT ON LEAVING SIDE OF DUCT IN CONCEALED LOCATIONS FOR EXTENSION TO FLEX FOR DIFFUSERS, UNLESS OTHERWISE INDICATED.
D. SEAL ALL CONCEALED DUCTWORK JOINTS WITH NON-HARDENING, NON-MIGRATING MASTIC SEALANT, AS RECOMMENDED FOR SEALING SEAMS AND JOINTS IN DUCTWORK. OIL BASE CAULKING AND GLAZING COMPOUNDS SHALL NOT BE ACCEPTABLE.
E. DUCT SIZES SHOWN ON THE DRAWINGS ARE SHEETMETAL SIZES, ALLOWANCE FOR DUCT LINER HAS BEEN MADE WHERE APPLICABLE.
F. INSTALLATION OF METAL DUCTWORK:
1) GENERAL: ASSEMBLE AND INSTALL DUCTWORK IN ACCORDANCE WITH RECOGNIZED INDUSTRY PRACTICES WHICH WILL ACHIEVE AIR-TIGHT SYSTEMS (MAXIMUM 5% LEAKAGE), WITH NO OBJECTABLE NOISE, AND CAPABLE OF PERFORMING INDICATED SERVICE. INSTALL EACH RUN WITH MINIMUM NUMBER OF JOINTS. ALIGN DUCTWORK ACCURATELY WITH INTERNAL SURFACES SMOOTH. SUPPORT DUCTS RIGIDLY WITH SUITABLE STRAPS, BRACES, HANGERS AND ANCHORS IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS" LATEST EDITION. DUCT HANGERS SHALL BE HANGERS WITH HOLD DOWNS OF THE TYPE WHICH WILL HOLD TRUE-TO-SHAPE AND TO PREVENT BUCKLING. SUPPORT VERTICAL DUCTS AT EVERY FLOOR.
2) AUXILIARY STEEL: PROVIDE AUXILIARY STEEL AS REQUIRED TO ADEQUATELY SUPPORT DUCTWORK.
3) ROUTING: LOCATE DUCTWORK RUNS, EXCEPT AS OTHERWISE INDICATED, VERTICALLY AND HORIZONTALLY AND AVOID DIAGONAL RUNS WHEREVER POSSIBLE. LOCATE RUNS AS INDICATED BY DIAGRAMS, DETAILS AND NOTATIONS OR, IF NOT OTHERWISE INDICATED, RUN DUCTWORK IN SHORTEST ROUTE WHICH DOES NOT OBSTRUCT USABLE SPACE OR BLOCK ACCESS FOR SERVICING BUILDING AND ITS EQUIPMENT. HOLD DUCTS CLOSE TO WALLS, OVERHEAD CONSTRUCTION, COLUMNS, AND OTHER STRUCTURAL AND PERMANENT ENCLOSURE ELEMENTS OF BUILDING, WHEREVER POSSIBLE IN FINISHED AND OCCUPIED SPACES. CONCEAL DUCTWORK FROM VIEW, BY LOCATING IN MECHANICAL SHAFTS, VERTICAL WALL CONSTRUCTION OR ABOVE SUSPENDED CEILING. DO NOT ENGAGE HORIZONTAL RUNS IN SOLID PARTITIONS, EXCEPT AS SPECIFICALLY SHOWN. COORDINATE LAYOUT WITH SUSPENDED CEILING AND LIGHTING LAYOUTS AND SIMILAR FINISHED WORK.
4) DO NOT ROUTE DUCTWORK THROUGH ELECTRICAL EQUIPMENT SPACES AND ENCLOSURES, UNLESS INDICATED OTHERWISE.
5) PENETRATIONS:
a) WHERE DUCTS PASS THROUGH INTERIOR PARTITIONS OR EXTERIOR WALLS, AND ARE EXPOSED TO VIBRY, CONICAL SPACE BETWEEN OPENINGS AND DUCT OR DUCT INSULATION THIN SHEET METAL FLANGES OF SAME GAUGE AS DUCT. OVERLAP OPENING ON 4 SIDES BY AT LEAST 1-1/2". FASTEN TO DUCT AND WALL.
b) WHERE DUCTS PASS THROUGH FIRE-RATED FLOORS, WALLS, OR PARTITIONS, PROVIDE FIRESTOPPING BETWEEN DUCT AND WALL.
6) COORDINATION: COORDINATE DUCT INSTALLATIONS WITH INSTALLATION OF ACCESSORIES, DAMPERS, COIL FRAMES, EQUIPMENT CONTROLS, AND OTHER ASSOCIATED WORK OF THE DUCTWORK SYSTEM.
7) INSTALLATION: INSTALL METAL DUCTWORK IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS" LATEST EDITION.

MECHANICAL SPECIFICATIONS (CONTINUED)

- 6. EQUIPMENT CONNECTIONS:
1) CONNECT METAL DUCTWORK TO EQUIPMENT AS INDICATED. PROVIDE FLEXIBLE CONNECTION FOR EACH DUCTWORK CONNECTION TO EQUIPMENT MOUNTED ON VIBRATION ISOLATORS, AND/OR EQUIPMENT CONTAINING ROTATING MACHINERY. PROVIDE ACCESS DOORS AS REQUIRED.
H. SEAL ALL CONCEALED DUCTWORK JOINTS WITH NON-HARDENING, NON-MIGRATING MASTIC SEALANT, AS RECOMMENDED FOR SEALING SEAMS AND JOINTS IN DUCTWORK. OIL BASE CAULKING AND GLAZING COMPOUNDS SHALL NOT BE ACCEPTABLE. DUCTS SHALL BE SEALED TO THE CLASS LEVEL LISTED BELOW.
1) UNCONDITIONED SPACES CLASS B CLASS B CLASS B CLASS B
2) CONDITIONED SPACES (PLENUM) CLASS C CLASS B CLASS B CLASS C
SUPPLY < 2" I.P.C. SUPPLY > 2" I.P.C. EXHAUST RETURN
11. FLEXIBLE DUCT:
A. ATCO #086 (R-6), OR EQUAL.
B. FACTORY APPLIED INSULATION AND VAPOR BARRIER, 1-1/2" THICK.
C. MAXIMUM LENGTH OF 6'-0".
12. EXHAUST FANS:
A. CENTRIFUGAL TYPE FAN WITH CHARACTERISTICS AND CAPACITY AS SCHEDULED, ELECTRICALLY POWERED, SUITABLE FOR MOUNTING ON ROOF CURB, DIRECT OR

**ND-2 HANGING ANGLE DETAIL**



HOOD AND NUTS TO BE SUPPLIED BY INSTALLING CONTRACTOR. HANGING ANGLE IS PRE-PUNCHED AT FACTORY.

**HANGING ANGLE LOCATIONS**

HOOD STYLE	DIM FROM REAR	DIM FROM FRONT (24\"/>	
CANOPY ND2	4.166"	2.246"	2.246"
ND2-PSP-F	4.166"	2.246"	2.246"
BACKSHELF BD-2	4.166"	2.246"	-
VHB/VHB-G	36"x36"	42"x42"	48"x48"
FRONT/BACK DIMS BY SIZE	2.246"	2.246"	2.246"

**CALCULATIONS UTILIZED**

EXHAUST CFM=LENGTH OF HOOD X CFM/INCH FT. (LOAD)  
 SUPPLY CFM=EXHAUST CFM X PERCENTAGE REQUIRED  
 TOTAL DUCT AREA=144 X CFM  
 DUCT LENGTH= DUCT DEPTH

**BUILDING CODES**

CAPTIVE-AIRE HOODS ARE BUILT IN COMPLIANCE WITH:  
 ETL LISTED HOODS WITH NO. 94  
 INTERTEK  
 LISTED UNDER ETL FILE NUMBER 3054804-001/002



**CLEARANCE TO COMBUSTIBLES**

CAPTIVE-AIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:  
 MATERIAL CLEARANCE REDUCTION SYSTEM  
 NON-COMBUSTIBLE NONE REQUIRED  
 LIMITED-COMBUSTIBLE 3" UNINSULATED STANDOFF  
 COMBUSTIBLE 1" INSULATED STANDOFF

**GENERAL NOTES**

- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
  - ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
  - HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
  - ALL CONNECTIONS FROM CAPTIVE-AIRE DUCT PER MECHANICAL CONTRACTOR'S PLANS.
  - COOKING EQUIPMENT TO SHUT-OFF IN EVENT OF FIRE.
  - EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
  - ALL LIGHTS SHOWN INSTALLED BY CAPTIVE-AIRE ARE FACTORY PROVIDED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES BY ELECTRICAL CONTRACTORS.
  - LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
  - SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
  - INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTERPRETATION, AND ADMINISTRATION OF CODE REQUIREMENTS IN DIRECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.
- BALANCE**
- KITCHEN HOODS MUST BE BALANCED WITH KITCHEN.
  - KITCHEN SHALL BE NEGATIVE WITH RESPECT TO DRIVING AREA.
  - RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.
- ADDITIONAL**
- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
  - SHOWN AND APPROVED COPIES OF THIS DOCUMENT MUST BE RECEIVED BY THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

**FILTER DETAIL**



**HOOD INFORMATION - JOB#5680035**

HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TOP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	WIDTH	LENGTH	HEIGHT	DIA	CFM	VEL	SP	HOOD CONSTRUCTION	HOOD CONFIG
1	H-1A	5424 ND-2	CAPTIVEAIRE	6' 10"	450 DEG	I	MEDIUM	189	1292	10'	12'	4'					430 SS WHERE EXPOSED	ALDNE FRONT
2	H-1B	5424 ND-2	CAPTIVEAIRE	6' 10"	450 DEG	I	MEDIUM	189	1292	10'	12'	4'					430 SS WHERE EXPOSED	ALDNE BACK
3	H2	5424 ND-2	CAPTIVEAIRE	5' 0"	450 DEG	I	MEDIUM	153	775	9'	8'	4'					430 SS WHERE EXPOSED	ALDNE
4	H-3	4224 VHB-G	CAPTIVEAIRE	3' 6"	750 DEG	II	N/A	150	325	4'	10'	3'					304 SS 100%	ALDNE

PATENT NUMBERS  
 EXHAUST HOODS ND-2/BD-2/SND-2 (CANADA) - CA PATENT 2520435 C.

**HOOD INFORMATION**


HOOD NO	TAG	TYPE	QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE	TYPE	SIZE	MODEL #	QUANTITY	FIRE RISK	HOOD SYSTEM HANGING WEIGHT
1	H-1A	CAPTRATE SOLID FILTER	5	16"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO							NO	352 LBS
2	H-1B	CAPTRATE SOLID FILTER	5	16"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO							NO	353 LBS
3	H2	CAPTRATE SOLID FILTER	3	16"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO	RIGHT	12"x54"x24"			DCV-2011	1 LIGHT 1 FAN	NO	460 LBS
4	H-3						0									NO	161 LBS

**HOOD OPTIONS**

HOOD NO	TAG	OPTION
1	H-1A	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT.
2	H-1B	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT.
3	H2	RIGHT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. LEFT VERTICAL END PANEL 27" TOP WIDTH, 21" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS.
4	H-3	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT.

**SPECIFICATION: CAPTRATE GREASE-STOP SOLID FILTER**


THE CAPTRATE GREASE-STOP SOLID FILTER IS A SINGLE-STAGE FILTER FEATURING A SINGLE S-BUFFLE DESIGN IN CONJUNCTION WITH A SLOTTED REAR BAFFLE DESIGN TO DELIVER EXCEPTIONAL FILTRATION EFFICIENCY.  
 FILTER IS STAINLESS STEEL CONSTRUCTION, AND SIZED TO FIT INTO STANDARD 2-INCH DEEP HOOD CHANNELS.  
 UNITS SHALL INCLUDE STAINLESS STEEL HANDLES AND A FASTENING DEVICE TO SECURE THE TWO COMPONENTS WHEN ASSEMBLED.  
 GREASE EXTRACTION EFFICIENCY PERFORMANCE SHALL REMOVE AT LEAST 75% OF GREASE PARTICLES FIVE MICRONS IN SIZE, AND 85% GREASE PARTICLES SEVEN MICRONS IN SIZE AND LARGER, WITH A CORRESPONDING PRESSURE DROP NOT TO EXCEED 10 INCHES OF WATER GAUGE. THE CAPTRATE GREASE-STOP SOLID WAS TESTED TO ASTM STANDARD ASTM F259-05. MANUFACTURER APPROVED FOR USE IN SOLID FUEL APPLICATIONS AS A SPARK ARRESTER.





CAPTIVE FILTERS ARE BUILT IN COMPLIANCE WITH:  
 NSF STANDARD #2  
 UL STANDARD B146  
 INT. MECH. CODE (IMC)  
 ILC-5649.



PLAN VIEW - HOOD #2 (H-1B)  
 6' 10.00" LONG 5424ND-2




PLAN VIEW - HOOD #1 (H-1A)  
 6' 10.00" LONG 5424ND-2




ASSEMBLY INSTRUCTIONS

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TPI GRADE 5 OXIDIZING ALL-THREAD. SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 OXIDIZING STEEL FLAT WASHERS AND 1/2" - 13 TPI GRADE 5 OXIDIZING HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION ABOVE CEILING ANCHORS. SINGLE HEX NUT BENEATH HANGING ANGLE IS ACCEPTABLE FOR FULL LENGTH HANGING ANGLES. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.




ASSEMBLY INSTRUCTIONS


HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TPI GRADE 5 OXIDIZING ALL-THREAD. SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 OXIDIZING STEEL FLAT WASHERS AND 1/2" - 13 TPI GRADE 5 OXIDIZING HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION BENEATH HOOD HANGING ANGLES AND ABOVE CEILING ANCHORS. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.




PLAN VIEW - HOOD #3 (H2)  
 5' 0.00" LONG 5424ND-2




PLAN VIEW - HOOD #4 (H-3)  
 3' 6.00" LONG 4224VHB-G




SECTION VIEW - MODEL 4824ND-2 HOOD - #2 (H-1B)



SECTION VIEW - MODEL 4824ND-2 HOOD - #1 (H-1A)



SECTION VIEW - MODEL 5424ND-2 HOOD - #3 (H2)



SECTION VIEW - MODEL 4224VHB-G HOOD - #4 (H-3)

FOR QUESTIONS, CALL THE:  
 KANSAS CITY REGIONAL OFFICE  
 1128 SWIFT STREET, KANSAS CITY, MO 64116  
 PHONE: (816) 221-8375  
 FAX: (816) 221-8311

CUSTOMER APPROVAL TO MANUFACTURE:  
 Approved as Noted   
 Approved with ND Exception Taken   
 Revised and Resubmit   
 SIGNATURE \_\_\_\_\_  
 Your Title \_\_\_\_\_ Date \_\_\_\_\_

\*\*\* NOTE \*\*\*  
 ALL WALLS AND STRUCTURES THAT COME WITHIN 18" OF HOOD MUST BE METAL STUDS AND SHEETROCK. WOOD STUDS OR ANY OTHER COMBUSTIBLE MATERIAL WITHIN 18" OF HOOD NOT ALLOWED.

\*\*\* NOTE \*\*\*  
 HOOD MANUFACTURER RECOMMENDS NO RETURNS OR 4-WAY DIFFUSERS WITHIN 10 FEET OF HOOD IN ALL DIRECTION.

\*\*\* NOTE \*\*\*  
 MAKEUP AIR SHALL BE DELIVERED INTO SPACE IN MANNER THAT WILL NOT DISRUPT HOODS ABILITY TO CAPTURE AND CLEAN.

**REVISIONS**

NO.	DESCRIPTION	DATE

**REVISIONS**

DATE: 12/20/2022  
 DWG.#: 5776897  
 DRAWN BY: michael.co  
 SCALE: 1/2" = 1'-0"  
 MASTER DRAWING

**SHEET NO.**  
 1

**CAPTIVEAIRE**

HBT Foodservice  
 104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8675 FAX: (816) 221-8311 EMAIL: reg@captivaire.com

**CASE Engineering Inc.**  
 796 Merri Court  
 St. Louis, MO 63106  
 CERTIFICATE OF AUTHORITY NO. 4758

**FREDDY'S FROZEN CUSTARD**  
 1101 Julian Drive  
 LaGrange, KY 40031  
 Oldham County

**LK ARCHITECTURE, INC.**  
 346 RIVERVIEW,  
 WENTZLA, MO 67203  
 F 316 286 0206

Architecture - Engineering - Planning - Interior Design - Landscape Architecture

Professional Seal:  
 STATE OF KENTUCKY  
 DARRELL R. CASE  
 20334  
 REGISTERED PROFESSIONAL ENGINEER  
 09-24-2023

**MECHANICAL HOOD DRAWINGS**

DATE: Dec. 02, 2022  
 03-24-2023  
 REVISION

DRAWN BY: NM  
 CHECKED BY: MC  
 LK #22330

SHEET NO. M5.0











FAN #4 CASRTU3-I,400-18-20T - HEATER (DDAS-1)

NOTES:

- DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
- DENOTES CORNER WEIGHT.
- ROOF OPENING MUST BE 2" SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.

\*NOTE: SUPPLY DUCT MUST BE INSTALLED TO MEET SMACNA STANDARDS. A MINIMUM STRAIGHT DUCT LENGTH MUST BE MAINTAINED DOWNSTREAM OF UNIT DISCHARGE AS OUTLINED IN AMCA PUBLICATION 201. WHEN USING RECTANGULAR DUCTWORK, ELBOWS MUST BE RADIUS THROAT, RADIUS BACK WITH TURNING VANES. FLEXIBLE DUCTWORK AND SQUARE THROAT/SQUARE BACK ELBOWS SHOULD NOT BE USED. ANY TRANSITION AND/OR TURNS IN THE DUCTWORK WILL CAUSE SYSTEM EFFECT. SYSTEM EFFECT WILL DRASTICALLY INCREASE STATIC PRESSURE AND REDUCE AIRFLOW. DO NOT RELY ON UNIT TO SUPPORT DUCT IN ANY WAY. FAILURE TO PROPERLY SIZE DUCTWORK MAY CAUSE SYSTEM EFFECTS AND REDUCE PERFORMANCE OF THE EQUIPMENT. SUGGESTED STRAIGHT DUCT SIZE IS 21.5' x 39'.



REVISIONS	
DESCRIPTION	DATE

**CAPTIVE**  
www.captiveair.com  
HBT Foodservice  
104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: reg@captveair.com

Freddy's - La Grange, KY  
LA GRANGE, KY, 40031

DATE: 12/20/2022  
DWG.#: 5776897  
DRAWN BY: michael.co  
SCALE: 1/2" = 1'-0"  
MASTER DRAWING  
SHEET NO. 3

**CASE**  
Engineering Inc.  
796 Merri Court  
St. Louis, MO 63106  
F 636.349.1600  
T 636.349.1730  
CERTIFICATE OF AUTHORITY NO. 1758

**FREDDY'S FROZEN CUSTARD**  
1101 Julian Drive  
LaGrange, KY 40031  
Oldham County

**LK ARCHITECTURE, INC.**  
346 RIVERVIEW,  
WENTZLA, MO 67203  
F 316.286.0236  
Architecture · Engineering · Planning · Interior  
Design · Landscape Architecture

Professional Seal:  
STATE OF KENTUCKY  
DARRELL R. CASE  
20334  
REGISTERED PROFESSIONAL ENGINEER  
03-24-2023

MECHANICAL HOOD DRAWINGS

DATE  
Dec. 02, 2022  
03-24-2023  
REVISION

DRAWN BY: NM  
CHECKED BY: MC  
LK #22330

SHEET NO.  
**M7.0**

