



## **Project Summary**

The scope for the visit at Ralphs 004 in Laguna Beach CA was to measure the airflow as-is for the main AHU, gather performance data, and provide an as-built ductwork sketch.

The airflow for the AHU was traversed as 5647 CFM and the supply diffusers were measured as 4581 CFM. These readings indicate that there is a large amount of leakage however a major source was not be found.