

MECHANICAL SHEET INDEX

M001	MECHANICAL GENERAL INFORMATION
M101	MECHANICAL FLOOR PLAN
M150	MECHANICAL ROOF PLAN
M501	MECHANICAL DETAILS
M590	MECHANICAL SPECIFICATIONS
M591	MECHANICAL SPECIFICATIONS
M592	MECHANICAL SPECIFICATIONS
M601	MECHANICAL SCHEDULES
M630	MECHANICAL ENERGY CODE COMPLIANCE
M631	MECHANICAL ENERGY CODE COMPLIANCE
M701	CAPTIVE AIRE DRAWINGS
M702	CAPTIVE AIRE DRAWINGS
M703	CAPTIVE AIRE DRAWINGS
M704	CAPTIVE AIRE DRAWINGS
M705	CAPTIVE AIRE DRAWINGS
M706	CAPTIVE AIRE DRAWINGS
M707	CAPTIVE AIRE DRAWINGS
M708	CAPTIVE AIRE DRAWINGS
M709	CAPTIVE AIRE DRAWINGS

GENERAL NEW NOTES:

- PRIOR TO SUBMITTING BID, VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH THE EXISTING CONDITIONS OF THE PROJECT. REVIEW THE GENERAL NOTES, SPECIFICATIONS AND OTHER DRAWINGS FOR ADDITIONAL REQUIREMENTS WHICH MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY ARCHITECT, ENGINEER AND/OR OWNER OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
- COORDINATE THE INSTALLATION OF THE MECHANICAL SYSTEMS WITH OTHER TRADES TO ENSURE A NEAT AND ORDERLY INSTALLATION. INSTALL DUCTWORK AND PIPING AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS. COORDINATE INSTALLATION OF DUCTWORK AND PIPING TO AVOID CONFLICTS WITH ELECTRICAL PANELS, LIGHTING FIXTURES, ETC. ANY MODIFICATIONS REQUIRED DUE TO LACK OF COORDINATION WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AT NO EXTRA COST TO THE OWNER.
- WHERE SHUTDOWN OF EXISTING SYSTEMS IS REQUIRED DURING NEW WORK, COORDINATE SHUTDOWN TIME AND DURATION WITH THE OWNER TO MINIMIZE DOWNTIME. NOTIFY OWNER SEVEN (7) DAYS PRIOR TO INTERRUPTION OF SERVICE.
- PROVIDE TEMPORARY BARRIERS TO CONTAIN DUST AND DEBRIS RESULTING FROM THE PERFORMANCE OF THE WORK TO THE AREA WHERE WORK IS BEING PERFORMED.
- ALL MECHANICAL EQUIPMENT SHOWN ON THE MECHANICAL PLANS SHALL BE PROVIDED BY DIVISION 25 UNLESS OTHERWISE NOTED.
- NEW MECHANICAL EQUIPMENT, DUCTWORK AND PIPING ARE SHOWN AT APPROXIMATE LOCATIONS. FIELD MEASURE FINAL DUCTWORK AND PIPING LOCATIONS PRIOR TO FABRICATION AND MAKE ADJUSTMENTS AS REQUIRED TO FIT THE DUCTWORK AND PIPING WITHIN THE AVAILABLE SPACE. VERIFY THAT FINAL EQUIPMENT LOCATIONS MEET MANUFACTURER'S RECOMMENDATIONS REGARDING SERVICE CLEARANCE AND PROPER AIRFLOW CLEARANCE AROUND EQUIPMENT.
- REFER TO ARCHITECTURAL DRAWINGS FOR RELATED CONSTRUCTION DETAILS AS APPLICABLE TO THE HVAC SYSTEM. VERIFY CHASES AND PENETRATIONS SHOWN ON ARCHITECTURAL DRAWINGS THAT ARE INTENDED FOR DUCTWORK AND PIPING MEET REQUIREMENTS.
- COORDINATE LOCATION OF ROOF MOUNTED HVAC EQUIPMENT AND ROOF PENETRATIONS WITH THE ARCHITECTURAL AND STRUCTURAL DRAWINGS.
- INDOOR AIR QUALITY MEASURES: PROTECT INSIDE OF (INSTALLED AND DELIVERED) DUCTWORK AND HVAC UNITS FROM EXPOSURE TO DUST, PAINT AND MOISTURE. REPLACE INSULATION THAT HAS BECOME WET AT ANY TIME DURING CONSTRUCTION. DRYING THE INSULATION IS NOT ACCEPTABLE. SEAL ANY TEARS OR JOINTS OF INTERNAL FIBERGLASS INSULATION. REMOVE DEBRIS FROM CEILING/RETURN AIR PLenums INCLUDING DUST. AN INDEPENDENT, PROFESSIONAL DUCT CLEANING COMPANY SHALL VACUUM CLEAN ANY DUCTWORK CONNECTED TO HVAC UNITS THAT WERE OPERATED DURING THE CONSTRUCTION PERIOD AFTER NEW FILTERS ARE INSTALLED AND PRIOR TO TURNING SYSTEM OVER TO THE OWNER. THE INTERNAL SURFACES AND ASSOCIATED COILS OF ANY HVAC UNITS THAT WERE OPERATED SHALL ALSO BE CLEANED.
- INSTALL DUCTWORK AND PIPING PARALLEL TO BUILDING COLUMN LINES UNLESS OTHERWISE SHOWN OR NOTED.
- OVERHEAD HANGERS AND SUPPORTS FOR EQUIPMENT, DUCTWORK AND PIPING SHALL BE FASTENED TO BUILDING JOISTS OR BEAMS. DO NOT ATTACH HANGERS AND SUPPORTS TO THE ABOVE FLOOR SLAB OR ROOF EXCEPT WHERE CONCRETE INSERTS IN CONCRETE SLABS ARE ALLOWED BY THE SPECIFICATIONS.
- COORDINATE LOCATION OF EQUIPMENT SUPPORTS WITH LOCATION OF EQUIPMENT ACCESS PANELS/DOORS TO ENABLE SERVICE OF EQUIPMENT AND/OR FILTER REPLACEMENT.
- SEAL PENETRATIONS THROUGH THE BUILDING COMPONENTS IN ACCORDANCE WITH THE CONTRACT SPECIFICATIONS. FIREPROOF PENETRATIONS THROUGH FIRE RATED COMPONENTS IN ACCORDANCE WITH U.L. REQUIREMENTS.
- COORDINATE THE EXACT MOUNTING SIZE AND FRAME TYPE OF DIFFUSERS, REGISTERS AND GRILLES WITH THE SUPPLIER TO MEET THE CEILING, WALL AND DUCT INSTALLATION REQUIREMENTS.
- ADJUST LOCATION OF CEILING DIFFUSERS, REGISTERS AND GRILLES AS REQUIRED TO ACCOMMODATE FINAL CEILING GRID AND LIGHTING LOCATIONS.
- PAINT PORTIONS OF DUCTWORK AND INSULATION THAT ARE EXPOSED TO VIEW BY THE INSTALLATION OF DIFFUSERS, REGISTERS, AND GRILLES IN CEILINGS OR WALLS FLAT BLACK. PORTIONS INCLUDE BOTH THE INTERIOR OF UNLINED DUCTWORK AND THE EXTERIOR OF DUCTWORK AND INSULATION.
- LOCATE AND SET THERMOSTATS AND HUMIDISTATS AT LOCATIONS SHOWN ON PLANS. VERIFY EXACT LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION. INSTALL DEVICES WITH TOP OF DEVICE AT MAXIMUM 48" AFF TO MEET ADA REQUIREMENTS UNLESS NOTED OTHERWISE ON PLANS. PROVIDE INSULATED BACKING FOR THERMOSTATS MOUNTED ON EXTERIOR BUILDING WALLS. INSTALL WRAP IN CONDUIT PROVIDED BY DIVISION 26. AT A MINIMUM, PROVIDE CONDUIT IN THE WALL FROM THE JUNCTION BOX TO 6" ABOVE THE CEILING.
- COORDINATE THE LOCATION AND ELEVATION OF WALL-MOUNTED DEVICES WITH PRESENTATION CABINETS, DISPLAY CABINETS, SHELVES OR OTHER COMPONENTS SHOWN ON THE ARCHITECTURAL DRAWINGS THAT ARE TO BE INSTALLED UNDER OTHER DIVISIONS. CONTRACTOR WILL NOT BE REIMBURSED FOR RELOCATION OF WALL-MOUNTED DEVICES CAUSED BY A LACK OF COORDINATION.
- PROVIDE A MANUAL BALANCING DAMPER IN EACH DUCT TAKEOFF FROM SUPPLY, RETURN, OUTDOOR AND EXHAUST AIR DUCTS.
- PROVIDE A PREFABRICATED 45 DEGREE, HIGH EFFICIENCY, RECTANGULAR/ROUND BRANCH DUCT TAKEOFF FITTING FOR BRANCH DUCT CONNECTIONS AND TAKE-OFFS TO INDIVIDUAL DIFFUSERS, REGISTERS AND GRILLES. PROVIDE WITH INTEGRAL MANUAL BALANCING DAMPER AND LOCKING QUADRANT WHERE INDICATED ON PLANS.
- BRANCH DUCTWORK TO AIR OUTLETS SHALL BE SAME SIZE AS OUTLET NECK SIZE UNLESS OTHERWISE NOTED.
- REFER TO SPECIFICATIONS FOR DUCTWORK AND PIPING INSULATION REQUIREMENTS. DUCT SIZES ON MECHANICAL PLANS INDICATE CLEAR INSIDE AIRFLOW DIMENSIONS. INCREASE SHEET METAL SIZES ACCORDINGLY TO ACCOUNT FOR THICKNESS OF DUCT LINER.
- FLEXIBLE DUCTWORK SHALL NOT EXCEED 5'-0" IN LENGTH AND SHALL BE INSTALLED AND SUPPORTED TO AVOID SHARP BENDS AND SAGGING. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- PROVIDE EQUIPMENT VENTS AND FLUES PER EQUIPMENT MANUFACTURERS RECOMMENDATIONS AND EQUIPMENT SPECIFICATIONS. KEEP PENETRATIONS THROUGH ROOF AT A MINIMUM OF 10'-0" FROM HVAC EQUIPMENT FRESH AIR INLETS AND 2'-0" FROM ROOF PARAPETS.
- PROVIDE TYPE I GREASE HOOD EXHAUST DUCTWORK OF MINIMUM 1/8 GAUGE BLACK IRON WITH LIQUID TIGHT WELDS, WITH ACCESS PANELS FOR GREASE CLEANING AS REQUIRED BY NFPA 96 AND LOCAL CODES. SLOPE DUCT BACK TOWARDS HOOD AT MINIMUM OF 1/4" PER LINEAL FOOT MAINTAIN 18" CLEARANCE TO COMBUSTIBLE MATERIALS. INSTALL GREASE DUCTS IN AN APPROVED FIRE-RATED ENCLOSURE SEPARATED FROM THE EXHAUST DUCT BY A MINIMUM OF 6" AND MAXIMUM OF 12". VENTILATE ENCLOSURE TO THE OUTSIDE AIR IF REQUIRED BY CODE. AS AN OPTION, IF APPROVED BY LOCAL CODES, PROVIDE AN APPROVED WRAP SYSTEM IN LIEU OF THE RATED DUCT ENCLOSURE SYSTEM. DUCT WRAP SYSTEM SHALL MEET UL REQUIREMENTS FOR GREASE DUCT ENCLOSURES.
- PROVIDE A NEW SET OF AIR FILTERS IN UNITS PRIOR TO TESTING, ADJUSTING AND BALANCING AND BEFORE TURNING SYSTEM(S) OVER TO OWNER.
- TEMPORARY INSTALLATIONS OF INFECTION CONTROL MEASURES DURING CONSTRUCTION SHALL BE COORDINATED WITH THE FACILITY'S INFECTION CONTROL STAFF. PRIOR TO CONSTRUCTION PROVIDE ALL REQUIRED TEMPORARY INSTALLATIONS, INCLUDING DETAILS OF THE INFECTION CONTROL MEASURES SUCH AS TEMPORARY BARRIERS AND MEMBRANES, PORTABLE EXHAUST FANS AND TEMPORARY DUCTWORK. TEMPORARY INSTALLATIONS MUST NOT HAVE A NEGATIVE IMPACT ON EXISTING SYSTEMS NOR CAUSE UNSAFE CONDITIONS. TEMPORARY INSTALLATIONS SHALL MAINTAIN ADEQUATE EGRESS AND SHALL NOT OBSTRUCT EXISTING EXITS. CREATE A FIRE HAZARD OR REDUCE REQUIRED FIRE RESISTANCE. TEMPORARY VENTILATION SYSTEMS SHALL NOT CAUSE THE AIR BALANCE OF ADJACENT ROOMS OR SPACES TO BE IMPACTED OR ALTER THE PERFORMANCE OF PERMANENT BUILDING VENTILATION SYSTEMS. AIRFLOW MEASUREMENTS SHALL BE TAKEN TO VERIFY ADJACENT ROOMS OR SPACES ARE NOT IMPACTED.

MECHANICAL SYMBOLS

THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS OR ABBREVIATIONS ARE USED.

V2.06

STANDARD MOUNTING HEIGHT		HVAC DUCTWORK AND ACCESSORIES		PIPING SYMBOLS	
THERMOSTATS (USER ADJUSTABLE/TOP OF DEVICE)		48" 48"		DIRECTION OF FLOW	
INSTALL DEVICES AT THE MOUNTING HEIGHTS SHOWN ABOVE UNO IN THE CONSTRUCTION DOCUMENTS. MOUNTING HEIGHTS LISTED ABOVE OR ELSEWHERE IN THE CONSTRUCTION DOCUMENTS ARE AFF OR AFG TO BOTTOM OF DEVICE UNO. ALL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH CURRENT ADA AND LOCAL REQUIREMENTS.		LINEAR SLOT DIFFUSER		CONTROL VALVE	
ANNOTATION		INSULATED FLEXIBLE DUCT (MAX. 5'-0" LONG)		THREE-WAY CONTROL VALVE	
MECHANICAL PLAN NOTE CALLOUT		BRANCH DUCT WITH 45° RECTANGLE-ROUND BRANCH FITTING AND MANUAL VOLUME DAMPER		SHUTOFF VALVE	
MECHANICAL EQUIPMENT DESIGNATION (CONTRACTOR FURNISHED AND INSTALLED UNLESS NOTED OTHERWISE)		ELBOW WITH TURNING VANES		CHECK VALVE	
CONNECTION POINT OF NEW WORK TO EXISTING		BRANCH DUCT WITH BELL-MOUTH FITTING & MANUAL VOLUME CONTROL DAMPER		BALANCING VALVE WITH PRESSURE PORTS	
DETAIL REFERENCE. UPPER NUMBER INDICATES DETAIL NUMBER LOWER NUMBER INDICATES SHEET NUMBER		RETURN, EXHAUST, OR OUTSIDE AIR DUCT UP		TRIPLE DUTY VALVE WITH PRESSURE PORTS	
SECTION CUT DESIGNATION		RETURN, EXHAUST, OR OUTSIDE AIR DUCT DOWN		STRAINER	
ABBREVIATIONS		SUPPLY AIR DUCT UP		STRAINER WITH BLOWDOWN VALVE	
A/C AIR CONDITIONING		SUPPLY AIR DUCT DOWN		RELIEF / SAFETY VALVE	
ACC AIR COOLED CHILLER		EQUIPMENT WITH FLEXIBLE DUCT CONNECTION		SOLENOID VALVE	
ACCU AIR COOLED CONDENSING UNIT		10" (NECK SIZE) CSD-1 (TYPE) 300 CFM (CFM OF SUPPLY DIFFUSER OR REGISTER)		PRESSURE REDUCING VALVE	
AFC ABOVE FINISHED CEILING		24x24 (NECK SIZE) CEG-1 (TYPE) 800 CFM (CFM OF EXHAUST GRILLE)		GAS PRESSURE REGULATOR	
AFF ABOVE FINISHED FLOOR		MANUAL VOLUME DAMPER		THERMOSTATIC MIXING VALVE	
AFG ABOVE FINISHED GRADE		SQUARE TO ROUND TRANSITION		PIPE ANCHOR	
AHJ AUTHORITY HAVING JURISDICTION		DUCT MOUNTED SMOKE DETECTOR (SD=SUPPLY/R=RETURN)		EXPANSION JOINT	
AHU AIR HANDLING UNIT		ROUND DUCT TAG INDICATING DIAMETER		PIPE GUIDE	
AI ANALOG INPUT		RECTANGULAR DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS.		PIPING SUPPORT	
AO ANALOG OUTPUT		FLAT OVAL DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS		F & T TRAP	
AP ACCESS PANEL		RISER DESIGNATION		BUCKET TRAP	
APD AIR PRESSURE DROP		FIRE DAMPER		THERMOSTATIC TRAP	
AWG AMERICAN WIRE GAUGE		FIRE SMOKE DAMPER		BACKFLOW PREVENTER	
B BOILER		SMOKE DAMPER		PRESSURE GAUGE	
BAS BUILDING AUTOMATION SYSTEM		VOLUME DAMPER		THERMOMETER	
BB BACKDRAFT DAMPER		MOTORIZED DAMPER		PRESSURE AND TEMPERATURE TEST PLUG	
BD BLOWDOWN		BACKDRAFT DAMPER		UNION	
BFC BELOW FINISHED CEILING		HUMIDISTAT		FLANGE CONNECTION	
BFF BELOW FINISHED FLOOR		THERMOSTAT		VACUUM RELIEF VALVE	
BFG BELOW FINISHED GRADE		CARBON MONOXIDE SENSOR		AUTOMATIC AIR VENT	
BFP BOILER FEED PUMP		CARBON DIOXIDE SENSOR		MANUAL AIR VENT	
BHP BRAKE HORSEPOWER		DIFFERENTIAL PRESSURE SENSOR		PRESSURE / VACUUM SWITCH	
BI BINARY INPUT		FLOW SWITCH		CLEANOUT	
BO BINARY OUTPUT		HUMIDITY SENSOR		CAP	
BOD BOTTOM OF DUCT		PULL STATION		ELBOW UP	
BOS BOTTOM OF STRUCTURE		TEMPERATURE SENSOR		ELBOW DOWN	
BTU BRITISH THERMAL UNIT		TEMPERATURE CONTROL		TEE UP	
CFM CUBIC FEET PER MINUTE		TRANSFER FAN		TEE DOWN	
CH CHILLER		TO FLOOR ABOVE		ELBOW UP WITH SHUT-OFF VALVE (SOV)	
CO COOLING COIL		TO FLOOR BELOW		ELBOW DOWN WITH SHUT-OFF VALVE (SOV)	
COP CLEANOUT		TOTAL HEAT CAPACITY		TEE UP WITH SHUT-OFF VALVE (SOV)	
CP CONDENSATE PUMP		TOTAL STATIC PRESSURE		TEE DOWN WITH SHUT-OFF VALVE (SOV)	
CPT CONTROL POWER TRANSFORMER		TEMPERATURE		REDUCER	
CRAC COMPUTER ROOM AIR CONDITIONING UNIT		TEMPERATURE CONTROLS CONTRACTOR		RECIRCULATION PUMP	
CRU COMPUTER ROOM UNIT		TEMPERATURE CONTROL		P-TRAP	
CT COOLING TOWER		TYPICAL		GAS COCK	
CV CONTROL VALVE		UNDERFLOOR		TOP BEAM CLAMP	
CWP CONDENSER		UNDERGROUND		TRAPEZE HANGER	
CU WATER PUMP		UNDERSLAB		FLEXIBLE CONNECTION	
CUC CONDENSING UNIT		UNIT HEATER			
CHWP CHILLED WATER PUMP		UNLESS NOTED OTHERWISE			
DBA DECIBEL AVERAGE		UNIT HEATER			
DDC DIRECT DIGITAL CONTROL		TOTAL HEAT CAPACITY			
DI DIGITAL INPUT		TOTAL STATIC PRESSURE			
DISC DISCONNECT		TEMPERATURE			
DN DOWN		TEMPERATURE CONTROL			
DS DUCT SILENCER		TRANSFER FAN			
DX DIRECT EXPANSION		TO FLOOR ABOVE			
(E) EXISTING		TO FLOOR BELOW			
EA EXHAUST AIR		TOTAL HEAT CAPACITY			
EAT ENTERING AIR TEMPERATURE		TOTAL STATIC PRESSURE			
ED EXHAUST DUCT		TEMPERATURE			
EDB ENTERING DRY BULB EXHAUST FAN		TRANSFERRING			
EFF EFFICIENCY		TYPICAL			
EMS ENERGY MANAGEMENT SYSTEM		UNDERFLOOR			
ESP EXTERNAL STATIC PRESSURE		UNDERGROUND			
ETR EXISTING TO REMAIN		UNDERSLAB			
EWT ENTERING WET BULB TEMPERATURE		UNIT HEATER			
EWD ENTERING WATER DRIVE		UNLESS NOTED OTHERWISE			
FCU FAN COIL UNIT		UNIT HEATER			
FFA FROM FLOOR ABOVE		TOTAL HEAT CAPACITY			
FFB FROM FLOOR BELOW		TOTAL STATIC PRESSURE			
FFC FINISHED FLOOR		TEMPERATURE			
FFD FINISHED FLOOR		TRANSFER FAN			
FFI FINIS PER INCH		TO FLOOR ABOVE			
FFM FEET PER MINUTE		TO FLOOR BELOW			
GC GENERAL CONTRACTOR		TOTAL HEAT CAPACITY			
GPM GALLONS PER MINUTE		TEMPERATURE			
HOA HAND-OFF-AUTOMATIC		TEMPERATURE CONTROL			
HP HORSEPOWER		TRANSFER FAN			
HTG HEATING		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL STATIC PRESSURE			
		TEMPERATURE			
		TRANSFER FAN			
		TO FLOOR ABOVE			
		TO FLOOR BELOW			
		TOTAL HEAT CAPACITY			
		TOTAL			

REVISION

DATE	DESCRIPTION
09.11.24	PERMIT SET
C 11.05.24	REVISION C
D 12.02.24	REVISION D / IFC SET

STATUS:
IFC SET

LANDLORD'S REVIEW COMMENTS

MECHANICAL COMMENTS:

- ANY CHANGES AND/OR UPGRADES TO TENANT'S EXISTING MECHANICAL SYSTEMS SHALL COMPLY WITH ALL CODES AND MALL CRITERIA. EXISTING SYSTEMS SHALL POSSESS THE CAPACITY TO HANDLE ANY AND ALL CHANGES IN LOAD.
- NO PITCH POCKETS ARE PERMITTED ON THE ROOF FOR ANY CONDENSATE DRAINS, REFRIGERANT PIPING, POWER OR CONTROL WIRING. ALL CONNECTIONS ARE TO BE MADE INSIDE THE EQUIPMENT CURB OR THROUGH PRE-MANUFACTURED PIPING CURB.
- NOTHING IS PERMITTED TO BE ATTACHED TO, SUSPENDED FROM, OR PENETRATE LANDLORD'S STRUCTURE, FLOOR DECK, OR ROOF DECK. YOU MAY ATTACH, ATTACH, NON-DESTRUCTIVELY, TO OR SUSPEND FROM THE TOP CHORD OF THE JOIST OR THE STRUCTURAL STEEL WHICH EXISTS ABOVE THE TENANT SPACE. WHEN ATTACHING TO LANDLORD'S STRUCTURE, **DO NOT DRILL, WELD, SCREW, OR SHOOT** INTO STRUCTURE. ALTERNATIVE METHODS OF ATTACHMENT ONLY. NOTHING TO DAMAGE LANDLORD'S BASE STRUCTURE. TENANT SHALL PROVIDE SIGNED AND SEALED STRUCTURAL DRAWINGS, BY A STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION AS INDICATED BY ALL JURISDICTIONAL REQUIREMENTS, FOR ALL STRUCTURAL MODIFICATIONS FOR LANDLORD RECORDS.
- ALL PENETRATIONS TO ROOF MUST BE APPROVED BY LANDLORD. ALL RELATED ROOF WORK MUST BE DONE BY MALL'S DESIGNATED ROOFING CONTRACTOR, AT TENANT'S EXPENSE. COORDINATE ALL WORK WITH PROPERTY MANAGEMENT ON SITE.
- TENANT MUST REMOVE ALL ABANDONED ROOFTOP AND/OR MECHANICAL EQUIPMENT ABOVE THE LEASED PREMISES AND WITHIN THE LEASED PREMISES, AT TENANT EXPENSE. PATCH AND REPAIR ROOF AS NEEDED.
- TENANT'S GO TO LABEL ALL ROOF TOP EQUIPMENT WITH TENANT NAME SPACE NUMBER AND EQUIPMENT IDENTIFICATION (RTU-1, EF-1), PER MALL SPECIFICATIONS/ STANDARDS.
- ALL PIPING ON ROOF SHALL BE SUPPORTED ON PRE-MANUFACTURED PIPE SUPPORTS INSTALLED ON CARRY TREAD, SPACED PROPERLY TO SUPPORT PIPING. TREATED WOOD SUPPORTS ARE NOT PERMITTED.
- ALL UNEXPOSED SUPPLY AIR AND OUTSIDE AIR DUCTWORK SHALL BE EXTERNALLY INSULATED WITH 1 1/2" THICK FOIL FACE INSULATION. INTERNALLY LINED DUCTWORK MAY BE USED FOR ACOUSTIC PURPOSES ONLY, NOT AS A SUBSTITUTE FOR EXTERNAL INSULATION.
- ALL DUCTWORK SHALL BE SHEET METAL. FLEX DUCT MAY ONLY BE USED IN RUNS OF 5'-0" OR LESS.
- AT CONCLUSION OF PROJECT, HVAC SYSTEM MUST BE TESTED AND BALANCED BY A LICENSED CONTRACTOR. COPY OF A BALANCE REPORT MUST BE PROVIDED TO PROPERTY MANAGEMENT OFFICE ON-SITE.
- LANDLORD STRONGLY PREFERS USE ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.

MECHANICAL GENERAL NOTES:

- DO NOT ROUTE ANY DUCTWORK OR PIPING ABOVE ELECTRICAL PANELS. REFER TO SHEET M001 FOR ADDITIONAL GENERAL NOTES AND REQUIREMENTS.
- REFER TO DETAILS AND SCHEDULES SHEETS FOR FURTHER INFORMATION. MOUNT ALL THERMOSTATS AND SENSORS CONTROLLING HVAC EQUIPMENT AT 48" AFF UNLESS OTHERWISE NOTED.

MECHANICAL PLAN NOTES:

- TYPE I HOODS SHALL BE FURNISHED COMPLETE WITH INTERNALLY PIPED FIRE SUPPRESSION SYSTEM AND EXTERNAL FOAM SUPPLY BOTTLES WITH REMOTE PULL CONTROLS AND IN COMPLIANCE WITH NFPA 96. DIVISION 23 SHALL COORDINATE COMPLETE INSTALLATION WITH FIRE PROTECTION CONTRACTOR TO MEET APPROVAL OF LOCAL INSPECTOR AND CODE COMPLIANCE INCLUDING TESTING.
- MOUNT THERMOSTATS, HUMIDITY SENSORS, AND TEMPERATURE SENSOR(S) ON WALL. THERMOSTATS AND SENSOR(S) SHALL BE LABELED TO MATCH THE UNIT TAG AND CORRESPOND TO THE ELECTRICAL LEGEND IN THE ELECTRICAL PANELBOARD SERVING THE EQUIPMENT. COORDINATE COLOR WITH ARCHITECT.
- MOUNT TEMPERATURE SENSOR PROVIDED WITH KITCHEN EXHAUST HOODS ON WALL.
- INSTALL "DUCTIMATE ULTIMATE DOOR" ON DUCTS 12" OR LARGER AND INSTALL "DUCTIMATE P2 SANDWICH ACCESS DOOR" FOR DUCTS LESS THAN 12" ON GREASE DUCT FOR CLEANING IN LOCATION SHOWN AT A MINIMUM AND AS REQUIRED BY NFPA 96 AND LOCAL CODES.
- INSTALL HOOD FIRE SUPPRESSION MANUAL PULL STATION, COORDINATE EXACT LOCATION AND REQUIREMENTS WITH FIRE SUPPRESSION SYSTEM INSTALLER AND THE AUTHORITY HAVING JURISDICTION.
- PROVIDE RA DUCT THROUGH ROOF, FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR, TRANSITION 45 DEGREES THROUGH ROOF CURB.
- PROVIDE SA DUCT THROUGH ROOF, FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR, TRANSITION 45 DEGREES THROUGH ROOF CURB.
- INSTALL DUCT SMOKE DETECTOR IN RETURN AIR PLENUM.
- COMBINATION TEMPERATURE SENSOR AND HUMIDITY SENSOR.
- TYPE I GREASE HOOD EXHAUST DUCTWORK SHALL BE MINIMUM 18 GAUGE STEEL OR MINIMUM 18 GAUGE STAINLESS STEEL WITH LIQUID TIGHT WELDS.
- AIR CURTAIN MOUNTED ABOVE DOOR, INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
- TRANSITION 8" OUTDOOR AIR DUCT TO 4" FLEXIBLE DUCTWORK AND CONNECT TO UNIT.
- HOOD SHALL OVERHANG THE COOKING SURFACE BY AT LEAST 6" ON BOTH SIDES.
- REFRIGERANT PIPING UP TO CU-1 ON ROOF, REF 1M150.
- PROVIDE COMBUSTION AIR AND EXHAUST PIPE AND ROUTE TO CONCENTRIC VENT THROUGH ROOF.
- 8"X8" GREASE EXHAUST DUCT UP TO KEF-1 ON ROOF.
- 10"X10" GREASE EXHAUST DUCT UP TO KEF-2 ON ROOF.
- CARBON DIOXIDE SENSOR WITH REMOTE ALARM REPEATER FURNISHED BY OWNER'S CO2 VENDOR AND LOCATED AT 12" AFF. THE SENSOR SHALL BE EQUIPPED WITH A LOCAL AUDIBLE AND VISUAL ALARM. THE LOW-LEVEL ALARM SHALL ACTIVATE THE LOCAL AUDIBLE AND VISUAL ALARM. IF THE BUILDING HAS A FIRE ALARM, PROVIDE THE APPROPRIATE FIRE ALARM INTERFACE MODULE TO INTERLOCK WITH THE BUILDING FIRE ALARM SYSTEM. THE HIGH-LEVEL CO2 ALARM SHALL SIGNAL BUILDING FIRE ALARM WHEN EQUIPPED. LOW LEVEL ALARM - 0.5% = 5,000 PPM. HIGH LEVEL ALARM - 3.0% = 30,000 PPM.
- PROVIDE EA DUCT THROUGH ROOF, TRANSITION TO EXHAUST FAN INLET SIZE WITHIN CURB.

DIFFUSER LOCATIONS TO BE LOCATED SO AIRFLOW DOES NOT DISTURB EXHAUST THRU THE HOODS.

HOODS MUST CAPTURE AND CONTAIN ALL KITCHEN EXHAUST.

THIS TENANT'S GREASE EXHAUST OPERATION MUST MAINTAIN A NEGATIVE AIR BALANCE TO THIS TENANT'S DINING AREA AND TO THE MALL. IF ODORS MIGRATE OUT OF LEASED SPACE, TENANT WILL THEN BE REQUIRED TO INCREASE THE EXHAUST FLOW RATE AND MAINTAIN A GREATER NEGATIVE AIR PRESSURE. THIS REQUIREMENT WILL ALSO BE AT MALL MANAGERMENTS DISCRETION.

EXTERNALLY INSULATED FLEXIBLE DUCT NOT TO EXCEED 15'-0" LENGTH, MAY BE USED FOR VERTICAL CONNECTIONS TO SUPPLY DIFFUSERS ONLY.

EXTERNAL FOIL WRAP INSULATION IS MANDATORY FOR ALL SUPPLY AIR DUCT WORK IN CLOSED CEILING AREA AND NOT IN LIEU OF INTERNAL DUCT LINER.



MECHANICAL FLOOR PLAN
 1/4" = 1'-0"

THE BUILDINGS HVAC SYSTEMS SHALL BE BALANCED BY NATIONAL TAB (NO EXCEPTIONS) AND CONTRACTED BY THE GENERAL CONTRACTOR.

CONTACT:
 WILL TURNBOUGH
 will@natonstab.com
 855-682-6822 ext704

ALL GREASE DUCT TO BE WATER TESTED BY ENVIROMATIC AT MECHANICAL CONTRACTOR'S EXPENSE. CONTACT OWNER'S NATIONAL ACCOUNT VENDOR.

ENVIROMATIC
 DON PFLEDERER
 1.800.325.9476
 inspections@enviromatic.com



REVISION	
DATE	DESCRIPTION
09.11.24	PERMIT SET
11.05.24	REVISION C
12.02.24	REVISION D / IFC SET

STATUS:
IFC SET

SHEET NAME:
MECHANICAL ROOF PLAN

DATE:
09/11/24

PROJECT NO:
39018

DRAWN:
HEI

SCALE:
AS NOTED

SHEET NO:
M150

MECHANICAL PLAN NOTES:

- CONTRACTOR SHALL VERIFY WITH EQUIPMENT SUPPLIER EXACT ROUTING AND SIZE OF INSULATED REFRIGERANT PIPING. SINGLE LINESET SHOWN FOR CLARITY. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
- TURN DOWN 6" INTAKE AND END OPEN OVER ROOF (MIN. 24") WITH INSECT SCREEN.
- CONTRACTOR SHALL COORDINATE WITH NATIONAL TAB TO PROVIDE UV-PIH INDOOR AIR PURIFICATION SYSTEM, MODEL PH-PRO-24V. INSTALL IN UNIT BLOWER COMPARTMENT PER MANUFACTURER'S INSTRUCTIONS.
- REFERENCE PLUMBING DRAWINGS FOR CONDENSATE DRAIN ROUTING AND TERMINATION REQUIREMENTS.
- PROVIDE CONCENTRIC VENT MODEL NUMBER PVC-3CT.
- MAINTAIN ALL OUTSIDE AIR INTAKES A MINIMUM OF 10'-0" RADIUS FROM EXHAUST, TYPICAL.
- AREA RESERVED FOR REFRIGERATION CONDENSER(S) PROVIDED BY KITCHEN EQUIPMENT CONTRACTOR. COORDINATE EQUIPMENT LOCATION AND CONDENSER INSTALLATION WITH KITCHEN EQUIPMENT CONTRACTOR.

LANDLORD COMMENTS:


- ENSURE THAT PARAPET COVERS ROOF TOP EQUIPMENT VISIBILITY FROM THE GROUND, OR PROVIDE A SCREEN WALL.
- ENSURE THAT ALL ROOFING WARRANTIES REMAIN IN TACT.
- ENSURE THAT ALL ODORS/SMELLS FROM EXHAUST DO NOT EMANATE INTO THE MALL OR OTHER TENANT INTAKES.
- ALL ROOF TOP EQUIPMENT LOCATIONS TO BE LOCATED IN AREAS DESIGNATED BY ALL I APPROVED STRUCTURAL ENGINEER.
- ALL ROOF TOP UNITS SHALL BE SET ON A FACTORY SUPPLIED CURB AND MUST EXTEND A MINIMUM OF 12" ABOVE HIGH POINT ROOFING MATERIAL. CURB ADAPTERS ARE NOT ALLOWED.
- VERIFY WITH AMLL OPERATIONS FOR APPROVAL OF ALL ROOF EQUIPMENT LOCATIONS FOR SIGN LINE ISSUES.
- POWER CONNECTION AND DUCTWORK TO RTU TO BE WITHIN PERIMETER OF THE ROOF CURB AND NOT THROUGH ROOF.
- ALL CONDENSATE PIPING SHALL BE COPPER AND INSULATED BELOW ROOF LINE. TENANT SHALL VERIFY WITH THE MALL OPERATIONS DIRECTOR THE CORRECT METHOD AND LOCATION OF CONDENSATE DISCHARGE FROM UNITS PRIOR TO BID.
- IF MALL CRITERIA CALLS FOR CONDENSATE TO DRAIN WITHIN TENANT SPACE, THEN CONDENSATE FROM RTU TO ROUTE WITHIN THE PERIMETER OF THE ROOF CURB AND NOT THROUGH THE ROOF.
- VERIFY A MINIMUM 10' DISTANCE FROM ALL EXHAUST FROM THE CLOSEST AIR INTAKE POINT.
- ALL ROOFWORK TO BE PERFORMED BY LANDLORD'S ROOFING CONTRACTOR AT TENANT'S EXPENSE.
- ALL STEEL MODIFICATIONS TO RTU INSTALLATION TO BE DONE BY LANDLORD APPROVED STEEL CONTRACTOR AT TENANT'S EXPENSE.
- TGC TO LABEL ALL ROOF TOP EQUIPMENT WITH TENANT NAME, SPACE NUMBER, AND EQUIPMENT ID PER SMALL STANDARD.
- AT CONCLUSION OF PROJECT, HVAC SYSTEMS MUST BE TESTED AND BALANCED BY A LICENSED CONTRACTOR. COPY OF BALANCE REPORT MUST BE PROVIDED TO THE PROPERTY MANAGEMENT OFFICE ON SITE.
- ROOF TOP UNITS MUST INCLUDE HAIL GUARD ON THE CONDENSER COIL.
- THE MALL OPERATIONS DIRECTOR MUST APPROVE THE LOCATION OF THE CONDENSATE AND REFRIGERANT PIPING ROUTING.
- ALL PIPING THROUGH ROOF MUST USE A PRE-MANUFACTURED PORTALS PLUS OR PATE TYPE RAIL SYSTEM. (NO WOOD BLOCKING IS PERMITTED)
- THE CONDENSING UNIT MUST BE ON FULL PERIMETER CURBS WITH PORTAS PLUS OR PATE TYPE RAILS (NO WOOD BLOCKING IS PERMITTED)
- ALL PIPING ON THE ROOF SHALL BE SUPPORTED WITH PRE-MANUFACTURED PIP SUPPORTS ON CARRY THREAD, SPACED TO PROPERLY SUPPORTING PIPING. USE PORTALS PLUS OR MIRO SUPPORTS—THE USE OF WOOD FOR SUPPORTS IS PROHIBITED.
- ALL ROOF WORK TO BE PERFORMED BY LANDLORD'S ROOFING CONTRACTOR AT TENANT'S EXPENSE.
- THE ROOF AREA AROUND THE EXHAUST FAN SHALL BE PROTECTED WITH GREASE-GUARD G-2 GREASE COLLECTION SYSTEM, AS MANUFACTURED BY ROOFTOP DEFENSE SYSTEMS, 1-800-913-7034.


LANDLORD'S REVIEW COMMENTS

LANDLORD ROOF TOP EQUIPMENT COMMENTS:

- ROOF EQUIPMENT, INCLUDING BUT NOT LIMITED TO HVAC EQUIPMENT, KITCHEN EQUIPMENT, DUCTS, AND PIPING SHALL BE SHOWN ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. SHALL NOT BE VISIBLE FROM THE OUTER RING ROAD OR FROM MALL SKYLIGHTS, LOCATED WITHIN THE ROOF AREA OF THE PREMISES AND MINIMUM OF 5'-0" FROM THE VERTICAL PLANE OF ANY DEMISING PARTITION LOCATED, AND SHALL BE COORDINATE WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK. EQUIPMENT SCREENS OR SCREEN WALLS MAYBE REQUIRED AND SHALL BE APPROVED IN WRITING BY LANDLORD UNDER SEPARATE COVER.
- TENANT SHALL PROVIDE A STRUCTURAL ENGINEER EVALUATION OF THE EXISTING CONSTRUCTION / STRUCTURE AND DETERMINES THAT IT IS SUFFICIENT FOR THE ADDITIONAL LOADS OF ALL NEW ROOF TOP EQUIPMENT IN ACCORDANCE WITH THE BUILDING CODE THAT HAS BEEN ADOPTED BY THE AUTHORITIES HAVING JURISDICTION (AHJ) AT TENANT'S SOLE EXPENSE. STRUCTURAL DETAILS ARE TO INCLUDE REFERENCE OF APPLICABLE BUILDING CODE(S), EXISTING BUILDING LOADS, AND ADDITIONAL LOADS THAT WILL BE ADDED TO THE STRUCTURE AN ANY REINFORCING THAT IS REQUIRED. STRUCTURAL DETAILS ARE TO BE SIGNED, SEALED, AND SUBMIT TO THE LANDLORD FOR THEIR RECORDS BY A LICENSED STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION IN THE STATE IN WHICH THE PROJECT IS LOCATED. LANDLORD RESERVE THE RIGHT TO HAVE A 3RD PARTY ENGINEER PROVIDE DOCUMENTATION BY A 3RD PARTY INSPECTOR TO VERIFY THAT STRUCTURAL INSTALLATION HAS BEEN INSTALLED CORRECTLY.
- ROOF EQUIPMENT REQUIRING DECK PENETRATION SHALL BE SET ON THE FACTORY SUPPLIED CURB AND MUST EXTEND A MINIMUM OF 12" ABOVE HIGHEST ROOF MATERIAL. RE-USE OF EXISTING CURBS OR THE USE OF CURB ADAPTERS IS STRICTLY PROHIBITED. TENANT SHALL RE-SLOPE ROOF TO MAIN PROPER DRAINAGE AND PROVIDE ROOFING, FLASHING, AND WATERPROOFING FOR INSTALLATION OF NEW CURB PER LANDLORD'S CRITERIA TENANT'S SOLE EXPENSE.
- ALL CONDENSATION, ELECTRICAL AND DUCTWORK SHALL BE SET INSIDE THE PERIMETER OF CURB. CONDENSATE SHALL DRAIN INTO AN INTERIOR FLOOR DRAIN OR MOP SINK WITHIN THE PREMISES. DRAINING CONDENSATE LINES DIRECTLY ONTO THE ROOF, DOWNSPOUT OR ROOF DRAIN IS STRICTLY PROHIBITED.
- TENANT SHALL PROVIDE "ROOF TRAFFIC" / WALKWAY PADS" AROUND ALL ROOF TOP EQUIPMENT AND SHALL INDICATE LOCATION OF PADS ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. COORDINATE FINAL LOCATION, MATERIAL, AND INSTALLATION OF PADS WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK.
- TENANT SHALL LABEL ALL ROOF TOP EQUIPMENT INDICATING: TENANT NAME, SPACE NUMBER, AND EQUIPMENT IDENTIFICATION (RTU-1, EFT-1) PER LANDLORD'S DESIGN CRITERIA.
- EQUIPMENT THAT UTILIZES CONDENSER COILS SHALL BE EQUIPPED WITH HAIL GUARDS.
- LANDLORD STRONGLY PREFERS USE OF ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.


1 MECHANICAL ROOF PLAN
1/4" = 1'-0"






- NOTES:
- CUT METAL DECKING TO ALLOW CURB INSTALLATION ON STEEL FRAMING. AFTER CURB IS SET IN PLACE, TRIM REMAINING METAL DECKING AND INSTALL WITH CURB. TACK WELD DECKING TO SUPPORT STEEL. DO NOT WELD INTERIOR DECKING TO ROOF CURB. PROVIDE ADDITIONAL CROSS FRAMING TO SUPPORT INTERIOR DECKING AND FILL MATERIAL AS REQUIRED.
 - REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR ROOF CURBS, ANCHORING AND SEISMIC/WIND RESISTANCE.

13 ROOF CURB DETAIL NTS




- NOTES:
- REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR EQUIPMENT SUPPORTS, ANCHORING AND SEISMIC/WIND RESISTANCE.

9 ROOF EQUIPMENT SUPPORT RAIL DETAIL NTS




- NOTES:
- USE THREADED ROD FOR RECTANGULAR DUCTS LARGER THAN 60\"/>

6 DUCT HANGER LOWER ATTACHMENT DETAILS NTS




3 DUCT MOUNTED REGISTER DETAIL NTS




- NOTES:
- ARRANGEMENT SHOWN IS SCHEMATIC. ADJUST TO SUIT FIELD CONDITIONS AND MEET LOCAL CODE.
 - PROVIDE CURB EXTENSION MADE FROM NON-COMBUSTIBLE MATERIAL. OF HEIGHT REQUIRED TO MOUNT FAN BASE A MINIMUM 18 INCHES ABOVE COMBUSTIBLE CURB MATERIAL AND DISCHARGE GREASE OUTLET A MINIMUM OF 40 INCHES ABOVE ROOF SURFACE OR ANY ADJACENT BUILDING STRUCTURE WITHIN 10 FEET OF OUTLET, WHICHEVER IS HIGHER.
 - PREFABRICATED INSULATED ROOF CURB WITH TREATED WOOD NAILER, CANT, AND STEP AS REQUIRED TO ACCOMMODATE ROOF INSULATION. FRAME AND SECURE CURB TO ROOF WITH METHOD CONSISTENT WITH ROOF CONSTRUCTION. ROOF CURB SHALL BEAR ON ROOF STRUCTURE. FOR SLOPED ROOFS, PROVIDE CURB WITH DIMENSIONS CAPABLE OF COMPENSATING ROOF SLOPE TO ENSURE FAN IS INSTALLED LEVEL. REFER TO ARCHITECTURAL DRAWINGS AND CURB MANUFACTURER'S DETAILS FOR MORE INFORMATION.

12 UPBLAST GREASE EXHAUST FAN DETAIL NTS




- NOTES:
- FOR REFERENCE ONLY. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
 - AT CONTRACTOR'S OPTION, A LISTED UL 1978 GREASE ACCESS DOOR PRODUCT MAY BE SUBSTITUTED FOR THE ACCESS DOOR PICTURED IN THIS DETAIL. DOOR SHALL BE RATED FOR UP TO 2,300°F AND MEET NFPA 96 STANDARDS LONG ENOUGH FOR DUCT WRAP SYSTEM (WHEN USED), INSTALL IN ACCORDANCE WITH MANUFACTURER'S LITERATURE.

8 GREASE DUCT CLEANOUT ACCESS DOOR DETAIL NTS




- NOTES:
- SUBMIT SHOP DRAWINGS OF ALL HOOD SYSTEMS TO CITY FOR APPROVAL PRIOR TO INSTALLATION.
 - TOTAL HOOD SYSTEM TO BE IN COMPLETE CONFORMANCE WITH NFPA, AND ALL LOCAL CODES AND REGULATIONS.
 - COORDINATE ALL FIRE PROTECTION SYSTEMS WITH FIRE PROTECTION CONTRACTOR WHO SHALL ALSO BE RESPONSIBLE FOR ALL PERMITS AND TESTING REQUIRED.
 - PROVIDE WRAP SYSTEM WHERE APPROVED BY LOCAL CODES IN LIEU OF RATED ENCLOSURE
 - PROVIDE ACCESS PANELS AS REQUIRED BY LOCAL CODE AND PER PLAN.
 - HOODS SHALL EXTEND MINIMUM 6\"/>

5 KITCHEN EXHAUST HOOD ELEVATION DETAIL NTS




- NOTES:
- FLEXIBLE DUCT LENGTH MAY NOT EXCEED 5'-0\"/>

2 HARD CEILING DIFFUSER DETAIL NTS




11 DOWNBLAST EXHAUST FAN DETAIL NTS




- NOTES:
- INSTALL GREASE EXHAUST AND FIRE RATED DUCT WRAP IN ACCORDANCE WITH THE MANUFACTURER'S APPROVED INSTRUCTIONS AND UL LISTED INSTALLATION DETAILS. TECHNIQUES THAT DIFFER FROM THE ABOVE METHOD ARE ACCEPTABLE IF THEY ARE UL TESTED AND APPROVED.

7 GREASE DUCT FIRE WRAP INSULATION INSTALLATION DETAIL NTS




- NOTES:
- ARRANGEMENT SHOWN IS SCHEMATIC. ADJUST TO SUIT FIELD CONDITIONS AND MEET LOCAL CODE REQUIREMENTS.
 - SET DAMPER TO DELIVER SCHEDULED OUTSIDE AIR FLOW.
 - REFER TO MANUFACTURER'S RECOMMENDATIONS FOR MAXIMUM CONDENSATE DRAIN LIFT HEIGHTS.
 - REFER TO MANUFACTURER'S RECOMMENDATIONS FOR HORIZONTAL CONDENSATE DRAIN LIFT CONNECTION FROM THE UNIT.

4 CEILING CASSETTE DETAIL NTS



- NOTES:
- FLEXIBLE DUCT LENGTH MAY NOT EXCEED 5'-0\"/>

1 LAY-IN CEILING DIFFUSER DETAIL NTS



10 ROUND AIR DUCT OR PIPE PENETRATION THROUGH ROOF DETAIL NTS

LANDLORD'S REVIEW COMMENTS

- MECHANICAL COMMENTS:**
- ANY CHANGES AND/OR UPGRADES TO TENANT'S EXISTING MECHANICAL SYSTEMS SHALL COMPLY WITH ALL CODES AND MALL CRITERIA. EXISTING SYSTEMS SHALL POSSESS THE CAPACITY TO HANDLE ANY AND ALL CHANGES IN LOAD.
 - NO PITCH POCKETS ARE PERMITTED ON THE ROOF FOR ANY CONDENSATE DRAINS. REFRIGERANT PIPING, POWER OR CONTROL WIRING, ALL CONNECTIONS ARE TO BE MADE INSIDE THE EQUIPMENT CURB OR THROUGH PRE-MANUFACTURED PIPING CURB.
 - NOTHING IS PERMITTED TO BE ATTACHED TO, SUSPENDED FROM, OR PENETRATE LANDLORD'S STRUCTURE, FLOOR DECK, OR ROOF DECK. YOU MAY ATTACH, ATTACH, NON-DESTRUCTIVELY, TO OR SUPPORT FROM THE TOP CHORD OF THE JOIST OR THE STRUCTURAL STEEL WHICH EXISTS ABOVE THE TENANT SPACE. WHEN ATTACHING TO LANDLORD'S STRUCTURE, **DO NOT DRILL, WELD, SCREW, OR SHOOT** INTO STRUCTURE. ALTERNATIVE METHODS OF ATTACHMENT ONLY NOTHING TO DAMAGE LANDLORD'S BASE STRUCTURE. TENANT SHALL PROVIDE SIGNED AND SEALED STRUCTURAL DRAWINGS, BY A STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION AS INDICATED BY ALL JURISDICTIONAL REQUIREMENTS, FOR ALL STRUCTURAL MODIFICATIONS FOR LANDLORD RECORDS.
 - ALL PENETRATIONS TO ROOF MUST BE APPROVED BY LANDLORD. ALL RELATED ROOF WORK MUST BE DONE BY MALL'S DESIGNATED ROOFING CONTRACTOR. AT TENANT'S EXPENSE. COORDINATE ALL WORK WITH PROPERTY MANAGEMENT ON SITE.
 - TENANT MUST REMOVE ALL ABANDONED ROOFTOP AND/OR MECHANICAL EQUIPMENT ABOVE THE LEASED PREMISES AND WITHIN THE LEASED PREMISES, AT TENANT'S EXPENSE. PATCH AND REPAIR ROOF AS NEEDED.
 - TENANT'S GC TO LABEL ALL ROOF TOP EQUIPMENT WITH TENANT NAME SPACE NUMBER AND EQUIPMENT IDENTIFICATION (RTU-1, EF-1), PER MALL SPECIFICATIONS/ STANDARDS.
 - ALL PIPING ON ROOF SHALL BE SUPPORTED ON PRE-MANUFACTURED PIPE SUPPORTS INSTALLED ON GARY TREAD, SPACED PROPERLY TO SUPPORT PIPING. TREATED WOOD SUPPORTS ARE NOT PERMITTED.
 - ALL UNEXPOSED SUPPLY AIR AND OUTSIDE AIR DUCTWORK SHALL BE EXTERNALLY INSULATED WITH 1 1/2" THICK FOIL FACE INSULATION. INTERNALLY LINED DUCTWORK MAY BE USED FOR ACOUSTIC PURPOSES ONLY, NOT AS A SUBSTITUTE FOR EXTERNAL INSULATION.
 - ALL DUCTWORK SHALL BE SHEET METAL. FLEX DUCT MAY ONLY USED IN RUNS OF 5'-0" OR LESS.
 - AT CONCLUSION OF PROJECT, HVAC SYSTEM MUST BE TESTED AND BALANCED BY A LICENSED CONTRACTOR. COPY OF A BALANCE REPORT MUST BE PROVIDED TO PROPERTY MANAGEMENT OFFICE ON-SITE.
 - LANDLORD STRONGLY PREFERS USE ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.

LANDLORD ROOF TOP EQUIPMENT COMMENTS:

- ROOF EQUIPMENT, INCLUDING BUT NOT LIMITED TO HVAC EQUIPMENT, KITCHEN EQUIPMENT, DUCTS, AND PIPING SHALL BE SHOWN ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. SHALL NOT BE VISIBLE FROM THE OUTER RING ROAD OR FROM MALL LIGHTS. LOCATED WITHIN THE ROOF AREA OF THE PREMISES AND MINIMUM OF 5'-0" FROM THE VERTICAL PLANE OF ANY DEMISING PARTITION LOCATED. AND SHALL BE COORDINATE WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK. EQUIPMENT SCREENS OR SCREEN WALLS MAYBE REQUIRED AND SHALL BE APPROVED IN WRITING BY LANDLORD UNDER SEPARATE COVER.
- TENANT SHALL PROVIDE A STRUCTURAL ENGINEER EVALUATION OF THE EXISTING CONSTRUCTION / STRUCTURE AND DETERMINES THAT IT IS SUFFICIENT FOR THE ADDITIONAL LOADS OF ALL NEW ROOF TOP EQUIPMENT IN ACCORDANCE WITH THE BUILDING CODE THAT HAS BEEN ADOPTED BY THE AUTHORITIES HAVING JURISDICTION (AHJ) AT TENANT'S SOLE EXPENSE. STRUCTURAL DETAILS ARE TO INCLUDE REFERENCE OF APPLICABLE BUILDING CODES, EXISTING BUILDING LOADS, AND ADDITIONAL LOADS THAT WILL BE ADDED TO THE STRUCTURE AN ANY REINFORCING THAT IS REQUIRED. STRUCTURAL DETAILS ARE TO BE SIGNED, SEALED, AND SUBMIT TO THE LANDLORD FOR THEIR RECORDS BY A LICENSED STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION IN THE STATE WITH WHICH THE PROJECT IS LOCATED. LANDLORD RESERVE THE RIGHT TO HAVE A 3RD PARTY ENGINEER PROVIDE DOCUMENTATION BY A 3RD PARTY INSPECTOR TO VERIFY THAT STRUCTURAL INSTALLATION HAS BEEN INSTALLED CORRECTLY.
- ROOF EQUIPMENT REQUIRING DECK PENETRATION SHALL BE SET ON THE FACTORY SUPPLIED CURB AND MUST EXTEND A MINIMUM OF 12" ABOVE HIGHEST ROOF MATERIAL. RE-USE OF EXISTING CURBS OR THE USE OF CURB ADAPTERS IS STRICTLY PROHIBITED. TENANT SHALL FLE-SLOPE ROOF TO MAIN PROPER DRAINAGE AND PROVIDE ROOFING, FLASHING, AND WATERPROOFING FOR INSTALLATION OF NEW CURB PER LANDLORD'S CRITERIA TENANT'S SOLE EXPENSE.
- ALL CONDENSATION, ELECTRICAL AND DUCTWORK SHALL BE SET INSIDE THE PERIMETER OF CURB. CONDENSATE SHALL DRAIN INTO AN INTERIOR FLOOR DRAIN OR MOP SINK WITHIN THE PREMISES. DAYLIGHTING CONDENSATE LINES DIRECTLY ONTO THE ROOF, DOWNSPOUT OR ROOF DRAIN IS STRICTLY PROHIBITED.
- TENANT SHALL PROVIDE 'ROOF TRAFFIC' / WALKWAY PADS' AROUND ALL ROOF TOP EQUIPMENT AND SHALL INDICATE LOCATION OF PADS ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. COORDINATE FINAL LOCATION, MATERIAL, AND INSTALLATION OF PADS WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK.
- TENANT SHALL LABEL ALL ROOF TOP EQUIPMENT INDICATING: TENANT NAME, SPACE NUMBER, AND EQUIPMENT IDENTIFICATION (RTU-1, EFT-1) PER LANDLORD'S DESIGN CRITERIA.
- EQUIPMENT THAT UTILIZES CONDENSER COILS SHALL BE EQUIPPED WITH HAIL GUARDS.
- LANDLORD STRONGLY PREFERS USE OF ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.

zebra
 ZEBRA ARCHITECTURE, PLLC
 1464 N KIERLAND BLVD SUITE N300
 SCOTTSDALE, ARIZONA 85254
 PHONE: 480.912.1169 zbr.global

HNY CONSULTING ENGINEERS
 240 WEST 37TH STREET, 3RD FLOOR
 NEW YORK, NY 10018
 PH: 212.413.8400
 www.hny.com
 245002475
 NC CORPORATION NO. P-2451
 EXPIRES 6/30/2022

PROFESSIONAL SEAL
 NORTH CAROLINA PROFESSIONAL ENGINEER
 SEAL 046826
 CURTIS N. HOY
 12/02/2024

STORE NO: NC #1645

SHAKE SHACK
 CHARLOTTE
 5404 NEW MARKET SUITE 190
 CHARLOTTE, NC 28227

REVISION

Δ	DATE	DESCRIPTION
A	09.11.24	PERMIT SET
C	11.05.24	REVISION C
D	12.02.24	REVISION D / IFC SET

STATUS: IFC SET

SHEET NAME: MECHANICAL DETAILS

DATE: 09/11/24 PROJECT NO: 39018

DRAWN: HEI SCALE: AS NOTED

SHEET NO: M501

Division 23: TABLE OF CONTENTS

GENERAL MECHANICAL REQUIREMENTS

1. GENERAL INSTRUCTIONS

- A. GENERAL REQUIREMENTS
- B. DEFINITIONS
- C. PRE-BID SITE VISIT
- D. MATERIAL AND WORKMANSHIP
- E. MANUFACTURERS
- F. COORDINATION
- G. ORDINANCES AND CODES
- H. PROTECTION OF EQUIPMENT AND MATERIALS
- I. SUBSTITUTIONS
- J. SUBMITTALS
- K. ELECTRONIC DRAWINGS FILES
- L. RECORD DRAWINGS (AS-BUILT DRAWINGS)
- M. OPERATION AND MAINTENANCE INSTRUCTIONS
- N. SPARE PARTS
- O. WARRANTIES
- P. WARRANTIES

2. GENERAL MATERIALS AND INSTALLATION

- A. BUILDING OPERATION
- B. EXISTING EQUIPMENT REUSE AND REMOVAL
- C. EXCAVATION AND BACKFILLING
- D. COINCIDENTAL DAMAGE
- E. CUTTING AND PATCHING
- F. ROUGH-IN
- G. STRUCTURAL SUPPORT SYSTEMS
- H. PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS AND CURBS
- I. ACCESS PANELS AND DOORS
- J. PENETRATIONS
- K. ELECTRICAL WIRING
- L. MOTORS AND STARTERS
- M. VARIABLE FREQUENCY DRIVES
- N. EQUIPMENT FURNISHED BY OTHERS
- O. SYSTEM TESTING, ADJUSTING, AND BALANCING
- P. VIBRATION ISOLATION
- R. SEISMIC CONTROLS FOR MEFP SYSTEMS
- S. AIR FILTERS
- T. REFRIGERANT AND OIL
- U. IDENTIFICATION

3. DUCT INSULATION, DUCTWORK, ACCESSORIES, FLUES AND FANS

- A. DUCT INSULATION
- B. FLEXIBLE DUCT
- C. PLASTIC FLUE GAS VENTS
- D. AIR CURTAINS
- E. CONTROL DAMPERS
- F. LOUVERS, PLENUMS, SCREENS
- G. EXHAUST AIR SYSTEMS
- H. KITCHEN EXHAUST AIR SYSTEMS

4. HVAC EQUIPMENT

- A. ROOFTOP UNITS (HEAT PUMP) 3-25 TONS
- B. SPLIT DUCTLESS AIR-CONDITIONING SYSTEMS
- C. AIR CURTAINS

5. PIPING AND PIPING SPECIALTIES

- A. REFRIGERANT PIPING AND INSULATION
- B. SYSTEM EVACUATION AND CHARGING

6. TEMPERATURE CONTROLS

- A. GENERAL REQUIREMENTS
- B. WIRING
- C. THERMOSTAT CONTROL EQUIPMENT
- D. SENSORS AND RELAYS

7. ALTERNATIVES

- A. DESCRIPTION

8. COMMISSIONING OF MECHANICAL SYSTEM

- A. GENERAL
- B. EXECUTION

LANDLORD'S REVIEW COMMENTS

MECHANICAL COMMENTS:

- ANY CHANGES AND/OR UPGRADES TO TENANT'S EXISTING MECHANICAL SYSTEMS SHALL COMPLY WITH ALL CODES AND MALL CRITERIA. EXISTING SYSTEMS SHALL POSSESS THE CAPACITY TO HANDLE ANY AND ALL CHANGES IN LOAD.
- NO PITCH POCKETS ARE PERMITTED ON THE ROOF FOR ANY CONDENSATE DRAINS, REFRIGERANT PIPING, POWER OR CONTROL WIRING. ALL CONNECTIONS ARE TO BE MADE INSIDE THE EQUIPMENT CURB OR THROUGH PRE-MANUFACTURED PIPING CURBS.
- NOTHING IS PERMITTED TO BE ATTACHED TO, SUSPENDED FROM, OR PENETRATE LANDLORD'S STRUCTURE, FLOOR OR DECK. YOU MAY ATTACH, ATTACH, NON-DESTRUCTIVELY, TO OR SUSPEND FROM THE TOP CHORD OF THE JOIST OR THE STRUCTURAL STEEL WHICH EXISTS ABOVE THE TENANT SPACE. WHEN ATTACHING TO LANDLORD'S STRUCTURE, DO NOT DRILL, WELD, SCREW, OR SHOOT INTO STRUCTURE. ALTERNATIVE METHODS OF ATTACHMENT ONLY, NOTHING TO DAMAGE LANDLORD'S BASE STRUCTURE. TENANT SHALL PROVIDE SIGNED AND SEALED STRUCTURAL DRAWINGS, BY A STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION AS INDICATED BY ALL JURISDICTIONAL REQUIREMENTS, FOR ALL STRUCTURAL MODIFICATIONS FOR LANDLORD RECORDS.
- ALL PENETRATIONS TO ROOF MUST BE APPROVED BY LANDLORD. ALL RELATED ROOF WORK MUST BE DONE BY MALL'S DESIGNATED ROOFING CONTRACTOR. AT TENANT'S EXPENSE, COORDINATE ALL WORK WITH PROPERTY MANAGEMENT ON-SITE.
- TENANT MUST REMOVE ALL ABANDONED ROOFTOP AND/OR MECHANICAL EQUIPMENT ABOVE THE LEASED PREMISES AND WITHING THE LEASED PREMISES, AT TENANT EXPENSE. PATCH AND REPAIR ROOF AS NEEDED.
- TENANT'S GC TO LABEL ALL ROOF TOP EQUIPMENT WITH TENANT NAME SPACE NUMBER AND EQUIPMENT IDENTIFICATION (RTU-1, EF-1), PER MALL SPECIFICATIONS' STANDARDS.
- ALL PIPING ON ROOF SHALL BE SUPPORTED ON PRE-MANUFACTURED PIPE SUPPORTS INSTALLED ON CARRY TREAD, SPACED PROPERLY TO SUPPORT PIPING. TREATED WOOD SUPPORTS ARE NOT PERMITTED.
- ALL UNEXPOSED SUPPLY AIR AND OUTSIDE AIR DUCTWORK SHALL BE EXTERNALLY INSULATED WITH 1/2" THICK FOIL FACED INSULATED DUCTWORK OR SHALL BE USED FOR ACUSTIC PURPOSES ONLY, NOT AS A SUBSTITUTE FOR EXTERNAL INSULATION.
- ALL DUCTWORK SHALL BE SHEET METAL. FLEX DUCT MAY ONLY USED IN RUNS OF 5'-0" OR LESS.
- AT CONCLUSION OF PROJECT, HVAC SYSTEM MUST BE TESTED AND BALANCED BY LICENSED CONTRACTOR. COPY OF A BALANCE REPORT MUST BE PROVIDED TO PROPERTY MANAGEMENT OFFICE ON-SITE.
- LANDLORD STRONGLY PREFERENCES USE ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.

LANDLORD ROOF TOP EQUIPMENT COMMENTS:

- ROOF EQUIPMENT, INCLUDING BUT NOT LIMITED TO HVAC EQUIPMENT, KITCHEN EQUIPMENT, DUCTS, AND PIPING SHALL BE SHOWN ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. SHALL NOT BE VISIBLE FROM THE OUTER RING ROAD OR FROM MALL SKYLIGHTS. LOCATED WITHIN THE ROOF AREA OF THE PREMISES AND MINIMUM OF 5'-0" FROM THE VERTICAL PLANE OF ANY DENISING PARTITION LOCATED, AND SHALL BE COORDINATE WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK. EQUIPMENT SCREENS OR SCREEN WALLS MAYBE REQUIRED AND SHALL BE APPROVED IN WRITING BY LANDLORD UNDER SEPARATE COVER.
- TENANT SHALL PROVIDE A STRUCTURAL ENGINEER EVALUATION OF THE EXISTING CONSTRUCTION / STRUCTURE AND DETERMINE THAT IT IS SUFFICIENT FOR THE ADDITIONAL LOADS OF ALL NEW ROOF TOP EQUIPMENT IN ACCORDANCE WITH THE BUILDING CODE THAT HAS BEEN ADOPTED BY THE AUTHORITIES HAVING JURISDICTION (AHJ) AT STRUCTURE'S SOLE EXPENSE. STRUCTURAL DETAILS ARE TO INCLUDE REFERENCE TO APPLICABLE BUILDING CODE(S), EXISTING BUILDING LOADS, AND ADDITIONAL LOADS THAT WILL BE ADDED TO THE STRUCTURE AN ANY REINFORCING THAT IS REQUIRED. STRUCTURAL DETAILS ARE TO BE SIGNED, SEALED, AND SUBMIT TO THE LANDLORD FOR THEIR RECORDS BY A LICENSED STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION IN THE STATE IN WHICH THE PROJECT IS LOCATED. LANDLORD RESERVE THE RIGHT TO HAVE A 3RD PARTY ENGINEER PROVIDE DOCUMENTATION BY A 3RD PARTY INSPECTOR TO VERIFY THAT STRUCTURAL INSTALLATION HAS BEEN INSTALLED CORRECTLY.
- ROOF EQUIPMENT REQUIRING DECK PENETRATION SHALL BE SET ON THE FACTORY SUPPLIED CURB AND MUST EXTEND A MINIMUM 12" ABOVE THE CURB. REUSE OF MATERIAL, REPAIR OF EXISTING CURBS OR THE USE OF CURB ADAPTERS IS STRICTLY PROHIBITED. TENANT SHALL RE-SLOPE ROOF TO MAINTAIN PROPER DRAINAGE AND PROVIDE ROOFING, FLASHING, AND WATERPROOFING FOR INSTALLATION OF NEW CURB PER LANDLORD'S CRITERIA. TENANT'S SOLE EXPENSE.
- ALL CONDENSATION, ELECTRICAL AND DUCTWORK SHALL BE SET INSIDE THE PERIMETER OF CURB. CONDENSATE DRAIN INTO INTERIOR FLOOR DRAIN OR MOP SINK WITHIN THE PREMISES. DAYLIGHTING CONDENSATE LINES DIRECTLY ONTO THE ROOF, DOWNSPOUT OR ROOF DRAIN IS STRICTLY PROHIBITED.
- TENANT SHALL PROVIDE "ROOF TRAFFIC / WALKWAY PADS" AROUND ALL ROOF TOP EQUIPMENT AND SHALL INDICATE LOCATION OF PADS ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. COORDINATE FINAL LOCATION, MATERIAL, AND INSTALLATION OF PADS WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK.
- TENANT SHALL LABEL ALL ROOF TOP EQUIPMENT INDICATING: TENANT NAME, SPACE NUMBER, AND EQUIPMENT IDENTIFICATION (RTU-1, EFT-1) PER LANDLORD'S DESIGN CRITERIA.
- EQUIPMENT THAT UTILIZES CONDENSER COILS SHALL BE EQUIPPED WITH HALL GUARDS.
- LANDLORD STRONGLY PREFERENCES USE OF ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.

Division 23: HEATING, VENTILATING, AND AIR CONDITIONING

1. GENERAL INSTRUCTIONS

A. GENERAL REQUIREMENTS

All requirements under Division 01 and the general and supplementary conditions of these specifications apply to this section and division. Where the requirements of this section and division exceed those of Division 01, this section and division take precedence. Become thoroughly familiar with all its contents as to requirements that affect this division, section, or both. Work required under this division includes all materials, equipment, transportation, services, and labor required to complete the entire system as required by the drawings and specifications, or reasonably inferred to be necessary to facilitate the function of each system as implied by the design and the equipment specified.

The specifications and drawings for the project are complementary, and any portion of work described in one shall be provided as if described in both. In the event of discrepancies, notify the Engineer and request clarification prior to proceeding with the work involved.

Drawings are graphic representations of the work upon which the contract is based. They show the materials and their relationship to one another, including sizes, shapes, locations, and connections. They convey the scope of work, indicating the intended general arrangement of the systems without showing all of the exact details as to elevations, offsets, control lines, and other installation requirements. Use the drawings as a guide when laying out the work and to verify that materials and equipment will fit into the designated spaces, and which when installed per manufacturers' requirements, will ensure a complete, coordinated, satisfactory, and properly operating system.

B. DEFINITIONS

Division: References contained in this specification follow the numbering system defined in the Construction Specifications Institute (CSI) MasterFormat 2004 Edition. Specification Divisions 01 through 13 provided with this project may reference the CSI MasterFormat 1995 Edition. The corresponding division references between the 2004 Edition and 1995 Edition are as follows:

2004 Edition	1995 Edition
1. Division 15 - Suppression	Division 15
2. Division 22 - Plumbing	Division 15
3. Division 23 - HVAC	Division 15
4. Division 26 - Electrical	Division 16
5. Division 27 - Communications	Division 16
6. Division 28 - Electronic Safety and Security	Division 16

Furnish: "to supply and deliver to the project site, ready for unloading, unpacking, assembly, installation and similar operations." Install: "to perform all operations at the project site including, but not limited to, the actual unloading, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, testing, commissioning, starting up and similar operations, complete, and ready for the intended use."

Provide: "to furnish and install." Furnished by Owner (or Owner-Furnished) or Furnished by Others: "an item furnished by the Owner or under other divisions or contracts, and installed under the requirements of this division, complete and ready for intended use, including all items and services incidental to the work necessary for proper installation and operation. Include the installation under the warranty required by this division."

Engineer: Where referenced in this division, "Engineer" is the Engineer of Record and the Design Professional for the work under this division and the Architect and/or an authorized representative of the Architect, as defined in the General and/or Supplementary Conditions. When used in this division, Engineer means increased involvement by and obligations to the Engineer, in addition to involvement by and obligations to the Architect.

AHJ: The local code and/or inspection agency (Authority) Having Jurisdiction over the work.

NRTL: Nationally recognized testing laboratory, as defined and listed by OSHA in 29 CFR 1910.7 (e.g., UL, ETL, CSA), and acceptable to the AHJ over this project. Nationally recognized testing laboratories and standards listed are used only to represent the characteristics required and are not intended to restrict the use of other NRTLs that are acceptable to the AHJ and standards that meet the specified criteria.

Substitution: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor or Architect, or an authorized representative of the Architect, as defined in the General and/or Supplementary Conditions. When used in this division, Engineer means increased involvement by and obligations to the Engineer, in addition to involvement by and obligations to the Architect.

Approved: The local code and/or inspection agency (Authority) Having Jurisdiction over the work.

Approved equal, "equivalent", or "equal" are used synonymously and shall mean "accepted by or acceptable to the Engineer as equivalent to the item or manufacturer specified". The term "approved" shall mean labeled, listed, or both, by an NRTL and acceptable to the AHJ over this project.

C. PRE-BID SITE VISIT

Prior to submitting bid, visit the site of the proposed work and become fully informed as to the conditions under which the work is to be done. Failure to comply with this requirement shall not be considered sufficient justification to request or obtain extra compensation over and above the contract price.

D. MATERIAL AND WORKMANSHIP

Provide new material, equipment, and apparatus under this contract unless otherwise stated herein, of best quality normally used for the purpose in good commercial practice, and free from defects. Install material and equipment in accordance with the manufacturer's installation instructions. Model numbers listed in the specifications or shown on the drawings are not necessarily intended to designate the required trim, written descriptions of the trim govern model numbers.

Pipe, pipe fittings, pipe specialties and valves shall be manufactured in plants located in the United States or certified to meet the specified ASTM and ANSI standards.

Work performed under this contract shall provide a neat and "workmanlike" appearance when completed, to the satisfaction of the Architect and Engineer. Workmanship shall be the finest possible by experienced mechanics. Installations shall comply with applicable codes and laws.

The complete installation shall function as designed and intended with respect to efficiency, capacity, noise level, etc. Abnormal noise caused by rattling equipment, piping, ducts, air devices, and squeaks in rotating components shall not be acceptable. Materials and equipment shall be of commercial specification grade in quality. Light duty and residential grade equipment shall not be accepted unless otherwise indicated.

Remove from the premises waste material present as a result of work, including cartons, crating, paper, stickers, and/or excavation material not used in building, etc. Clean equipment installed under this contract to present a neat and clean installation at the termination of the work.

Repair or replace public and private property damaged as a result of work performed under this contract to the satisfaction of authorities and regulations having jurisdiction. Provide all safety lights, guards, and warning signs required for the performance of the work and for the safety of the public.

E. MANUFACTURERS

In other articles where lists of manufacturers are introduced, subject to compliance with requirements, provide products by one of the manufacturers specified.

Where a list is provided, manufacturers are listed alphabetically and not in accordance with any ranking or preference.

Where manufacturers are not listed, provide products subject to compliance with requirements from manufacturers that have been actively involved in manufacturing the specified product for no less than 5 years.

F. COORDINATION

Coordinate work with that of other trades so that the various components of the systems are installed at the proper time, will fit the available space, and will allow proper service access to those items requiring maintenance. Components which are installed without regard to the above shall be relocated at no additional cost to the Owner.

Unless otherwise indicated, the General Contractor shall provide chases and openings in building construction required for installation of the systems specified herein. The General Contractor shall furnish the General Contractor with information where chases and openings are required. Contractor shall keep informed as to the work of other trades engaged in the construction of the project and shall execute work in a manner as to not interfere with or delay the work of other trades.

Figured dimensions shall be taken in preference to scale dimensions. Contractor shall take his own measurements at the building, as variations may occur. Contractor shall be held responsible for errors that could have been avoided by proper checking and inspection. Provide materials with trim that will properly fit the types of ceiling, wall, or floor finishes actually installed. Model numbers listed in the specifications or shown on the drawings are not intended to designate the required trim.

G. ORDINANCES AND CODES

Work performed under this contract shall, at a minimum, be in conformance with applicable national, state and local codes having jurisdiction. Equipment furnished and associated installation work performed under this contract shall be in strict compliance with current applicable codes adopted by the local AHJ, including any amendments and standards as set forth by the following:

1. National Electrical Code (NEC)
2. National Fire Protection Association (NFPA)
3. Underwriters Laboratories (UL)
4. Occupational Safety and Health Administration (OSHA)
5. American Society of Mechanical Engineers (ASME)
6. American Society of Heating, Refrigerating, and Air Conditioning Engineers (ASHRAE)
7. American National Standards Institute (ANSI)
8. American Society of Testing and Materials (ASTM)
9. Other national standards and codes applicable.
10. 2018 North Carolina Mechanical Code
11. 2018 North Carolina Fuel Gas Code

Where the contract documents exceed the requirements of the referenced codes, standards, etc., the contract documents shall take precedence. Where conflicts between various codes, ordinances, rules, and regulations exist, comply with the most stringent.

Promptly bring all conflicts observed between codes, ordinances, rules, regulations, referenced standards, and these documents to the attention of the Architect and Engineer for final resolution. Contractor will be held responsible for any violation of the law.

Procure and pay for permits and licenses required for the accomplishment of the work herein described. Where required, obtain pay, and furnish certificates of inspection to Owner.

H. PROTECTION OF EQUIPMENT AND MATERIALS

Store and protect from damage equipment and materials delivered to job site. For materials and equipment susceptible to changing weather conditions, dampness, or temperature variations, store inside in conditioned spaces. For materials and equipment not susceptible to these conditions, cover with waterproof, tear-resistant, heavy tarp or polyethylene plastic as required to protect from plaster, dust, dirt, paint, water, or physical damage. Repair installation that has become wet at any time during construction. Drying the installation is acceptable. Seal any tears or joints of internal fiberglass insulation. Equipment and material damaged by construction activities shall be rejected and Contractor shall furnish new equipment and material of a like kind at his own expense.

Keep premises broom clean of foreign material created during work performed under this contract. Piping, equipment, etc., shall have a neat and clean appearance at the termination of the work. Remove debris from ceiling/return air plenum, including dust.

Plug, seal, or cap open ends of ductwork and piping systems while stored and installed during construction when not in use to prevent the entrance of debris into the systems. Remove temporary protection prior to starting equipment and turning the system over to the owner.

I. SUBSTITUTIONS

Materials, products, equipment, and systems described in the Bidding Documents establish a standard of required function, dimension, appearance and quality to be met by the proposed substitution. The base bid shall include only the products from manufacturers specifically named in the drawings and specifications. To request a substitution, request the Substitution Request Form from the Architect or Engineer. Complete and send the Substitution Request Form for each item of equipment, or system that is proposed to be substituted. The burden of proof of the merit of the proposed substitution is upon the proposer.

D. COINCIDENTAL DAMAGE

Repair streets, sidewalks, drives, paving, walls, finishes, and other facilities damaged in the course of the work. Repair materials shall match existing construction. Repair work shall meet all requirements of the Owner, local authorities having jurisdiction, and meet the satisfaction of the Architect.

Unless stated otherwise in writing to the Engineer by the Contractor, Contractor warrants to the Engineer, Architect, and Owner the following:

1. Proposed substitution has been fully investigated and determined to meet or exceed the specified Work in all respects unless stated otherwise in the substitution request.
2. Proposed substitution is consistent with the Contract Documents and will produce indicated results, including functional clearances, maintenance service, and sourcing of replacement parts.
3. Proposed substitution has received necessary approvals of authorities having jurisdiction.
4. Same warranty will be furnished for proposed substitution as for specified Work.
5. If accepted substitution fails to perform as required, Contractor shall replace substitute material or system with that originally specified and bear the cost of replacement, transportation, services, and labor required to complete the entire system as required by the drawings and specifications.
6. Coordination, installation and changes in the Work as necessary for accepted substitution will be complete in all respects.

No substitutions will be considered unless the Substitution Request Form is completed and attached with the appropriate substitution documentation. No substitution will be considered prior to receipt of bids unless written request for approval to bid has been received by the Engineer at least ten (10) calendar days prior to the date of receipt of bids.

If the proposed substitution is approved prior to receipt of bids, such approval will be stated in an addendum. Bidders shall not rely upon approvals made in any other way. Vendor approval will not be given. No substitutions will be considered after the contract is awarded unless specifically provided in the contract documents.

J. SUBMITTALS

Assemble and submit for review shop drawings, material lists, manufacturer product literature for equipment to be furnished, and items requiring coordination between contractors under this contract. Provide submittals in sufficient detail so as to demonstrate compliance with these contract documents and the design concept. Prior to transmitting submittals, verify that the equipment submitted is mutually compatible and suitable for the intended use, will fit the available space, and maintain manufacturer recommended service clearances. If the size of equipment furnished makes necessary any change in location or configuration, submit a shop drawing showing the proposed layout.

Transmit submittals as early as required to support the project schedule. Allow for two weeks Engineer review time, plus 10% from mailing time via the Architect, plus a duplication of this time for resubmittal, if required. Only submit those sections requested for resubmittal.

Submittals shall contain the project name, applicable specification section, submittal date, equipment identification acronym as used on the drawings, and the Contractor's stamp. The stamp shall certify that the submittal has been checked by the Contractor, complies with the drawings and specifications, and is coordinated with other trades. Manufacturer product literature shall include shop drawings, product data, performance sheets, samples and cutaway drawings required by this division, highlight, mark, list, or indicate the materials, performance criteria, and accessories that are being proposed. General product catalog data not specifically noted to be part of the specified product will be rejected and returned without review.

Submittals and shop drawings shall not contain the firm name, logo, seal, or signature of the Engineer. They shall not be copies of the work product of the Engineer. If the Contractor desires to use elements of such product, refer to paragraph "Electronic Drawing Files" for procedures to be used.

Separate submittals according to individual specification sections. Illegible submittals will be rejected and returned without review. Catalog data shall be properly bound, identified by a 3-ring binder. Each item or model number shall be clearly marked and accessories indicated. Label the catalog data with the equipment identification acronym or number as used on the drawings and include performance curves, capacities, sizes, weights, materials, finishes, wiring diagrams, electrical requirements and deviations from specified equipment or materials. For equipment with the procurement and installation of equipment only after receiving approved shop drawings relative to each item.

Provide the quantity of submittals required by Division 01. If not indicated and hard-copy sets are provided, submit a minimum of six (6) copies. Refer to Division 01 for acceptance of electronic submittals for this project. For electronic submittals, Contractor shall submit the documents in accordance with the procedures specified in Division 01. Contractor shall notify the Architect and Engineer that the submittals have been posted. If electronic submittal procedures are not defined in Division 01, Contractor shall include the website, user name, and password information needed to access the submittals. For submittals sent by e-mail, Contractor shall copy the designated representatives of the Architect and Engineer. Contractor shall allow for the Engineer review time as specified above in the construction schedule. Contractor shall submit only the documents required to purchase the materials and/or equipment in the electronic submittal.

The checking and subsequent acceptance of submittals by the Engineer and/or Architect shall not relieve the Contractor from responsibility for deviations from the drawings and specifications, errors in dimensions, details, size of members, or quantities, omissions of components or fittings; coordination of electrical requirements, and not coordinating items with actual building conditions and adjacent work. Proceed with the procurement and installation of equipment only after receiving approved shop drawings relative to each item.

K. ELECTRONIC DRAWING FILES

In preparation of shop drawings or record drawings, Contractor may, at his option, obtain electronic drawing files in AutoCAD or DXF format on CD-ROM disk, DVD disk, flash drive or direct download, as desired, from the Engineer for a shipping and handling fee of \$200 for a drawing set up to 12 sheets and \$15 per sheet for each additional sheet. Contact the Architect for written authorization and Engineer for the necessary release agreement form and to specify shipping method and drawing format. In addition to payment, the written authorization from the Architect and release agreement form from the Engineer must be received before electronic drawing files will be sent.

L. RECORD DRAWINGS (AS-BUILT DRAWINGS)

During progress of the work in this division, Contractor shall maintain an accurate record of all changes made during the installation of the system. Upon completion of the work, Contractor shall submit all record information to three identical sets of the approved shop drawings. Insert one set into each copy of the manual described below.

M. OPERATION AND MAINTENANCE INSTRUCTIONS

During the course of construction, collect and compile a complete brochure of equipment furnished and installed on this project. Include operational and maintenance instructions, manufacturer's catalog sheets, wiring diagrams, parts lists, approved submittals and shop drawings, warranties, and descriptive literature by the equipment manufacturer. Include an inside cover sheet that lists the project name, date, Owner, Architect, Engineer, General Contractor, Sub-Contractor, and an index of contents.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Paper clips, staples, rubber bands, loose-leaf binding, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Include Record Drawings as described above.

Refer to Division 01 for acceptance of electronic manuals for this project. For electronic manuals, refer to paragraph "Submittals" for requirements.

N. SPARE PARTS

Furnish to Owner, with receipt, the following spare parts for the equipment furnished for this project:

1. One set of spare filters of each type required for each unit. In addition to the spare set of filters, install new filters prior to testing, adjusting, and balancing work and before turning system over to Owner.
2. Furnish one complete set of belts for each fan.
3. Furnish three operating keys for each type of air outlet and inlet that require them.

O. TRAINING

At a time mutually agreed upon between the Owner and Contractor, provide the services of a factory trained and authorized representative to train Owner's designated personnel on the operation and maintenance of the equipment provided for this project.

Provide training to include, but not be limited to, an overview of the system and/or equipment as it relates to the facility as a whole; operation and maintenance procedures and schedules related to startup and shutdown, troubleshooting, servicing, preventive maintenance and appropriate operator intervention; and review of data included in the operation and maintenance manuals.

Submit a certification letter to the Architect stating that the Owner's designated representative has been trained as specified herein. Letter shall include date, time, attendees and subject of training. The Contractor and the Owner's representative shall sign the certification letter indicating agreement that the training has been provided.

Schedule training with Owner with at least 7 days advance notice.

P. WARRANTIES

Warrant each system and each element thereof against all defects due to faulty workmanship, design, or material for a period of 12 months from date of Substantial Completion, unless specific items are noted to carry a longer warranty in the construction documents or manufacturer's standard warranty exceeds 12 months. Remedy all defects, occurring within the warranty period(s), as stated in the General Conditions and Division 01.

Warranties shall include labor and material, including travel expenses. Make repairs or replacements without any additional costs to the Owner, and to the satisfaction of the Owner, Architect, and Engineer.

Perform the remedial work promptly, upon written notice from the Engineer or Owner.

At the time of Substantial Completion, deliver to the Owner all warranties, in writing and properly executed, including time limits for warranties extending beyond the one year period and any actions the Owner must take in order to maintain warranty status. Each warranty instrument shall be addressed to the Owner and state the commencement date and term.

2. GENERAL MATERIALS AND INSTALLATION

A. BUILDING OPERATION

Comply with the schedule of operations as outlined in the architectural portions of this specification. Accomplish work requiring interruption of building operation at a time when the building is not in operation and only with written approval of building Owner and/or tenant. Coordinate initiation of building operation with the Owner and/or tenant a minimum of seven (7) days in advance of work.

B. EXISTING EQUIPMENT REUSE AND REMOVAL

Remove all unused equipment, ductwork, piping, and associated supports. Cap ductwork and piping at mains and seal air and water tight.

Provide items of HVAC systems modification required because of building remodeling, as noted on the drawings or necessary for proper operation. Match existing materials and construction techniques when modifying existing systems unless specified otherwise. Coordinate additional requirements with General Contractor and Architect.

Seal airtight existing ductwork required to be abandoned in place or not in use at the termination of the work.

Cap and seal weathertight existing roof curbs and roof openings to be abandoned in place as a result of equipment removal.

Clean and rebalance existing ductwork, diffusers, registers, and grilles intended for reuse as required or as indicated on drawings.

Clean and refurbish existing HVAC equipment intended for reuse as required for proper operation including replacement of filters, belts, motors, remote controls, and safety interlocks.

C. EXCAVATION AND BACKFILLING

Perform excavation and backfill required for installation of underground work under this contract. Trenches shall be of sufficient width. Curb or brace trenches to prevent cave-in or settlement. Do not excavate trenches close to columns and walls of new building without prior consultation with the Architect. Use pumping equipment if required to keep trenches free of water. Backfill trenches in maximum 6 inch layers of well-lamped dry earth in a manner to prevent future settlement.

Excavation as specified herein shall be classified as common excavation. Common excavation shall comprise the satisfactory removal and disposition of material of whatever substance and of every description encountered, including rock, if any, within the limits of the work as specified and shown on the drawings. Excavation shall be performed to the lines and grades indicated on the drawings. Dispose of excavated materials that are considered unsuitable for backfill and surplus of excavated material which is not required for backfill to the satisfaction of the Architect.

D. COINCIDENTAL DAMAGE

Repair streets, sidewalks, drives, paving, walls, finishes, and other facilities damaged in the course of the work. Repair materials shall match existing construction. Repair work shall meet all requirements of the Owner, local authorities having jurisdiction, and meet the satisfaction of the Architect.

E. CUTTING AND PATCHING

Conform to the requirements in Division 01. Cut walls, floors, ceilings, and other portions of the facility as required to install work under this division. Obtain permission from the Architect prior to cutting. Do not cut or disturb structural members without prior approval from the Architect and Structural Engineer. For post-tension slabs, x-ray slab and closely coordinate all core drill locations with Architect and Structural Engineer prior to performing any work. Obtain approval from Architect and Structural Engineer for all core drills and penetrations at least four days prior to performing work. Penetrations shall be made as small as possible while maintaining required clearances between the building element penetrated and the system component. Patch around openings to match the adjacent construction including fire ratings

Install wiring parallel to building lines wherever possible. Conceal all control wiring in finished rooms. Do not install Class 2 wiring in raceway containing Class 1 wiring. Boxes and panels containing high voltage wiring and equipment may not be used for low-voltage wiring except for the purpose of interfacing the two wires (e.g., relays and transformers). All wire, device and wire-bow connections shall be made at a terminal block or terminal strip. All runs of communication wiring shall be unspliced length when that length is commercially available. Verify the integrity of the entire network following the cable installation. Use appropriate test equipment for all wiring and cabling at each end within 2 inches of termination with the controller termination number. Label control devices used in the system with permanent labels using the identifiers that match the record documents.

O. EQUIPMENT FURNISHED BY OTHERS

Provide necessary equipment and accessories that are not provided by the equipment supplier or Owner to complete installation of equipment furnished by others in locations as indicated on the drawings, specified herein, or both. Equipment and accessories not provided by the equipment supplier may include, but not be limited to, fuses, wires, starters, associated rod jacks and caps to accessories, dampers, inline fans, roof fans, and control interlocks, etc. as required for proper operation of the complete system in accordance with the manufacturer's instructions.

Contractor shall be responsible for correct rough-in dimensions and shall verify them with Architect and/or equipment supplier prior to service installations.

P. SYSTEM TESTING, ADJUSTING, AND BALANCING

Upon completion of each phase of the installation, test each system in conformance with local code requirements and as noted below. Furnish labor and equipment required to test each system installed under this contract. Assume all costs involved in making the tests and repairing and/or replacing any damages resulting therefrom.

The final test and balance of the building HVAC systems shall be completed by National TAB (no exceptions) and contracted by the General Contractor. The representative from National TAB shall be certified by the National Environmental Balancing Bureau (NEBB), Associated Air Balance Council (AABC), or Testing, Adjusting and Balancing Bureau (TAB). TAB shall be performed in accordance with the most current edition of the certified agencies procedural standard for testing, adjusting and balancing and shall comply with the strictest interpretation of that standard for execution and reporting of all TAB work.

Work shall include but not be limited to: Perform test readings on fans, units, coils, pumps, etc. and adjust equipment to deliver specified amounts of air. Prepare testing and balancing report log showing air supply quantities, air entering and leaving temperatures and pressures at test readings, motor voltage and amperage, and amp draws, etc., and submit six copies of the final completion data to the Architect for evaluation and approval before final inspection of the project. Balance air systems to within plus or minus 10 percent for terminal devices and branch lines and plus or minus 5 percent for main ducts and air handling equipment of the amount of air shown on the drawings. TAB Contractor shall record space temperatures and make adjustments in airflow to each diffuser to obtain uniform temperature (no greater than +/- 3 F) in spaces. Document temperatures and adjustments in tab report. Adjust equipment to operate as intended by the specification. TAB report shall include a report summary/remarks in accordance with the procedural standard that provides both system set-up and a summary of deficiencies as defined by the procedural standard.

TAB Contractor shall be responsible to calibrate, set, and adjust automatic temperature control sensors, actuators and control devices. Check proper sequencing of interlock systems, and operation of safety controls, adjust thermostats, and control setpoints, limits and time based adjustment to operate in accordance with the performance requirements of the Construction Documents. Adjust pumps, fans, etc. for proper and efficient operation. Certify to Architect that adjustments have been made and that system is operating satisfactorily. Calibrate, set, and adjust automatic temperature controls. Check proper sequencing of interlock systems, and operation of safety controls.

Division 23 contractor shall align bearings and replace bearings that have dirt or foreign material in them with new bearings without additional cost to the Owner.

Q. VIBRATION ISOLATION

Provide vibration isolation equipment and materials by a single manufacturer. If type and deflection for specific equipment is not specified within the contract documents, reference ASHRAE Handbook "HVAC Applications" or provide per manufacturer's recommendations. Approved manufacturers include Caltny, Kinetics Noise Control, Mason Industries, Inc., Vibration Eliminator Co., Inc., Vibration Mounting and Controls, or Vibro-Acoustics, providing their systems are in compliance with the specified design and performance requirements.

General Requirements: Select vibration isolators by the weight distribution to provide uniform deflection. Vibration isolators shall have either known un-deflected height or calibration marks so that other deflection can be verified. The deflection shall be verified by determining that the load is within the proper range of the isolator. Isolators shall operate in the linear portion of their load versus deflection curves. Spring isolators shall have 50 percent excess capacity without becoming coil bound. Coil vibration isolators with epoxy-applied paint. Other contractors shall be responsible to wash and other concrete surfaces with epoxy-applied concrete surface protection. Install and adjust vibration isolators in accordance with manufacturer's written instructions.

Pipe connections: Provide flexible connectors for piping system connections on equipment side of shutoff valves for all pumps, mechanical equipment supported or suspended by spring isolators, and where indicated on drawings. Fabricate flexible piping connectors from stainless steel or rubber materials as suitable for system fluid. Flexible piping connectors shall be bellows, spherical or bellows hose type as recommended by the manufacturer for the application.

Isolator Types:

1. Type WP (Waffle Pads): Provide 5/16 inch thick neoprene pads ribbed or waffled on both sides. Manufacture pads with bridge bearing quality neoprene and select for a maximum diameter of 5/8 and designed for 15 percent strain, with a static deflection of 0.05 inches. Isolate equipment where required between the equipment and the supporting structure and neoprene pad to prevent deflection. If the isolator is bolted to the structure, install a neoprene mounting sleeve under the bolt head between the steel washer and the base plate to prevent metal to metal contact. Provide Mason Industries Type W or equal.

2. Type SPNH (Spring and Neoprene Hangers): Provide a steel hanger box containing a laterally stable, double-deflecting neoprene isolator in series with a steel spring. Design springs so the ratio of the horizontal to vertical spring constant is between one and two. The spring constant shall be not less than 80 percent of the compression height of the spring. Loaded springs shall operate within its linear portion of their load versus deflection curve over a deflection range of not less than 50 percent above design deflection. Spring diameter and hanger box hole size shall be large enough to permit the hanger rod to swing through a 30 degree arc. Include a locking device to prevent contact between the lower hanger rod and hanger box and short-cutting the isolating function. The neoprene element shall have a maximum diameter of 5/8 and designed for 15 percent strain, with a static deflection of not less than 0.4 inches. Unless otherwise specified, the static deflection of SPNH hangers shall be 2 inches. Provide SPNH hangers with 1/4 inch static deflection for water source heat pumps and fan-powered VAV terminal units. When installed, do not lock the spring element and do not allow the hanger box to rotate through a full 360 degree arc without encountering obstructions.

3. Type NR (Neoprene Bushing): Provide neoprene, rubber-in-shear bushings for lightweight (less than 100 pounds), suspended equipment supported from structure with all thread rod and angle iron or Unistrut. Select for a maximum diameter of 5/8 and designed for 15 percent strain, with a static deflection of 0.15 inches. Provide Mason Industries Type HMB or equal.

R. SEISMIC CONTROLS FOR MEFP SYSTEMS

Seismic Protection Criteria: Risk/Occupancy Category: III(IV) Contractor's Seismic Engineer to Determine. Seismic Design Category: Contractor's Seismic Engineer to Determine. Component Importance Factor: Determined from ASCE 7, most recent version.

The Contractor shall be responsible for determining the requirements for seismic bracing of mechanical, electrical, and plumbing systems. Seismic protection criteria used to determine seismic bracing requirements of all mechanical, electrical, and plumbing systems shall be determined by the applicable code adopted in the project jurisdiction and the requirements set forth in the contract documents. The Contractor shall be responsible for contracting a licensed professional engineer to establish building site class, seismic design category, seismic zone, or any other criteria necessary to determine the requirements for seismic bracing on mechanical, electrical, and/or plumbing systems.

Seismic bracing of fire protection systems shall be installed in strict accordance with the provisions of NFPA 13 (2010 or later edition).

The Contractor shall determine the type and location of seismic bracing required for the mechanical, electrical, and plumbing elements shown on the drawings based on the established seismic criteria, the size and weight of the supported element, and the distance from structure of the supported element.

The Contractor shall submit the following shop drawing information to the AHJ and the Engineer for review and approval:

1. Seismic analysis listing all applicable seismic design criteria.
 2. Descriptive catalog data of seismic bracing materials.
 3. Shop drawings showing bracing type and location.
 4. Installation details of all bracing used.
 5. Calculations showing that the seismic restraints meet the seismic requirements.
- Shop drawings and calculations shall be signed and sealed by a registered professional engineer, licensed in the state of the project and employed by the manufacturer of the seismic bracing products. Calculations shall include dead loads, static seismic loads, and capacity of materials utilized for connections.

Seismic bracing, restraints, isolators, and isolation materials shall be of the same manufacturer and shall be certified by the manufacturer. Approved manufacturers are: Amber/Booth Company, Inc., B-Line/Tokto, ISAT, Kinetics Noise Control, Inc., Loos & Company, Inc., Mason Industries, Inc., Uni-Strut, or Vibro-Acoustics. Each device shall have a pre-approval number from California OSHPD or other recognized government agency showing maximum restraint ratings.

Seismic bracing measures to be applied to mechanical, electrical, and plumbing equipment systems shall be installed in strict accordance with all applicable local, state, and/or federal codes as well as manufacturer's requirements. The most stringent criteria shall apply. All anchor connectors to structure for support of mechanical and electrical equipment, regardless of the need for seismic restraints, shall be shown on shop drawings.

S. AIR FILTERS

Provide AAF/Flanders Perfect Pleat HC M8, Camfil FAP 3000, pleated, throwaway type filters, minimum MERV 8, or similar as manufactured by Air Filter, Inc., Bioclimatic, Cushman, Koch, or approved equal, unless otherwise indicated.

Temporary filters used to protect openings in ductwork and inside equipment when permanent HVAC equipment is used during the construction period shall be pleated, throwaway type filters, minimum MERV 6.

T. REFRIGERANT AND OIL

Provide full refrigerant and oil charge in new air conditioning refrigeration systems, and maintain it for full term of the guarantee.

U. IDENTIFICATION

Provide manufacturer's standard pre-printed, semi-rigid snap-on or permanent adhesive, pressure-sensitive vinyl pipe markers. Color code pipe markers to comply with ANSI A13.1.

Install pipe markers on each HVAC piping system and include arrows to show normal direction of flow.

Locate pipe markers and color bands wherever piping is exposed to view in occupied spaces, machine rooms, accessible maintenance spaces (shafts, tunnels, plenums) and exterior non-concealed locations.

Provide plastic laminate or brass valve tag on every valve, coil and control device in each HVAC piping system; exclude check valves, valves within factory-fabricated equipment units, and shutoff valves at HVAC terminal devices and similar rough-in connections of end-use fixtures and units.

Provide manufacturer's standard laminated plastic, color coded equipment markers. Conform to the following color code: Green for Cooling; Yellow for Heating; Yellow/Green for combination Cooling and Heating; Brown for Energy Reduction; Blue for other equipment types. Conform to ANSI A13.1 for Hazardous Equipment.

Provide stenciled signs for equipment identification at Contractor's option or where distance of required identification requires lettering larger than 1 inch height. Stencil paint shall be exterior type, oil-based, non-metallic, minimum 1-1/4 inch height or greater as required for long distance identification, white or black color for best contrast.

Provide duct markers or provide stenciled signs and arrows indicating ductwork service and flow direction in black or white lettering for best contrast with duct or insulation color. Locate markers maximum 50 feet along each duct side and within 5 feet of all control and balancing dampers or branch ducts more than 25 feet length and within 5 feet on each side of wall, floor, and ceiling penetrations. Provide additional markers in congested areas or at multiple duct runs as required for clarity.

3. DUCT INSULATION, DUCTWORK, ACCESSORIES, FLUES AND FANS

A. DUCT INSULATION

Provide fiberglass duct liner with fibers firmly bonded together with a thermostating resin. Liner surface shall serve as a barrier against infiltration of dust and dirt, shall meet ASTM C1338 for fungi resistance, and shall be cleanable using duct cleaning methods and equipment outlined by North American Insulation Manufacturers Association (NAIMA) duct cleaning guide. Install with liner adhesive mechanical fasteners in accordance with manufacturer's instructions and recommendations. Ductwork sizes shown on drawings are inside clear dimensions. Increase sheet metal by liner thickness in both directions where liner is installed.

Provide rectangular liner conforming to ASTM C1071, Type I or II that is 1-1/2 inch thick, 1-1/2 pound density, minimum R-6.0 Certainteed Corp. "Toughguard" or equivalent, Johns Manville, Owens-Corning, or Knauf.

Provide round liner that is 1-1/2 inch thick, 4 pound density, minimum R-6.0 Johns Manville "Spiracooustic Plus" or equivalent, Certainteed or Owens-Corning.

Provide liner on the following interior air ducts and where specified on the drawings:

1. Exposed round and rectangular supply ductwork.
2. Exposed round and rectangular return ductwork.

At interface of lined and wrapped ductwork, overlap lined ductwork at least 2 feet beyond wrapped insulation.

Cover concealed, rigid ductwork with ASTM C553, Type II flexible fiberglass insulation. Installed insulation shall be 2 inch thick, 3/4 pound density, minimum R-5.0 duct wrap, Certainteed or equivalent Johns Manville, Owens-Corning, or Knauf with heavy-duty foil-scrim-faced facing, and with joints taped with 3 inch wide foil tape as follows:

1. Round and rectangular supply and return air ductwork.
2. Unlined Round and rectangular outside air ductwork.
3. Round and rectangular exhaust and relief air ductwork within 10 feet of exterior discharge.

Cover Outdoor air, Exhaust air and Relief air Plenums connected to exterior louvers with 1-1/2 inch thick, 1.5 pound density, rigid fiberglass insulation conforming to ASTM C912, Class 2.

Insulating materials, adhesives, coatings, etc., shall not exceed flame spread rating of 25 and smoke developed rating of 50 per ASTM E84. Containers for mastics and adhesives shall have U.L. Label.

For supply and return ductwork located exterior to the building, insulation shall be minimum R-8.0. Provide Insulation and jacket in accordance with one of the following three options:

1. Exterior insulation and jacket consisting of 2 inch thickness of Armauff flexible elastomeric insulation or equivalent meeting ASTM C534 with integral 1/2 inch thick UV resistant cladding laminated at factory. Cover all seams with Armauff seal tape.
2. Exterior insulation consisting of 2 inch thickness of flexible elastomeric insulation meeting ASTM C534 or 3 inch density rigid fiberglass meeting ASTM C612, and jacket consisting of 20 gauge corrugated aluminum meeting ASTM C115 with aluminum fitting covers and minimum three aluminum attachment bands per section.
3. Exterior insulation consisting of 2 inch thickness of flexible elastomeric insulation meeting ASTM C534 or 3 inch density rigid fiberglass meeting ASTM C612, and jacket consisting of 15.5 mils thick Venturedex Plus UV resistant cladding.

Install exterior ductwork with sufficient slope to ensure that water cannot pond anywhere on the duct. Drainage must be achieved by sloping ductwork - not by varying the insulation thickness. Locate longitudinal seams of outer shell (aluminum, flexible elastomeric, or cladding as applicable) at bottom of duct. Install cladding in strict conformance with cladding manufacturer's instructions.

B. DUCTWORK

Provide galvanized steel ductwork and housings as shown on drawings. Construct ductwork including fittings and transitions in conformance with current SMACNA standards relative to gauge, bracing, joints, etc. Minimum thickness of duct shall be 26-gauge sheet metal. Reinforce housings and ductwork over 30 inches with 1-1/4 inch angles not less than 5'-8" on centers, and closer if required for sufficient rigidity to prevent vibration. Support horizontal runs of duct from strap iron hangers on centers not to exceed 5'-0". Do not support ceiling grid, conduits, pipes, equipment, etc. from ductwork. Coordinate routing of ductwork with other contractors such that piping, electrical conduit, and associated supports are not routed through the ductwork.

Provide pre-engineered roof duct supports supporting by Cooper-B-Line, Elite Components, ERICO, FNV, Miro, PHD Manufacturing, PHP Systems, Roof Top Box, Unistrut (Akrore), Zai Foster, or approved equal. Support ductwork on the roof with pre-engineered roof supports that are designed for the roof structure and are bolted to the roof structure and do not penetrate the roof structure, with embedded support fasteners as required to support duct. Provide steel pedestal type supports with minimum 18x18 inch thermoplastic or rubber base or 4 inch wide closed-cell polyethylene block with length as required. Maintain minimum 6 inches clearance under duct to finished roof surface.

Coordinate with the pre-engineered roof duct support manufacturer to anchor the duct supports directly to the roof structure in accordance with installation instructions or provide intermediate duct supports engineered to meet the wind resistance and seismic design criteria. Reference Section, "PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS."

Construct non-VAV supply ducts that meet SMACNA positive pressure of 2 inches w.g. Construct Return, Outdoor and Exhaust ductwork upstream of fans to meet SMACNA negative pressure of 1 inch w.g. Construct exhaust ductwork downstream of fans to meet SMACNA positive pressure of 1 inch w.g.

Provide mill phosphatized or galvanized finish for exposed ductwork to be field painted. Shop treated sheet metal shall have galvanized metal primer applied in the shop after fabrication and prior to shipping.

Seal ductwork with heavy liquid sealant, Hardcast Kongrip 601, Design Polymer DP 1010, United Mopll duct sealant or approved equal, applied according to sealant manufacturer's instructions. Seal all longitudinal and transverse ductwork joints to meet SMACNA Seal Class A. Tapes and mastics shall be listed and labeled in accordance with UL 181A.

Provide radius elbows, turns, and offsets with a minimum centerline radius of 1-1/2 times the duct width. Where space does not permit full radius elbows, provide short radius elbows with a minimum of two continuous spigot vanes. Vanes shall be the entire length of the bend. Provide mirrored elbows where space does not permit radius elbows, where shown on the drawings, or at the option of the contractor with the engineer's approval. Mirrored elbows less than 45 degrees shall not require turning vanes. Mirrored elbows 45 degrees and greater shall have single thickness turn vanes of same gauge as ductwork, rigidly fastened with guide strips to ductwork. Vanes for mirrored elbows shall be provided in all supply and exhaust ductwork and in return and outside air ductwork that has an air velocity exceeding 1000 fpm. Do not install vanes in grease ductwork. The use of square throat, radius air elbow is prohibited. Remove and replace all installed elbows of this type with an approved elbow at no additional cost to the owner.

Connect ducts to vibrating equipment and when transitioning between two different metallic duct materials (e.g., aluminum to galvanized steel) by means of flexible connectors. Flexible connectors shall be neoprene coated glass cloth canvas connections, Duo-Dyne, Elgen, Ventifabric or equal. Flexible connectors shall have a flame spread of 25 or less and smoke developed rating not higher than 50. Make airtight joints and install with minimum 1-1/2 inches seal.

Provide balancing dampers, manufactured by Cesco, Greenheck, Louvers & Dampers, Nalor Industries, Pottoff, Ruskin, Tamco, or approved equal, where shown on drawings and wherever necessary for complete control of air flow. Splitter dampers shall be controlled by locking quadrants; provide Young Regulator or Ventikac end bearings for the damper rod. Rectangular volume dampers shall be opposed blade interlocking type. Round volume dampers shall be single-blade type consisting of circular blade mounted to a shaft. Provide Flexmaster model ST1 or equal 45 degree rectangular/round slide taking fitting with model B03 damper with locking quadrant and insulating foam in duct and ductwork branch takeoffs to individual air devices. Omit damper at takeoff fitting when damper is located downstream of takeoff.

Where access to dampers through a hard ceiling is required, provide a concealed, remote control-operated, butterfly-type volume damper assembly with external worm gear operator. Damper assembly shall include duct casing with rolled beam stiffeners, reinforced blade, self-lubricating bearing, and remote operator mounting plate. External operator shall attach to damper as a single piece with no linkage adjustment required. Damper shall be adjustable through the diffuser frame with standard 1/4 inch nutdriver or flat screwdriver. Provide positive, direct, two-way damper control with no sleeves, springs or screw adjustments to come loose after installation. Provide cable length to span the distance from the damper to the remote operator location. Install damper in branch duct. Do not install in diffuser neck. Install remote operator on the back of the diffuser frame or side of a slit diffuser plenum. Support cable assembly to avoid bends and kinks in cable at manufacturer recommended intervals. Where approved by architect, a ceiling cup with cover plate may be used for access to cable operator. Provide round dampers by Metropolitan Air Technology model RT-250, Young's Regulator model 6020-1200, or approved equal. Provide rectangular dampers by Metropolitan Air Technology model RT-200, Young's Regulator model 820-1200, or approved equal. Provide remote cable control by Metropolitan Air Technology model RT-WGA, Young's Regulator model 270-275, or approved equal.

Round or oval ductwork shall be FlakGroup Seismco, United, Hercules Industries or equal, sheetmetal, with smooth interior surface, with low pressure (duct pressure class up to and including 2 inches w.g.) Round ductwork gauges per the following table (reference SMACNA HVAC duct construction standards for gauges when pressures exceed 2 inches w.g.):

Size	Duct Gauge	Fitting Gauge
14" & under	26	24
15" thru 26"	24	22
28" thru 36"	22	20
38" thru 50"	20	18
52" thru 60"	18	18

Lewis & Lambert, Linx Industries Lindt Safety, or approved equal factory-manufactured round ductwork and fittings may be substituted for specified round branch ductwork, at Contractor's option. Heavy liquid joint sealant may be omitted on factory-manufactured round ductwork.

Spot-welded (duct pressure class up to and including 2 inches w.g.) Fittings 24 inches in diameter and less shall be prefabricated, low-pressure and internally sealed. Continuously welded fittings larger than 24 inches in diameter. Fitting gauge shall be 22 gauge for 36 inch fittings and under, 20 gauge for larger sizes. 90 degree tees shall be conical type. Seal longitudinal and transverse ductwork joints airtight with heavy liquid sealant applied according to manufacturer's instructions. Provide gauge thickness in medium pressure (duct pressure class 3 inches to 16 inches w.g.) ductwork as recommended by SMACNA.

C. FLEXIBLE DUCT

Low pressure (duct pressure class up to and including 2 inches w.g.) and medium pressure (duct pressure class 2.1 inch to 6 inches w.g.) flexible duct shall be Flexmaster type 8B, Thermalex type G-KM, M-KE, JPL type Silver Jacket, or equal (fire retarding polyethylene) protective vapor barrier, UL 181 Class 1, acoustical insulated duct, R-6.0 fiberglass insulation, Provide CPE liner with steel wire helix mechanically locked or permanently bonded to the liner.

Flexible duct runs shall not exceed 5 feet in length, and shall be installed fully extended and straight as possible avoiding tight turns. Flexible duct shall be installed in accordance with manufacturer's instructions. Support flexible duct at maximum 5 feet on center and within 6 inches of bends. Bends shall not exceed a centerline radius of one duct diameter. Duct sag shall not exceed 1/2 inch. Supporting material in direct contact with the duct shall not be less than 1-1/2 inches in width.

Connect flexible duct to rigid metal duct or air devices as recommended by the manufacturer. At a minimum, install two wraps of duct tape around the inner core connection and a metallic or non-metallic clamp over the tape and two wraps of duct tape or a clamp over the duct tape jacket. Duct clamps shall be labeled in accordance with UL-181B and marked 181B-C. Duct tape shall be labeled in accordance with UL 181B and marked 181B-FX.

D. PLASTIC FLUE GAS VENTS

Provide UL 1739 listed plastic flue gas vents, with positive or negative fire pressures complying with NFPA 211 and suitable for condensing gas appliances. Provide PVC system by IPEX "System 1738" or Polypropylene system by Centermith "Innoflu" or equal by Nova Flex Group "Z-DENS."

Vents and combustion air ducts for condensing type appliances shall be Schedule 40 PVC pipe and socket fittings meeting ASTM D2685 and UL 1738, manufactured by IPEX. Use solvent cement meeting ASTM D2564 and make joints in accordance with ASTM D2685.

Where plastic gas vents are installed in a return air plenum, wrap the vent with fire rated plenum insulation. Reference Article "Plenum Insulation" for plenum-rated fire wrap. Coordinate vent material compatibility with the appliance manufacturer's installation instructions prior to purchasing and installation.

E. AIR DEVICES

Provide air devices as scheduled on drawings, manufactured by Carnes, Krueger, Metalair, Nalor Industries, Price, Titus, or Tuttle & Bailey. Select air devices to limit room noise level to no higher than NC-30 unless otherwise shown. Provide devices with a soft plastic gasket to make an airtight seal against the mounting surface. Coordinate final location, frame, and mounting type of air devices with Architectural reflected ceiling plans.

Submit complete shop drawings including information on noise level, pressure drop, throw, CFM for each air device, styles, borders, etc. Clearly mark with specified equipment number. Submit samples of each air device as requested by the Engineer.

Provide wall return air grilles and exhaust air registers with horizontal 35 or 45 degree angle air-question-by Register. Provide concealed fasteners for wall mounted registers and grilles. Provide floor supply air registers of aluminum heavy duty type with 0 degree deflection. Provide opposed blade dampers for supply air registers and exhaust air registers unless indicated otherwise.

Provide ceiling mounted air devices of lay-in or surface mounted type as required to be compatible with ceiling construction. Provide ceiling diffusers and grilles with white enamel finish unless noted otherwise.

Provide linear slot diffusers of standard one-piece lengths up to 6-feet and furnished in multiple sections greater than 6-feet. Join multiple sections together end-to-end with alignment pins to form a continuous slot appearance. For installations in a hard ceiling, install diffuser per manufacturer's installation instructions prior to installation of drywall. Contractor shall use manufacturer's hard ceiling clips for mounting to ceiling framing. Screws through face of linear slot diffuser are not acceptable. Provide alignment components by the manufacturer. Provide plenums by the slot diffuser manufacturer. Plenums shall be internally insulated by the manufacturer with minimum 1/4 inch thick, fiberglass insulation.

F. CONTROL DAMPERS

Provide factory fabricated, parallel blade control dampers sized as shown on the drawings and as specified. Individual damper sections shall not be larger than 48 inches x 60 inches with maximum blade width of 6 inches. Frames shall be constructed in a hard ceiling, install diffuser per manufacturer's installation instructions prior to installation of drywall. Contractor shall use manufacturer's hard ceiling clips for mounting to ceiling framing. Screws through face of linear slot diffuser are not acceptable. Provide alignment components by the manufacturer. Provide plenums by the slot diffuser manufacturer. Plenums shall be internally insulated by the manufacturer with minimum 1/4 inch thick, fiberglass insulation.

Provide modulating dampers with linear flow characteristics. Size modulating dampers based on the smaller of 1,500 FPM through the damper or full open air pressure drop of 0.1 inches W.C. Size two-position dampers full duct size and select to minimize pressure drop.

Motorized dampers used for ventilation air intake, exhaust air, or relief air shall have leakage rates not to exceed 4.0 CFM/square foot in full closed position at 1 inch W.G. pressure differential across the damper.

Provide dampers as manufactured by Greenheck, CESCO, Pottoff, Nalor, or Ruskin. Reference manufacturer with model number for outside air dampers is Ruskin CD-50 constructed of aluminum, and all other applications is Ruskin CD-35 constructed of galvanized steel.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee tight close-off of dampers against system pressure encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruption as required by the control systems specified on the drawings. Damper operators shall be manufactured by Belmont, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

G. LOUVERS, PLENUMS, SCREENS

Provide intakes and exhaust air bar screens by Ruskin model ELF373R or equal American Warming & Ventilating, Cesco, Greenheck, Industrial Louvers or Louvers & Dampers as scheduled on the drawings. Coordinate exact size and location with architectural drawings. Louvers shall be stationary, with mill finish. Louvers shall extend aluminum blades, 0.090 inch wall thickness, 45 degree blade angle; blades on 5 inch centers; frame shall be extruded aluminum, 0.090 inch wall thickness, with expanded flattened aluminum. Louvers shall have a minimum free area of 45 percent, with a maximum air pressure drop of 0.1 inch at scheduled airflow.

Construct plenums with galvanized steel framing members and galvanized sheet metal, braced with expanded angles. Gauges and bracing shall conform to SMACNA recommendations for ductwork of like sizes. Where access doors are shown, provide hinged doors with #202 Ventlok latch. Make watertight connections to louvers, sloping bottom of plenum to drain water to weepholes in bottom of louver.

Provide screens on louvers, ducts, hoods, fans, and openings to the outdoors as scheduled and/or noted on the drawings. Insect screens shall be 1/16 inch thick, 16 to 20 mesh, aluminum mesh. Bar screens shall be 0.041-inch, 1/2 mesh galvanized steel wire. Provide motorized control louvers or backdraft dampers where shown on the drawings.

Wind Driven Rain Performance: Louvers shall comply with ANSI/AMCA 509L for wind driven rain performance. Louvers shall have not less than 90 percent effectiveness when subjected to wind velocities of 29 and 50 mph with rainfall rates of 3 in/hr and 8 in/hr respectively and a one minute velocity not less than what is scheduled on the plans.

Windborne-Debris Impact Resistance: Louvers located within 30 feet of grade shall comply with AMCA 540.

H. EXHAUST AIR SYSTEMS

Provide roof mounted exhaust fans as scheduled on the drawings, or equal ACME, Carnes, Cook, Greenheck, Pembury, or Twin City Fans complete with aluminum louvers, aluminum rain caps, and down pipe. Exhaust fans shall be 0.041-inch, 1/2 mesh galvanized steel wire. Provide motorized control louvers or backdraft dampers where shown on the drawings.

I. KITCHEN EXHAUST AIR SYSTEMS

Install kitchen grease exhaust package furnished by the owner. System includes kitchen hood, grease exhaust fan/pullout control unit, filtered makeup air unit and a mechanical or electrical gas shutoff valve provided with the kitchen exhaust system to shutoff fuel or power source to cooking equipment upon detection of fire. Valve shall have a clearly marked open/closed indicator.

Provide ducts connecting Type 1 exhaust hoods to exhaust fans made of #16 gauge black iron with continuously welded joints and clean-out doors. Provide transition at connection to fan with opening size equal to or greater than the vertical opening of the fan inlet. Provide gasket at flanged connection to fan rated for 1500 degrees Fahrenheit and grease applications. Enclose duct in fireproof enclosure per locally adopted mechanical code or, if approved by local code official, in fire rated wrap insulation. Installation shall be minimum two-hour rated duct wrap insulation for Type I hood grease exhaust duct applications and shall conform to ASTM E2338 when required to comply with 2018 North Carolina Mechanical Code. Insulation shall be flexible wrap enclosure rated for minimum 2000 degrees Fahrenheit and for zero clearance to combustibles. Insulation shall be non-mineral wool, passive, low bio-persistent fiber totally encapsulated on all sides with aluminum foil. Insulation shall be as manufactured by Certainteed, Thermal Ceramics, Unifrax or 3M. Slope duct back towards hood at minimum of 1/4 inch per linear foot. At Contractor's option, a UL listed concentric ductwork package that complies with UL 1978 standard for grease ducts may be used in lieu of the welded black iron duct for connecting hood to exhaust fan. Ductwork package shall be as manufactured by Meta-Fab, Schebler, Selkirk, or approved equal. Provide manufacturers UL listing number and verification certificate as a part of the shop drawing submittal. Install duct package in strict conformance with manufacturer's instructions and recommendations.

All portions of grease duct systems shall be tested for leakage in accordance with the "Grease Duct Test" paragraph of the 2018 North Carolina Mechanical Code. Leakage tests shall be by water leakage type or equivalent test methods as approved by the local code official to determine that all joints are tight. Water leakage test shall be performed by Environmental Corporation of America or owner approved testing contractor. Tests shall be performed in the presence of the local code official. Any joints found defective shall be repaired and retested until satisfactory results are obtained. The contractor shall submit a copy of the grease duct leakage test report to the architect/engineer complete with the approval signature of the local code official.

4. HVAC EQUIPMENT

A. ROOFTOP UNITS (HEAT PUMP) 3-20 TONS

Provide package rooftop heat pump units as scheduled on the drawings, manufactured by Aaon, Carrier, Daikin, Lennox, Johnson Controls, Trane, or York, with features as scheduled in the RTU Control Matrix, and complete with factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater, and low pressure switches; direct expansion evaporating and condensing coils with 1 inch factory installed flexible elastomeric insulation around the suction and liquid lines; a factory installed condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating (cooling) and minimum HSPF or COP rating (heating) as required by the applicable energy code or greater if scheduled on the drawings; centrifugal evaporator blower; air filter rack; propeller type condenser fan; electric supplemental heat modules constructed of heavy-duty nickel chromium elements (UL listed) with code required integral safety features and controls including automatic reset high limit; complete factory installed micro-processor controls including anti-short cycle timers, time delay relays and minimum "on" time controls; built-in thermal overload protection on motors and compressors;

Provide remote sensors where indicated on the drawings and integrate them with the thermostat control equipment. Remote sensors shall have the following features:

- 1. Wired connection.
2. Temperature sensor.
3. Humidity sensor.
4. Blank faceplate.
5. Where multiple remote sensors are shown for a single unit, the sensors shall be provided in a single device.

Dry-bulb temperature sensors at a minimum shall be accurate to +/- 2 degrees Fahrenheit over the range of 40 to 80 degrees Fahrenheit. Wet-bulb temperature shall be calculated using dry-bulb temperature and humidity and shall be accurate to +/- 2 degrees Fahrenheit. Enthalpy shall be calculated using dry-bulb temperature and humidity and shall be accurate to +/- 3 BTU/lb over the range of 20 to 35 BTU/lb. Humidity sensors at a minimum shall be accurate within +/- 3 percent full range between 20 and 95 percent, with drift less than 1 percent full scale per year. Pressure transmitters at a minimum shall be accurate to +/- 1 percent full scale with drift less than 1 percent full scale per year.

Smoke detectors furnished and installed as indicated in this section or as scheduled on the plans (or heat detectors, if permitted by code) shall shut down each associated unit supply fan upon activation where required by code. Provide remote visual and audible alarm device in an approved location if smoke detectors are not connected to a fire alarm panel and label device as "Air Duct Detector Trouble".

Provide 24 Volt or 120 Volt timeswitches Intermatic Series FMD20 or equal programmable type with 7-day programming with up to two "ons" and "offs" per day. Battery backup shall provide 48 hours of memory retention. Override limiter switches shall be spring wound, 6-hour, normally open type. Coordinate 120 V wiring of timeswitch with electrical contractor if 120 V model is provided.

Provide relays with contact rating, configuration, and coil voltage that is suitable for the application. Relay shall be general purpose, enclosed plug-in type and protected by a heat and shock resistant duct cover. Number of contacts and operational function shall be as required. Transient suppression shall be provided as an integral part of the relay. Contactors shall be single coil, electrically operated, mechanically held, double-break, silver-to-silver type protected by arcing contacts. Positive locking shall be obtained without the use of hooks, latches, or semi-permanent magnets. Operating and release times shall be 100 milliseconds or less.

7. ALTERNATES

A. DESCRIPTION

Refer to the architectural portion of the specification for list of alternates. Applicable sections of the base specifications shall apply to all work required by the alternate unless otherwise specified. Determine whether or not and how each alternate affects work. Include labor, materials, equipment, and transportation services necessary for and incidental to the completion of work under each particular alternate. Furnish separate bid for each alternate applicable to work, stating the amount to be added or deducted from the base bid.

9. COMMISSIONING OF MECHANICAL SYSTEMS

COMMISSIONING OF HVAC SYSTEM

A. PART 1 GENERAL

1.1 SUMMARY

a. Section includes Cx process requirements for the following HVAC systems, assemblies, and equipment:

- 1. Air handling units (Supply fans, return fan, packaged units, roof top units, specialized fans)
2. Exhaust fans
3. Fan coil units and terminal units
4. Condensing units
5. Make-Up air units
6. Ductwork and piping

b. Related Requirements:
1. Section 019113 "General Commissioning Requirements" for general Cx process requirement and CxA responsibilities.

1.2 INFORMATIONAL SUBMITTALS

a. Construction Checklists: Draft construction checklists will be created by CxA for Contractor review.
b. Construction Checklists: Installation and Performance test checklists for systems, assemblies, subsystems, equipment, and components to be part of the Cx process and according to requirement in Section 019113 "General Commissioning Requirement."

- 1. Refrigerant piping, including the following:
a. Refrigerant piping, fittings, and specialties.
b. Refrigerant charge.
c. General duty and specialty valves.
d. Meters and gages.
2. Air distribution systems, including the following:
a. Supply, return, and exhaust systems.
b. Metal ducts, liners, and fittings.
c. Nonmetal ducts, liners, and fittings.
d. Air-duct accessories, including volume dampers, fire and smoke dampers, turning vanes, sound attenuators, and flexible connectors.
e. Duct-mounted access doors and panels.
3. Kitchen exhaust system, including the following:
a. Exhaust and makeup air system.
b. Metal ducts, liners, and fittings.
c. Air-duct accessories, including volume dampers, fire and smoke dampers, turning vanes, sound attenuators, and flexible connectors.
d. Duct-mounted access doors and panels.
4. Exhaust fans.
5. Make-Up air unit
6. Air-handling equipment, including the following:
a. Fans and motors.
b. Indoor air-handling units with and without coils, dampers, and filters.
c. Outdoor air-handling units with and without coils, dampers, and filters.

B. PART 3 EXECUTION

3.1 CONSTRUCTION CHECKLISTS

- a. Complete detailed construction checklists (prefunctional checklists) prepared by the CxA for HVAC systems, assemblies, subsystems, equipment, and components.
1. Air and hydronic distribution systems, including the following:
a. Supply, return, outdoor-air, and exhaust-air distribution systems.
b. Automatic dampers.
c. Control valves.
2. Heating and cooling terminal and unitary equipment, including the following:
a. Unit heaters.
b. Fan coil units.
c. Electric heating.
3. TAB verification.

3.2 CONSTRUCTION CHECKLIST REVIEW

- a. Review and provide written comments on draft construction checklists. CxA will create required draft construction checklists and provide them to Contractor.
b. Return draft construction checklist review comments within 5 days of receipt.
c. When review comments have been resolved, the CxA will provide final construction checklists marked "Approved for Use, (date)."
d. Use only construction checklists marked "Approved for Use, (date)."

3.3 Cx TESTING PREPARATION

- a. Certify that HVAC systems, subsystems, and equipment have been installed, calibrated, and started and that they are operating according to the Contract Documents and approved submittals.
b. Set systems, subsystems, and equipment into operating mode to be tested according to approved test procedures (for example, normal shutdown, normal auto position, normal manual position, unoccupied cycle, and alarm conditions).

3.4 Cx TESTS COMMON TO HVAC SYSTEMS

- a. Comply with construction checklist requirements, including installation checks, startup, and performance tests requirements for HVAC systems and equipment.
b. Measure capacities and effectiveness of systems, assemblies, subsystems, equipment and components, including operational and control functions, to verify compliance with acceptance criteria.
c. Coordinate schedule with, and perform Cx activities at the direction of CxA.
d. Provide technicians, instrumentation, tools, and equipment to perform and document the following:
1. Construction checklist verification tests.
2. Construction checklist verification tests demonstrations
3. Cx test demonstrations.

3.5 START-UP DOCUMENTATION COMMON TO ALL SYSTEMS

- a. The following Start-Up Documentation (Checklists and Tests) shall be considered common to all systems:
1. Checkout shall proceed from lower level devices to larger components to the entire system operation.
2. Verify labeling is affixed per specification and visible.
3. Verify prerequisite procedures are done.
4. Inspect for damage and ensure none is present.
5. Verify system is installed per the manufacturer's recommendations.
6. Verify system has undergone Start-Up per the manufacturer's recommendations.
7. Verify that access is provided for inspection, operation and repair.
8. Verify that access is provided for eventual replacement of the equipment.
9. Verify that record drawings, submittal data and O&M documentation accurately reflect the installed systems.
10. Verify all gauges and test ports are provided as required by contract documents and manufacturer's recommendations.
11. Verify all recorded nameplate data is accurate.
12. Verify that the installation ensures safe operation and maintenance.
13. Verify all rotating and moving parts are properly lubricated.
14. Verify specified replacement material/electrical has been provided as required by the Contract Documents.
15. Verify all monitoring and ensure all alarms are active and set per requirements.

3.6 MECHANICAL IDENTIFICATION

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following checks:
1. Verify all valve tags, piping, duct, and equipment labeling corresponds with drawings and indexes and meets requirements specified. Correct any deficiencies for all piping and duct system.
2. Adjusting: Relocate any mechanical identification device which has become visually blocked by work of this division or other divisions.
3. Cleaning: Clean face of identification devices, and glass frames of valve charts.

3.7 MECHANICAL INSULATION

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Examine all piping, systems and equipment specified to be insulated.
1. Ensure quality of insulation. Patch and repair all insulation damaged after installation.
2. Ensure the integrity of vapor barrier around all cold surfaces.

3.8 PIPING GENERAL

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: These procedures apply to all installed piping systems, including underground site utilities.
1. Inspect all piping for proper installation, adequate support (with appropriate vibration isolation where applicable) and adequate isolation valves for required service.
2. Provide notification of pipe cleaning and flushing activities.
3. Flush and clean all piping and clean all strainers. Provide documentation of all related procedures.
4. Ensure adequate drainage is provided at low points and venting is provided at high points.
5. Ensure facilities to effectively drain and fill the system are in place.
6. Ensure air is thoroughly removed from the system as applicable.
7. Provide notification of pressure testing.
8. Pressure and/or leak test all applicable systems in accordance with the requirements in the applicable Division 23 specification.
9. Sterilize applicable piping systems as specified in the individual sections and as required by regulatory authorities.
10. Submit pressure test reports that document the pressure testing results with certification of the results. Include drawings/diagrams indicating sections of pipe that are tested with the corresponding report.
11. Set and adjust fill, pressure, or level controls to the required setting.

3.9 AC MOTORS

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following checks during start-up and as specified in manufacturer's instructions:
1. Verify proper alignment, installation, and rotation.
2. Verify properly sized overloads are in place.
c. Start-Up Tests: Perform the following tests, measurements, or procedures during start-up and as specified in the manufacturer's instruction:
1. Measure voltage available to all phases. Measure amps and RPM after motor has been placed in operation and is under load.
2. Record all motor nameplate data.

3.10 PACKAGED HEATING AND COOLING UNITS

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Refer to AC Motors in this section.
c. General: Provide the services of a factory-authorized service representative to test and inspect unit installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
b. Start-Up Checks: Perform the following inspections/checks during start-up:
1. Test controls and demonstrate compliance with requirements. Replace damaged or malfunctioning controls and equipment.
2. Install new filters after start-up.

3.11 TERMINAL UNITS

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following inspections/checks during start-up:
1. After construction is completed, including painting if applicable, clean unit exposed surfaces.
2. Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
3. Verify adequate access for maintenance.
4. Check power and control voltages.
5. Check rotation of fan where applicable.
6. Check operation of water leak sensors.
7. Check calibration and operation of the controlling elements.
8. Check control valves for required close-off and fail position.
9. Install new filter units for terminals requiring same.

3.12 FANS

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. General: Provide the services of a factory-authorized service representative to test and inspect exhaust fan installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
c. Start-Up Checks: Perform the following inspections/checks during start-up:
1. Inspect the field assembly of components and installation of the units, piping, ductwork, and electrical connections.
2. Clean unit cabinet interiors to remove foreign material and construction dirt and dust. Vacuum clean fan wheel, fan cabinet, coils entering air face. Ensure volatile irritants are contained and kept out of occupied spaces.
3. Adjust and lubricate dampers and linkages for proper damper operation.
4. Verify the unit is secure on mountings and supporting devices and connections for ductwork, and electrical are complete. Verify proper thermal overload protection is installed in motors, starters, and disconnects.
5. Ensure vibration isolation integrity is maintained with the fan installation and associated connections.
6. Lubricate bearings, pulleys, belts, and other moving parts with factory-recommended lubricants.
7. Stroke all dampers to ensure free and full travel.

3.13 DUCTWORK ACCESSORIES

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following checks during start-up and as specified:
1. Cleaning: Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
c. Start-Up Tests: In addition to specifications, perform the following as a minimum:
1. Operate installed ductwork accessories to demonstrate compliance with requirements. Test for air leakage while system is operating. Repair or replace faulty accessories, as required to obtain proper operation and peak performance.
2. Label access doors in accordance with Division 21 Section "Mechanical Identification"
3. Adjusting: Adjust ductwork accessories for proper settings, install fusible links in fire dampers and adjust for proper action.

END OF SECTION 23

LANDLORD'S REVIEW COMMENTS

MECHANICAL COMMENTS:

- ANY CHANGES AND/OR UPGRADES TO TENANT'S EXISTING MECHANICAL SYSTEMS SHALL COMPLY WITH ALL CODES AND MALL CRITERIA. EXISTING SYSTEMS SHALL POSSESS THE CAPACITY TO HANDLE ANY AND ALL CHANGES IN LOAD.
NO PITCH POCKETS ARE PERMITTED ON THE ROOF FOR ANY CONDENSATE DRAINS, REFRIGERANT PIPING, POWER OR CONTROL WIRING. ALL CONNECTIONS ARE TO BE MADE INSIDE THE EQUIPMENT CURB OR THROUGH PRE-MANUFACTURED PIPING CURB.
NOTHING IS PERMITTED TO BE ATTACHED TO, SUSPENDED FROM, OR PENETRATE LANDLORD'S STRUCTURE, FLOOR DECK, OR ROOF DECK. YOU MAY ATTACH, ATTACH, NON-DESTRUCTIVELY, TO OR SUPPORT FROM THE TOP CHORD OF THE JOIST OR THE STRUCTURAL STEEL WHICH EXISTS ABOVE THE TENANT SPACE, WHEN ATTACHING TO LANDLORD'S STRUCTURE. DO NOT DRILL, WELD, SCREW, OR SHOOT INTO STRUCTURE. ALTERNATIVE METHODS OF ATTACHMENT ONLY. NOTHING TO DAMAGE LANDLORD'S BASE STRUCTURE. TENANT SHALL PROVIDE SIGNED AND SEALED STRUCTURAL DRAWINGS, BY A STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION AS INDICATED BY ALL JURISDICTION REQUIREMENTS, FOR ALL STRUCTURAL MODIFICATIONS FOR LANDLORD RECORDS.
ALL PENETRATIONS TO ROOF MUST BE APPROVED BY LANDLORD. ALL RELATED ROOF WORK MUST BE DONE BY MALL'S DESIGNATED ROOFING CONTRACTOR. AT TENANT'S EXPENSE. COORDINATE ALL WORK WITH PROPERTY MANAGEMENT ON SITE.
TENANT MUST REMOVE ALL ABANDONED ROOF TOP AND/OR MECHANICAL EQUIPMENT ABOVE THE LEASED PREMISES AND WITHING THE LEASED PREMISES, AT TENANT EXPENSE, PATCH AND REPAIR ROOF AS NEEDED.
TENANT'S GC TO LABEL ALL ROOF TOP EQUIPMENT WITH TENANT NAME SPACE NUMBER AND EQUIPMENT IDENTIFICATION (RTU-1, EF-1), PER MALL SPECIFICATIONS/STANDARDS.
ALL PIPING ON ROOF SHALL BE SUPPORTED ON PRE-MANUFACTURED PIPE SUPPORTS INSTALLED ON GARRY TREAD, SPACED PROPERLY TO SUPPORT PIPING. TREATED WOOD SUPPORTS ARE NOT PERMITTED.
ALL UNEXPOSED SUPPLY AIR AND OUTSIDE AIR DUCTWORK SHALL BE EXTERNALLY INSULATED WITH 1 1/2" THICK FOIL FACE INSULATION. INTERNALLY LINED DUCTWORK MAY BE USED FOR ACOUSTIC PURPOSES ONLY, NOT AS A SUBSTITUTE FOR EXTERNAL INSULATION.
ALL DUCTWORK SHALL BE SHEET METAL. FLEX DUCT MAY ONLY USED IN RUNS OF 5'-0" OR LESS.
AT CONCLUSION OF PROJECT, HVAC SYSTEM MUST BE TESTED AND BALANCED BY A LICENSED CONTRACTOR. COPY OF A BALANCE REPORT MUST BE PROVIDED TO PROPERTY MANAGEMENT OFFICE ON-SITE.
LANDLORD STRONGLY PREFERS USE ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.

LANDLORD ROOF TOP EQUIPMENT COMMENTS:

- ROOF EQUIPMENT, INCLUDING BUT NOT LIMITED TO HVAC EQUIPMENT, KITCHEN EQUIPMENT, DUCTS, AND PIPING SHALL BE SHOWN ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. SHALL NOT BE VISIBLE FROM THE OUTER RING ROAD OR FROM MALL SKYLIGHTS LOCATED WITHIN THE ROOF AREA OF THE PREMISES AND MINIMUM OF 5'-0" FROM THE VERTICAL PLANE OF ANY DEMISING PARTITION LOCATED, AND SHALL BE COORDINATE WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK. EQUIPMENT SCREENS OR SCREEN WALLS MAYBE REQUIRED AND SHALL BE APPROVED IN WRITING BY LANDLORD UNDER SEPARATE COVER.
TENANT SHALL PROVIDE A STRUCTURAL ENGINEER EVALUATION OF THE EXISTING CONSTRUCTION / STRUCTURE AND DETERMINES THAT IT IS SUFFICIENT FOR THE ADDITIONAL LOADS OF ALL NEW ROOF TOP EQUIPMENT IN ACCORDANCE WITH THE BUILDING CODE THAT HAS BEEN ADOPTED BY THE AUTHORITIES HAVING JURISDICTION (AHJ) AT TENANT'S SOLE EXPENSE. STRUCTURAL DETAILS ARE TO INCLUDE REFERENCE OF APPLICABLE BUILDING CODE(S), EXISTING BUILDING LOADS, AND ADDITIONAL LOADS THAT WILL BE ADDED TO THE STRUCTURE AN ANY REINFORCING THAT IS REQUIRED. STRUCTURAL DETAILS ARE TO BE SIGNED, SEALED, AND SUBMIT TO THE LANDLORD FOR THEIR RECORDS BY A LICENSED STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION IN THE STATE WIN WHICH THE PROJECT IS LOCATED. LANDLORD RESERVE THE RIGHT TO HAVE A 3RD PARTY ENGINEER PROVIDE DOCUMENTATION BY A 3RD PARTY INSPECTOR TO VERIFY THAT STRUCTURAL INSTALLATION HAS BEEN INSTALLED CORRECTLY.
ROOF EQUIPMENT REQUIRING DECK PENETRATION SHALL BE SET ON THE FACTORY SUPPLIED CURB AND MUST EXTEND A MINIMUM OF 12" ABOVE HIGHEST ROOF MATERIAL. RE-USE OF EXISTING CURBS OR THE USE OF CURB ADAPTERS IS STRICTLY PROHIBITED. TENANT SHALL RE-SLOPE ROOF TO MAIN PROPER DRAINAGE AND PROVIDE ROOFING, FLASHING, AND WATERPROOFING FOR INSTALLATION OF NEW CURB PER LANDLORD'S CRITERIA TENANT'S SOLE EXPENSE.
ALL CONDENSATION, ELECTRICAL AND DUCTWORK SHALL BE SET INSIDE THE PERIMETER OF CURB. CONDENSATE SHALL DRAIN INTO AN INTERIOR FLOOR DRAIN OR MOP SINK WITHIN THE PREMISES. DAYLIGHTING CONDENSATE LINES DIRECTLY ONTO THE ROOF, DOWNSPOUT OR ROOF DRAIN IS STRICTLY PROHIBITED.
TENANT SHALL PROVIDE 'ROOF TRAFFIC / WALKWAY PADS' AROUND ALL ROOF TOP EQUIPMENT AND SHALL INDICATE LOCATION OF PADS ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. COORDINATE FINAL LOCATION, MATERIAL, AND INSTALLATION OF PADS WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK.
TENANT SHALL LABEL ALL ROOF TOP EQUIPMENT INDICATING: TENANT NAME, SPACE NUMBER, AND EQUIPMENT IDENTIFICATION (RTU-1, EFT-1) PER LANDLORD'S DESIGN CRITERIA.
EQUIPMENT THAT UTILIZES CONDENSER COOLS SHALL BE EQUIPPED WITH HALL GUARDS.
LANDLORD STRONGLY PREFERS USE OF ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.



ZEBRA ARCHITECTURE, PLLC
1464 N KIERLAND BLVD SUITE N3000
SCOTTSDALE, ARIZONA 85254
PHONE: 480.912.1169 zbr.globeal




240 WEST 37TH STREET, 3RD FLOOR
NEW YORK, NY 10018
Tel: 212.413.8400
www.hnyeng.com
245002475
INC. CORPORATE NO. P-2451
EXPRES 6/30/2022



12/02/2024

STORE NO:
NC #1645



5404 NEW MARKET SQUARE SUITE 190
CHARLOTTE, NC 28227

REVISION

Table with 3 columns: Rev, Date, Description. Row 1: C, 11.05.24, REVISION C. Row 2: D, 12.02.24, REVISION D / IFC SET.

STATUS:
IFC SET

SHEET NAME:
MECHANICAL SPECIFICATIONS

DATE: 09/11/24 PROJECT NO: 39018

DRAWN: HEI SCALE: AS NOTED

SHEET NO:
M592

ROOFTOP UNIT CONTROL MATRIX						
CONTROL FEATURE	UNITS	RTU-1 SETPOINT OR Y/N	RTU-2 SETPOINT OR Y/N	NOTES		
CONTROL STRATEGY						
SPACE TEMPERATURE CONTROL			Y			
HEATING AND COOLING SET POINTS			Y			
COOLING MODE ENABLE - SPACE TEMPERATURE - OCCUPIED SETPOINT	"F DB	75	75			
COOLING MODE ENABLE - SPACE TEMPERATURE - UNOCCUPIED SETPOINT	"F DB	80	80			
COOLING SUPPLY AIR TEMPERATURE SETPOINT	"F DB	55	55			
HEATING MODE ENABLE - SPACE TEMPERATURE - OCCUPIED SETPOINT	"F DB	70	70			
HEATING MODE ENABLE - SPACE TEMPERATURE - UNOCCUPIED SETPOINT	"F DB	60	60			
HEATING - SUPPLY AIR TEMPERATURE SETPOINT	"F DB	85	85			
DEAD BAND - MINIMUM HEATING AND COOLING TEMPERATURE SETPOINT DIFFERENCE	"F DB	5	5			
DEHUMIDIFICATION SETPOINT HUMIDITY SENSOR FEEDBACK	"RH	50	50			
DEHUMIDIFICATION - REHEAT CONTROL - SUPPLY AIR TEMPERATURE SETPOINT	"F DB	70	70	F		
PROGRAMMED CONTROL FEATURES						
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT		Y	Y	B		
OPTIMAL START SEQUENCE		Y	Y			
EQUIPMENT COMPONENTS, ACCESSORIES AND CONTROL FEATURES						
COOLING COIL (DX - MODULATING CAPACITY)		Y	Y	K		
DEHUMIDIFICATION - MODULATING HOT GAS REHEAT		Y	Y			
RETURN AIR PATH WITH MOTORIZED RETURN AIR DAMPER FOR UNOCCUPIED OPERATION		Y	Y	D, T		
OUTSIDE AIR DAMPER - MOTOR OPERATED		Y	Y	J		
RELIEF/EXHAUST AIR DAMPER - BAROMETRIC		Y	N			
RELIEF/EXHAUST AIR DAMPER - MOTOR OPERATED		N	Y	J		
OUTSIDE/SUPPLY AIR AIRFLOW MONITORING		Y	Y	F		
REMOTE COMBINATION TEMPERATURE AND HUMIDITY SENSOR		Y	Y	B		
INTEGRATED ECONOMIZER - DIFFERENTIAL ENTHALPY ENABLE (EA ENTHALPY < RA ENTHALPY)	BTULB	Y	Y	U		
SUPPLY FAN CONTROL, METHODS						
ON DURING OCCUPIED MODE		Y	Y			
CYCLE WITH LOADS DURING UNOCCUPIED HOURS		Y	Y			
VARIABLE VOLUME - STAGED FAN CONTROL IN RESPONSE TO ACTIVE COOLING COIL STAGES		Y	Y	K, V		
SAFETIES, INTERLOCKS, AND ALARMS		Y	Y			
RETURN AIR SMOKE DETECTOR - SAFETY SHUTDOWN		Y	Y	E		
LOW LIMIT FREEZE/STAT - FREEZE PROTECTION SAFETY SHUTDOWN		Y	Y	F		
DIFFERENTIAL PRESSURE SWITCH - FILTER CHANGE ALARM		Y	Y	F		
FIRE ALARM CONTROL PANEL - SAFETY SHUTDOWN INTERLOCK		Y	Y	S		
OUTSIDE AIR DAMPER END SWITCH - SAFETY SHUTDOWN		Y	Y	S		
KITCHEN EXHAUST SYSTEM INTERLOCK		Y	Y	L		

Div. 23 CONTRACTOR SHALL PROVIDE CONTROL PANEL(S), WIRING, THERMOSTAT(S), TEMPERATURE SENSOR(S), HUMIDISTAT(S), AND/OR CO2 SENSOR(S) WHERE SHOWN ON THE DRAWINGS AND AS REQUIRED TO FACILITATE THE SCHEDULED CONTROL, MODULES AND SEQUENCES OF OPERATION. EACH UNIT SHALL CONTROL BASED ON ITS OWN INTERNAL SAFETIES, TIME DELAYS, AND SEQUENCES UNLESS NOTED OTHERWISE. COORDINATE WITH OWNER FINAL BUILDING AND EQUIPMENT SCHEDULES DURING STARTUP. REFERENCE DIVISION SPECIFICATIONS FOR INDIVIDUAL DEVICE REQUIREMENTS.

- NOTES:
- DIVISION 23 CONTRACTOR SHALL PROVIDE DEVICE.
 - DURING UNOCCUPIED OPERATION, EXHAUST AND OUTSIDE AIR DAMPERS SHALL CLOSE. THE RETURN AIR DAMPER SHALL OPEN TO PERMIT RECIRCULATION OF INDOOR AIR THROUGH UNIT.
 - DIVISION 28 CONTRACTOR SHALL PROVIDE DEVICE.
 - DEVICE SHALL BE FACTORY MOUNTED AND PRE-WIRED FOR OPERATION SUBJECT TO THE ONBOARD CONTROLLER.
 - DAMPER SHALL BE CLOSED DURING UNOCCUPIED MODE.
 - UNITARY CONTROLLER SHALL MODULATE AND/OR CYCLE SUPPLY FAN SPEED AND COIL CAPACITY SUBJECT TO THE INTERNAL SAFETIES AND SEQUENCES TO MAINTAIN SCHEDULED SETPOINTS.
 - INTERLOCK RTU WITH KITCHEN EXHAUST HOOD SYSTEMS) TO SHUT DOWN UPON SIGNAL FROM HOOD FIRE EXTINGUISHING SYSTEM. INTERLOCK RTU WITH KITCHEN EXHAUST FAN TO ENERGIZE WHEN HOOD SYSTEM IS ENERGIZED FOR PRESSURIZATION.
 - UNITS THAT PROVIDE VENTILATION AIR TO MULTIPLE ZONES AND OPERATE IN CONJUNCTION WITH ZONE HEATING AND COOLING SYSTEMS SHALL NOT USE HEATING OR HEAT RECOVERY TO WARM SUPPLY AIR TO A TEMPERATURE GREATER THAN VALUE INDICATED WHEN THE OUTSIDE AIR TEMPERATURE EXCEEDS 75F.
 - VENTILATION ONLY MODE PROVIDES OUTSIDE AIR DIRECTLY TO SPACE WITHOUT HEATING OR COOLING WHEN OUTDO... ARE FAVORABLE. VENTILATION ONLY MODE CAN BE INTERRUPTED ON A CALL FOR DEHUMIDIFICATION.
 - PROVIDE END SWITCH ON THE OUTSIDE AIR DAMPER AND INTERLOCK THE SWITCH WITH THE SUPPLY FAN TO KEEP IT FROM STARTING IF END SWITCH IS NOT MADE.
 - DURING UNOCCUPIED OPERATION, OUTSIDE AIR DAMPERS SHALL CLOSE AND RETURN AIR DAMPER SHALL MODULATE... IF SETPOINT VALUE IS LISTED, IT INDICATES ECONOMIZER HIGH/LIMIT SHUTOFF. UNIT SHALL BE IN ECONOMIZER IF CONDITIONS ARE LESS THAN SETPOINT. THE FOLLOWING SENSORS SHALL DETERMINE ECONOMIZER ON POINT. OUTSIDE AIR TEMPERATURE; DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE. RETURN AIR TEMPERATURE; DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE. OUTSIDE AIR HUMIDITY; DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE. RETURN AIR HUMIDITY; DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
 - PROVIDE STAGED FAN CONTROL WITH MINIMUM 2 FAN SPEEDS. LOW SPEED SHALL NOT EXCEED 66% OF FULL SPEED AND SHALL DRAW NO MORE THAN 40% OF FAN POWER AT FULL SPEED.

MARK	MANUFACTURER	MODEL	NOMINAL TONS	UNIT TYPE	SUPPLY FAN										HEAT PUMP HEATING COIL						AUXILIARY HEATING COIL				ELECTRICAL		WEIGHT (LBS)	NOTES				
					DESIGN		ESP		VFD		REFR		EAT		LAT		MIN EFF		MIN NO		MIN OUT		VPH		MCA				MOCP		DISC	
					OA	CFM	(IN)	HP	(Y/N)	TYPE	TH	SH	(F DB)	(F WB)	(F DB)	(F WB)	(EER)	STAGES	(MBH)	(DB)	(F DB)	(F WB)	(ISCCP)	(KW)	MIN NO	MIN NO			(MBH)	(DB)	(F DB)	(F WB)
RTU-1	CAPTIVEAIRE	CAS-HVAC-E-152-18-10T	10	SINGLE ZONE	900	3,600	1.0	5.0	Y	R410A	138.3	99.9	79.8	65.9	54.6	53.2	18.6	3	105.95	21	57.8	85	3.4	11	2	2083	81.4	80	NF	2051	A-P	
RTU-2	CAPTIVEAIRE	CAS-HVAC-E-302-24-15T	15	SINGLE ZONE	1,200	5,300	0.8	7.5	Y	R410A	194.3	143.9	79.4	65.5	54.7	53.4	18.8	3	149.36	21	58.9	85	3.5	22	2	2083	103.8	110	NF	2665	A-P	

MARK	MFR	MODEL	SUPPLY FAN		COOLING COIL						HEAT PUMP HEATING COIL						ELECTRICAL		WEIGHT (LBS)	NOTES						
			CFM	ESP	TH	SH	EAT		LAT		MIN EFF		MIN NO		MIN OUT		VPH				MCA		MOCP		DISC	
			(IN)	(SEER)	(F DB)	(F WB)	(F DB)	(F WB)	TYPE	(MBH)	(DB)	(F DB)	(F WB)	(EER)	STAGES	(MBH)	(DB)	(F DB)			(F WB)	(ISCCP)	(KW)	MIN NO	MIN NO	(MBH)
FCU-1	CARRIER	40MBQC018	420	0.025	0.061	10.7	9.2	76.8	63.8	56.9	55.4	R410A	8.92	21	65.3	85	40	2081	N/A	N/A	N/A	NF	45	A - J		

*EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION. MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

MARK	SERVICE	MANUFACTURER	MODEL	REFR	HEAT PUMP CONDENSING UNIT SCHEDULE						ELECTRICAL		WEIGHT (LBS)	NOTES						
					COOLING CAPACITY		HEATING CAPACITY		MIN		VPH				MCA		MOCP		DISC	
					TH	SH	AMBIENT	MIN EFF	AMBIENT	MIN EFF	MIN	HP			VFD	DISC	STARTER	TYPE	(LBS)	
CU-1	FCU-1	CARRIER	38MARB018AA3	R410A	10.7	94.2	19.0	8.9	21	3.3	18	25	2081.1	102.5	A - H					

*EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION. MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

MARK	SERVICE AREA	MANUFACTURER	MODEL	UNIT SPECS				NOTES	
				LENGTH	AIRFLOW	HEATING	MOTOR		
				(IN)	(CFM)	(KW)	(HP)		
AC-1	SERVICE ENTRY	MARS	ST02	36	1379	N/A	1/2	115/1	A-F

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

MARK	SERVICE	MANUFACTURER	MOUNTING	MODEL	FAN SCHEDULE										NOTES
					CFM	ESP	DRIVE	MIN.	FAN	VFD	ELECTRICAL				
					(IN)	(IN)	(Y/N)	HP	RPM	(Y/N)	VPH	DISC.	STARTER	TYPE	
EF-1	TOILETS	GREENHECK	ROOF	G-080-VG	200	0.5	DIRECT	1/4	1516	N	120/1	NF	N/A	A-E	

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

MARK	SERVICE	MANUFACTURER	MOUNTING	MODEL	FAN SCHEDULE										NOTES
					CFM	ESP	DRIVE	MIN.	FAN	VFD	ELECTRICAL				
					(IN)	(IN)	(Y/N)	HP	RPM	(Y/N)	VPH	DISC.	STARTER	TYPE	
EF-1	TOILETS	GREENHECK	ROOF	G-080-VG	200	0.5	DIRECT	1/4	1516	N	120/1	NF	N/A	A-E	

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

MARK	MANUFACTURER	MODEL	NOMINAL TONS	UNIT TYPE	SUPPLY FAN										HEAT PUMP HEATING COIL						AUXILIARY HEATING COIL				ELECTRICAL		WEIGHT (LBS)	NOTES				
					DESIGN		ESP		VFD		REFR		EAT		LAT		MIN EFF		MIN NO		MIN OUT		VPH		MCA				MOCP		DISC	
					OA	CFM	(IN)	HP	(Y/N)	TYPE	TH	SH	(F DB)	(F WB)	(F DB)	(F WB)	(EER)	STAGES	(MBH)	(DB)	(F DB)	(F WB)	(ISCCP)	(KW)	MIN NO	MIN NO			(MBH)	(DB)	(F DB)	(F WB)
RTU-1	CAPTIVEAIRE	CAS-HVAC-E-152-18-10T	10	SINGLE ZONE	900	3,600	1.0	5.0	Y	R410A	138.3	99.9	79.8	65.9	54.6	53.2	18.6	3	105.95	21	57.8	85	3.4	11	2	2083	81.4	80	NF	2051	A-P	
RTU-2	CAPTIVEAIRE	CAS-HVAC-E-302-24-15T	15	SINGLE ZONE	1,200	5,300	0.8	7.5	Y	R410A	194.3	143.9	79.4	65.5	54.7	53.4	18.8	3	149.36	21	58.9	85	3.5	22	2	2083	103.8	110	NF	2665	A-P	

BUILDING AIR BALANCE SUMMARY STANDARD				
UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/S/A
RTU-1	3,600	900	--	25%
RTU-2	5,300	1,200	--	23%
FCU-1	450	40	--	9%
KEF-1	--	--	750	--
KEF-2	--	--	700	--
EF-1	--	--	200	--
TOTALS	9,350	2,140	1,650	--
TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)				490
PERCENT POSITIVE PRESSURIZATION				22.9%

BUILDING AIR BALANCE SUMMARY ECONOMIZER				
UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/S/A
RTU-1	3,600	3,600	--	100%
RTU-2	5,300	5,300	--	100%
FCU-1	450	40	--	9%
KEF-1	--	--	750	--
KEF-2	--	--	700	--
EF-1	--	--	200	--
RELIEF RTU-1	--	--	2,700	--
RELIEF RTU-2	--	--	4,100	--
TOTALS	9,350	8,940	8,450	--
TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)				490
PERCENT POSITIVE PRESSURIZATION				5.5%

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

MARK	MANUFACTURER	SERVICE	MODEL	CONSTRUCTION MATERIAL	FACE TYPE	MOUNTING LOCATION	FACE SIZE (IN)	MAX. NC	NOTES
CEG	E.H. PRICE	EXHAUST GRILLE W/ DAMPER	800	STEEL	EGGCRATE	SURFACE	12x12	30	A B C F G H
CRG	E.H. PRICE	RETURN GRILLE	80	STEEL	EGGCRATE	LAY-IN	24x24	30	A B C F H
CSD1	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	SURFACE	12x12	30	A B C F H J K L
CSD2	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	LAY-IN	24x24	30	A B C F H K
CSD3	E.H. PRICE	SUPPLY DIFFUSER	PDOR	STEEL	PERFORATED	LAY-IN	24x24	30	A B C F H
WRG	E.H. PRICE	RETURN GRILLE W/DAMPER	530D	STEEL	LOUVERED FACE	WALL OR DUCT	(SEE PLANS)	30	A B C D F H
WSR	E.H. PRICE	SUPPLY REGISTER W/ DAMPER	520D	STEEL	LOUVERED FACE	WALL OR DUCT	(SEE PLANS)	30	A B C D E F G H

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

- NOTES:
- EQUIPMENT FURNISHED AND INSTALLED PER THE EQUIPMENT RESPONSIBILITY SCHEDULE.
 - NECK SIZE SHOWN ON DRAWINGS. PROVIDE BRANCH DUCT TO MATCH NECK SIZE UNLESS OTHERWISE SHOWN ON DRAWINGS.
 - DIFFUSERS SHALL BE PREFINISHED TO MATCH CEILING/WALL/EXPOSED DUCT COLOR (COORDINATE WITH ARCHITECT).
 - FRONT BLADES PARALLEL TO LONG DIMENSION.
 - DOUBLE DEFLECTION BARS SHALL BE ADJUSTABLE.
 - FRAME TYPE TO MATCH CEILING/WALL CONSTRUCTION. COORDINATE WITH ARCHITECTURAL REFLECTED CEILING/WALL PLAN.
 - PROVIDE OPPOSED BLADE DAMPER ADJUSTABLE FROM FACE OF DEVICE.
 - PROVIDE DIFFUSERS, LINEAR SLOTS, AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.
 - CONTRACTOR SHALL PROVIDE REMOTE OPERATED VOLUME DAMPER BY METROPOLITAN AIR TECHNOLOGIES MODEL RT-255 WITH EXTERNAL WORM GEAR OPERATOR OR EQUIVALENT YOUNG REGULATOR BUTTERFLY DAMPER WITH 270-275 CONTROLLER. OPERATOR SHALL HAVE A SQUARE DRIVE FOR 1/4" NUT DRIVER. DAMPER ASSEMBLY SHALL INCLUDE GALVANIZED STEEL DUCT WITH ROLLED BEAD STIFFENERS, REINFORCED BLADE, SELF LUBRICATING BEARING AND WORM GEAR MOUNTING PLATE. DAMPER SHALL BE INSTALLED IN BRANCH DUCT NOT INLET OF PLENUM DIFFUSER. (REF: 21M91)
 - 4-WAY THROW PATTERN UNLESS OTHERWISE INDICATED BY FLOW ARROWS ON DRAWINGS.
 - PROVIDE RAPID MOUNT FRAME FOR INSTALLATION IN HARD CEILING.

PROJECT DESIGN CONDITIONS																					
CLIMATE CONDITIONS					BUILDING OPERATING HOURS:																
WEATHER STATION: CHARLOTTE DOUGLASS, NC					MONDAY - FRIDAY: TBD BY OWNER																
CLIMATE ZONE: 3A					SATURDAY: TBD BY OWNER																
HEATING (DB): 99.6% 21.0 °F					SUNDAY: TBD BY OWNER																
COOLING (DB&MCWB): 0.4% 94.2 °F/ 74.8 °F/					HOLIDAY: TBD BY OWNER																
SPACE / UNIT DESCRIPTION	COOLING / DE-HUMIDIFICATION				HEATING				HUMIDIFICATION				ZONE VENTILATION RESET				SPACE OPERATING HOURS OCCUPIED / UNOCCUPIED				NOTES
	OCC	UNOCC	MAX RH %	MIN RH %	OCC	UNOCC	MIN	MAX	CONTROL METHOD	BASE PPM	MAXIMUM PPM	M-F	SAT	SUN	TBD	TBD	TBD	A-B,C			
DINING AREAS	75	80	50%	NA	70	60	NA	NA	NA	NA	NA	TBD	TBD	TBD	TBD	TBD	TBD	A,B,C			
OFFICES	75	80	50%	NA	70	60	NA	NA	NA	NA	NA	TBD	TBD	TBD	TBD	TBD	TBD	A,B,C			
MECHANICAL ROOM	NA	NA	NA	NA	70	60	NA	NA	NA	NA	NA	TBD	TBD	TBD	TBD	TBD	TBD	A,B,C			
KITCHEN/BOH	75	80	5																		

COMcheck Software Version COMcheckWeb
Mechanical Compliance Certificate

Project Information

Energy Code: 2015 IECC
 Project Title: CHARLOTTE Shake Shack
 Location: Charlotte, North Carolina
 Climate Zone: 3a
 Project Type: New Construction

Construction Site: 5404 New Fashion Way, Charlotte, North Carolina 28278
 Owner/Agent: Shake Shack
 Designer/Contractor: Henderson Engineers, 8345 Lenexa Dr #300, Lenexa, Kansas 66214

Additional Efficiency Package(s)

Credits: 1.0 Required, 1.0 Proposed
 Reduced Lighting Power, 1.0 credit

Mechanical Systems List

Quantity System Type & Description

- RTU-1 (Single Zone):
 Heating: 1 each - Other, Gas, Capacity = 81 kBtu/h
 No minimum efficiency requirement applies
 Cooling: 1 each - Single Package DX Unit, Capacity = 143 kBtu/h, Air-Cooled Condenser, Air Economizer
 Proposed Efficiency = 11.80 EER, Required Efficiency = 10.80 EER
 Proposed Part Load Efficiency = 18.60 EER, Required Part Load Efficiency = 12.20 EER
 Fan System: RTU-1 | Dining/Queueing - Compliance (Motor nameplate HP and fan efficiency method) : Passes
 Fans:
 RTU Supply, Single-Zone VAV, 3600 CFM, 5.0 motor nameplate hp, 0.0 fan efficiency grade, 0.0 total fan efficiency, 0.0 design fan efficiency, fan exception: Part of code listed equipment
- RTU-2 (Single Zone):
 Heating: 1 each - Other, Gas, Capacity = 109 kBtu/h
 No minimum efficiency requirement applies
 Cooling: 1 each - Single Package DX Unit, Capacity = 211 kBtu/h, Air-Cooled Condenser, Air Economizer
 Proposed Efficiency = 11.80 EER, Required Efficiency = 10.80 EER
 Proposed Part Load Efficiency = 18.60 EER, Required Part Load Efficiency = 12.20 EER
 Fan System: RTU-2 | Kitchen/BOH - Compliance (Brake HP and fan efficiency method) : Passes
 Fans:
 RTU2 Supply, Constant Volume, 5300 CFM, 5.0 motor nameplate hp, 4.1 design brake hp (4.1 max. BHP), 0.0 fan efficiency grade, 0.0 total fan efficiency, 0.0 design fan efficiency, fan exception: Part of code listed equipment
- FCU-1 (Single Zone):
 Heating: 1 each - Other, Gas, Capacity = 11 kBtu/h
 No minimum efficiency requirement applies
 Cooling: 1 each - Split System, Capacity = 12 kBtu/h, Air-Cooled Condenser, Air Economizer
 Proposed Efficiency = 13.00 SEER, Required Efficiency = 13.00 SEER
 Proposed Part Load Efficiency = 0.00, Required Part Load Efficiency = 0.00
 Fan System: FCU-1/FCU-1 | Office - Compliance (Motor nameplate HP and fan efficiency method) : Passes
 Fans:
 FCU1 Supply, Constant Volume, 420 CFM, 0.1 motor nameplate hp, 0.0 fan efficiency grade, 0.0 total fan efficiency, 0.0 design fan efficiency, fan exception: Part of code listed equipment
- Water Heater:
 Gas Instantaneous Water Heater, Capacity: 0 gallons, Input Rating: 199 kBtu/h w/ Circulation Pump
 Proposed Efficiency: 95.00 EF, Required Efficiency: 0.62 EF

Project Title: CHARLOTTE Shake Shack Report date: 09/10/24
 Data filename: Page 1 of 9

Section & Req ID	Footing / Foundation Inspection	Complies?	Comments/Assumptions
C403.2.4.5, C403.2.4.6, (FC9)1	Snowice melting system sensors for future connection to controls. Freeze protection systems have automatic controls installed.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

1 | High Impact (Tier 1) | 2 | Medium Impact (Tier 2) | 3 | Low Impact (Tier 3)

Project Title: CHARLOTTE Shake Shack Report date: 09/10/24
 Data filename: Page 4 of 9

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2015 IECC requirements in COMcheck Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Cesar Giron 09/10/2024
 Name - Title Signature Date

Section & Req ID	Plumbing Rough-In Inspection	Complies?	Comments/Assumptions
C404.5, C404.5.1, C404.5.2, (PL6)1	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C404.6.1, C404.6.2, (PL3)1	Automatic time switches installed to automatically switch off the recirculating hot-water system or heat traces.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C404.6.3, (PL7)1	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C404.7, (PL8)1	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

1 | High Impact (Tier 1) | 2 | Medium Impact (Tier 2) | 3 | Low Impact (Tier 3)

Project Title: CHARLOTTE Shake Shack Report date: 09/10/24
 Data filename: Page 5 of 9

COMcheck Software Version COMcheckWeb
Inspection Checklist

Energy Code: 2015 IECC

Requirements: 5.0% were addressed directly in the COMcheck software

Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section & Req ID	Plan Review	Complies?	Comments/Assumptions
C103.2 (PR2)1	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical systems and equipment and document where exceptions to the standard are claimed. Load calculations per acceptable engineering standards and handbooks.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C103.2 (PR3)1	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the service water heating systems and equipment and document where exceptions to the standard are claimed. Hot water system sized per manufacturer's sizing guide.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C406 (PR9)1	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the additional energy efficiency package options.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

1 | High Impact (Tier 1) | 2 | Medium Impact (Tier 2) | 3 | Low Impact (Tier 3)

Project Title: CHARLOTTE Shake Shack Report date: 09/10/24
 Data filename: Page 3 of 9

Section & Req ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C402.2.6, (ME1)1	Thermally ineffective panel surfaces of sensible heating panels have insulation >= R-3, 5.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.13, (ME7)1	Unenclosed spaces that are heated use only radiant heat.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.4, (ME13)1	Fault detection and diagnostics installed with air-cooled unitary DX units having economizers.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.6, (ME59)1	Demand control ventilation provided for spaces >900 ft ² and >25 people/1000 ft ² occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow > 3,000 cfm.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.6, (ME15)1	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.7, (ME57)1	Exhaust air energy recovery on systems meeting Table C403.2.7(1) and C403.2.7(2).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.8, (ME16)1	Kitchen exhaust systems comply with replacement air and conditioned supply air limitations, and satisfy hood rating requirements and maximum exhaust rate criteria.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.9, (ME60)1	HVAC ducts and plenums insulated. Where ducts or plenums are installed in or under a slab, verification may need to occur during Foundation Inspection.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.9, (ME10)1	Ducts and plenums sealed based on static pressure and location.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.9, (ME11)1	Ductwork operating >3 in. water column requires air leakage testing.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.3, (ME62)1	Air economizers provided where required, meet the requirements for design capacity, control signal, ventilation controls, high-limit shut-off, integrated economizer control, and provide a means to relieve excess outside air during operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.4.4, (ME10)1	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	See the Mechanical Systems list for values.

1 | High Impact (Tier 1) | 2 | Medium Impact (Tier 2) | 3 | Low Impact (Tier 3)

Project Title: CHARLOTTE Shake Shack Report date: 09/10/24
 Data filename: Page 6 of 9

LANDLORD'S REVIEW COMMENTS

MECHANICAL COMMENTS:

- ANY CHANGES AND/OR UPGRADES TO TENANT'S EXISTING MECHANICAL SYSTEMS SHALL COMPLY WITH ALL CODES AND MALL CRITERIA. EXISTING SYSTEMS SHALL POSSESS THE CAPACITY TO HANDLE ANY AND ALL CHANGES IN LOAD.
- NO PITCH POCKETS ARE PERMITTED ON THE ROOF FOR ANY CONDENSATE DRAINS. REFRIGERANT PIPING, POWER OR CONTROL WIRING, ALL CONNECTIONS ARE TO BE MADE INSIDE THE EQUIPMENT CURB OR THROUGH PRE-MANUFACTURED PIPING CURB.
- NOTHING IS PERMITTED TO BE ATTACHED TO, SUSPENDED FROM, OR PENETRATE LANDLORD'S STRUCTURE, FLOOR DECK, OR ROOF DECK, YOU MAY ATTACH, ATTACH, NON-DESTRUCTIVELY, TO OR SUSPEND FROM THE TOP CHORD OF THE JOIST OR THE STRUCTURAL STEEL WHICH EXISTS ABOVE THE TENANT SPACE. WHEN ATTACHING TO LANDLORD'S STRUCTURE, DO NOT DRILL, WELD, SCREW, OR SHOOT INTO STRUCTURE. ALTERNATIVE METHODS OF ATTACHMENT ONLY. NOTHING TO DAMAGE LANDLORD'S BASE STRUCTURE. TENANT SHALL PROVIDE SIGNED AND SEALED STRUCTURAL DRAWINGS, BY A STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION AS INDICATED BY ALL JURISDICTIONAL REQUIREMENTS, FOR ALL STRUCTURAL MODIFICATIONS FOR LANDLORD RECORDS.
- ALL PENETRATIONS TO ROOF MUST BE APPROVED BY LANDLORD. ALL RELATED ROOF WORK MUST BE DONE BY MALL'S DESIGNATED ROOFING CONTRACTOR. AT TENANT'S EXPENSE. COORDINATE ALL WORK WITH PROPERTY MANAGEMENT ON-SITE.
- TENANT MUST REMOVE ALL ABANDONED ROOF TOP AND/OR MECHANICAL EQUIPMENT ABOVE THE LEASED PREMISES AND WITHING THE LEASED PREMISES, AT TENANT EXPENSE, PATCH AND REPAIR ROOF AS NEEDED.
- TENANT'S GC TO LABEL ALL ROOF TOP EQUIPMENT WITH TENANT NAME SPACE NUMBER AND EQUIPMENT IDENTIFICATION (RTU-1, EF-1), PER MALL SPECIFICATIONS/ STANDARDS.
- ALL PIPING ON ROOF SHALL BE SUPPORTED ON PRE-MANUFACTURED PIPE SUPPORTS INSTALLED ON GARRY TREAD, SPACED PROPERLY TO SUPPORT PIPING. TREATED ARE NOT ADMITTED.
- ALL UNEXPOSED SUPPLY AIR AND OUTSIDE AIR DUCTWORK SHALL BE EXTERNALLY INSULATED WITH 1 1/2" THICK FOIL FACE INSULATION. INTERNALLY NESTED DUCTWORK MAY BE USED FOR ACOUSTIC PURPOSES ONLY, NOT AS A SUBSTITUTE FOR EXTERNAL INSULATION.
- ALL DUCTWORK SHALL BE SHEET METAL. FLEX DUCT MAY ONLY USED IN RUNS OF 5'-0" OR LESS.
- AT CONCLUSION OF PROJECT, HVAC SYSTEM MUST BE TESTED AND BALANCED BY A LICENSED CONTRACTOR. COPY OF A BALANCE REPORT MUST BE PROVIDED TO PROPERTY MANAGEMENT OFFICE ON-SITE.
- LANDLORD STRONGLY PREFERS USE ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.

LANDLORD ROOF TOP EQUIPMENT COMMENTS:

- ROOF EQUIPMENT, INCLUDING BUT NOT LIMITED TO HVAC EQUIPMENT, KITCHEN EQUIPMENT, DUCTS, AND PIPING SHALL BE SHOWN ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. SHALL NOT BE VISIBLE FROM THE OUTER RING ROAD OR FROM MALL SKYLIGHTS. LOCATED WITHIN THE ROOF AREA OF THE PREMISES AND MINIMUM OF 5'-0" FROM THE VERTICAL PLANE OF ANY DEMISING PARTITION LOCATED, AND SHALL BE COORDINATE WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK. EQUIPMENT SCREENS OR SCREEN WALLS MAYBE REQUIRED AND SHALL BE APPROVED IN WRITING BY LANDLORD UNDER SEPARATE COVER.
- TENANT SHALL PROVIDE A STRUCTURAL ENGINEER EVALUATION OF THE EXISTING CONSTRUCTION / STRUCTURE AND DETERMINES THAT IT IS SUFFICIENT FOR THE ADDITIONAL LOADS OF ALL NEW ROOF TOP EQUIPMENT IN ACCORDANCE WITH THE BUILDING CODE THAT HAS BEEN ADOPTED BY THE AUTHORITIES HAVING JURISDICTION (AHJ) AT TENANT'S SOLE EXPENSE. STRUCTURAL DETAILS ARE TO INCLUDE REFERENCE OF APPLICABLE BUILDING CODE(S), EXISTING BUILDING LOADS, AND ADDITIONAL LOADS THAT WILL BE ADDED TO THE STRUCTURE AN ANY REINFORCING THAT IS REQUIRED. STRUCTURAL DETAILS ARE TO BE SIGNED, SEALED, AND SUBMIT TO THE LANDLORD FOR THEIR RECORDS BY A LICENSED STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION IN THE STATE WITH WHICH THE PROJECT IS LOCATED. LANDLORD RESERVE THE RIGHT TO HAVE A 3RD PARTY ENGINEER PROVIDE DOCUMENTATION BY A 3RD PARTY INSPECTOR TO VERIFY THAT STRUCTURAL INSTALLATION HAS BEEN INSTALLED CORRECTLY.
- ROOF EQUIPMENT REQUIRING DECK PENETRATION SHALL BE SET ON THE FACTORY SUPPLIED CURB AND MUST EXTEND A MINIMUM OF 12" ABOVE HIGHEST ROOF MATERIAL. RE-USE OF EXISTING CURBS OR THE USE OF CURB ADAPTERS IS STRICTLY PROHIBITED. TENANT SHALL RE-SLOPE ROOF TO MAIN PROPER DRAINAGE AND PROVIDE ROOFING, FLASHING, AND WATERPROOFING FOR INSTALLATION OF NEW CURB PER LANDLORD'S CRITERIA TENANT'S SOLE EXPENSE.
- ALL CONDENSATION, ELECTRICAL AND DUCTWORK SHALL BE SET INSIDE THE PERIMETER OF CURB. CONDENSATE SHALL DRAIN INTO AN INTERIOR FLOOR DRAIN OR MOP SINK WITHIN THE PREMISES. DAYLIGHTING CONDENSATE LINES DIRECTLY ONTO THE ROOF, DOWNSPOUT OR ROOF DRAIN IS STRICTLY PROHIBITED.
- TENANT SHALL PROVIDE 'ROOF TRAFFIC / WALKWAY PADS' AROUND ALL ROOF TOP EQUIPMENT AND SHALL INDICATE LOCATION OF PADS ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. COORDINATE FINAL LOCATION, MATERIAL, AND INSTALLATION OF PADS WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK.
- TENANT SHALL LABEL ALL ROOF TOP EQUIPMENT INDICATING: TENANT NAME, SPACE NUMBER, AND EQUIPMENT IDENTIFICATION (RTU-1, EFT-1) PER LANDLORD'S DESIGN CRITERIA.
- EQUIPMENT THAT UTILIZES CONDENSER COILS SHALL BE EQUIPPED WITH HALL GUARDS.
- LANDLORD STRONGLY PREFERS USE OF ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.

STORE NO:
NC #1645

SHAKE SHACK
 CHARLOTTE
 5404 NEW FASHION WAY, SUITE 190
 CHARLOTTE, NC 28278

REVISION

Δ	DATE	DESCRIPTION
C	09.11.24	REVISION C
D	12.02.24	REVISION D / IFC SET

STATUS:
IFC SET

SHEET NAME:
MECHANICAL ENERGY CODE COMPLIANCE

DATE: 09/11/24 PROJECT NO: 39018
 DRAWN: HEI SCALE: AS NOTED
 SHEET NO:
M630

zebra
 ZEBRA ARCHITECTURE, PLLC
 1464 N KIERLAND BLVD, SUITE N300
 SCOTTSDALE, ARIZONA 85254
 PHONE: 480.912.1169 zbr.global

HNY CONSULTING ENGINEERS
 240 WEST 37TH STREET, 3RD FLOOR
 NEW YORK, NY 10018
 TEL: 212.413.8400
 www.hny.com

245002475
 EXPRES 8/07/2024
 NC CORPORATE NO. P-2451

PROFESSIONAL SEAL
 NORTH CAROLINA PROFESSIONAL ENGINEER
 046826
 CHARLES W. HOOPER
 12/02/2024

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C408.2.3.1 [F131]	HVAC equipment has been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C408.2.3.2 [F110]	HVAC control systems have been tested to ensure proper operation, calibration and adjustment of controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C408.2.3.3 [F132]	Economizers have been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C408.2.4 [F129]	Preliminary commissioning report completed and certified by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C408.2.5.1 [F17]	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C408.2.5.3 [F143]	An air and/or hydronic system balancing report is provided for HVAC systems.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C408.2.5.4 [F130]	Final commissioning report due to building owner within 90 days of receipt of certificate of occupancy.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

High Impact (Tier 1)
 Medium Impact (Tier 2)
 Low Impact (Tier 3)

Project Title: CHARLOTTE Shake Shack Report date: 09/10/24
Data filename: Page 9 of 9

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C408.2.2.2 [ME3]	Air outlets and zone terminal devices have means for air balancing.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.5.1 [ME123]	Refrigerated display cases, walk-in coolers or walk-in freezers served by remote compressors and remote condensers not located in a condensing unit, have fan-powered condensers that comply with Sections C403.5.1 and refrigeration compressor systems that comply with C403.5.2.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

High Impact (Tier 1)
 Medium Impact (Tier 2)
 Low Impact (Tier 3)

Project Title: CHARLOTTE Shake Shack Report date: 09/10/24
Data filename: Page 7 of 9

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C303.3.1 [F18]	Furnished O&M manuals for HVAC systems within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.2 [F127]	HVAC systems and equipment capacity does not exceed calculated loads.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.4.1 [F147]	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.4.1.2 [F138]	Thermostatic controls have a 5°F deadband.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.4.1.3 [F120]	Temperature controls have setpoint overlap restrictions.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.4.2 [F139]	Each zone equipped with setback controls using automatic time clock or programmable control system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.4.2.1 [F140]	Automatic Controls: Setback to 55°F (heat) and 55°F (cool); 7-day clock, 2-hour occupant override, 10-hour backup.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.2.4.2.2 [F141]	Systems include optimum start controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C404.3 [F111]	Heat traps installed on supply and discharge piping of non-circulating systems.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C404.4 [F125]	All piping insulated in accordance with section details and Table C403.2.10.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C404.6.1 [F112]	Controls are installed that limit the operation of a recirculation pump installed to maintain temperature of a storage tank. System return pipe is a dedicated return pipe or a cold water supply pipe.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C408.2.1 [F128]	Commissioning plan developed by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

High Impact (Tier 1)
 Medium Impact (Tier 2)
 Low Impact (Tier 3)

Project Title: CHARLOTTE Shake Shack Report date: 09/10/24
Data filename: Page 8 of 9

LANDLORD'S REVIEW COMMENTS

MECHANICAL COMMENTS:

- ANY CHANGES AND/OR UPGRADES TO TENANT'S EXISTING MECHANICAL SYSTEMS SHALL COMPLY WITH ALL CODES AND MALL CRITERIA. EXISTING SYSTEMS SHALL POSSESS THE CAPACITY TO HANDLE ANY AND ALL CHANGES IN LOAD.
- NO PITCH POCKETS ARE PERMITTED ON THE ROOF FOR ANY CONDENSATE DRAINS, REFRIGERANT PIPING, POWER OR CONTROL WIRING. ALL CONNECTIONS ARE TO BE MADE INSIDE THE EQUIPMENT CURB OR THROUGH PRE-MANUFACTURED PIPING CURB.
- NOTHING IS PERMITTED TO BE ATTACHED TO, SUSPENDED FROM, OR PENETRATE LANDLORD'S STRUCTURE, FLOOR DECK, OR ROOF DECK. YOU MAY ATTACH, ATTACH, NON-DESTRUCTIVELY, TO OR SUSPEND FROM THE TOP CHORD OF THE JOIST OR THE STRUCTURAL STEEL WHICH EXISTS ABOVE THE TENANT SPACE. WHEN ATTACHING TO LANDLORD'S STRUCTURE, **DO NOT DRILL, WELD, SCREW, OR SHOOT** INTO STRUCTURE. ALTERNATIVE METHODS OF ATTACHMENT ONLY. NOTHING TO DAMAGE LANDLORD'S BASE STRUCTURE. TENANT SHALL PROVIDE SIGNED AND SEALED STRUCTURAL DRAWINGS, BY A STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION AS INDICATED BY ALL JURISDICTIONAL REQUIREMENTS, FOR ALL STRUCTURAL MODIFICATIONS FOR LANDLORD RECORDS.
- ALL PENETRATIONS TO ROOF MUST BE APPROVED BY LANDLORD. ALL RELATED ROOF WORK MUST BE DONE BY MALL'S DESIGNATED ROOFING CONTRACTOR. AT TENANT'S EXPENSE. COORDINATE ALL WORK WITH PROPERTY MANAGEMENT ON-SITE.
- TENANT MUST REMOVE ALL ABANDONED ROOF TOP AND/OR MECHANICAL EQUIPMENT ABOVE THE LEASED PREMISES AND WITHIN THE LEASED PREMISES, AT TENANT EXPENSE. PATCH AND REPAIR ROOF AS NEEDED.
- TENANT'S GC TO LABEL ALL ROOF TOP EQUIPMENT WITH TENANT NAME SPACE NUMBER AND EQUIPMENT IDENTIFICATION (RTU-1, EF-1), PER MALL SPECIFICATIONS/ STANDARDS.
- ALL PIPING ON ROOF SHALL BE SUPPORTED ON PRE-MANUFACTURED PIPE SUPPORTS INSTALLED ON GARRY TREAD, SPACED PROPERLY TO SUPPORT PIPING. TREATED WOOD SUPPORTS ARE NOT PERMITTED.
- ALL UNEXPOSED SUPPLY AIR AND OUTSIDE AIR DUCTWORK SHALL BE EXTERNALLY INSULATED WITH 1 1/2" THICK FOIL FACE INSULATION. INTERNALLY LINED DUCTWORK MAY BE USED FOR ACOUSTIC PURPOSES ONLY, NOT AS A SUBSTITUTE FOR EXTERNAL INSULATION.
- ALL DUCTWORK SHALL BE SHEET METAL. FLEX DUCT MAY ONLY USED IN RUNS OF 5'-0" OR LESS.
- AT CONCLUSION OF PROJECT, HVAC SYSTEM MUST BE TESTED AND BALANCED BY A LICENSED CONTRACTOR. COPY OF A BALANCE REPORT MUST BE PROVIDED TO PROPERTY MANAGEMENT OFFICE ON-SITE.
- LANDLORD STRONGLY PREFERS USE ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.

LANDLORD ROOF TOP EQUIPMENT COMMENTS:

- ROOF EQUIPMENT, INCLUDING BUT NOT LIMITED TO HVAC EQUIPMENT, KITCHEN EQUIPMENT, DUCTS, AND PIPING SHALL BE SHOWN ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. SHALL NOT BE VISIBLE FROM THE OUTER RING ROAD OR FROM MALL SKYLIGHTS. LOCATED WITHIN THE ROOF AREA OF THE PREMISES AND MINIMUM OF 5'-0" FROM THE VERTICAL PLANE OF ANY DEMISING PARTITION LOCATED, AND SHALL BE COORDINATE WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK. EQUIPMENT SCREENS OR SCREEN WALLS MAYBE REQUIRED AND SHALL BE APPROVED IN WRITING BY LANDLORD UNDER SEPARATE COVER.
- TENANT SHALL PROVIDE A STRUCTURAL ENGINEER EVALUATION OF THE EXISTING CONSTRUCTION / STRUCTURE AND DETERMINES THAT IT IS SUFFICIENT FOR THE ADDITIONAL LOADS OF ALL NEW ROOF TOP EQUIPMENT IN ACCORDANCE WITH THE BUILDING CODE THAT HAS BEEN ADOPTED BY THE AUTHORITIES HAVING JURISDICTION (AHJ) AT TENANT'S SOLE EXPENSE. STRUCTURAL DETAILS ARE TO INCLUDE REFERENCE OF APPLICABLE BUILDING CODE(S), EXISTING BUILDING LOADS, AND ADDITIONAL LOADS THAT WILL BE ADDED TO THE STRUCTURE AN ANY REINFORCING THAT IS REQUIRED. STRUCTURAL DETAILS ARE TO BE SIGNED, SEALED, AND SUBMIT TO THE LANDLORD FOR THEIR RECORDS BY A LICENSED STRUCTURAL ENGINEER WITH LEGALLY ACTIVE REGISTRATION IN THE STATE IN WHICH THE PROJECT IS LOCATED. LANDLORD RESERVE THE RIGHT TO HAVE A 3RD PARTY ENGINEER PROVIDE DOCUMENTATION BY A 3RD PARTY INSPECTOR TO VERIFY THAT STRUCTURAL INSTALLATION HAS BEEN INSTALLED CORRECTLY.
- ROOF EQUIPMENT REQUIRING DECK PENETRATION SHALL BE SET ON THE FACTORY SUPPLIED CURB AND MUST EXTEND A MINIMUM OF 12" ABOVE HIGHEST ROOF MATERIAL. RE-USE OF EXISTING CURBS OR THE USE OF CURB ADAPTERS IS STRICTLY PROHIBITED. TENANT SHALL RE-SLOPE ROOF TO MAIN PROPER DRAINAGE AND PROVIDE ROOFING, FLASHING, AND WATERPROOFING FOR INSTALLATION OF NEW CURB PER LANDLORD'S CRITERIA TENANT'S SOLE EXPENSE.
- ALL CONDENSATION, ELECTRICAL AND DUCTWORK SHALL BE SET INSIDE THE PERIMETER OF CURB. CONDENSATE SHALL DRAIN INTO AN INTERIOR FLOOR DRAIN OR MOP SINK WITHIN THE PREMISES. DRYLIGHTING CONDENSATE LINES DIRECTLY ONTO THE ROOF, DOWNSPOUT OR ROOF DRAIN IS STRICTLY PROHIBITED.
- TENANT SHALL PROVIDE 'ROOF TRAFFIC / WALKWAY PADS' AROUND ALL ROOF TOP EQUIPMENT AND SHALL INDICATE LOCATION OF PADS ON A ROOF PLAN TO BE INCLUDED IN TENANT'S DRAWINGS SUBMISSION. COORDINATE FINAL LOCATION, MATERIAL, AND INSTALLATION OF PADS WITH THE MALL OPERATIONS TEAM PRIOR TO THE START OF ANY WORK.
- TENANT SHALL LABEL ALL ROOF TOP EQUIPMENT INDICATING: TENANT NAME, SPACE NUMBER, AND EQUIPMENT IDENTIFICATION (RTU-1, EFT-1) PER LANDLORD'S DESIGN CRITERIA.
- EQUIPMENT THAT UTILIZES CONDENSER COILS SHALL BE EQUIPPED WITH HALL GUARDS.
- LANDLORD STRONGLY PREFERS USE OF ENERGY STAR PRODUCTS AND/OR EQUIPMENT WHENEVER POSSIBLE DURING TENANT BUILD OUT, WHICH CAN REDUCE ENERGY CONSUMPTION.



STORE NO:
NC #1645

SHAKE SHACK
 CHARLOTTE
 5604 NEW MARKET BLVD, SUITE 190
 CHARLOTTE, NC 28220


REVISION	
DATE	DESCRIPTION
09.11.24	PERMIT SET
11.05.24	REVISION C
12.02.24	REVISION D / IFC SET

STATUS:
IFC SET

SHEET NAME:
MECHANICAL ENERGY CODE COMPLIANCE

DATE: 09/11/24 PROJECT NO: 39018
 DRAWN: HEI SCALE: AS NOTED

SHEET NO:
M631



HANGING ANGLE DETAILS

HOOD STYLE / MODEL	450 DEGREES cfm/ft.	600 DEGREES cfm/ft.	700 DEGREES cfm/ft.
CANOPY ND-2	150	200	250
CANOPY ND-2 W/ END PANELS	105	140	175
SLOPED SNO-2	228	294	-
ISLAND ND-2WI	269	300	350
ISLAND ND-2I	346	422	475

ETL HOOD LISTING DETAIL

EXHAUST CFM = LENGTH OF HOOD X CFM/INCH (0.040)
 SUPPLY CFM = EXHAUST CFM X PERCENTAGE REQUIRED
 TOTAL DUCT AREA (sq. in.) = 144 X CFM
 DUCT LENGTH = TOTAL DUCT AREA

DUCT WIDTH
 CAPTIVEAIRE VENTILATOR DUCT SIZES ARE CALCULATED USING AN EXHAUST VELOCITY OF 1500-1800 FPM AND A SUPPLY VELOCITY OF 1000 FPM

CALCULATIONS UTILIZED

CAPTIVE-AIRE HOODS BUILT IN COMPLIANCE WITH:

ETL File number: 3054804-001/002

BUILDING CODES



CAPTIVE-AIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:

MATERIAL	CLEARANCE REDUCTION SYSTEM
NON-COMBUSTIBLE	NONE REQUIRED
LIMITED-COMBUSTIBLE	3" UNINSULATED STANDOFF
COMBUSTIBLE	1" INSULATED STANDOFF

- CLEARANCE TO COMBUSTIBLES**
- INSTALLATION**
- ALL ELECTRICAL "TIE-UP" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
 - ALL PLUMBING "TIE-UP" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
 - HANGING BRACKET LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
 - ALL CONNECTIONS FROM CAPTIVEAIRE HOOD PER MECHANICAL CONTRACTOR'S PLANS.
 - COOKING EQUIPMENT TO SHUT OFF IN EVENT OF FIRE.
 - EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
 - ALL LIGHT FIXTURES SHOWN INSTALLED BY CAPTIVEAIRE ARE FACTORY PREWIRED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES ARE BY ELECTRICAL CONTRACTOR.
 - LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
 - SEMI-RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
 - INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA. CONTRACTORS MUST VERIFY ALL DIMENSIONS FOR ACCURACY. INTEGRATION AND ADMINISTRATION OF CODE REQUIREMENTS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.

- BALANCE**
- KITCHEN HOOD MUST BE BALANCED WITH KITCHEN.
 - KITCHEN SHALL BE NEGATIVE WITH RESPECT TO STREET AIR.
 - RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.
- ADDITIONAL**
- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
 - SHOWN AND "APPROVED" COPIES OF THIS DOCUMENT TO BE SUBMITTED TO THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

GENERAL NOTES



FILTER DETAIL

FOR QUESTIONS, CALL THE
 Eastern PA Mechanical
 REGION 108
 PHONE: (267) 504 - 4126
 EMAIL: reg108@captiveaire.com

HOOD INFORMATION - JOB#6947037





HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST PLENUM RISER(S)				HOOD CONSTRUCTION	HOOD CONFIG			
										WIDTH	LENG	HEIGHT	DIA		CFM	VEL	SP	END TO END
1	Hood (Fryer)	S430 ND-2	CAPTIVEAIRE	4' 0"	600 DEG	I	HEAVY	175	700	8"	8"	4"	700	1575	-0.375"	430 SS WHERE EXPOSED	ALONE	ALONE
2	Hood (Grill)	S430 ND-2	CAPTIVEAIRE	5' 0"	450 DEG	I	MEDIUM	150	750	9"	8"	4"	750	1500	-0.330"	430 SS WHERE EXPOSED	ALONE	ALONE

HOOD INFORMATION

HOOD NO	TAG	TYPE	QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE	UTILITY CABINET(S)		ELECTRICAL	SWITCHES	FIRE SYSTEM PIPING	HOOD HANGING WEIGHT
												FIRE SYSTEM	SIZE				
1	Hood (Fryer)	CAPTRATE SLOD FILTER	2	20"	20"	85% SEE FILTER SPEC	1	RECESSED ROUND	NO	LEFT	12"x54"x30"	TANK FS	4.0/4.0	SC-320110MA	1 LIGHT 1 FAN	YES	621 LBS
2	Hood (Grill)	CAPTRATE SLOD FILTER	3	20"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO							YES	441 LBS

HOOD OPTIONS

HOOD NO	TAG	OPTION
1	Hood (Fryer)	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT. RIGHT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. LEFT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. INSULATION FOR BACK OF HOOD. RISER SENSOR INSTALL 6IN PLEN.
2	Hood (Grill)	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT. INSULATION FOR BACK OF HOOD. RISER SENSOR INSTALL 6IN PLEN. LEFT VERTICAL END PANEL 27" TOP WIDTH, 21" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS. GFCI DUPLEX OUTLET, 20A 125V - HOOD FRONT LEFT - HORIZONTAL - DIST FROM END: 3.50 DIST FROM BOTTOM: 4.00. RIGHT WIDE VERTICAL END PANEL 42" TOP WIDTH, 36" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS.



REVISIONS

NO	DESCRIPTION	DATE

CAPTIVEAIRE
 Eastern PA Mechanical
 www.captiveaire.com
 225 E City Line Avenue, Suite #103, Baller Cymwyd, PA, 19004 PHONE: (267) 504 - 4126 EMAIL: reg108@captiveaire.com

Shake Shack-XXXX- Premium Outlets, NCKitchen
 CHARLOTTE, NC, 28278

DATE: 7/31/2024
DWG.#: 6947037
DRAWN BY: Joe.shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING

SHEET NO.
 1

STORE NO:
NC #1645

SHAKE SHACK
 CHARLOTTE, NC, SUITE 190
 5604 NEW MARKET BLVD
 CHARLOTTE, NC 28227

REVISION

NO	DATE	DESCRIPTION
A	09.11.24	PERMIT SET
D	12.02.24	REVISION D / IFC SET

STATUS:
 IFC SET

FOR REFERENCE ONLY

SHEET NAME:
 CAPTIVEAIRE DRAWINGS

DATE: 09/11/24 **PROJECT NO:** 39018
DRAWN: HEI **SCALE:** AS NOTED

SHEET NO.:
M701

NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

FIRE SYSTEM INFORMATION - JOB#6947037

FIRE SYSTEM NO	TAG	TYPE	SIZE	MAX FP	DESIGN FP	INSTALLATION	
						SYSTEM	LOCATION ON HOOD
1		TANK FS	4.0/4.0	40	36	FIRE CABINET LEFT	LEFT, HOOD 1

CAS VALVE(S)

FIRE SYSTEM NO	TAG	TYPE	SIZE	SUPPLIED BY
1		SC ELECTRICAL	1.000	CAPTIVEAIRE SYSTEMS

NOTES

- FIELD PIPE DROPS AS SHOWN
- PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
- FIELD INSTALLED DROP: FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
- SHIP LOOSE DROP: FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
- RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVING, SALAMANDERS, ETC.
- OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
- IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
- FACTORY PIPING EXTENDS A MAXIMUM OF 6' ABOVE THE TOP OF THE HOOD.

- APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.
- THIS FIRE SYSTEM COMPLIES WITH U.L. 300 REQUIREMENTS.
- DL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS

JOB #: 6947037.
 JOB NAME: SHAKE SHACK-XXXX- PREMIUM OUTLETS, NC.
 SYSTEM SIZE: TANK-SP-2 DESIGN FP: 36, MAXIMUM FP: 40.
 HOOD # 1 4' 0.00' LONG x 54" WIDE x 30" HIGH.
 RISER # 1 SIZE: 8" x 8".
 HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.
 HOOD # 2 5' 0.00' LONG x 54" WIDE x 30" HIGH.
 RISER # 1 SIZE: 9" x 8".
 HOOD # 2 METAL BLOW-OFF CAPS INCLUDED.


- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
 - MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

AGENT DISTRIBUTION PIPING LIMITATIONS	
PIPE SECTION	MAX PIPE LENGTH (FT)
MAX SUPPLY LINE TO FIRST OVERLAPPING NOZZLE	42
OVERLAPPING NOZZLE APPLIANCE BRANCH	10
DEDICATED NOZZLE APPLIANCE BRANCH	10

LEGEND - FIRE CABINET TANK SYSTEM


- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.

- SYSTEM REQUIRES A MINIMUM OF 7 FT OF EQUIVALENT PIPE LENGTH BETWEEN TANK AND NEAREST APPLIANCE NOZZLE FOR MOST APPLIANCES. EACH 90 DEGREE ELBOW ADDS 13 FT OF EQUIVALENT LENGTH. SEE MANUAL FOR DETAILS



REVISIONS

DESCRIPTION	DATE



CAPTIVEAIRE
 Eastern PA Mechanical
 225 E City Line Avenue, Suite #103, Ball's Bluff, PA 19004
 PHONE: (267) 504-4126
 EMAIL: reg103@captiveaire.com
 www.captiveaire.com

Shake Shack-XXXX- Premium Outlets, NC(Kitchen)
 CHARLOTTE, NC, 28278

DATE: 7/31/2024

DWG.#: 6947037


DRAWN BY: Joe Shilba

SCALE: 3/4" = 1'-0"

MASTER DRAWING

SHEET NO. 3


STORE NO: NC #1645



REVISION

DATE	DESCRIPTION
09.11.24	PERMIT SET
12.02.24	REVISION D / IFC SET

STATUS: IFC SET



SHEET NAME: CAPTIVEAIRE DRAWINGS

DATE: 09/11/24 PROJECT NO: 39018


DRAWN: HEI SCALE: AS NOTED

SHEET NO: M703

NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

ELECTRICAL PACKAGE - JOB#6947037





NO	TAG	PACKAGE #	LOCATION	SWITCHES		OPTION	FANS CONTROLLED					
				LOCATION	QUANTITY		FAN TAG	TYPE	HP	VOLTS	FLA	
1		SC-320110MA	UTILITY CABINET LEFT	UTILITY CABINET LEFT HOOD # 1	1 LIGHT 1 FAN	SMART CONTROLS THERMOSTATIC CONTROL W/ RELAY ON/OFF WITH SUPPLY	KEF(FRYER)	EXHAUST	1	0500	208	3.8



CASlink Monitor and Control
 - Broad control panel to support communications to cloud-based Building Management System.
 - Broad Control Panel to allow cloud-based Building Management System to monitor real time parameters outlined as MONITOR in the points list.
 - Broad Control Panel to allow cloud-based Building Management System to control parameters outlined as CONTROL in the points list.
 - Broad Control Panel to allow cloud-based Building Management System to implement SYSTEM OPTIMIZER control strategies for fully integrated Building Management.

MONITORING AND CONTROL POINTS LIST

DC Packages	Function	DC Packages	Function
Room Temperature	MONITOR	Room Temperature	MONITOR
Duct Temperature(s)	MONITOR	Duct Temperature(s)	MONITOR
WALL Discharge Temperature	MONITOR	WALL Discharge Temperature	MONITOR
Return Air Discharge Temperature	MONITOR	Return Air Discharge Temperature	MONITOR
Fan Speed	MONITOR	Control Panel	MONITOR & CONTROL
Fan Amperage	MONITOR	Fan Status	MONITOR
Fan Power	MONITOR	FCU Status	MONITOR
FCU Status	MONITOR	FCU Filter Change Percentage	MONITOR
Control Panel	MONITOR	Fan Condition	MONITOR & CONTROL
Fan Status	MONITOR	CO2 Pre System	MONITOR
FCU Status	MONITOR	Building Pressure	MONITOR
FCU Filter Change Percentage	MONITOR	Fan Status	MONITOR & CONTROL
Fan Condition	MONITOR	Light Status	MONITOR & CONTROL
CO2 Pre System	MONITOR	Room Temp	MONITOR & CONTROL
Building Pressure	MONITOR	Light Status	MONITOR & CONTROL
Prep Panel Status	MONITOR & CONTROL	Room Temp	MONITOR & CONTROL
Fan Status	MONITOR & CONTROL		



REVISIONS

NO	DESCRIPTION	DATE

CAPTIVE
 Eastern PA Mechanical
 225 E City Line Avenue, Suite # 103, Bala Cynwyd, PA 19004 PHONE: (267) 904-4126 EMAIL: reg.06@caprive.com

Shake Shack-XXXX- Premium Outlets, NC(Kitchen)
 CHARLOTTE, NC, 28278

DATE: 7/31/2024
 DWG.#: 6947037
 DRAWN BY: joe.shiiba
 SCALE: 3/4" = 1'-0"
 MASTER DRAWING

SHEET NO. 5

STORE NO: NC #1645



REVISION

NO	DATE	DESCRIPTION
A	09/11/24	PERMIT SET
D	12.02.24	REVISION D / IFC SET

STATUS: IFC SET

FOR REFERENCE ONLY



SHEET NAME: CAPTIVEAIR DRAWINGS

DATE: 09/11/24 PROJECT NO: 39018

DRAWN: HEI SCALE: AS NOTED

SHEET NO: M705


NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.



Instructions below outline single, or dual, one gallon grease cup installation for ND-2 hood models.


The one gallon grease cup comes as an assembly of stainless steel wall mounting bracket and one gallon cup. The mounting bracket should be installed 2" from the edge of the containment plenum and 3"-4" below the bottom of the hood.

Piping from the hood grease drain should route to the opening of the grease cup, but not into the cup, otherwise the cup will not be able to be removed and emptied.




* Mounting hardware not included
 **Must be mounted to stud or wall anchor

Left & Right hand Grease Cup Install



Support the bottom of the drain pipe using 1.5" adjustable pipe support. Do not allow drain pipe to drop into the grease cup, otherwise cup will catch when removing and cleaning the grease cup.

Gallon Grease Cup Assembly



1 GALLON GREASE COLLECTION BOX AND WALL MOUNTING BRACKET SHIPPED LOOSE FOR FIELD INSTALLATION BY MECHANICAL CONTRACTOR.

REVISIONS	
DESCRIPTION	DATE

CAPTIVE
 Eastern PA Mechanical
 225 E City Line Avenue, Suite #103, Balla Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg.108@captiveaire.com
 www.captiveaire.com

Shake Shack-XXXX- Premium Outlets, NC(Kitchen)
 CHARLOTTE, NC, 28278

DATE: 7/31/2024
 DWG.#: 6947037
 DRAWN BY: Joe.shilba
 SCALE: 3/4" = 1'-0"
 MASTER DRAWING

SHEET NO. 6

STORE NO: NC #1645

SHAKE SHACK
 CHARLOTTE, NC, SUITE 190
 564 NEW MARKET
 CHARLOTTE, NC 28278

REVISION	
DATE	DESCRIPTION
09.11.24	PERMIT SET
12.02.24	REVISION D) IFC SET

STATUS: IFC SET

FOR REFERENCE ONLY

SHEET NAME: CAPTIVEAIRE DRAWINGS

DATE: 09/11/24 PROJECT NO: 39018

DRAWN: HEI SCALE: AS NOTED

SHEET NO: M706

NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

DOAS/RTU FAN SCHEDULE -- JOB#7016118

FAN UNIT NO	TAG	QTY	DOAS/RTU MODEL #	FAN INFORMATION				ELECTRICAL INFORMATION				COOLING INFORMATION				REHEAT INFORMATION		ELECTRIC HEAT INFORMATION				HEAT PUMP INFORMATION		NOTES																						
				MANUFACTURER	BLOWER	RETURN AIR CFM	MAX OUTSIDE AIR CFM	TOTAL CFM	WEIGHT (LBS)	ESP	HP	PHASE	VOLT	MCA	MDCP	OUTSIDE AIR DB	MIXED AIR WB	LEAVING AIR DB	WB	DP	TOTAL	SENS.	IEER		ISMRE	DISCHARGE DB	WB	DESIRED	MAX	MOISTURE REMOVAL RATE	ISSN KW'S	MAX KW'S	VOLTS	AMPS	TEMP RISE	ENTERING TEMP	MAX TEMP RISE	DISCHARGE TEMP	CDP							
1	RTU-1	1	CAS-HVAC2-E15E-18-10T	CAPTIVEAIRE	18MF-2-RTU	2700	900	3600	2051	1.000	5.00	3	208	81.4A	90A	94.2°F	74.6°F	79.8°F	65.9°F	52.8°F	52.6°F	52.5°F	143.6	MBH	105.7	MBH	18.6	4.3	70.0°F	61.0°F	68	MBH	96	MBH	33.5	LBS/HR	11	15	208	36.1	10 °F	58.0°F	21.0°F	79.0°F	3.4	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18,19
2	RTU-2	1	CAS-HVAC3-E30E-24-15T	CAPTIVEAIRE	24MF-3-RTU	4100	1200	5300	2665	0.800	7.50	3	208	103.8A	110A	94.2°F	76.0°F	79.4°F	65.5°F	52.4°F	52.2°F	52.1°F	211.0	MBH	156.0	MBH	18.8	5.7	70.0°F	60.7°F	68	MBH	129.6	MBH	48.4	LBS/HR	22	30	208	72.2	14 °F	58.9°F	19.0°F	78.0°F	3.5	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18,19

NOTES:
 1. INVERTER SCROLL COMPRESSOR WITH INTEGRATED OIL SENSOR. DIGITAL OR STAGED SCROLL NOT AN APPROVED EQUAL.
 2. DIRECT DRIVE PLENUM BLOWERS. BELT DRIVEN BLOWERS ARE NOT ACCEPTABLE.
 3. INTEGRATED MONITORING VIA CELLULAR CONNECTION BY MANUFACTURER.
 4. REFRIGERATION PRESSURE MONITORING ON HIGH AND LOW PRESSURE SIDE OF SYSTEM INCLUDED THROUGH DIGITAL INTERFACE.
 5. EC MOTOR CONDENSING FANS.
 6. ELECTRONIC EXPANSION VALVE. TXV NOT ACCEPTABLE.
 7. SUCTION LINE ACCUMULATOR.
 8. FACTORY COMMISSIONING WITH 5 YEAR PARTS WARRANTY.
 9. AVERAGING INTAKE, EVAP AND DISCHARGE TEMPERATURE SENSORS (DISCHARGE SENSOR TO BE FACTORY MOUNTED WITHIN UNIT).
 10. 2" EXTERIOR DUAL-WALL CONSTRUCTION W/ R-13 INSULATION-MINIMUM 20GA EXTERIOR W/ 14GA BASE.
 11. SUPPLY CFM MONITORING INTEGRAL TO UNIT WITH CFM MEASUREMENT INCLUDED THROUGH DIGITAL INTERFACE.
 12. FULLY MODULATING HOT GAS REHEAT.
 13. 15 DEGREE LOW AMBIENT OPERATION.
 14. -20 DEGREE LOW AMBIENT OPERATION.
 15. HAIL GUARD FOR CONDENSING COIL.
 16. RTU ECONOMIZER WITH DIFFERENTIAL ENTHALPY CONTROL.
 17. BAROMETRIC RELIEF DAMPER.
 18. DOWN DISCHARGE/DOWN RETURN.
 19. SINGLE POINT POWER CONNECTION FOR UNIT & ELECTRIC HEATER.

FOR QUESTIONS, CALL THE
 Eastern PA Mechanical
 REGION 108
 PHONE: (667) 504 - 4126
 EMAIL: regi108@captiveaire.com

FAN OPTIONS




FAN UNIT NO	TAG	DESCRIPTION
1	RTU-1	TOTAL CFM MONITORING
1	RTU-1	INTAKE FIRESTAT SET TO 135°F
1	RTU-1	FREEZESTAT
1	RTU-1	DISCHARGE FIRESTAT SET TO 240°F
1	RTU-1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
1	RTU-1	2" MERV 13 FILTERS FOR RTU3 (QTY. 4)
1	RTU-1	2" MERV 8 FILTERS FOR RTU2 (QTY. 4)
1	RTU-1	OVERHEAT STAT
1	RTU-1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
1	RTU-1	RTU2 DOWN DISCHARGE ELECTRIC HEAT
1	RTU-1	EXTREME LOW AMBIENT HEAT PUMP - 10 TON MODULATING COOLING OPTION WITH HEAT PUMP, 208/230V, R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS. USED FOR HEATING CONDITIONS BELOW 40° DEGREES
1	RTU-1	EXTREME LOW AMBIENT COOLING OPERATION - DOWN TO -20° AMBIENT
1	RTU-1	LOW AMBIENT COOLING OPERATION - DOWN TO 0° AMBIENT
1	RTU-1	10 TON MODULATING REHEAT OPTION WITH HEAT PUMP - SPACE BEWPOINT CONTROL - R410A
1	RTU-1	120V FIRE INPUT
1	RTU-1	RTU2 CURB DUCT HANGER
1	RTU-1	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS
1	RTU-1	RTU ECONOMIZER - DIFFERENTIAL ENTHALPY CONTROL
1	RTU-1	RTU2 ECONOMIZER BAROMETRIC RELIEF
1	RTU-1	RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI
1	RTU-1	RTU2 HAIL GUARD
1	RTU-1	RTU2 DOWN RETURN
1	RTU-1	VAV PACKAGE W/ MANUAL/BDC CONTROL (S71 VFD INCLUDED)
1	RTU-1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI
1	RTU-1	RTU2 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX
1	RTU-1	OCCUPIED SCHEDULING
1	RTU-1	SINGLE POINT CONNECTION - ELECTRIC HEATER RTU, BLOWER & HEATER MUST BE THE SAME VOLTAGE & PHASE. 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #80, #47, #44, OR #25 PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE.
1	RTU-1	LOAD REACTOR MOUNTED IN FAN
1	RTU-1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT
1	RTU-1	EXTERIOR GAS CONNECTION PROVIDED BY FACTORY WITH QUICK SEAL AND ANTI-ROTATION BRACKET
1	RTU-1	TOTAL CFM MONITORING
1	RTU-1	INTAKE FIRESTAT SET TO 135°F
1	RTU-1	FREEZESTAT
1	RTU-1	DISCHARGE FIRESTAT SET TO 240°F
1	RTU-1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
1	RTU-1	2" MERV 13 FILTERS FOR RTU3 (QTY. 4)
1	RTU-1	2" MERV 8 FILTERS FOR RTU3 (QTY. 4)
1	RTU-1	OVERHEAT STAT
1	RTU-1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
1	RTU-1	RTU3 DOWN DISCHARGE ELECTRIC HEAT, 15-60KW
1	RTU-1	RTU3 CURB DUCT HANGER
1	RTU-1	RTU ECONOMIZER - DIFFERENTIAL ENTHALPY CONTROL
1	RTU-1	RTU3 ECONOMIZER BAROMETRIC RELIEF
1	RTU-1	RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI
1	RTU-1	RTU3 HAIL GUARD
1	RTU-1	ZIEHL POWERED EXHAUST FOR RTU3 - MANUAL CONTROL, 3000 CFM MAX AT 0"
1	RTU-1	RTU3 DOWN RETURN
1	RTU-1	VAV PACKAGE W/ MANUAL/BDC CONTROL (S71 VFD INCLUDED)
1	RTU-1	SINGLE POINT CONNECTION - ELECTRIC HEATER RTU, BLOWER & HEATER MUST BE THE SAME VOLTAGE & PHASE. 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #80, #47, #44, OR #25 PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE.
1	RTU-1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI
1	RTU-1	RTU3 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX
1	RTU-1	OCCUPIED SCHEDULING
1	RTU-1	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS
1	RTU-1	LOAD REACTOR MOUNTED IN FAN
1	RTU-1	EXTREME LOW AMBIENT HEAT PUMP - 15 TON MODULATING COOLING OPTION WITH HEAT PUMP, 208/230V, R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS. USED FOR HEATING CONDITIONS BELOW 40° DEGREES
1	RTU-1	EXTREME LOW AMBIENT COOLING OPERATION - DOWN TO -20° AMBIENT
1	RTU-1	LOW AMBIENT COOLING OPERATION - DOWN TO 0° AMBIENT
1	RTU-1	15 TON MODULATING REHEAT OPTION WITH HEAT PUMP - SPACE BEWPOINT CONTROL - R410A
1	RTU-1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT
1	RTU-1	EXTERIOR GAS CONNECTION PROVIDED BY FACTORY WITH QUICK SEAL AND ANTI-ROTATION BRACKET
2	RTU-2	TOTAL CFM MONITORING
2	RTU-2	INTAKE FIRESTAT SET TO 135°F
2	RTU-2	FREEZESTAT
2	RTU-2	DISCHARGE FIRESTAT SET TO 240°F
2	RTU-2	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
2	RTU-2	2" MERV 13 FILTERS FOR RTU3 (QTY. 4)
2	RTU-2	2" MERV 8 FILTERS FOR RTU3 (QTY. 4)
2	RTU-2	OVERHEAT STAT
2	RTU-2	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
2	RTU-2	RTU3 DOWN DISCHARGE ELECTRIC HEAT, 15-60KW
2	RTU-2	RTU3 CURB DUCT HANGER
2	RTU-2	RTU ECONOMIZER - DIFFERENTIAL ENTHALPY CONTROL
2	RTU-2	RTU3 ECONOMIZER BAROMETRIC RELIEF
2	RTU-2	RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI
2	RTU-2	RTU3 HAIL GUARD
2	RTU-2	ZIEHL POWERED EXHAUST FOR RTU3 - MANUAL CONTROL, 3000 CFM MAX AT 0"
2	RTU-2	RTU3 DOWN RETURN
2	RTU-2	VAV PACKAGE W/ MANUAL/BDC CONTROL (S71 VFD INCLUDED)
2	RTU-2	SINGLE POINT CONNECTION - ELECTRIC HEATER RTU, BLOWER & HEATER MUST BE THE SAME VOLTAGE & PHASE. 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #80, #47, #44, OR #25 PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE.
2	RTU-2	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI
2	RTU-2	RTU3 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX
2	RTU-2	OCCUPIED SCHEDULING
2	RTU-2	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS
2	RTU-2	LOAD REACTOR MOUNTED IN FAN
2	RTU-2	EXTREME LOW AMBIENT HEAT PUMP - 15 TON MODULATING COOLING OPTION WITH HEAT PUMP, 208/230V, R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS. USED FOR HEATING CONDITIONS BELOW 40° DEGREES
2	RTU-2	EXTREME LOW AMBIENT COOLING OPERATION - DOWN TO -20° AMBIENT
2	RTU-2	LOW AMBIENT COOLING OPERATION - DOWN TO 0° AMBIENT
2	RTU-2	15 TON MODULATING REHEAT OPTION WITH HEAT PUMP - SPACE BEWPOINT CONTROL - R410A
2	RTU-2	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT
2	RTU-2	EXTERIOR GAS CONNECTION PROVIDED BY FACTORY WITH QUICK SEAL AND ANTI-ROTATION BRACKET

CURB ASSEMBLIES

NO	DN FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	RTU-1	90 LBS	CURB	49.500"W X 75.000"L X 14.000"H INSULATED.
2	# 2	RTU-2	104 LBS	CURB	59.500"W X 91.000"L X 14.000"H INSULATED.

HMI SCHEDULE

UNIT NUMBER	HMI #	HMI LOCATION	TEMP AVERAGING	MODBUS ADDRESS
FAN #1	HMI #1 - UNIT	IN UNIT	NOT AVERAGED	55
FAN #1	HMI #2 - SPACE	SPACE	AVERAGED	56
FAN #2	HMI #1 - UNIT	IN UNIT	NOT AVERAGED	55
FAN #2	HMI #2 - SPACE	SPACE	AVERAGED	56



REVISIONS

DESCRIPTION	DATE

CAPTIVEAIRE
 Eastern PA Mechanical
 www.captiveaire.com
 225 E City Line Avenue, Suite #103, Balla Cynnydd, PA 19004 PHONE: (267) 504 - 4126 EMAIL: regi108@captiveaire.com

Shake Shack-XXXX- Premium Ductlets, NCHVAD-RC
 CHARLOTTE, NC, 28278

DATE: 8/30/2024
 DWG.#: 7016118
 DRAWN BY: joe.shilba
 SCALE: 1/2" = 1'-0"
 MASTER DRAWING
 SHEET NO. 1

STORE NO: NC #1645

SHAKE SHACK
 CHARLOTTE, NC SUITE 190
 5604 NEW MARKET RD
 CHARLOTTE, NC 28226

REVISION

DATE	DESCRIPTION
09.11.24	PERMIT SET
12.02.24	REVISION D / IFC SET

STATUS: IFC SET




FOR REFERENCE ONLY

SHEET NAME: CAPTIVEAIRE DRAWINGS

DATE: 09/11/24 PROJECT NO: 39018
 DRAWN: HEI SCALE: AS NOTED

SHEET NO: M707

NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.



FAN #2 CAS-HVAC3-E.302-24MF-15T - HEATER (RTU-2)

- NOTES:**
- DO NOT OBTURCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
 - DENOTES CORNER WEIGHT.
 - ROOF OPENING MUST BE 2" SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.
 - CONNECTION FROM BREAKER TO UNITS SAFETY DISCONNECT SWITCH TO BE COPPER WIRE ONLY.
 - EXTERIOR GAS CONNECTION PROVIDED BY FACTORY WITH QUICK SEAL AND ANTI-ROTATION BRACKET.

REVISIONS

REVISION	DESCRIPTION	DATE
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		

STORE NO: NC #1645

SHAKE SHACK
 CHARLOTTE, NC, SUITE 190
 564 NEW MARKET CHARLOTTE, NC 28278

CAPTIVEAIRE
 Eastern PA Mechanical
 225 E City Line Avenue, Suite #103, Balla Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg109@captveaire.com

Smoke Shack-XXX- Premium Outlets, NCHVAC-R2
 CHARLOTTE, NC, 28278

DATE: 8/30/2024
DWG.#: 7016118
DRAWN BY: Joe.shiloo
SCALE: 1/2" = 1'-0"
MASTER DRAWING

SHEET NO.
 3

REVISION

DATE	DESCRIPTION
09.11.24	PERMIT SET
12.02.24	REVISION D / IFC SET

STATUS: IFC SET

FOR REFERENCE ONLY

SHEET NAME: CAPTIVEAIRE DRAWINGS

DATE: 09/11/24 **PROJECT NO:** 39018
DRAWN: HEI **SCALE:** AS NOTED

SHEET NO: M709

NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.