 Comfort. Under control.		1126 SWIFT ST.	
		NORTH KANSAS CITY, MO 64116	
		will@nationaltab.com	
		P# (855)682-6822 / DIRECT# 513-889-8927	
COMPANY:	European Wax Center (EWC)	JOB NAME:	European Wax Center (EWC)
	5830 Granite Pkwy Plano, TX 75024	LOCATION:	3485 Del Mar Heights RD., STE A4 San Diego, CA 92130
EMAIL:	Rico.Andrews@myewc.com		
ATTN:	Rico Andrews	BID DATE:	January 28, 2022

Thank you for allowing National TAB the opportunity to be your Indoor Air Quality partner. The following is our understanding of the scope of work and the associated cost.

National TAB will provide and install RGF's PHI (Photohydroionization® technology) air purification systems. This technology provides active sanitation in the occupied space and reduces viruses, bacteria, and more up to 99% in the air and on surfaces. National TAB will also be your advocate on site to ensure a high level of indoor air quality via industry leading test and balance services. We are European Wax Center's HVAC field experts to ensure Comfort. Under Control.

See [www.nationaltab.com](http://www.nationaltab.com) for more information

## PRODUCT

- PHI-PKG-14 Air Purifier
  - Installed inside blower compartment for the RTU
- Additional parts included: 24V transformer and split loom to protect wiring from UV light
- Freight included

## SERVICES

### INSTALLATION

- Installation of (1) PHI-PKG-14 Air Purifier inside (1) RTU.
- Includes checklist and pictures of the installation.

### PLAN REVIEW

- Purpose is to ensure success for the entire team and a smoother construction process and turnover.
- In depth review of construction documents to ensure that the requirements are aligned, and design intent is being met.
- Alert construction team, client, and engineer to any possible discrepancies so that they can be resolved prior to construction.
- Provide report with findings.

### TEST, ADJUST, AND BALANCE (TAB)

- Qty (1) RTU
- Zone X System
  - Approx. (3) Zone Dampers
  - Bypass damper
- EFs
- Associated air devices
- Field Installation Verification checks tailored for EWC
- Ensure that thermostats and Zone X controller are programmed.
- HVAC balance schedule of flows as compared to design tolerances
- NEBB Certified TAB report with Remarks, executive summary, pictures, checklists, asset pages, and schematics.
- FaciliBuild HUB used as communication and issue tracking platform. Free login available for client

**Product Subtotal = \$546.38**  
**Services Subtotal = \$2198.89**


**TOTAL PRICE = \$2745.27**

\*Add \$995 for each additional RTU to include additional product and service.  
\*\*Tax not included.

Any parts (other than those listed above) if required will be additional. However, no parts will be provided without initial approval unless National TAB, LLC has agreed with the client for a set fee to perform specific task. Lift rental to be additional if required if not provided by owner or GC. Work to be performed 1<sup>st</sup> shift only.

**Not included in price:** Sheave or belt replacement, DALT, Sound and Vibration testing, Indoor Air Quality testing, or Pre-testing unless price is specified separately above.

WE HEREBY PROPOSE to furnish labor complete in accordance with NATIONAL TAB specifications, for the sum of: **\$2745.27** US Dollars. Payment to be made as follows: **Terms as specified by our accounting department.**

<p><b>Acceptance of proposal</b> - The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made in accordance to terms agreed upon.</p> <p><b>Client Signature:</b> </p> <p><b>Client Date of Acceptance:</b> <u>3/10/22</u></p>	<p><b>Authorized Signature for NT:</b></p> <p><u>William Turnbough</u> <u>VP National Markets</u></p> <p><b>Date:</b> <u>January 28, 2022</u></p>
--	---