



| SHEET NUMBER | SHEET NAME |
|--------------|---|
| M001 | MECHANICAL ABBREVIATIONS & SYMBOLS |
| M101 | MECHANICAL FLOOR PLAN |
| M102 | MECHANICAL REFRIGERATION PIPING AND LAYOUT PLAN |
| M150 | MECHANICAL ROOF PLAN |
| M501 | MECHANICAL DETAILS |
| M502 | MECHANICAL DETAILS |
| M590 | MECHANICAL SPECIFICATIONS |
| M591 | MECHANICAL SPECIFICATIONS |
| M592 | MECHANICAL SPECIFICATIONS |
| M601 | MECHANICAL SCHEDULES |
| M701 | CAPTIVEAIRE DRAWINGS |
| M702 | CAPTIVEAIRE DRAWINGS |
| M703 | CAPTIVEAIRE DRAWINGS |
| M704 | CAPTIVEAIRE DRAWINGS |
| M705 | CAPTIVEAIRE DRAWINGS |
| M706 | CAPTIVEAIRE DRAWINGS |
| M707 | CAPTIVEAIRE DRAWINGS |
| M708 | CAPTIVEAIRE DRAWINGS |
| M709 | CAPTIVEAIRE DRAWINGS |

| RESPONSIBILITY MATRIX | | | | | | | |
|--|--------------------|-------|----------|--------------------|-------|----------|---|
| DESCRIPTION | FURNISHED | | | INSTALLED | | | REMARKS |
| | GENERAL CONTRACTOR | OWNER | LANDLORD | GENERAL CONTRACTOR | OWNER | LANDLORD | |
| DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING | | | | | | | |
| 23.1 HVAC DUCTWORK AND PIPING IDENTIFICATION | | | | | | | |
| 23.1.1 HVAC DUCTWORK SYSTEM IDENTIFICATION | X | | | X | | | |
| 23.1.2 PIPING SYSTEM IDENTIFICATION | X | | | X | | | |
| 23.1.3 UTILITY SHUT OFF IDENTIFICATION IN KITCHEN | X | | | X | | | |
| 23.1.4 VALVE TAGS AND CHART | X | | | X | | | |
| 23.1.5 HVAC DAMPER IDENTIFICATION | X | | | X | | | |
| 23.2 ROOF CURBS | | | | | | | |
| 23.2.1 EXHAUST FAN CURBS | X | | | X | | | GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES |
| 23.2.2 ROOFTOP UNIT CURBS | X | | | X | | | GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES |
| 23.2.3 CONDENSING UNIT CURBS | X | | | X | | | GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES |
| 23.2.4 MAKE UP AIR AND DOAS UNIT CURBS | X | | | X | | | GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES |
| 23.2.5 KITCHEN EXHAUST FAN CURBS | X | | | X | | | GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES |
| 23.3 HVAC DUCTWORK SYSTEM COMPONENTS | | | | | | | |
| 23.3.1 HVAC DUCTWORK | X | | | X | | | |
| 23.3.2 INSULATION AND FIRE WRAP | X | | | X | | | GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE TENANT FIT OUT FROM LANDLORD POINT OF CONNECTION |
| 23.3.3 DAMPERS | X | | | X | | | |
| 23.3.4 SMOKE DETECTORS | X | | | X | | | |
| 23.3.5 SUPPLY, RETURN, AND EXHAUST GRILLS AND REGISTERS | X | | | X | | | |
| 23.4 MECHANICAL PIPING SYSTEM COMPONENTS | | | | | | | |
| 23.4.1 WALK-IN COOLER AND FREEZER REFRIGERATION | | X | | | X | | WALK-IN COOLER AND FREEZER SUPPLIED BY VENDOR NO. 103 GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE PIPING INSTALLATION AND FINAL CONNECTION |
| 23.4.2 REFRIGERATION FOR OTHER HVAC EQUIPMENT | | X | | | X | | |
| 23.4.3 CHILLED WATER | | | NA | | | NA | |
| 23.4.4 CONDENSER WATER | | | NA | | | NA | |
| 23.4.5 HEATING HOT WATER | | | NA | | | NA | |
| 23.4.6 VALVES AND ACCESSORIES (E.G. AIR VENTS) | X | | | X | | | |
| 23.5 HVAC EQUIPMENT | | | | | | | |
| 23.5.1 SUPPLY FAN | X | | | X | | | |
| 23.5.2 TOILET EXHAUST FAN | X | | | X | | | |
| 23.5.3 KITCHEN EXHAUST FAN | X | X | | X | | | SUPPLIED BY VENDOR NO. 102 |
| 23.5.4 DUCTED AND NON-DUCTED HEATING AND COOLING UNITS | X | | | X | | | |
| 23.5.5 MAKE UP AIR AND DOAS UNITS | X | | | X | | | SUPPLIED BY VENDOR NO. 102 |
| 23.5.6 ELECTRIC PATIO HEATERS | X | | | X | | | |
| 23.5.7 HVAC CONDENSING UNITS | X | | | X | | | |
| 23.5.8 REFRIGERATION CONDENSING UNITS | X | X | | X | | | |
| 23.5.9 RGF PHI SYSTEM | X | | | X | | | GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 7 VENDOR SUBSTITUTION IS NOT PERMITTED |
| 23.6 KITCHEN EXHAUST WITH FIRE SUPPRESSION SYSTEM | | | | | | | |
| 23.6.1 HOOD CONTROL PANEL | | X | | X | | | SUPPLIED BY VENDOR NO. 102 |
| 23.6.2 KITCHEN EXHAUST HOOD | | X | | X | | | SUPPLIED BY VENDOR NO. 102 |
| 23.6.3 STRUCTURAL SUPPORT | X | | | X | | | |
| 23.6.4 ELECTRICAL AND CONTROL WIRING | X | | | X | | | |
| 23.6.5 ANSUL OR TANK FIRE SUPPRESSION SYSTEM | | X | | X | | | SUPPLIED BY VENDOR NO. 102 GENERAL CONTRACTOR TO COORDINATE AND FACILITATE SYSTEM SIGN-OFF |
| 23.6.6 ANSUL OR TANK WIRING AND UTILITIES CONNECTION | X | | | X | | | |
| 23.6.7 ANSUL OR TANK GAS VALVE | | X | | X | | | SUPPLIED BY VENDOR NO. 102 |
| 23.7 COMMISSIONING ACTIVITIES | | | | | | | |
| 23.7.1 GREASE EXHAUST WATER LEAKAGE TEST | X | | | X | | | GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 6 VENDOR SUBSTITUTION IS NOT PERMITTED |
| 23.7.2 TESTING AIR BALANCE (TAB) REPORT | X | | | X | | | GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 7 VENDOR SUBSTITUTION IS NOT PERMITTED |



New York • Miami • Omaha • Los Angeles • Seattle • Honolulu
800-581-0963 www.schnackel.com

Seal



Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.dp3architects.com

Project

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.

| SYMBOLS | | | |
|--|------------------------------------|--------|---------------------------------------|
| HEATING - VENTILATING - AIR CONDITIONING | | | |
| SYMBOL | DESCRIPTION | SYMBOL | DESCRIPTION |
| | STEAM (LOW PRESSURE) | | AUTOMATIC CONTROL VALVE |
| | STEAM (MEDIUM PRESSURE) | | PRESSURE REGULATING VALVE (PRV) |
| | STEAM (HIGH PRESSURE) | | SAFETY RELIEF VALVE |
| | CONDENSATE (LOW PRESSURE) | | BLOW OFF VALVE |
| | CONDENSATE (MEDIUM PRESSURE) | | T AND T TRAP (CAP. #/RR) |
| | CONDENSATE (HIGH PRESSURE) | | THERMOSTATIC TRAP |
| | ETHYLENE GLYCOL SUPPLY | | STATIC PRESSURE |
| | ETHYLENE GLYCOL RETURN | | CIRCUIT SETTER FLOW CONTROL VALVE |
| | CHILLED WATER SUPPLY | | AIR BLEEDER VALVE (RADIANT PANEL) |
| | CHILLED WATER RETURN | | AIR ELIMINATOR |
| | CONDENSATE (LOW PRESSURE) | | AUTOMATIC BALANCING VALVE |
| | CONDENSATE (MEDIUM PRESSURE) | | SOLENOID VALVE (REFRIGERANT) |
| | CONDENSATE (HIGH PRESSURE) | | THERMOSTATIC EXPANSION VALVE (REFR) |
| | HUMIDIFICATION LINE | | BACK PRESSURE VALVE |
| | FUEL OIL SUPPLY | | SIGHT GLASS |
| | FUEL OIL RETURN | | ROUND DUCT RISER |
| | FUEL OIL VENT | | FAN COIL UNIT AND MARK |
| | GAS LINE | | UNIT HEATER-PROPELLER TYPE & MARK |
| | REFRIGERANT LIQUID LINE | | CABINET UNIT HEATER & MARK |
| | REFRIGERANT SUCTION LINE | | FIN TUBE, MARK AND CAPACITY |
| | REFRIGERANT HOT GAS DISCHARGE LINE | | CONNECTOR AND MARK |
| | CONDENSER WATER | | UNIT VENTILATOR AND MARK |
| | CONDENSER WATER RETURN | | ELECTRICAL PANEL FIRST FLOOR IS SHOWN |
| | BOLDER BLOW OFF | | SOUND DUCT |
| | EXHAUST STEAM | | CANVAS CONNECTION |
| | CONCENTRIC REDUCER | | STRAINER |
| | ECCENTRIC REDUCER | | EXPANSION JOINT |
| | UNION | | THERMOMETER |
| | STRAINER | | PRESSURE GAGE |
| | EXPANSION JOINT | | EXHAUST FAN RISER NUMBER |
| | THERMOMETER | | TURNING VANE |
| | PRESSURE GAGE | | REMOTE SENSOR |
| | | | EXTRACTOR |
| | | | THERMOSTAT |

NOT ALL ITEMS SHOWN WITHIN THE SYMBOLS LEGENDS ARE USED WITHIN THE DRAWINGS.

| SUBMITTAL MATRIX | | | | | |
|--|--------------------------------------|------------------|---------------|--------------------------|---|
| GENERAL CONTRACTORS TO ALSO REVIEW ARCHITECTURAL SPECIFICATIONS AS NOTED IN PLANS IN PLAN SECTION 700 OF THE ARCHITECTURAL PACKAGE FOR REQUIRED SUBMITTALS THAT MIGHT NOT BE LISTED BELOW. | | | | | |
| SUBMITTAL DESCRIPTION | Required Review Time (Business Days) | Number of Record | Shop Drawings | Physical Sample Required | Submitted for Submittal for Record Only |
| Anchor Bolts Shops | 5 | X | | | X |
| ATAS-Detailed Shop DWGS(Submitted by Owner Vendor to Owner/AOR prior to const.) | 5 | X | | | X |
| Concrete Mix Design | 5 | X | | | X |
| Construction Prefunctional Checklists | 5 | X | | | X |
| Decorative Metal Shop Drawings | 5 | X | | | X |
| Diffusers, Grills & Registers | 5 | X | | | X |
| Doors, Frames & Hardware | 7 | X | | | X |
| Ductwork Layout (if there are significant changes in field) | 5 | X | | | X |
| Electrical Distribution Equipment | 5 | X | | | X |
| Elevator & Vertical Transportation Shop Drawings | 5 | X | | | X |
| Epoxy Floor | 5 | X | | | X |
| Fire Alarm Shop Drawings & Device Cut Sheets | 5 | X | | | X |
| Fire Sprinkler Shop Drawings, Hydraulic Calculations & Device Cut Sheets | 5 | X | | | X |
| HVAC Equipment(if Carrier - Submitted by Owner Vendor to Owner/AOR prior to const.) | 5 | X | | | X |
| Light Fixtures(Submitted by Owner Vendor to Owner/AOR prior to construction) | 5 | X | | | X |
| M&P Tests, Start-Up, and Programming Reports | 5 | X | | | X |
| Millwork - Material Submittals (if differs from spec) | 5 | X | X | | |
| Millwork - Shop Drawings (custom items & design features only) | 5 | X | | | |
| Restroom Partitions | 5 | X | | | X |
| Plumbing Fixtures | 5 | X | | | X |
| Railing Shop Drawings | 5 | X | | | X |
| Rebar | 5 | X | | | X |
| Stair Shop Drawings | 5 | X | | | X |
| Structural Steel Shop Drawings | 7 | X | | | X |
| Storefront - product data Submittal (if different from specified) | 5 | X | | | |
| Storefront - Shop Drawings | 5 | X | | | X |
| Tile (if differs from spec) | 5 | X | | | X |
| Window Film | 5 | X | | | |



SHAKE SHACK #1797
WILMINGTON, NC

Project Number 25163
Drawn By SEI
Checked By GRS
Date 4 AUG 2025

Revisions
1 23 OCT 2025 HEALTH DEPARTMENT REVIEW COMMENTS
2 17 NOV 2025 IFC SET


Drawing

MECHANICAL ABBREVIATIONS & SYMBOLS

M001

SE_008 - 20202


Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.



1 MECHANICAL FLOOR PLAN


- GENERAL NOTES:**
- A. EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - B. CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - C. ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - E. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - F. MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - G. ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - H. ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGNOSTIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHERE DECISION SHALL BE FINAL. NO CLAIMS WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - I. COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - J. THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - K. ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - L. DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E. BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - M. ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMCMA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT PAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - N. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - O. ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE.
 - P. PROVIDE REMOTE VOLUME DAMPER MANUFACTURED BY YOUNG REGULATOR OR UNITED ENERTECH FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILING.
 - Q. REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - R. TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE REDUCTION OF DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - S. ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - T. ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
 - U. GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - Z. MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND 7 OR 8 YEAR WARRANTY ON ALL GREASE EXHAUST DUCTWORK. WARRANTY SHALL INCLUDE LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - W. AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE LISTED IN THE GENERAL NOTES. THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURGH AT WILL@NATIONALTAB.COM OR 314-954-6244.

- HVAC NOTES:**
1. TOP OPEN RETURN AIR DUCT. PROVIDE OPENING WITH 1/4" MESH GALVANIZED SCREEN.
 2. CONTRACTOR SHALL UNDERCUT DOOR 3/4".
 3. PROVIDE 8/8 EXHAUST AIR DUCT UP TO EF-4 ON ROOF.
 4. NEW CAPTIVE HOOD TO BE FURNISHED BY OWNER FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. SEE CAPTIVE SHEETS FOR ADDITIONAL INFORMATION. BALANCE HOOD EXHAUST AS NOTED ON CAPTIVE SHEETS. VERIFY ALL MANUFACTURER AND CODE REQUIRED CLEARANCES ARE MAINTAINED. PROVIDE APPROVED GASKETS FOR ALL JOINTS. HOOD SHALL BE WRAPPED WITH TWO (2) LAYERS OF THERMAL CERAMICS FAST WRAP XL, 1 1/2" THICK WITH 3" PERIMETER AND LONGITUDINAL OVERLAPS OR EQUIVALENT U.L. LISTED GREASE DUCT WRAP FOR ZERO CLEARANCE TO COMBUSTIBLES. REFER TO SHEET M501, DETAIL 1, FOR ADDITIONAL INFORMATION, TYPICAL.
 6. HOOD MANUFACTURER TO PROVIDE A "KIT" TO FASTEN THE BOTTOM FLANGE OF THE HOOD TO THE WALL WITH ONE FASTENER PER STD WALL. SIL-BOND RTV-4500 ALUMINUM SILICONE SEALANT OR APPROVED SIMILAR, TO BE APPLIED BY GENERAL CONTRACTOR/HOOD INSTALLER FOR ANY REMAINING SMALL GAPS. HOOD FASTENING "KIT" DETAIL TO BE INCLUDED IN MANUFACTURER DRAWINGS. REFERENCE SHEET M501, DETAIL 9, FOR ADDITIONAL INFORMATION.
 7. DUCTWORK TO BE TO BE INSTALLED AS HIGH AS CONDITIONS ALLOW. COORDINATE ROUTING AND MOUNTING HEIGHT WITH LIGHTING FIXTURES. NOTIFY THE ARCHITECT OF ANY CONFLICTS AND COORDINATE WITH THE CONSTRUCTION MANAGER.
 8. PROVIDE NEW FC UNIT AS NOTED ON PLANS AND AS SCHEDULED ON SHEET M501.
 9. PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 10. PROVIDE CLEANOUTS ON GREASE DUCTWORK AS REQUIRED BY CODE, WHERE GREASE DUCT CLEANOUT POINTS ARE REQUIRED, DUCTMATE ULTIMATE GREASE EXHAUST ACCESS PANELS SHALL BE UTILIZED. TYPICAL OF GREASE EXHAUST DUCTWORK. REFERENCE SHEET M501, DETAIL 2, FOR ADDITIONAL INFORMATION.
 11. PROVIDE REMOTE VOLUME DAMPER AS INDICATED ON PLANS. REFERENCE SHEET M501, DETAIL 3, FOR ADDITIONAL INFORMATION, TYPICAL OF DIFFUSERS/GRILLES INSTALLED IN GYP. BOARD CEILING.
 12. COORDINATE WITH CAPTIVEWARE ON REMOTE SENSORS AND COMFORT CONTROLS PACKAGE THAT IS TO BE INSTALLED IN THE OFFICE. VERIFY CONTROLS ARE A FULLY DIGITAL 7 DAY PROGRAMMABLE TYPE THERMOSTAT WITH REMOTE SENSING CAPABILITIES, AUTO CHANGE OVER AND AUTO SET BACK. MOUNT SENSOR AND CONTROLS AT 48" ABOVE FINISHED FLOOR. UNITS SERVING THE SAME TEMPERATURE ZONE SHALL BE INTERLOCKED TO PREVENT SIMULTANEOUS HEATING AND COOLING. LOCATE REMOTE TEMPERATURE SENSORS AS INDICATED ON PLAN. REFERENCE CAPTIVEWARE SHEETS FOR ADDITIONAL INFORMATION. COORDINATE INSTALLATION LOCATION OF REMOTE SENSORS WITH ARCHITECT AND CONSTRUCTION MANAGER. REFERENCE #401 FOR ADDITIONAL INFORMATION.
 13. MOUNT TEMPERATURE CAPTIVEWARE ROOM TEMPERATURE SENSOR FURNISHED WITH KITCHEN HOODS ON WALL AS INDICATED ON THE PLANS AND AS SPECIFIED BY THE MANUFACTURER.
 14. PROVIDE WITH INSULATED BACK PAN.
 15. COORDINATE FINAL COLOR/FINISH OF EXPOSED DUCTWORK/DIFFUSERS WITH ARCHITECT AND CONSTRUCTION MANAGER. TYPICAL THROUGHOUT SPACE.



New York • Miami • Chicago • Los Angeles • Seattle • Honolulu
800-581-0963 www.schnackel.com

Seal



Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.dp3architects.com

Project



SHAKE SHACK #1797
WILMINGTON, NC

Project Number 25163
Drawn By SEI
Checked By GRS
Date 4 AUG 2025

Revisions


| | | |
|---|-------------|-----------------------------------|
| 1 | 23 OCT 2025 | HEALTH DEPARTMENT REVIEW COMMENTS |
| 2 | 17 NOV 2025 | IFC SET |

Drawing
MECHANICAL FLOOR PLAN

M101

SE_026 - 10/202

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.



1 MECHANICAL REFRIGERANT PIPING LAYOUT PLAN
 SCALE: 1/4" = 1'-0"


- GENERAL NOTES:**
- A. EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - B. CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - C. ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - D. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - E. MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - F. ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - G. ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGNOSTIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHERE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - H. COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - I. THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - J. ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - K. DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E. BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - L. ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WEAVED WITH 1-1/2" THICK FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMCMA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - M. ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE.
 - N. PROVIDE REMOTE VOLUME DAMPER MANUFACTURED BY YOUNG REGULATOR OR UNITED ENERTECH FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILING.
 - O. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - P. REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - Q. TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - R. ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - S. ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
 - T. GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - U. MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - V. AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE TENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURGH AT WILL@NATIONALTAB.COM OR 314-954-6244.

- HVAC NOTES:**
1. PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.
 2. KITCHEN EQUIPMENT CONTRACTOR TO PROVIDE REFRIGERANT LINES FROM CONDENSING UNIT ON ROOF TO KITCHEN EQUIPMENT AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.



New York • Miami • Chicago • Los Angeles • Seattle • Honolulu
 800-581-0963 www.schnackel.com

Seal



Brian S. Thomas
 Architect

DP3 Architects, Ltd.
 15 South Main Street, Suite 400
 Greenville, SC 29601
 864.232.8200
 www.DP3architects.com

Project



SHAKE SHACK #1797
 WILMINGTON, NC

Project Number 25163
 Drawn By SEI
 Checked By GRS
 Date 4 AUG 2025

Revisions

| | | |
|---|-------------|-----------------------------------|
| 1 | 23 OCT 2025 | HEALTH DEPARTMENT REVIEW COMMENTS |
| 2 | 17 NOV 2025 | IFC SET |


Drawing

MECHANICAL REFRIGERANT PIPING LAYOUT PLAN

M102

SEI_008-10202



Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.



1 MECHANICAL ROOF PLAN
 SCALE: 1/4" = 1'-0"
 SCALE: 1/4" = 1'-0"

- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGNOSTIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER. DECISION SHALL BE FINAL. NO CLAIMS WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E. BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WEARER WITH 1-1/2" THICK FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMACNA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITED ENERTECH FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILINGS. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND 7 OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE TENDR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURGH AT WILL@NATIONALTAB.COM OR 314-954-6244.

- HVAC NOTES:**
- NEW CAPTIVE/RTU TO BE FURNISHED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE CAPTIVE/RTU SHEETS FOR ADDITIONAL INFORMATION. FIELD VERIFY EXACT LOCATION.
 - NEW CAPTIVE/RTU GREASE EXHAUST FAN TO BE FURNISHED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE CAPTIVE/RTU SHEETS FOR ADDITIONAL INFORMATION. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE.
 - DUCT SMOKE DETECTOR ON RETURN SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
 - RFC ENVIRONMENTAL GROUP, INC. AIR PURIFICATION SYSTEM TO BE PROVIDED BY NTAB. REFER TO RESPONSIBILITY MATRIX ON SHEET M001 FOR ADDITIONAL INFORMATION, SHEET M601 FOR SCHEDULE, AND SHEET M592 FOR SPECIFICATIONS.
 - PROVIDE NEW EXHAUST FAN AS NOTED ON PLANS AND SCHEDULED ON SHEET M601. THE CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE.
 - MECHANICAL CONTRACTOR TO PROVIDE ASHP AS NOTED ON PLANS AND SCHEDULED ON SHEET M601.
 - MECHANICAL CONTRACTOR TO PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.
 - KITCHEN EQUIPMENT CONTRACTOR TO PROVIDE REFRIGERANT LINES FROM CONDENSING UNIT ON ROOF TO KITCHEN EQUIPMENT AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.



Brian S. Thomas
 Architect

DP3 Architects, Ltd.
 15 South Main Street, Suite 400
 Greenville, SC 29601
 864.232.8200
 www.dp3architects.com

Project

SHAKE SHACK
 SHAKE SHACK #1797
 WILMINGTON, NC

Project Number 25163
 Drawn By SEI
 Checked By GRS
 Date 4 AUG 2025

Revisions


| | | |
|---|-------------|-----------------------------------|
| 1 | 23 OCT 2025 | HEALTH DEPARTMENT REVIEW COMMENTS |
| 2 | 17 NOV 2025 | IFC SET |

Drawing
MECHANICAL ROOF PLAN

M150


| MAXIMUM HALF OF DUCT PERIMETER | PAIR AT 10 FT. SPACING | | PAIR AT 8 FT. SPACING | | PAIR AT 5 FT. SPACING | | PAIR AT 4 FT. SPACING | |
|---|---------------------------|--------------------------------------|-----------------------|-------------------|-----------------------|--------------------|-----------------------|----------------|
| | STRAP | WIRE/ROD | STRAP | WIRE/ROD | STRAP | WIRE/ROD | STRAP | WIRE/ROD |
| P/2 = 30" | 1" x 22 GA. | 10 GA. (.135") | 1" x 22 GA. | 10 GA. (.135") | 1" x 22 GA. | 12 GA. (.106") | 1" x 22 GA. | 12 GA. (.106") |
| P/2 = 72" | 1" x 18 GA. | 3/8" | 1" x 20 GA. | 1/4" | 1" x 22 GA. | 1/4" | 1" x 22 GA. | 1/4" |
| P/2 = 96" | 1" x 16 GA. | 3/8" | 1" x 18 GA. | 3/8" | 1" x 20 GA. | 3/8" | 1" x 22 GA. | 1/4" |
| P/2 = 120" | 1 1/2" x 16 GA. | 1/2" | 1" x 16 GA. | 3/8" | 1" x 18 GA. | 3/8" | 1" x 20 GA. | 1/4" |
| P/2 = 168" | 1 1/2" x 16 GA. | 1/2" | 1 1/2" x 16 GA. | 1/2" | 1" x 16 GA. | 3/8" | 1" x 18 GA. | 3/8" |
| P/2 = 192" | --- | 1/2" | 1 1/2" x 16 GA. | 1/2" | 1" x 16 GA. | 3/8" | 1" x 16 GA. | 3/8" |
| P/2 = 193" UP | SPECIAL ANALYSIS REQUIRED | | | | | | | |
| WHEN STRAPS ARE LAP JOINED USE THESE MINIMUM FASTENERS: | | SINGLE HANGER MAXIMUM ALLOWABLE LOAD | | STRAP | | WIRE OR ROD (DIA.) | | |
| 1" x 18, 20, 22 GA. - TWO #10 OR ONE 1/4" BOLT | | 1" x 22 GA. - 260 LBS. | | 0.106" - 80 LBS. | | | | |
| 1" x 16 GA. - TWO 1/4" DIA. | | 1" x 20 GA. - 320 LBS. | | 0.135" - 120 LBS. | | | | |
| 1" x 16 GA. - TWO 3/8" DIA. | | 1" x 18 GA. - 420 LBS. | | 0.162" - 160 LBS. | | | | |
| PLACE FASTENERS IN SERIES, NOT SIDE BY SIDE. | | 1" x 16 GA. - 700 LBS. | | 1/4" - 270 LBS. | | | | |
| | | 1 1/2" x 16 GA. - 1100 LBS. | | 3/8" - 680 LBS. | | | | |
| | | | | 1/2" - 1250 LBS. | | | | |
| | | | | 5/8" - 2000 LBS. | | | | |
| | | | | 3/4" - 3000 LBS. | | | | |

NOTES:
1. DIMENSIONS OTHER THAN GAUGE ARE IN INCHES.
2. TABLES ALLOW FOR DUCT WEIGHT, 1 LB./SF INSULATION WEIGHT AND NORMAL REINFORCEMENT AND TRAPEZE WEIGHT, BUT NO EXTERNAL LOADS.
3. STRAPS ARE GALVANIZED STEEL; OTHER MATERIALS ARE UNCOATED STEEL.
4. ALLOWABLE LOADS FOR P/2 ASSUME THAT DUCTS ARE 18 GA. MAXIMUM, EXCEPT THAT WHEN MAXIMUM DUCT DIMENSION (W) IS OVER 60" THEN P/2 MAXIMUM IS 1.25 W.
5. 12, 10 OR 8 GA. WIRE IS STEEL OF BLACK ANNEALED, BRIGHT BASIC OR GALVANIZED TYPE.
6. DUCTS SHALL BE SUPPORTED AT INTERVALS NOT EXCEEDING 10 FEET.



NOTE: HANGERS MUST NOT DEFORM DUCT SHAPE

- NOTES:
1. THERMAL CERAMICS FIREMASTER FASTWRAP XL IS TESTED TO ASTM E2336 AND UL LISTED PER HNK1.G18 TO PROVIDE ZERO CLEARANCE TO COMBUSTIBLES AND TO PROVIDE A 1 OR 2 HOUR EXPOSURE THROUGH PENETRATIONS. FIRESTOP SYSTEMS ARE TESTED IN ACCORDANCE WITH ASTM E 814 (UL 1479), ICC-ES APPROVAL PER REPORT ESR 2213 OR ESR 2832.
2. COMPLIANT TO THE FOLLOWING CODES:
NFPA 96
INTERNATIONAL MECHANICAL CODES
UNIFORM MECHANICAL CODE
CALIFORNIA MECHANICAL CODE
3. INSULATION APPLIED IN TWO LAYERS WITH TIGHT COMPRESSION JOINT ON BOTH LAYERS AT ALL JOINTS.
4. MINIMUM 18 GAUGE CARBON STEEL (OR 18 GAUGE STAINLESS STEEL) RECTANGULAR OR ROUND GREASE EXHAUST DUCT.
5. INSTALL UL LISTED AND LIQUID TIGHT THERMAL CERAMICS FASTDOOR XL ACCESS DOORS AT ALL CHANGES IN DIRECTION AND AT MINIMUM EVERY 20 FT. ON HORIZONTAL RUNS.
6. SUPPORT HANGER SYSTEMS DO NOT NEED TO BE WRAPPED PROVIDED THE HANGER RODS ARE MINIMUM OF 3/8" IN. DIAMETER AND SUPPORTS ARE MINIMUM 2 1/2 x 1 1/8 IN. STEEL ANGLE OR SMACTA EQUIVALENT SUPPORT SYSTEM.
7. THERMAL CERAMICS DUCT WRAP SHALL BE INSTALLED DIRECTLY ONTO THE DUCT AND APPLIED FROM THE HOOD CONNECTION TO THE CONNECTION OF THE FAN.
8. THERMAL CERAMICS DUCT ENCLOSURE SYSTEM SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS AND UL LISTINGS.




** DETAIL COURTESY OF MORGAN THERMAL CERAMICS.

7 RECTANGULAR DUCT HANGER TABLE
NOT TO SCALE


4 DUCT HANGER DETAIL
NOT TO SCALE

1 FIREMASTER FASTWRAP XL DETAIL
NOT TO SCALE




8 TYPICAL DIFFUSER CONNECTION
NOT TO SCALE


9 CURB FLASHING DETAIL
NOT TO SCALE




5 CONDENSER REFRIGERANT LINE PIPING AND POWER THROUGH ROOF DECK
NOT TO SCALE




2 KITCHEN HOOD EXHAUST FAN
NOT TO SCALE




10 HOOD FASTENING DETAIL
NOT TO SCALE



6 FLEXIBLE DUCT SUPPORTS
NOT TO SCALE



3 REMOTE VOLUME DAMPER CONTROLLER
NOT TO SCALE



Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.dp3architects.com

Project

SHAKE SHACK
SHAKE SHACK #1797
WILMINGTON, NC

Project Number 25163
Drawn By SEI
Checked By GRS
Date 4 AUG 2025


Revisions
1 23 OCT 2025 HEALTH DEPARTMENT REVIEW COMMENTS
2 17 NOV 2025 IFC SET

Drawing
MECHANICAL
DETAILS


M501

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.

SE_008-10002




9 CONDENSING UNIT SUPPORT DETAIL
NOT TO SCALE




NOTES:
1. CUT AND PATCH EXISTING ROOFING AS REQUIRED FOR NEW CURB INSTALLATION.
2. CURB SHALL BE SHIMMED LEVEL. PROVIDE TAPERED ROOF CURB IF REQUIRED.
3. SECURELY INSTALL CURB TO ROOF STRUCTURE; USE FASTENERS AS REQUIRED BY ROOF CONSTRUCTION.


10 ROOF CURB DETAIL
NOT TO SCALE




11 CONDENSING UNIT ANCHOR DETAIL (METAL)
NOT TO SCALE



5 DUCTWORK DETAILS
NOT TO SCALE



6 ROOF EXHAUST FAN DETAIL
NOT TO SCALE




7 EXPOSED RECTANGULAR DUCT SUPPORT DETAIL
NOT TO SCALE


| DIA. | WIRE DIA. | ROD | STRAP |
|--------|-------------------------|----------|---------------------|
| 10" DN | ONE 12 GA. | 1/4" | 1" x 22 GA. |
| 11-18" | TWO 12 GA. OR ONE 8 GA. | 1/4" | 1" x 22 GA. |
| 19-24" | TWO 10 GA. | 1/4" | 1" x 22 GA. |
| 25-36" | TWO 8 GA. | 3/8" | 1" x 20 GA. |
| 37-50" | - | TWO 3/8" | TWO 1" x 20 GA. |
| 51-60" | - | TWO 3/8" | TWO 1" x 18 GA. |
| 61-84" | - | TWO 3/8" | TWO 1" x 16 GA. |
| 85-96" | - | TWO 1/2" | TWO 1 1/2" x 16 GA. |

NOTES:
1. STRAPS ARE GALVANIZED STEEL; RODS ARE UNCOATED OR GALVANIZED STEEL; WIRE IS BLACK ANNEALED, BRIGHT BASIC OR GALVANIZED STEEL. ALL ARE ALTERNATIVES.
2. TABLE ALLOWS FOR CONVENTIONAL WALL THICKNESS, AND JOINT SYSTEMS PLUS ONE LB/SF OF INSULATION WEIGHT. IF HEAVIER DUCTS ARE TO BE INSTALLED, ADJUST HANGER SIZES TO BE WITHIN THEIR LOAD LIMITS.


8 ROUND DUCT HANGER TABLE
NOT TO SCALE



1 TYPICAL ROUND DUCT FITTINGS
NOT TO SCALE




2 TYPICAL DRYWALL MOUNTING FRAME DETAIL
NOT TO SCALE




NOTE:
1. DUCT SMOKE DETECTOR ON RETURN AND/OR SUPPLY SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.

3 DUCT SMOKE DETECTOR DETAIL
NOT TO SCALE



NOTES:
1. PROVIDE THROUGH CURB ELECTRICAL CONNECTIONS. NO ROOF PENETRATIONS OF ELECTRICAL CONDUITS WILL BE ACCEPTABLE.
2. DUCT SMOKE DETECTOR SHALL BE MOUNTED AND INSTALLED PER LOCAL CODES.

4 TYPICAL ROOF TOP UNIT DETAIL
NOT TO SCALE



New York • Miami • Omaha • Los Angeles • Seattle • Honolulu
800-581-0963 www.schnackel.com



Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.dp3architects.com

Project

SHAKE SHACK #1797
WILMINGTON, NC

Project Number 25163
Drawn By SEI
Checked By GRS
Date 4 AUG 2025

Revisions
1 23 OCT 2025 HEALTH DEPARTMENT REVIEW COMMENTS
2 17 NOV 2025 IFC SET

Drawing
MECHANICAL DETAILS

M502

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.

SE_026-10002

SPECIFICATIONS TABLE OF CONTENTS

SECTION 230000 - HVAC GENERAL CONDITIONS
SECTION 230548 - VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT
SECTION 230593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC
SECTION 230713 - DUCT INSULATION
SECTION 230713.13 - GREASE DUCT FIREPROOFING
SECTION 230719 - HVAC PIPING INSULATION
SECTION 230800 - COMMISSIONING OF HVAC
SECTION 230963 - SEQUENCE OF OPERATIONS FOR HVAC CONTROLS
SECTION 232300 - REFRIGERANT PIPING
SECTION 233100 - HVAC DUCTS AND CASINGS
SECTION 233300 - AIR DUCT ACCESSORIES
SECTION 233443 - HVAC POWER VENTILATORS
SECTION 233700 - AIR OUTLETS AND INLETS
SECTION 237413 - PACKAGED OUTDOOR ROOF TOP UNITS - GAS FIRED
SECTION 238127 - SMALL SPLIT-SYSTEM HEATING AND COOLING

SECTION 230000 - HVAC GENERAL CONDITIONS

PART 1 GENERAL

1.01 APPLICABILITY

A. This section supplements all sections of the Specifications for Division 23 and shall apply to all materials and services specified, shown on the Drawings, or required to provide a complete installation of approved HVAC systems.

1.02 DEFINITIONS

A. "Work" is hereby defined as, "The construction and services required by the Contract Documents whether completed or partially completed and includes all labor, materials, equipment, and services provided or to be provided by the Contractor to fulfill the Contractor's obligations. The work may constitute the whole or a part of the project."
B. "Furnish" is hereby defined as, "To supply and deliver, unload, and inspect for damage."
C. "Install" is hereby defined as, "To unpack, assemble, erect, apply, place, finish, cure, protect, clean, connect, and place into operation into the work."
D. "Provide" is hereby defined as, "To provide the equipment and make final attachment including installation and final verification."
E. "Connect" is hereby defined as, "To bring service to the equipment and make final attachment including installation and final verification."
F. "Concealed" is hereby defined as, "Hidden from sight in chases, furred spaces, shafts, hung ceilings, embedded in construction, in crawl spaces, or buried."
G. "Exposed" is hereby defined as, "Not installed underground nor concealed as defined by the Specifications."
H. "Drawings" is hereby defined as, "All plans, details, equipment schedules, diagrams, sketches, etc. issued for the construction of the work."

1.03 CODES AND STANDARDS

A. Perform work in accordance with the applicable Building Code, Electrical Code, Fire Code, Mechanical Code, Plumbing Code, Energy Code, and all other applicable codes, ordinances, and regulations. Also perform work in accordance with the Americans with Disabilities Act (ADA) and the Authority Having Jurisdiction (AHJ) including The Marshall's.
B. Perform work in accordance with Landlord requirements, including any Tenant Criteria Manuals and Lease Documents.
C. Perform work in accordance with the applicable utility companies serving the project. Make all arrangements with the utility companies for proper coordination of the work.
D. Recognized Standards: Design, manufacture, testing and method of installation of all apparatus and equipment shall conform to the latest publications or standard rules of Underwriters Laboratories, Inc. (UL); International Brotherhood of Electrical Workers (IBEW); American National Standards Institute (ANSI); and National Electrical Code (NEC), National Fire Protection Association (NFPA), American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE), and the Society of Air Conditioning Contractors' National Association (SMACTA).

1.04 PERMITS AND FEES

A. Permits, licenses, fees, inspections and arrangements required for the work under this Contract shall be obtained by the Contractor at his expense, unless otherwise indicated.

1.05 CONTRACT DRAWINGS

A. The Contractor is responsible to obtain, fully understand, and coordinate the work with the complete set of Contract Documents. Any required corrections, including all associated costs, arising from issues concerning the drawings shall be the Contractor's responsibility.
B. Work under these sections is diagrammatic unless indicated otherwise and is intended to convey the scope of work and indicate the general arrangement of ductwork, piping, equipment, and accessories. Follow the drawings in laying out the work and verify spaces for the installation of these materials and equipment. Wherever a question exists as to the exact intended location of ductwork, piping, or equipment, obtain instructions from the Architect before proceeding with the work.
C. Notify the Architect for resolution if a discrepancy is discovered within the Contract Documents. Failure of the Contractor to notify the Architect of discrepancies shall result in the contractor being held responsible for the discrepancy, responsibility and subject to the Architect's review and possible rejection. Should the Architect reject a discrepancy, the Contractor shall be notified, the Contractor is fully responsible to correct the installation, including all associated costs, until approval of the installation is given by the Architect.

1.06 EXISTING CONDITIONS

A. Verify all existing conditions prior to beginning work.
B. Any existing conditions indicated in the Contract Documents are based on information drawings provided by others and existing conditions. The Contractor shall adjust for actual field conditions at no additional expense to the Owner.
C. The Contractor shall visit the project site, review existing conditions against the Contract Documents, and familiarize himself with the work prior to bidding and start of the work. By signing the Contract Documents, the Contractor certifies that the work has been completed and the existing conditions are accepted.
D. The Contractor shall notify the Architect of any discrepancies in writing as the appropriate modifications to the design can be made without delay to the project. The Contractor assumes full responsibility of adjusting for discrepancies if which the Architect is not informed.

1.07 SUBMITTALS

A. Shop Drawings:
1. Furnish the following submittals to the Architect for review by the Engineer:
a. Provide product data and shop drawings for vibration isolation.
b. Provide balancing fan qualifications and final test report for Testing, Adjusting, and Balancing.
c. Provide product data for duct insulation.
d. Provide product data for grease duct fireproofing (if specified).
e. Provide product data for HVAC piping insulation.
f. Provide product data for refrigerant piping.
g. Provide product data for HVAC ductwork.
h. Provide product data for air duct accessories.
i. Provide product data and shop drawings for HVAC power ventilators.
j. Provide product data and shop drawings for air outlets and inlets.
k. Provide product data and shop drawings for condensing units and heat pumps.
l. Provide product data and shop drawings for air handling and fan coil units.
2. Submittals other than those listed above will not be reviewed and will be returned stating as such.
3. Shop drawings shall be prepared by a manufacturer's representative, and shall contain names of the manufacturer and cut sheets of equipment to be used on the project. Use manufacturer's specification sheets identified by number indicated on drawings or schedules. Indicate catalog number on the cut sheets. As applicable, provide construction details for voltage, current, voltage ratings, performance data, listing data, pump curves, fan curves and sound data as part of the shop drawing submittals.
4. Submittals are reviewed only for general compliance with the Contract Documents. Dimensions, quantities and details are not checked during submittal review. Review of the submittals does not relieve the Contractor of the responsibility for providing all materials, equipment and accessories necessary for a complete and operating installation.
5. Electrical Characteristics: Verify that proper power supply is available prior to ordering equipment. Verify proper voltage and amperage rating of power supply and inform Engineer of any deviations prior to order.
6. Test Reports: Provide Testing, Adjusting, and Balancing (TAB) and Commissioning reports to the Architect for review by the Engineer. All other reports shall be provided to the Owner.

1.08 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum five years experience.
B. Installer Qualifications: Company specializing in performing the work of this section, with minimum five years experience.
C. Products:
1. Listed and classified by Underwriters Laboratories Inc. as suitable for the purpose specified and indicated.
D. All equipment and components shall be free of oil rust/corrosion or any visible damage. All items not complying with this requirement shall be replaced without any charge in the Contract amount.
E. Equipment performance and accessories shall be as scheduled on the Drawings and specified herein. Inclusion in both locations is not a prerequisite to inclusion in the Contract. Equipment and accessories specified in either location shall be included in the Contract. Provide all necessary accessories and connections as required for a complete, functional system, including all required components reasonably inferred to be necessary although such components may or may not be specifically identified in the Contract Documents.
F. Code or utility company requirements shall supersede any conflicting requirements of this section.

1.09 DELIVERY, STORAGE AND HANDLING

A. Rooftop Equipment: Protect units from physical damage by storing off site until roof mounting curbs are in place, ready for installation.
B. Protect insulation from weather and construction traffic, dirt, water, chemical, and mechanical damage by attaching, adjusting, and weathering.
C. Protect dampers and accessories from damage to operating linkages, blades and finishes.
D. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.
E. Protect motors stored on site from weather and moisture by maintaining factory covers and suitable weather-proof covering. For extended outdoor storage, remove motors from equipment and store separately.

1.10 WARRANTY AND GUARANTEE

A. Submit manufacturer's warranty and ensure forms have been filled out in Owner's name and registered with manufacturer.
B. Provide one year manufacturer warranty for pumps.
C. Provide three year manufacturer warranty for condenser water legion modules.
D. Provide five year manufacturer warranty for compressors, heat exchangers, condensing units, and electronic air cleaners.

PART 2 PRODUCTS

2.01 SUBSTITUTIONS

A. The manufacturers listed are listed to set minimum standards for quality, design, and functionality. The products of other manufacturers may be submitted, at the Contractor's option, during submittal review. The Contractor shall submit the products of other manufacturers shall meet or exceed all requirements of the Contract Documents. The Contractor accepts all responsibility for costs and coordination issues arising out of the substitution of materials, equipment, and the coordination of such substitutions with all other contractors and subcontractors.
B. The Contractor may use any of the following ductwork, piping or insulation materials at his option, provided the selected materials meet with the approval of all State, local authorities and any utility company requirements. Verification of compliance of the selected material is the sole responsibility of the installing Contractor.

PART 3 EXECUTION

3.01 COORDINATION OF WORK

A. Examine the Contract Documents as a whole for the work of other trades. Coordinate all work accordingly.
B. Promptly report to the Architect any delay or difficulties encountered in the installation of the work, which might prevent prompt and proper installation, or make it unsuitable to connect or receive the work of others. Failure to so report shall constitute an acceptance of the work of other trades as being fit and proper for the execution of this work.
C. Plan, lay out, and coordinate the work with all trades well on in advance so that it is completed with a minimum of interference to work that has not been completed and work that is in progress. Inform all trades of openings required for the work and provide all special forms, shims, and anchor bolts required. The HVAC system layout may be altered to suit the conditions with engineer approval, prior to the installation of any equipment, and without additional cost to the Owner. Conflicts arising from lack of coordination shall be this Contractor's responsibility.
D. Perform all work in conformity with the Contract Documents and afford other trades reasonable opportunity for the execution of their work. Properly connect and coordinate this work with the work of other trades at such time and in such a manner as not to delay or interfere with their work.
E. All roof penetrations and roof weather sealed by the roofing manufacturer's authorized roofing contractor at the Contractor's expense. This Contractor shall contract with the factory authorized roofing contractor for the specific roofing system applicable to the Project. The use of an unauthorized roofing contractor will result in removal and replacement of the penetration systems at this Contractor's expense.

3.02 EXAMINATION

A. Verify field measurements are as indicated on the Drawings.
B. Verify all equipment locations prior to rough-in. Maintain adequate equipment service clearance per manufacturer and code.
C. Verify routing of all ductwork and piping in field prior to fabrication or installation. Verify adequate clearance with structure, light fixtures, and other obstructions.
D. Verify that proper fuel and power supply is available for connection.

3.03 INTERFERENCE WITH OTHER PRODUCTS

A. Install all ductwork, pipe, equipment, and accessories to preserve fire resistance ratings of partitions and other elements, using materials and methods specified.

3.04 FIELD QUALITY CONTROL

A. Provide tests as necessary to establish the adequacy, quality, safety, completed status, and suitable operation of each system. Tests shall be conducted under the supervision of the Architect.

3.05 CLEANING AND REPAIR

A. Clean fire suppression parts to remove harmful materials.
B. Clean exposed surfaces of all ductwork pipe, equipment, and accessories of all dirt, debris, splatter and other deleterious materials. Follow the manufacturer's recommendations for cleaning as applicable.
C. Repair or replace damaged ductwork, pipe, equipment, and accessories, as directed by and to the satisfaction of the Architect, where marring or disfigurement has occurred. All pipe, equipment, and accessories shall be new.

3.06 PROJECT CLOSEOUT

A. Project Record Documents: At project closeout, provide one printed copy and one electronic copy of the project record documents to the Owner. Record documents will not be reviewed by the Engineer.

3.07 MAINTENANCE

A. Actual locations of all equipment, ductwork, air inlets/outlets, accessories, etc.
B. Actual routing of ductwork with sizes and elevations.
C. Nameplates: Nameplates shall be provided for all valves and volume dampers. Operation and Maintenance Data: Provide descriptive literature, maintenance and operation data for all valves, equipment, control systems, accessories, and materials used. Include maintenance procedures, intervals, and parts list of each item installed under this contract. Include all manufacturer's warranties and warranties.

3.08 MAINTENANCE MATERIALS

A. At project closeout, furnish to the Owner the following:
1. One set of replacement parts for all HVAC equipment.
2. The maintenance contract for the HVAC system, if applicable.
3. Test Reports: Submit to the Owner all testing reports.

END OF SECTION

SECTION 230548 - VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Vibration Isolators.
B. Equipment: Fans, axial and centrifugal
2. Condensing units and air source heat pumps
3. Furnaces and fan coil units
4. Packaged roof top equipment

1.02 SUBMITTALS

A. Product Data: Provide schedule of vibration isolator type with location and load on each.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Isolation Technology, Inc.; Kinetics Noise Control, Inc.; Mason Industries.

2.02 VIBRATION ISOLATORS

A. Spring Hanger:
1. Service: Minimum horizontal stiffness equal to 75 percent vertical stiffness, with working deflection between 0.3 and 0.6 of maximum deflection.
2. Housings: Incorporate neoprene isolation pad meeting requirements for neoprene pad isolators or rubber hanger with threaded insert.
3. Misalignment: Capable of 20 degree hanger misalignment.
4. For Exterior and Humid Areas: Hot dipped galvanized housings and neoprene pad.
B. Neoprene Pad Isolators:
1. Hardness: 30 durometer.
2. Thickness: Minimum 1/2 inch.
3. Maximum Loading: 50 psf.
4. RB Height: Maximum 0.7 times width.
5. Configuration: Single Layer.
C. Rubber Mount or Hanger: Molded rubber designed for 0.4 inch deflection with threaded insert.
D. Glass Fiber Pad: Neoprene jacketed pre-compressed molded glass fiber.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions.
B. Provide flexible connections on all piping and ductwork connections to equipment. Refer to other sections of this Specification for the acceptable types of flexible connectors to be used.
C. Selection of type, thickness and deflection of vibration isolation shall be by the vibration control manufacturer based on the specific equipment type and size, as indicated on the Drawings and indicated below.

3.02 SCHEDULES

A. Equipment Isolation Schedule: (Minimum deflection as sized by the isolation equipment manufacturer)
1. Fans, axial and centrifugal:
a. Small fans up to 22" diameter wheel:
1. Rubber Mount or Hanger
2. Condensing units and air source heat pumps.
b. Base: Concrete Housekeeping Pad.
c. Isolation: Neoprene Pad, Rubber Mount or Glass Fiber Pad.
2. Above grade floor or roof structures:
1. Base: Concrete Housekeeping Pad.
2. Isolation: Neoprene Pad, Rubber Mount or Glass Fiber Pad.
3. Furnaces and fan coil units:
1. Base: Concrete Housekeeping Pad.
2. Isolation: Neoprene Pad, Rubber Mount or Glass Fiber Pad.
4. Packaged roof top equipment:
a. Above grade curbs:
1. Base: Rubber Curbs.
2. Isolation: Full perimeter Neoprene Pad between curb and units.
b. Project: Name; location; Engineer; Contractor; Report date.
c. Isolation: as on the Drawings.

END OF SECTION

SECTION 230593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Testing, adjustment, and balancing of air systems.
1. Air handling units; Packaged heating and/or cooling equipment; Fans (Exhaust and supply); Coils; Terminal equipment; Air inlets and outlets; Diffusers, grilles, louvers, etc.
B. Measurement of final operating condition of HVAC systems.
C. Independent agency requirements.

1.02 SUBMITTALS

A. Qualifications: Submit name of adjusting and balancing agency and TAB supervisor for approval within 30 days after award of Contract. Provide TAB Agency qualifications.
B. Final Reports: Indicate deficiencies in systems that would prevent proper testing, adjusting, and balancing of systems and equipment to achieve specified performance.
1. Submit to the Construction Manager within two weeks after completion of final testing, adjusting, and balancing.
2. Provide reports in bound manuals, complete with index page and indexing tabs, with cover identification at front and side. Include set of reduced drawings with air outlets and equipment identified to correspond with data sheets, and indicating thermostat and equipment location.
3. Include actual instrument list, with manufacturer name, serial number, and date of calibration.
4. Provide Test Reports: Where the TAB standard being followed recommends a report format use that; otherwise, follow ASHRAE Std 111.
5. Include the following on the title page of each report:
a. Name, address and telephone number of Testing, Adjusting, and Balancing Agency.
b. Project: Name; location; Engineer; Contractor; Report date.

1.03 WARRANTY

A. The Balancing Contractor shall be prepared to return to the site at no additional cost to re-adjust air quantities as required to provide uniform temperatures, eliminate drafts and objectionable noise during the first year of occupancy, including one full heating and one full cooling season, after the acceptance of the final balancing report.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 GENERAL REQUIREMENTS

A. Perform total system balance in accordance with one of the following:
1. ASHRAE Std 111, Practices for Measurement, Testing, Adjusting and Balancing of Building Heating, Ventilation, Air-Conditioning, and Refrigeration Systems.
2. NBSB Procedural Standards for Testing Adjusting Balancing of Environmental Control Systems.
B. Linear Fasteners: Galvanized steel, self-adhesive pad or impact applied with integrals, or press-on head.

3.02 SCHEDULES

A. The Contractor may use any of the following insulating materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected insulating material and thickness with all State and local codes and utility company requirements is the sole responsibility of the installing Contractor.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 GENERAL

A. Flexible Glass Fiber Duct Insulation: 1-1/2 inches thick.
B. Flexible Glass Fiber Duct Liner Insulation: 1 inches thick.
C. Flexible Glass Fiber Duct Insulation: 3 inches thick.
D. Return or exhaust air ducts exposed in finished areas: None.

END OF SECTION

SECTION 230713.13 - GREASE DUCT FIREPROOFING

fire and smoke detection, alarm, and control, coordinate scheduling and testing and inspection procedures with the authorities having jurisdiction.

TAB Agency Qualifications:

1. The TAB Agency shall be a member of the International Association of Testing, Adjusting, and Balancing Engineers (IATAB) and shall be certified by the International Association of Testing, Adjusting, and Balancing Engineers (IATAB).
2. The TAB Agency shall be a member of the National Environmental Balancing Bureau (NEBB), National Environmental Balancing Bureau.
3. The TAB Agency must be a completely independent, third party balancing contractor with no financial, common owners or other ties to the installing contractors.

3.02 ADJUSTMENT TOLERANCES

A. Air Handling Systems; Air Outlets and Inlets; Hydraulic Systems: Adjust to within plus or minus 15 percent of design.

3.03 RECORDING AND ADJUSTING

A. Permanently mark settings of valves, dampers, and other adjustment devices allowing settings to be restored. Set and lock memory stops.

3.04 AIR SYSTEM PROCEDURE

A. Adjust air handling and distribution systems to provide required or design supply, return, and exhaust air quantities.
B. Make air quantity measurements in ducts by Pitot tube traverse of entire cross sectional area of duct.
C. Measure air quantities at air inlets and outlets.
D. Adjust distribution system to obtain uniform space temperatures free from objectionable drafts and noise.
E. Use volume control devices to regulate air quantities only to extend that adjustment; do not create objectionable air motion or sound levels. Effect volume control by duct internal devices such as dampers and splitters. Do not use diffuser, grille or register integral dampers for balancing adjustments unless the manufacturer's instructions are followed.
F. Very total system air quantities by adjustment of fan speeds. Provide drive motor speed control to the Owner. Very branch air quantities by damper regulation.
G. Measure static air pressure conditions on air supply units, including filter and coil pressure drops, and total pressure across the fan. Make allowances for 50 percent loading of filters.
H. Adjust outside air automatic dampers, outside air, return air, and exhaust dampers for design conditions in all operating modes as indicated in the sequence of control.

3.05 CLEANING AND REPAIR

A. Where modulating dampers are provided, take measurements and balance at extreme conditions and at all intermediate operating conditions specified in the sequence of control. Balance variable volume systems at maximum air flow rate, full cooling, and at minimum air flow rate, full heating.

3.06 SCOPES

A. Equipment Requiring Testing, Adjusting, and Balancing (if present on the project):
1. HVAC Pumps; Boilers; All Air Handling Equipment; All Packaged Heating and/or Cooling Equipment; All Coils; All Heat Exchangers; Terminal Heat Transfer Units; Air Terminal Units; Air Inlets and Outlets

3.07 MINIMUM DATA TO BE REPORTED

A. Report (if applicable to the project):
1. Summary Comments:
a. Design versus field performance
b. Notable characteristics of system
c. Summary of outdoor and exhaust flows to indicate amount of building ventilation
d. Pressure/flow used throughout report and test conditions.

B. Electric Motors and drives:

1. Manufacturer; Model/Frame; HP/BHP; Phase, voltage, amperage; nameplate, actual, no load; RPM; Service factor; Sheave Make/Size/Bore.
2. V-belt Drives: Identification/Location; Required driven RPM; Driven sheave, diameter and RPM; Belt, size and quantity.

C. Cooling and Heating Coils:

1. Identification/number; Manufacturer
2. Air flow, design and actual
3. Air pressure drop, design and actual
4. Entering and leaving air DB and WB temperature, design and actual
5. Water flow, design and actual (if applicable)
6. Water pressure drop, design and actual (if applicable)
7. Entering and leaving water temperature, design and actual (if applicable)

D. Air Moving Equipment:

1. Manufacturer; Model number; Serial number; Arrangement/Class/Discharge
2. Air flow, specified and actual
3. Inlet; Discharge; Total static pressure (total external), specified and actual

E. Air Distribution Tests:

1. Air terminal number
2. Room number/Location
3. Terminal type
4. Furnaces and fan coil units
5. Area factor
6. Design velocity
7. Design air flow
8. Test (final) velocity
9. Test (final) air flow
10. Percent of design air flow

END OF SECTION

SECTION 230713 - DUCT INSULATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Insulation:
1. Insulation:
a. Duct Insulation.
b. Duct liner.
c. Insulation jackets.
d. Insulation pockets.
e. Supply, return or exhaust ducts in ceiling spaces.
f. Supply, return or exhaust ducts in interior unconditioned areas.
g. Supply, return or exhaust ducts in exterior unconditioned areas.
2. Vapor Barrier Jacket:
a. Minimum Service Temperature: 450 degrees F.
b. Design velocity.
c. Design air flow.
d. Test (final) velocity.
e. Test (final) air flow.
f. Percent of design air flow

1.02 FIELD CONDITIONS

A. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cements.
B. Maintain temperature during and after installation for minimum period of 24 hours.

PART 2 PRODUCTS

2.01 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION

A. Surface Burning Characteristics: Flame spread/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E 84, NFPA 255, UL 723.
B. Manufacturer: Knauf Fiberglase; Johns Manville Corporation; Owens Corning Corp.; CertainTeed Corporation.
C. Certifications:
1. "K" value: ASTM C 553; flexible, noncombustible blanket.
2. "K" value: 0.31 at 75 degrees F, when tested in accordance with ASTM C 518.
3. Maximum Service Temperature: 450 degrees F.
4. Maximum Water Vapor Sorption: 5.0 percent by weight.

B. Vapor Barrier Jacket:

1. Minimum Service Temperature: -40 degrees F.
2. Maximum Service Temperature: 220 degrees F.
3. Connection: Waterproof vapor barrier adhesive.
C. Vapor Barrier Tape:
1. Minimum Service Temperature: -40 degrees F.
2. Maximum Service Temperature: 220 degrees F.
3. Connection: Waterproof vapor barrier adhesive.
D. Jacket:
1. Kraft paper reinforced with glass fiber yarn and bonded to aluminumized film, with pressure sensitive rubber based adhesive.
2. Outdoor Vapor Barrier Finish:
a. Unretreated: 0.2 oz/ft sq weight.
b. Retreated: 0.2 oz/ft sq weight.
c. Vinyl emulsion type acrylics, compatible with insulation, black color.
d. Insulating Cement: ASTM C 449/C 449M.
e. Flexible Elastomeric Cellular Insulation:
1. Manufacturer: ArmoCell International.
2. Minimum Service Temperature: -40 degrees F.
3. Maximum Service Temperature: 220 degrees F.
4. Connection: Waterproof vapor barrier adhesive.
E. Jacket:
1. Minimum Service Temperature: -40 degrees F.
2. Maximum Service Temperature: 220 degrees F.
3. Connection: Waterproof vapor barrier adhesive.
D. JACKETS:
1. Manufacturer: Knauf Fiberglase; Johns Manville Corporation; Owens Corning Corp.; CertainTeed Corporation.
2. Jacket: One piece molded type fitting covers and sheet material, off-white color.
a. Minimum Service Temperature: 0 degrees F.
b. Maximum Service Temperature: 180 degrees F.
c. Moisture Vapor Permeability: 0.002 perm inch, maximum, when tested in accordance with ASTM E 96/E 96M.
d. Thickness: 10 mil.
e. Connections: Brush on welding adhesive.
3. Covering Thermal Conductivity:
a. Maximum Thermal Conductivity: Maximum of 0.31 at 75 degrees F.
b. Service Temperature: Up to 250 degrees F.
c. Rated Velocity on Coated Air Side for Air Erosion: 5,000 fpm, minimum.
4. Minimum Noise Reduction Coefficients:
a. 1/2 inch Thickness: 0.30.
b. 1 inch Thickness: 0.45.
c. 1-1/2 inch Thickness: 0.60.
d. 2 inch Thickness: 0.70.
5. Adhesive: Waterproof, fire-retardant type.
6. Liner Fasteners: Galvanized steel, self-adhesive pad or impact applied with integrals, or press-on head.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions and NAIMA National Insulation Standards.
B. Insulated ducts conveying air below ambient temperature:
1. Provide insulation with vapor barrier jackets.
2. Finish with tape and vapor barrier jacket.
3. Continue insulation through fittings, sleeves, hangers, and other duct penetrations.
4. Insulate entire system including flanges, joints, flanges, fire dampers, flexible connections, and expansion joints.
C. Insulated ducts conveying air above ambient temperature:
1. Provide with or without standard vapor barrier jacket.
2. Insulate fittings and joints. Where service access is required, bevel and seal ends of insulation.
D. External Duct Insulation Application:
1. Secure insulation with vapor barrier with wres and seal jacket joints with vapor barrier adhesive or tape to match joints.
2. Secure insulation without vapor barrier with staples, tacks, or wires.
3. Test, adjust, and balance.
4. Seal vapor barrier penetrations by mechanical fasteners with vapor barrier adhesive.
5. Seal and smooth joints. Seal and coat transverse joints.
6. Seal and smooth joints. Seal and coat transverse joints.
7. Seal and smooth joints. Seal and coat transverse joints.
8. Seal and smooth joints. Seal and coat transverse joints.
9. Seal and smooth joints. Seal and coat transverse joints.
10. Seal and smooth joints. Seal and coat transverse joints.
11. Seal and smooth joints. Seal and coat transverse joints.
12. Seal and smooth joints. Seal and coat transverse joints.
13. Seal and smooth joints. Seal and coat transverse joints.
14. Seal and smooth joints. Seal and coat transverse joints.
15. Seal and smooth joints. Seal and coat transverse joints.
16. Seal and smooth joints. Seal and coat transverse joints.
17. Seal and smooth joints. Seal and coat transverse joints.
18. Seal and smooth joints. Seal and coat transverse joints.
19. Seal and smooth joints. Seal and coat transverse joints.
20. Seal and smooth joints. Seal and coat transverse joints.
21. Seal and smooth joints. Seal and coat transverse joints.
22. Seal and smooth joints. Seal and coat transverse joints.
23. Seal and smooth joints. Seal and coat transverse joints.
24. Seal and smooth joints. Seal and coat transverse joints.
25. Seal and smooth joints. Seal and coat transverse joints.
26. Seal and smooth joints. Seal and coat transverse joints.
27. Seal and smooth joints. Seal and coat transverse joints.
28. Seal and smooth joints. Seal and coat transverse joints.
29. Seal and smooth joints. Seal and coat transverse joints.
30. Seal and smooth joints. Seal and coat transverse joints.
31. Seal and smooth joints. Seal and coat transverse joints.
32. Seal and smooth joints. Seal and coat transverse joints.
33. Seal and smooth joints. Seal and coat transverse joints.
34. Seal and smooth joints. Seal and coat transverse joints.
35. Seal and smooth joints. Seal and coat transverse joints.
36. Seal and smooth joints. Seal and coat transverse joints.
37. Seal and smooth joints. Seal and coat transverse joints.
38. Seal and smooth joints. Seal and coat transverse joints.
39. Seal and smooth joints. Seal and coat transverse joints.
40. Seal and smooth joints. Seal and coat transverse joints.
41. Seal and smooth joints. Seal and coat transverse joints.
42. Seal and smooth joints. Seal and coat transverse joints.
43. Seal and smooth joints. Seal and coat transverse joints.
44. Seal and smooth joints. Seal and coat transverse joints.
45. Seal and smooth joints. Seal and coat transverse joints.
46. Seal and smooth joints. Seal and coat transverse joints.
47. Seal and smooth joints. Seal and coat transverse joints.
48. Seal and smooth joints. Seal and coat transverse joints.
49. Seal and smooth joints. Seal and coat transverse joints.
50. Seal and smooth joints. Seal and coat transverse joints.
51. Seal and smooth joints. Seal and coat transverse joints.
52. Seal and smooth joints. Seal and coat transverse joints.
53. Seal and smooth joints. Seal and coat transverse joints.
54. Seal and smooth joints. Seal and coat transverse joints.
55. Seal and smooth joints. Seal and coat transverse joints.
56. Seal and smooth joints. Seal and coat transverse joints.
57. Seal and smooth joints. Seal and coat transverse joints.
58. Seal and smooth joints. Seal and coat transverse joints.
59. Seal and smooth joints. Seal and coat transverse joints.
60. Seal and smooth joints. Seal and coat transverse joints.
61. Seal and smooth joints. Seal and coat transverse joints.
62. Seal and smooth joints. Seal and coat transverse joints.
63. Seal and smooth joints. Seal and coat transverse joints.
64. Seal and smooth joints. Seal and coat transverse joints.
65. Seal and smooth joints. Seal and coat transverse joints.
66. Seal and smooth joints. Seal and coat transverse joints.
67. Seal and smooth joints. Seal and coat transverse joints.
68. Seal and smooth joints. Seal and coat transverse joints.
69. Seal and smooth joints. Seal and coat transverse joints.
70. Seal and smooth joints. Seal and coat transverse joints.
71. Seal and smooth joints. Seal and coat transverse joints.
72. Seal and smooth joints. Seal and coat transverse joints.
73. Seal and smooth joints. Seal and coat transverse joints.
74. Seal and smooth joints. Seal and coat transverse joints.
75. Seal and smooth joints. Seal and coat transverse joints.
76. Seal and smooth joints. Seal and coat transverse joints.
77. Seal and smooth joints. Seal and coat transverse joints.
78. Seal and smooth joints. Seal and coat transverse joints.
79. Seal and smooth joints. Seal and coat transverse joints.
80. Seal and smooth joints. Seal and coat transverse joints.
81. Seal and smooth joints. Seal and coat transverse joints.
82. Seal and smooth joints. Seal and coat transverse joints.
83. Seal and smooth joints. Seal and coat transverse joints.
84. Seal and smooth joints. Seal and coat transverse joints.
85. Seal and smooth joints. Seal and coat transverse

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.

- K. Connect diffusers to low pressure ducts directly or with 5 feet maximum length of flexible duct held in place with strap or clamp. Longer duct lengths are acceptable if depicted on the design drawings and allowed per local code.
- L. Max fan unit V-belt or direct driven as indicated, with spun aluminum housing; resilient mounted motor; 1/2 inch mesh, 1 inch thick aluminum wire birdscreen; secure base to suit roof continuous curb gaskets.
- M. Roof Curb: 20 inch high above the finished roof surface (compensate for roof insulation thickness at fan location) self-finishing of galvanized steel or aluminum construction with continuously welded seams, built-in cast strips, insulation and factory installed roller strip.
- N. Disconnect Switch: Factory wired, non-fusible, in housing for thermal overload protection.
- O. Kitchen hood exhaust, Type 1 stainless steel for ductwork exposed to view and stainless steel or carbon steel for ducts where concealed.
- P. For all hood systems, perform all required regulatory duct leakage and weld tests in the presence of the code official, including but not limited to light tests and smoke tests, to demonstrate the integrity of the duct construction prior to the installation of any insulation that prevents visual inspection of the ductwork on all sides.
- Q. Provide residue traps in kitchen hood exhaust ducts at base of vertical risers with provisions for clean out.
- R. All roofing penetrations shall be flashed and weather sealed by the roofing contractor's authorized roofing competent at this Contractor's expense. This Contractor shall contract with the factory authorized roofing contractor for the specific roofing system applicable to this project. The use of an unauthorized roofing contractor may result in removal and replacement of the penetration systems at this Contractor's expense.

- 3.03 CLEANING
 - A. Clean duct system and force air at high velocity through duct to remove accumulated dust or clean with high power vacuum machines. To obtain sufficient air, clean half the system at a time. Protect equipment which may be harmed by excessive dirt with temporary filters, or bypass during cleaning.
- 3.04 SCHEDULES
 - A. Ductwork Material:
 - B. The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected piping material is the sole responsibility of the installing Contractor.
 1. Low Velocity Supply (System with Cooling): Galvanized Steel, Aluminum.
 2. Low Velocity Supply (System with Cooling Coils): Galvanized Steel, Aluminum.
 3. Return and Relief: Aluminum.
 4. General Exhaust: Galvanized Steel, Aluminum.
 5. Outside Air Intake: Galvanized Steel.
 6. Kitchen Hood Exhaust, Type 1: Carbon Steel, Stainless Steel, Constructed per NFPA 96.
 - C. Ductwork Pressure Class:
 1. Low Velocity Supply (Heating Systems): Scheduled System ESP+0.25", round up to next higher pressure class.
 2. Low Velocity Supply (Systems with Cooling): Scheduled System ESP +0.5", round up to next higher pressure class.
 3. Return and Relief: 1 inch.
 4. General Exhaust: Scheduled System ESP +1.0", round up to next higher pressure class.
 5. Outside Air Intake: 1 inch.
 6. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional.

END OF SECTION

SECTION 233300 - AIR DUCT ACCESSORIES

- PART 1 GENERAL
 - 1.01 SECTION INCLUDES
 - A. Air turning devices/extractors.
 - B. Volume control dampers.
 - C. Flexible duct connections.
 - D. Duct access doors.
 - PART 2 PRODUCTS
 - 2.01 AIR TURNING DEVICES/EXTRACTORS
 - A. Manufacturers: Krueger; Ruskin Company; Titus.
 - B. Multi-blade device with blades aligned; steel or aluminum construction; with individually adjustable blades, mounting straps.
 - 2.02 VOLUME CONTROL DAMPERS
 - A. Manufacturers: Louvers & Dampers, Inc.; Nalor Industries Inc.; Ruskin Company; Prefico Inc.
 - B. Fabricate in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible, and as indicated.
 - C. Single Blade Damper: Fabricate for duct sizes up to 6 x 30 inch.
 - D. Multi-Blade Damper: Fabricate for opposed blade pattern with maximum blade size 8 x 72 inch. Assemble center and edge crimped blades in prime coated or galvanized channel frame with suitable hardware.
 - E. End Bearings: Except in round ducts 12 inches and smaller, provide end bearings. On multiple blade dampers, provide oil-impregnated nylon or sintered bronze bearings.
 - F. The contractor shall provide either a mechanical or electrical cable operated system wherever dampers are located in non-accessible areas.
 1. Mechanical cable operated system shall be similar and equal to Young Regulator Company, "Bowden Cable Control" system including damper, flexible cable with coating and concealed ceiling regulator control.
 2. Electrically operated damper control system shall be similar and equal to United Erectech Corporation, "Power Balance" system including motor operated damper, Rn-11 plenum rated cabling and flush ceiling or wall mounted Rn-11 jack in remote plate. Include one hand held battery pack operator pack to be delivered to the Owner upon completion of the balancing.
 - 2.03 FLEXIBLE DUCT CONNECTIONS
 - A. Fabricate in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible, and as indicated.
 - B. Flexible Duct Connections: Fabric crimped into metal edging strip.
 1. Fabric: UL listed fire-retardant neoprene coated woven glass fiber fabric to NFPA 90A, minimum density 30 oz per sq yd.
 2. Net fabric width: Approximately 2 inches wide.
 3. Metal: 3 inches wide, 24 gage thick galvanized steel.
 - 2.04 DUCT ACCESS DOORS
 - A. Manufacturers: Acador Products Inc.; Nalor Industries Inc.; Ruskin Company; SEMCO Incorporated.
 - B. Fabricate in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible, and as indicated.
 - C. Fabrication: Rigid and close-fitting of galvanized steel with sealing gaskets and quick fastening locking devices. For insulated ducts, install minimum 1 inch thick insulation with sheet metal cover.
 1. Less than 12 inches Square: Secure with sash locks.
 2. Up to 18 inches Square: Provide two hinges and two sash locks.
 - D. Access doors with sheet metal screw fasteners are not acceptable.

AIR PURIFICATION DEVICES

- Model: PHI-PKG14-24V Specifications
- LISTING: UL 1598:2008 (3rd Edition)
- FACTORY UV-PHI 02L
- INSTALLATION: RTU PACKAGED UNIT / BLOWER CABINET
- PART 1 GENERAL
 - 1.01 SUMMARY
 - A. This section includes hydro-peroxide, Super-Oxide ions, & Hydroxide Ion's delivered via PHI technology through packaged heating and cooling units capable of supplying 3,000 to 8,000 CFM of supply air to the indoor space.
 - 1.02 QUALITY ASSURANCE
 - A. All models shall be UL listed and comply with safety standards UL 1598:2008 (3rd Edition) and CSA Standard C22.2 No. 250.0-2008.
 - 1.03 WARRANTY
 - A. All units shall be provided with the following standard warranties:
 1. 2-year or 18,000 hours from initial startup. National TAB provides service plan. The phi cell & UV light replacement 18,000 hour replacements are provide/installed at no cost if National TAB is providing Renew-CC Service after initial installation.
 2. This warranty shall not apply if:
 1. The equipment is not installed by a qualified installer per the manufacturer's installation instructions shipped with the product.
 2. The equipment is misused or neglected, or not maintained per the manufacturer's maintenance instructions.
 3. The equipment is not operated within its published capacity.
 4. The invoice is not paid within the terms of the sales agreement.

END OF SECTION

SECTION 233423 - HVAC POWER VENTILATORS

- PART 1 GENERAL
 - 1.01 SECTION INCLUDES
 - A. Roof exhausters.
 - B. Kitchen range hood exhausters.
 - PART 2 PRODUCTS
 - 2.01 MANUFACTURERS
 - A. Greenheck; Loren Cook Company; PennBray; CaptiveAir.
 - 2.02 POWER VENTILATORS - GENERAL
 - A. Performance Ratings: Determined in accordance with AMCA 210 and bearing the AMCA Certified Rating Seal.
 - B. Sound Ratings: AMCA 301, tested to AMCA 300, and bearing AMCA Certified Sound Rating Seal.
 - C. Fabrication: Conform to AMCA 99.

END OF SECTION

SECTION 233743 - PACKAGED OUTDOOR ROOF TOP UNITS - GAS FIRED

- PART 1 GENERAL
 - 1.01 SECTION INCLUDES
 - A. Packaged roof top units.
 - B. Thermostat control.
 - C. Roof mounting curb and base.
 - D. Power exhaust.
 - PART 2 PRODUCTS
 - 2.01 MANUFACTURERS
 - A. Carrier Corporation; Trane Inc.; Lennox Industries; York; AAOB Incorporated.
 - 2.02 AIR CONDITIONING UNITS
 - A. General: Roof mounted units having gas burner and electric refrigeration.
 - B. Description: Self-contained, packaged, factory assembled and pre-wired, consisting of cabinet and frame, supply fan, heat exchanger and burner, controls, air filters, refrigerant cooling coil and compressor, dry bulb economizer and power exhaust fan where indicated on the Drawings, condenser coil and condenser fan.
 - C. Electrical Characteristics: As scheduled on the Drawings.
 - D. Disconnect Switch: Factory mount disconnect switch on equipment.
 - 2.03 FABRICATION
 - A. Cabinet: Steel with baked enamel finish, including access panels with screwdriver operated flush cam type fasteners or doors with piano hinges with locking handles. Structural members shall be minimum 18 gage, with access doors or panels of minimum 20 gage.
 - B. Insulation: one inch thick neoprene coated glass fiber with edges protected from erosion.
 - C. Heat Exchangers: Aluminumized steel or stainless steel where indicated on the Drawings, of welded construction.
 - D. Supply Fan: Forward curved centrifugal type, resiliently mounted with V-belt drive, adjustable variable pitch motor pulley, and rubber isolated hinge-mount motor or direct drive as indicated, include complete fan assembly.
 1. Fans for units with a mechanical cooling capacity greater than or equal to 65,000 Btu/h shall have not fewer than two stages of fan control.
 - E. Air Filters: 2 inch thick disposable media in metal frames.
 - F. Roof Mounting Curb: Galvanized steel, channel frame, insulated with gaskets, roller strips, damper roof curb of adequate height to provide a unit mounting height of 12" or greater above the top of the roof surface with the curb mounted to the building structure. Roof curb height must compensate for the roof insulation thickness to meet this requirement.
 - 2.04 BURNER
 - A. Gas Burner: Induced draft or forced draft type burner with adjustable combustion air supply, pressure regulator, gas valves, manual shut-off intermittent spark or glow coil ignition, flame sensing device, and automatic 100 percent shut-off pilot.
 - B. Gas Burner Safety Controls: Energize ignition, limit time for establishment of flame, prevent opening of gas valve until pilot flame is proven, stop gas flow on ignition failure, energize blower motor, and offer air flow proven and slight delay allow gas valve to open.
 - C. High Limit Control: Temperature sensor with fixed spot at maximum permissible setting, de-energize burner on excessive burner temperature and energize burner when temperature drops to lower safety limit on operation.
 - D. Supply Fan Control: Temperature sensor sensing burner temperatures and independent of burner controls, with provisions for continuous fan operation.
 - 2.05 EVAPORATOR COIL
 - A. Provide copper tube aluminum fin coil assembly with galvanized drain pan and connection.
 - B. Provide capillary tubes or thermostatic expansion valves for all of 1 tons capacity and less, and thermostatic expansion valves and alternate row circuiting for units 7.5 tons cooling capacity and larger.
 - 2.06 COMPRESSOR
 - A. Provide hermetic or semi-hermetic compressors, 3600 rpm maximum, resiliently mounted with positive lubrication, crankcase heater, high and low pressure safety controls, motor overload protection, suction and discharge service valves and gage ports, and filter drier.
 - B. Five minute timed off circuit to delay compressor start.
 - C. Outdoor thermostat to energize compressor above 35 degrees F ambient.
 - 2.07 CONDENSER COIL
 - A. Provide copper tube aluminum fin coil assembly with subcooling rows and coil guard.
 - B. Provide direct drive propeller fans, resiliently mounted with fan guards, motor overload protection, wired to operate with compressor.
 - 2.08 MIXED AIR CONTROL
 - A. Dampers: Provide outside, return, and relief dampers with damper operator and control package to automatically vary outside air quantity. Outside air damper to fall to closed position. Relief dampers may be gravity balanced.
 - B. Gaskets: Provide tight fitting dampers with edge gaskets maximum leakage 5 percent at 2 inches pressure differential.
 - C. Damper Operator: 24 volt with gear train sealed in oil.
 - D. Damper Operator, Units 7.5 Ton Cooling Capacity and Larger: 24 volt with gear train sealed in oil with spring return on.

- D. UL Compliance: UL listed and labeled, designed, manufactured, and tested as suitable for the purpose specified and indicated.
- 2.03 ROOF EXHAUSTERS AND VENTILATORS
 - A. Fan Unit: V-belt or direct driven as indicated, with spun aluminum housing; resilient mounted motor; 1/2 inch mesh, 1 inch thick aluminum wire birdscreen; secure base to suit roof continuous curb gaskets.
 - B. Roof Curb: 20 inch high above the finished roof surface (compensate for roof insulation thickness at fan location) self-finishing of galvanized steel or aluminum construction with continuously welded seams, built-in cast strips, insulation and factory installed roller strip.
 - C. Disconnect Switch: Factory wired, non-fusible, in housing for thermal overload protection.
 - D. Backdraft Damper: Motor actuated (or gravity damper if depicted on design drawings), aluminum multiple blade construction, felt edged with offset hinge pin, nylon bearings, blades linked, and line voltage motor drive, power open, spring return.
 - E. Shafts: Cast iron or steel, dynamically balanced, bored to fit shafts and keyed; variable and adjustable pitch motor shafts selected so required rpm is obtained with sheaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings.
 - F. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall metal curb adopter base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.

PART 3 EXECUTION

- 3.01 INSTALLATION
 - A. Install in accordance with manufacturer's instructions.
 - B. Provide sheaves required for final air balance at no additional expense to the project.
 - C. Secure roof and wall exhausters with cadmium plated steel lag screws to roof curb or structure.
 - D. Extend ducts to roof and wall exhausters into roof curb or wall structure.
 - E. Counterflash duct to roof or wall opening.
 - F. Install backdraft dampers (gravity or motorized as depicted on design drawings) on ducts to roof and wall exhausters.
 - G. All roofing penetrations shall be flashed and weather sealed by the roofing manufacturer's authorized roofing contractor at this Contractor's expense. This Contractor shall contract with the factory authorized roofing contractor for the specific roofing system applicable to this project. The use of an unauthorized roofing contractor may result in removal and replacement of the penetration systems at this Contractor's expense.

END OF SECTION

SECTION 233700 - AIR OUTLETS AND INLETS

- PART 1 GENERAL
 - 1.01 SECTION INCLUDES
 - A. Rectangular ceiling diffusers.
 - B. Perforated face ceiling diffusers.
 - C. Grid core exhaust and return grilles.
 - D. Wall registers and grilles.
 - 1.02 SUBMITTALS
 - A. Product Data: Provide data for equipment required for this project. Review outlets and inlets as to size, finish, and type of mounting prior to submission. Submit schedule of outlets and inlets showing type, size, location, application, accessories, and noise level.
 - 1.03 QUALITY ASSURANCE
 - A. Test and rate air outlet and inlet performance in accordance with ASHRAE Std 70.
 - B. Test and rate lower performance in accordance with AMCA 500-L.
 - C. Code requirements shall supersede any conflicting requirements of this Section.
 - 1.04 QUALIFICATIONS
 - A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this Section, with minimum five years of documented experience.

PART 2 PRODUCTS

- 2.01 MANUFACTURERS
 - A. Tlusa; Kuemper; Price Industries; Nalor Industries Inc.; Hart & Cooley; Ruskin; Greenheck.
- 2.02 RECTANGULAR CEILING DIFFUSERS
 - A. Type: Square, adjustable pattern, stamped, multi-cell, or architectural plaque diffuser to discharge air in 360 degree pattern with sectorizing baffles where indicated.
 - B. Frame: Inverted T-bar type. In plaster ceilings, provide plaster frame and ceiling frame. (To allow lift-out removal of the diffuser without removal of the plaster frame.)
 - C. Fabrication: Steel with baked enamel off-white finish.
 - D. Accessories: Opposed blade damper and multi-louvered equalizing grid with damper adjustable from diffuser face.
- 2.03 PERFORATED FACE CEILING DIFFUSERS
 - A. Type: Perforated face with removable face.
 - B. Frame: Inverted T-bar type. In plaster ceilings, provide plaster frame and ceiling frame. (To allow lift-out removal of the diffuser without removal of the plaster frame.)
 - C. Fabrication: Steel with steel frame and baked enamel off-white finish.
 - D. Accessories: Opposed blade damper and multi-louvered equalizing grid with damper adjustable from diffuser face.
- 2.04 GRID CORE EXHAUST AND RETURN GRILLES
 - A. Type: Fixed grilles of 1/2 x 1/2 x 1 inch louvers.
 - B. Fabrication: Aluminum with factory off-white enamel finish.
 - C. Frame: 1-1/4 inch margin with countersunk screw mounting.
 - D. Frame: Channel lay-in frame for suspended grid ceilings where face size exceeds 18 x 18 inch.
 - E. Damper (if specified on drawings): Integral, gang-operated, opposed blade type with removable key operator, operable from face.
- 2.05 WALL SUPPLY REGISTERS/GRILLES
 - A. Type: Streamlined and individually adjustable blades, 3/4 inch minimum depth, 3/4 inch maximum spacing with spring or other device to set blades, horizontal, double deflection.
 - B. Frame: 1-1/4 inch margin with countersunk screw mounting and gasket.
 - C. Fabrication: Steel with 20 gage minimum frames and 22 gage minimum blades, steel and aluminum with 20 gage minimum frame, or aluminum extrusions, with factory off-white enamel finish.
 - D. Damper: Integral, gang-operated opposed blade type with removable key operator, operable from face.
 - E. Rough Surface: Provide front pivoted or welded in place blades, securely fastened to be immovable.

PART 3 EXECUTION

- 3.01 INSTALLATION
 - A. Install in accordance with manufacturer's instructions.
 - B. Check location of outlets and inlets and make necessary adjustments in position to conform with architectural features, symmetry, and lighting arrangement.
 - C. Install diffusers to ductwork with air tight connection.
 - D. Provide balancing dampers on duct take-off to diffusers, and grilles and registers, despite whether dampers are specified as part of the diffuser, or grille or register assembly.
 - E. Point ductwork visible behind air outlets and inlets matte black.

END OF SECTION

SECTION 237415 - PACKAGED OUTDOOR ROOF TOP UNITS - GAS FIRED

- PART 1 GENERAL
 - 1.01 SECTION INCLUDES
 - A. Packaged roof top units.
 - B. Thermostat control.
 - C. Roof mounting curb and base.
 - D. Power exhaust.
 - PART 2 PRODUCTS
 - 2.01 MANUFACTURERS
 - A. Carrier Corporation; Trane Inc.; Lennox Industries; York; AAOB Incorporated.
 - 2.02 AIR CONDITIONING UNITS
 - A. General: Roof mounted units having gas burner and electric refrigeration.
 - B. Description: Self-contained, packaged, factory assembled and pre-wired, consisting of cabinet and frame, supply fan, heat exchanger and burner, controls, air filters, refrigerant cooling coil and compressor, dry bulb economizer and power exhaust fan where indicated on the Drawings, condenser coil and condenser fan.
 - C. Electrical Characteristics: As scheduled on the Drawings.
 - D. Disconnect Switch: Factory mount disconnect switch on equipment.
 - 2.03 FABRICATION
 - A. Cabinet: Steel with baked enamel finish, including access panels with screwdriver operated flush cam type fasteners or doors with piano hinges with locking handles. Structural members shall be minimum 18 gage, with access doors or panels of minimum 20 gage.
 - B. Insulation: one inch thick neoprene coated glass fiber with edges protected from erosion.
 - C. Heat Exchangers: Aluminumized steel or stainless steel where indicated on the Drawings, of welded construction.
 - D. Supply Fan: Forward curved centrifugal type, resiliently mounted with V-belt drive, adjustable variable pitch motor pulley, and rubber isolated hinge-mount motor or direct drive as indicated, include complete fan assembly.
 1. Fans for units with a mechanical cooling capacity greater than or equal to 65,000 Btu/h shall have not fewer than two stages of fan control.
 - E. Air Filters: 2 inch thick disposable media in metal frames.
 - F. Roof Mounting Curb: Galvanized steel, channel frame, insulated with gaskets, roller strips, damper roof curb of adequate height to provide a unit mounting height of 12" or greater above the top of the roof surface with the curb mounted to the building structure. Roof curb height must compensate for the roof insulation thickness to meet this requirement.
 - 2.04 BURNER
 - A. Gas Burner: Induced draft or forced draft type burner with adjustable combustion air supply, pressure regulator, gas valves, manual shut-off intermittent spark or glow coil ignition, flame sensing device, and automatic 100 percent shut-off pilot.
 - B. Gas Burner Safety Controls: Energize ignition, limit time for establishment of flame, prevent opening of gas valve until pilot flame is proven, stop gas flow on ignition failure, energize blower motor, and offer air flow proven and slight delay allow gas valve to open.
 - C. High Limit Control: Temperature sensor with fixed spot at maximum permissible setting, de-energize burner on excessive burner temperature and energize burner when temperature drops to lower safety limit on operation.
 - D. Supply Fan Control: Temperature sensor sensing burner temperatures and independent of burner controls, with provisions for continuous fan operation.
 - 2.05 EVAPORATOR COIL
 - A. Provide copper tube aluminum fin coil assembly with galvanized drain pan and connection.
 - B. Provide capillary tubes or thermostatic expansion valves for all of 1 tons capacity and less, and thermostatic expansion valves and alternate row circuiting for units 7.5 tons cooling capacity and larger.
 - 2.06 COMPRESSOR
 - A. Provide hermetic or semi-hermetic compressors, 3600 rpm maximum, resiliently mounted with positive lubrication, crankcase heater, high and low pressure safety controls, motor overload protection, suction and discharge service valves and gage ports, and filter drier.
 - B. Five minute timed off circuit to delay compressor start.
 - C. Outdoor thermostat to energize compressor above 35 degrees F ambient.
 - 2.07 CONDENSER COIL
 - A. Provide copper tube aluminum fin coil assembly with subcooling rows and coil guard.
 - B. Provide direct drive propeller fans, resiliently mounted with fan guards, motor overload protection, wired to operate with compressor.
 - 2.08 MIXED AIR CONTROL
 - A. Dampers: Provide outside, return, and relief dampers with damper operator and control package to automatically vary outside air quantity. Outside air damper to fall to closed position. Relief dampers may be gravity balanced.
 - B. Gaskets: Provide tight fitting dampers with edge gaskets maximum leakage 5 percent at 2 inches pressure differential.
 - C. Damper Operator: 24 volt with gear train sealed in oil.
 - D. Damper Operator, Units 7.5 Ton Cooling Capacity and Larger: 24 volt with gear train sealed in oil with spring return on.

- E. Mixed Air Controls: Maintain selected supply air temperature and return dampers to minimum position on coil for heating and above 75 degrees F ambient, or when ambient air temperature exceeds return air temperature.
- 2.09 INTEGRATED ECONOMIZER
 - A. Economizer shall be furnished and installed complete with outside air and relief dampers and controls.
 - B. Provide low-leakage, opposed blade dampers.
 - C. Meet leakage requirements of applicable energy code.
 - C. Economizer shall be capable of introducing up to 100% outdoor air for minimum ventilation or for free cooling.
 - D. Damper actuator shall be electronic, fully modulating design.
 - E. Economizer outdoor hood shall be pre-painted and fully integrated with the unit.
 - F. Dry Bulb Control: Provide dry bulb sensor capable of measuring temperature of outdoor air and controlling economizer cut-in point at the most economical level. High level cutoff shall be set per applicable energy code.
 - G. Provide economizer Fault Detection and Diagnostics (FDD).

- 2.10 POWER EXHAUST
 - A. Package shall include exhaust fan(s) and damper for units with economizer to control over-pressurization of building including integral pressure controls.
- 2.11 WATER LEVEL MONITORING DEVICE
 - A. A water-level monitoring device shall be installed inside the primary drain pan. This device shall shut off the equipment served in the event that the primary drain becomes restricted. Devices installed in the drain line shall not be permitted.

PART 3 EXECUTION

- 3.01 OPERATING CONTROLS
 - A. Provide low voltage, adjustable thermostat to control heater stages in sequence with delay between stages, compressor and condenser fan, and supply fan to maintain temperature setting.
 1. Include system selector switch (heat-off-auto-cool) and fan control switch (auto-on).
 2. The Mechanical Contractor shall provide all control wiring between thermostat and unit control panel and any required remote sensors.
 3. Locate thermostat in room as shown.
 4. Electric solid state microcomputer based room thermostat, located as indicated. Provide remote sensor when indicated on the Drawings.
 - a. Room thermostat shall incorporate:
 1. Automatic switching from heating to cooling.
 2. Preferential rate control to minimize overshoot and deviation from set point.
 3. Automatic Start Capabilities: Controls shall be capable of automatically adjusting the daily start time of the HVAC system in order to bring each space to the desired occupied temperature immediately prior to scheduled occupancy.
 4. Set-up for four separate temperatures per day.
 5. Instant override of set point for continuous or timed period from one hour to 31 days.
 6. Short cycle protection.
 7. Programming based on every day of the week.
 8. Selection features including degree F or degree C display, 12 or 24 hour clock, keyboard dial, remote sensor, fan on-auto.
 - b. Room thermostat display shall include:
 1. Time of day.
 2. Actual room temperature.
 3. Programmed temperature.
 4. Day of week.
 5. System mode indication: heating, cooling, auto, off, fan auto, on-off.

PART 3 EXECUTION

- 3.01 INSTALLATION
 - A. Install in accordance with manufacturer's instructions and NFPA 90A.
 - B. Mount units on factory built roof mounting curb providing weathertight enclosure to protect ductwork and utility services. Install roof mounting curb level, install roof mounting curb, so that it bears on the building structure, not on top of the roof load or roofing materials. Provide restraints where required by local code.
 - C. Provide cooling condensate drain piping (and overflow piping if required) to approved location. Condensate piping shall be Schedule 40 galvanized steel pipe, Type L copper tube, or PVC. Contractor shall verify the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected piping material is the sole responsibility of the installing Contractor.
 1. Condensate piping located within the building shall be insulated with 1/2 inch thick glass wool or flexible elastomeric cellular foam insulation. Only metallic piping systems will be allowed in return air plenum ceiling space.

END OF SECTION

SECTION 238127 - SMALL SPLIT-SYSTEM HEATING AND COOLING

- PART 1 GENERAL
 - 1.01 SECTION INCLUDES
 - A. Air-source heat pumps.
 - B. Indoor ductless fan & coil units.
 - C. Controls.
 - PART 2 PRODUCTS
 - 2.01 MANUFACTURERS
 - A. Carrier Corporation; Trane Inc.; YORK; Lennox Industries.
 - 2.02 SYSTEM DESIGN
 - A. Split-System Heating and Cooling Units: Self-contained, packaged, matched factory-engineered and assembled, pre-wired indoor and outdoor units; UL listed.
 1. Provide refrigerant lines internal to units and between indoor and outdoor units, factory cleaned, dried, pressurized and sealed, with insulated suction line. Size as recommended by the manufacturer. All refrigerant line sizes indicated on the Drawings are approximate and shall be adjusted as required based on the actual equipment provided to meet the manufacturer's recommended line sizing at no additional expense.
 2. Performance Requirements:
 1. Equipment performance, efficiency and accessories shall be as scheduled on the Drawings and specified herein. Inclusion in both locations is not a prerequisite to inclusion in the Contract. Equipment and accessories specified in either location shall be included in the Contract. Provide all necessary accessories and connections as required for a complete, functional system. Efficiency shall not be less than requirements of the applicable energy code specified or indicated on the drawings, or the applicable local energy code.


PART 3 EXECUTION

- 3.01 INDOOR UNITS FOR DUCTLESS SYSTEMS
 - A. Indoor Units: Self-contained, packaged, factory assembled, pre-wired unit consisting of cabinet, supply fan, evaporator coil, and controls; wired for single power connection with control transformer.
 - B. Evaporator Coils: Copper tube aluminum fin assembly, galvanized or polymer drain pan sloped in all directions to drain, drain connection, refrigerant piping connections, restricted distributor or thermostatic expansion valve. Construction and Ratings: in accordance with ARI 210/240 and UL listed.
- 3.02 OUTDOOR UNITS
 - A. Outdoor Units: Self-contained, packaged, factory assembled, pre-wired unit consisting of cabinet, with compressor and condenser, fan, and controls.
 1. Cabinet: Steel with baked enamel finish, easily removed and secured access doors with safety interlock switches, glass fiber insulation with reflective liner.
 2. Construction and Ratings: in accordance with ARI 210/240 with testing in accordance with ASHRAE Std 23 and UL listed.
 - B. Compressor: ARI 520; hermetic, 3600 rpm, (multi-speed when indicated on the Drawings) resiliently mounted integral with condenser, with positive lubrication; crankcase heater, high pressure control, motor overload protection, service valves and gage ports. Provide time delay circuit to prevent start cycling.
 - C. Air Cooled Condenser: ARI 520; Aluminum fin and copper tube coil, with direct air-side propeller fan resiliently mounted, galvanized fan guard.
 - D. Accessories: Filter drier, high pressure switch (manual reset), low pressure switch (automatic reset), service valves and gage ports, thermometer well (in liquid line).
 - E. Provide thermostatic expansion valves.
 - F. Provide heat pump reversing valves on all heat pump units.
- 3.03 OPERATING CONTROLS
 - 1. Control by room thermostat to maintain room temperature setting.
 - 2. Low Ambient Kit: On all systems not provided with economizer controls, provide refrigerant pressure switch to cycle condenser fan when condenser refrigerant pressure is above 295 psig and off when pressure drops below 140 psig for operation to 0 degrees F.
 - F. Mounting Feet: Poured in place concrete, precast concrete or resin composite pad, minimum 4 inches thick, square.
- 2.05 ACCESSORY EQUIPMENT
 - A. Room Thermostat: Wall-mounted, electric solid state microcomputer based room thermostat with remote sensor to maintain temperature setting; low-voltage; with following features:
 1. System selector switch (heat-off-cool) and fan control switch (auto-on).
 2. Automatic switching from heating to cooling.
 3. Preferential rate control to minimize overshoot and deviation from setpoint.
 4. Automatic Start Capabilities: Controls shall be capable of automatically adjusting the daily start time of the HVAC system in order to bring each space to the desired occupied temperature immediately prior to scheduled occupancy.
 5. Set-up for four separate temperatures per day.
 6. Instant override of setpoint for continuous or timed period from one hour to 31 days.
 7. Short cycle protection.
 8. Programming based on every day of the week.
 9. Selection features including degree F or degree C display, 12 or 24 hour clock, keyboard dial, remote sensor, fan on-auto.
 10. Battery replacement without program loss.
 11. Thermostat display shall include:
 - a. Time of day.
 - b. Actual room temperature.
 - c. Programmed temperature.
 - d. Day of week.
 - e. System mode indication: heating, cooling, fan auto, off, and on, auto or on, off.

PART 3 EXECUTION

- 3.01 INSTALLATION
 - A. Install in accordance with manufacturer's instructions and requirements of local authorities having jurisdiction.
 - B. Install in accordance with NFPA 90A and NFPA 90B as applicable.
 - C. Provide cooling condensate drain piping (and overflow piping if required) to approved location. Condensate piping shall be Schedule 40 galvanized steel pipe, Type L copper tube, or PVC pipe (non-plenum applications). Contractor shall verify the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected piping material is the sole responsibility of the installing Contractor. Only metallic piping systems will be allowed in return air plenum ceiling space.
 - D. Install refrigeration systems in accordance with ASHRAE Std 15. Provide filter drier, sight glass and solenoid valve on outdoor units and sight glass and expansion valve on indoor units.
 - E. All thermostat, humidifier (if required), damper interlock and other low voltage control wiring shall be installed by the Mechanical Contractor. The Electrical Contractor will furnish only the power system connections shown on the Electrical Drawings. All other control and interlock wiring is the responsibility of the Mechanical Contractor.

END OF SECTION



Schnackel engineers logo and contact information: New York • Miami • Charlotte • Los Angeles • Seattle • Honolulu. 800-581-0963 www.schnackel.com

Seal

| ROOM # | NAME | Az AREA (FT ²) | TABLE 403.3.1.1 OCCUPANCY CATEGORY | TABLE 403.3.1.1 Rp PEOPLE DA (CFM/PER) | TABLE 403.3.1.1 Ra AREA DA (CFM/FT ²) | TABLE 403.3.1.1 OCCUPANT DENSITY (#/1000 FT ²) | Pz (#) | Rv/Pz | Rv/Az | Vbz (CFM) | TABLE 403.3.1.1.1.2 Ez | Voz (CFM) | Vpz MAX SUPPLY (CFM) | Vpzm MIN SUPPLY (CFM) | Zp | CALCULATED TABLE 403.3.1.1.2.3.2 Ev |
|--------|-----------------|----------------------------|------------------------------------|--|---|--|--------|-------|-------|-----------|------------------------|-----------|----------------------|-----------------------|-------|-------------------------------------|
| 101 | DINING | 1,101 | DINING ROOMS | 7.5 | 0.18 | 70 | 78 | 648 | 158 | 783 | 0.80 | 679 | 3400 | 3400 | 0.288 | 0.86 |
| 102 | HALLWAY | 70 | CORRIDORS | 0.0 | 0.06 | 0 | 0 | 0 | 4 | 4 | 0.80 | 5 | 0 | 0 | 0.000 | 1.00 |
| 103 | UNISEX RESTROOM | 81 | NO LISTING | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0.80 | 0 | 50 | 50 | 0.000 | 1.00 |
| 104 | UNISEX RESTROOM | 86 | NO LISTING | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0.80 | 0 | 50 | 50 | 0.000 | 1.00 |
| 105 | KITCHEN | 615 | NO LISTING | 0.0 | 0.00 | 0 | 6 | 0 | 0 | 0 | 0.80 | 0 | 2610 | 2610 | 0.000 | 1.00 |
| 106 | BOH | 878 | NO LISTING | 0.0 | 0.00 | 0 | 5 | 0 | 0 | 0 | 0.80 | 0 | 700 | 700 | 0.000 | 1.00 |
| 107 | DISH | 140 | NO LISTING | 0.0 | 0.00 | 0 | 1 | 0 | 0 | 0 | 0.80 | 0 | 700 | 700 | 0.000 | 1.00 |
| 108 | OFFICE | 83 | OFFICE SPACES | 5.0 | 0.06 | 5 | 2 | 10 | 5 | 15 | 0.80 | 10 | 450 | 450 | 0.038 | 1.00 |
| | | 2,764 | | | | | 92 | 166 | 207 | 802 | | 1093 | 8000 | 8000 | 0.288 | 0.86 |

OUTDOOR AIR CALCULATIONS PER EQUATION 4-1:

SYMBOL VALUE DESCRIPTION

Pa = 82 SYSTEM POPULATION

SPz = 82 ZONE POPULATION

D = 1.000 OCCUPANT DIVERSITY

Voz = 802 UNCORRECTED OUTDOOR AIR INTAKE

Zp (ftmax) = 0.288 ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)

Ev = 0.86 SYSTEM VENTILATION EFFICIENCY

SVpz = 8000 ZONE PRIMARY AIRFLOW

Voz = 931 CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM

Voz = 2,700 DESIGN OUTDOOR AIRFLOW RATE, CFM

1 OUTSIDE AIR CALCULATIONS

| SETPOINT/CONTROL | RTU-1 DINING | RTU-2 KITCHEN | FC-1 OFFICE |
|--|--------------|---------------|-------------|
| *SETPOINTS* | | | |
| COOLING - OCCUPIED SETPOINT | 75 F | 75 F | 75 F |
| COOLING - UNOCCUPIED SETPOINT | 80 F | 80 F | 80 F |
| HEATING - OCCUPIED SETPOINT | 70 F | 70 F | 70 F |
| HEATING - UNOCCUPIED SETPOINT | 60 F | 60 F | 60 F |
| ECONOMIZER UPPER LIMIT SETPOINT | 65 F | 65 F | NA |
| *ACCESSORIES* | | | |
| HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT | YES | YES | YES |
| REMOTE TEMPERATURE SENSOR | YES | YES | NO |
| MOTORIZED OUTDOOR AIR DAMPER | YES | YES | NO |
| INTEGRATED ECONOMIZER | YES | YES | NO |
| ECONOMIZER FAULT DETECTION | YES | YES | NO |
| BAROMETRIC RELIEF | YES | NO | NO |
| POWERED EXHAUST RELIEF | NO | YES | NO |
| DEHUMIDIFICATION (HOT GAS REHEAT) | YES | YES | NO |
| *SUPPLY FAN* | | | |
| ON DURING OCCUPIED MODE | YES | YES | YES |
| VARIABLE VOLUME - MODULATE FAN SPEED | YES | YES | YES |
| *SAFETIES AND INTERLOCKS* | | | |
| RETURN AIR SMOKE DETECTOR | YES | YES | NO |
| LOW LIMIT FREEZESTAT | YES | YES | YES |
| FIRE ALARM CONTROL PANEL INTERLOCK | YES | YES | NO |
| KITCHEN EXHAUST SYSTEM INTERLOCK | YES | YES | NO |

| EQUIPMENT TAG | SUPPLY AIRFLOW (CFM) | OUTDOOR AIRFLOW (CFM) | RETURN AIRFLOW (CFM) | EXHAUST AIRFLOW (CFM) | OA/SA (%) | REMARKS |
|---|----------------------|-----------------------|----------------------|-----------------------|-----------|-----------|
| RTU-1 | 3,500 | 950 | 2,550 | | 27% | FOH |
| RTU-2 | 4,000 | 1,750 | 2,250 | | 44% | KITCHEN |
| FC-1 | 440 | 0 | 440 | | 0% | OFFICE |
| EF-1 | | | | 1,200 | | HOOD-1 |
| EF-2 | | | | 860 | | HOOD-2 |
| EF-3 | | | | 200 | | RESTROOMS |
| TOTAL = | 7,940 | 2,700 | 5,240 | 2,260 | | |
| RESULTING BUILDING PRESSURIZATION = 440 CFM | | | | | | |
| PRESSURIZATION PERCENTAGE = 5.5 % | | | | | | |

CARRIER EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. CONTACT CARRIER CORPORATION FOR PROPOSALS:

KEN REVILLA
CARRIER RETAIL STRATEGIC ACCOUNTS
EMAIL: KEN.REVILLA@CARRIER.COM
PHONE: (954) 218-0070

| MARK | LENGTH (N) | AIRFLOW (CFM) | HEATER | | FANS | | ELECTRICAL | | MANUFACTURER | MODEL NUMBER | REMARKS | | |
|------|------------|---------------|---------|-----------|------|----|---------------|------|--------------|--------------|---------|--------|-----|
| | | | IN (KW) | OUT (MBH) | QTY | HP | CIRCUIT (QTY) | VOLT | | | | PH | |
| AC-1 | 36.0 | 1,379 | NA | NA | NA | 1 | 1/2 | 1 | 115 | 1 | MARS | STD236 | 1-4 |

REMARKS:

- PROVIDE AUTOMATIC DOOR SWITCH.
- PROVIDE UNIT MOUNTED CONTROL PANEL.
- VERIFY FINAL COLOR/FINISH WITH ARCHITECT.
- FIELD VERIFY AND PROVIDE MOUNTING BRACKETS AS REQUIRED.

| MARK | SERVICE | LOCATION | CEILING TYPE | MOUNTING TYPE | MANUFACTURER | MODEL NUMBER | REMARKS |
|------|---------|----------|--------------|---------------|--------------|--------------------|-----------|
| D-1 | SUPPLY | CEILING | AC TILE | LAY-IN | TITUS | TMS XX 24x24 3 26 | 1,2,6 |
| D-2 | SUPPLY | CEILING | AC TILE | LAY-IN | TITUS | PAR XX 24x24 3 26 | 1,2,6 |
| D-3 | SUPPLY | DUCT | NA | SURFACE | TITUS | 300RL X X 1 26 | 1,5,6 |
| D-4 | SUPPLY | CEILING | AC TILE | LAY-IN | TITUS | OMNI XX 12x12 3 26 | 1,2,4,5,7 |
| G-1 | RETURN | CEILING | AC TILE | LAY-IN | TITUS | 50F X X 3 26 | 1,3,5,6 |
| G-2 | EXHAUST | CEILING | GYP. BOARD | SURFACE | TITUS | 50F X X 3 26 | 1,3-7 |

REMARKS:

- TITUS IS THE BASE OF DESIGN. KRUEGER, PRICE, NAILOR, CARNES ARE EQUAL. NO EXCEPTIONS.
- SEE PLAN FOR NECK SIZE.
- PROVIDE 1/2" X 1/2" X 1" CORE.
- PROVIDE WITH MODEL TRM FRAME.
- SEE PLAN FOR SIZE.
- DIFFUSERS/GRILLES SHALL BE FINISHED TO MATCH CEILING/WALL/EXPOSED DUCT COLOR. COORDINATE WITH ARCHITECT.
- PROVIDE DIFFUSERS AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.

| MARK | LOCATION | SERVICE | AIRFLOW (CFM) | EXTERNAL STATIC (IN H2O) | SONES | MOTOR DATA | | RPM | FEI | MANUFACTURER | MODEL NUMBER | REMARKS | |
|------|----------|-----------|---------------|--------------------------|-------|------------|---------|-----|-------|--------------|--------------|---------|-----|
| | | | | | | FAN (HP) | VOLT PH | | | | | | |
| EF-1 | ROOF | HOOD-1 | - | - | - | - | - | - | - | CAPTIVEAIRE | - | 4 | |
| EF-2 | ROOF | HOOD-2 | - | - | - | - | - | - | - | CAPTIVEAIRE | - | 4 | |
| EF-3 | ROOF | RESTROOMS | 200 | 0.50 | 6.8 | 1/8 | 115 | 1 | 1,550 | NA | GREENHECK | G-095-D | 1-3 |

REMARKS:

- PROVIDE SOLID STATE SPEED CONTROL.
- PROVIDE MOTORIZED BACKDRAFT DAMPER.
- PROVIDE MINIMUM 12 INCH HEIGHT ROOF CURB.
- REFERENCE CAPTIVEAIRE DRAWINGS FOR ADDITIONAL INFORMATION.

| MARK | COOLING | | HEATING | | SUPPLY AIR (CFM) | EXT. S.P. (IN) | FAN BHP | ELECTRICAL | | WEIGHT (LBS) | SEER | EER | IEER | REFRIG TYPE | CAPTIVEAIRE MODEL | REMARKS |
|-------|-----------|-----------|----------|-----------|------------------|----------------|---------|------------|----|--------------|------|-----|------|-------------|-------------------|---------|
| | SEN (MBH) | TOT (MBH) | IN (MBH) | OUT (MBH) | | | | VOLT | PH | | | | | | | |
| RTU-1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 1,2 |
| RTU-2 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 1,2 |

CAPTIVEAIRE IS THE BASIS OF DESIGN. NO EXCEPTIONS.

COOLING CAPACITIES ARE BASED ON AHRI STANDARD 210/240 OR 340/360: 80F DB/ 67F WB INDOOR ENTERING AIR TEMPERATURE. 95F DB AIR ENTERING OUTDOOR FAN. SCHEDULED UNIT MAY DIFFER FROM AHRI STANDARD CFM.

REFER TO THE ELECTRICAL ONE LINE DIAGRAM AND PANEL SCHEDULES FOR AVAILABLE FAULT CURRENT AT UPSTREAM PANELBOARD.

2. REFERENCE CAPTIVEAIRE DRAWINGS FOR ADDITIONAL INFORMATION.

| MARK | NOMINAL (TONS) | COOLING | | HEATING | | SUPPLY AIR (CFM) | FAN (WATT) | ELECTRICAL | | SEER2 | EER2 | IEER | HSPF2 | COP | REFRIG TYPE | MANUFACTURER | MODEL NUMBER | REMARKS |
|------|----------------|-----------|-----------|-----------|----------|------------------|------------|------------|-----|-------|------|------|-------|-------|-------------|--------------|--------------|---------|
| | | TOT (MBH) | SEN (MBH) | OUT (MBH) | IN (MBH) | | | VOLT | PH | | | | | | | | | |
| FC-1 | 3/4 | 9.00 | NA | 10.00 | 440 | 45 | 208 | 1 | 3.0 | NA | 26 | 14.9 | NA | R454B | CARRIER | 45MAHA009 | 1-3 | |

CARRIER IS THE BASIS OF DESIGN. NO EXCEPTIONS.

REMARKS:

- INDOOR UNIT POWER PROVIDED FROM OUTDOOR UNIT.
- PROVIDE NEW, WIRED, FULLY DIGITAL, 7 DAY PROGRAMMABLE TYPE THERMOSTAT WITH AUTO CHANGE OVER AND AUTO SET BACK.
- PROVIDE MICROBLUE CONDENSATE PUMP. COORDINATE WITH OTHER TRADES AS REQUIRED.


| MARK | LOCATION | SERVES | NOMINAL COOL (TONS) | HEATING AT 47F (MBH) | ELECTRICAL | | SEER2 | EER2 | IEER | HSPF2 | COP | REFRIG TYPE | MANUFACTURER | MODEL NUMBER | REMARKS | | |
|--------|----------|--------|---------------------|----------------------|------------|----|-------|------|------|-------|-----|-------------|--------------|--------------|---------|-----------|-----|
| | | | | | VOLT | PH | | | | | | | | | | | |
| ASHP-1 | ROOF | FC-1 | 3/4 | 10.0 | 208 | 1 | 12.0 | 15 | 26 | 14.9 | NA | 12.5 | 3.9 | R454B | CARRIER | 37MARAQ09 | 1,2 |

CARRIER IS THE BASIS OF DESIGN. NO EXCEPTIONS.

REMARKS:

- PROVIDE EQUIPMENT WITH SCOR GREATER THAN THE AVAILABLE FAULT CURRENT AT THE EQUIPMENT OR UPSTREAM PANELBOARD. REFER TO THE ELECTRICAL ONE LINE DIAGRAM AND PANEL SCHEDULES FOR AVAILABLE FAULT CURRENT AT UPSTREAM PANELBOARD.
- PROVIDE LOW AMBIENT CONTROL.

| UNIT NO. | PLACEMENT | PHI CELL MODEL # | UV/CELL SIZE | RANGE | INDOOR PPM TARGET | SIZE | TRANSFORMER | POWER | IN-VOLT | OUT-VOLT | MCA | WEIGHT (LBS.) |
|----------|----------------|------------------|--------------|----------------|-------------------|--------------------------|-------------|-------|---------|----------|-------|---------------|
| | | | | | | | | | | | | |
| RTU-2 | BLOWER CABINET | PHI-PKG14-24V | 14" | 3,000-8000 CFM | < 0.02 PPM | 2.25"W x 19.5"L x 1.75"D | SHIP LOOSE | 11W | 115 VAC | 24 VAC | 0.50A | 2 LBS |



Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.DP3architects.com

Project

SHAKE SHACK #1797
WILMINGTON, NC

Project Number 25163
Drawn By SEI
Checked By GRS
Date 4 AUG 2025


Revisions

| | | |
|---|-------------|-----------------------------------|
| 1 | 23 OCT 2025 | HEALTH DEPARTMENT REVIEW COMMENTS |
| 2 | 17 NOV 2025 | IFC SET |

Drawing
MECHANICAL SCHEDULES

M601

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.



| HOOD STYLE / MODEL | 450 DEGREES cfm/ft. | 600 DEGREES cfm/ft. | 700 DEGREES cfm/ft. |
|---------------------------|---------------------|---------------------|---------------------|
| CANOPY ND-2 | 150 | 200 | 250 |
| CANOPY ND-2 W/ END PANELS | 105 | 140 | 175 |
| SLOPED SND-2 | 228 | 294 | - |
| ISLAND ND-2WI | 269 | 300 | 350 |
| ISLAND ND-2I | 346 | 422 | 475 |

| |
|---|
| EXHAUST CFM = LENGTH OF HOOD X CFM/LIN.FT. (LOAD) |
| SUPPLY CFM = EXHAUST CFM X PERCENTAGE REQUIRED |
| TOTAL DUCT AREA (sq. in.) = 144 X CFM ² |
| DUCT LENGTH = TOTAL DUCT AREA / DUCT WIDTH |
| * CAPTIVE-AIRE HOODS FOR DUCT AREA ARE CALCULATED USING AN AIRFLOW VELOCITY OF 1500-1800 FPM AND A SUPPLY VELOCITY OF 1000 FPM. |

CALCULATIONS UTILIZED

CAPTIVE-AIRE HOODS BUILT IN COMPLIANCE WITH:

UL STANDARD 718
Intertek
BUILT TO ACCORDANCE WITH NFPA 96

#3054804-001
#3054804-002
Listed under ETL File number 3054804-001/002

BUILDING CODES


CAPTIVE-AIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:

| MATERIAL | CLEARANCE REDUCTION SYSTEM |
|---------------------|----------------------------|
| NON-COMBUSTIBLE | NONE REQUIRED |
| LIMITED-COMBUSTIBLE | 3" UNINSULATED STANDOFF |
| COMBUSTIBLE | 1" INSULATED STANDOFF |

- CLEARANCE TO COMBUSTIBLES**
- INSTALLATION**
- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
 - ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
 - HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
 - ALL CONNECTIONS FROM CAPTIVEAIRE HOOD PER MECHANICAL CONTRACTOR'S PLANS.
 - COOKING EQUIPMENT TO SHUT OFF IN EVENT OF FIRE.
 - EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
 - ALL LIGHT FIXTURES SHOWN INSTALLED BY CAPTIVEAIRE ARE FACTORY PREWIRED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES ARE BY ELECTRICAL CONTRACTOR.
 - LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
 - SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
 - INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTEGRATION, AND ADMINISTRATION OF CODE REQUIREMENTS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.

- ADDITIONAL**
- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
 - SIGNED AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE RECEIVED BY THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

GENERAL NOTES



FILTER DETAIL

FOR QUESTIONS, CALL THE
Eastern PA Mechanical
REGION 108
PHONE: (267) 504 - 4126
EMAIL: reg108@captiveaire.com

HOOD INFORMATION - JOB#7612770





| HOOD NO | TAG | MODEL | MANUFACTURER | LENGTH | MAX COOKING TEMP | TYPE | APPLIANCE DUTY | DESIGN CFM/FT | TOTAL EXH CFM | EXHAUST PLENUM RISER(S) | | | | HOOD CONSTRUCTION | HOOD CONFIG | | | |
|---------|--------------|-----------|--------------|--------|------------------|------|----------------|---------------|---------------|-------------------------|------|--------|------|-------------------|-------------|----------------------|-------|------------|
| | | | | | | | | | | WIDTH | LENG | HEIGHT | DIA | | CFM | VEL | SP | END TO END |
| 1 | Hood (Grill) | 5430 ND-2 | CAPTIVEAIRE | 7' 11" | 450 DEG | 1 | MEDIUM | 150 | 1188 | 10" | 11" | 4' | 1188 | 1555 | -0.462' | 430 SS WHERE EXPOSED | ALONE | ALONE |
| 2 | Hood (Fryer) | 5430 ND-2 | CAPTIVEAIRE | 4' 11" | 600 DEG | 1 | HEAVY | 175 | 860 | 9" | 9" | 4' | 860 | 1529 | -0.494' | 430 SS WHERE EXPOSED | ALONE | ALONE |

HOOD INFORMATION

| HOOD NO | TAG | TYPE | FILTER(S) | | LIGHT(S) | | UTILITY CABINET(S) | | FIRE SYSTEM | ELECTRICAL | SWITCHES | FIRE SYSTEM/HANGING PIPING | HOOD HANGING WEIGHT | | | | |
|---------|--------------|----------------------|-----------|--------|----------|------------------------|--------------------|----------------|-------------|------------|-------------|----------------------------|---------------------|-------------|------------------|------|---------|
| | | | QTY | HEIGHT | LENGTH | EFFICIENCY @ 7 MICRONS | QTY | TYPE | | | | | | WIRE GUARD | LOCATION | SIZE | TYPE |
| 1 | Hood (Grill) | CAPTRATE SOLO FILTER | 5 | 20" | 16" | 85% SEE FILTER SPEC | 2 | RECESSED ROUND | ND | | | YES | 484 LBS | | | | |
| 2 | Hood (Fryer) | CAPTRATE SOLO FILTER | 3 | 20" | 16" | 85% SEE FILTER SPEC | 2 | RECESSED ROUND | ND | LEFT | 12"x54"x30" | TANK FS | 4.0/4.0/4.0 | SC-320110MA | 1 LIGHT 1 FAN | YES | 748 LBS |

HOOD OPTIONS

| HOOD NO | TAG | OPTION |
|---------|--------------|--|
| 1 | Hood (Grill) | FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT. RIGHT END STANDOFF (FINISHED) 1" WIDE 54" LONG INSULATED. INSULATION FOR BACK OF HOOD. RISER SENSOR INSTALL 6IN PLEN. LEFT VERTICAL END PANEL 27" TOP WIDTH, 21" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS. GFCI DUPLEX OUTLET, 20A 125V - HOOD FRONT LEFT - HORIZONTAL - DIST FROM END: 3.50 DIST FROM BOTTOM: 4.00. RIGHT WALL AS END PANEL. |
| 2 | Hood (Fryer) | FIELD WRAPPER 12.00" HIGH FRONT, LEFT, RIGHT. RIGHT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. LEFT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. INSULATION FOR BACK OF HOOD. RISER SENSOR INSTALL 6IN PLEN. |



REVISIONS

| NO. | DESCRIPTION | DATE |
|-----|-------------|------|
| | | |
| | | |
| | | |

CAPTIVEAIRE

Eastern PA Mechanical
225 E. City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004 PHONE: (267) 504 - 4126 EMAIL: reg108@captiveaire.com

Shake Shack-1797-Wilmington, NC(Kitchen)

DATE: 7/1/2025
DWG.#: 7612770
DRAWN BY: joe.shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING

SHEET NO. 1

Schnackel engineers

New York • Miami • Chicago • Los Angeles • Seattle • Honolulu
800-581-0963 www.schnackel.com

Seal

Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.DP3architects.com

SHAKE SHACK

SHAKE SHACK #1797
WILMINGTON, NC

Project Number: 25163
Drawn By: SEI
Checked By: GRS
Date: 4 AUG 2025

Revisions


| | | |
|---|-------------|-----------------------------------|
| 1 | 23 OCT 2025 | HEALTH DEPARTMENT REVIEW COMMENTS |
| 2 | 17 NOV 2025 | IFC SET |

Drawing
CAPTIVEAIRE DRAWINGS

M701


Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.

1" LAYER OF INSULATION FACTORY
INSTALLED IN INTERNAL BACK STANDOFF.
MEETS 0 INCH REQUIREMENTS FOR
CLEARANCE TO COMBUSTIBLE SURFACES.



PLAN VIEW - HOOD #1 (Hood (Grill))
7' 11.00" LONG 5430ND-2



1" LAYER OF INSULATION
FACTORY INSTALLED IN
1.00" END STANDOFF MEETS
0" REQUIREMENTS CLEARANCE
TO COMBUSTIBLE SURFACES.



PLAN VIEW - HOOD #2 (Hood (Fryer))
4' 11.00" LONG 5430ND-2

INSTALLER MUST CONFIRM HOOD IS INSTALLED SUCH
THAT THE SPECIFIED WALL, ACTING AS AN END PANEL,
IS MATED TIGHT TO THE CORRECT END OF HOOD TO
ACHIEVE A REDUCED MINIMUM EXHAUST CFM LISTING.
NON-COMPLIANCE WILL NULLIFY THE ETL LISTING.
VOID THE MANUFACTURER'S WARRANTY, AND HOLD THE
CONTRACTOR LIABLE FOR ANY AND ALL LOSSES, COSTS,
AND EXPENSES RELATED TO THE NON-COMFORMANCE OF
THE MANUFACTURER'S SPECIFIED INSTRUCTION. THE
WALL ACTING AS AN END PANEL MUST EXTEND NO LESS
THAN 20" FROM THE INTERSECTING WALL IN WHICH HOOD
IS MOUNTED AND MUST EXTEND NO LESS THAN 20" UNDER
BOTTOM OF HOOD TO BE ELIGIBLE FOR REDUCED
MINIMUM EXHAUST CFM LISTING.

(1) DUPLEX OUTLET




| REVISIONS | |
|-------------|------|
| DESCRIPTION | DATE |
| | |
| | |
| | |
| | |


CAPTIVEAIRE
 Eastern, PA Mechanical
 225 E. City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg108@captiveaire.com

Shake Shack-1797-Wilmington, NC (Kitchen)

DATE: 7/1/2025
 DWG.#:
7612770
 DRAWN
By: joe.shilba
 SCALE:
3/4" = 1'-0"
 MASTER DRAWING
 SHEET NO.
2



Seal



Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.DP3architects.com

Project

SHAKE SHACK #1797
WILMINGTON, NC

Project Number 25163
Drawn By SEI
Checked By GRS
Date 4 AUG 2025

Revisions
1 23 OCT 2025 HEALTH DEPARTMENT REVIEW COMMENTS
2 17 NOV 2025 IFC SET

Drawing
CAPTIVEAIRE
DRAWINGS

M702

FIRE SYSTEM INFORMATION - JOB#7612770

| FIRE SYSTEM NO | TAG | TYPE | SIZE | MAX FP | DESIGN FP | INSTALLATION | |
|----------------|-----|---------|-------------|--------|-----------|-------------------|------------------|
| | | | | | | SYSTEM | LOCATION ON HOOD |
| 1 | | TANK FS | 4.0/4.0/4.0 | 60 | 46 | FIRE CABINET LEFT | LEFT, HOOD 2 |

- NOTES**
- FIELD PIPE DROPS AS SHOWN
 - PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
 - FIELD INSTALLED DROP; FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
 - SHIP LOOSE DROP; FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
 - RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVING, SALAMANDERS, ETC.
 - OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
 - IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
 - FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.
 - APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.
 - THIS PRE-ENGINEERED FIRE SYSTEM COMPLIES WITH U.L. 300 REQUIREMENTS.

- DL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS
 JOB #: 7612770.
 JOB NAME: SHAKE SHACK-1797-WILMINGTON,NC(KITCHEN).

SYSTEM SIZE: TANK-SP-3 DESIGN FP: 46. MAXIMUM FP: 60.
 HOOD # 1 7' 11.00" LONG x 54" WIDE x 30" HIGH.
 RISER # 1 SIZE: 10" x 11".
 HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.
 HOOD # 2 4' 11.00" LONG x 54" WIDE x 30" HIGH.
 RISER # 1 SIZE: 9" x 9".
 HOOD # 2 METAL BLOW-OFF CAPS INCLUDED.





- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

| AGENT DISTRIBUTION PIPING LIMITATIONS | |
|---|----------------------|
| PIPE SECTION | MAX PIPE LENGTH (FT) |
| MAX SUPPLY LINE TO FIRST OVERLAPPING NOZZLE | 42 |
| OVERLAPPING NOZZLE APPLIANCE BRANCH | 10 |
| DEDICATED NOZZLE APPLIANCE BRANCH | 10 |

LEGEND - FIRE CABINET TANK SYSTEM

- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.

- SYSTEM REQUIRES A MINIMUM OF 7 FT OF EQUIVALENT PIPE LENGTH BETWEEN TANK AND NEAREST APPLIANCE NOZZLE FOR MOST APPLIANCES. EACH 90 DEGREE ELBOW ADDS 1.3 FT OF EQUIVALENT LENGTH. SEE MANUAL FOR DETAILS




| REVISIONS | |
|-------------|------|
| DESCRIPTION | DATE |
| | |
| | |
| | |
| | |

Eastern, PA Mechanical
 225 E City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg108@captiveaire.com

Shake Shack-1797-Wilmington,NC(Kitchen)

DATE: 7/1/2025
 DWG.#: 7612770
 DRAWN BY: joe.shilba
 SCALE: 3/4" = 1'-0"
 MASTER DRAWING

SHEET NO. 3



Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.DP3architects.com

SHAKE SHACK
SHAKE SHACK #1797
WILMINGTON, NC

Project Number: 25163
 Drawn By: SEI
 Checked By: GRS
 Date: 4 AUG 2025

Revisions
 1 23 OCT 2025 HEALTH DEPARTMENT REVIEW COMMENTS
 2 17 NOV 2025 IFC SET

Drawing
CAPTIVEAIRE
DRAWINGS

M703

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.

SE JOB# 25163

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.

EXHAUST FAN INFORMATION - JOB#7612770

| FAN UNIT NO | TAG | QTY | FAN UNIT MODEL # | MANUFACTURER | CFM | ESP | RPM | MOTOR ENCL | HP | BHP | PHASE | VOLT | FLA | DISCHARGE VELOCITY | WEIGHT (LBS) | SDNES |
|-------------|------------|-----|------------------|--------------|------|-------|------|------------|-------|--------|-------|------|-----|--------------------|--------------|-------|
| 1 | KEF(GRILL) | 1 | DUBSHFA | CAPTIVEAIRE | 1188 | 1.000 | 1213 | TEAD-ECM | 0.750 | 0.3070 | 1 | 208 | 5.2 | 376 FPM | 90 | 9.1 |
| 2 | KEF(FRYER) | 1 | DUBSHFA | CAPTIVEAIRE | 860 | 1.000 | 1141 | TEAD-ECM | 0.750 | 0.2550 | 1 | 208 | 5.2 | 272 FPM | 90 | 8.1 |

FAN ACCESSORIES

| FAN UNIT NO | TAG | EXHAUST | | | | SUPPLY | | | |
|-------------|------------|------------|----------------|------------|----------------|----------------|------------------|------------|--|
| | | GREASE CUP | GRAVITY DAMPER | WALL MOUNT | SIDE DISCHARGE | GRAVITY DAMPER | MOTORIZED DAMPER | WALL MOUNT | |
| 1 | KEF(GRILL) | YES | | | | | | | |
| 2 | KEF(FRYER) | YES | | | | | | | |



CURB ASSEMBLIES

| NO | DN FAN | TAG | WEIGHT | ITEM | SIZE |
|----|--------|------------|--------|------|--|
| 1 | # 1 | KEF-1 | 36 LBS | CURB | 23.000"W X 23.000"L X 20.000"H HINGED. |
| 2 | # 2 | KEF(FRYER) | 36 LBS | CURB | 23.000"W X 23.000"L X 20.000"H HINGED. |

FAN OPTIONS

| FAN UNIT NO | TAG | QTY | DESCRIPTION |
|-------------|------------|-----|--|
| 1 | KEF(GRILL) | 1 | GREASE BOX |
| | | 1 | FAN BASE CERAMIC SEAL - DU/DR85HFA - INSTALLED AT PLANT - FOR GREASE DUCTS |
| | | 1 | ECM WIRING PACKAGE - EXHAUST - MODBUS CONTROL -MSC- (TELCOD), CCW ROTATION |
| | | 1 | 2 YEAR PARTS WARRANTY |
| 2 | KEF(FRYER) | 1 | GREASE BOX |
| | | 1 | FAN BASE CERAMIC SEAL - DU/DR85HFA - INSTALLED AT PLANT - FOR GREASE DUCTS |
| | | 1 | ECM WIRING PACKAGE - EXHAUST - MODBUS CONTROL -MSC- (TELCOD), CCW ROTATION |
| | | 1 | 2 YEAR PARTS WARRANTY |

FANS #1 (KEF(GRILL)), #2 (KEF(FRYER)) - DUBSHFA EXHAUST FAN



TOP VIEW

FEATURES:


- DIRECT DRIVE CONSTRUCTION (NO BELTS/PULLEYS).
- ROOF MOUNTED FANS.
- RESTAURANT MODEL.
- UL705 AND UL762 AND ULC-S645
- VARIABLE SPEED CONTROL.
- INTERNAL WIRING.
- THERMAL OVERLOAD PROTECTION (SINGLE PHASE).
- HIGH HEAT OPERATION 300°F (149°C).
- GREASE CLASSIFICATION TESTING.
- NEMA 3R SAFETY DISCONNECT SWITCH.

NORMAL TEMPERATURE TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING AIR AT 300°F (149°C) UNTIL ALL FAN PARTS HAVE REACHED THERMAL EQUILIBRIUM, AND WITHOUT ANY DETERIORATING EFFECTS TO THE FAN WHICH WOULD CAUSE UNSAFE OPERATION.

ABNORMAL FLARE-UP TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING BURNING GREASE VAPORS AT 600°F (316°C) FOR A PERIOD OF 15 MINUTES WITHOUT THE FAN BECOMING DAMAGED TO ANY EXTENT THAT COULD CAUSE AN UNSAFE CONDITION.

OPTIONS

- GREASE BOX.
- FAN BASE CERAMIC SEAL - DU/DR85HFA - INSTALLED AT PLANT - FOR GREASE DUCTS.
- ECM WIRING PACKAGE - EXHAUST - MODBUS CONTROL -MSC- (TELCOD), CCW ROTATION.
- 2 YEAR PARTS WARRANTY.




REVISIONS


| NO | DESCRIPTION | DATE |
|----|-------------|------|
| | | |
| | | |
| | | |

CAPTIVEAIRE

E. Oster, P.A. Mechanical
225 E. City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg108@captiveaire.com



Seal



Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.DP3architects.com

Project

SHAKE SHACK
SHAKE SHACK #1797
WILMINGTON, NC

Project Number: 25163
Drawn By: SEI
Checked By: GRS
Date: 4 AUG 2025

Shake Shack-1797-Wilmington,NC(Kitchen)

DATE: 7/1/2025



DWG.#: 7612770

DRAWN By: joe.shilba

SCALE: 3/4" = 1'-0"

MASTER DRAWING

SHEET NO. 4




Drawing

CAPTIVEAIRE
DRAWINGS


M704

Copyright : These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.



1 GALLON GREASE COLLECTION BOX AND WALL MOUNTING BRACKET SHIPPED LOOSE FOR FIELD INSTALLATION BY MECHANICAL CONTRACTOR.

EQUIPMENT BY OTHERS




One Gallon Grease Cup Installation

Instructions below outline single, or dual, one gallon grease cup installation for ND-2 hood models.


The one gallon grease cup comes as an assembly of stainless steel wall mounting bracket and one gallon cup. The mounting bracket should be installed 2" from the edge of the containment plenum and 3"-4" below the bottom of the hood.

Piping from the hood grease drain should route to the opening of the grease cup, but not into the cup, otherwise the cup will not be able to be removed and emptied.




* Mounting hardware not included
**Must be mounted to stud or wall anchor

Left & Right hand Grease Cup Install



Gallon Grease Cup Assembly



1 GALLON GREASE COLLECTION BOX AND WALL MOUNTING BRACKET SHIPPED LOOSE FOR FIELD INSTALLATION BY MECHANICAL CONTRACTOR.

| REVISIONS | |
|-------------|------|
| DESCRIPTION | DATE |
| | |
| | |
| | |
| | |

Eastern PA Mechanical
 225 E. City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg108@captiveaire.com

Shake Shack-1797-Wilmington, NC(Kitchen)

DATE: 7/1/2025



DWG.#: 7612770

DRAWN BY: Joe Shilba

SCALE: 3/4" = 1'-0"

MASTER DRAWING

SHEET NO. 6



Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.DP3architects.com

SHAKE SHACK®
SHAKE SHACK #1797
WILMINGTON, NC

Project Number 25163
Drawn By SEI
Checked By GRS
Date 4 AUG 2025

Revisions
1 23 OCT 2025 HEALTH DEPARTMENT REVIEW COMMENTS
2 17 NOV 2025 IFC SET

Drawing
CAPTIVEAIRE
DRAWINGS

M706

SE_026-10002

DOAS/RTU FAN SCHEDULE - JOB#7612769

| FAN UNIT NO | TAG | QTY | DOAS/RTU MODEL # | FAN INFORMATION | | | | | | | | | | ELECTRICAL INFORMATION | | | | | | | | | | COOLING INFORMATION | | | | | | | | | | REHEAT INFORMATION | | | | | | | | | | GAS HEAT INFORMATION | | | | | | | | | | AEL MINIMUM ROOM VOLUME | | | NOTES |
|-------------|-----------------|-----|-----------------------|-----------------|------------|----------------|---------------------|-----------|--------------|-------|------|-------|------|------------------------|------|----------------|----------------|--------------|--------------|----------------|----------------|-----------|-----------|---------------------|------|--------|--------------|--------------|------------------|--------------|-----------------------|----------|------------|--------------------|--------------------------|-----------------------------|------------------------------|---------------|---|--|--|--|--|----------------------|--|--|--|--|--|--|--|--|--|-------------------------|--|--|-------|
| | | | | MANUFACTURER | BLDWR | RETURN AIR CFM | MAX OUTSIDE AIR CFM | TOTAL CFM | WEIGHT (LBS) | ESP | HP | PHASE | VOLT | NCA | MDCP | OUTSIDE AIR DB | OUTSIDE AIR WB | MIXED AIR DB | MIXED AIR WB | LEAVING AIR DB | LEAVING AIR WB | DP | TOTAL | SENS. | IEER | ISMRE2 | DISCHARGE DB | DISCHARGE WB | CAPACITY DESIRED | CAPACITY MAX | MOISTURE REMOVAL RATE | GAS TYPE | INPUT BTUs | OUTPUT BTUs | TEMP RISE | REQUIRED INPUT GAS PRESSURE | ROOM AREA (FT ²) | AIRFLOW (CFM) | HEIGHT (FT) | | | | | | | | | | | | | | | | | | |
| 1 | RTU-1(DINING) | 1 | CAS-HVAC3-1150-24-1ST | CAPTIVEAIRE | 24MF-3-RTU | 2550 | 950 | 3500 | 2531 | 0.700 | 5.00 | 3 | 208 | 70.9A | 80A | 88.3°F | 79.8°F | 78.6°F | 67.5°F | 47.2°F | 47.3°F | 204.6 MBH | 119.3 MBH | 18.8 | 8.3 | 75.0°F | 62.5°F | 110.6 MBH | 129.6 MBH | 76.5 LBS/HR | NATURAL | 104908 | 84971 | 22°F | 7 IN. W.C. - 14 IN. W.C. | 572.7 | 1031 | 7.2 | 1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18,19 | | | | | | | | | | | | | | | | | | |
| 2 | RTU-2 (KITCHEN) | 1 | CAS-HVAC3-1200-24-20T | CAPTIVEAIRE | 24MF-3-RTU | 2250 | 1750 | 4000 | 2707 | 0.700 | 5.00 | 3 | 208 | 91.4A | 100A | 88.3°F | 79.8°F | 80.9°F | 70.7°F | 49.7°F | 49.7°F | 255.7 MBH | 135.5 MBH | 18.2 | 7.9 | 70.0°F | 58.5°F | 91.9 MBH | 129.6 MBH | 107.8 LBS/HR | NATURAL | 187785 | 152106 | 34°F | 7 IN. W.C. - 14 IN. W.C. | 572.7 | 1031 | 7.2 | 1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18,19 | | | | | | | | | | | | | | | | | | |

FOR QUESTIONS, CALL THE
Eastern PA Mechanical
REGION 108
PHONE: (267) 504 - 4126
EMAIL: reg108@captiveaire.com




CURB ASSEMBLIES

| NO | FAN | TAG | WEIGHT | ITEM | SIZE |
|----|-----|-----------------|---------|------|---|
| 1 | # 1 | RTU-1(DINING) | 104 LBS | CURB | 59.500"W X 91.000"L X 14.000"H INSULATED. |
| 2 | # 2 | RTU-2 (KITCHEN) | 104 LBS | CURB | 59.500"W X 91.000"L X 14.000"H INSULATED. |

FAN OPTIONS

| FAN UNIT NO | TAG | QTY | DESCRIPTION |
|-------------|--|-----|--|
| 1 | RTU-1 (DINING) | 1 | INLET PRESSURE GAUGE, 0-35" |
| | | 1 | MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE |
| | | 1 | COOLING OVERRIDE |
| | | 1 | SINGLE POINT ELECTRICAL CONNECTION FOR RTU 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #28, #47, "MA", OR "E2" PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE. |
| | | 1 | RTU BLOWER DOOR SWITCH |
| | | 1 | RTU3 DOWN DISCHARGE |
| | | 1 | 2" MERV 13 FILTERS FOR RTU3 (QTY. 4) |
| | | 1 | 2" MERV 8 FILTERS FOR RTU3 (QTY. 4) |
| | | 1 | OVERHEAT STAT |
| | | 1 | TOTAL CFM MONITORING |
| | | 1 | VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE |
| | | 1 | 15 TON MODULATING COOLING OPTION, 208/230V, R454B REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS |
| | | 1 | LOW AMBIENT COOLING OPERATION - DOWN TO 0F AMBIENT |
| | | 1 | R454B LEAK DETECTOR OPTION FOR RTU3 |
| | | 1 | OCCUPIED SCHEDULING |
| | | 1 | INTAKE FIRESTAT SET TO 135°F |
| | | 1 | FREEZESTAT |
| | | 1 | DISCHARGE FIRESTAT SET TO 240°F |
| | | 1 | GASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED |
| | | 1 | 15 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL - R454B |
| | | 1 | RTU3 CURB DUCT HANGER |
| | | 1 | 120V FIRE INPUT |
| | | 1 | COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS |
| | | 1 | CLOGGED FILTER SWITCH - NOTIFICATION ON HMI |
| | | 1 | RTU3 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION INCLUDES RECEPTACLE, COVER AND J-BOX |
| | | 1 | RTU ECONDMIZER - DIFFERENTIAL ENTHALPY CONTROL |
| | | 1 | RTU3 ECONDMIZER BAROMETRIC RELIEF |
| | | 1 | 2" METAL MESH FILTERS FOR RTU3 OUTDOOR INTAKE |
| | | 1 | RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI |
| | | 1 | RTU3 HAIL GUARD |
| 1 | RTU3 DOWN RETURN | | |
| 1 | VAV PACKAGE W/ MANUAL/DDC CONTROL (S71 VFD INCLUDED) | | |
| 1 | 5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS) | | |
| 1 | EXTERIOR GAS CONNECTION PROVIDED BY FACTORY WITH QUICK SEAL AND ANTI-ROTATION BRACKET | | |

| HMI SCHEDULE | | | | |
|--------------|----------------|-----------------|----------------|----------------|
| UNIT NUMBER | HMI # | HMI LOCATION | TEMP AVERAGING | MODBUS ADDRESS |
| FAN #1 | HMI #1 - UNIT | IN UNIT | NOT AVERAGED | 55 |
| FAN #1 | HMI #2 - SPACE | DINING ROOM | AVERAGED | 56 |
| FAN #1 | HMI #3 - SPACE | MANAGERS OFFICE | AVERAGED | 57 |
| FAN #2 | HMI #1 - UNIT | IN UNIT | NOT AVERAGED | 55 |
| FAN #2 | HMI #2 - SPACE | KITCHEN | AVERAGED | 56 |
| FAN #2 | HMI #3 - SPACE | MANAGERS OFFICE | NOT AVERAGED | 57 |



REVISIONS

| NO | DESCRIPTION | DATE |
|----|-------------|------|
| | | |
| | | |
| | | |
| | | |

www.captiveaire.com

Eastern PA Mechanical

225 E City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004 PHONE: (267) 504 - 4126 EMAIL: reg108@captiveaire.com

Shake Shack-1797-Wilmington, NC(HVAC)

WILMINGTON, NC, 28401

DATE: 7/1/2025

DWG.#: 7612769

DRAWN BY: Joe.shilba

SCALE: 1/2" = 1'-0"

MASTER DRAWING

SHEET NO. 1

New York • Miami • Omaha • Los Angeles • Seattle • Honolulu
800-581-0963 www.schnackel.com

Seal

Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.DP3architects.com

Project

SHAKE SHACK®
SHAKE SHACK #1797
WILMINGTON, NC

Project Number 25163
Drawn By SEI
Checked By GRS
Date 4 AUG 2025

Revisions
1 23 OCT 2025 HEALTH DEPARTMENT REVIEW COMMENTS
2 17 NOV 2025 IFC SET

Drawing
CAPTIVEAIRE
DRAWINGS

M707

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.

SE_026-10002

DOAS/RTU FAN SCHEDULE - JOB#7612769

| FAN UNIT NO | TAG | QTY | DOAS/RTU MODEL # | FAN INFORMATION | | | | | | | | | | ELECTRICAL INFORMATION | | | | | | | | | | COOLING INFORMATION | | | | | | | | | | REHEAT INFORMATION | | | | | | | | | | GAS HEAT INFORMATION | | | | | | | | | | AEL MINIMUM ROOM VOLUME | | | NOTES |
|-------------|-----------------|-----|-----------------------|-----------------|------------|----------------|---------------------|-----------|--------------|-------|------|-------|------|------------------------|------|----------------|----------------|--------------|--------------|----------------|----------------|-----------|----------------|---------------------|------|--------|--------------|--------------|------------------|--------------|-----------------------|----------|------------|--------------------|--------------------------|-----------------------------|------------------------------|---------------|---|--|--|--|--|----------------------|--|--|--|--|--|--|--|--|--|-------------------------|--|--|-------|
| | | | | MANUFACTURER | BLDWR | RETURN AIR CFM | MAX OUTSIDE AIR CFM | TOTAL CFM | WEIGHT (LBS) | ESP | HP | PHASE | VOLT | NCA | MDCP | OUTSIDE AIR DB | OUTSIDE AIR WB | MIXED AIR DB | MIXED AIR WB | LEAVING AIR DB | LEAVING AIR WB | DP | TOTAL CAPACITY | SENS. | IEER | ISMRE2 | DISCHARGE DB | DISCHARGE WB | CAPACITY DESIRED | CAPACITY MAX | MOISTURE REMOVAL RATE | GAS TYPE | INPUT BTUs | OUTPUT BTUs | TEMP RISE | REQUIRED INPUT GAS PRESSURE | ROOM AREA (FT ²) | AIRFLOW (CFM) | HEIGHT (FT) | | | | | | | | | | | | | | | | | | |
| 1 | RTU-1(DINING) | 1 | CAS-HVAC3-1150-24-1ST | CAPTIVEAIRE | 24MF-3-RTU | 2550 | 950 | 3500 | 2531 | 0.700 | 5.00 | 3 | 208 | 70.9A | 80A | 88.3°F | 79.8°F | 78.6°F | 67.5°F | 47.2°F | 47.3°F | 204.6 MBH | 119.3 MBH | 18.8 | 8.3 | 75.0°F | 62.5°F | 110.6 MBH | 129.6 MBH | 76.5 LBS/HR | NATURAL | 104908 | 84971 | 22°F | 7 IN. W.C. - 14 IN. W.C. | 572.7 | 1031 | 7.2 | 1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18,19 | | | | | | | | | | | | | | | | | | |
| 2 | RTU-2 (KITCHEN) | 1 | CAS-HVAC3-1200-24-20T | CAPTIVEAIRE | 24MF-3-RTU | 2250 | 1750 | 4000 | 2707 | 0.700 | 5.00 | 3 | 208 | 91.4A | 100A | 88.3°F | 79.8°F | 80.9°F | 70.7°F | 49.7°F | 49.8°F | 255.7 MBH | 135.5 MBH | 18.2 | 7.9 | 70.0°F | 58.5°F | 91.9 MBH | 129.6 MBH | 107.8 LBS/HR | NATURAL | 187785 | 152106 | 34°F | 7 IN. W.C. - 14 IN. W.C. | 572.7 | 1031 | 7.2 | 1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18,19 | | | | | | | | | | | | | | | | | | |

FOR QUESTIONS, CALL THE
Eastern PA Mechanical
REGION 108
PHONE: (267) 504 - 4126
EMAIL: regi108@captiveaire.com




CURB ASSEMBLIES

| NO | FAN TAG | WEIGHT | ITEM | SIZE |
|----|---------------------|---------|------|---|
| 1 | # 1 RTU-1(DINING) | 104 LBS | CURB | 59.500"W X 91.000"L X 14.000"H INSULATED. |
| 2 | # 2 RTU-2 (KITCHEN) | 104 LBS | CURB | 59.500"W X 91.000"L X 14.000"H INSULATED. |

FAN OPTIONS

| FAN UNIT NO | TAG | QTY | DESCRIPTION |
|-------------|--|-----|--|
| 1 | RTU-1 (DINING) | 1 | INLET PRESSURE GAUGE, 0-35" |
| | | 1 | MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE |
| | | 1 | COOLING OVERRIDE |
| | | 1 | SINGLE POINT ELECTRICAL CONNECTION FOR RTU 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #28, #47, #4A, OR #2' PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE. |
| | | 1 | RTU BLOWER DOOR SWITCH |
| | | 1 | RTU3 DOWN DISCHARGE |
| | | 1 | 2" MERV 13 FILTERS FOR RTU3 (QTY. 4) |
| | | 1 | 2" MERV 8 FILTERS FOR RTU3 (QTY. 4) |
| | | 1 | OVERHEAT STAT |
| | | 1 | TOTAL CFM MONITORING |
| | | 1 | VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE |
| | | 1 | 15 TON MODULATING COOLING OPTION, 208/230V. R454B REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS |
| | | 1 | LOW AMBIENT COOLING OPERATION - DOWN TO 0F AMBIENT |
| | | 1 | R454B LEAK DETECTOR OPTION FOR RTU3 |
| | | 1 | OCCUPIED SCHEDULING |
| | | 1 | INTAKE FIRESTAT SET TO 135°F |
| | | 1 | FREEZESTAT |
| | | 1 | DISCHARGE FIRESTAT SET TO 240°F |
| | | 1 | GASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED |
| | | 1 | 15 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL - R454B |
| | | 1 | RTU3 CURB DUCT HANGER |
| | | 1 | 120V FIRE INPUT |
| | | 1 | COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS |
| | | 1 | CLOGGED FILTER SWITCH - NOTIFICATION ON HMI |
| | | 1 | RTU3 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX |
| | | 1 | RTU ECONOMIZER - DIFFERENTIAL ENTHALPY CONTROL |
| | | 1 | RTU3 ECONOMIZER BAROMETRIC RELIEF |
| | | 1 | 2" METAL MESH FILTERS FOR RTU3 OUTDOOR INTAKE |
| | | 1 | RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI |
| | | 1 | RTU3 HAIL GUARD |
| 1 | RTU3 DOWN RETURN | | |
| 1 | VAV PACKAGE W/ MANUAL/DDC CONTROL (S71 VFD INCLUDED) | | |
| 1 | 5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS) | | |
| 1 | EXTERIOR GAS CONNECTION PROVIDED BY FACTORY WITH QUICK SEAL AND ANTI-ROTATION BRACKET | | |

| HMI SCHEDULE | | | | |
|--------------|----------------|-----------------|----------------|----------------|
| UNIT NUMBER | HMI # | HMI LOCATION | TEMP AVERAGING | MODBUS ADDRESS |
| FAN #1 | HMI #1 - UNIT | IN UNIT | NOT AVERAGED | 55 |
| FAN #1 | HMI #2 - SPACE | DINING ROOM | AVERAGED | 56 |
| FAN #1 | HMI #3 - SPACE | MANAGERS OFFICE | AVERAGED | 57 |
| FAN #2 | HMI #1 - UNIT | IN UNIT | NOT AVERAGED | 55 |
| FAN #2 | HMI #2 - SPACE | KITCHEN | AVERAGED | 56 |
| FAN #2 | HMI #3 - SPACE | MANAGERS OFFICE | NOT AVERAGED | 57 |



REVISIONS

| NO. | DESCRIPTION | DATE |
|-----|-------------|------|
| | | |
| | | |
| | | |
| | | |

www.captiveaire.com

Eastern PA Mechanical
225 E. City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004 PHONE: (267) 504 - 4126 EMAIL: regi108@captiveaire.com

Shake Shack-1797-Wilmington, NC(HVAC)
WILMINGTON, NC, 28401

DATE: 7/1/2025
DWG.#: 7612769
DRAWN BY: Joe.shilba
SCALE: 1/2" = 1'-0"
MASTER DRAWING

SHEET NO. 1

New York • Miami • Omaha • Los Angeles • Seattle • Honolulu
800-581-0963 www.schnackel.com

Seal

Brian S. Thomas
Architect

DP3 Architects, Ltd.
15 South Main Street, Suite 400
Greenville, SC 29601
864.232.8200
www.DP3architects.com

SHAKE SHACK®
SHAKE SHACK #1797
WILMINGTON, NC

Project Number: 25163
Drawn By: SEI
Checked By: GRS
Date: 4 AUG 2025

Revisions
1 23 OCT 2025 HEALTH DEPARTMENT REVIEW COMMENTS
2 17 NOV 2025 IFC SET




Drawing
CAPTIVEAIRE
DRAWINGS

M708

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.

SE_026-25002

Copyright: These Drawings are the property of DP3 Architects, Ltd., and reuse on any other project without written permission will result in legal action.



REVISIONS

| NO. | DESCRIPTION | DATE |
|-----|-------------|------|
| 1 | | |
| 2 | | |

CAPTIVE

Eastern, PA Mechanical
 225 E. City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004
 PHONE: (267) 504-4126
 EMAIL: reg108@captiveair.com
 www.captiveair.com

Shake Shack-1797-Wilmington, NC(HVAC)
 WILMINGTON, NC, 28401

DATE: 7/1/2025
 DWG.#: 7612769
 DRAWN BY: Joe.shilba
 SCALE: 1/2" = 1'-0"
 MASTER DRAWING

SHEET NO. 3

Schnackel engineers.
 New York • Miami • Omaha • Los Angeles • Seattle • Honolulu
 800-581-0963 www.schnackel.com

Brian S. Thomas Architect
 DP3 Architects, Ltd.
 15 South Main Street, Suite 400
 Greenville, SC 29601
 864.232.8200
 www.DP3architects.com

SHAKE SHACK #1797 WILMINGTON, NC

Project Number: 25163
 Drawn By: SEI
 Checked By: GRS
 Date: 4 AUG 2025

FAN #2 CAS-HVAC3-I.200-24MF-20T - HEATER (RTU-2 (KITCHEN))

NOTES:
 1. DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
 2. DENOTES CORNER WEIGHT.
 3. ROOF OPENING MUST BE 2" SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.
 4. CONNECTION FROM BREAKER TO UNITS SAFETY DISCONNECT SWITCH TO BE COPPER WIRE ONLY.
 5. EXTERIOR GAS CONNECTION PROVIDED BY FACTORY WITH QUICK SEAL AND ANTI-ROTATION BRACKET.
 *NOTE: INTEGRAL CO2 MONITORING AND CONTROL CAPABILITIES FOR ALL SPACE MOUNTED THERMOSTATS.

Drawing
CAPTIVEAIRE DRAWINGS

M709