



THE DESIGN AND DETAILS DISCLOSED HEREIN ARE THE EXCLUSIVE PROPERTY OF DAN WINTER ARCHITECT AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT PRIOR WRITTEN CONSENT.

DAN WINTER, ARCHITECT

FREDDY'S FROZEN CUSTARD
EMORY VIEW SHOPPING CENTER
 229 E. EMORY RD., BLDG. 'D/2', SUITE 101-D/2
 POWELL, TN.

DAN WINTER ARCHITECT
 1024 EAST FIRST STREET
 WICHITA, KS. 67214
 PH. 316-267-7142

MECHANICAL PLAN

DATE
 2/11/2022

DRAWN BY:
 CHECKED BY:


SHEET NO.
M1

GENERAL NOTES:

- DUCT SYSTEMS SERVING REMOVAL OF GREASE LADEN AIR (TYPE 1 HOOD) SHALL BE CONSTRUCTED AND INSTALLED SO THAT GREASE WILL NOT ACCUMULATE IN DUCTWORK. DUCTWORK SHALL SLOPE AT 2% TOWARD HOOD OR GREASE RESERVOIR. PROVIDE DUCT CLEAN OUTS AT ALL CHANGES OF DIRECTION WITH GREASE TIGHT ACCESS DOORS.
- DUCTWORK SERVING KITCHEN AND WORK ROOM AREAS SHALL NOT BE LINED. DUCTWORK SERVING THESE AREAS SHALL UTILIZE EXTERNAL DUCT WRAP INSULATION.
- MAINTAIN MINIMUM 10'-0" CLEARANCE BETWEEN OUTDOOR AIR INTAKES AND EXHAUST FAN/VENT TERMINATIONS.
- KITCHEN HOODS ARE PROVIDED BY KITCHEN EQUIPMENT SUPPLIER AND INSTALLED BY MECHANICAL CONTRACTOR.
- REFER TO HOOD MANUFACTURER SHOP DRAWINGS FOR HOOD SUPPORT INFORMATION.
- CEILING SPACE IS LIMITED. COORDINATE WORK WITH OTHER TRADES.
- EXPOSED DUCTWORK SHALL BE CLEAN AND FREE OF DEFECTS.
- EXPOSED DUCTWORK SHALL BE CONSTRUCTED OF PAINT LOCK SHEETMETAL AND PAINTED AS DIRECTED BY ARCHITECT.

PLAN NOTES:

- MOUNTING LOCATION FOR DUCT MOUNTED SMOKE DETECTOR.
- LOCATION OF MANUAL PULL STATION. INSTALL PER MANUFACTURER INSTRUCTIONS.
- LOCATION OF RTU THERMOSTATS. LABEL THERMOSTATS WITH RTU NUMBER. LABELS BY M.C.
- LOCATION OF RTU TEMPERATURE SENSORS MOUNTED 7'-0" AFF.
- COORDINATE DUCT BETWEEN STRUCTURAL TRUSSES WITH SIZES SHOWN.
- EXHAUST HOOD PROVIDED BY OTHERS. INSTALLED BY MECHANICAL CONTRACTOR. INSTALL PER MANUFACTURER'S INSTRUCTIONS.
- TRANSITION AND CONNECT 10" GREASE DUCT TO EXHAUST FAN AS SHOWN. ROUTE DUCT UP AND CONNECT TO EXHAUST FAN. OFFSET AS REQUIRED TO AVOID ROOF STRUCTURE AND TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTSIDE AIR INTAKES AND 5'-0" FROM PARAPET WALLS. REFER TO DETAIL ON SHEET M-2. ALL GREASE DUCT SHALL BE INSTALLED WITH DUCT WRAP AND ACCESS DOORS AS DETAILED AND PER MANUFACTURER INSTRUCTIONS. SEE CAPTIVE AIRE DRAWING.
- TRANSITION AND CONNECT 14" GREASE DUCT TO EXHAUST FAN AS SHOWN. ROUTE DUCT UP AND CONNECT TO EXHAUST FAN. OFFSET AS REQUIRED TO AVOID ROOF STRUCTURE AND TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTSIDE AIR INTAKES AND 5'-0" FROM PARAPET WALLS. REFER TO DETAIL ON SHEET M-2. ALL GREASE DUCT SHALL BE INSTALLED WITH DUCT WRAP AND ACCESS DOORS AS DETAILED AND PER MANUFACTURER INSTRUCTIONS. SEE CAPTIVE AIRE DRAWING.
- COMBUSTION AIR AND VENT PIPING THROUGH ROOF. PROVIDE TERMINATION PER MANUFACTURER'S RECOMMENDATIONS. EXTEND TO WATER HEATER. COORDINATE REQUIREMENTS WITH HEATER.
- COORDINATE DUCT ROUTING WITH ELECTRICAL GEAR. DO NOT ROUTE DUCTWORK ABOVE ELECTRICAL GEAR.
- RETURN AIR DUCT LOCATED BETWEEN ROOF TRUSSES. OPEN DUCTWORK UP TOWARD STRUCTURE. COVER OPENING WITH 3/4" EXPANDED WITH MESH.
- SUPPORT EXHAUST FAN FROM STRUCTURE AS REQUIRED BY THE MANUFACTURER.
- ROUTE DUCT AS HIGH AS POSSIBLE OVER OFFICE AREA TO ALLOW FOR ROUTING OF CABLES.
- MOUNT CONDENSING UNIT ON ROOF AS DETAILED AND AS REQUIRED BY THE MANUFACTURER. CONNECT REFRIGERANT PIPING PER MANUFACTURER RECOMMENDATIONS. SEE ARCHITECTURAL PLANS FOR MOUNTING DETAIL.
- ROUTE RETURN AIR DUCT THROUGH OR BETWEEN ROOF TRUSSES.
- ROUTE 10" EXHAUST DUCT UP THROUGH ROOF TO ROOF CAP. VERIFY 10' CLEARANCE FROM ALL OUTSIDE AIR INTAKES.
- HOOD SHALL BE PROVIDED WITH FACTORY PRE-WIRE PACKAGE AND A PRE-ENGINEERED UL-300 FIRE SUPPRESSION SYSTEM. SYSTEM SHALL BE PROPERLY SIZED FOR THE HOOD. DUCT PLENUM AND ALL EQUIPMENT BELOW (VERIFY EXACT REQUIREMENTS WITH KITCHEN EQUIPMENT SUPPLIER). HOOD EXHAUST, MAKE-UP AND LIGHTS SHALL BE SWITCHED FROM CONTROL PANEL THAT IS INTEGRAL TO FRONT OF UTILITY CABINET. UTILITY CABINET SHALL SERVE ALL HOODS.
- PROVIDE LOCKING QUADRANT DAMPER AND SQUARE TO ROUND TRANSITION FOR DUCT CONNECTION TO RETURN GRILLE.
- COORDINATE DUCT DROP BETWEEN STRUCTURAL TRUSSES WITH SIZES SHOWN. TRANSITION RETURN AIR DUCT TO FIT BETWEEN STRUCTURE.
- PROVIDE CAPTIVE AIRE WBE WINDBAND EXTENSION FOR KEF-1 AND KEF-2.
- EXPOSED DUCTWORK SHALL BE DUAL WALL, PAINTLOCK CONSTRUCTION AND PAINTED AS PER DIRECTION OF ARCHITECT (TYP.).
- COORDINATE EXPOSED DUCTWORK WITH LIGHTS (TYP.).



SPECIFICATION SECTION 230593 TESTING, ADJUSTING, AND BALANCE REQUIRES AN INDEPENDENT TAB CONTRACTOR (NEBB OR AABC) TO TEST ALL EQUIPMENT TO ENSURE COMPLIANCE WITH DRAWINGS. OWNER'S REPRESENTATIVE SHALL RECEIVE REPORT / VERIFICATION.

NORTH

A MECHANICAL PLAN
 SCALE: 1/4" = 1'-0"





MECHANICAL LEGEND

HVAC		HVAC		HVAC		MISC. SYMBOLS	
	SUPPLY AIR DIFFUSER		ELBOW ROUND DUCT		ECCENTRIC TRANSITION		EQUIPMENT IDENTIFICATION
	RETURN AIR GRILLE WITH SOUND ROOT		ROUND DUCT DROP / DOWN		DUCT OFFSET - RISE OR DROP		PLAN NOTE
	RETURN AIR GRILLE WITH SOUND ROOT		ROUND DUCT RISE / UP		FLEX DUCT (5'-0" MAX. LENGTH)		ABOVE FINISHED FLOOR
	SIDE WALL REGISTER / GRILLE		FLEXIBLE CONNECTION		OBD OPOSED BLADE DAMPER		SUPPLY AIR
	SUPPLY AIR DUCT RISE / UP		DUCT SIZE / DIMENSIONS FIRST SIZE TOP DIMENSION		PBD PARALLEL BLADE DAMPER		RETURN AIR
	SUPPLY DUCT DROP / DOWN		45° HIGH EFFICIENCY TAKE-OFF		T THERMOSTAT / SENSOR		EA EXHAUST AIR
	RETURN OR EXHAUST DUCT RISE / UP		45° HIGH EFFICIENCY TAKE-OFF WITH LOCKING QUAD. DAMPER		H HUMIDISTAT / SENSOR		OSA OUTSIDE AIR
	RETURN OR EXHAUST DUCT DROP / DOWN		CONCENTRIC TRANSITION		FS FIRE SMOKE DAMPER		RAG RETURN AIR GRILLE
	ELBOW WITH TURNING VANES		RECT. TO ROUND TRANSITION		FD FIRE DAMPER		


OUTDOOR AIR CALCULATION

UNIT	AREA (SQFT)	OCCUPANCY CLASSIFICATION	OCCUPANT DENSITY # PEOPLE	PEOPLE OUTDOOR AIRFLOW RATE IN BREATHING ZONE (RP) CFM/PERSON	AREA OUTDOOR AIRFLOW RATE IN BREATHING ZONE (RA) CFM/SQFT	EXHAUST AIRFLOW RATE CFM/SQFT	BREATHING ZONE OUTDOOR AIRFLOW (Vbz)	ZONE AIR DISTRIBUTION EFFECTIVENESS (Ez)	ZONE OUTDOOR AIRFLOW (CFM)
RTU-1	1595	DINING RM	80	7.5	0.18	...	0.8	...	888
	120	RESTROOM	0	0	0.06	...	0.8	...	8
							TOTAL		896
RTU-2	975	KITCHEN	20	7.5	0.12	0.7	...	0.8	267
	45	OFFICE	1	5	0.06	...	0.8	...	8
							TOTAL		1171




NOTE: PROVIDE SHORT RADIUS ELBOWS (1 TIMES CENTERLINE 90° ELL) FOR ELBOW DOWN TO DIFFUSER ON EXPOSED DUAL WALL. DUCTWORK IN DINING ROOM. DIFFUSER SHALL BE MINIMUM OF 10'-0" A.F.F. SEE DETAIL.


NOTE: REMOTE SENSORS WIRE TO THERMOSTAT. HUMIDITY SENSORS WIRE UP TO THE PRODIGY CONTROL PANEL. REFER TO HUMIDITY SENSOR INSTALLATION INSTRUCTIONS. HUMIDITY LEVEL IS CONTROL ON THE PRODIGY PANEL. SET HUMIDITY LEVEL AT 50-55%. CONTACT NA TECH SUPPORT GROUP AT 1-800-367-6285 FOR QUESTIONS.




1 ROUND DUCT TAKE-OFF
NO SCALE



2 RECTANGULAR DUCT TAKE-OFF
NO SCALE




3 DOWNFLOW ROOF TOP UNIT DETAIL
NO SCALE




4 DINING ROOM DIFFUSER DETAIL
NO SCALE

- NOTES:
1. PROVIDE MANUFACTURERS RECOMMENDED CLEARANCES BETWEEN CU & HP UNITS.
 2. PROVIDE ADDITIONAL SUPPORTS AS REQUIRED IF UNITS ARE NOT SAME WIDTH.
 3. PAINT EXPOSED INSULATION WITH MANUFACTURER RECOMMENDED ULTRAVIOLET PROTECTIVE COATING.




5 ROOF CONDENSING UNIT MOUNTING
NO SCALE
CONDENSER ON ROOF

- NOTES:
1. THERMAL CERAMICS FIREMASTER FASTWRAP XL OR PYROSCAT XL HAS BEEN TESTED IN ACCORDANCE WITH ASTM E2336 TO PROVIDE ZERO CLEARANCE TO COMBUSTIBLES AND MEETS THE REQUIREMENTS FOR ONE OR TWO HOUR ENCLOSURES. THROUGH PENETRATIONS FIRESTOP SYSTEMS ARE TESTED IN ACCORDANCE WITH EITHER ASTM E 814 OR UL 1479. ICC-ES APPROVAL PER REPORT ESR 2213 OR ESR 2832. UNDERWRITERS LABORATORIES (UL) LISTINGS SHOW COMPLIANCE TO UL 1479 FOR THROUGH PENETRATION FIRESTOP SYSTEMS.
 2. COMPLIANT TO THE FOLLOWING CODES: NFPA 96 2003 AND 2006 INTERNATIONAL MECHANICAL CODES 2006 UNIFORM MECHANICAL CODE.
 3. INSULATION APPLIED IN TWO LAYERS WITH TIGHT COMPRESSION JOINT ON INSIDE LAYER AND 3 INCH MINIMUM OVERLAPS ON BOTH PERIMETER AND LONGITUDINAL OVERLAPS ON OUTSIDE LAYER.
 4. GREASE EXHAUST DUCT RUNS FROM THE HOOD EXHAUST CONNECTION UP TO THE EXHAUST FAN ON THE ROOF WITH MINIMAL TURNS OR BENDS AND MAINTAINING MINIMUM 1/4 UNIT VERTICAL RISE PER 12 UNITS HORIZONTAL RUN. NFPA 96 COMPLIANT ACCESS DOORS LOCATED AS REQUIRED BY CODE.
 5. THERMAL CERAMICS FIREMASTER ACCESS DOORS AS SPECIFIED IN ICC-ES BUILDING CODE REPORTS ESR 2213 OR ESR 2832.
 6. ROOF MOUNTED EXHAUST FAN IS MOUNTED ON A HINGED BASE WHICH ALLOWS ACCESS TO THE DUCT FROM THE ROOF.
 7. SUPPORT HANGER SYSTEMS DO NOT NEED TO BE WRAPPED PROVIDED THE HANGER RODS ARE AT LEAST A MINIMUM OF 3/8 IN. DIAMETER. USE MINIMUM 2 X 2 X 1/8 IN. STEEL ANGLE OR SMACNA EQUIVALENT SUPPORT SYSTEM.
 8. THERMAL CERAMICS DUCT ENCLOSURE SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS.
 9. THERMAL CERAMICS DUCT WRAP SHALL BE INSTALLED ON THE DUCT FROM THE HOOD CONNECTION TO THE CONNECTION TO THE FAN.



6 COMMERCIAL KITCHEN GREASE DUCT SYSTEM
NO SCALE



7 GREASE HOOD DETAIL
NO SCALE

ROOFTOP UNIT SCHEDULE

MARK	MFR	MODEL NO.	NOM. TONS	EVAP. CFM	EXT. STATIC P. IN. WG (NOTE 2)	COOLING			HEATING (GAS)			ELECTRICAL			MINIMUM OUTDOOR AIR (CFM)	TOTAL WEIGHT (LBS)	EER	REFRIG.	NOTES	
						TOTAL MBH	SENS. MBH	AMB.	EVAP. EAT DB/WB	MBH INPUT	MBH OUTPUT	VOLT/PHZ	BLOWER MOTOR	MIN. MCA (AMPS)						MIN. MOCPP (AMPS)
RTU-1	LENNOX	LGH150	12.5	4,850	1.0	134.2	113.5	100	80/67	260	205	208/3/60	5 HP	71	90	1000	1,650	12.8	R-410a	1,2,3,4,5,6
RTU-2	LENNOX	LGH092	7.5	3,000	1.0	86.0	66.2	100	80/67	130	104	208/3/60	2 HP	42	50	300	1,500	--	R-410a	1,2,3,4,5,6

ALTERNATE RTU MANUFACTURER

MARK	MFR	MODEL NO.	NOM. TONS	EVAP. CFM	EXT. STATIC P. IN. WG (NOTE 2)	COOLING			HEATING (GAS)			ELECTRICAL			MINIMUM OUTDOOR AIR (CFM)	TOTAL WEIGHT (LBS)	EER	REFRIG.	NOTES	
						TOTAL MBH	SENS. MBH	AMB.	EVAP. EAT DB/WB	BTUH INPUT	BTUH OUTPUT	VOLT/PHZ	BLOWER MOTOR	MIN. MCA (AMPS)						MIN. MOCPP (AMPS)
RTU-1	TRANE	YHD150G3R	12.5	4,850	1.0	146.74	98.91	95	80/67	250,000	200,000	208/3/60	3 HP	67	80	1000	2,500	12.1	R-410a	1,2,3,4,5,6
RTU-2	TRANE	YHD092F3R	7.5	3,000	1.0	96.5	65.3	95	80/67	150,000	121,000	208/3/60	2.75 HP	42.4	50	300	1,450	14.5	R-410a	1,2,3,4,5,6

- NOTES:
1. PROVIDE LOW LEAK OUTDOOR AIR ECONOMIZER WITH DIFFERENTIAL ENTHALPY CONTROL, FAULT DETECTION AND DIAGNOSTIC MODULE. PROVIDE UNIT WITH HOT GAS REHEAT WITH 75° L.A.T. TIME DELAY ON COMPRESSOR RE-START, CRANKCASE HEATER, BAROMETRIC RELIEF DAMPER, AND COMPRESSOR LOCK-OUT WITH AMBIENT BELOW 55 °F FOR EACH UNIT. OUTDOOR AIR DAMPER TO FULLY CLOSE W/ FAN SHUTDOWN FOR ALL UNITS. PROVIDE UNIT WITH 2-SPEED FAN.
 2. EXTERNAL STATIC PRESSURE LISTED REPRESENTS STATIC PRESSURE REQUIRED FOR DUCTWORK AND DIFFUSERS OUTSIDE THE HVAC UNIT COMPLETELY INDEPENDENT OF ANY PRESSURE DROP THROUGH THE HVAC EQUIPMENT INCLUDING BUT NOT LIMITED TO FILTERS, COILS AND ECONOMIZERS. THE FAN AND MOTOR SHALL BE SIZED APPROPRIATELY TO MEET THIS DEFINITION OF EXTERNAL STATIC PRESSURE.
 3. PROVIDE HONEYWELL #TH8320R1003JU VISIONPRO 8000 WITH REDLINK INCLUDE WIRELESS ADAPTER, REDLINE INTERNET GATEWAY, REMOTE INDOOR SENSOR, AND ECONOMIZER OUTPUT. ECONOMIZER/OUTDOOR AIR DAMPER TO CLOSE DURING UNOCCUPIED MODE.
 4. PROVIDE 18" HIGH (AT LOWEST POINT) PRE-FABRICATED INSULATED ROOF CURB WITH SLOPE TO MATCH SLOPE OF ROOF FOR EACH UNIT.
 5. PROVIDE HAIL GUARDS FOR EACH UNIT.
 6. DISCONNECTS BY RTU MANUFACTURER. MECHANICAL CONTRACTOR TO COORDINATE UNIT MOCPP WITH ELECTRICAL CONTRACTOR.
- NOTES:
LL TO PURCHASE AND INSTALL RTU AND CURBS.

NATIONAL ACCOUNT INFORMATION

FREDDY'S FROZEN CUSTARD HAS NATIONAL ACCOUNT AGREEMENTS FOR ROOF TOP UNITS WITH LENNOX AND TRANE. NO ALTERNATE MANUFACTURERS ARE ALLOWED.

FOR LENNOX EQUIPMENT CONTACT:
DAVE EBNER, LENNOX INDUSTRIES NATIONAL ACCOUNT MANAGER, (612) 860-5933, Dave.Ebner@lennoxind.com

FOR TRANE EQUIPMENT EQUAL TO THE UNITS SPECIFIED CONTACT:
TOM ROOD OR PAUL MINOCK, TRANE ACCOUNT MANAGER - NATIONAL ACCOUNTS, (800) 729-9115, TOM.ROOD@TRANE.COM, P.MINOCK@TRANE.COM

DIFFUSER SCHEDULE

MARK	MFR	MODEL	NECK SIZE	FACE SIZE	FINISH	REMARKS
SD-1	TITUS	TMR	12"0	22"0	WHITE	WITH OPPOSED BLADE DAMPER, FIELD PREP FOR PAINTING
SD-2	TITUS	TMS3	10"0	24"x24"	WHITE	
SD-3	TITUS	PAS3	10"0	24"x24"	WHITE	
SD-4	TITUS	T3SQ4	8"0	24"x24"	WHITE	THERMAL VAV DIFFUSER
SD-5	TITUS	TMS3	6"0	12"x12"	WHITE	WITH OPPOSED BLADE DAMPER AND TRM KIT
SD-6	TITUS	TMS3	8"0	24"x24"	WHITE	WITH OPPOSED BLADE DAMPER AND TRM KIT
SD-7	TITUS	TMS3	8"0	12"x12"	WHITE	WITH OPPOSED BLADE DAMPER AND TRM KIT
RG-1	AMER. LOUVER CO.	STRATL	20"x20"	24"x24"	WHITE	SEE NOTE 1.
RG-2	TITUS	330RL	8"x8"	-	WHITE	
RG-3	TITUS	50F	10"x22"	24X12	WHITE	

- NOTES:
1. RETURN GRILL TO BE PLASTIC FILTER RETURN. FILTER TO BE AMERICAN AIR FILTER (AAF) FRONTLINE GREEN 1", WITH AAF AMERFRAME SIZE 20x20x1.

EXHAUST FAN SCHEDULE

MARK	MFR	MODEL	CFM	EXTERNAL STATIC P. IN. WG.	RPM	ELECTRICAL		FAN TYPE	REMARKS
						VOLT/PHZ	PWR		
EF-1	COOK	GC-146	75	0.25	900	120/1/60	30.3W	CEILING EXH.	
EF-2	COOK	GC-168	150	0.25	1099	120/1/60	50.4W	CEILING EXH.	

- NOTES:
1. PROVIDE CEILING GRILLE, INTEGRAL BACK DRAFT DAMPER, DISCONNECT SWITCH, AND VARIABLE SPEED CONTROLLER.
 2. FANS SHALL NOT EXCEED SCHEDULED RPM.

PUMP SCHEDULE

MARK	SERVICE	GPM	HEAD	EFFICIENCY	MOTOR			PIPE INCHES		FLOW	STARTER BY	REMARKS
					HP	RPM	ELECTRICAL	SUCTION	DISCHARGE			
RCP-1	DOMESTIC HW	10	6	-	1/8	3250	115/60/1	-	-	CONST	-	(1)

REMARKS:
(1) SELECTION BASED ON BELL & GOSSETT INLINE PUMP MODEL PL-30. ALL BRONZE CONSTRUCTION.

BUILDING AIR BALANCE SCHEDULE

MARK	SPACE OR AREA	EXHAUST AIR CFM	OUTSIDE AIR CFM	RETURN AIR CFM	SUPPLY AIR CFM	REMARKS
RTU-1	DINING	--	1000	4850	4850	--
RTU-2	DINING	--	300	3000	3000	--
MAU-1	KITCHEN	--	1900	0	1900	--
KEF-1	RANGE - KITCHEN HOOD	1600	--	--	--	--
KEF-2	FRYERS - KITCHEN HOOD	775	--	--	--	--
EF-1	WOMEN'S RESTROOM	75	--	--	--	--
EF-2	MEN'S RESTROOM	150	--	--	--	--
TOTALS	BUILDING TOTALS	2,600	3,200	5,150	9,750	NOTE: AREA IS 600 CFM POSITIVE



THE DESIGN AND DETAILS DISCLOSED HEREIN ARE THE EXCLUSIVE PROPERTY OF DAN WINTER ARCHITECT AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT PRIOR WRITTEN CONSENT.

DAN WINTER, ARCHITECT

FREDDY'S FROZEN CUSTARD
EMORY VIEW SHOPPING CENTER
229 E. EMORY RD., BLDG. 'D/2', SUITE 101-D/2
POWELL, TN.

DAN WINTER ARCHITECT
1024 EAST FIRST STREET
WICHITA, KS. 67214
PH. 316-267-7142


MECHANICAL DETAILS

DATE
2/11/2022

DRAWN BY:
CHECKED BY:

SHEET NO.
M2

ND-2 HANGING ANGLE DETAIL



HOOD AND NUTS TO BE SUPPLIED BY INSTALLING CONTRACTOR. HANGING ANGLE IS PRE-FURNISHED AT FACTORY.

HANGING ANGLE LOCATIONS

HOOD STYLE	DIM FROM REAR	DIM FROM FRONT (24\"/>	
CANOPY ND2	4.166"	2.246"	2.246"
ND2-PSP-F	4.166"	2.246"	2.246"
BACKSHELF BD-2	4.166"	2.246"	-
VHB/VHB-G	36"X36"	42"X42"	48"X48"
FRONT/BACK DIMS BY SIZE	2.246"	2.246"	2.246"

CALCULATIONS UTILIZED

EXHAUST CFM=LENGTH OF HOOD X CFM/LIN.FT. (LOAD)
 SUPPLY CFM=EXHAUST CFM X PERCENTAGE REQUIRED
 TOTAL DUCT AREA=144 X $\frac{CFM}{FMQ}$
 DUCT LENGTH= $\frac{TOTAL DUCT AREA}{DUCT DEPTH}$

*CAPTIVE-AIRE DUCT CONNECTION SIZES ARE CALCULATED USING AN EXHAUST VELOCITY OF 1500-1800 FPM AND A SUPPLY VELOCITY OF 300-400 FPM.

BUILDING CODES

CAPTIVE-AIRE HOODS ARE BUILT IN COMPLIANCE WITH:
 ETL LISTED
 IFTL
 INTERTEK
 LISTED UNDER ETL FILE NUMBER 3054804-001/002



CLEARANCE TO COMBUSTIBLES

MATERIAL	CLEARANCE REDUCTION SYSTEM
NON-COMBUSTIBLE	NONE REQUIRED
LIMITED-COMBUSTIBLE	3" UNINSULATED STANDOFF
COMBUSTIBLE	1" INSULATED STANDOFF

GENERAL NOTES

- INSTALLATION**
- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
 - ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
 - HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
 - ALL CONNECTIONS FROM CAPTIVE-AIRE DUCT PER MECHANICAL CONTRACTOR'S PLANS.
 - COOKING EQUIPMENT TO SHUTOFF IN EVENT OF FIRE.
 - EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
 - ALL LIGHTS FEATURE SHOWN INSTALLED BY CAPTIVE-AIRE ARE FACTORY PREWIRED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES BY ELECTRICAL CONTRACTORS.
 - LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
 - SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTORS.
 - INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTEGRATION, AND ADMINISTRATION OF CODE REQUIREMENTS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.
- BALANCE**
- KITCHEN HOODS MUST BE BALANCED WITH KITCHEN.
 - KITCHEN SHALL BE NEGATIVE WITH RESPECT TO DINING AREA.
 - RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.
- ADDITIONAL**
- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
 - SIGNED AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE RECEIVED BY FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

FILTER DETAIL



CaptiveAire Captrate Solo Filter
 ETL Listed Grease Extracting Filters
 Made From 430 Stainless Steel

HOOD INFORMATION - JOB#5266912

HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST PLENUM (RISERS)					MUA CFM	AC CFM	HOOD CONSTRUCTION	HOOD CONFIG		
										WIDTH	LENG	HEIGHT	DIA	CFM				VEL	SP	END TO END
1	ITEM 33A	5424	ND-2-ACPS-P-F	CAPTIVEAIRE	8' 0"	450 DEG	1	MEDIUM	200	1600	4"	14"	1600	1407	-0.734"	1280	505	430 SS WHERE EXPOSED	ALONE	FRONT
2	ITEM 33B	5424	ND-2-ACPS-P-F	CAPTIVEAIRE	5' 0"	450 DEG	1	MEDIUM	155	775	4"	10"	775	1421	-0.436"	620	309	430 SS WHERE EXPOSED	ALONE	ALONE

PATENT NUMBERS
 AC-PSP (UNITED STATES) - US PATENT 7068300 B2
 AC-PSP WALL (CANADA) - CA PATENT 2202059
 AC-PSP ISLAND (CANADA) - CA PATENT 2520330

HOOD INFORMATION

HOOD NO	TAG	TYPE	QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE	UTILITY CABINET(S)		ELECTRICAL	SWITCHES	FIRE SYSTEM	HOOD SYSTEM PIPING	HOOD WEIGHT	
												TYPE	SIZE						
1	ITEM 33A	CAPTRATE SOLO FILTER	5	16"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO	LEFT	12"X4"X24"	TYPE	SIZE	MODEL #	QUANTITY			NO	681 LBS
2	ITEM 33B	CAPTRATE SOLO FILTER	3	16"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO						1 FAN			NO	432 LBS

HOOD OPTIONS


HOOD NO	TAG	OPTION
1	ITEM 33A	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT, BACK LEFT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. RIGHT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. FINISHED BACK - GROUND/POLISH 96.00" LONG FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT RIGHT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. RIGHT VERTICAL END PANEL 27" TOP WIDTH, 21" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS.
2	ITEM 33B	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT LEFT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. RIGHT VERTICAL END PANEL 27" TOP WIDTH, 21" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS.

PERFORATED SUPPLY PLENUM(S)


HOOD NO	TAG	POS	LENGTH	WIDTH	HEIGHT	TYPE	RISERS				
							WIDTH	LENG	DIA	CFM	SP
1	ITEM 33A	Front	108"	24"	6"	MUA	12"	256	0.084"		
						MUA	12"	256	0.084"		
						MUA	12"	256	0.084"		
						MUA	12"	256	0.084"		
						AC	8"	101	0.033"		
						AC	8"	101	0.033"		
						AC	8"	101	0.033"		
						AC	8"	101	0.033"		
						MUA	10"	155	0.047"		
						MUA	10"	155	0.047"		
2	ITEM 33B	Front	60"	22"	6"	MUA	10"	155	0.047"		
						MUA	10"	155	0.047"		
						MUA	10"	155	0.047"		
						MUA	10"	155	0.047"		
						AC	8"	103	0.034"		
						AC	8"	103	0.034"		
						AC	8"	103	0.034"		
						AC	8"	103	0.034"		
						MUA	10"	155	0.047"		
						MUA	10"	155	0.047"		

SPECIFICATION: CAPTRATE GREASE-STOP SOLO FILTER

THE CAPTRATE GREASE-STOP SOLO FILTER IS A SINGLE-STAGE FILTER FEATURING A UNIQUE S-BAFFLE DESIGN IN CONJUNCTION WITH A SLOTTED REAR BAFFLE DESIGN TO DELIVER EXCEPTIONAL FILTRATION EFFICIENCY.
 FILTER IS STAINLESS STEEL CONSTRUCTION, AND SIZED TO FIT INTO STANDARD 2-INCH DEEP HOOD CHANNELS.
 UNITS SHALL INCLUDE STAINLESS STEEL HANDLES AND A FASTENING DEVICE TO SECURE THE TWO COMPONENTS WHEN ASSEMBLED.
 GREASE EXTRACTION EFFICIENCY PERFORMANCE SHALL REMOVE AT LEAST 75% OF GREASE PARTICLES FIVE MICRONS IN SIZE, AND 85% GREASE PARTICLES SEVEN MICRONS IN SIZE AND LARGER, WITH A CORRESPONDING PRESSURE DROP NOT TO EXCEED 1.0 INCHES OF WATER GAUGE.
 THE CAPTRATE GREASE-STOP SOLO WAS TESTED TO ASTM STANDARD ASTM F2919-05 MANUFACTURER APPROVED FOR USE IN SOLID FUEL APPLICATIONS AS A SPARK ARRESTER.
 EFFICIENCY VS PARTICLE DIAMETER




CAPTIVE FILTERS ARE BUILT IN COMPLIANCE WITH:
 NFPA #96
 NSF STANDARD #2
 UL STANDARD #1046
 INT. MECH. CODE (IMC)
 ILC-5846




PLAN VIEW - HOOD #1 (ITEM 33A)
 8' 0.00" LONG 5424ND-2-ACPS-P-F

ACPSHIPS LOOSE FOR FIELD INSTALLATION




SECTION VIEW - MODEL 5424ND-2-ACPS-P-F
 HOOD - #1 (ITEM 33A)




PLAN VIEW - HOOD #2 (ITEM 33B)
 5' 0.00" LONG 5424ND-2-ACPS-P-F

ACPSHIPS LOOSE FOR FIELD INSTALLATION




SECTION VIEW - MODEL 5424ND-2-ACPS-P-F
 HOOD - #2 (ITEM 33B)




ASSEMBLY INSTRUCTIONS

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TRI GRADE 5 (MINIMUM) ALL-THREAD, SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TRI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION BENEATH HOOD HANGING ANGLES AND ABOVE CEILING ANCHORS. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.



ASSEMBLY INSTRUCTIONS

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TRI GRADE 5 (MINIMUM) ALL-THREAD, SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TRI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION ABOVE CEILING ANCHORS. SINGLE HEX NUT BENEATH HANGING ANGLE IS ACCEPTABLE FOR FULL LENGTH HANGING ANGLES. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.



ASSEMBLY INSTRUCTIONS

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TRI GRADE 5 (MINIMUM) ALL-THREAD, SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TRI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION ABOVE CEILING ANCHORS. SINGLE HEX NUT BENEATH HANGING ANGLE IS ACCEPTABLE FOR PSP HANGING ANGLES. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.

FOR QUESTIONS, CALL THE KANSAS CITY REGIONAL OFFICE
 1126 SWIFT STREET, KANSAS CITY, MO 64116
 PHONE: (816) 221-8575
 FAX: (816) 221-8311

CUSTOMER APPROVAL TO MANUFACTURE:

Approved as Noted
 Approved with NO Exception Taken
 Revise and Resubmit
 SIGNATURE _____
 Your Title _____ Date _____

***** NOTE *****
 ALL WALLS AND STRUCTURES THAT COME WITHIN 18" OF HOOD MUST BE METAL STUDS AND SHEETROCK. WOOD STUDS OR ANY OTHER COMBUSTIBLE MATERIAL WITHIN 18" OF HOOD NO ALLOWED.

***** NOTE *****
 HOOD MANUFACTURER RECOMMENDS NO RETURNS OR 4-WAY DIFFUSERS WITHIN 10 FEET OF HOOD IN ALL DIRECTION.

***** NOTE *****
 MAKEUP AIR SHALL BE DELIVERED INTO SPACE IN MANNER THAT WILL NOT DISRUPT HOODS ABILITY TO CAPTURE AND CONTAIN.



THE DESIGN AND DETAILS DISCLOSED HEREIN ARE THE EXCLUSIVE PROPERTY OF DAN WINTER ARCHITECT AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT PRIOR WRITTEN CONSENT.

DAN WINTER, ARCHITECT

FREDDY'S FROZEN CUSTARD
 EMORY VIEW SHOPPING CENTER
 229 E. EMORY RD., BLDG. 'D/2', SUITE 101-D/2
 POWELL, TN.

DAN WINTER ARCHITECT
 1024 EAST FIRST STREET
 WICHITA, KS. 67214
 PH. 316-267-7142




DATE
 2/11/2022

DRAWN BY:
 CHECKED BY:

SHEET NO.
M3


ELECTRICAL PACKAGE - JOB#5266912

NO	TAG	PACKAGE#	LOCATION	QUANTITY	OPTION	FAN CONTROLLED	HP	VOL-T	FLA		
1	ECM-1	DCV2111	UTILITY CABINET LEFT	1 LIGHT	SMART CONTROLS DCV						
			HOOD # 1	1 FAN							
						FAN TAG	TYPE	HP	VOL-T	FLA	
						ITEM T-1	EXHAUST	3	1,000	206	3.8
						ITEM T-2	EXHAUST	1	5,000	115	8.3
						MUA-1	SUPPLY	3	3,000	208	8.8



Demand Control Ventilation Hood Control Panel Specifications:

- Controls shall be listed by ETL (UL 308A) and shall comply with demand ventilation system shutdown requirements outlined in IECC 403.2.8 (2015).
- The control enclosure shall be NEMA 1 rated and listed for installation inside of the exhaust hood utility cabinet. The control enclosure may be constructed of stainless steel or painted steel.
- Temperature probe(s) located in the exhaust duct riser(s) shall be constructed of stainless steel.
- A digital controller shall be provided to activate the hood exhaust fans dynamically based on a fixed differential between the ambient and duct temperature sensors. The function shall meet the requirements of IMC 507.1.1.
- A digital controller shall provide adjustable hysteresis settings to prevent cycling of the fans after the cooling appliances have been turned off and/or the heat in the exhaust system is reduced.
- A digital controller shall provide an adjustable minimum fan run-time setting to prevent fan cycling.
- Variable Frequency Drives (VFDs) shall be provided for fans as required. The digital controller shall modulate the VFDs between a minimum setpoint and a maximum setpoint on demand. The duct temperature sensor output(s) to the digital controller shall be used to calculate the speed reference signal.
- The VFD speed range of operation shall be from 0% to 100% for the system, with the actual minimum speed set as required to meet minimum ventilation requirements.
- An internal algorithm to the digital controller shall modulate supply fan VFD speed proportional to all exhaust fans that are located in the same fan group as the supply fan.
- The system shall operate in PREP MODE during light cooking load or COOL DOWN MODE when sufficient heat remains underneath the hood system after cooking operations have completed. Operation during either of these periods will disable the supply fans and provide an exhaust fan speed that is equal to the minimum ventilation requirement.
- A digital controller shall disable the supply fan(s), activate the exhaust fan(s), activate the appliance shutoff tray, and disable an electric gas valve automatically when fire condition is detected on a covered hood.
- A digital controller shall allow for external BMS fan control via Dry Contact (external control shall not override fan operation logic as required by code).
- An LCD interface shall be provided with the following features:
 - On/Off push button fan & light switch activation
 - Integrated gas valve reset for electronic gas valves (no reset relay required)
 - VFD Fault display with audible & visual alarm notification
 - Duct temperature sensor failure detection with audible & visual alarm notification
 - Mid-wind duct temperature sensor detection with audible & visual alarm notification
 - A single low-voltage Cat-5 RJ45 wiring connection
 - An energy savings indicator that utilizes measured kWh from the VFDs




Sequence of Operations:

- The hood control panel is capable of operating in one or more of the following states at any given time:
 - **Automatic:** The system operates based on the differential between room temperature and the temperature at the hood cavity or exhaust duct collar. Fans activate as a configurable temperature differential threshold. Depending on the job configuration each fan zone can be configured as static or dynamic. These terms refer to whether a variable motor (such as EC Motors or VFD driven motors) modulate with temperature. If the panel is equipped with variable speed fans and the zone is defined as "dynamic", these will modulate within a user-defined range based on the temperature differential. Panels equipped with variable speed fans and a fan zone defined as "static", fans will run at a set speed calculated for the drive. Demand control ventilation systems are capable of modulating exhaust and make up air fan speeds per the requirements outlined in IECC 403.2.8.
 - **Manual:** The system operates based on human input from an HMI.
 - **Schedule:** A weekly schedule can be set to run fans for a specified period throughout the day. There are three occupied times per day to allow for the user to set up a time that is suitable to their needs. Any time that is within the defined occupied time, the system will run at modulation mode and follow the fan procedure algorithm based on temperature during this time. During unoccupied time, the system will have an extra offset to prevent unintended activation of the system during a time where the system is not being occupied.
 - **Other:** The system operates based on the input from an external source (ODC, BMS or hard-wired interlock).

SPECIFICATIONS

- THE RESTAURANT FIRE SUPPRESSION SYSTEM SHALL BE THE PRE-ENGINEERED TYPE WITH A FIXED NOZZLE AGENT DISTRIBUTION NETWORK. IT SHALL BE LISTED WITH UNDERWRITERS LABORATORIES, INC. (UL)
- THE SYSTEM SHALL BE CAPABLE OF AUTOMATIC DETECTION AND ACTUATION WITH LOCAL OR REMOTE MANUAL ACTUATION. ACCESSORIES SHALL BE AVAILABLE FOR MECHANICAL OR ELECTRICAL GAS LINE SHUT-OFF APPLICATIONS.
- THE EXTINGUISHING AGENT SHALL BE A POTASSIUM CARBONATE, POTASSIUM ACETATE BASED FORMULATION DESIGNED FOR FLAME KNOCKDOWN AND SECUREMENT OF GREASE RELATED FIRES. IT SHALL BE AVAILABLE IN PLASTIC CONTAINERS WITH INSTRUCTIONS FOR LIQUID AGENT HANDLING AND USAGE.
- THE REGULATED RELEASE MECHANISM SHALL BE COMPATIBLE WITH A FUSIBLE LINK DETECTION SYSTEM. THE FUSIBLE LINK SHALL BE SELECTED AND INSTALLED ACCORDING TO THE OPERATING TEMPERATURE IN THE VENTILATING SYSTEM. THE FUSIBLE LINK SHALL BE SUPPORTED BY A DETECTOR BRACKET/ LINKAGE ASSEMBLY.



TYPICAL ANSUL R-102 SYSTEM LAYOUT



THE DESIGN AND DETAILS DISCLOSED HEREIN ARE THE EXCLUSIVE PROPERTY OF DAN WINTER ARCHITECT AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT PRIOR WRITTEN CONSENT.

DAN WINTER, ARCHITECT

FREDDY'S FROZEN CUSTARD
EMORY VIEW SHOPPING CENTER
 229 E. EMORY RD., BLDG. 'D/2', SUITE 101-D/2
 POWELL, TN.

DAN WINTER ARCHITECT
 1024 EAST FIRST STREET
 WICHITA, KS. 67214
 PH. 316-267-7142

DATE
 2/11/2022

DRAWN BY:
 CHECKED BY:

SHEET NO.
M6

Mechanical Specifications

Table of Contents

Division 23 - Mechanical

23000 - Heating & Ventilating, and Air Conditioning, General

23001 - Operation & Maintenance Manuals

23003 - Testing, Adjusting, & Balance

23013 - Insulation, Low Pressure Duct

23016 - HVAC Insulation, General

23090 - Controls, Electric

23113 - Ductwork, Low Pressure, Galvanized Steel

23116 - Ductwork, Low Pressure, Flexible

23117 - Diffusers, Registers, & Grilles

23540 - Air Distribution Equipment (Furnaces, Condensing Units & Exhaust Fans)

237413 - Packaged, Outdoor, Central-Station Air-Handling Units

23000 - Heating & Ventilating, and Air Conditioning, General

PART 1 - GENERAL

1.1 DESCRIPTION

A. Section 23000 pertains to heating, ventilating, and air conditioning (HVAC) work. This section applies to and governs all HVAC sections.

B. Refer to other divisions for continuation of exterior work.

1.2 PERMITS, FEES, CODES, ORDINANCES, AND REGULATIONS

A. Obtain and pay for all permits, inspections and connection fees required by governing bodies in connection with the work. Deliver certificates of inspection to the owner.

B. All work shall comply with governing codes, ordinances, and regulations of the city, county, and state having jurisdiction, and the national electrical code, mechanical code, and requirements of the Board of Health.

1.3 QUALITY ASSURANCE

A. Industry standards and codes. Unless modified by these specifications, the design, manufacture, testing, and methods of installing all materials, apparatus and equipment shall conform to the following:

1. ARI Code for Refrigeration Apparatus.
2. ANSI B91.1 Safety Code for Mechanical Refrigeration.
3. Standards of National Fire Protection Association.
4. SMACNA.
5. ASHRAE.

B. Submittals

A. Product data: Submit on all materials, products, and equipment unless otherwise specified or acknowledged in writing.

B. Samples: Submit when specified or requested.

C. Operation and maintenance manuals: Submit copies of O and M manuals to Architect.

1.5 JOB CONDITIONS

A. Protect materials, apparatus, and equipment from damage, moisture, dirt, debris, and work of other trades.

B. Use of paper, cardboard, or other flimsy material will not be permitted. Replace damaged protective materials immediately. Do not install damaged materials and equipment; remove from the site.

1.6 RECORDED DOCUMENTS

A. Furnish owner with one set of accurately marked blue-line copies of the drawings, indicating all changes from the contract drawings and all work and controls as installed.

1.7 GUARANTEE AND SERVICE

A. Where standard guarantees are called for herein, furnish three (3) copies to be inserted in operation and maintenance manuals.

B. All preventative maintenance and normal service will be performed by the owner's maintenance personnel after final acceptance of the work. This shall not alter the contractor's guarantee of the work in any way.

C. All labels shall be securely affixed.

PART 2 - PRODUCTS

2.1 GENERAL

A. All materials and equipment shall be new. Systems shall be provided complete, and each system as a whole, and in all its parts, shall function correctly up to the specified capacity. Should a system, or any part thereof fail to meet performance requirements by the owner, necessary replacements, alterations, or repairs, as required by the owner, shall be made to bring performance up to specified requirements of building construction and finished damaged or marred by such replacements, alterations, or repairs shall be restored to prior conditions, at no additional cost to the owner.

B. Where multiple items of equipment of materials are required, they shall be the product of a single manufacturer. Before ordering any equipment, the size of all equipment shall be checked to easily fit spaces allotted on the drawings.

C. Where pipe, sleeve supports, and anchorage of air conditioning equipment shall be provided as specified herein. Where such items are to set or embedded in concrete, masonry, or similar work, the items shall be furnished and layout made at the proper time for the setting or embedment thereof so as to cause no delay in the work.

E. Piping assemblies of equipment shown on the drawings are diagrammatic. All piping and appurtenances required for the proper operation of all equipment shall be provided.

2.2 MANUFACTURER'S NAMES AND CATALOG NUMBERS

A. Specific references have been made to one or more manufacturer's names and name or catalog numbers. This does not indicate that the material and equipment specified is necessarily an "off the shelf" item. Requirements for specific finishes, materials, or other modifications may differ from those of the manufacturer's standards. Contractor shall ascertain that such modifications are fully considered.

2.3 DIAGRAMS, NAMEPLATES, AND LABELS

A. Each major component of equipment shall have the manufacturer's names, address, and catalog number on a plate securely affixed in a conspicuous place. The nameplate of a distributing agent will not be accepted.

B. All pieces of equipment, valves, starters, disconnects, and all pneumatic and electrical control instruments and apparatus shall be identified with 1/16" thick black laminated plastic nameplates, with 3/16" high white laminated letters. Similar and line equipment shall be designated with numerical suffix (Example: Thermostat, T-1). The nameplate identifications shall coincide with items appearing on diagrams.

C. Provide a label for the mechanical system stating:

"Installation by (Name, Address, and Phone Number of Contractor)"

D. Letters shall be 1/4" high and located on a conspicuous place in the mechanical room.

PART 3 - EXECUTION

3.1 INSTALLATION AND WORKMANSHIP

A. The work shall be performed by qualified mechanics and all materials, apparatus, and equipment shall be installed in neat, workmanlike matter. Any material, apparatus, or equipment which in the opinion of the owner, is improperly installed shall be removed and the reinstalled in an approved manner at no additional cost to the owner.

B. The work shall be coordinated with the work of other trades. Where the work is dependent upon work of other trades or work already in place, such other work and work in place shall be examined and shall be in proper condition and state of completion before continuing the installation.

C. The installation of the system shall, in general, be in accordance with the drawings with regards to location of equipment, ducts, pipes, and the like. Piping ductwork shall be followed as accurately as actual construction will permit and any deviations whatsoever shall be called to the attention of the architect-engineer. Where necessary, as determined by the architect-engineer, contractor shall furnish drawings showing proposed changes.

3.2 EARTHWORK AND Dewatering

A. Perform in accordance with Division 2.

3.3 CUTTING AND PATCHING

A. Layout openings for cutting by other trades as required.

B. Cutting of steel, concrete, or any other structural part must be approved in writing by owner prior to cutting.

3.4 WATERPROOFING

A. Do not cut or penetrate waterproofed surfaces, or waterproofing membranes, without first making arrangements for repair by a method approved by architect-engineer.

B. Copies of certificates of inspection.

C. Contractors, including extended guarantees.

3.5 ELECTRICAL WORK

A. Power wiring from panels to motor controllers and from controllers to motors is specified in Division 16.

B. Motor starters not specified to be provided with the motors at the factory area specified in Division 16.

C. Submit wiring diagrams for approval provided with motors that the electrical work may be properly accomplished.

D. Electrical control wiring for connection of temperature controllers, push buttons, interlocks in motor controllers, and like items is specified in the control section (a) in this division. Furnish all equipment with complete internal control wiring.

E. Electrical work specified in this division shall conform to applicable provisions of Division 16. All control wiring shall be in conduit.

F. Provide motors conforming to characteristics shown on electrical drawings.

3.6 SUPPORTS FOR PIPING AND EQUIPMENT

A. Support for piping shall be furnished from structural members and not from metal deck and slab assemblies.

3.7 ACCESS DOORS (ACCESS PANELS)

A. Provide access doors for maintenance, adjustment, removal, and repair of valves, controls, dampers, equipment, and like items furnished hereunder.

B. Provide access doors where required. Panels shall be located to make all items easily accessible.

3.8 CLEAN UP

A. Refer to general conditions for cleaning-up.

B. Clean all materials and equipment of dirt, dust, paint, spots and stains, soil marks, and other foreign matter.

3.9 FINAL INSPECTION

A. Notice to the architect-engineer that the work is ready for final inspection. The contractor shall:

1. Submit test and balance report and complete requirements as noted.
2. Submit letter from control manufacturer certifying that controls have been checked for operation and calibration, and that system is operating as intended.

B. Contractor shall furnish necessary mechanics to operate system, make necessary adjustments and assist with final inspection.

3.10 INSTRUCTION OF OWNERS OPERATING PERSONNEL

A. The contractor shall include the cost of the services of qualified instructor(s) to instruct the owner's operating personnel in the operation, adjustment, care, and maintenance of all HVAC equipment and systems.

B. Instruction shall be performed at a time approved by the owner and after all HVAC equipment and systems are installed, complete, adjusted, and operating to specified requirements, contractor shall notify the architect-engineer when instructions will be given.

C. Qualifications of instructors shall be subject to approval of the owner and equipment manufacturer.

D. Additional requirements concerning operation and maintenance of mechanical equipment and systems may be specified in other sections.

E. Two (2) copies of acknowledgment of all required instructions to owner's operating personnel, signed by the owner or his authorized representative, shall be submitted prior to submitting application for final payment. An additional copy of this acknowledgment is required in each copy of operation and maintenance manuals required in the section "Operation & Maintenance Manuals."

END OF SECTION

23001 - Operation & Maintenance Manuals

PART 1 - GENERAL

1.1 DESCRIPTION

A. Furnish one (1) copies of complete operation and maintenance manuals to the owner, for approval and for the owner, on all equipment and systems. The manuals shall be bound in hard-back, three ring loose-leaf binders.

PART 2 - PRODUCTS

2.1 MANUAL CONTENTS

A. Title sheet with job name, and the names, addresses, and phone numbers of the contractor, subcontractor, control subcontractor, related contractors and material and equipment suppliers.

B. Table of contents.

C. A copy of acknowledgment of instruction to the owner's operating personnel in the operation of all mechanical equipment and systems, signed by the owner or his authorized representative.

D. Typewritten operating instructions for the owner's personnel describing how to stop and start each piece of equipment; how to set the temperature control system for normal operation and normal restarting procedures, caution and warning notices. Record drawings of all systems including electrical and control diagrams.

PART 3 - EXECUTION

3.1 DELIVERY

A. Deliver the manuals to the Architect at substantial completion.

END OF SECTION

23093 - Testing, Adjusting, & Balance

PART 1 - GENERAL

1.1 SPECIAL NOTICE

A. Each contractor shall read all relevant documents, become familiar with the job, scope of work, type of general construction, and the architectural, structural, mechanical, and electrical drawings and specification. Each contractor shall also familiarize himself with the purpose for which these documents have been prepared and shall become cognizant of all the details involved. Each contractor shall coordinate his work with that of others.

B. An independent test and balance contractor shall provide test and balance services. TAB contractor shall be NEBS or AABC certified. TAB contractor shall be National TAB and contracted through the building owner.

STARTUP TEST AND ADJUSTMENT

1.2 TEST AND ADJUSTMENT

A. Startup, testing, and adjusting this equipment is to be put into final operating condition for the owner's use and benefit. All tests of equipment and systems required to prove compliance with the drawings and specification shall be performed in the presence of the owner's representative.

1.3 GENERAL

A. Inquire about any problems or complaints.

B. Compare mechanical plans to installed system.

C. Document design specifications for report.

D. Ensure all fans are running for balance.

E. Measure initial building pressure.

1.4 INSPECT ROOFTOP EQUIPMENT

A. Inspect units and note any deficiencies.

B. Record unit nameplate data.

C. Check thermostats for proper settings.

D. Check for correct fan rotation (including condenser fans).

E. Check conditions of filters and coils.

F. Check position of outside air dampers.

G. Check gas lines and condensate lines.

H. Check belt tension and pulley alignment.

I. Check disconnect switches for proper placement.

J. Check any fan noise and vibration.

K. Check heat-cool modes of RTUs.

1.5 TEST AND BALANCE KITCHEN HOOD SYSTEM (WHERE APPLICABLE)

A. Measure supply and exhaust FPM hoods.

B. Observe hood smoke capture and equipment on fan.

C. Adjust supply and exhaust RPM and supply air damper, as required.

D. Note adjustments made on pulleys.

E. Measure final RPM's.

F. Evaluate duct system design and installation.

G. Ensure hood smoke capture and equipment on fan.

1.6 TEST AND BALANCE HEATING/COOLING SYSTEM

A. Measure RTU supply and return airflow systems.

B. Check for drafts, hot/cold spots in occupied spaces.

C. Adjust RPM as necessary to achieve design.

D. Check actual motor amps versus motor rated f.a.

E. Note adjustments made on pulleys.

F. Measure and record motor RPM.

G. Evaluate duct system design and installation.

H. Ensure slightly positive building pressure.

I. Set and record damper positions.

J. Measure final building pressure.

1.7 FINAL REVIEW

A. Review report and data for completeness.

B. Discuss results and findings with superintendent.

C. Air qualities shall be balance to within +/-10% of design as a general rule. However, its come cases, the air quantities may need to be adjusted differently in order to ensure acceptable control levels; hood capture pressure, positive building pressure, etc. Notify the superintendent of any deficiencies needing immediate attention. The G.C. shall have the mechanical and electrical contractors call to promptly correct any such problems (i.e. replace burned out motors, failed thermostats, incorrect wiring, bad coil breakers and starters, dirty filters)

PART 2 - PRODUCTS

PART 3 - EXECUTION

23013 - Insulation, Low Pressure Duct

PART 1 - GENERAL

1.1 DESCRIPTION

A. All low pressure duct systems, two (2) inches water gage or less, shall be insulated.

B. All applicable requirements of this section, "HVAC-Insulation, General," shall apply to this section.

1.2 EQUIVALENT MATERIALS

A. Materials other than those specified will be considered for approved equal.

PART 2 - PRODUCTS

2.1 INSULATION

A. Manufacturer's: Schuller (Johns Manville) Microtex - Textra-Fire - Certain-Teed/Saint - Cobein - Owens Corning - Knauf Fiberglas

B. Insulate internally low velocity rectangular supply ducts, and return air ducts with fiberglass duct liner with a minimum density of 2.0 pounds per cubic foot and a maximum "K" factor of 0.27 at 75 degrees F mean temperature comply with ASTM C 1071 (Type 1). The liner insulation surface coating shall contain an EPA registered, anti-microbial agent so it will not support microbial growth as tested in accordance with ASTM G21 and G22. The liner shall have an NRC not less than the minimum standard listed in ASTM C 1071. Liner for supply ductwork shall be 1"-thick and liner for return ductwork shall be 1"-thick.

C. Insulate internally air recirculating exhaust ducts with 1/2"-thick liner of 2.0 pounds per cubic foot density, as follows: Note: Do not insulate ducts in kitchens.

1. Apply insulation from the fan back down the duct for a distance of 15 feet in all directions. Apply in all branches of multiple branches occur near the fan.

2. Round exposed ducts shall be insulated.

D. Coat all exposed edges with Foster's gray no. 30-70 lagtime adhesive.

E. Adhere liner to interior sides of duct with minimum 50% coverage of fire retardant adhesive such as Foster 85-11, Childrens, or Minnesota Mining. Equivalent to comply with ASCE-A-7001.

F. Use mechanical fastening of Gaskets Hinged Pits, or Sika-Blocks on maximum 18" centers at all sections when width exceeds 12" and/or sides when height exceeds 24". Pins shall comply with SMACNA MF-1.

G. Apply a brush width of Foster's fire retardant coating gray no. 30-70 lagtime over all joints, visible cut edges, and leading edges of insulation to prevent fire erosion.

H. Duct sizes on drawings that do not show dimensions made of lining and sheet metal shall be increased accordingly if adhesive is applied in shop use Foster Spans - FAS 85-11 if applied in field use Foster Spans - FAS adhesive 85-20. Adhesives shall be approved and listed by underwriters laboratory and shall bear the U.L. label.

I. Thickness and classifications of duct liner shall be printed on the face of the liner by the manufacturer.

J. Duct liner shall have and underwriters laboratories fire hazard rating with a flame spread not to exceed 25 and fuel contributed and smoke developed ratings not to exceed 50.

2.2 DUCT INSULATION (EXTERNAL)

A. Manufacturer's: Schuller (Johns Manville) - Textra-Fire - Certain-Teed/Saint - E.O. Wood - Owens Corning - Knauf Fiberglas

B. Insulate externally all round and oval ducts, all concealed rectangular supply air ducts which are noted or specified to have no duct lining: 1/2"-thick and of 0.5 - 0.75 pound density fiberglass ductwrap with a foil-form kraft vapor barrier applied with outward-clinging straps. Insulation to have a minimum R-value of 5.7.

C. Insulation shall be continuous through partitions, coils, etc. Insulate fire damper sleeves to partitions.

D. Exposed round ductwork in dining and lounge areas shall be uninsulated.

2.3 GREASE DUCT INSULATION

A. 1 and 2 Hour; zero clearance Applied Fire Protection for Commercial Kitchen Grease Ducts when tested in accordance with ASTM E 2337. These systems are listed in Section 16.1 to 16.5 - Reference ICC-ES Building Code Report ESR 2213 or ESR 2832, also reference UL Listing HNK1 G-18.

B. 1 and 2 Hour Applied Fire Protection when tested in accordance with UL 1978, Compliant per Interlock Listing TCB1 120-1.

C. 1 and 2 Hour F- and T-Rated Through Penetration Firestop when tested in accordance with ASTM E 814 (UL 1479); UL Through Penetration Listings, C-A1-1562; C-A1-704; F-A-1012; C-A1-7014; C-A1-7019; C-A1-7021; C-A1-7047; C-A1-7095; C-A1-7098; C-A1-7119; F-A-1093; F-A-1094; F-A-3048; F-C-7038; FC-7037; WL-7041; WL-7099; WL-7121; WL-7145; WL-7088.

D. 1 and 2 Hour Applied Fire Protection for Ventilation Air Duct when tested in accordance with ISO 8944-1985 - Reference UL Listings HNLJ V19; HNLJ V26.

E. Manufacturers: Subject to compliance with requirements, provide one of the following:

1. CertainTeed Corp., FlameChok
2. Nelson Fire Stop Products, Nelson FSB Firemashed Blanket
3. Thermal Ceramics, FireMaster XL
4. 3M, Fire Barrier Wrap Products
5. Unifrax Corporation, FireWrap

F. Access Doors (Fire Rated): Thermal Ceramics FireDoor XL (or equal) for duct access to Type I commercial kitchen hood exhaust ductwork. Install access openings at each change in direction and at intervals as required by code. Insulation cover system shall be tested and listed by UL (PNK1 G18) to provide zero clearance to combustible construction and [1] [2] hour fire rating per ASTM E 2336. Duct access cover panel shall be tested and listed by UL (VYS1 HX165) with integral response gasket to provide liquid tight seal and shall have a 90F temperature gasket and signage "Access Door - Do not Obstruct" compliant to code and NFPA 96. Installation shall be performed by an experienced contractor per manufacturer instructions and applicable UL Listings. Sheet metal and insulation contractors shall coordinate installation of the FireDoor XL and duct enclosure system.

PART 3 - EXECUTION

3.1 INSTALLATION

A. All supply and return air ductwork.

B. Air supply diffuser blades and necks:

1. All supply diffusers backs and necks, shall be insulated with one (1) inch-thick, 3/4 pound density, Manville P-series Smaller, or approved equal fiberglass blanket insulation, having a conductance (K) no greater than 0.31. Adhere insulation to the duct as specified below.

END OF SECTION

23016 - HVAC Insulation, General

PART 1 - GENERAL

1.1 DESCRIPTION

A. The section governs all HVAC insulation.

1.2 SUBMITTALS

A. Submit product data covering thermal, permeability, and fire performance characteristics of all insulation material, adhesives, and finishes. Data shall be clearly marked to show intended use, thickness, finishes, adhesives, and application techniques.

PART 2 - PRODUCTS

2.1 INSULATION

A. Insulation shall not be installed until testing procedures have been complied with all surfaces and have been cleaned free of dirt and grease and are completely dried.

B. Protect adjacent surfaces, equipment and premises from dropping of coatings adhesives and finishes. Remove all excess materials and debris from both exposed and concealed areas so that these areas are completely clean.

C. Remove all excess materials and debris from both exposed and concealed areas so that these areas are completely clean.

D. Insulation shall not be applied until the general construction has progressed sufficiently to ensure against physical or moisture damage to the insulation. Replace any insulation which has become wet.

E. Ductwork hanger rods must be installed and perpendicular before insulation is installed.

F. All joints between insulation blankets, sleeves, etc. shall be sealed and taped with 7-mil pressure sensitive tape with adhesive applied to overlapping vapor barriers before tape is applied. Tape to be foil faced, reinforced tape as recommended by insulation manufacturer to maintain all ratings of insulation. Cloth back generic "duct tape" is not acceptable.

G. Insulation to be secured externally to all ductwork as well as permanently joined to other portions of insulation on the same duct per manufacturer's recommendations.

H. All duct insulation is to U.L. Classified.

END OF SECTION

23093 - Controls, Electric

PART 1 - GENERAL

1.1 DESCRIPTION

A. The work consists of installing controls for the HVAC system as on the drawings.

1.2 SUBMITTALS

A. Provide substantial consisting of complete control diagrams for the system with construction details and engineering data sheet on all system components.

1.3 ELECTRICAL

A. Electrical work and materials associated with the control system shall be installed as work of this section but in accordance with Division 16.

B. Power wiring is specified under Division 16 and show on electrical drawings.

C. Electrical control wiring conduit and fittings associated with the space temperature and humidity control including interlocking with motor controllers, control accessories, and appurtenances are to be provided under this section. Control wiring shall be in conduit.

PART 2 - PRODUCTS

2.1 ELECTRONIC ROOM THERMOSTATS AND REMOTE SENSORS

A. Thermostat shall be as specified in the drawings.

B. Thermostat shall have automatic heating-cooling changeover to control operation of the heating and cooling on rooftop air conditioning units.

2.2 SMOKE DETECTION/FAN SHUT-DOWN

A. Smoke detector shall be by integrally installed by the mechanical contractor as specified in the drawings.

B. Remote alarm indicator for duct mounted smoke detectors shall be specified in the drawings.

C. Smoke detector shall be powered as specified in drawings.

PART 3 - EXECUTION

3.1 ELECTRIC ROOM THERMOSTATS

A. Smoke detectors shall be wired as low voltage circuit. (24v)

B. Thermostats and sensors shall be wired as low voltage circuit.

C. Line voltage wiring shall be by the electrical contractor.

D. Mechanical contractor shall provide and install all wiring and necessary appurtenances to perform all of the temperature control sequences.

END OF SECTION

237413 - PACKAGED, OUTDOOR, CENTRAL-STATION AIR-HANDLING UNITS

PART 1 - GENERAL

1.1 SUMMARY

1.1.1 QUALITY ASSURANCE

A. Ducts shall be constructed and installed in accordance with "HVAC Duct Construction Standards" published by the Steel Metal and Air Conditioning Contractors National Association, Inc. (SMACNA)

B. Ductwork shape, size, and location shall be in accordance with plans as closely as possible. Note that duct sizes called out on plans are clear inside dimensions of ductwork. Increase ductwork to accommodate duct liner.

1.2 JOB CONDITIONS

A. Inspect the drawings and verify existing conditions of the field. Report conflicts before starting fabrication.

PART 2 - PRODUCTS

2.1 DUCT MATERIAL

A. Weights and gages shall be in accordance with Table 1 of "HVAC Duct Construction Standards" published by SMACNA as minimum requirements or as per local codes. Duct material shall be galvanized steel.

END OF SECTION

237413 - PACKAGED, OUTDOOR, CENTRAL-STATION AIR-HANDLING UNITS

PART 1 - GENERAL

1.1 SUMMARY

1.1.1 QUALITY ASSURANCE

A. This section includes packaged, outdoor, central-station air-handling units (rooftop units) with the following components and accessories:

1. Direct-expansion cooling
2. Gas furnace.
3. Economizer outdoor air-return air damper section.
4. Integral space-temperature controls.
5. Roof curbs.

1.2 DEFINITIONS

A. Outdoor-Air Refrigerant Coil: Refrigerant coil in the outdoor-air stream to reject heat during cooling operations and to absorb heat during heating operations. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated throughout the system.

B. Outdoor-Air Refrigerant-Coil Fan: The outdoor-air refrigerant-coil fan in RTUs. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated through the system.

C. RTU: Rooftop unit. As used in this Section, this abbreviation means packaged, outdoor, central-station air-handling units. This abbreviation is used regardless of whether the unit is mounted on the roof or on a concrete base on ground.

D. Supply-Air Fan: The fan providing supply air to conditioned space. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.

E. Supply-Air Refrigerant Coil: Refrigerant coil in the supply-air stream to absorb heat (provide cooling) during cooling operations and to reject heat (provide heating) during heating operations. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.

1.3 ACTION SUBMITTALS

A. Product Data: Include manufacturer's technical data for each RTU, including rated capacities, dimensions, required clearances, characteristics, furnished specialties, and accessories.

B. Shop Drawings: Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.

1. Wiring Diagrams: Power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Field quality-control test reports.

B. Warranty.

1.5 CLOSE-OUT SUBMITTALS

A. Operation and maintenance data.

1.6 QUALITY ASSURANCE

A. ARI Compliance:

1. Comply with ARI 210240 and ARI 340360 for testing and rating energy efficiencies for RTUs.
2. Comply with ARI 270 for testing and rating sound performance for RTUs.

B. ASHRAE Compliance:

1. Comply with ASHRAE 159 for refrigerant system sound.
2. Comply with ASHRAE 33 for methods of testing cooling and heating coils.
3. Comply with applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Start-up."

C. ASHRAE/IESNA 91.1 Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

D. NFPA Compliance: Comply with NFPA 90A and NFPA 90B.

END OF SECTION

23316 - Ductwork, Low Pressure, Flexible

PART 1 - GENERAL

1.1 DESCRIPTION

A. Provides where indicated on the drawings and specified herein, factory fabricated and pre-insulated flexible ducts.

1.2 QUALITY ASSURANCE

A. Flexible ducts, including insulation and sealants, shall conform to the requirements of NFPA 90A and UL Standard 181 for class 1 ducts.

B. Performance data shall be based on test performed in accordance with an Diffusion Council flexible air duct test code FD72.

PART 2 - PRODUCTS

2.1 LOW PRESSURE FLEXIBLE DUCTWORK

A. Low pressure flexible ductwork shall consist of constant resistant spring steel helix bonded to a gasket reinforced neoprene sleeve insulated with a minimum of 1 inch-thick, 1 pound density fiberglass insulation which is in turn covered with an outer vapor barrier of fiber reinforced foil-core kraft laminate.

B. Insulation shall have a thermal conductivity (K) no greater than 0.25 at 75 degrees F.

C. Duct for low velocity system connectors shall have a working pressure of not less than 1-1/2 inches of water gage and a maximum operating temperature of not less than 250 degrees F.

2.2 DUCT CONNECTORS

A. Where flexible ducts connect to low pressure ducts to form run-outs to individual outlets, plenums, or low pressure terminals, provide factory fabricated fittings complete with manuals and balancing dampers having locking quadrants. Where low pressure ducts are internally insulated the connector shall be furnished with air extension to project through and protect the insulation for connection to equipment, auxiliary sleeves shall be provided to allow at least 2 inches of surface for clamping of flexible ductwork. Sleeves shall be screwed or bolted to equipment lip frame.

2.3 CLAMPS

A. Provide galvanized spring steel clamps or Panduit straps at connections to duct fittings or devices.

2.4 MANUFACTURER

A. Flexible ductwork and components shall be as manufactured by general environmental corporation or approved by code.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install duct connectors to low pressure ducts using manufacturer's template for all holes and secure the connector with sheet metal screws having first applied Foster's 30-02 duct sealant to the adjoining surfaces. Do not pressurize the system for 48 hours.

B. Stretch new duct when removing it from cartons where it may have been shipped in a compressed state.

C. Use the minimum length of flexible duct required to make the specific connection unless specifically noted otherwise on the drawings. The maximum develop length of flex duct is 4'-0".

D. Avoid sharp bends. Use a minimum inside bend radius equal to one (1) times the inside diameter of the duct.

E. Support horizontal duct runs as detailed in the construction documents.

F. Allow the flexible duct to extend straight away from connectors for a few inches prior to inflating all bends.

G. Adhesive and sealants to connection of flexible duct to the rigid duct or terminate as follows:

1. Apply Foster's 30-02 sealant to the inside of the flexible duct to a depth of three (3) inches.
2. Repair all damage to vapor barrier with Foster's 35-50 reinforced with 4-inch-wide glass fabric and a second coat of Foster's 35-50.

END OF SECTION

23317 - DIFFUSERS, REGISTERS, AND GRILLES

PART 1 - GENERAL

1.1 DESCRIPTION

A. Air distribution devices shall be provided to deliver the indicated volume of supply air without exceeding the available flow with NC rating as follows:

1. Kitchen & Work Areas: NC-45.
2. Dining and Customer Lobby Area: NC-30.

1.2 SUBMITTALS

A. Shop drawings: Indicate locations, spacing air volume, and type of each device.

B. Product data: Manufacturers catalog cuts and product description including air quantity, pattern, throw, pressure drop, NC ratings, finish, dimensions, and complete construction details and materials.

PART 2 - PRODUCTS

2.1 DIFFUSERS, GRILLES, AND REGISTERS

A. Diffusers, grilles, and registers shall be from one of the following manufacturers:

1. Klueger.
3. Pice.
4. Nalor.
6. For model numbers and type see air distribution schedule on drawing.

B. Diffusers, grilles, and registers shall be of the surface, flush, or lay-in type, color corresponding to the ceiling which they are located.

D. The finish of the diffusers, grille, or register face panel shall be as noted on plans.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install where shown on drawings.

B. Diffusers, registers, and fittings shall be securely attached to finish surfaces, or structural member behind finish surfaces.

C. Lay-in diffusers mounted in acoustical ceilings shall be rigidly mounted, above the face panel, to the ceiling suspension system.

END OF SECTION

23540 - Air Distribution Equipment (Exhaust Fans)

PART 1 - GENERAL

1.1 CEILING-MOUNTED VENTILATORS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Greenheck Fan Corporation
2. Loren Cook Company
3. PennFan
4. Twin City Fan

B. Housing: Steel, lined with acoustical insulation.

C. Fan Wheel: Centrifugal wheels directly mounted on motor shaft. Fan shrouds, motor, and fan wheel shall be removable for service.

D. Grille: Plastic, louvered grille with flange on intake and thumbcrew attachment to fan housing.

E. Electrical Requirements: Junction box and electrical connection to housing and reconnected for motor plug-in.

F. Accessories (not included for additional information):

1. Variable-Speed Controller: Solid-state controller to reduce speed from 100 to less than 50 percent.
2. Manual Start Switch: Single-pole rocker switch assembly with cover and pilot light.
3. Time-Delay Switch: Assembly with single-pole rocker switch, timer, and cover plate.
4. Motion Sensor: Motion detector with adjustable shutoff timer.

G. Ceiling Radiation Damper: Fire-rated assembly with ceramic blanket, stainless-steel springs, and fusible link.

6. Filter: Washable aluminum to fit between fan and grille.

7. Isolation: Rubber-in-shear vibration isolators.

8. Manufacturer's standard roof jack or wall cap, and transition fittings.

END OF SECTION

237413 - PACKAGED, OUTDOOR, CENTRAL-STATION AIR-HANDLING UNITS

PART 1 - GENERAL

1.1 SUMMARY

1.1.1 QUALITY ASSURANCE

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Greenheck Fan Corporation
2. Loren Cook Company
3. PennFan
4. Twin City Fan

B. Housing: Steel, lined with acoustical insulation.

C. Fan Wheel: Centrifugal wheels directly mounted on motor shaft. Fan shrouds, motor, and fan wheel shall be removable for service.

D. Grille: Plastic, louvered grille with flange on intake and thumbcrew attachment to fan housing.

E. Electrical Requirements: Junction box and electrical connection to housing and reconnected for motor plug-in.

F. Accessories (not included for additional information):

1. Variable-Speed Controller: Solid-state controller to reduce speed from 100 to less than 50 percent.
2. Manual Start Switch: Single-pole rocker switch assembly with cover and pilot light.
3. Time-Delay Switch: Assembly with single-pole rocker switch, timer, and cover plate.
4. Motion Sensor: Motion detector with adjustable shutoff timer.

G. Ceiling Radiation Damper: Fire-rated assembly with ceramic blanket, stainless-steel springs, and fusible link.

6. Filter: Washable aluminum to fit between fan and grille.

7. Isolation: Rubber-in-shear vibration isolators.

8. Manufacturer's standard roof jack or wall cap, and transition fittings.

END OF SECTION

237413 - PACKAGED, OUTDOOR, CENTRAL-STATION AIR-HANDLING UNITS

PART 1 - GENERAL

1.1 SUMMARY

1.1.1 QUALITY ASSURANCE

A. This section includes packaged, outdoor, central-station air-handling units (rooftop units) with the following components and accessories:

1. Direct-expansion cooling
2. Gas furnace.
3. Economizer outdoor air-return air damper section.
4. Integral space-temperature controls.
5. Roof curbs.

1.2 DEFINITIONS

A. Outdoor-Air Refrigerant Coil: Refrigerant coil in the outdoor-air stream to reject heat during cooling operations and to absorb heat during heating operations. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated throughout the system.

B. Outdoor-Air Refrigerant-Coil Fan: The outdoor-air refrigerant-coil fan in RTUs. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated through the system.

C. RTU: Rooftop unit. As used in this Section, this abbreviation means packaged, outdoor, central-station air-handling units. This abbreviation is used regardless of whether the unit is mounted on the roof or on a concrete base on ground.

D. Supply-Air Fan: The fan providing supply air to conditioned space. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.

E. Supply-Air Refrigerant Coil: Refrigerant coil in the supply-air stream to absorb heat (provide cooling) during cooling operations and to reject heat (provide heating) during heating operations. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.

1.3 ACTION SUBMITTALS

A. Product Data: Include manufacturer's technical data for each RTU, including rated capacities, dimensions, required clearances, characteristics, furnished specialties, and accessories.

B. Shop Drawings: Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.

1. Wiring Diagrams: Power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Field quality-control test reports.

B. Warranty.

1.5 CLOSE-OUT SUBMITTALS

A. Operation and maintenance data.

1.6 QUALITY ASSURANCE

A. ARI Compliance:

1. Comply with ARI 210240 and ARI 340360 for testing and rating energy efficiencies for RTUs.
2. Comply with ARI 270 for testing and rating sound performance for RTUs.

B. ASHRAE Compliance:

1. Comply with ASHRAE 159 for refrigerant system sound.
2. Comply with ASHRAE 33 for methods of testing cooling and heating coils.
3. Comply with applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Start-up."

C. ASHRAE/IESNA 91.1 Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

D. NFPA Compliance: Comply with NFPA 90A and NFPA 90B.

END OF SECTION

23316 - Ductwork, Low Pressure, Flexible

PART 1 - GENERAL

1.1 DESCRIPTION

A. Provides where indicated on the drawings and specified herein, factory fabricated and pre-insulated flexible ducts.

1.2 QUALITY ASSURANCE

A. Flexible ducts, including insulation and sealants, shall conform to the requirements of NFPA 90A and UL Standard 181 for class 1 ducts.

B. Performance data shall be based on test performed in accordance with an Diffusion Council flexible air duct test code FD72.

PART 2 - PRODUCTS

2.1 LOW PRESSURE FLEXIBLE DUCTWORK

A. Low pressure flexible ductwork shall consist of constant resistant spring steel helix bonded to a gasket reinforced neoprene sleeve insulated with a minimum of 1 inch-thick, 1 pound density fiberglass insulation which is in turn covered with an outer vapor barrier of fiber reinforced foil-core kraft laminate.

B. Insulation shall have a thermal conductivity (K) no greater than 0.25 at 75 degrees F.

C. Duct for low velocity system connectors shall have a working pressure of not less than 1-1/2 inches of water gage and a maximum operating temperature of not less than 250 degrees F.

2.2 DUCT CONNECTORS

A. Where flexible ducts connect to low pressure ducts to form run-outs to individual outlets, plenums, or low pressure terminals, provide factory fabricated fittings complete with manuals and balancing dampers having locking quadrants. Where low pressure ducts are internally insulated the connector shall be furnished with air extension to project through and protect the insulation for connection to equipment, auxiliary sleeves shall be provided to allow at least 2 inches of surface for clamping of flexible ductwork. Sleeves shall be screwed or bolted to equipment lip frame.

2.3 CLAMPS

A. Provide galvanized spring steel clamps or Panduit straps at connections to duct fittings or devices.

2.4 MANUFACTURER

A. Flexible ductwork and components shall be as manufactured by general environmental corporation or approved by code.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install duct connectors to low pressure ducts using manufacturer's template for all holes and secure the connector with sheet metal screws having first applied Foster's 30-02 duct sealant to the adjoining surfaces. Do not pressurize the system for 48 hours.

B. Stretch new duct when removing it from cartons where it may have been shipped in a compressed state.

C. Use the minimum length of flexible duct required to make the specific connection unless specifically noted otherwise on the drawings. The maximum develop length of flex duct is 4'-0".

D. Avoid sharp bends. Use a minimum inside bend radius equal to one (1) times the inside diameter of the duct.

E. Support horizontal duct runs as detailed in the construction documents.

F. Allow the flexible duct to extend straight away from connectors for a few inches prior to inflating all bends.

G. Adhesive and sealants to connection of flexible duct to the rigid duct or terminate as follows:

1. Apply Foster's 30-02 sealant to the inside of the flexible duct to a depth of three (3) inches.
2. Repair all damage to vapor barrier with Foster's 35-50 reinforced with 4-inch-wide glass fabric and a second coat of Foster's 35-50.

END OF SECTION

23317 - DIFFUSERS, REGISTERS, AND GRILLES

PART 1 - GENERAL

1.1 DESCRIPTION

A. Air distribution devices shall be provided to deliver the indicated volume of supply air without exceeding the available flow with NC rating as follows:</