

SHEET NUMBER	SHEET NAME
M001	MECHANICAL ABBREVIATIONS AND SYMBOLS
M101	MECHANICAL FLOOR PLAN
M102	MECHANICAL REFRIGERANT PIPING LAYOUT PLAN
M501	MECHANICAL DETAILS
M502	MECHANICAL DETAILS
M590	MECHANICAL SPECIFICATIONS
M591	MECHANICAL SPECIFICATIONS
M592	MECHANICAL SPECIFICATIONS
M601	MECHANICAL SCHEDULE
M701	HALTON DRAWINGS
M702	HALTON DRAWINGS
M703	HALTON DRAWINGS
M704	HALTON DRAWINGS
M705	HALTON DRAWINGS
M706	HALTON DRAWINGS

△

△

RESPONSIBILITY MATRIX

THIS SCHEDULE IS PROVIDED FOR QUICK REFERENCE ONLY.
 THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ALL WORK DESCRIBED IN THE CONSTRUCTION DOCUMENTS.
 CONFLICTS BETWEEN THIS SCHEDULE AND THE REST OF THE CONTRACT DOCUMENTS SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION PRIOR TO BEGINNING WORK.

DESCRIPTION	FURNISHED			INSTALLED			REMARKS
	GENERAL CONTRACTOR	OWNER	LANDLORD	GENERAL CONTRACTOR	OWNER	LANDLORD	
DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING							
23.1 HVAC DUCTWORK AND PIPING IDENTIFICATION							
23.1.1 HVAC DUCTWORK SYSTEM IDENTIFICATION	X			X			
23.1.2 PIPING SYSTEM IDENTIFICATION	X			X			
23.1.3 UTILITY SHUT OFF IDENTIFICATION IN KITCHEN	X			X			
23.1.4 VALVE TAGS AND CHART	X			X			
23.1.5 HVAC DAMPER IDENTIFICATION	X			X			
23.2 ROOF CURBS							
23.2.1 EXHAUST FAN CURBS	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.2 ROOFTOP UNIT CURBS	△		X	X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.3 CONDENSING UNIT CURBS	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.4 MAKE UP AIR UNIT CURBS	△	△	X	△	X		GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.5 KITCHEN EXHAUST FAN CURBS			X	X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.3 HVAC DUCTWORK SYSTEM COMPONENTS							
23.3.1 HVAC DUCTWORK	X			X			
23.3.2 INSULATION AND FIRE WRAP	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE TENANT FIT OUT FROM LANDLORD POINT OF CONNECTION
23.3.3 DAMPERS	X			X			
23.3.4 SMOKE DETECTORS	X			X			
23.3.5 SUPPLY, RETURN, AND EXHAUST GRILLS AND REGISTERS	X			X			
23.4 MECHANICAL PIPING SYSTEM COMPONENTS							
23.4.1 WALK-IN COOLER AND FREEZER REFRIGERATION			X		X		WALK-IN COOLER AND FREEZER SUPPLIED BY VENDOR NO. 27 GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE PIPING INSTALLATION AND FINAL CONNECTION
23.4.2 REFRIGERATION FOR OTHER HVAC EQUIPMENT	X			X			
23.4.3 CHILLED WATER	X			X			
23.4.4 CONDENSER WATER	X			X			
23.4.5 HEATING HOT WATER	X			X			
23.4.6 VALVES AND ACCESSORIES (E.G. AIR VENTS)	X			X			
23.5 HVAC EQUIPMENT							
23.5.1 SUPPLY FAN	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING FOR ALL ROOFTOP EQUIPMENT
23.5.2 TOILET EXHAUST FAN	X			X			
23.5.3 KITCHEN EXHAUST FAN	△		X	X			SUPPLIED BY VENDOR NO. 26
23.5.4 DUCTED AND NON-DUCTED HEATING AND COOLING UNITS			X	X			
23.5.5 MAKE UP AIR AND DOAS UNITS			X	X			SUPPLIED BY VENDOR NO. 26
23.5.6 ELECTRIC PATIO HEATERS	△		X	X			
23.5.7 HVAC CONDENSING UNITS	△	X		X			
23.5.8 REFRIGERATION CONDENSING UNITS		X		X			
23.5.9 RGF PHI SYSTEM		X		X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 12 VENDOR SUBSTITUTION IS NOT PERMITTED
23.6 KITCHEN EXHAUST WITH FIRE SUPPRESSION SYSTEM							
23.6.1 HOOD CONTROL PANEL			X	X			SUPPLIED BY VENDOR NO. 26
23.6.2 KITCHEN EXHAUST HOOD			X	X			SUPPLIED BY VENDOR NO. 26
23.6.3 STRUCTURAL SUPPORT			X	X			
23.6.4 ELECTRICAL AND CONTROL WIRING			X	X			
23.6.5 ANSUL SYSTEM			X	X			SUPPLIED BY VENDOR NO. 26 GENERAL CONTRACTOR TO COORDINATE AND FACILITATE SYSTEM SIGN-OFF
23.6.6 ANSUL WIRING AND UTILITIES CONNECTION			X	X			
23.6.7 ANSUL GAS VALVE			X	X			SUPPLIED BY VENDOR NO. 26
23.7 COMMISSIONING ACTIVITIES							
23.7.1 GREASE EXHAUST WATER LEAKAGE TEST	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 10 VENDOR SUBSTITUTION IS NOT PERMITTED
23.7.2 TESTING AIR BALANCE (TAB) REPORT	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 12 VENDOR SUBSTITUTION IS NOT PERMITTED

SUBMITTAL MATRIX

GENERAL CONTRACTORS TO ALSO REVIEW ARCHITECTURAL SPECIFICATIONS AS NOTED IN PLANS IN PLAN SECTION 700 OF THE ARCHITECTURAL PACKAGE FOR REQUIRED SUBMITTALS THAT MIGHT NOT BE LISTED BELOW.

SUBMITTAL DESCRIPTION	Required Review (Business Days)	Architect of Record	Shack	Physical Sample Required	Submitted for Record
Anchor Bolts Shops	5	X			X
ATAS-Detailed Shop DWGS(Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X			X
Concrete Mix Design	5	X			X
Construction Prefunctional Checklists	5	X			X
Decorative Metal Shop Drawings	5	X			X
Diffusers, Grills & Registers	5	X			X
Doors, Frames & Hardware	7	X			X
Ductwork Layout (if there are significant changes in field)	5	X			X
Electrical Distribution Equipment	5	X			X
Elevator & Vertical Transportation Shop Drawings	5	X			X
Epoxy Floor	5	X			X
Fire Alarm Shop Drawings & Device Cut Sheets	5	X			X
Fire Sprinkler Shop Drawings, Hydraulic Calculations & Device Cut Sheets	5	X			X
HVAC Equipment(if Carrier - Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X			X
Light Fixtures(Submitted by Owner Vendor to Owner/AOR prior to construction)	5	X			X
MEP Tests, Start-Up, and Programming Reports	5	X			X
Millwork - Material Submittals (if differs from spec)	5	X	X	X	
Millwork - Shop Drawings (custom items & design features only)	5	X			
Restroom Partitions	5	X			X
Plumbing Fixtures	5	X			X
Rolling Shop Drawings	5	X			X
Rebar	5	X			X
Stair Shop Drawings	5	X			X
Structural Steel Shop Drawings	7	X			X
Storefront - product data Submittal (if different from specified)	5	X			
Storefront - Shop Drawings	5	X			
Tile (if differs from spec)	5	X			X
Window Film	5	X			

SYMBOLS

HEATING - VENTILATING - AIR CONDITIONING

SYMBOL	DESCRIPTION
	THERMOSTAT
	REMOTE SENSOR
	SUPPLY DIFFUSER
	RETURN OR EXHAUST GRILLE
	SUPPLY OR FRESH AIR DUCT (SA OR FA)
	RETURN OR EXHAUST AIR DUCT (RA OR EA)
	RECTANGULAR DUCT (FIRST FIGURE IS SIDE SHOWN)
	ROUND DUCT
	VOLUME DAMPER (ELEV AND PLAN)
	TURNING VANES
	SUPPLY REGISTER OR GRILLE (R OR G)
	RETURN REGISTER OR GRILLE (R OR G)
	FRESH AIR INTAKE (FA)
	SQUARE CEILING DIFFUSER (SUPPLY)
	FAN COIL UNIT AND MARK
	MOTORIZED DAMPER
	REFRIGERANT LIQUID LINE
	REFRIGERANT SUCTION LINE



ZEBRA PROJECTS, INC.
 1464 N KIERNAND BLVD, SUITE N500
 SCOTTSDALE, ARIZONA 85254
 PHONE: 480.912.1169 zbr.global



STORE NO: 1397




REVISION

DATE	DESCRIPTION
08/28/22	REVISION A
11/29/22	REVISION E
01/16/23	REVISION 1

STATUS: IFC SET

PRELIMINARY:
 Preliminary Documents Are for Design Review only and not intended for bidding, programming, permitting or construction purposes. They were prepared by or under the supervision of Zebra Projects, Inc.



FIELD VERIFICATION:
 The contractor shall verify all figured dimensions and location at the project site and notify Zebra Projects, Inc. of any dimensional errors, or omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.

COPYRIGHT © 2023:
 Zebra Projects, Inc. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, photocopied or otherwise without the written consent of Zebra Projects, Inc.

SHEET NAME:
MECHANICAL ABBREVIATIONS & SYMBOLS

DATE: 01/16/23 PROJECT NO: 34286

DRAWN: RAS SCALE:

SHEET NO:
M001


- 4. DEMAND CONTROL VENTILATION DEVICES.**
- FOR EACH SYSTEM WITH DEMAND CONTROL VENTILATION (DCV), CO2 SENSORS SHALL BE INSTALLED IN EACH ROOM THAT MEETS THE CRITERIA OF SECTION 120.1(D)(3) WITH NO LESS THAN ONE SENSOR PER 10,000 FT OF FLOOR SPACE. WHEN A ZONE OR A SPACE IS SERVED BY MORE THAN ONE SENSOR, A SIGNAL FROM ANY SENSOR INDICATING THAT CO2 IS NEAR OR AT THE SETPOINT WITHIN THE ZONE OR SPACE SHALL TRIGGER AN INCREASE IN VENTILATION.
 - CO2 SENSORS SHALL BE LOCATED IN THE ROOM BETWEEN 3 FT AND 6 FT ABOVE THE FLOOR OR AT THE ANTICIPATED HEIGHT OF THE OCCUPANTS' HEADS.
 - DEMAND VENTILATION CONTROLS SHALL MAINTAIN CO2 CONCENTRATIONS LESS THAN OR EQUAL TO 600 PPM PLUS THE OUTDOOR AIR CO2 CONCENTRATION IN ALL ROOMS WITH CO2 SENSORS. EXCEPT TO SECTION 120.1(D)(4).
 - THE OUTDOOR AIR VENTILATION RATE IS NOT REQUIRED TO BE LARGER THAN THE DESIGN OUTDOOR AIR VENTILATION RATE REQUIRED BY SECTION 120.1(C)(3) REGARDLESS OF CO2 CONCENTRATION.
 - OUTDOOR AIR CO2 CONCENTRATION SHALL BE DETERMINED BY ONE OF THE FOLLOWING:
 - CO2 CONCENTRATION SHALL BE ASSUMED TO BE 400 PPM WITHOUT ANY DIRECT MEASUREMENT; OR
 - CO2 CONCENTRATION SHALL BE DYNAMICALLY MEASURED USING A CO2 SENSOR LOCATED WITHIN 4 FT OF THE OUTDOOR AIR INTAKE.
 - WHEN THE SYSTEM IS OPERATING DURING HOURS OF EXPECTED OCCUPANCY, THE CONTROLS SHALL MAINTAIN SYSTEM OUTDOOR AIR VENTILATION RATES NO LESS THAN THE RATE LISTED IN TABLE 120.1-A FOR DCV. TIMES THE CONDITIONED FLOOR AREA FOR SPACES WITH CO2 SENSORS, PLUS THE RATE REQUIRED BY SECTION 120.1(C)(3) FOR OTHER SPACES SERVED BY THE SYSTEM, OR THE EXHAUST AIR RATE WHICHEVER IS GREATER.
 - CO2 SENSORS SHALL BE CERTIFIED BY THE MANUFACTURER TO BE ACCURATE WITHIN PLUS OR MINUS 75 PPM AT A 600 AND 1000 PPM CONCENTRATION WHEN MEASURED AT SEA LEVEL AND 25 °C. FACTORY CALIBRATION, AND CERTIFIED BY THE MANUFACTURER TO REQUIRE CALIBRATION NO MORE FREQUENTLY THAN ONCE EVERY 5 YEARS. UPON DETECTION OF SENSOR FAILURE, THE SYSTEM SHALL PROVIDE A SIGNAL WHICH RESETS TO SUPPLY THE MINIMUM QUANTITY OF OUTSIDE AIR TO LEVELS REQUIRED BY SECTION 120.1(C)(3) TO THE ZONE SERVED BY THE SENSOR AT ALL TIMES THAT THE ZONE IS OCCUPIED.
 - THE CO2 SENSOR(S) REQUIRED FOR EACH ZONE SHALL BE DISPLAYED CONTINUOUSLY, AND SHALL BE RECORDED ON SYSTEMS WITH DOC TO THE ZONE LEVEL.

- [2019 TITLE 24, PART 6, SECTION 120.1(D)(4)]

- GENERAL 2019 CALIFORNIA GREEN BUILDING STANDARDS CODE NOTES:**
- TESTING AND ADJUSTING OF SYSTEMS SHALL BE REQUIRED PER SECTION 5.410.4 FOR BUILDINGS WITH FLOOR AREA LESS THAN 10,000 SQUARE FEET OR NEW SYSTEMS TO SERVE AN ADDITION OR ALTERATION SUBJECT TO SECTION 303.1.
 - DEVELOP A WRITTEN PLAN OF PROCEDURES FOR TESTING AND ADJUSTING SYSTEMS TO BE INCLUDED FOR TESTING AND ADJUSTING SHALL INCLUDE, AS APPLICABLE TO THE PROJECT, THE SYSTEMS LISTED IN SECTION 5.410.4.2.
 - PERFORM TESTING AND ADJUSTING PROCEDURES IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND APPLICABLE STANDARDS ON EACH SYSTEM BEFORE A NEW SPACE-CONDITIONING SYSTEM SERVING A BUILDING OR SPACE IS OPERATED FOR NORMAL USE. THE SYSTEM SHOULD BE BALANCED IN ACCORDANCE WITH THE PROCEDURES DEFINED BY NATIONAL STANDARDS LISTED IN SECTION 5.410.4.3.1.
 - AFTER COMPLETION OF TESTING, ADJUSTING, AND BALANCING, PROVIDE A FINAL REPORT OF TESTING SIGNED BY THE INDIVIDUAL RESPONSIBLE FOR PERFORMING THESE SERVICES.
 - PROVIDE THE BUILDING OWNER OR REPRESENTATIVE WITH DETAILED OPERATING AND MAINTENANCE INSTRUCTIONS AND COPIES OF WARRANTIES/WARRANTIES FOR EACH SYSTEM PRIOR TO FINAL INSPECTION. O&M INSTRUCTIONS SHALL BE CONSISTENT WITH OSHA REQUIREMENTS IN OCR, TITLE 8, SECTION 5142 AND OTHER RELATED REGULATIONS.
 - INCLUDE A COPY OF ALL INSPECTION VERIFICATIONS AND REPORTS REQUIRED BY THE ENFORCING AGENCY.
 - HVAC EQUIPMENT USED DURING CONSTRUCTION SHALL USE RETURN AIR FILTERS WITH A MERV 8, BASED UPON ASHRAE 55.2-1999, OR AN AVERAGE EFFICIENCY OF 30% BASED UPON ASHRAE 52.1-1992. ALL FILTERS SHALL BE REPLACED PRIOR TO OCCUPANCY.
 - AT THE TIME OF ROUGH INSTALLATION OR DURING STORAGE ON THE CONSTRUCTION SITE AND UNTIL FINAL STARTUP OF THE HEATING, COOLING, AND VENTILATING EQUIPMENT, ALL DUCT AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPERINGS SHALL BE COVERED WITH TAPE, PLASTIC, SHEETMETAL OR SIMILAR METHODS ACCEPTABLE TO THE ENFORCING AGENCY TO REDUCE THE AMOUNT OF DUST, WATER OR DEBRIS WHICH MAY ENTER THE SYSTEM.
 - IN MECHANICALLY VENTILATED BUILDINGS, PROVIDE REGULARLY OCCUPIED AREAS IN THE BUILDING WITH AIR FILTRATION MEDIA FOR EXHAUST AND RETURN AIR THAT PROVIDES AT LEAST A MERV 13 RATING. FILTERS SHALL BE INSTALLED PRIOR TO OCCUPANCY, AND RECOMMENDATIONS FOR MAINTENANCE WITH MERV 13 FILTERS SHALL BE INCLUDED IN THE OPERATION AND MAINTENANCE MANUAL.
 - INSTALLATIONS OF HVAC, REFRIGERATION AND FIRE SUPPRESSION EQUIPMENT SHALL COMPLY WITH SECTIONS 5.508.1.1 AND 5.508.1.2.
 - INSTALL HVAC AND REFRIGERATION AND FIRE SUPPRESSION EQUIPMENT THAT DO NOT CONTAIN CFCs.
 - INSTALL HVAC AND REFRIGERATION AND FIRE SUPPRESSION EQUIPMENT THAT DO NOT CONTAIN HALONS.
 - ADHESIVES, SEALANTS, AND CAULKS USED ON THE PROJECT SHALL MEET THE REQUIREMENTS OF SECTIONS 5.504.4.1 THROUGH 5.504.4.6.

- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATION AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE SPECIFICATIONS. PRESERVE EXISTING CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.e., BEAMS, JOISTS) ONLY. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ADJUSTABLE DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SHAWM AND WAUSA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ADJUSTABLE DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - EXPOSED SPIRAL DUCT TO BE GALVANIZED FINISH, FREE FROM SCRATCHES, DENTS OR BLEMISHES AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT SHALL BE INTERNALLY LINED AND SEALED WITH DUCT SEALER COMPLETELY CONCEALED WITHIN THE DUCT JOINT. NO EXPOSED SEALER OR TAPE WILL BE ACCEPTED.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE OR JOIST SPACE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITED ENERTECH FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILING. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ROOF MOUNTED EQUIPMENT SHALL BE LABELED WITH THE TENANT NAME AND SPACE NUMBER WITH 3" HIGH WEATHER PROOF LETTERS.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 98 AND ASTM E 2338 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND 7 YEAR WARRANTY ON ALL INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AAFC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. APPROVED. THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOUR AT WILL@NATIONTAB.COM OR 314-924-8244.
 - THE CONTRACTOR SHALL OBTAIN A COPY OF THE LANDLORD'S TENANT CRITERIA MANUAL. TENANT CRITERIA MANUAL IS AN INTEGRAL PART OF THIS CONTRACT. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING WITH LANDLORD REQUIREMENTS AND ANY ADDITIONAL COST TO THE CONTRACTOR SHALL REMAIN UNDISTURBED UNLESS NOTED OTHERWISE.
 - PROVIDE ALL NECESSARY WIRING, RELAY DEVICES, COMPONENTS, ETC., FOR FIRE ALARM OR CONTROL SYSTEM INTERLOCK IF APPLICABLE. VERIFY WITH BUILDING PERSONNEL BEFORE BID.

- HVAC NOTES:**
- NEW HALTON GREASE EXHAUST HOOD TO BE FURNISHED BY OWNER FOR INSTALLATION. SEE MECHANICAL SHEETS M701 THROUGH M706 FOR ADDITIONAL INFORMATION. BALANCE HOOD MAKE-UP AIR, SUPPLY AIR, AND EXHAUST COLLARS AS NOTED ON THE HOOD SCHEDULE. PROVIDE FULL SIZE TRANSITION MAKE-UP AIR DUCT FROM COLLAR TO AIR DUCT AND CONDITIONED AIR DUCT AS INDICATED ON PLANS. PROVIDE EACH DROP WITH VOLUME DAMPERS. VERIFY ALL MANUFACTURER AND CODE REQUIRED CLEARANCES ARE MAINTAINED. NOTIFY ARCHITECT IF ANY CONFLICTS OCCUR.
 - TRANSITION FROM HOOD EXHAUST COLLAR AS INDICATED ON PLANS AND EXTEND 12/12 KITCHEN HOOD GREASE EXHAUST DUCTWORK UP TO GREASE EXHAUST FAN ON ROOF. SEE SHEET M150 FOR CONTINUATION. GREASE DUCT SHALL BE WRAPPED WITH TWO (2) LAYERS OF THERMAL CERAMICS FAST WRAP XL, 1 1/2" THICK WITH 3" PERIMETER AND LONGITUDINAL OVERLAPS OR EQUIVALENT U.L. LISTED GREASE DUCT WRAP FOR ZERO CLEARANCE TO COMBUSTIBLES. REFER TO DETAIL ON SHEET M501 FOR ADDITIONAL INFORMATION.
 - TRANSITION FROM HOOD EXHAUST COLLAR AS INDICATED ON PLANS AND EXTEND 8/8 KITCHEN HOOD GREASE EXHAUST DUCTWORK UP TO GREASE EXHAUST FAN ON ROOF. SEE SHEET M150 FOR CONTINUATION. GREASE DUCT SHALL BE WRAPPED WITH TWO (2) LAYERS OF THERMAL CERAMICS FAST WRAP XL, 1 1/2" THICK WITH 3" PERIMETER AND LONGITUDINAL OVERLAPS OR EQUIVALENT U.L. LISTED GREASE DUCT WRAP FOR ZERO CLEARANCE TO COMBUSTIBLES. REFER TO DETAIL ON SHEET M501 FOR ADDITIONAL INFORMATION.
 - PROVIDE CLEANOUTS ON GREASE DUCTWORK AS REQUIRED BY CODE. REFERENCE SHEET M501 DETAIL 5 FOR ADDITIONAL INFORMATION. TYPICAL OF GREASE EXHAUST DUCTWORK.
 - DUCTWORK TO BE TO BE INSTALLED AS HIGH AS CONDITIONS ALLOW. COORDINATE ROUTING AND MOUNTING HEIGHT WITH LIGHTING FIXTURES. NOTIFY THE ARCHITECTS OF ANY CONFLICTS AND COORDINATE WITH THE CONSTRUCTION MANAGER.
 - PROVIDE REMOTE VOLUME DAMPER AS INDICATED ON PLANS. REFERENCE SHEET M502 DETAIL 5 FOR ADDITIONAL INFORMATION. TYPICAL OF GREASE EXHAUST DUCTWORK.
 - PROVIDE NEW FC UNIT AS NOTED ON PLANS AND AS SCHEDULED ON SHEET M601.
 - PROVIDE REFRIGERANT LINES FROM ASUP-1 ON ROOF TO FC-1 IN ROOM 104. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - PROVIDE NEW VENSTAR T2900 COMMERCIAL THERMOSTAT. MOUNT THERMOSTAT AT 48" ABOVE FINISHED FLOOR. PROVIDE REMOTE TEMPERATURE SENSORS AS INDICATED ON PLAN. COORDINATE LOCATION WITH WALL GRAPHICS LAYOUT. PROVIDE 10/10 EXHAUST AIR DUCT UP TO EF-3 ON ROOF.
 - CONTRACTOR SHALL UNDERCUT DOOR 3.
 - REUSE AND TRANSITION DUCTWORK AS REQUIRED TO INSTALL BELOW EXISTING SPRINKLER PIPING. NOTIFY ENGINEER WITH ANY CONFLICTS.
 - PROVIDE WITH INSULATED BACK-PAN.
 - MOUNT TRANSFER GRILLE AS HIGH AS CONDITIONS ALLOW.
 - PROVIDE CO2 SENSOR FOR DEMAND CONTROL VENTILATION AS SPECIFIED IN THE CALIFORNIA ENERGY CODE, TITLE 24, PART 6, SECTION 120.1(D)(4). REFERENCE BOX NOTE ON THIS SHEET FOR ADDITIONAL INFORMATION.
 - HOOD MANUFACTURER TO PROVIDE A "KIT" TO FASTEN THE BOTTOM FLANGE OF THE HOOD TO THE WALL, WITH ONE FASTENER PER STUD WALL. SIL-BOND RTV 4500 ALUMINUM SILICONE SEALANT OR APPROVED SIMILAR, TO BE APPLIED BY GENERAL CONTRACTOR HOOD INSTALLER FOR ANY REMAINING SMALL GAPS. HOOD FASTENING "KIT" DETAIL TO BE INCLUDED IN MANUFACTURER DRAWINGS. REFERENCE SHEET M601 DETAIL 3 FOR ADDITIONAL INFORMATION.
 - MOUNT RETURN GRILLE ON WALL AS HIGH AS CONDITIONS ALLOW. COORDINATE EXACT LOCATION WITH ARCHITECT AND CONSTRUCTION SUPERVISOR.
 - ROUTE DUCTWORK TO AVOID CONFLICTS WITH EXISTING CONDITIONS OR FUTURE ELECTRICAL SYSTEMS. COORDINATE WITH ELECTRICAL AND GENERAL CONTRACTOR BEFORE INSTALLATION.



1 MECHANICAL FLOOR PLAN
SCALE: 1/4" = 1'-0"

*KITCHEN EXHAUST FANS ARE TO BE INTERLOCKED WITH THE MAKE-UP AIR UNIT.
-ALL JOINTS AND SEAMS OF EXHAUST HOODS SHALL BE CONSTRUCTED TO BE TIGHT AND EASILY CLEANABLE AND FLASHED TO THE WALLS AND CEILING.
-CANOPY-TYPE EXHAUST HOODS SHALL EXTEND A MINIMUM OF SIX (6) INCHES BEYOND THE OUTER EDGES OF THE COOKING SURFACES AS MEASURED FROM THE INSIDE EDGE OF THE HOOD. THE VERTICAL DISTANCE BETWEEN THE LOWER LIP OF THE HOOD AND THE COOKING SURFACE SHALL NOT EXCEED 4 (FOUR) FEET. (114149.1)

zebra
ZEBRA PROJECTS, I.N.C.
1464 N KIERLAND BLVD, SUITE N504
SCOTTSDALE, ARIZONA 85254
PHONE: 480.912.1169 zbr-global

CONSULTANT LOGO

Schnackel
engineers
800-581-0963
www.schnackel.com
18 JUN 2014

STORE NO: 1397

SHAKE SHACK
IRVINE SPECTRUM CENTER
IRVINE, CALIFORNIA 92618

REVISION	
DATE	DESCRIPTION
08/26/22	REVISION A
08/30/22	REVISION B
11/29/22	REVISION E
02/17/23	REVISION 2

STATUS: IFC SET

PRELIMINARY:
Preliminary Documents Are for Design Review only and not intended for bidding, permitting, construction or construction. They are prepared by or under the supervision of Zebra Projects, Inc.

REGISTERED PROFESSIONAL ENGINEER
No. M33299
MECHANICAL
STATE OF CALIFORNIA
Date: 02/17/23

FIELD VERIFICATION:
The contractor shall verify all figured dimensions and conditions on the project site and notify Zebra Projects, Inc. of any dimensional errors, omissions or discrepancies unless beginning of fabrication any work. Do not commence these activities.

COPYRIGHT © 2023:
Zebra Projects, Inc. shall retain all common law, statutory or other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, modified or otherwise used without the written consent of Zebra Projects, Inc.

SHEET NAME: **MECHANICAL FLOOR PLAN**

DATE: 01/16/23 PROJECT NO: 34286

DRAWN: RAS SCALE:

SHEET NO: **M101**




STORE NO: 1397

SHAKE SHACK
 IRVINE SPECTRUM CENTER
 IRVINE, CALIFORNIA 92618

REVISION	
DATE	DESCRIPTION

STATUS: IFC SET

PRELIMINARY:
 Preliminary Documents are for Design Review only and not intended for bidding, permitting, or construction purposes. They were prepared by or under the supervision of Zebra Projects, Inc.



FIELD VERIFICATION:
 The contractor shall verify all figured dimensions and location at the project site and notify Zebra Projects, Inc. of any dimensional errors, or omissions or discrepancies before beginning or fabricating any work. Do not make these

COPYRIGHT © 2023:
 Zebra Projects, Inc. shall retain all common law, statutory and other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, photocopied or otherwise used without the written consent of Zebra Projects, Inc.

SHEET NAME:
MECHANICAL REFRIGERATION PIPING AND LAYOUT PLAN


DATE: 01/16/23 PROJECT NO: 34286

DRAWN: RAS SCALE:

SHEET NO: **M102**

- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS NECESSARY TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.e., BEAMS, JOISTS) ONLY. DUST HANDERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOG AND WASH. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - EXPOSED SPIRAL DUCT TO BE GALVANIZED FINISH, FREE FROM SCRATCHES, DENTS OR BLEMISHES AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT SHALL BE INTERNALLY LINED AND SEALED WITH DUCT SEALER COMPLETELY CONCEALED WITHIN THE DUCT JOINT. NO EXPOSED SEALER OR TAPE WILL BE ACCEPTED.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE OR THIRD JOIST SPACE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITED ENERTECH FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILING. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ROOF MOUNTED EQUIPMENT SHALL BE LABELED WITH THE TENANT NAME AND SPACE NUMBER WITH 3" HIGH WEATHER PROOF LETTERS.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 98 AND ASTM E 2336 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOUR AT WILL@NATIONTAB.COM OR 314-954-8244.
 - THE CONTRACTOR SHALL OBTAIN A COPY OF THE LANDLORD'S TENANT CRITERIA MANUAL. TENANT CRITERIA MANUAL IS AN INTEGRAL PART OF THIS CONTRACT. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING WITH LANDLORD REQUIREMENTS AT NO ADDITIONAL COST TO THE TENANT.
 - PARTS OF THE BASE BUILDING SYSTEMS THAT FALL INTO LEASE LINE SHALL REMAIN UNDISTURBED UNLESS NOTED OTHERWISE.
 - FOR FIRE ALARM OR CONTROL SYSTEM INTERLOCK IF APPLICABLE. VERIFY WITH BUILDING PERSONNEL BEFORE BID.

- HVAC NOTES:**
- PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE (104) AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.
 - PROVIDE REFRIGERANT LINES FROM CONDENSING UNIT ON ROOF TO KITCHEN EQUIPMENT AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.




MECHANICAL REFRIGERANT PIPING LAYOUT PLAN
 SCALE: 1/4" = 1'-0"

CITY COMMENT:
 PER SECTION 3-20-1B OF THE ZONING ORDINANCE, SCREENING SHALL BE PROVIDED SO THAT MATERIALS STORED IN ANY OUTDOOR STORAGE AREA AND/OR EQUIPMENT AT GRADE OR ON THE ROOF AREA, SCREENED FROM ADJACENT STREETS, NO MATTER THE STREET GRADE, AND ALL PROPERTIES AT THE SAME GRADE.

- GENERAL 2019 CALIFORNIA GREEN BUILDING STANDARDS CODE NOTES:**
- TESTING AND ADJUSTING OF SYSTEMS SHALL BE REQUIRED PER SECTION 5.410.4 FOR BUILDINGS WITH FLOOR AREA LESS THAN 10,000 SQUARE FEET OR NEW SYSTEMS TO SERVE AN ADDITION OR ALTERATION SUBJECT TO SECTION 303.1.
 - DEVELOP A WRITTEN PLAN OF PROCEDURES FOR TESTING AND ADJUSTING SYSTEMS. SYSTEMS TO BE INCLUDED FOR TESTING AND ADJUSTING SHALL INCLUDE, AS APPLICABLE TO THE PROJECT, THE SYSTEMS LISTED IN SECTION 5.410.4.2.
 - PERFORM TESTING AND ADJUSTING PROCEDURES IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND APPLICABLE STANDARDS ON EACH SYSTEM BEFORE A NEW SPACE-CONDITIONING SYSTEM SERVING A BUILDING OR SPACE IS OPERATED FOR NORMAL USE. THE SYSTEM SHOULD BE BALANCED IN ACCORDANCE WITH THE PROCEDURES DEFINED BY NATIONAL STANDARDS LISTED IN SECTION 5.410.4.3.1.
 - AFTER COMPLETION OF TESTING, ADJUSTING, AND BALANCING, PROVIDE A FINAL REPORT OF TESTING SIGNED BY THE INDIVIDUAL RESPONSIBLE FOR PERFORMING THESE SERVICES.
 - PROVIDE THE BUILDING OWNER OR REPRESENTATIVE WITH DETAILED OPERATING AND MAINTENANCE INSTRUCTIONS AND COPIES OF WARRANTIES/WARRANTIES FOR EACH SYSTEM PRIOR TO FINAL INSPECTION. O&M INSTRUCTIONS SHALL BE CONSISTENT WITH OSHA REQUIREMENTS IN OCR, TITLE 8, SECTION 5142 AND OTHER RELATED REGULATIONS.
 - INCLUDE A COPY OF ALL INSPECTION VERIFICATIONS AND REPORTS REQUIRED BY THE ENFORCING AGENCY.
 - HVAC EQUIPMENT USED DURING CONSTRUCTION SHALL USE RETURN AIR FILTERS WITH A MERV 8, BASED UPON ASHRAE 55.2-1999, OR AN AVERAGE EFFICIENCY OF 30% BASED UPON ASHRAE 52.1-1992. ALL FILTERS SHALL BE REPLACED PRIOR TO OCCUPANCY.
 - AT THE TIME OF ROUGH INSTALLATION OR DURING STORAGE ON THE CONSTRUCTION SITE AND UNTIL FINAL STARTUP OF THE HEATING, COOLING, AND VENTILATING EQUIPMENT, ALL DUCT AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED WITH TAPE, PLASTIC, SHEETMETAL OR OTHER METHODS ACCEPTABLE TO THE ENFORCING AGENCY TO REDUCE THE AMOUNT OF DUST, WATER OR DEBRIS WHICH MAY ENTER THE SYSTEM.
 - IN MECHANICALLY VENTILATED BUILDINGS, PROVIDE REGULARLY OCCUPIED AREAS OF THE BUILDING WITH AIR FILTRATION MEDIA FOR OUTSIDE AND RETURN AIR THAT PROVIDES AT LEAST A MERV 13 RATING. FILTERS SHALL BE INSTALLED PRIOR TO OCCUPANCY, AND RECOMMENDATIONS FOR MAINTENANCE, WITH MERV 13 FILTERS SHALL BE INCLUDED IN THE OPERATION AND MAINTENANCE MANUAL.
 - INSTALLATIONS OF HVAC, REFRIGERATION AND FIRE SUPPRESSION EQUIPMENT SHALL COMPLY WITH SECTIONS 5.508.1.1 AND 5.508.1.2.
 - INSTALL HVAC AND REFRIGERATION AND FIRE SUPPRESSION EQUIPMENT THAT DO NOT CONTAIN HCFCs.
 - INSTALL HVAC AND REFRIGERATION AND FIRE SUPPRESSION EQUIPMENT THAT DO NOT CONTAIN HALONS.
 - ADHESIVES, SEALANTS, AND CAULKS USED ON THE PROJECT SHALL MEET THE REQUIREMENTS OF SECTIONS 5.504.4.1 THROUGH 5.504.4.6.

- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS SHOWN AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOKE AND HEAT RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - EXPOSED SPIRAL DUCT TO BE GALVANIZED FINISH, FREE FROM SCRATCHES, DENTS OR BLEMISHES AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT SHALL BE INTERNALLY LINED AND SEALED WITH DUCT SEALER COMPLETELY CONCEALED WITHIN THE DUCT JOINT. NO EXPOSED SEALER OR TAPE WILL BE ACCEPTED.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE OR JOIST SPACE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITED ENERTECH FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILING. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ROOF MOUNTED EQUIPMENT SHALL BE LABELED WITH THE TENANT NAME AND SPACE NUMBER WITH 3" HIGH WEATHER PROOF LETTERS.
 - ALL GREASE EXHAUST SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 98 AND ASTM E 2338 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND 70% OF THE INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING THE WORK, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOUR AT WILL@NATIONTAB.COM OR 314-924-8244.
 - THE CONTRACTOR SHALL OBTAIN A COPY OF THE LANDLORD'S TENANT CRITERIA MANUAL. TENANT CRITERIA MANUAL IS AN INTEGRAL PART OF THIS CONTRACT. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING WITH LANDLORD REQUIREMENTS OUT TO THE DATE OF BIDDING. IF NOT CONTRACTOR SHALL COORDINATE WITH LANDLORD AND PROVIDE.
 - NEW HALTON GREASE EXHAUST FAN TO BE FURNISHED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE HALTON SHEET M-701 THROUGH M706 FOR ADDITIONAL INFORMATION. FIELD VERIFY AND CONFIRM WITH LANDLORD INSTALLATION LOCATION. LANDLORD TO PROVIDE STRUCTURAL SUPPORT FOR UNIT. UNIT SHALL REQUIRE VIBRATION ISOLATION PER LANDLORD REQUIREMENTS. VERIFY IF EQUIPPED. IF NOT CONTRACTOR SHALL COORDINATE WITH LANDLORD AND PROVIDE.
 - PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN ROOM 106. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - PROVIDE REFRIGERANT LINES FROM KITCHEN EQUIPMENT CONDENSING UNITS ON ROOF TO UNITS IN THE KITCHEN SPACE AS INDICATED ON THE KITCHEN DRAWINGS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - RFC AIR PURIFICATION SYSTEM TO BE PROVIDED AND INSTALLED BY NTAB. REFER TO RESPONSIBILITY MATRIX ON SHEET M001 FOR ADDITIONAL INFORMATION, SHEET M601 FOR SCHEDULE, AND SHEET M592 FOR SPECIFICATIONS.
 - PROVIDE ASHP AS NOTED ON PLANS AND SCHEDULED ON SHEET M601. UNIT SHALL REQUIRE VIBRATION ISOLATION PER LANDLORD REQUIREMENTS. CONTRACTOR SHALL COORDINATE WITH LANDLORD AND PROVIDE.
 - NEW HALTON MAKE-UP AIR UNIT TO BE FURNISHED BY OWNER FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. SEE HALTON SHEET M-701 THROUGH M706 FOR ADDITIONAL INFORMATION. FIELD VERIFY AND CONFIRM WITH LANDLORD INSTALLATION LOCATION. LANDLORD TO PROVIDE STRUCTURAL SUPPORT FOR UNIT. VERIFY UNIT SHALL REQUIRE VIBRATION ISOLATION PER LANDLORD REQUIREMENTS. VERIFY IF EQUIPPED. IF NOT CONTRACTOR SHALL COORDINATE WITH LANDLORD AND PROVIDE.
 - PROVIDE ROOF CAP TERMINATION WITH BUG SCREEN FOR OUTDOOR AIR INTAKE FOR FC-1. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION IS A MINIMUM OF 10' FROM ANY EXHAUST/FLUE TERMINATION.
 - DUCT SMOKE DETECTOR ON SUPPLY SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
 - ENVIRONMENTAL EXHAUST SHALL TERMINATE NOT LESS THAN 3 FEET FROM A PROPERTY LINE, OPENINGS INTO THE BUILDINGS, AND 10 FEET FROM A FORCED AIR INLET.
 - WHEN EXISTING ROOF IS A RED COLOR, ALL ROOF EQUIPMENT, VENTS, DISHES, AND ASSOCIATED CONDUIT LINES INSTALLED DURING THE TENANT IMPROVEMENT CONSTRUCTION ON THE ROOF MUST BE PAINTED. THE PAINT IS A CUSTOM COLOR TO BE PURCHASED THROUGH VISTA PAINT #8 MISSION VIEJO (949.568.9330). SPECIFICATION: VP2-98280. COPPER BROWN. PLEASE CONTACT TENANT COORDINATION WITH QUESTIONS.
 - EXISTING CARRIER, 50T00D12, 12.5 TON ROOFTOP UNIT TO REMAIN. CONTRACTOR SHALL BALANCE EXISTING UNIT TO PROVIDE 5,000 CFM OF SUPPLY AIR AND THE OUTDOOR AIR INDICATED ON THE PLANS. FIELD VERIFY EXACT LOCATION.

- HVAC NOTES:**
- EXISTING CARRIER, 50T00D12, 12.5 TON ROOFTOP UNIT TO REMAIN. CONTRACTOR SHALL BALANCE EXISTING UNIT TO PROVIDE 5,000 CFM OF SUPPLY AIR AND THE OUTDOOR AIR INDICATED ON THE PLANS. FIELD VERIFY EXACT LOCATION.
 - PROVIDE NEW EXHAUST FAN AS NOTED ON PLANS AND SCHEDULED ON SHEET M601. THE CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE. FIELD VERIFY EXACT LOCATION. THE LANDLORD THE INSTALLATION LOCATION. LANDLORD TO PROVIDE STRUCTURAL SUPPORT FOR UNIT. VERIFY UNIT SHALL REQUIRE VIBRATION ISOLATION PER LANDLORD REQUIREMENTS. VERIFY IF EQUIPPED. IF NOT CONTRACTOR SHALL COORDINATE WITH LANDLORD AND PROVIDE.
 - NEW HALTON GREASE EXHAUST FAN TO BE FURNISHED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE HALTON SHEET M-701 THROUGH M706 FOR ADDITIONAL INFORMATION. FIELD VERIFY AND CONFIRM WITH LANDLORD INSTALLATION LOCATION. LANDLORD TO PROVIDE STRUCTURAL SUPPORT FOR UNIT. UNIT SHALL REQUIRE VIBRATION ISOLATION PER LANDLORD REQUIREMENTS. FIELD VERIFY IF EQUIPPED. IF NOT CONTRACTOR SHALL COORDINATE WITH LANDLORD AND PROVIDE.
 - PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN ROOM 106. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - PROVIDE REFRIGERANT LINES FROM KITCHEN EQUIPMENT CONDENSING UNITS ON ROOF TO UNITS IN THE KITCHEN SPACE AS INDICATED ON THE KITCHEN DRAWINGS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - RFC AIR PURIFICATION SYSTEM TO BE PROVIDED AND INSTALLED BY NTAB. REFER TO RESPONSIBILITY MATRIX ON SHEET M001 FOR ADDITIONAL INFORMATION, SHEET M601 FOR SCHEDULE, AND SHEET M592 FOR SPECIFICATIONS.
 - PROVIDE ASHP AS NOTED ON PLANS AND SCHEDULED ON SHEET M601. UNIT SHALL REQUIRE VIBRATION ISOLATION PER LANDLORD REQUIREMENTS. CONTRACTOR SHALL COORDINATE WITH LANDLORD AND PROVIDE.
 - NEW HALTON MAKE-UP AIR UNIT TO BE FURNISHED BY OWNER FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. SEE HALTON SHEET M-701 THROUGH M706 FOR ADDITIONAL INFORMATION. FIELD VERIFY AND CONFIRM WITH LANDLORD INSTALLATION LOCATION. LANDLORD TO PROVIDE STRUCTURAL SUPPORT FOR UNIT. VERIFY UNIT SHALL REQUIRE VIBRATION ISOLATION PER LANDLORD REQUIREMENTS. VERIFY IF EQUIPPED. IF NOT CONTRACTOR SHALL COORDINATE WITH LANDLORD AND PROVIDE.
 - PROVIDE ROOF CAP TERMINATION WITH BUG SCREEN FOR OUTDOOR AIR INTAKE FOR FC-1. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION IS A MINIMUM OF 10' FROM ANY EXHAUST/FLUE TERMINATION.
 - DUCT SMOKE DETECTOR ON SUPPLY SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
 - ENVIRONMENTAL EXHAUST SHALL TERMINATE NOT LESS THAN 3 FEET FROM A PROPERTY LINE, OPENINGS INTO THE BUILDINGS, AND 10 FEET FROM A FORCED AIR INLET.
 - WHEN EXISTING ROOF IS A RED COLOR, ALL ROOF EQUIPMENT, VENTS, DISHES, AND ASSOCIATED CONDUIT LINES INSTALLED DURING THE TENANT IMPROVEMENT CONSTRUCTION ON THE ROOF MUST BE PAINTED. THE PAINT IS A CUSTOM COLOR TO BE PURCHASED THROUGH VISTA PAINT #8 MISSION VIEJO (949.568.9330). SPECIFICATION: VP2-98280. COPPER BROWN. PLEASE CONTACT TENANT COORDINATION WITH QUESTIONS.
 - EXISTING CARRIER, 50T00D14, 12.5 TON ROOFTOP UNIT TO REMAIN. CONTRACTOR SHALL BALANCE EXISTING UNIT TO PROVIDE 5,000 CFM OF SUPPLY AIR AND THE OUTDOOR AIR INDICATED ON THE PLANS. FIELD VERIFY EXACT LOCATION.



1 MECHANICAL ROOF PLAN
 SCALE: 1/4" = 1'-0"

zebra
 ZEBRA PROJECTS, INC.
 1464 N KIERLAND BLVD, SUITE 5504
 SCOTTSDALE, ARIZONA 85254
 PHONE: 480.912.1169 zbr-global

CONSULTANT LOGO

Schnackel
 engineers
 800-581-0963
 www.schnackel.com
 88 JEFFERSON ST. SUITE 1000


STORE NO: 1397

SHAKE SHACK
 IRVINE SPECTRUM CENTER
 15000 CALIFORNIA ST. IRVINE, CALIFORNIA 92618

REVISION	
DATE	DESCRIPTION
08/26/22	REVISION A
11/29/22	REVISION B
02/17/23	REVISION 2

STATUS: IFC SET

PRELIMINARY:
 Preliminary Documents Are for Design Review Only and not intended for bidding, engineering, permitting or construction purposes. They were prepared by or under the supervision of Zebra Projects, Inc.



FIELD VERIFICATION:
 The contractor shall verify all figured dimensions and conditions at the project site and notify Zebra Projects, Inc. of any dimensional errors, or omissions or discrepancies before beginning or fabricating any work. Do not make these changes.


COPYRIGHT © 2023:
 Zebra Projects, Inc. shall retain all common law, statutory and other reserved rights. No part of these documents nor the information herein is to be reproduced, distributed, modified or otherwise used without the written consent of Zebra Projects, Inc.

SHEET NAME: MECHANICAL ROOF PLAN

DATE: 01/16/23 PROJECT NO: 34286


DRAWN: RAS SCALE:

SHEET NO: M150



SEISMIC REQUIREMENTS:
 - ATTACH ALL CEILING AIR TERMINALS SHALL BE SUPPORTED DIRECTLY BY THE CEILING MAIN RUNNERS OR BY SUPPLEMENTAL FRAMING WHICH IS SUPPORTED BY MAIN RUNNERS AND POSITIVELY ATTACHED WITH SCREWS OR OTHER APPROVED CONNECTORS.
 - SURFACE MOUNTED FIXTURES SHALL BE ATTACHED TO A MAIN RUNNER WITH A POSITIVE CLAMPING DEVICE MADE OF MATERIAL WITH A MINIMUM OF 14 GAUGE. ROTATIONAL SPRING CLAMPS DO NOT COMPLY.

7 TYPICAL DIFFUSER-DRYWALL CEILING-SEISMIC
 NOT TO SCALE



NOTES:
 1. USE A MINIMUM OF (1) PLATE PER SIDE OF UNIT.
 2. PLATE MUST BE PAINTED WHERE IT CONTACTS RAIL.
 3. USE (6) SCREWS TO SECURE PLATE, NO SMALLER THAN #10x1/2"
 4. CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF, AND COMPLIANCE WITH ALL LOCAL CODES.
 5. CUT AND PATCH EXISTING ROOFING AS REQUIRED FOR NEW CURB INSTALLATION.
 6. CURB SHALL BE SHIMMED LEVEL. PROVIDE TAPERED ROOF CURB IF REQUIRED.


8 SEISMIC ROOF CURB DETAIL
 NOT TO SCALE

MAXIMUM HALF OF DUCT PERIMETER	PAIR AT 10 FT. SPACING		PAIR AT 8 FT. SPACING		PAIR AT 5 FT. SPACING		PAIR AT 4 FT. SPACING		
	STRAP	WIRE/ROD	STRAP	WIRE/ROD	STRAP	WIRE/ROD	STRAP	WIRE/ROD	
P/2 = 30"	1" x 22 GA.	10 GA. (.135")	1" x 22 GA.	10 GA. (.135")	1" x 22 GA.	12 GA. (.106")	1" x 22 GA.	12 GA. (.106")	
P/2 = 72"	1" x 18 GA.	3/8"	1" x 20 GA.	1/4"	1" x 22 GA.	1/4"	1" x 22 GA.	1/4"	
P/2 = 96"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"	1" x 20 GA.	3/8"	1" x 22 GA.	1/4"	
P/2 = 120"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"	1" x 20 GA.	1/4"	
P/2 = 168"	1 1/2" x 16 GA.	1/2"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"	
P/2 = 192"	---	1/2"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 16 GA.	3/8"	
P/2 = 193" UP	SPECIAL ANALYSIS REQUIRED								
WHEN STRAPS ARE LAP JOINED USE THESE MINIMUM FASTENERS:				SINGLE HANGER MAXIMUM ALLOWABLE LOAD					
				STRAP		WIRE OR ROD (DIA.)			
1" x 18, 20, 22 GA. - TWO #10 OR ONE 1/4" BOLT				1" x 22 GA. - 260 LBS.		0.106" - 80 LBS.			
1" x 16 GA. - TWO 1/4" DIA.				1" x 20 GA. - 320 LBS.		0.135" - 120 LBS.			
1" x 16 GA. - TWO 3/8" DIA.				1" x 18 GA. - 420 LBS.		0.162" - 160 LBS.			
PLACE FASTENERS IN SERIES, NOT SIDE BY SIDE.				1" x 16 GA. - 700 LBS.		1/4" - 270 LBS.			
				1 1/2" x 16 GA. - 1100 LBS.		3/8" - 680 LBS.			
						1/2" - 1250 LBS.			
						5/8" - 2000 LBS.			
						3/4" - 3000 LBS.			

NOTES:
 1. DIMENSIONS OTHER THAN GAUGE ARE IN INCHES.
 2. TABLES ALLOW FOR DUCT WEIGHT, 1 LB./SF INSULATION WEIGHT AND NORMAL REINFORCEMENT AND TRAPEZE WEIGHT, BUT NO EXTERNAL LOADS.
 3. STRAPS ARE GALVANIZED STEEL. OTHER MATERIALS ARE UNCOATED STEEL.
 4. ALLOWABLE LOADS FOR P/2 ASSUME THAT DUCTS ARE 16 GA. MAXIMUM, EXCEPT THAT WHEN MAXIMUM DUCT DIMENSION (W) IS OVER 60" THEN P/2 MAXIMUM IS 1.25 W.
 5. 12, 10 OR 8 GA. WIRE IS STEEL OF BLACK ANNEALED, BRIGHT BASIC OR GALVANIZED TYPE.
 6. DUCTS SHALL BE SUPPORTED AT INTERVALS NOT EXCEEDING 10 FEET.


4 RECTANGULAR DUCT HANGER TABLE
 NOT TO SCALE

NOTES:
 1. THERMAL CERAMICS FIREMASTER FASTWRAP XL IS TESTED TO ASTM E2336 AND UL LISTED PER HNTK018 TO PROVIDE ZERO CLEARANCE TO COMBUSTIBLES AND TO PROVIDE A 1 OR 2 HOUR EXPOSURE. THROUGH PENETRATIONS FIRESTOP SYSTEMS ARE TESTED IN ACCORDANCE WITH ASTM E 814 (UL 1479). ICC-ES APPROVAL PER REPORT ESR 2213 OR ESR 2832.
 2. COMPLIANT TO THE FOLLOWING CODES:
 NFPA 96
 INTERNATIONAL MECHANICAL CODES
 UNIFORM MECHANICAL CODE
 CALIFORNIA MECHANICAL CODE
 3. INSULATION APPLIED IN TWO LAYERS WITH TIGHT COMPRESSION JOINT ON BOTH LAYERS AT ALL JOINTS.
 4. MINIMUM 16 GAUGE CARBON STEEL (OR 18 GAUGE STAINLESS STEEL) RECTANGULAR OR ROUND GREASE EXHAUST DUCT.
 5. INSTALL UL LISTED AND LIQUID TIGHT THERMAL CERAMICS FASTDOOR XL ACCESS DOORS AT ALL CHANGES IN DIRECTION AND AT MINIMUM EVERY 20 FT ON HORIZONTAL RUNS.
 6. SUPPORT HANGER SYSTEMS DO NOT NEED TO BE WRAPPED PROVIDED THE HANGER RODS ARE MINIMUM OF 3/8" IN. DIAMETER AND SUPPORTS ARE MINIMUM 2 2 x 1/8 IN. STEEL ANGLE OR SMACNA EQUIVALENT SUPPORT SYSTEM.
 7. THERMAL CERAMICS DUCT WRAP SHALL BE INSTALLED DIRECTLY ONTO THE DUCT AND APPLIED FROM THE HOOD CONNECTION TO THE CONNECTION OF THE FAN.
 8. THERMAL CERAMICS DUCT ENCLOSURE SYSTEM SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS AND UL LISTINGS.




** DETAIL COURTESY OF MORGAN THERMAL CERAMICS.


5 FIREMASTER FASTWRAP XL DETAIL
 NOT TO SCALE



6 ROOF EXHAUST FAN DETAIL
 NOT TO SCALE




1 DUCTWORK DETAILS
 NOT TO SCALE



NOTE: HANGERS MUST NOT DEFORM DUCT SHAPE

2 DUCT HANGER DETAIL
 NOT TO SCALE



3 CONDENSER REFRIGERANT LINE PIPING AND POWER THROUGH ROOF DECK
 NOT TO SCALE

zebra
 ZEBRA PROJECTS, I.N.C.
 1464 N KIERNAND BLVD, SUITE N500
 SCOTTSDALE, ARIZONA 85254
 PHONE: 480.912.1169 zbr-global

CONSULTANT LOGO

Schnackel
 engineers

800-581-0963
 www.schnackel.com

STORE NO: 1397

SHAKE SHACK
 IRVINE SPECTRUM CENTER
 15000 SPECTRUM BLVD
 IRVINE, CALIFORNIA 92618

REVISION	
DATE	DESCRIPTION

STATUS: IFC SET

PRELIMINARY:
 Preliminary Documents are for Design Review only and not intended for bidding, permitting, permitting or construction purposes. They were prepared by or under the supervision of Zebra Projects, Inc.

REGISTERED PROFESSIONAL ENGINEER
 CALIFORNIA REG. NO. M33299
 MECHANICAL
 STATE OF CALIFORNIA
 Date: 02/17/23

FIELD VERIFICATION:
 The contractor shall verify all figured dimensions and conditions at the project site and notify Zebra Projects, Inc. of any dimensional errors, or omissions or discrepancies before beginning or fabricating any work. Do not make these

COPYRIGHT © 2023:
 Zebra Projects, Inc. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, modified or otherwise used without the written consent of Zebra Projects, Inc.


SHEET NAME: MECHANICAL DETAILS

DATE: 01/16/23 PROJECT NO: 34286

DRAWN: RAS SCALE:


SHEET NO: M501

DATE	DESCRIPTION
11/29/22	REVISION E




FIELD VERIFICATION:
The contractor shall verify all figured dimensions and conditions at the project site and notify Zebra Projects, Inc. of any dimensional errors, omissions or discrepancies before beginning or fabricating any work. Do not make these changes.


COPYRIGHT © 2023:
Zebra Projects, Inc. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, photocopied or otherwise without the written consent of Zebra Projects, Inc.




1 CONDENSING UNIT SUPPORT DETAIL
NOT TO SCALE




5 REMOTE VOLUME DAMPER CONTROLLER
NOT TO SCALE




2 KITCHEN HOOD EXHAUST FAN
NOT TO SCALE




6 DUCT SMOKE DETECTOR DETAIL
NOT TO SCALE




3 TYPICAL DRYWALL MOUNTING FRAME DETAIL
NOT TO SCALE




7 FLEXIBLE DUCT SUPPORTS
NOT TO SCALE




NOTE: PROVIDE SUPPORTS 10'-0" O.C. MIN. EACH SUPPORT SHALL BE CAPABLE OF 240 LBS. (WORKING LOAD 60 LB.)




9 EXPOSED ROUND DUCT SUPPORT DETAIL
NOT TO SCALE



11 EXPOSED RECTANGULAR DUCT SUPPORT DETAIL
NOT TO SCALE



12 CURB FLASHING DETAIL
NOT TO SCALE



SEISMIC REQUIREMENT NOTES:
A. AIR TERMINALS WEIGHING LESS THAN 20 POUNDS SHALL BE POSITIVELY ATTACHED TO THE MAIN RUNNER.
B. AIR TERMINALS WEIGHING BETWEEN 20 POUNDS AND 56 POUNDS SHALL HAVE TWO 12 GAUGE HANGER WIRES CONNECTED FROM THE TERMINAL TO THE STRUCTURE ABOVE AND SHALL BE POSITIVELY ATTACHED TO THE MAIN RUNNER. THE HANGER WIRES MAY BE SLACK.
C. AIR TERMINALS WEIGHING MORE THAN 56 POUNDS SHALL HAVE INDEPENDENT SUPPORT FROM THE STRUCTURE ABOVE.
D. HANGER WIRES SHALL MEET THE SAME INSTALLATION REQUIREMENTS AS VERTICAL SUSPENSION WIRES.

13 TYPICAL DIFFUSER CONNECTION - SEISMIC
NOT TO SCALE


DIA.	WIRE DIA.	ROD	STRAP
10\"/>			

NOTES:
1. STRAPS ARE GALVANIZED STEEL; RODS ARE UNCOATED OR GALVANIZED STEEL; WIRE IS BLACK ANNEALED, BRIGHT BASIC OR GALVANIZED STEEL. ALL ARE ALTERNATIVES.
2. TABLE ALLOWS FOR CONVENTIONAL WALL THICKNESS, AND JOINT SYSTEMS PLUS ONE LB/SF OF INSULATION WEIGHT. IF HEAVIER DUCTS ARE TO BE INSTALLED, ADJUST HANGER SIZES TO BE WITHIN THEIR LOAD LIMITS.


14 ROUND DUCT HANGER TABLE
NOT TO SCALE

BRACE SIZING		BRACING SPACING		
BRACE SIZE	MAXIMUM LENGTH	PIPE SIZE	MAXIMUM HANGER SPACING	MAXIMUM BRACE SPACING* (SEE NOTE B)
2\"/>				

15 SEISMIC BRACE SCHEDULE
NOT TO SCALE



8 CONDENSING UNIT ANCHOR DETAIL (METAL)
NOT TO SCALE



4 TYPICAL ROUND DUCT FITTINGS
NOT TO SCALE

SPECIFICATIONS TABLE OF CONTENTS

SECTION 230000 – HVAC GENERAL CONDITIONS

SECTION 230548 – VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT

SECTION 230583 – TESTING, ADJUSTING, AND BALANCING FOR HVAC

SECTION 230713 – DUCT INSULATION

SECTION 230713.13 – GREASE DUCT FIREPROOFING

SECTION 230718 – HVAC PIPING INSULATION

SECTION 230800 – REFRIGERANT PIPING

SECTION 230993 – SEQUENCE OF OPERATIONS FOR HVAC CONTROLS

SECTION 232000 – AIR DUCT ACCESSORIES

SECTION 232100 – HVAC DUCTS AND CASINGS

SECTION 232300 – AIR DUCT ACCESSORIES

SECTION 232423 – HVAC POWER VENTILATORS

SECTION 232700 – AIR OUTLETS AND INLETS

SECTION 232923 – PACKAGED AIR-COOLED REFRIGERANT COMPRESSOR AND CONDENSER UNITS

SECTION 233713 – MODULAR INDOOR CENTRAL-STATION AIR-HANDLING UNITS

SECTION 234743 – PACKAGED INDOOR ROOF-TOP UNITS

SECTION 238127 – SMALL SPLIT-SYSTEM HEATING AND COOLING

SECTION 230000 – HVAC GENERAL CONDITIONS

1.01 APPLICABILITY

A. This section supplements all sections of the Specifications for Division 23 and shall apply to all phases of work hereinafter specified, shown on the Drawings, or required to provide a complete installation of approved HVAC systems.

1.02 DEFINITIONS

A. "Work" is hereby defined as, "The construction and services required by the Contract Documents whether completed or partially completed and includes all labor, materials, equipment, and services provided or to be provided by the Contractor to fulfill the Contractor's obligations. The work may constitute the whole or a part of the project."

B. "Install" is hereby defined as, "To unpack and deliver, unload, and inspect for damage."

C. "Install" is hereby defined as, "To unpack, assemble, erect, place, finish, cure, protect, clean, connect, and place into operation into the work."

D. "Provide" is hereby defined as, "To furnish and install."

E. "Connect" is hereby defined as, "To bring service to the equipment and make final attachment including necessary ductwork, piping, wiring, etc."

F. "Concealed" is hereby defined as, "Hidden from sight in chases, furred spaces, shafts, hung ceilings, embedded in construction, in crawl spaces, or buried."

G. "Exposed" is hereby defined as, "Not installed underground nor concealed as defined by the Specifications."

H. "Drawings" is hereby defined as, "All plans, details, equipment schedules, diagrams, sketches, etc. issued for the construction of the work."

1.03 CODES AND STANDARDS

A. Perform work in accordance with the applicable Building Code, Electrical Code, Fire Code, Mechanical Code, Plumbing Code, Energy Code, and all other applicable codes, amendments, and ordinances. Also perform all work in accordance with the Americans with Disabilities Act (ADA) and the Authority Having Jurisdiction (AHJ) including Fire Marshal(s).

B. Perform work in accordance with Landlord requirements, including any Tenant Criteria Manuals and Lease Exhibits, where applicable.

C. Perform work in accordance with the applicable utility companies serving the project. Make all arrangements with the utility companies for proper coordination of the work.

D. Recognized Standards: Design, manufacture, testing and method of installation of all optical and material samples furnished under the requirements of these Specifications shall conform to the latest publications or standard rules of Underwriters Laboratories, Inc. (U.L.), American Society for Testing and Materials (ASTM), American National Standards Institute (ANSI), National Electrical Code (NEC), National Fire Protection Association (NFPA), American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE), International Brotherhood of Air Conditioning Contractors' National Association (SMAACNA).

E. The Contractor shall obtain instructions from the Architect before proceeding with the work. All permits, fees, inspections and arrangements required for the work under this Contract shall be obtained by the Contractor at his expense, unless otherwise indicated.

1.04 PERMITS AND FEES

A. Permits, licenses, fees, inspections and arrangements required for the work under this Contract shall be obtained by the Contractor at his expense, unless otherwise indicated.

1.05 CONTRACT DRAWINGS

A. The Contractor is responsible to obtain, fully understand, and coordinate the work with the complete set of Contract Documents. Any required corrections, including all associated costs, arising from issues caused by the Contractor's failure to understand and/or coordinate the work with the complete set of Contract Documents are the Contractor's sole responsibility.

B. Work under these sections is diagrammatic unless indicated otherwise and is intended to convey the scope of work and indicate the general arrangement of ductwork, piping, equipment, and accessories. Follow these drawings in laying out the work and verify spaces for the installation of these materials and equipment. Wherever a question exists as to the exact intended location of ductwork, piping, equipment, obtain instructions from the Architect before proceeding with the work.

C. Notify the Architect for resolution if a discrepancy is discovered within the Contract Documents. Failure of the Contractor to notify the Architect of discrepancies shall result in the Contractor being held responsible for the discrepancy and subject to the Architect's review and possible rejection. Should the Architect reject a discrepancy resolution of which they were not notified, the Contractor is fully responsible to correct the discrepancy, including all associated costs, until approval of the installation is given by the Architect.

1.06 EXISTING CONDITIONS

A. Verify all existing conditions prior to beginning work.

B. Any existing conditions indicated in the Contract Documents are based on information drawings provided by others and possibly limited field verification. The Contractor shall adjust for actual field conditions and notify the Architect.

C. The Contractor shall visit the project site, review existing conditions against the Contract Documents, and familiarize himself with the work prior to bidding and start of the work. By signing the Contract Documents, the Contractor certifies that the site visit has been completed and the existing conditions are accepted.

D. The Contractor shall notify the Architect of major discrepancies in writing so the appropriate modifications to the design can be made without delay. The Contractor assumes full responsibility of adjusting for discrepancies of which the Architect is not informed.

1.07 SUBMITTALS

A. Shop Drawings:

- Furnish the following submittals to the Architect for review by the Engineer:
 - Provide product data and shop drawings for vibration isolation.
 - Provide balancing fan qualifications and final test report for Testing, Adjusting, and Balancing.
 - Provide product data for duct insulation.
 - Provide product data for grease duct fireproofing (if specified).
 - Provide product data for HVAC piping insulation.
 - Provide product data for refrigerant piping.
 - Provide product data and shop drawings for HVAC ductwork.
 - Provide product data for duct accessories.
 - Provide product data and shop drawings for HVAC power ventilators.
 - Provide product data and shop drawings for air outlets and inlets.
 - Provide product data and shop drawings for condensing units and heat pumps.
- Provide product data and shop drawings for air handling and fan coil units.

2. Submittals other than those listed above will not be reviewed and will be returned stating as such.

3. Shop drawings shall be prepared by a manufacturer's representative, and shall contain names of the manufacturer and cut sheets of equipment to be used on the project. Use manufacturer's specification drawings or cut sheets of equipment indicated on drawings or schedules. Indicate catalog number on the cut sheets, include construction data, weight and dimensional data, voltage ratings, performance data, listing data, pump curves, fan curves and sound data as part of the shop drawing submittal.

4. Submittals are reviewed only for general compliance with the Contract Documents. Dimensions, quantities and details are not checked during submittal review. Review of the submittals does not relieve the Contractor of the responsibility for providing all materials, equipment and accessories necessary for a complete and operational system meeting the requirements of the project and the intent of the Contract Documents. The responsibility for coordination of substituted materials and equipment lies solely with the substituting Contractor.

5. Electrical Characteristics: Verify that proper power supply is available prior to ordering equipment. Verify proper voltage, phase and current rating of power supply and inform Engineer of any deviations prior to order, connection of equipment or start-up. Responsibility for verification of proper power supply voltage and any product returns or damage resulting from incorrect connections shall rest with this Contractor.

B. Test Reports: Provide Testing, Adjusting, and Balancing (TAB) and Commissioning reports to the Architect for review by the Engineer. All other reports shall be provided to the Owner.

1.08 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum five years experience.

B. Installer Qualifications: Company specializing in performing the work of this section, with minimum five years experience.

C. Products:

- Listed and classified by Underwriters Laboratories Inc. as suitable for the purpose specified and indicated.
- All equipment and components shall be free of all rust/corrosion or any visible damage. All items not complying with this requirement shall be replaced without any change in the Contract amount.
- Equipment performance and accessories shall be as scheduled on the Drawings and specified herein. Inclusion in both locations is not a prerequisite to inclusion in the Contract. Equipment and other location not specified shall be included in the Contract. Provide all necessary accessories and connections as necessary to complete, functional and safe operation of the system. The responsibility for coordination of substituted materials and equipment lies solely with the substituting Contractor.
- Code or utility company requirements shall supersede any conflicting requirements of this section.

1.09 DELIVERY, STORAGE AND HANDLING

A. Rooftop Equipment: Protect units from physical damage by storing off site until roof mounting curbs are in place, ready for immediate installation.

B. Protect insulation from weather and construction traffic, dirt, water, chemical, and mechanical damage, by storing in original wrapping.

C. Protect dampers and accessories from damage to operating linkages, blades and finishes.

D. Provide temporary caps and closures on piping and fittings. Maintain in place until installation.

E. Protect motors stored on site from weather and moisture by maintaining factory covers and suitable weather-proof covering. For extended outdoor storage, remove motors from equipment and store separately.

1.10 WARRANTY AND GUARANTEE

A. Submit manufacturer's warranty and ensure forms have been filled out in Owner's name and registered with manufacturer reports in accordance with manufacturer's name and registered with manufacturer reports for pumps.

B. Provide three year manufacturer warranty for solid state ignition modules.

C. Provide five year manufacturer warranty for compressors, heat exchangers, condensing units, and electronic air cleaners.

PART 2 PRODUCTS

2.01 SUBSTITUTIONS

The manufacturers listed are listed to set minimum standards for quality, design, and functionality. The products of other manufacturers may be substituted, at the Contractor's option, during construction, provided the selected material meets with the products of other manufacturers shall meet or exceed all requirements of the Contract Documents. The Contractor shall be responsible for costs and coordination issues arising out of the substitution of materials or equipment, and the coordination of such substitutions with all other contractors and subcontractors.

B. The Contractor may use any of the following ductwork, piping or insulation materials at his option, provided the selected material meets with the approval of all State, local authorities and any utility company requirements. Verification of compliance of the selected material is the sole responsibility of the installing Contractor.

PART 3 EXECUTION

3.01 COORDINATION OF WORK

A. Examine the Contract Documents as a whole for the work of other trades. Coordinate all work according to drawings and specifications.

B. Promptly report to the Architect any delay or difficulties encountered in the installation of the work, which might prevent prompt and proper installation, or make it unfeasible to connect with or receive the work of others. Failure to so report shall constitute an acceptance of the work of other trades as being fit and proper for the execution of this work.

C. Plan, lay out, and coordinate the work with all trades well enough in advance so that it proceeds with a minimum of interference to the work of others not being completed and work that is in progress. Inform all trades of openings required for the work and provide all special frames, sleeves, and anchor bolts required. The HVAC system layout may be altered to suit the conditions with engineer approval prior to the installation of any work and without additional cost to the Owner.

D. Conflicts arising from lack of coordination shall be the Contractor's responsibility.

E. Perform work in conformity with the Contract Documents and afford other trades reasonable opportunity for the execution of their work. Properly connect and coordinate this work with the work of other trades at such time and in such manner as not to interfere with their work.

F. All roofing penetrations shall be flashed and weather sealed by the roofing manufacturer's authorized roofing contractor by adjustment of National Energy Research Institute (NERI) Flashing and Waterproofing Systems. This Contractor shall contract with the factory authorized roofing contractor for the specific roofing system applicable to this project. The use of an unauthorized roofing contractor may result in removal and replacement of the penetration systems at this Contractor's expense.

G. All temperature control wiring, thermostat wiring, damper interlock wiring, control panel interlock wiring and miscellaneous low voltage wiring associated with the equipment shall be installed under this contract shall be furnished and installed by the mechanical contractor or his sub-contractor. All wiring installed under this contract shall be in full compliance with the National Electrical Code, all State and local codes and requirements of the Electrical Specifications for this project.

3.02 EXAMINATION

A. Verify field measurements are as indicated on the Drawings.

B. Verify equipment locations prior to roughing and adequate equipment service clearance per manufacturer and code.

C. Verify routing of all ductwork and piping in field prior to fabrication or installation. Verify adequate clearance with structure, light fixtures, and ceiling heights.

D. Verify that proper fuel and power supply is available for connection.

3.03 INTERFERENCE WITH OTHER PRODUCTS

A. Install ductwork, pipe, equipment, and accessories to preserve fire resistance rating of partitions and other elements, using materials and methods specified.

3.04 FIELD QUALITY CONTROL

A. Provide tests as necessary to establish the adequacy, quality, safety, completed status, and suitable operation of each system. Tests shall be conducted under the supervision of the Architect.

B. Clean fire suppression parts to remove harmful materials.

C. Clean exposed surfaces of all ductwork pipe, equipment, and accessories, as directed by and to the satisfaction of the Architect, when marking or disfiguring his recommendations for cleaning as applicable.

D. Repair or replace damaged ductwork, pipe, equipment, and accessories, as directed by and to the satisfaction of the Architect, when marking or disfiguring his recommendations for cleaning as applicable.

3.05 CLEANING AND REPAIR

A. Clean fire suppression parts to remove harmful materials.

B. Clean exposed surfaces of all ductwork pipe, equipment, and accessories, as directed by and to the satisfaction of the Architect, when marking or disfiguring his recommendations for cleaning as applicable.

C. Repair or replace damaged ductwork, pipe, equipment, and accessories, as directed by and to the satisfaction of the Architect, when marking or disfiguring his recommendations for cleaning as applicable.

3.06 PROJECT CLOSEOUT

A. Project Record Documents: At project closeout, provide one printed copy and one electronic copy of the project record documents to the Owner. Record documents will not be reviewed by the Engineer.

B. Record Drawings: Information contained on project record drawings shall include, but not be limited to:

- Actual locations of all equipment, ductwork, air inlets/outlets, accessories, etc.
- Actual routing of ductwork with sizes and elevations.
- Actual locations of control valves and volume dampers.
- Operation and Maintenance Data: Provide descriptive literature, maintenance and operation data for all HVAC equipment, control systems, accessories, and materials used. Include maintenance procedures, intervals, and parts list for each item installed under this contract. Include all manufacturer's guarantees and warranties.
- Maintenance Materials: At project closeout, furnish to the Owner the following:
 - One set of replacement parts for all HVAC equipment.
 - The maintenance contract for the HVAC system, if applicable.
- Test Reports: Submit to the Owner all testing reports.

END OF SECTION

SECTION 230548 – VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT

1.01 SECTION INCLUDES

A. Vibration Isolators.

B. Equipment:

- Fans, axial and centrifugal
- Condensing units and air source heat pumps
- Furnaces and fan coil units.

1.02 SUBMITTALS

A. Product Data: Provide schedule of vibration isolator type with location and load on each.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Isolation Technology, Inc.; Kinetics Noise Control, Inc.; Mason Industries.

2.02 VIBRATION ISOLATORS

A. Spring Hanger:

- Minimum horizontal stiffness equal to 75 percent vertical stiffness with working deflection between 0.3 and 0.6 of maximum deflection.
- Coil code springs for load carrying capacity.
- Hoistings: Incorporate neoprene isolation pad meeting requirements for neoprene pad isolators or metal hanger with threaded insert.
- Misalignment: Capable of 20 degree hanger rod misalignment.
- For Exterior and Humid Areas: Hot dipped galvanized housings and neoprene coated springs.

B. Neoprene Pad Isolators:

- Rubber or neoprene waffle pads.
 - Hardness: 30 durometer.
 - Thickness: Minimum 1/2 inch.
 - Maximum Loading: 50 psi.
 - Height: Maximum 0.7 times width.
- Configuration: Single layer.

C. Rubber Mount or Hanger: Molded rubber designed for 0.4 inch deflection with threaded insert.

D. Fiber Pad: Neoprene jacketed pre-compressed molded glass fiber.

PART 3 EXECUTION

3.01 INSTALLATION

A. Refer in accordance with manufacturer's instructions.

B. Provide flexible connections on all piping and ductwork connections to equipment. Install in other sections of this Specification for the acceptable types of flexible connections to be used in accordance with the National Electrical Code.

C. Selection of type, thickness and deflection of vibration isolation shall be by the vibration control manufacturer based on the specific equipment type and size, as scheduled on the Drawings and indicated below.

3.02 SCHEDULES

A. Equipment Isolation Schedule: (Minimum deflection as sized by the isolation equipment manufacturer.)

- Fans, axial and centrifugal.
 - Small fans up to 22" diameter wheel:
 - Rubber Mount or Hanger
 - Condensing heat pumps.
 - Slab on grade.
 - Base: Concrete Housekeeping Pad.
 - Isolation: Neoprene Pad, Rubber Mount or Glass Fiber Pad.
 - Above grade floor or roof structures.
 - Base: Plastic or Fiber Cement Pad.
 - Isolation: Neoprene Pad, Rubber Mount or Glass Fiber Pad.
- Furnaces and fan coil units.
 - Floor mounted (all locations).
 - Base: Concrete Housekeeping Pad.
 - Isolation: Neoprene Pad, Rubber Mount or Glass Fiber Pad.
 - Suspended.
 - Isolation: Rubber or Spring Hanger.

SECTION 230583 – TESTING, ADJUSTING, AND BALANCING FOR HVAC

1.01 SECTION INCLUDES

A. Testing, adjustment, and balancing of air systems.

B. Air handling units: Packaged heating and/or cooling equipment; Fans (Exhaust and supply); Coils; Terminal equipment; Air inlets and outlets; Diffusers, (Return and supply).

C. Measurement of final operating condition of HVAC systems.

D. Independent agency requirements.

1.02 SUBMITTALS

A. Qualifications: Submit name of adjusting and balancing agency and TAB supervisor for approval within 30 days of award of Contract. Provide the following information:

B. Field Reports: Indicate deficiencies in systems that would prevent proper testing, adjusting, and balancing of systems and equipment to achieve specified performance.

1.03 INSTALLATION

A. Install in accordance with manufacturer's instructions and NAIMA National Insulation Standards.

B. Insulate all ducts conveying air below ambient temperature.

C. Provide insulation with vapor barrier jackets.

D. Finish with tape and vapor barrier jacket.

E. Continue insulation through walls, sleeves, hangers, and other duct penetrations.

F. Insulate entire system including fittings, joints, flanges, fire dampers, flexible connections, and expansion joints.

5. Include the following on the title page of each report:

- Name, address and telephone number of Testing, Adjusting, and Balancing Agency.
- Project: Name; location; Engineer; Contractor; Report date.

1.03 WARRANTY

A. The Balancing Contractor shall be required to return to the site at no additional cost to re-adjust air quantities as prepared to provide uniform temperatures, eliminate drafts and objectionable noises during the first year of occupancy, including one full heating and one full cooling season, after the acceptance of the final balancing report.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION

3.01 GENERAL REQUIREMENTS

A. Perform total system balance in accordance with one of the following:

- ASHRAE 90.1, ASHRAE National Standards for Total System Balance.
- ASHRAE Std 111, Practices for Measurement, Testing, Adjusting and Balancing of Building Heating, Ventilation, Air-Conditioning, and Refrigeration Systems.
- NEBB Procedural Standards for Testing Adjusting Balancing of Environmental Systems.
- SMACNA HVAC Systems Testing, Adjusting, and Balancing.

B. Begin work after completion of systems to be tested, adjusted, or balanced and complete work prior to Substantial Completion of the Project.

C. Where HVAC systems and/or components interface with life safety systems, including fire and smoke detection, alarm, and control, coordinate scheduling and testing and inspection procedures with the authorities having jurisdiction.

TAB Agency Qualifications:

- Company specializing in the testing, adjusting, and balancing of systems specified in this section with a minimum of five years experience.
- Certified by one of the following:
 - ASHRAE Accredited Air Balance Council; upon completion submit AABC or National Performance Guaranty.
 - NEBB, National Environmental Balancing Bureau.
 - TABS, The Testing, Adjusting, and Balancing Bureau of National Energy Research Institute.
- The TAB Agency must be a completely independent, third party balancing contractor with no financial, common owners or other ties to the installing contractor.

TAB Supervisor and Technician Qualifications: Certified by some organization as:

- TAB Agency.
- ASHRAE License.
- Air Handling Systems; Air Outlets and Inlets; Hydronic Systems: Adjust to within 1/2% or minus 15 percent of design.

3.02 RECORDING AND ADJUSTING

A. Permanently mark settings of valves, dampers, and other adjustment devices allowing settings to be restored. Set and lock memory stops.

B. Mark on the Drawings the locations where traverse and other critical measurements were taken and cross reference the location in the final report.

3.04 AIR SYSTEM PROCEDURE

A. Verify all equipment locations prior to roughing and adequate equipment service clearance per manufacturer and code.

B. Make air quantity measurements in field prior to fabrication or installation. Verify adequate clearance with structure, light fixtures, and ceiling heights.

C. Measure air quantities at air inlets and outlets.

D. Adjust distribution system to obtain uniform space temperatures free from objectionable drafts and noise.

E. Install volume control devices to regulate air quantities only to extend that adjustments do not create objectionable air motion or sound levels. Effect volume by adjusting damper devices such as dampers and splitters. Do not use diffuser, grille or register integral dampers for balancing adjustments unless the plans do not indicate duct mounted devices.

F. Clean fire suppression parts to remove harmful materials.

G. Measure static air pressure conditions on air supply units, including filter and coil pressure drops, and total pressure across the fan. Make allowances for 50 percent loading of filters.

H. Adjust outside air automatic dampers, outside air, return air, and exhaust dampers by and to the satisfaction of the Architect, when marking or disfiguring his recommendations for cleaning as applicable.

I. Measure temperature conditions across outside air, return air, and exhaust dampers to check leakage.

J. Where modulating dampers are provided, take measurements and balance at extreme conditions and at all intermediate operating conditions specified in the sequence of control. Balance variable volume systems at maximum air flow rate, full cooling, and at minimum air flow rate, full heating.

3.05 SCOPE

A. Equipment Requiring Testing, Adjusting, and Balancing (if present on the project):

- HVAC Pumps; Boilers; All Air Handling Equipment; All Packaged Heating and/or Cooling Equipment; All Coils; All Heat Exchangers; Terminal Heat Transfer Units; Air Terminal Units; Air Inlets and Outlets

3.06 MINIMUM DATA TO BE REPORTED TO THE ARCHITECT:

A. Report (if applicable to the project):

- Summary Comments:
 - Design versus field performance
 - Notable characteristics of system
 - Summary of outdoor and exhaust flows to indicate amount of building pressurization
 - Nomenclature used throughout report and test conditions.
- Electric Motors and Drives:
 - Manufacturer; Make/Frame; HP/BHP; Phase, voltage, amperage; nameplate, actual, no load; RPM; Service factor; Sheave Make/Size/Type.
 - V-Belt Drives: Identification/location; Required driven RPM; Driven sheave, diameter and RPM; Belt; size and quantity.
 - Cooling and Heating Coils:
 - Identification/number.
 - Air flow, design and actual.
 - Air pressure drop, design and actual.
 - Entering and leaving air DB and WB temperature, design and actual.
 - Water flow, design and actual (if applicable).
 - Water pressure drop, design and actual (if applicable).
 - Entering and leaving water temperature, design and actual (if applicable).
- Air Moving Equipment: Model number; Serial number; Arrangement; Class/Discharge
- Inlet, Discharge: Total static pressure (total external), specified and actual

END OF SECTION

SECTION 230713 – DUCT INSULATION

1.01 SECTION INCLUDES

A. Duct insulation.

B. Rubber Mount or Hanger: Molded rubber designed for 0.4 inch deflection with threaded insert.

C. Insulation jackets.

D. Glass Fiber Pads: Neoprene jacketed pre-compressed molded glass fiber.

1.02 FIELD CONDITIONS

A. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cement.

B. Maintain temperature during and after installation for minimum period of 24 hours.

PART 2 PRODUCTS

2.01 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION

A. Surface Burning Characteristics: Flame spread/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E 84, NFPA 255, or UL 723.

B. Manufacturer: Knauf Fiberglast; Johns Manville Corporation; Owens Corning Corp.; CertainTeed Corporation.

2.02 GLASS FIBER, FLEXIBLE

A. Insulation: ASTM C 553; flexible, noncombustible blanket.

- "K" value: 0.31 at 75 degrees F, when tested in accordance with ASTM C 518.
- Maximum Service Temperature: 450 degrees F.
- Maximum Water Vapor Sorption: 5.0 percent by weight.

B. Vapor Barrier Jacket:

- Kraft paper with glass fiber yarn and bonded to aluminumized film.
- Molature Vapor Permeability: 0.029 ng/Pa s m (0.02 perm inch), when tested in accordance with ASTM E 96/E 96M.
- Secure with pressure sensitive tape.

C. Vapor Barrier Tape:

- Kraft paper reinforced with glass fiber yarn and bonded to aluminumized film, with pressure sensitive rubber based adhesive.

D. Outdoor Vapor Barrier Mastic:

- Vinyl emulsion type acrylic or mastic, compatible with insulation, black color.

E. Tie Wire: Annealed steel, 16 gage.

2.03 DUCT LINES

A. Insulation: Incombustible glass fiber complying with ASTM C 1071; flexible blanket, rigid board, and preformed round liner board; impregnated surface and edges coated with acrylic polymer shown to be fungus and bacteria resistant by testing to ASTM C 21.

- Minimum Service Temperature: Up to 250 degrees F.
- Rated Vapor Sorption: Maximum of 0.31 at 75 degrees F.
- Minimum Noise Reduction Coefficient: 0.30.
- Minimum Noise Reduction Coefficient: 0.45.
- 1-1/2 inches Thickness: 0.60.
- 1 inch Thickness: 0.45.

B. Adhesive: Waterproof, fire-retardant type.

C. Liner Fasteners: Galvanized steel, self-adhesive pad or impact applied with integral, or press-on head.

END OF SECTION

SECTION 230718 – HVAC PIPING INSULATION

1.01 SECTION INCLUDES

A. Duct insulation.

B. Rubber Mount or Hanger: Molded rubber designed for 0.4 inch deflection with threaded insert.

C. Insulation jackets.

D. Glass Fiber Pads: Neoprene jacketed pre-compressed molded glass fiber.

1.02 FIELD CONDITIONS

A. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cement.

B. Maintain temperature during and after installation for minimum period of 24 hours.

PART 2 PRODUCTS

2.01 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION

A. Surface Burning Characteristics: Flame spread/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E 84, NFPA 255, or UL 723.

B. Manufacturer: Knauf Fiberglast; Johns Manville Corporation; Owens Corning Corp.; CertainTeed Corporation.

2.02 GLASS FIBER, FLEXIBLE

A. Insulation: ASTM C 553; flexible, noncombustible blanket.

- "K" value: 0.31 at 75 degrees F, when tested in accordance with ASTM C 518.
- Maximum Service Temperature: 450 degrees F.
- Maximum Water Vapor Sorption: 5.0 percent by weight.

B. Vapor Barrier Jacket:

- Kraft paper with glass fiber yarn and bonded to aluminumized film.
- Molature Vapor Permeability: 0.029 ng/Pa s m (0.02 perm inch), when tested in accordance with ASTM E 96/E 96M.
- Secure with pressure sensitive tape.

C. Vapor Barrier Tape:

- Kraft paper reinforced with glass fiber yarn and bonded to aluminumized film, with pressure sensitive rubber based adhesive.

D. Outdoor Vapor Barrier Mastic:

- Vinyl emulsion type acrylic or mastic, compatible with insulation, black color.

E. Tie Wire: Annealed steel, 16 gage.

2.03 DUCT LINES

A. Insulation: Incombustible glass fiber complying with ASTM C 1071; flexible blanket, rigid board, and preformed round liner board; impregnated surface and edges coated with acrylic polymer shown to be fungus and bacteria resistant by testing to ASTM C 21.

- Minimum Service Temperature: Up to 250 degrees F.
- Rated Vapor Sorption: Maximum of 0.31 at 75 degrees F.
- Minimum Noise Reduction Coefficient: 0.30.
- Minimum Noise Reduction Coefficient: 0.45.
- 1-1/2 inches Thickness: 0.60.
- 1 inch Thickness: 0.45.

B. Adhesive: Waterproof, fire-retardant type.

C. Liner Fasteners: Galvanized steel, self-adhesive pad or impact applied with integral, or press-on head.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions and NAIMA National Insulation Standards.

B. Insulate all ducts conveying air below ambient temperature.

C. Provide insulation with vapor barrier jackets.

D. Finish with tape and vapor barrier jacket.

E. Continue insulation through walls, sleeves, hangers, and other duct penetrations.

F. Insulate entire system including fittings, joints, flanges, fire dampers, flexible connections, and expansion joints.

Insulated ducts conveying air above ambient temperature: Provide with or without standard vapor barrier jacket.

2. Insulate fittings and joints. Where service access is required, bevel and finish ends of insulation.

D. External Duct Insulation Application:

- Apply vapor barrier adhesive or tape to match jacket.
- Secure insulation without vapor barrier with staples, tape, or wire.
- Install without sag on underside of duct. Use adhesive or mechanical fasteners where necessary to prevent sagging. Lift duct off trapeze hangers.
- Seal linear penetrations by mechanical fasteners with vapor barrier.
- Stop and point insulation around access doors and damper operators to allow insulation without disturbing wrapping.

E. Duct and Plenum Liner Application:

- Adhere insulation with adhesive for 90 percent coverage.
- Secure insulation with mechanical liner fasteners. Refer to SMACNA HVAC Duct Construction Standards – Metal and Flexible for spacing.
- Seal and smooth all penetrations with adhesive.
- Seal linear surface penetrations with adhesive.
- Duct dimensions indicated on net inside dimensions required for air flow. Increase duct size to allow for insulation thickness.

3.02 SCHEDULES

A. The Contractor may use any of the following insulating materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected insulating material and thickness with all State and local codes and utility company requirements is the sole responsibility of the installing Contractor.

B. Flexible Glass Fiber Duct Insulation: 1-1/2 inches thick.

C. Flexible Glass Fiber Duct Liner Insulation: 1 inches thick.

D. Supply of ducts:

- Flexible Glass Fiber Duct Insulation: 3 inches thick.
- Flexible Glass Fiber Duct Liner Insulation: 1 inches thick.

E. Outside air intake ducts (untempered):

- Flexible Glass Fiber Duct Insulation: 1-1/2 inches thick.
- Rigid Glass Fiber Duct Insulation: 1-1/2 inches thick.
- Flexible Glass Fiber Duct Liner Insulation: 1 inches thick.
- Rigid Glass Fiber Duct Insulation: 1 inches thick.

F. Outside air intake ducts (tempered): None.

END OF SECTION

SECTION 230713.13 – GREASE DUCT FIREPROOFING

1.01 SECTION INCLUDES

A. The resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts).

B. Firestopping at duct penetrations through fire rated walls and floors.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Acceptable Manufacturer: 3M Fire Protection Products, Inc.; Unifrax FireWrap; Versar Thermal Coatings.

2.02 MATERIALS

A. Grease D

ROOM #	NAME	Az AREA (FT ²)	TABLE 402.1 OCCUPANCY CATEGORY	TABLE 402.1 Rp PEOPLE DA (CFM/PER)	TABLE 402.1 Ra AREA DA (CFM/FT ²)	TABLE 402.1 OCCUPANT DENSITY (#/1000 FT ²)	Pz	Rp/Pz	Ra/Pz	Vbz	TABLE 403.2.2 Voz (CFM)	Xz	Vz	Vzpm	INTERPOLATED TABLE 403.5.2 Ev	
100	DINING AREA	150	SALES	7.5	0.26	15	4	30	20	53	0.80	49	0.128	975	0.059	1.00
101	DINING	819	CAFETERIA/FAST FOOD DINING	7.5	0.80	100	38	285	165	450	0.80	460	0.128	3025	0.186	0.96
		1,109					42	315	188	503		508		4000	0.186	0.98

OUTDOOR AIR CALCULATIONS PER EQUATION 403.5.4

SYMBOL VALUE DESCRIPTION

P_s = 42 SYSTEM POPULATION

SP_z = 42 ZONE POPULATION

D = 1.00 OCCUPANT DIVERSITY

V_{ou} = 503 UNCORRECTED OUTDOOR AIR INTAKE

Z_p (max) = 0.186 ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)

E_v = 0.96 SYSTEM VENTILATION EFFICIENCY

SV_z = 4000 ZONE PRIMARY AIRFLOW

V_{ot} = 506 CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM

V_{oz} = 550 DESIGN OUTDOOR AIRFLOW RATE, CFM

ROOM #	NAME	Az AREA (FT ²)	TABLE 402.1 OCCUPANCY CATEGORY	TABLE 402.1 Rp PEOPLE DA (CFM/PER)	TABLE 402.1 Ra AREA DA (CFM/FT ²)	TABLE 402.1 OCCUPANT DENSITY (#/1000 FT ²)	Pz	Rp/Pz	Ra/Pz	Vbz	TABLE 403.2.2 Voz (CFM)	Xz	Vz	Vzpm	INTERPOLATED TABLE 403.5.2 Ev	
102	OPEN KITCHEN	527	KITCHEN (COOKING)	7.5	0.15	20	11	83	63	148	0.80	80	0.080	2080	0.068	1.00
103	BACK KITCHEN	550	KITCHEN (COOKING)	7.5	0.15	20	11	83	66	149	0.80	83	0.080	2450	0.078	1.00
105	CUSTARD	69	NO LISTING	0.0	0.00	0	0	0	0	0	0.80	0	0.000	175	0.000	1.00
108	CORRIDOR	36	NO LISTING	0.0	0.15	0	0	0	0	0	0.80	0	0.000	0	0.000	1.00
107	WOMENS	168	NO LISTING	0.0	0.00	0	0	0	0	0	0.80	0	0.000	150	0.000	1.00
108	MENS	137	NO LISTING	0.0	0.00	0	0	0	0	0	0.80	0	0.000	150	0.000	1.00
		1,534					22	165	134	299		176		5005	0.068	1.00

OUTDOOR AIR CALCULATIONS PER EQUATION 403.5.4

SYMBOL VALUE DESCRIPTION

P_s = 22 SYSTEM POPULATION

SP_z = 22 ZONE POPULATION

D = 1.00 OCCUPANT DIVERSITY

V_{ou} = 299 UNCORRECTED OUTDOOR AIR INTAKE

Z_p (max) = 0.988 ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)

E_v = 1.00 SYSTEM VENTILATION EFFICIENCY

SV_z = 5000 ZONE PRIMARY AIRFLOW

V_{ot} = 176 CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM

V_{oz} = 500 DESIGN OUTDOOR AIRFLOW RATE, CFM

ROOM #	NAME	Az AREA (FT ²)	TABLE 402.1 OCCUPANCY CATEGORY	TABLE 402.1 Rp PEOPLE DA (CFM/PER)	TABLE 402.1 Ra AREA DA (CFM/FT ²)	TABLE 402.1 OCCUPANT DENSITY (#/1000 FT ²)	Pz	Rp/Pz	Ra/Pz	Vbz	TABLE 403.2.2 Voz (CFM)	Xz	Vz	Vzpm	INTERPOLATED TABLE 403.5.2 Ev	
104	MANAGERS	53	OFFICE SPACE	5.0	0.15	5	2	10	3	13	0.80	2	0.038	350	0.047	1.00

OUTDOOR AIR CALCULATIONS PER ASHRAE 62.1, APPENDIX A

SYMBOL VALUE DESCRIPTION

P_s = 2 ZONE POPULATION

SP_z = 2 ZONE POPULATION

D = 1.00 OCCUPANT DIVERSITY

V_{ou} = 13 UNCORRECTED OUTDOOR AIR INTAKE

V_{ov} = SV_z SYSTEM PRIMARY AIRFLOW

X_s = 0.938 AVERAGE OUTDOOR AIR FRACTION

E_v = Ev (min) 0.99 ZONE VENTILATION EFFICIENCY

Ep = TYPICAL 1.0, MAY VARY PRIMARY AIR FRACTION TO THE ZONE

E_s = TYPICAL 0.8, MAY VARY FRACTION OF SECONDARY RECIRCULATED AIR TO THE ZONE

E_z = TYPICAL 0.8, MAY VARY ZONE AIR DISTRIBUTION EFFECTIVENESS

F_s = TYPICAL 0.8, MAY VARY FRACTION OF SUPPLY AIR TO THE ZONE FROM SOURCES OUTSIDE THE ZONE

F_z = VARIES FRACTION OF SUPPLY AIR TO THE ZONE FROM FULLY MIXED PRIMARY AIR

F_z = VARIES FRACTION OF OUTDOOR AIR TO THE ZONE FROM SOURCES OUTSIDE THE ZONE

E_v = VARIES ZONE VENTILATION EFFICIENCY

Z_p = VARIES THE OUTDOOR AIR FRACTION REQUIRED IN AIR DISCHARGED TO THE ZONE BASED ON THE MINIMUM DISCHARGE AIRFLOW

V_{ot} = 8 CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM

V_{oz} = 20 DESIGN OUTDOOR AIRFLOW RATE, CFM

1 OUTSIDE AIR CALCULATIONS

Air System Sizing Summary for BLOCK LOAD		05/02/2022 01:16PM	
Project Name: 210564hvac_for_FA_20220502113853-FAFinal			
Prepared by: Schnackel Engineers, Inc			
Air System Information		Number of zones 1	
Air System Name BLOCK LOAD	Floor Area 2696.0 ft ²	Location Los Angeles LAX, California	
Equipment Class PKG ROF			
Air System Type SZCAV			
Sizing Calculation Information		Calculation Months Jan to Dec	
Zone and Space Sizing Method:	Sizing Data Calculated		
Zone CFM Peak zone sensible load			
Space CFM Individual peak space loads			
Central Cooling Coil Sizing Data		Load occurs at Aug 1600	
Total coil load 16.7 Tons	OA DB / WB 84.7 / 63.9 °F		
Sensible coil load 186.3 MBH	Entering DB / WB 76.9 / 62.9 °F		
Coil CFM at Aug 1600 8113 CFM	Leaving DB / WB 55.6 / 54.3 °F		
Max block CFM 8113 CFM	Coil ADP 53.2 °F		
Sum of peak zone CFM 8113 CFM	Bypass Factor 0.100		
Sensible heat ratio 0.929	Resulting RH 48 %		
BTU/Ton 161.4	Design supply temp. 55.0 °F		
BTU/(hr-ft ²) 74.3	Zone T-stat Check 1 of 1 OK		
Water flow @ 10.0 °F rise N/A	Max zone temperature deviation 0.0 °F		
Central Heating Coil Sizing Data		Load occurs at Des Htg	
Max coil load 68.1 MBH	BTU/(hr-ft ²) 25.3		
Coil CFM at Des Htg 8113 CFM	Ent. DB / Lvg DB 69.1 / 76.9 °F		
Max coil CFM 8113 CFM			
Water flow @ 20.0 °F drop N/A			
Supply Fan Sizing Data		Fan motor BHP 1.33 BHP	
Actual max CFM 8113 CFM	Fan motor kW 1.06 kW		
Standard CFM 8082 CFM	Fan static 0.60 in wg		
Actual max CFM/ft ² 3.01 CFM/ft ²			

2 LOAD CALCULATIONS

RTU/AHU CONTROL MATRIX			
SETPOINT/CONTROL	RTU-1 DINING	RTU-2 KITCHEN	FC-1 OFFICE
SETPOINTS			
COOLING - OCCUPIED SETPOINT	75 F	75 F	75 F
COOLING - UNOCCUPIED SETPOINT	70 F	70 F	70 F
HEATING - OCCUPIED SETPOINT	70 F	70 F	70 F
HEATING - UNOCCUPIED SETPOINT	60 F	60 F	60 F
ECONOMIZER UPPER LIMIT SETPOINT	70 F	70 F	NA
ACCESSORIES			
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT	YES	YES	YES
REMOTE TEMPERATURE SENSOR	YES	YES	NO
MOTORIZED OUTDOOR AIR DAMPER	YES	YES	YES
INTEGRATED ECONOMIZER	YES	YES	NO
ECONOMIZER FAULT DETECTION	YES	YES	NO
BAROMETRIC RELIEF	YES	YES	NO
POWERED EXHAUST RELIEF	NO	NO	NO
DEHUMIDIFICATION (HOT GAS REHEAT)	NO	NO	NO
SUPPLY FAN			
ON DURING OCCUPIED MODE	YES	YES	YES
VARIABLE VOLUME - MODULATE FAN SPEED	YES	YES	YES
SAFETIES AND INTERLOCKS			
SUPPLY AIR SMOKE DETECTOR	YES	YES	NO
LOW LIMIT FREEZE STAT	YES	YES	YES
FIRE ALARM CONTROL PANEL INTERLOCK	YES	YES	YES
KITCHEN EXHAUST SYSTEM INTERLOCK	YES	YES	YES

AIR BALANCE SCHEDULE						
EQUIPMENT TAG	SUPPLY AIRFLOW (CFM)	OUTDOOR AIRFLOW (CFM)	RETURN AIRFLOW (CFM)	EXHAUST AIRFLOW (CFM)	OA/SA (%)	REMARKS
RHP-1	4,000	850	3,150		21%	
RHP-2	5,000	500	4,500		10%	
MUA-1	1,950	1,950	0		100%	
FC-1	350	20	330		6%	
EF-1				825		
EF-2				1,815		
EF-3				420		
TOTAL	11,300	3,320	7,980	3,060		
RESULTING BUILDING PRESSURIZATION = 260 CFM						
PRESSURIZATION PERCENTAGE = 2.3 %						

CARRIER EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. CONTACT CARRIER CORPORATION FOR PROPOSALS:
KEN REVILLA
CARRIER RETAIL STRATEGIC ACCOUNTS
EMAIL: KEN.REVILLA@CARRIER.COM
PHONE: (954) 218-0070

EXISTING LANDLORD PROVIDED ROOF TOP HEAT PUMP UNITS (FOR REFERENCE ONLY)																	
MARK	COOLING			HEATING			SUPPLY AIR (CFM)	EXT. S.P. (IN)	ELECTRICAL				REMARKS				
	SEN (MBH)	TOT (MBH)	COOL (TON)	AT 47°F (MBH)	ELEC (KW)	FAN BHP			VOLT	PH	MCA	MOCP		WEIGHT (LBS)	SEER /EER	HSPF /COP	CARRIER MODEL NUMBER
RHP-1	88.1	118.2	10	115.9	N/A	4,000	0.50	1.68	460	3	26.0	30	1,732	-/11.00	-/3.3	50TCOD12	NA
RHP-2	113.9	148.8	12.5	143.0	N/A	5,000	0.50	1.73	460	3	31.0	40	1,742	-/10.60	-/3.2	50TCOD14	NA

COOLING CAPACITIES ARE BASED ON AHRI STANDARD 210/240 OR 340/360; 80°F DB/ 67°F WB INDOOR ENTERING AIR TEMPERATURE, 95°F DB AIR ENTERING OUTDOOR FAN. SCHEDULED UNIT MAY DIFFER FROM AHRI STANDARD CFM.

EXHAUST FANS												
MARK	LOCATION	SERVICE	AIRFLOW (CFM)	EXTERNAL STATIC (IN H2O)	SONES	MOTOR DATA			RPM	MANUFACTURER	MODEL NUMBER	REMARKS
						FAN (HP)	VOLT	PH				
EF-3	ROOF	RESTROOMS	420	0.50	7.5	1/8	115	1	1,550	GREENHECK	G-095-D	[1-3]

REMARKS:
1. PROVIDE SOLID STATE SPEED CONTROL.
2. PROVIDE BACKDRAFT DAMPER.
3. PROVIDE MINIMUM 12 INCH HEIGHT ROOF CURB.

AIR SOURCE HEAT PUMPS													
MARK	LOCATION	SERVES	NOMINAL COOL (TONS)	HEATING AT 47°F (MBH)	ELECTRICAL			SEER /EER	HSPF /COP	MANUFACTURER	MODEL NUMBER	REMARKS	
					VOLT	PH	MCA						
ASHP-1	ROOF	FC-1	3/4	10.0	208	1	15.0	15	20.5/13.0	108/2.93	CARRIER	38MARB009	[1]

REMARKS:
1. PROVIDE EQUIPMENT WITH SCOR GREATER THAN THE AVAILABLE FAULT CURRENT AT THE EQUIPMENT OR UPSTREAM PANELBOARD. REFER TO THE ELECTRICAL ONE LINE DIAGRAM AND PANEL SCHEDULES FOR AVAILABLE FAULT CURRENT AT UPSTREAM PANELBOARD.

DUCTLESS SPLIT SYSTEMS													
MARK	NOMINAL (TONS)	COOLING		HEATING		SUPPLY AIR (CFM)	FAN (WATT)	ELECTRICAL			SEER /EER	CARRIER MODEL NUMBER	REMARKS
		TOT (MBH)	SEN (MBH)	OUT (MBH)	IN (MBH)			VOLT	PH	MCA			
FC-1	3/4	11.73	8.79	10.00	350	45	208	1	0.2	N/A	20.5/13.0	40MBC009	[1,2]

REMARKS:
1. PROVIDE CONDENSATE PUMP.
2. INDOOR UNIT POWER PROVIDED FROM OUTDOOR UNIT.


DIFFUSERS, GRILLES AND REGISTERS							
MARK	SERVICE	LOCATION	CEILING TYPE	MOUNTING TYPE	MANUFACTURER	MODEL NUMBER	REMARKS
D-1	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	PAR XX 24x24 3 26	[1,2,6]
D-2	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	TMS XX 24x24 3 26	[1,2,6]
D-3	SUPPLY	CEILING	GYP. BOARD	LAY-IN	TITUS	OMNI XX 12x12 3 26	[1,2,4,6]
D-4	SUPPLY	CEILING	GYP. BOARD	LAY-IN	TITUS	OMNI XX 24x24 3 26	[1,2,4,6]
D-5	SUPPLY	DUCT	NA	SURFACE	TITUS	300R X X 1 26	[1,5-7]
G-1	RETURN	CEILING	AC TILE	LAY-IN	TITUS	50F X X 3 26	[1,3,5,6]
G-2	EXHAUST	CEILING	GYP. BOARD	SURFACE	TITUS	50F X X 3 26	[1,3-5-7]
G-3	RETURN	CEILING	GYP. BOARD	SURFACE	TITUS	50F X X 1 26	[1,3-5-7]

REMARKS:
1. TITUS IS THE BASE OF DESIGN. KRUEGER, PRICE, NAILOR, CARNES ARE EQUAL. NO EXCEPTIONS.
2. SEE PLAN FOR NECK SIZE.
3. PROVIDE 1/2" X 1/2" X 1" CORE.
4. PROVIDE WITH MODEL TRM FRAME.
5. SEE PLAN FOR SIZE.
6. DIFFUSERS SHALL BE FINISHED TO MATCH CEILING/WALL/EXPOSED DUCT COLOR. COORDINATE WITH ARCHITECT.
7. PROVIDE DIFFUSERS AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.

AIR CURTAINS													
MARK	LENGTH (IN)	AIRFLOW (CFM)	HEATER		FANS		ELECTRICAL			MANUFACTURER	MODEL NUMBER	REMARKS	
			IN (KW)	OUT (MBH)	QTY	HP	CIRCUIT (QTY)	VOLT	PH				
AC-1	36.0	1,379	NA	NA	NA	1	1/2	1	115	1	MARS	STD236	[1-3]

REMARKS:
1. PROVIDE AUTOMATIC DOOR SWITCH.
2. PROVIDE UNIT MOUNTED CONTROL PANEL.
3. VERIFY FINAL COLOR/FINISH WITH ARCHITECT.

UV SYSTEMS												
UNIT NO.	PLACEMENT	PHI CELL MODEL #	UV/CELL SIZE	RANGE	INDOOR PPM TARGET	SIZE	TRANSFORMER	POWER	IN-VOLT	OUT-VOLT	MCA	WEIGHT (LBS.)
EX-RP-1	BLOWER CABINET	PHI-PKG14-24V	14"	3,000-8000 CFM	< 0.02 PPM	2.25"W x 19.5"L x 1.75"D	SHIP LOOSE	11W	115 VAC	24 VAC	0.50A	2 LBS
EX-RP-2	BLOWER CABINET	PHI-PKG14-24V	14"	3,000-8000 CFM	< 0.02 PPM	2.25"W x 19.5"L x 1.75"D	SHIP LOOSE	11W	115 VAC	24 VAC	0.50A	2 LBS



3 HOOD FASTENING DETAIL

NOT TO SCALE

zebra
ZEBRA PROJECTS, INC.
1664 N KIPLAND BLVD SUITE N500
SCOTTSDALE, ARIZONA 85254
PHONE: 480.912.1169 zbr-global

CONSULTANT LOGO

Schnackel
engineers
800-581-0963
www.schnackel.com
88 2088 210044

STORE NO: 1397

SHAKE SHACK
IRVINE SPECTRUM CENTER
5700 CALIFORNIA STREET
IRVINE, CALIFORNIA 92618

REVISION	
DATE	DESCRIPTION
08/28/22	REVISION A
11/29/22	REVISION E
02/17/23	REVISION 2

STATUS: IFC SET

PRELIMINARY:
Preliminary Documents Are for Design Review only and not intended for bidding, permitting, permitting or construction purposes. They were prepared by or under the supervision of Zebra Projects, Inc.

FIELD VERIFICATION:
The contractor shall verify all figured dimensions and location at the project site and notify Zebra Projects, Inc. of any dimensional errors, or omissions or discrepancies before beginning or fabricating any work. Do not make these

COPYRIGHT © 2023:
Zebra Projects, Inc. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, published or otherwise without the written consent of Zebra Projects, Inc.

SHEET NAME: MECHANICAL SCHEDULES

DATE: 01/16/23 PROJECT NO: 34286

DRAWN: RAS SCALE:

SHEET NO: M601