

SHEET NUMBER	SHEET NAME
M001	MECHANICAL ABBREVIATIONS AND SYMBOLS
M101	MECHANICAL FLOOR PLAN
M102	MECHANICAL REFRIGERANT PIPING LAYOUT PLAN
M150	MECHANICAL ROOF PLAN
M501	MECHANICAL DETAILS
M502	MECHANICAL DETAILS
M590	MECHANICAL SPECIFICATIONS
M591	MECHANICAL SPECIFICATIONS
M592	MECHANICAL SPECIFICATIONS
M601	MECHANICAL SCHEDULE
M701	CAPTIVEAIR DRAWINGS
M702	CAPTIVEAIR DRAWINGS
M703	CAPTIVEAIR DRAWINGS
M704	CAPTIVEAIR DRAWINGS
M705	CAPTIVEAIR DRAWINGS
M706	CAPTIVEAIR DRAWINGS
M707	CAPTIVEAIR DRAWINGS
M708	CAPTIVEAIR DRAWINGS
M709	CAPTIVEAIR DRAWINGS

RESPONSIBILITY MATRIX

THIS SCHEDULE IS PROVIDED FOR QUICK REFERENCE ONLY.
THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ALL WORK DESCRIBED IN THE CONSTRUCTION DOCUMENTS.
CONFLICTS BETWEEN THIS SCHEDULE AND THE REST OF THE CONTRACT DOCUMENTS SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION PRIOR TO BEGINNING WORK.

DESCRIPTION	FURNISHED			INSTALLED			REMARKS
	GENERAL CONTRACTOR	OWNER	LANDLORD	GENERAL CONTRACTOR	OWNER	LANDLORD	
DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING							
23.1 HVAC DUCTWORK AND PIPING IDENTIFICATION							
23.1.1 HVAC DUCTWORK SYSTEM IDENTIFICATION	X			X			
23.1.2 PIPING SYSTEM IDENTIFICATION	X			X			
23.1.3 UTILITY SHUT OFF IDENTIFICATION IN KITCHEN	X			X			
23.1.4 VALVE TAGS AND CHART	X			X			
23.1.5 HVAC DAMPER IDENTIFICATION	X			X			
23.2 ROOF CURBS							
23.2.1 EXHAUST FAN CURBS			X		X		SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.2 ROOFTOP UNIT CURBS			X		X		SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.3 CONDENSING UNIT CURBS	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.4 MAKE UP AIR UNIT CURBS			X		X		SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.5 KITCHEN EXHAUST FAN CURBS			X		X		SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.3 HVAC DUCTWORK SYSTEM COMPONENTS							
23.3.1 HVAC DUCTWORK	X			X			
23.3.2 INSULATION AND FIRE WRAP	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE TENANT FIT OUT FROM LANDLORD POINT OF CONNECTION
23.3.3 DAMPERS	X			X			
23.3.4 SMOKE DETECTORS	X			X			
23.3.5 SUPPLY, RETURN, AND EXHAUST GRILLS AND REGISTERS	X			X			
23.4 MECHANICAL PIPING SYSTEM COMPONENTS							
23.4.1 WALK-IN COOLER AND FREEZER REFRIGERATION			X		X		WALK-IN COOLER AND FREEZER SUPPLIED BY VENDOR NO. 103 GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE PIPING INSTALLATION AND FINAL CONNECTION
23.4.2 REFRIGERATION FOR OTHER HVAC EQUIPMENT	X			X			
23.4.3 CHILLED WATER	X			X			
23.4.4 CONDENSER WATER	X			X			
23.4.5 HEATING HOT WATER	X			X			
23.4.6 VALVES AND ACCESSORIES (E.G. AIR VENTS)	X			X			
23.5 HVAC EQUIPMENT							
23.5.1 SUPPLY FAN			X		X		
23.5.2 TOILET EXHAUST FAN	X			X			
23.5.3 KITCHEN EXHAUST FAN			X	X			SUPPLIED BY VENDOR NO. 102
23.5.4 DUCTED AND NON-DUCTED HEATING AND COOLING UNITS			X		X		
23.5.5 MAKE UP AIR UNITS			X		X		SUPPLIED BY VENDOR NO. 102
23.5.6 ELECTRIC PATIO HEATERS	X			X			
23.5.7 CONDENSING UNITS			X		X		
23.5.8 RGF PFI SYSTEM	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 7 VENDOR SUBSTITUTION IS NOT PERMITTED
23.6 KITCHEN EXHAUST WITH FIRE SUPPRESSION SYSTEM							
23.6.1 HOOD CONTROL PANEL			X		X		SUPPLIED BY VENDOR NO. 102
23.6.2 KITCHEN EXHAUST HOOD			X		X		SUPPLIED BY VENDOR NO. 102
23.6.3 STRUCTURAL SUPPORT			X		X		
23.6.4 ELECTRICAL AND CONTROL WIRING	X			X			
23.6.5 TANK SYSTEM			X		X		SUPPLIED BY VENDOR NO. 102 GENERAL CONTRACTOR TO COORDINATE AND FACILITATE SYSTEM SIGN-OFF
23.6.6 TANK WIRING AND UTILITIES CONNECTION	X			X			
23.6.7 TANK GAS VALVE			X		X		SUPPLIED BY VENDOR NO. 102
23.7 COMMISSIONING ACTIVITIES							
23.7.1 GREASE EXHAUST WATER LEAKAGE TEST	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 6 VENDOR SUBSTITUTION IS NOT PERMITTED
23.7.2 TESTING AIR BALANCE (TAB) REPORT	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 7 VENDOR SUBSTITUTION IS NOT PERMITTED

SUBMITTAL MATRIX

GENERAL CONTRACTORS TO ALSO REVIEW ARCHITECTURAL SPECIFICATIONS AS NOTED IN PLANS IN PLAN SECTION 700 OF THE ARCHITECTURAL PACKAGE FOR REQUIRED SUBMITTALS THAT MIGHT NOT BE LISTED BELOW.

SUBMITTAL DESCRIPTION	Required Before Time (Quarantee Day)	Architect of Record	Shake Shack	Physical Sample Required	Submitted for Record	Record Only
Anchor Bolts Shops	5	X			X	
ATAS-Detailed Shop DWGS(Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X			X	
Concrete Mix Design	5	X			X	
Construction Prefunctional Checklists	5	X			X	
Decorative Metal Shop Drawings	5	X			X	
Diffusers, Grills & Registers	5	X			X	
Doors, Frames & Hardware	7	X			X	
Ductwork Layout (if there are significant changes in field)	5	X			X	
Electrical Distribution Equipment	5	X			X	
Elevator & Vertical Transportation Shop Drawings	5	X			X	
Epoxy Floor	5	X			X	
Fire Alarm Shop Drawings & Device Cut Sheets	5	X			X	
Fire Sprinkler Shop Drawings, Hydraulic Calculations & Device Cut Sheets	5	X			X	
HVAC Equipment(if Carrier - Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X			X	
Light Fixtures(Submitted by Owner Vendor to Owner/AOR prior to construction)	5	X			X	
MEP Tests, Start-Up, and Programming Reports	5	X			X	
Millwork - Material Submittals (if differs from spec)	5	X	X	X		
Millwork - Shop Drawings (custom items & design features only)	5	X				
Restroom Partitions	5	X			X	
Plumbing Fixtures	5	X			X	
Rolling Shop Drawings	5	X				X
Rebar	5	X			X	
Stair Shop Drawings	5	X			X	
Structural Steel Shop Drawings	7	X			X	
Storefront - product data Submittal (if different from specified)	5	X				
Storefront - Shop Drawings	5	X				
Tile (if differs from spec)	5	X			X	
Window Film	5	X				

SYMBOLS

SYMBOL	DESCRIPTION
	THERMOSTAT
	REMOTE SENSOR
	SUPPLY DIFFUSER
	RETURN OR EXHAUST GRILLE
	SUPPLY OR FRESH AIR DUCT (SA OR FA)
	RETURN OR EXHAUST AIR DUCT (RA OR EA)
	RECTANGULAR DUCT FIRST FIGURE IS SIDE SHOWN
	ROUND DUCT
	VOLUME DAMPER (ELEV AND PLAN)
	TURNING VANES
	SUPPLY REGISTER OR GRILLE (R OR G)
	RETURN REGISTER OR GRILLE (R OR G)
	FRESH AIR INTAKE (FA)
	SQUARE CEILING DIFFUSER (SUPPLY)
	FAN COIL UNIT AND MARK
	MOTORIZED DAMPER
	REFRIGERANT LIQUID LINE
	REFRIGERANT SUCTION LINE

Bergmeyer

800 South Figueroa St.
Los Angeles, CA 90017
213.337.1090

875 N. High St.
Columbus, OH 43215
380.900.8867

Shepley St.
Boston, MA 02210
617.542.1025


www.bergmeyer.com

CONSULTANTS:



MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL SIGNATURE:



NO.	BY	DATE	DESCRIPTION
2		2024-07-02	FIELD NOTICE 1
1		2024-06-14	IFC
A		2024-05-07	ADDENDUM A
		2024-03-18	PERMIT / BID SET



NOVI, MI

43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605

PERMIT / BID SET


MECHANICAL
ABBREVIATIONS
& SYMBOLS

DRAWN BY: RS

CHECKED BY: GRS

JOB NO: 20230423.00

M001



- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E. BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODES. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOGON AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITE EXISTING FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILING. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE. IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ROOF MOUNTED EQUIPMENT SHALL BE LABELED WITH THE TENANT NAME AND SPACE NUMBER WITH 3" HIGH WEATHER PROOF LETTERS.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 98 AND ASTM E 2336 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB CONTACT WILL TURNBOURNE AT WILL@NATIONTAB.COM OR 314-954-8244.
 - PARTS OF THE BASE BUILDING SYSTEMS THAT FALL INTO LEASE LINE SHALL REMAIN UNDISTURBED UNLESS NOTED OTHERWISE.
 - PROVIDE ALL NECESSARY WIRING, RELAYS, DETECTORS, COMPONENTS, ETC., FOR FIRE ALARM OR CONTROL SYSTEM INTERLOCK IF APPLICABLE. VERIFY WITH BUILDING PERSONNEL BEFORE BID.
- HVAC NOTES:**
- RETURN GRILLE TO BE MOUNTED AS HIGH AS CONDITIONS ALLOW. COORDINATE EXACT INSTALLATION LOCATION WITH ARCHITECT AND CONSTRUCTION MANAGER. CONTRACTOR SHALL UNDERCUT DOOR 3/4"
 - PROVIDE 8/10 EXHAUST AIR DUCT UP TO EF-3 ON ROOF.
 - NEW CAPTIVEAIRE GREASE EXHAUST HOOD TO BE FURNISHED BY OWNER FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. SEE CAPTIVEAIRE SHEETS FOR ADDITIONAL INFORMATION. BALANCE HOOD EXHAUST AS NOTED ON CAPTIVEAIRE SHEETS. VERIFY WITH MANUFACTURER AND CODE REQUIRED CLEARANCES ARE MAINTAINED. NOTIFY ARCHITECT IF ANY CONFLICTS OCCUR.
 - TRANSITION FROM HOOD EXHAUST COLLAR AS INDICATED ON PLANS AND EXTEND KITCHEN HOOD GREASE EXHAUST DUCTWORK UP TO CORRESPONDING GREASE EXHAUST FAN ON ROOF AS INDICATED ON THE PLANS. SEE SHEET M100 FOR CONTINUATION. GREASE DUCT SHALL BE WRAPPED WITH TWO (2) LAYERS OF THERMAL CERAMIC FAST WRAP XL, 1 1/2" THICK WITH 3" PERIMETER AND LONGITUDINAL OVERLAPS OR EQUIVALENT UL-LISTED GREASE DUCT WRAP FOR ZERO CLEARANCE TO COMBUSTIBLES. REFER TO SHEET M501, DETAIL 2, FOR ADDITIONAL INFORMATION. TYPICAL OF GREASE DUCTWORK AS REQUIRED BY CODE. REFERENCE SHEET M501, DETAIL 1 FOR ADDITIONAL INFORMATION. TYPICAL OF GREASE EXHAUST DUCTWORK.
 - DUCTWORK TO BE TO BE INSTALLED AS HIGH AS CONDITIONS ALLOW. COORDINATE ROUTING AND MOUNTING HEIGHT WITH LIGHTING FIXTURES. NOTIFY THE ARCHITECTS OF ANY CONFLICTS AND COORDINATE WITH THE CONSTRUCTION MANAGER.
 - PROVIDE REMOTE VOLUME DAMPER AS INDICATED ON PLANS. REFERENCE SHEET M501, DETAIL 3, FOR ADDITIONAL INFORMATION. TYPICAL OF DIFFUSERS/GRILLES INSTALLED IN GYP. BOARD CEILING.
 - PROVIDE NEW FC UNIT AS NOTED ON PLANS AND AS SCHEDULED ON SHEET M601.
 - PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - HOOD MANUFACTURER TO PROVIDE A "KIT" TO FASTEN THE BOTTOM FLANGE OF THE HOOD TO THE WALL, WITH ONE FASTENER PER STUD WALL. SIL-BOND RTV 4500 ALUMINUM SILICONE SEALANT OR APPROVED SIMILAR, TO BE APPLIED BY GENERAL CONTRACTOR. HOOD INSTALLER FOR ANY REMAINING SMALL GAPS. HOOD FASTENING "KIT" DETAIL TO BE INCLUDED IN MANUFACTURER DRAWINGS. REFERENCE SHEET M501, DETAIL 11, FOR ADDITIONAL INFORMATION.
 - BALANCE THE DAMPER TO PROVIDE A MAXIMUM OF 30 CFM OF OUTDOOR AIR.
 - COORDINATE WITH CAPTIVEAIRE ON REMOTE SENSORS AND COMFORT CONTROLS PACKAGE THAT IS TO BE INSTALLED IN THE OFFICE. VERIFY CONTROLS ARE A FULLY DIGITAL 7 DAY PROGRAMMABLE TYPE THERMOSTAT WITH REMOTE SENSING CAPABILITIES, AUTO CHANGE OVER AND AUTO SET BACK. MOUNT SENSOR AND CONTROLS AT 48" ABOVE FINISHED FLOOR. UNITS SERVING THE SAME TEMPERATURE ZONE SHALL BE INTERLOCKED TO PREVENT SIMULTANEOUS HEATING AND COOLING. LOCATE REMOTE TEMPERATURE SENSORS AS INDICATED ON PLAN. COORDINATE LOCATION WITH CONSTRUCTION MANAGER AND WALL GRAPHICS LAYOUT. REFERENCE CAPTIVEAIRE SHEETS FOR ADDITIONAL INFORMATION.
 - DUCTWORK TO BE TO BE ROUTED FROM HIGH ROOF TO LOW ROOF. COORDINATE ROUTING AND MOUNTING HEIGHT WITH EXISTING CONDITIONS AND OTHER TRADES AS REQUIRED. NOTIFY THE ARCHITECT AND CONSTRUCTION MANGER OF ANY CONFLICTS.
 - VERIFY A MINIMUM 12/12 OR EQUIVALENT OPENING EXISTS ABOVE THE CEILING SPACE OF THE STORAGE AND UTILITIES AREA [109] TO ENCLOSED AREA WITH GLAZING.
 - OPEN END TRANSFER AIR DUCT. PROVIDE OPENING WITH 1/4" MESH GALVANIZED SCREEN.
 - PROVIDE FULL SIZE SUPPLY AIR DUCT DROP INTO SPACE. 20/10 BRANCH FOR HIGH ROOF DINING AREA TO CONNECT TO DROP BEFORE TRANSITIONING TO 22/10.

Bergmeyer

800 South Figueroa St.
Los Angeles, CA 90017
213.337.1090

875 N High St.
Columbus, OH 43215
614.542.1025
380.900.8867

CONSULTANTS:

Schnackel engineers

New York • Miami • Chicago • Los Angeles • Seattle • Honolulu
900-981-0863 www.schnackel.com

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL. 402.391.7680

SEAL SIGNATURE:

GREGORY SCHNACKEL
ENGINEER
No. 37570
Date: 07/02/24

2	2024-07-02	FIELD NOTICE 1	
1	2024-06-14	IFC	
A	2024-05-07	ADDENDUM A	
NO.	BY	DATE	DESCRIPTION

SHAKE SHACK

NOVI, MI

43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605

PERMIT / BID SET


MECHANICAL FLOOR PLAN

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 20230423.00

M101

1/4" = 1'-0"

1



- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E., BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACoustICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOGON AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACoustICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITE EMERTECH FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILING. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE. IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ROOF MOUNTED EQUIPMENT SHALL BE LABELED WITH THE TENANT NAME AND SPACE NUMBER WITH 3" HIGH WEATHER PROOF LETTERS.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2339 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURNE AT WILL@NATIONTAB.COM OR 314-954-6244.
 - PARTS OF THE BASE BUILDING SYSTEMS THAT FALL INTO LEASE LINE SHALL REMAIN UNDISTURBED UNLESS NOTED OTHERWISE.
 - PROVIDE ALL NECESSARY WIRING, RELAYS, DETECTORS, COMPONENTS, ETC., FOR FIRE ALARM OR CONTROL SYSTEM INTERLOCK IF APPLICABLE. VERIFY WITH BUILDING PERSONNEL BEFORE BID.

- HVAC NOTES:**
- PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 ABOVE KITCHEN OFFICE AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.
 - PROVIDE REFRIGERANT LINES FROM CONDENSING UNIT ON ROOF TO KITCHEN EQUIPMENT AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.

Bergmeyer

CONSULTANTS:

Schnackel engineers

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL. 402.391.7680

SEAL SIGNATURE:

GREGORY SCHNACKEL
ENGINEER
No. 37570
Date: 07/02/24

2	2024-07-02	FIELD NOTICE 1
1	2024-06-14	IFC
A	2024-05-07	ADDENDUM A
	2024-03-18	PERMIT / BID SET

SHAKE SHACK

NOVI, MI

43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605


PERMIT / BID SET

MECHANICAL REFRIGERANT PIPING LAYOUT PLAN

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 20230423.00

M102

16-2000-221188



- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS.
 - CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E., BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOGA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITE ENERGY FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILING. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE. IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ROOF MOUNTED EQUIPMENT SHALL BE LABELED WITH THE TENANT NAME AND SPACE NUMBER WITH 3" HIGH WEATHER PROOF LETTERS.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURNE AT WILL@NATIONTAB.COM OR 314-954-6244.
 - PARTS OF THE BASE BUILDING SYSTEMS THAT FALL INTO LEASE LINE SHALL REMAIN UNDISTURBED UNLESS NOTED OTHERWISE.
 - PROVIDE ALL NECESSARY WIRING, RELAYS, DETECTORS, COMPONENTS, ETC., FOR FIRE ALARM OR CONTROL SYSTEM INTERLOCK IF APPLICABLE. VERIFY WITH BUILDING PERSONNEL BEFORE BID.
- HVAC NOTES:**
- NEW CAPTIVE/RE RTU TO BE FURNISHED AND INSTALLED BY LANDLORD. SEE CAPTIVE/RE SHEETS FOR ADDITIONAL INFORMATION. FIELD VERIFY EXACT LOCATION.
 - NEW CAPTIVE/RE GREASE EXHAUST FAN TO BE FURNISHED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE CAPTIVE/RE SHEETS FOR ADDITIONAL INFORMATION. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE. CURB AN OPENING TO BE PROVIDED BY LANDLORD.
 - DUCT SMOKE DETECTOR ON SUPPLY SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
 - RFC ENVIRONMENTAL GROUP, INC. AIR PURIFICATION SYSTEM TO BE PROVIDED BY NAB. REFER TO RESPONSIBILITY MATRIX ON SHEET M001 FOR ADDITIONAL INFORMATION. SHEET M001 FOR SCHEDULE AND SHEET M002 FOR SPECIFICATIONS.
 - PROVIDE NEW EXHAUST FAN AS NOTED ON PLANS AND SCHEDULED ON SHEET M001. THE CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE. RE-USE EXISTING ROOF OPENING.
 - LANDLORD TO PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - PROVIDE REFRIGERANT LINES FROM KITCHEN EQUIPMENT CONDENSING UNITS ON ROOF TO UNITS IN THE KITCHEN SPACE AS INDICATED ON THE KITCHEN DRAWINGS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.

Bergmeyer

LA
CO
BOB

875 N High St.
Columbus, OH 43210
617.542.1025
380.900.8867

800 South Figueroa St.
Los Angeles, CA 90017
213.337.1090

www.bergmeyer.com

CONSULTANTS:

Schnackel
engineers

New York • Miami • Chicago • Los Angeles • Seattle • Honolulu
900-981-0963 www.schnackel.com

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL SIGNATURE:

2	2024-07-02	FIELD NOTICE 1
1	2024-06-14	IFC
A	2024-05-07	ADDENDUM A
	2024-03-18	PERMIT / BID SET

NO. BY DATE DESCRIPTION

SHAKE SHACK

NOVI, MI


43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605


PERMIT / BID SET

MECHANICAL
ROOF PLAN


DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 20230423.00

M150






9 FLEXIBLE DUCT SUPPORTS
NOT TO SCALE



10 CONDENSER REFRIGERANT LINE PIPING AND POWER THROUGH ROOF DECK
NOT TO SCALE



7 ROOF EXHAUST FAN DETAIL
NOT TO SCALE

DIA.	WIRE DIA.	ROD	STRAP
10" DN	ONE 12 GA.	1/4"	1" x 22 GA.
11-18"	TWO 12 GA. OR ONE 8 GA.	1/4"	1" x 22 GA.
19-24"	TWO 10 GA.	1/4"	1" x 22 GA.
25-36"	TWO 8 GA.	3/8"	1" x 20 GA.
37-50"	---	TWO 3/8"	TWO 1" x 20 GA.
51-60"	---	TWO 3/8"	TWO 1" x 18 GA.
61-84"	---	TWO 3/8"	TWO 1" x 18 GA.
85-96"	---	TWO 1/2"	TWO 1 1/2" x 16 GA.

NOTES:
1. STRAPS ARE GALVANIZED STEEL; RODS ARE UNCOATED OR GALVANIZED STEEL; WIRE IS BLACK ANNEALED, BRIGHT BASIC OR GALVANIZED STEEL. ALL ARE ALTERNATIVES.
2. TABLE ALLOWS FOR CONVENTIONAL WALL THICKNESS, AND JOINT SYSTEMS PLUS ONE LB/SF OF INSULATION WEIGHT. IF HEAVIER DUCTS ARE TO BE INSTALLED, ADJUST HANGER SIZES TO BE WITHIN THEIR LOAD LIMITS.


5 ROUND DUCT HANGER TABLE
NOT TO SCALE

MAXIMUM HALF OF DUCT PERIMETER	PAIR AT 10 FT. SPACING		PAIR AT 8 FT. SPACING		PAIR AT 5 FT. SPACING		PAIR AT 4 FT. SPACING	
	STRAP	WIRE/ROD	STRAP	WIRE/ROD	STRAP	WIRE/ROD	STRAP	WIRE/ROD
P/2 = 30"	1" x 22 GA.	10 GA. (.135")	1" x 22 GA.	10 GA. (.135")	1" x 22 GA.	12 GA. (.106")	1" x 22 GA.	12 GA. (.106")
P/2 = 72"	1" x 18 GA.	3/8"	1" x 20 GA.	1/4"	1" x 22 GA.	1/4"	1" x 22 GA.	1/4"
P/2 = 96"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"	1" x 20 GA.	3/8"	1" x 22 GA.	1/4"
P/2 = 120"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"	1" x 20 GA.	1/4"
P/2 = 168"	1 1/2" x 16 GA.	1/2"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"
P/2 = 192"	---	1/2"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 16 GA.	3/8"
P/2 = 193" UP	SPECIAL ANALYSIS REQUIRED							

WHEN STRAPS ARE LAP JOINED USE THESE MINIMUM FASTENERS:	SINGLE HANGER MAXIMUM ALLOWABLE LOAD	
	STRAP	WIRE OR ROD (DIA.)
1" x 18, 20, 22 GA. - TWO #10 OR ONE 1/4" BOLT	1" x 22 GA. - 260 LBS.	0.106" - 80 LBS.
1" x 16 GA. - TWO 1/4" DIA.	1" x 20 GA. - 320 LBS.	0.135" - 120 LBS.
1" x 16 GA. - TWO 3/8" DIA.	1" x 18 GA. - 420 LBS.	0.162" - 160 LBS.
PLACE FASTENERS IN SERIES, NOT SIDE BY SIDE.	1/4" - 270 LBS.	3/8" - 680 LBS.
	1" x 16 GA. - 700 LBS.	1/2" - 1250 LBS.
	1 1/2" x 16 GA. - 1100 LBS.	5/8" - 2000 LBS.
		3/4" - 3000 LBS.


NOTES:
1. DIMENSIONS OTHER THAN GAUGE ARE IN INCHES.
2. TABLES ALLOW FOR DUCT WEIGHT, 1 LB./SF INSULATION WEIGHT AND NORMAL REINFORCEMENT AND TRAPEZE WEIGHT, BUT NO EXTERNAL LOADS.
3. STRAPS ARE GALVANIZED STEEL; OTHER MATERIALS ARE UNCOATED STEEL.
4. ALLOWABLE LOADS FOR P/2 ASSUME THAT DUCTS ARE 16 GA. MAXIMUM, EXCEPT THAT WHEN MAXIMUM DUCT DIMENSION (W) IS OVER 60" THEN P/2 MAXIMUM IS 1.25 W.
5. 12, 10 OR 8 GA. WIRE IS STEEL OF BLACK ANNEALED, BRIGHT BASIC OR GALVANIZED TYPE.
6. DUCTS SHALL BE SUPPORTED AT INTERVALS NOT EXCEEDING 10 FEET.

8 RECTANGULAR DUCT HANGER TABLE
NOT TO SCALE




1 KITCHEN HOOD EXHAUST FAN
NOT TO SCALE

- NOTES:
1. THERMAL CERAMICS FIREMASTER FASTWRAP XL IS TESTED TO ASTM E2336 AND UL LISTED PER WIKI016 TO PROVIDE ZERO CLEARANCE TO COMBUSTIBLES AND TO PROVIDE A 1 OR 2 HOUR EXPOSURE THROUGH PENETRATIONS FIRESTOP SYSTEMS ARE TESTED IN ACCORDANCE WITH ASTM E 814 (UL 1479). ICC-ES APPROVAL PER REPORT ESR 2213 OR ESI 2835.
2. COMPLIANT TO THE FOLLOWING CODES:
NFPA 96
INTERNATIONAL MECHANICAL CODES
UNIFORM MECHANICAL CODE
CALIFORNIA MECHANICAL CODE
3. INSULATION APPLIED IN TWO LAYERS WITH TIGHT COMPRESSION JOINT ON BOTH LAYERS AT ALL JOINTS.
4. MINIMUM 16 GAUGE CARBON STEEL (OR 18 GAUGE STAINLESS STEEL) RECTANGULAR OR ROUND GREASE EXHAUST DUCT.
5. INSTALL UL LISTED AND LIQUID TIGHT THERMAL CERAMICS FASTDOOR XL ACCESS DOORS AT ALL CHANGES IN DIRECTION AND AT MINIMUM EVERY 20 FT ON HORIZONTAL RUNS.
6. SUPPORT HANGER SYSTEMS DO NOT NEED TO BE WRAPPED PROVIDED THE HANGER RODS ARE MINIMUM OF 3/8" IN. DIAMETER AND SUPPORTS ARE MINIMUM 2 2 x 1/8 IN. STEEL ANGLE OR SMAWVA EQUIVALENT SUPPORT SYSTEM.
7. THERMAL CERAMICS DUCT WRAP SHALL BE INSTALLED DIRECTLY ONTO THE DUCT AND APPLIED FROM THE HOOD CONNECTION TO THE CONNECTION OF THE FAN.
8. THERMAL CERAMICS DUCT ENCLOSURE SYSTEM SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS AND UL LISTINGS.




** DETAIL COURTESY OF MORGAN THERMAL CERAMICS.

2 FIREMASTER FASTWRAP XL DETAIL
NOT TO SCALE




NOTE: HANGERS MUST NOT DEFORM DUCT SHAPE

6 DUCT HANGER DETAIL
NOT TO SCALE



3 REMOTE VOLUME DAMPER CONTROLLER
NOT TO SCALE



4 EXPOSED RECTANGULAR DUCT SUPPORT DETAIL
NOT TO SCALE

11 HOOD FASTENING DETAIL
NOT TO SCALE

Bergmeyer

800 South Figueroa St.
Columbus, OH 43215
380.900.8887

875 N. High St.
Columbus, OH 43215
617.542.1025

www.bergmeyer.com

CONSULTANTS:

Schnackel engineers

New York • Miami • Chicago • Los Angeles • Seattle • Houston
900-981-0863 www.schnackel.com

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL SIGNATURE:

STATE OF MICHIGAN
GREGORY SCHNACKEL
ENGINEER
No. 37570
Date: 07/02/24

NO.	BY	DATE	DESCRIPTION
2		2024-07-02	FIELD NOTICE 1
1		2024-06-14	IFC
A		2024-05-07	ADDENDUM A
		2024-03-18	PERMIT / BID SET

SHAKE SHACK

NOVI, MI


43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605

PERMIT / BID SET


MECHANICAL DETAILS

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 20230423.00


M501




8 DUCTWORK DETAILS
NOT TO SCALE




5 DUCT SMOKE DETECTOR DETAIL
NOT TO SCALE




1 TYPICAL DRYWALL MOUNTING FRAME DETAIL
NOT TO SCALE




6 TYPICAL ROOF TOP UNIT DETAIL
NOT TO SCALE




7 TYPICAL ROOF TOP UNIT TEE CONNECTION
NOT TO SCALE



2 TYPICAL DIFFUSER CONNECTION
NOT TO SCALE



3 TYPICAL ROUND DUCT FITTINGS
NOT TO SCALE



4 CURB FLASHING DETAIL
NOT TO SCALE

Bergmeyer
 800 South Figueroa St.
 Los Angeles, CA 90017
 213.337.1090
 875 N High St.
 Columbus, OH 43210
 614.542.1025
 380.900.8867
 www.bergmeyer.com

CONSULTANTS:
Schnackel engineers
 New York • Miami • Chicago • Los Angeles • Seattle • Honolulu
 900-981-0963 www.schnackel.com

MEPF ENGINEER
 3035 S 72ND ST
 OMAHA NE 68124
 TEL 402.391.7680

SEAL SIGNATURE:

 GREGORY SCHNACKEL
 ENGINEER
 No. 37570
 Date: 07/02/24

2	2024-07-02	FIELD NOTICE 1	
1	2024-06-14	IFC	
A	2024-05-07	ADDENDUM A	
	2024-03-18	PERMIT / BID SET	
NO.	BY	DATE	DESCRIPTION

SHAKE SHACK

NOVI, MI
 43335 CRESCENT BLVD.
 NOVI TOWN, MI 48375
 SHACK #1605

PERMIT / BID SET

MECHANICAL DETAILS

DRAWN BY: RAS
 CHECKED BY: GRS
 JOB NO: 20230423.00

M502

SECTION 230800 - COMMISSIONING HVAC

PART 1 GENERAL

- 1.01 SUMMARY
A. Section 01 9113 - General Commissioning Requirements for overall objectives; comply with the requirements of Section 01 9113.
B. This section covers the Contractor's responsibilities for commissioning, each subcontractor or installer responsible for the installation of a particular system or equipment item to be commissioned is responsible for the commissioning activities relating to that system or equipment item.
C. The Commissioning Authority (CA) directs and coordinates all commissioning activities and provides Pre-Functional Checklists and Functional Test Procedures for Contractor's use.
D. The entire HVAC system is to be commissioned, including commissioning activities for the following specific items:
1. Control system.
2. Major and minor equipment items.
3. Piping systems and equipment.
4. Ductwork and accessories.
5. Terminal units.
6. Sound control devices.
7. Vibration control devices.
8. Variable frequency drives.
9. Special Ventilation: Hoods, pressurization, exhaust, etc.
10. Other equipment and systems explicitly identified elsewhere in Contract Documents as requiring commissioning.
11. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; Contractor will execute; see Section 01 5710.
E. The Pre-Functional Checklist and Functional Test requirements specified in this section are in addition to, not a substitute for, inspection or testing specified in other sections.
1.02 RELATED REQUIREMENTS
A. Section 23 0993 - Sequence of Operations for HVAC Controls.
B. Section 23 0993 - Testing, Adjusting, and Balancing for HVAC Controls.
1.03 REFERENCE STANDARDS
A. ASHRAE Guideline 1.1 - The HVAC Commissioning Process, 2012.
1.04 SUBMITTALS
A. Updated Submittals: Keep the Commissioning Authority informed of all changes to control system documentation made during programming and setting and resubmit when substantial changes are made.
B. DRAFT Pre-Functional Checklists and Functional Test Procedures for Control System: Detailed written plan indicating the procedures to be followed to test, check-out and adjust the control system packages and power-up restart functions.
C. Startup Reports, Pre-Functional Checklists, and Trend Logs: Submit for approval of Commissioning Authority.
D. HVAC Control System O&M Manual Requirements: In addition to documentation specified elsewhere, complete and organize the following data on the control system:
1. Specific step-by-step instructions on how to perform and apply all functions, features, modes, etc. mentioned in the controls training sessions with the specification and other features of this system. Provide an index and clear description of contents, including a detailed technical manual for programming and customizing control loops and algorithms.
2. Full as-built set of drawings.
3. Full as-built sequence of operations for each piece of equipment.
4. Full points list; in addition to the points on the original points list submitted, include a listing of all rooms with the following information for each room:
a. Floor.
b. Room number.
c. Air handler unit ID.
d. Reference device number.
e. Air terminal unit tag ID.
f. Heating and/or cooling valve tag ID.
g. Minimum air flow.
h. Maximum air flow rate.
5. Full as-built print out of software program.
6. Electronic copy on disk of the entire program for this facility.
7. Marking of all system sensors and thermostats on the as-built floor plan and HVAC drawings with their control system design and manufacturer's part numbers.
8. Maintenance instructions, including sensor calibration requirements and methods by which to calibrate sensors.
9. Control equipment component submittals, parts lists, etc.
10. Warranty requirements.
11. Copies of all check-out tests and calibrations performed by the Contractor (not commissioning tests).
12. Check-out and submittal manual with permanently labeled tabs for each of the following data in the given order:
a. Sequence of operation.
b. Control drawings.
c. Points lists.
d. Controller and/or module data.
e. Thermostats and timers.
f. Sensors and DP switches.
g. Valves and valve actuators.
h. Dampers and damper actuators.
i. Program setups (software program prints).
E. Project Record Documents
1. Submit updated version of control system documentation, for inclusion with operation and maintenance data.
2. Show actual locations of all static and differential pressure sensors (air, water and building pressure) and air-flow stations on project record drawings.
F. Draft Training Plan
1. Follow the recommendations of ASHRAE Guideline 1.1.
2. Control system manufacturer's recommended training.
3. Demonstrate and instruct on function and overrides of any local packaged controls not controlled by the HVAC control system.
G. Training Manuals
1. Provide three extra copies of the controls training manuals in a separate manual from the O&M manuals.
2. Submittals are reviewed for general compliance with the Contract Documents. Dimensions, quantities and details are not checked during submittal review. Review of the submittals does not relieve the Contractor of the responsibility for providing all materials, equipment and accessories necessary for a complete, energy efficient and operational system meeting the requirements of the project and the intent of the Contract Documents. The responsibility for providing substituted materials and equipment lies solely with the substituting Contractor.
PART 2 PRODUCTS
2.01 TEST EQUIPMENT
A. Provide all standard testing equipment required to perform startup and initial check-out and required functional performance testing; unless otherwise noted such testing equipment will NOT become the property of Owner.
B. Equipment-Specific Tools: Where specific testing, adjusting, and balancing tools are specific to a piece of equipment, are only available from the vendor, and are required in order to accomplish startup and functional testing, provide such equipment, tools, and instruments as part of the work at no extra cost to Owner; such equipment, tools, and instruments are to become the property of Owner.
PART 3 EXECUTION
3.01 PREPARATION
A. Cooperate with the Commissioning Authority in development of the Pre-Functional Checklists and Functional Test Procedures.
B. Furnish additional information requested by the Commissioning Authority.
C. Prepare a preliminary schedule for HVAC pipe and duct system testing, flushing and cleaning, equipment start-up and testing, adjusting, and balancing start and completion for use by the Commissioning Authority; update the schedule as appropriate.
D. Notify the Commissioning Authority when pipe and duct system testing, flushing, cleaning, startup of each piece of equipment and testing, adjusting, and balancing will occur; when commissioning activities not yet performed or not yet scheduled will delay construction ahead of time and be proactive in seeing that the Commissioning Authority has the scheduling information needed to efficiently execute the commissioning process.
E. Put all HVAC equipment and systems into operation and continue operation during each working day of testing, adjusting, and balancing and commissioning, as required.
1. Include cost of shaves and belts that may be required for testing, adjusting, and balancing.
2. Provide test holes in ducts and plenums where directed to allow air measurements and balancing.
3. Provide temperature and pressure taps in accordance with the Contract Documents.
3.02 INSPECTING AND TESTING
A. Submit startup plans, startup reports, and Pre-Functional Checklists for each item of equipment or other assembly to be commissioned.
B. Perform the Functional Tests in accordance with the Commissioning Authority for each item of equipment or other assembly to be commissioned.
C. Provide two-way radio for use during the testing.
D. Valve/Damper Stroke Setup and Check:
1. For all valves/damper actuators:
a. Heilions checked, verify the actual position against the control system setting.
b. Set pump/fan to normal operating mode.
c. Command valve/damper closed; visually verify that valve/damper is closed and adjust output zero signal as required.
d. Command valve/damper to full open position; visually verify that valve/damper is fully open and adjust output signal as required.
e. Verify proper operation of Normally Open or Normally closed positions of all valves/dampers by means of normal operating mode tests plus removal of power to confirm proper closure or opening upon failure of power or control signal.
f. Verify valve/damper leakage testing on all dampers by applying normal operating pressure with the valve/damper in the closed position and measure either the delta P or the system static pressure; if the delta P or the static pressure compliance with specification requirements for dampers and zero leakage for valves.
g. If actual valve/damper position does not reasonably correspond, replace output actuator.
h. Deficiencies: Correct deficiencies and re-inspect or re-test, as applicable, at no extra cost to Owner.
3.03 TAB COORDINATION
A. TAB: Testing, adjusting, and balancing of HVAC.
B. Coordinate the commissioning schedule with TAB schedule.
C. Review the TAB plan to determine the capabilities of the control system toward completing TAB.
D. Provide necessary unique instruments and instruct the TAB technicians in their use; such as handheld control system interface for setting terminal unit boxes, etc.

- E. Have all required Pre-Functional Checklists, calibrations, startup and component functional tests of the system completed and approved by the Commissioning Authority prior to starting TAB.
F. Provide a qualified control system technician to operate the controls to assist the TAB technicians or provide sufficient training for the TAB technicians to operate the system without assistance.
3.04 CONTROL SYSTEM FUNCTIONAL TESTING
A. Pre-Functional Checklists for control system components will require a signed and dated certification that all system programming is complete as required to accomplish the requirements of the Contract Documents and the detailed Sequences of Operation.
B. Do not start Functional Testing until all controlled components have themselves been successfully Functionally Tested in accordance with the Contract Documents.
C. The Commissioning Authority (CA) familiar with this building, execute the Functional Testing of the control system as required by the Commissioning Authority.
D. Functional Testing of the control system constitutes demonstration and trend logging of control points monitored by the control system.
1. The scope of trend logging is partially specified; trend log up to 50 percent more points than specified at no extra cost to Owner.
2. Perform all trend logging specified in Pre-Functional Checklists and Functional Test procedures.
E. Functionally Test integral or stand-alone controls in conjunction with the Functional Tests of the equipment they are attached to, including any interlocks and safety equipment or systems; further testing during control system Functional Test is not required unless specifically indicated below.
F. Demonstrate the following to the Commissioning Authority during testing of controlled equipment, coordinate with commissioning of equipment.
1. Setpoint changing features and functions.
2. Sensor calibrations.
G. Demonstrate to the Commissioning Authority:
1. That all specified functions and features are set up, debugged and fully operable.
2. That scheduling features are fully functional and setup, including holidays.
3. That all graphic screens and video displays are complete.
4. Correct date and time setting in control computer.
5. Percent field points ready for the same or similar control, complete 10 percent of field points; if any of those fail, sample another 10 percent; if any of those fail, test all remaining units at no extra cost to Owner.
6. Functionality of field points using local operator keypads and local ports (plug-ins) with portable computer/keypad; demonstrate 100 percent of points of those 10 percent ports; if any of those fail, sample another 10 percent; if any of those fail, test all remaining units at no extra cost to Owner.
7. Control System Diagrams: Submit graphic schematic of the control system showing each control component and each component controlled, monitored, or enabled.
8. Label with settings, adjustable range of control and limits.
9. Occupant over-rides (manual, telephone, key, keypad, etc.).
10. O&M schedules and alarms.
11. Occupancy sensors and controls.
12. "After hours" use tracking and billing.
13. Fire alarm interlocks and response.
14. Fire protection and suppression systems interfaces.
15. Security system interfaces.
16. That points that are monitored only, having no control function, are controlled by the control system.
17. All control strategies and sequences not tested during controlled equipment testing.
18. Trend logging and graphing features that are specified.
19. Other integrated tests specified in the Contract Documents.
20. That control system features that are included but not specified to be setup are actually installed.
H. Perform and submit trend logging on the following using the control system, for minimum period of 5 days including one weekend, if the control points are monitored by the control system:
1. Duty cycling, if specified.
2. Demand limiting, including over-ride of limiting.
3. Sequential staging ON of equipment; optionally demonstrate manually.
4. Optimum start-stop functions.
5. Miscellaneous equipment current or status for duty cycling and demand limiting.
6. Equipment or building kW or current for demand limiting.
7. Equipment optimum start/stop functions.
I. If the control system, integral controls, or related equipment do not respond to changing conditions and parameters appropriately as expected, as specified and according to acceptable operating practice, under any of the conditions, sequences, or parameters tested, correct all systems, equipment, components, and software required at no additional cost to Owner.
3.05 OPERATION AND MAINTENANCE MANUALS
A. Add design intent documentation furnished by Engineer to manuals prior to submission to Owner.
B. Submit manuals related to items that were commissioned to Commissioning Authority for review; make changes recommended by Commissioning Authority.
C. Commissioning Authority will add commissioning records to manuals after submission to Owner.
3.06 DEMONSTRATION AND TRAINING
A. Demonstrate operation and maintenance of HVAC system to Owner personnel; if during any demonstration, the system fails to perform, duct runs, diffusers, coils, fans and pumps that are close to or are not meeting their design capacity.
B. Discuss any temporary settings and steps to finalize them for any areas that are not finished.
C. Other pertinent information that may be useful for facility operations, relative to TAB.
F. HVAC Control System Training: Perform training in at least three phases:
1. Basic Control System: Provide minimum of 16 hours of actual training on the control system itself. Upon completion of training, each attendee, using appropriate control system, should be able to perform elementary operations and describe general hardware architecture and functionality of the system.
2. This training may be held on-site or at the manufacturer's facility.
3. If held off-site, the training may occur prior to final completion of the system installed building exhaust fans.
c. For off-site training, Contractor shall pay expenses of up to two attendees.
2. Phase 2 - Integrating with HVAC systems: Provide minimum of 16 hours of on-site, hands-on training after completion of Functional Testing. Include the following:
a. The specific hardware configuration of installed systems in this facility and specific instruction for operating the installed system, including interfaces with other systems, if any.
b. Security levels, alarms, system start-up, shut-down, power outage and restart routines, changing setpoints and alarms and other typical changed parameters, overrides, freeze protection, manual operation of equipment, optional control strategies that can be considered, energy savings strategies and set points that, if changed will adversely affect the system.
c. Troubleshooting procedures for obtaining vendor assistance, etc.
d. Trend logging and monitoring features (values, change of state, totalization, etc.), including setting up, executing, downloading, viewing both tabular and graphically and printing trends; provide procedures in setting up trend logging and monitoring during training session.
e. Use of keypad or plug-in laptop computer at the zone level.
f. Use of remote access to the system via phone lines or networks.
g. Setting up and changing an air terminal unit controller.
h. Graphics generation.
i. Point determine entry and modifications.
j. Understanding DDC field panel operating programming, when applicable.
3. Phase 3 - Post-Occupancy: Six months after occupancy conduct minimum hours of training. Tailor training session to questions and topics sought out beforehand from Owner. Also be prepared to address technical questions and answer questions concerning operation of the system.
G. Provide the services of manufacturer representatives to assist instructors where necessary.
H. Provide the services of the HVAC controls instructor at other training sessions, when requested, to discuss the interaction of the controls system as it relates to the equipment being discussed.
END OF SECTION
SECTION 230993 - SEQUENCE OF OPERATIONS FOR HVAC CONTROLS
PART 1 GENERAL
1.01 SECTION INCLUDES
A. This Section defines the manner and method by which controls function.
B. Requirements for each type of control system operation are specified. Equipment, devices, and system components required for control systems are specified in other sections.
C. This Section provides the intended sequence of operation for each piece of controlled equipment. Other Sections in this Specification indicate the requirements for direct digital control systems, energy management systems, packaged factory controls or conventional analog control systems. Equipment, devices, and system components required for a complete, functional system for all other Sections.
D. Wherever the sequences contained herein indicate control by a thermostat or EMS sensor/controller, the Temperature Control Contractor shall furnish EMS sensor/controller for direct digital control systems or a thermostat for conventional analog control systems as specified in other sections of this Specification.
E. Sequence of operation:
1. Fan coil units.
a. Heat pump heating/cooling.
b. Automatic chgover.
c. Variable speed supply fan.
d. Exhaust fans.
e. General duty building exhaust fans.
f. Single Zone Systems.
g. Control of package HVAC equipment containing factory mounted controls.
h. Heat pump systems.
i. Heat pump unit controls.
1.02 RELATED REQUIREMENTS
A. Section 23 0913 - Instrumentation and Control Devices for HVAC.
1.03 SYSTEM DESCRIPTION
A. Equipment performance, controls and accessories shall be as scheduled on the Drawings and specified herein. Inclusion in both locations is not a prerequisite to inclusion in the Contract. Equipment, controls and accessories specified in either location shall be included in the Contract. Provide all necessary controls, accessories and connections as required for a complete, functional system for all systems indicated on the Drawings.
B. All wiring of control systems including connections to controlled devices external to the control systems shall be included in the temperature controls contract as a part of the Mechanical Contractor will not include the wiring of control system connections to devices at the locations indicated on the Electrical Drawings.
C. Provide the Electrical Drawings for locations where power connections will be provided.
D. Refrigerant Charging (Packed Angle) Valve: Use in liquid line between receiver shut-off valve and expansion valve.
E. Filter-Driers:
1. Use a filter-drier immediately ahead of liquid-line controls, such as thermostatic expansion valves, solenoid valves and moisture indicators.
2. Use a filter-drier on suction line just ahead of compressor.
1.03 REGULATORY REQUIREMENTS

- required by applicable local and national codes. Other locations may be installed utilizing pleated rated coaling without condit; provided that all coaling is neatly and adequately supported independent of all other systems, equipment, ductwork, etc. Where cases exist, all wiring shall utilize the cable tray path, except at direct run outs to equipment or control connections.
D. All control settings and set points shall be individually adjustable. Set points specified in this Section shall be used as a guide for initial setup and may require subsequent adjustment to achieve the desired system functionality and performance.
1.04 SUBMITTALS
A. Sequence of Operation Documentation: Submit written sequence of operation for entire HVAC system and each piece of equipment.
1. Preface: 1 or 2 paragraph overview narrative of the system describing its purpose, components and function.
2. State each sequence in small segments and give each segment a unique number for reference in Functional Test procedures; provide a complete description regardless of the completeness and clarity of the sequences specified in the Contract Documents.
3. Include at least the following sequences:
a. Start-up.
b. Warm-up mode.
c. Normal operating mode.
d. Unoccupied mode.
e. Shutdown.
f. Capacity control sequences and equipment staging.
g. Temperature and pressure control, such as setbacks, setps, resets, etc.
h. Detailed sequences for all control strategies, such as economizer control, optimum start/stop, staging, optimization, demand limiting, etc.
i. Effects of power or equipment failure with all standby component functions.
j. Sequences for all alarms and emergency shut down.
k. Seasonal operational differences and recommendations.
l. Interactions and interlocks with other systems.
4. Include initial and recommended values for all adjustable settings, setpoints and parameters that are typically set or adjusted by operating staff; and any other control settings or fixed values, delays, etc. that will be useful during testing and operating the equipment.
5. For packaged controlled equipment, include manufacturer's furnished sequence of operation amplified as required to describe the relationship between the packaged controls and the control system, indicating which points are adjustable control settings and which points are not relationship.
B. Control System Diagrams: Submit graphic schematic of the control system showing each control component and each component controlled, monitored, or enabled.
2. Include flow diagrams for each control system, graphically depicting control logic.
3. Include the system and component layout of all equipment that the control system monitors, enables or controls, even if the equipment is primarily controlled by packaged or integral controls.
4. Include draft copies of graphic displays indicating mechanical system status, control system components, and controlled function status and value.
5. Include all monitoring, control and virtual points specified in elsewhere.
6. Provide a key to all abbreviations.
C. Points List: Submit list of all control points indicating at least the following for each point:
1. Name of controlled system.
2. Point abbreviation.
3. Point description; such as dry bulb temperature, airflow, etc.
4. Display unit.
5. Control point or setpoint (Yes / No); i.e. a point that controls equipment and can have its setpoint changed.
6. Monitoring point (Yes / No); i.e. a point that does not control or contribute to the control of equipment but is used for operation, maintenance, or performance verification.
7. Intermediate point (Yes / No); i.e. a point whose value is used to make a calculation which then controls equipment, such as space temperatures that are averaged to a virtual point or control reset.
8. Calculated point (Yes / No); i.e. a "virtual" point generated from calculation of other point values.
9. Project Record Documents: Record actual locations of components and setpoints of controls, including changes to records after owner submission of stop drawings.
1.05 QUALITY ASSURANCE
A. Design system under direct supervision of a Professional Engineer experienced in design of this work and licensed at the State in which the Project is located.
B. Code or utility company requirements shall supersede any conflicting requirements of this Section.
PART 2 PRODUCTS - NOT USED
3.01 FAN COIL UNITS
A. Time Schedule: Control fan coil units based on the programmed time schedule as determined by the Owner's operating personnel. Provide occupie/unoccupied mode control with night setback of temperatures, where applicable.
B. Supply fan shall run continuously during the occupied period and cycle during the unoccupied period based on a demand for heating or cooling.
C. Provide automatic change over from heating to cooling based on room demand.
D. Provide automatic change over from heating to cooling based on room demand.
E. Provide automatic change over from heating to cooling based on room demand.
F. Outside, Return, and Relief Dampers:
1. When supply fan is not running, outside and relief dampers are closed and return damper is open.
2. When supply fan is running, dampers are controlled and operate with outside and relief dampers opening, and return damper closing.
3. For cooling, and outside air temperatures below 55 degrees F (12 degrees C), modulate dampers to maintain mixed air temperature of 55 degrees F (12 degrees C).
4. For cooling and outside air temperatures above 55 degrees F (12 degrees C) drive outside damper to minimum, close relief damper, and open return damper.
5. For outside air temperatures above 79 degrees F (26 degrees C), drive outside damper to minimum, close relief damper, and open return damper.
6. For heating, drive outside damper to minimum, close relief damper, and open return damper.
7. Minimum outside air position shall be as determined by the demand controlled ventilation control specified below (if any), or outside air quantity as indicated on the Drawings.
8. Close outside air damper in unoccupied mode, unless there is a call for cooling and the outside air enthalpy is below the return air enthalpy.
9. Freeze Protection: Stop fans and close outside air dampers and open heating coil valves (if any) to 100K opf (except pre-heat coils) below 37 degrees F (3 degrees C).
3.02 EXHAUST FANS
A. General building exhaust fans
1. Time Schedule: Start and stop exhaust fan based on the programmed time schedule as determined by the Owner's operating personnel.
2. Specific purpose exhaust fans shall be interlocked with the respective equipment as indicated on the Drawings. Provide necessary sensors and relays to allow control system to accurately sense equipment operation and provide fan system accordingly. Interlock make up air units/fans and air handling systems providing make up air for exhaust systems as required to provide 100K make up air to all operating exhaust fans.
A. Single Zone Systems
1. Time Schedule: Control HVAC equipment based on the programmed time schedule as determined by the Owner's operating personnel. Provide occupie/unoccupied mode control with adjustable night setback of temperatures, where applicable.
2. Maintain the integrity of the packaged control equipment and sequences. The packaged unit controls shall operate such functions as the economizer, operations, burner modulation, high limit and low limit safeties, etc. All setpoint, occupancy, staging and shut-down capabilities shall be controlled by the temperature control system.
3. The control system shall monitor and indicate at the operators console the status of the unit including:
a. System on/off status.
b. System on/off command status.
c. Supply fan status (if present).
d. Return fan status (if present).
e. System operating mode (heating/cooling/ventilation).
f. Pressure Rating: -10 degrees F to 175 degrees F.
g. Discharge air temperature setpoint (where applicable).
h. Discharge air temperature setpoint (where applicable).
i. Outdoor air temperature and humidity.
j. Return air temperature and humidity.
k. Space temperature (where applicable).
l. Compressor status, individually by compressor.
4. Control system shall be able to control any of the following functions:
a. Turn the system on or off.
b. Control the number of stages of heating or cooling to be utilized based on room or duct temperature conditions.
c. Change equipment or unoccupied temperature setpoints.
d. Modify occupancy schedules by unit.
3.04 HEAT PUMP SYSTEMS
A. Heat Pump Unit Controls: Control system for the individual heat pump units shall be furnished by the equipment manufacturer. The program clock or energy management functions listed below must be integrated with the packaged controls furnished by the heat pump manufacturer. During the unoccupied mode, as indicated by the program clock or EMS controller, the unit shall provide heating and cooling functions as specified by the unit manufacturer. During the unoccupied mode, the unit shall provide heating only if the night setback temperature set by the room set/back thermostat or EMS sensor/controller. Heat pump control (heat, cool, occupied, unoccupied) shall be individually addressable for each heat pump unit. Heat pump supply fans shall run continuously during the occupied mode. This feature shall be individually programmable for each heat pump.
B. Automatic Start Capabilities: Controls shall be capable of automatically adjusting the duty start time of the HVAC system in order to bring each space to the desired occupied temperature immediately prior to scheduled occupancy.
END OF SECTION
SECTION 232300 - REFRIGERANT PIPING
PART 1 GENERAL
1.01 SECTION INCLUDES
A. Piping.
B. Refrigerant.
C. Moisture and liquid indicators.
D. Filter-driers.
1.02 SYSTEM DESCRIPTION
A. Where more than one piping system material is specified ensure system components are compatible and joined to ensure the integrity of the system is not jeopardized.
B. Provide necessary joining fittings. Ensure flanges, unions, and couplings for servicing are consistently provided.
C. Provide pipe hangers and supports in accordance with ASME B31.5 unless indicated otherwise.
D. Liquid Indicators:
1. Use line size liquid indicators in main liquid line leaving condenser.
2. If receiver is provided, install in liquid line leaving receiver.
E. Filter-Driers:
1. Use a filter-drier immediately ahead of liquid-line controls, such as thermostatic expansion valves, solenoid valves and moisture indicators.
2. Use a filter-drier on suction line just ahead of compressor.
1.03 REGULATORY REQUIREMENTS

- A. Standards to ASME B31.9 for installation of piping system.
B. Welding Methods and Procedures: Conform to ASME (BPV IX) and applicable state labor regulations.
C. Welders Certification: In accordance with ASME (BPV IX).
PART 2 PRODUCTS
2.01 PIPING
A. Copper Tube: ASTM B 280, H58 hard drawn or O60 soft annealed.
1. Fittings: ASME B16.22 wrought copper.
2. Gaskets: ASME B16.25 phosphorus/copper alloy.
B. Copper Tube to 7/8 inch OD: ASTM B 88 (ASTM B 88M), Type K (A), annealed.
1. Fittings: ASME B16.26 cast copper.
C. Pipe Supports and Anchors:
1. Conform to ASME B31.5, ASTM F 708, MSS SP-58, MSS SP-69, and MSS SP-89.
2.02 REFRIGERANT
A. Refrigerant: As specified by the manufacturer of the refrigeration equipment.
2.03 MOISTURE AND LIQUID INDICATORS
A. Manufacturers:
1. Henry Technologies; Parker Hannifin/Refrigeration and Air Conditioning; Ingersoll Rand; Ingersoll Rand; Ingersoll Rand.
B. Indicators: Single port type, UL listed, with copper or brass body, flared or solder metal sight glass, color coded vapor moisture indicator with removable element cartridge and plastic cap; for maximum temperature of 200 degrees F and maximum working pressure of 500 psi.
2.04 FILTER-DRIERS
A. Manufacturers:
1. Flow Controls Division of Emerson Electric; Parker Hannifin/Refrigeration and Air Conditioning; Sparion Valve Company.
B. Performance:
1. Flow Capacity - Liquid Line: As required by capacities indicated on the Drawings, minimum, rated in accordance with ARI 730.
2. Flow Capacity - Suction Line: As required by capacities indicated on the Drawings, minimum, rated in accordance with ARI 730.
3. Pressure Drop: Maximum pressure drop at full controlled evaporator capacity.
4. Working Pressure: 350 psi, minimum.
C. Cores: Milled or loose-fill molecular sieve desiccant compatible with refrigerant, activated alumina, activated charcoal, and filtration to 40 microns, with secondary activated carbon and activated charcoal that will not pass into refrigerant lines.
D. Construction: UL listed.
1. Replaceable Core Type: Steel shell with removable cap.
2. Connections: As specified for applicable pipe type.
2.05 EXPANSION VALVES
A. Manufacturers:
1. Flow Controls Division of Emerson Electric; Parker Hannifin/Refrigeration and Air Conditioning; Sparion Valve Company.
B. Angle or Straight Through Type: ARI 750, design suitable for refrigerant, brass fire protection and supervised installation, bi-directional, adjustable, superheat setting, replaceable inlet strainer, with non-replaceable capillary tube and remote sensing bulb.
C. Selection: Evaluate refrigerant pressure drop through system to determine available pressure drop across valve. Select valve for maximum load at design operating pressure and superheat. Select to avoid being oversized at full load and excessively oversized at part load.
PART 3 EXECUTION
3.01 INSTALLATION
A. All refrigeration specialties in accordance with manufacturer's instructions.
B. All roofing penetrations shall be flashed and weather sealed by the roofing contractor's authorized roofing contractor at the Contractor's expense. This Contractor shall contract with the factory authorized roofing contractor for the installation of the roof. The use of an unauthorized roofing contractor may result in removal and replacement of the penetration systems at this Contractor's expense.
C. Provide a minimum of 15 minutes for charging and purging of systems and for disposal of refrigerant.
D. Provide control system with refrigerant after testing.
3.02 FIELD QUALITY CONTROL
A. Test refrigeration system in accordance with ASME B31.5.
END OF SECTION
SECTION 233100 - HVAC DUCTS AND CASINGS
PART 1 GENERAL
1.01 SECTION INCLUDES
A. All ductwork.
B. Nonmetal ductwork.
C. Round spiral ductwork.
D. Kitchen hood ductwork, Type 1 grease hoods.
1.02 PERFORMANCE REQUIREMENTS
A. No variation of duct configuration or sizes permitted except by written permission. Size round ducts in accordance with the manufacturer's specifications. ASHRAE table of equivalent rectangular and round ducts, only after approval of the Engineer. Round ducts shall be fabricated in accordance with the use of an unauthorizd contractor may result in removal and replacement of the penetration systems at this Contractor's expense.
B. Report all conflicts with structure or other obstructions, prior to fabrication of ductwork. The size of ducts shall be accommodated without any additional expense to the Owner.
1.03 SUBMITTALS
A. Shop Drawings: Indicate duct fittings, particulars such as gages, sizes, welds, etc. of TAB on the following:
1. Round ductwork: Indicate ductwork to be fabricated and shop drawings have been received by the Contractor. Identify on ductwork shop drawings any deviations in sizes or shapes.
B. Test Reports: Indicate pressure tests performed, include date, section tested, leakage rate, and leakage rate, following SHAKO (LEAK) - HVAC Air Duct Leakage Test Manual.
1.04 REGULATORY REQUIREMENTS
A. Construct ductwork to NFPA 90A, NFPA 90B, and NFPA 96 standards.
B. Code or utility company requirements shall supersede any conflicting requirements of this Section.
1.05 FIELD CONDITIONS
A. Insulate duct sections when temperatures are less than those recommended by sealant manufacturers.
B. Insulate temperatures within acceptable range during and after installation of duct sections.
PART 2 PRODUCTS
2.01 MATERIALS
A. Galvanized Steel Ducts: Hot-dipped galvanized steel sheet, ASTM A 653/A 653M F5.
B. Steel Ducts: ASTM A 1008/A 1008M, Designation CS, cold-rolled commercial steel.
C. Aluminum Ducts: ASTM B 202 (ASTM B 202M), aluminum sheet, alloy 3003-H14.
D. Insulated Flexible Ducts:
1. The contractor may propose any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, Federal, and local regulatory control equipment manufacturers. Verification of compliance of the selected ductwork material is the sole responsibility of the installing Contractor.
2. Insulated flexible ducting fabricated by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film.
a. Maximum Velocity: 5000 fpm.
b. Maximum Velocity: 4000 fpm.
c. Temperature Rating: -10 degrees F to 160 degrees F.
d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes.
3. Black polymer film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film.
a. Pressure Rating: 8 inches WG positive and 0.5 inches WG negative.
b. Maximum Velocity: 4000 fpm.
c. Temperature Rating: -10 degrees F to 175 degrees F.
d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes.
4. Multi-plyers of aluminum laminate supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film.
a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative.
b. Maximum Velocity: 4000 fpm.
c. Temperature Rating: -20 degrees F to 210 degrees F.
d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes.
5. UL 181, Class 1, aluminum laminate and polyester film with latex adhesive supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film.
a. Pressure Rating: 8 inches WG positive or negative.
b. Maximum Velocity: 5000 fpm.
c. Temperature Rating: -20 degrees F to 250 degrees F.
d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes.
E. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant.
1. Type: Heavy mastic or liquid used alone or with tape, suitable for joint and surface sealing and compatible with substrates, and recommended by manufacturer for pressure class of ducts.
2. Viscosity: Minimum viscosity of 250 g/L, excluding water.
3. Surface Burning Characteristics: Flame spread of zero, smoke developed of zero, when tested in accordance with ASTM E 84.
4. Use with fire-rated substrates. Provide duct materials, gaskets, reinforcement and sealant.
5. Ductwork Exposed to Weather: Hard coat Versaprot 102, (V-102), UL listed, 100% compliant duct joint sealer as manufactured by Corliss, Inc.
6. Fiberglass scrim tape reinforcement on all seams and joints, lateral and longitudinal.
F. Hanger Rods: ASTM A 36/A 36M; steel; threaded both ends, threaded one end, and continuously threaded.
2.02 DUCTWORK FABRICATION
A. Fabricate, support and seal in accordance with SMACNA HVAC Duct Construction Standards - Metal and Fabric Duct Systems. Provide duct material, gages, reinforcing, and sealing for operating pressures indicated.
B. Contract Tolerances: All materials, gages, and reinforcement shall be within 1-1/2 times width of duct on centerline. Where not possible and where rectangular elbows must be used, provide turning vanes. Where applicable lining is indicated, provide turning vanes of same material as the duct.
C. Increase duct sizes gradually, not exceeding 15 degrees divergence wherever equipment maximum 30 degrees divergence upstream of equipment and 45 degrees convergence downstream.
D. Provide standard 45 degree elbows. Provide duct materials unless otherwise indicated where 90 degree conical tee connections may be used.
E. Where ducts are installed with louvers and duct outlet is smaller than lower frame, provide blank not panels sealing lower duct around duct. Use same material as duct.
2.03 DUCT MANUFACTURERS
A. Meta-Fab, Inc.; SEMCO Incorporated; United McGill Corporation.
2.04 MANUFACTURING
A. Manufacture in accordance with SMACNA HVAC Duct Construction Standards - Metal and Fabric Duct Systems. Provide duct materials, gaskets, reinforcement and sealant for operating pressures indicated.
B. Round Spiral Duct: Machine made from round spiral lockseam duct with light reinforcing corrugations; fittings manufactured of at least two gages heavier metal than duct.

Bergmeyer logo and contact information. Schnackel engineers logo and contact information. Gregor Schnackel Engineer stamp. SHAKE SHACK logo and contact information. NOVI, MI 48375. PERMIT / BID SET. MECHANICAL SPECIFICATIONS. DRAWN BY: RAS. CHECKED BY: GRS. JOB NO: 20230422.0

C. Double Wall Insulated Round Ducts: Round spiral lockseam duct with galvanized steel outer wall, 1 inch thick fiberglass insulation, perforated galvanized steel inner wall, fitted with seal with spring device or screw to ensure against air leakage.

D. Transverse Duct Connection System: SMAACNA "E" rated rigidly class connection, interlocking angle and duct edge connection system with sealant, gaskets, metal, and corner clips.

2.05 KITCHEN HOOD EXHAUST DUCTWORK, TYPE I

A. Fabricate in accordance with SMAACNA HVAC Duct Construction Standards - Metal and Flexible, and NFPA 96.

B. Construct of 18 gage carbon steel or 18 gage stainless steel, using continuous external welded joints.

PART 3 EXECUTION

3.01 EXAMINATION

A. Confirm drawings for the Architectural, Structural, Electrical and all other trades prior to preparation of ductwork shop drawings and prior to the fabrication of any ductwork.

B. Resolve any conflicts encountered with the Engineer prior to fabrication.

C. Identify on ductwork shop drawings any deviations in sizes or shapes made necessary by the obstructions of other trades.

3.02 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Duct sizes indicated are inside clear dimensions. For lined ducts, maintain sizes inside lining.

C. Install and seal metal and flexible ducts in accordance with SMAACNA HVAC Duct Construction Standards - Metal and Flexible.

D. Provide openings in ductwork where required to accommodate thermometers and controllers. Provide pilot tube openings where required for testing of systems, complete with metal cap with spring device or screw to ensure against air leakage. Where openings are provided in insulated ductwork, install insulation material inside or metal ring.

E. Locate ducts with sufficient space around equipment to allow normal operating and maintenance activities.

F. Use crimp joints with or without bead for joining round duct sizes 8 inch and smaller with crimp in direction of air flow.

G. Use double nuts and lock washers on threaded rod supports.

H. Support flexible ducts to metal ducts with draw bands.

I. Support flexible duct runs every 4 feet in the horizontal direction to avoid dips and sags.

J. Connect terminal units to supply ducts with one foot maximum length of flexible duct. Do not use flexible duct to change direction.

K. Connect diffusers to low pressure ducts directly or with 5 feet maximum length of flexible duct held in place with straps or clamps. Longer duct lengths unit acceptable if depicted on the design drawings and allowed per local code. A maximum of one 90 degree bend is allowed in a flexible duct run.

L. During construction provide temporary closures of metal or taped polyethylene on open ductwork to prevent construction dust from entering ductwork system.

M. All exposed ducts in finished areas must be completely free from all dents or imperfections in the galvanized coating and shall be checked CAREFULLY AND NEATLY with duct sealer completely containing the joint. Duct work will not be permitted in exposed locations unless hood exhaust, Type I; Use stainless steel for ductwork exposed to view and stainless steel or carbon steel for ducts where concealed.

N. For all hood systems, perform all required regulatory duct leakage and weld tests in the presence of the code official, including but not limited to light tests and smoke tests, to demonstrate the integrity of the duct construction and prior to the installation of any insulation that prevents visual inspection of the ductwork on all sides.

O. Provide residue traps in kitchen hood exhaust ducts at base of vertical risers with provisions for clean out.

P. All roof penetrations shall be flashed and weather sealed by the roofing manufacturer's authorized roofing contractor at this Contractor's expense. This Contractor shall contract with the factory authorized roofing contractor for the specific roofing system applicable to this project. The use of an unauthorized roofing contractor may result in removal and replacement of the penetration systems at this Contractor's expense.

3.03 CLEANING

A. Clean duct system and force air at high velocity through duct to remove accumulated dust or clean with high power vacuum machines. To obtain sufficient air, clean half the system at a time. Protect equipment which may be harmed by excessive dirt with temporary filters, or bypass during cleaning.

3.04 SCHEDULES

A. Ductwork Material:

B. The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected piping material is the sole responsibility of the Contractor. Equipment and accessories listed in the Schedule System ESP +0.5", rounded up to next higher pressure class.

1. Low Velocity Supply (Heating Systems): Galvanized Steel, Aluminum.

2. Low Velocity Supply (Systems with Cooling): Schedules System ESP +0.5", rounded up to next higher pressure class.

3. Return and Relief: Galvanized Steel, Aluminum.

4. General Exhaust: Galvanized Steel, Aluminum.

5. Outside Air Intake: Galvanized Steel.

6. Kitchen Hood Exhaust, Type I: Carbon Steel, Stainless Steel, Constructed per NFPA 96.

C. Ductwork Pressure Class:

1. Low Velocity Supply (Heating Systems): Scheduled System ESP+0.25", rounded up to next higher pressure class.

2. Low Velocity Supply (Systems with Cooling): Scheduled System ESP +0.5", rounded up to next higher pressure class.

3. Return and Relief: 3-inch.

4. General Exhaust: Scheduled System ESP +1.0", rounded up to next higher pressure class.

5. Outside Air Intake: 1 inch.

6. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional.

END OF SECTION

SECTION 233300 - AIR DUCT ACCESSORIES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Air turning devices/extractors.

B. Volume control dampers.

C. Duct access doors.

PART 2 PRODUCTS

2.01 AIR TURNING DEVICES/EXTRACTORS

A. Manufacturers: Krueger; Ruskin Company, Titus.

B. Multi-blade device with blades angled in short dimension; steel or aluminum construction with individually adjustable blades.

2.02 VOLUME CONTROL DAMPERS

A. Manufacturers: Louvers & Dampers, Inc.; Nalor Industries Inc.; Ruskin Company; Prefico Inc.

B. Fabricate in accordance with SMAACNA HVAC Duct Construction Standards - Metal and Flexible, and as indicated.

C. Single Blade Dampers: Fabricate for duct sizes up to 6 x 30 inch.

D. Multi-Blade Dampers: Fabricate for duct sizes up to 22 gage minimum blade sizes 8 x 72 inch. Assemble center and edge crimped blades in prime coated or galvanized channel frame with suitable frame. Provide 1/2 inch diameter end bearings.

E. End Bearings: Except in round ducts 12 inches and smaller, provide end bearings. On multiple blade dampers, provide oil-impregnated nylon or sintered bronze.

F. The contractor shall provide either a mechanical or electrical cable operated system wherever dampers are located in non-accessible areas.

1. Mechanical cable operator system shall be similar and equal to Young's Regulator Company "Bowden Cable Control" system including damper, flexible cable with coating and concealed ceiling regulator control.

2. Electrically operated damper control system shall be similar and equal to United Controls Corporation "Power Balance" system including motor operated damper, RJ-11 plenum rated cabling and flush ceiling or wall mounted RJ-11 lock in remote plate. Include one hand held battery pack operator key to be delivered to the Owner upon completion of the balancing.

2.03 FLEXIBLE DUCT CONNECTIONS

A. Fabricate in accordance with SMAACNA HVAC Duct Construction Standards - Metal and Flexible, and as indicated.

B. Flexible Duct Connections: Fabric crimped into metal edging strip.

1. Fabric UL listed fire-retardant neoprene coated woven glass fiber fabric to NFPA 90A, minimum density 30 cc per sq yd.

2. Net Fabric Width: Approximately 2 inches wide.

3. Metal: 3 inches wide, 24 gage thick galvanized steel.

2.04 DUCT ACCESS DOORS

A. Manufacturers: Aero Products Inc.; Nalor Industries Inc.; Ruskin Company; SEMCO Incorporated.

B. Fabricate in accordance with SMAACNA HVAC Duct Construction Standards - Metal and Flexible, and as indicated.

C. Fabrication: Rigid and close-fitting of galvanized steel with sealing gaskets and quick fastening locking device. For installation, provide minimum 1 inch thick insulation with sheet metal cover.

1. Less Than 12 inches Square: Secure with ash locks.

2. Up to 18 inches Square: Provide two hinges and two ash locks.

D. Access doors with sheet metal screw fasteners are not acceptable.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install accessories in accordance with manufacturer's instructions, NFPA 90A, and follow SMAACNA HVAC Duct Construction Standards - Metal and Flexible. Duct construction and pressure class.

B. Check duct access doors for inspection and cleaning before and after filters, coils, fans, automatic dampers, air filters, combination fire and smoke dampers, and elsewhere as indicated. Provide minimum 8 x 8 inch size for hand access, 18 x 18 inch size for shoulder access, and as indicated. Provide 4 x 4 inch for balancing dampers only. Review locations prior to fabrication.

C. Locate all dampers and control elements in accessible areas wherever possible to avoid access doors. Provide ceiling access for ceiling diffusers, grilles, and control elements located above inaccessible ceiling areas. Provide minimum 12 x 12 inch size for hand access, 18 x 18 inch size for shoulder access, and as indicated. Provide 4 x 4 inch for balancing dampers only. Review locations prior to fabrication.

D. Provide balancing dampers at points on supply, return, and exhaust systems where branches are taken from larger ducts as required for air balancing. Install minimum 2 duct widths from duct take-off.

E. Provide balancing dampers on duct take-off to diffusers, grilles, and registers, regardless of whether dampers are specified as part of the diffuser, grille, or register assembly. Do not locate dampers closer than 5 feet or 10 duct diameters from the terminal unit to the equipment.

F. All fans and motorized equipment associated with ducts, provide flexible duct connections immediately adjacent to the equipment.

G. At equipment supported by vibration isolators, provide flexible duct connections immediately adjacent to the equipment.

AIR PURIFICATION DEVICES

Model: PHI-PG14-24V Specifications

LISTING: UL 1598:2008 (3rd Edition)

FACTORY UV-PHI CELL

INSTALLATION: RTU PACKAGED UNIT / BLOWER CABINET

PART 1 GENERAL

1.01 SUMMARY

A. This section includes hydro-peroxide, Super-Oxide Ions, and Hydroxide Ion's delivered via PHI technology through ionizing units capable of supplying 3,000 to 8,000 CFM of air to the indoor space.

1.02 QUALITY ASSURANCE

A. All models shall be UL listed and comply with safety standards UL 1598:2008 (3rd Edition) and CSA Standard C22.2 No. 250.0:2008.

1.03 WARRANTY

A. All units shall be provided with the following standard warranties:

1. 2-year or 18,000 hours from initial startup. National TAB provided service plan. The pH cell & UV light replacement 18,000 hour replacements are provided/installed at no cost if National TAB is providing Renew-Cx Service after initial installation.

B. This warranty shall not apply if:

- The equipment is not installed by a qualified installer per the manufacturer's installation instructions aligned with the product.
- The equipment is misused or neglected, or not maintained per the manufacturer's maintenance instructions.
- The equipment is not operated within its published capacity.
- The invoice is not paid within the terms of the sales agreement.

PART 2 PRODUCTS

2.01 GENERAL

A. BUILT-IN-ZONE one piece packaged PHI Unit-Air Purification System.

2.02 HOUSING

A. Units shall be constructed of aluminum structural pop-rivets. All metal shall be CNC bent for precise assembly.

1. Quad Metallic Target

2. UV-C bulb

3. Electronic Enclosure (24VAC Input power jack)

4. Magnaptic mounting feet for easy placement and installation in the Blower Cabinet.

END OF SECTION

SECTION 233425 - HVAC POWER VENTILATORS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Roof exhausters.

B. Kitchen range hood exhausters.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Greenheck; Loren Cook Company; PennBray; CaptiveAir.

2.02 POWER VENTILATORS - GENERAL

A. Performance Ratings: Determined in accordance with AMCA 210 and bearing the AMCA Certified Rating label.

B. Sound Ratings: AMCA 301, tested to AMCA 300, and bearing AMCA Certified Sound Rating Seal.

C. Fabrication: Conform to AMCA 99.

D. UL Compliance: UL listed and labeled, designed, manufactured, and tested as suitable for the purpose specified and indicated.

2.03 ROOF EXHAUSTERS AND VENTILATORS

A. Units shall be fabricated as indicated, with spun aluminum housing; resilient mounted motor, 1/2 inch mesh, 0.62 inch thick aluminum wire birdscreen; variable and adjustable pitch motor where selected as required per the drawings.

B. Roof Curbs: 20 inch high above the finished roof surface (compensate for roof insulation thickness at fan location) self-flashing of galvanized steel or aluminum construction with continuously welded seams, built-in curb strips, insulation and curb bottom, and factory installed roller strip.

C. Backdraft Damper: Motor actuated (or gravity damper if depicted on design drawings), aluminum multiple blade construction, flg edged with offset hinge pin, nylon bearings, blades linked, and line voltage motor drive, power open, spring return.

E. Shafts: Cast iron or steel, dynamically balanced, bored to fit shafts and keyed; Contractor shall contract with the factory authorized roofing contractor for the specific roofing system applicable to this project. The use of an unauthorized roofing contractor may result in removal and replacement of the penetration systems at this Contractor's expense.

F. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb saddle base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Provide shafts required for final air balance at no additional expense to the project.

C. Secure roof and wall exhausters with minimum plated steel lag screws to roof curb or structure.

D. Extend ducts to roof and wall exhausters into roof curb or wall structure. Counterflashed duct to roof or wall opening.

E. Install backdraft dampers (gravity or motorized as depicted on design drawings) on inlet to roof and wall exhausters.

F. All roofing penetrations shall be flashed and weather sealed by the roofing manufacturer's authorized roofing contractor at this Contractor's expense. This Contractor shall contract with the factory authorized roofing contractor for the specific roofing system applicable to this project. The use of an unauthorized roofing contractor may result in removal and replacement of the penetration systems at this Contractor's expense.

END OF SECTION

SECTION 233700 - AIR OUTLETS AND INLETS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Rectangular ceiling diffusers.

B. Perforated face ceiling diffusers.

C. Grid core exhaust and return grilles.

D. Wall registers and grilles.

1.02 SUBMITTALS

A. Product Data: Provide data for equipment required for this project. Review and listers on to size, finish, and type of mounting prior to submission. Submit schedule of outlets and inlet showing type, size, location, application, accessories, and noise level.

1.03 QUALITY ASSURANCE

A. Test and rate air outlet and inlet performance in accordance with ASHRAE Std 70.

B. Test and rate lower performance in accordance with AMCA 500-1.

C. Code requirements shall supersede any conflicting requirements of this Section.

1.04 QUALIFICATIONS

A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this Section, with minimum five years of documented experience.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Titus; Krueger; Price Industries; Nalor Industries Inc.; Hart & Cooley; Ruskin, Flexible, and as indicated.

2.02 RECTANGULAR CEILING DIFFUSERS

A. Type: Square, adjustable pattern, stamped, multi-core, or architectural plaque diffuser with grille in 360 degree pattern with sectorizing baffles where indicated.

B. Frame: Inverted T-bar type. In plaster ceilings, provide plaster frame and nailing frame. (To allow lift-out removal of the diffuser without removal of the plaster frame.)

C. Fabrication: Steel with steel frame and baked enamel off-white finish.

D. Accessories: Opposed blade damper and multi-louvered equalizing grid with damper adjustable from diffuser face.

2.03 PERFORATED FACE CEILING DIFFUSERS

A. Type: Perforated face with removable face.

B. Frame: Inverted T-bar type. In plaster ceilings, provide plaster frame and nailing frame. (To allow lift-out removal of the diffuser without removal of the plaster frame.)

C. Fabrication: Steel with steel frame and baked enamel off-white finish.

D. Accessories: Opposed blade damper and multi-louvered equalizing grid with damper adjustable from diffuser face.

2.04 GRID CORE EXHAUST AND RETURN GRILLES

A. Type: Fixed grilles of 1/2 x 1/2 x 1 inch louvers.

B. Fabrication: Aluminum with factory off-white enamel finish.

C. Frame: 1-1/4 inch margin with countersunk screw mounting and gasket. Frame: Fabricated in place for suspended ceiling where face size exceeds 18 x 18 inch.

D. Net: (If specified on drawings). Integral, gong-operated, opposed blade type with removable key operator, operable from face.

2.05 WALL SUPPLY REGISTERS/GRILLES

A. Type: Steel frame and individually adjustable blades, 3/4 inch minimum depth, 3/4 inch maximum spacing with spring or other device to set blades, horizontal face.

B. Frame: 1-1/4 inch margin with countersunk screw mounting and gasket.

C. Fabrication: Steel with 20 gage minimum frames and 22 gage minimum blades, steel or aluminum with 20 gage minimum frame, or aluminum extrusions, with factory off-white enamel finish.

D. Damper: Integral, gong-operated opposed blade type with removable key operator, operable from face.

E. Rough Service: Provide front pivoted or welded in place blades, securely fastened to be immobile.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Check location of outlets and inlets and make necessary adjustments in position to conform with architectural features, symmetry, and lighting arrangement.

C. Install diffusers to ductwork with all tight connection.

D. Provide balancing dampers on duct take-off to diffusers, and grilles and registers, despite whether dampers are specified as part of the diffuser, or grille and register assembly.

E. Paint ductwork visible behind air outlets and inlets matte black.

END OF SECTION

SECTION 237413 - PACKAGED OUTDOOR ROOF TOP UNITS - GAS FIRED

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Packaged roof top units.

B. Thermostat controls.

C. Roof mounting curb and base.

D. Economizer.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. CaptiveAir, No Exceptions

2.02 AIR CONDITIONING UNITS

A. General: Roof mounted units having gas burner and electric refrigeration.

B. Description: Self-contained, packaged, factory assembled and prewired, consisting of cabinet and frame, supply fan, when indicated provide electric heating elements, controls, air filters, refrigerant cooling coil and compressor, dry bulb economizer and power exhaust fan where indicated on the drawings, condenser coil and condenser fan.

C. Electrical Characteristics: As scheduled on the Drawings.

D. Disconnect Switch: Factory mount disconnect switch on equipment.

2.03 FABRICATION

A. Cabinet: Steel with baked enamel finish, including access panels with screwdriver operated flush cam type fasteners or doors with piano hinges with locking handles. Structural members shall be minimum 18 gage, with access doors or panels of minimum 20 gage.

B. Insulation: Minimum 1/2 inch thick neoprene coated glass fiber with edges protected from erosion.

C. Supply Fan: Forward curved centrifugal type, resiliently mounted with V-belt drive, adjustable variable pitch motor pulley, and rubber isolated hinge mounted motor or direct drive as indicated. Isolate complete fan assembly.

D. Fans for units with a mechanical cooling capacity greater than or equal to 65,000 BTU/h shall have not fewer than two stages of fan control.

E. Air Filters: 2 inch thick disposable media in metal frames.

F. Roof Mounting Curb: Galvanized steel channel frame, insulated, with gaskets, roller strips. Provide roof curb of adequate height to provide a unit mounting height of 12" or greater above the top of the roof surface with the curb mounted to the building structure. Roof curb height must compensate for the roof insulation thickness to meet this requirement.

G. Vibration Isolation Curb: Only when indicated on the Drawings.

2.04 ELECTRIC HEATING COIL (PROVIDE IF INDICATED ON DESIGN DRAWINGS)

A. Helical nickel-chrome resistance wire coil heating elements with refractory ceramic support bushings or fired tube heating elements easily accessible with automatic reset thermal cut-out, built-in magnetic contactors, galvanized steel frame, control circuit transformer and fuse, manual reset thermal cut-out, airflow proving device.

B. Controls: Start supply fan before electric elements are energized and continue operating until air temperature reaches minimum setting, with switch for continuous fan operation. Controls shall prevent supplemental heater operation when heating load can be met by the heat pump alone. Heater operation is permitted during outdoor coil defrost cycles.

2.05 EVAPORATOR COIL

A. Provide copper tube aluminum fin coil assembly with galvanized drain pan and connection.

B. Provide capillary tubes or thermostatic expansion valves for units of 6 tons capacity and less, and thermostatic expansion valves and alternate row circulating for units 7.5 tons cooling capacity and larger.

2.06 COMPRESSOR

A. Provide hermetic or semi-hermetic compressors, 3600 rpm maximum, resiliently mounted with positive lubrication, crankcase heater, high and low pressure safety controls, motor overload protection, suction and discharge service valves and gage ports, and filter drier.

B. Five minute timed off circuit to delay compressor start.

C. Outdoor thermostat to energize compressor above 33 degrees F ambient.

2.07 CONDENSER COIL

A. Provide copper tube aluminum fin coil assembly with subcooling rows and coil guard.

B. Insulation: one inch thick neoprene coated glass fiber with edges protected from erosion.

2.08 MIXED AIR CASING

A. Heat Exchangers: Aluminumized steel or stainless steel where indicated on the Drawings, of welded construction.

B. Supply Fan: Forward curved centrifugal type, resiliently mounted with V-belt drive, adjustable variable pitch motor pulley, and rubber isolated hinge mounted motor or direct drive as indicated. Isolate complete fan assembly.

1. Fans for units with a mechanical cooling capacity greater than or equal to 65,000 BTU/h shall have not fewer than two stages of fan control.

D. Air Filters: 2 inch thick disposable media in metal frames.

E. Roof Mounting Curb: Galvanized steel channel frame, insulated with gaskets, roller strips. Provide roof curb of adequate height to provide a unit mounting height of 12" or greater above the top of the roof surface with the curb mounted to the building structure. Roof curb height must compensate for the roof insulation thickness to meet this requirement.

G. Vibration Isolation Curb: Only when indicated on the Drawings.

2.04 BURNER

A. Gas Burner: Induced draft or forced draft type burner with adjustable combustion air supply, pressure regulator, gas valves, manual shut-off, intermittent spark or glow coil ignition, flame sensing device, and automatic 100 percent shut-off pilot.

B. Gas Burner Safety Controls: Energy ignition, limit time for establishment of flame, prevent opening of gas valve until pilot flame is proven, stop gas flow on ignition failure, energize blower motor, and after air flow proven and slight delay allow gas valve to open.

C. High Limit Control: Temperature sensor with fixed spot at maximum permissible setting, de-energize burner on excessive bonnet temperature and energize burner when temperature drops to lower safe value.

D. Supply Fan Control: Temperature sensor bonnet temperature and independent of burner controls, with provisions for continuous fan operation.

2.05 EVAPORATOR COIL

A. Provide copper tube aluminum fin coil assembly with galvanized drain pan and connection.

B. Provide capillary tubes or thermostatic expansion valves for units of 6 tons capacity and less, and thermostatic expansion valves and alternate row circulating for units 7.5 tons cooling capacity and larger.

2.06 COMPRESSOR

A. Provide hermetic or semi-hermetic compressors, 3600 rpm maximum, resiliently mounted with positive lubrication, crankcase heater, high and low pressure safety controls, motor overload protection, suction and discharge service valves and gage ports, and filter drier.

B. Five minute timed off circuit to delay compressor start.

C. Outdoor thermostat to energize compressor above 33 degrees F ambient.

2.07 CONDENSER COIL

A. Provide copper tube aluminum fin coil assembly with subcooling rows and coil guard.

B. Insulation: one inch thick neoprene coated glass fiber with edges protected from erosion.

2.08 MIXED AIR CASING

A. Heat Exchangers: Aluminumized steel or stainless steel where indicated on the Drawings, of welded construction.

B. Supply Fan: Forward curved centrifugal type, resiliently mounted with V-belt drive, adjustable variable pitch motor pulley, and rubber isolated hinge mounted motor or direct drive as indicated. Isolate complete fan assembly.

C. Gaskets: Provide tight fitting dampers with edge gaskets maximum leakage 5 percent at 2 inches pressure differential.

D. Damper Operator: 24 volt with gear train sealed in oil.

E. Mixed Air Controls: Maintain selected supply air temperature and return dampers to minimum position on call for heating and above 75 degrees F ambient, or when ambient air temperature exceeds return air temperature.

2.09 INTEGRATED ECONOMIZER

A. Economizer shall be furnished and installed complete with outside air and relief dampers and controls.

B. Provide low leakage, opposed blade dampers.

1. Meet all leakage requirements of applicable energy code.

C. Economizer shall be capable of introducing up to 100% outdoor air for minimum ventilation as well as free cooling.

D. Damper actuator shall be electronic, fully modulating design.

E. Economizer outdoor hood shall be pre-assembled and fully integrated with the unit. Dry Bulb Control: Provide dry bulb sensor capable of measuring temperature of outdoor air to determine when the economizer should be used. High level cutoff shall be set per applicable energy code.

F. Automatic Start Capabilities: Controls shall be capable of automatically adjusting the daily start time of the HVAC system in order to bring each space to the desired occupied temperature immediately prior to scheduled occupancy per day.

G. Set-up: Set-up for four separate temperatures per day.

H. Instant override of set point for continuous or timed period from one hour to 31 days.

I. Short cycle protection.

J. Programming based on weekdays, Saturday and Sunday.

K. Switch selection features including temporal or metric display, 12 or 24 hour clock, keyboard disable, remote sensor, fan on-auto.

L. Room thermostats shall be included in the Drawings.

M. Time of day.

N. System mode indication: heating, cooling, auto, off, fan auto, fan on.

O. Staged (heating or cooling) operation.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions and NFPA 90A.

B. Mount units on factory built roof mounting curb providing watertight enclosure to protect ductwork and utility services. Install roof mounting curb level, install roof mounting curb so that it bears on the building structure, not on top of roof deck. Provide roof curb as indicated on the Drawings.

C. Provide cooling condensate drain piping (and overflow piping if required) to approved local drainage system. Condensate piping shall be Schedule 40 galvanized steel pipe, Type L copper tube, or PVC. Contractor shall verify the selected material meets with the approval of all State, local authorities and utility company requirements.

D. Provide piping within the building shall be insulated with 1/2 inch thick glass fiber or flexible elastomeric cellular foam insulation. Only metallic piping systems will be allowed in return air plenum ceiling space.

END OF SECTION

SECTION 238127 - SMALL SPLIT-SYSTEM HEATING AND COOLING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Air-source heat pumps.

B. Indoor ductless fan coil units.

C. Room thermostats.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Carrier Corporation, No Exceptions

2.02 SYSTEM DESIGN

A. System Heating and Cooling Units: Self-contained, packaged, matched factory-engineered and assembled, pre-wired indoor and outdoor units; UL listed, consisting of cabinet, supply fan, evaporator coil, and controls; wired for single power connection with control transformer.

B. Evaporator Coil: Copper tube aluminum fin assembly, galvanized or polymer drain pan angled in all directions to drain, drain connection, refrigerant piping connections, restricted distributor or thermostatic expansion valve.

C. Construction and Ratings: In accordance with ARI 210/240 and UL listed.

2.03 INDOOR UNITS

A. Indoor Units: Self-contained, packaged, factory assembled, pre-wired unit consisting of cabinet, with compressor and condenser.

1. Cabinet: Steel with baked enamel finish, easily removed and secured access doors with safety interlock switches, glass fiber insulation with reflective liner.

2. Construction and Ratings: In accordance with ARI 210/240 with reflecting liner.

B. Components: Self-contained, packaged, factory assembled, pre-wired indoor and outdoor units; UL listed, consisting of cabinet, supply fan, evaporator coil, and controls; wired for single power connection with control transformer.

C. Air Cooled Condenser: ARI 520; Aluminum fin and copper tube coil, with direct drive fan and fan speed control.

D. Accessories: Filter drier, high pressure switch (manual reset), low pressure switch (manual reset), pressure gage ports, thermometer well (N liquid line).

1. Provide thermostatic expansion valves.

2. Provide heat pump reversing valves on all heat pump units.

E. Operating Controls:

1. Control by room thermostat to maintain room temperature setting.

2. Low Ambient Kit: On all systems not provided with economizer controls, provide refrigerant pressure switch to cycle condenser fan on when condenser refrigerant pressure is above 285 psig and off when pressure drops below 140 psig for operation to 0 degrees F.

F. Mounting Pad: Four in square concrete, precast concrete or resin composite pad, minimum 4 inches thick in place.

2.04 ACCESSORY EQUIPMENT

A. Room Thermostat: Wall-mounted, electric solid state microcomputer based room thermostat with remote sensor to maintain temperature setting; low-voltage; with following features:

1. System selector switch (heat-off-cool) and fan control switch (auto-on).

2. Automatic switching from heating to cooling.

3. Preferential rate control to minimize overshoot and deviation from setpoint.

4. Automatic Start Capabilities: Controls shall be capable of automatically adjusting the daily start time of the HVAC system in order to bring each space to the desired occupied temperature immediately prior to scheduled occupancy.

5. Set-up for four separate temperatures per day.

6. Instant override of setpoint for continuous or timed period from one hour to 31 days.

7. Short cycle protection.

8. Programming based on every day of the week.

9. Switch selection features including degree F or degree C display, 12 or 24 hour clock, keyboard disable, remote sensor, fan on-auto.

10. Battery replacement without program loss.

11. Thermostat display:

a. Time of day.

b. Actual room temperature.

c. Programmed temperature.

d. System mode indication: heating, cooling, fan auto, off, and on, auto or on, off.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions and requirements of local authorities and utility company requirements.

B. Install in accordance with NFPA 90A and NFPA 90B as applicable.

C. Provide piping within the building shall be Schedule 40 galvanized steel pipe, Type L copper tube, or PVC pipe (non-plenum applications). Contractor shall verify the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected piping material is the sole responsibility of the installing Contractor. Only metallic piping systems will be allowed in return air plenum ceiling space.

D. Provide piping systems in accordance with ASHRAE Std 15. Provide filter drier, sight glass and solenoid valve on outdoor units and sight glass and expansion valve on indoor units.

E. All thermostats, humidistats (if roofed), damper interlock and other low voltage control wiring shall be installed by the Mechanical Contractor. The Electrical Contractor shall provide the wiring for the thermostat, equipment and interlock wiring in the responsibility of the Mechanical Contractor.

END OF SECTION

of 2 inches pressure differential.

C. Damper Operator: 24 volt with gear train sealed in oil.

D. Damper Operator: Units 7.5 Ton Cooling Capacity and Larger: 24 volt with gear train sealed in oil with spring return on.

E. Mixed Air Controls: Maintain selected supply air temperature and return dampers to minimum position on call for heating and above 75 degrees F ambient, or when ambient air temperature exceeds return air temperature.

2.09 INTEGRATED ECONOMIZER

A. Economizer shall be furnished and installed complete with outside air and relief dampers and controls.

B. Provide low leakage, opposed blade dampers.

1. Meet all leakage requirements of applicable energy code.

C. Economizer shall be capable of introducing up to 100% outdoor air for minimum ventilation as well as free cooling.

D. Damper actuator shall be electronic, fully modulating design.

E. Economizer outdoor hood shall be pre-assembled and fully integrated with the unit. Dry Bulb Control: Provide dry bulb sensor capable of measuring temperature of outdoor air to determine when the economizer should be used. High level cutoff shall be set per applicable energy code.

F. Automatic Start Capabilities: Controls shall be capable of automatically adjusting the daily start time of the HVAC system in order to bring each space to the desired occupied temperature immediately prior to scheduled occupancy per day.

G. Set-up: Set-up for four separate temperatures per day.

H. Instant override of set point for continuous or timed period from one hour to 31 days.

I. Short cycle protection.

J. Programming based on weekdays, Saturday and Sunday.

K. Switch selection features including temporal or metric display, 12 or 24 hour clock, keyboard disable, remote sensor, fan on-auto.

L. Room thermostats shall be included in the Drawings.

M. Time of day.

N. System mode indication: heating, cooling, auto, off, fan auto, fan on.

O. Staged (heating or cooling) operation.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions and NFPA 90A.

B. Mount units on factory built roof mounting curb providing watertight enclosure to protect ductwork and utility services. Install roof mounting curb level, install roof mounting curb so that it bears on the building structure, not on top of roof deck. Provide roof curb as indicated on the Drawings.

C. Provide cooling condensate drain piping (and overflow piping if required) to approved local drainage system. Condensate piping shall be Schedule 40 galvanized steel pipe, Type L copper tube, or PVC. Contractor shall verify the selected material meets with the approval of all State, local authorities and utility company requirements.

D. Provide piping within the building shall be insulated with 1/2 inch thick glass fiber or flexible elastomeric cellular foam insulation. Only metallic piping systems will be allowed in return air plenum ceiling space.

END OF SECTION

SECTION 238127 - SMALL SPLIT-SYSTEM HEATING AND COOLING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Air-source heat pumps.

B. Indoor ductless fan coil units.

C. Room thermostats.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Carrier Corporation, No Exceptions

2.02 SYSTEM DESIGN

A. System Heating and Cooling Units: Self-contained, packaged, matched factory-engineered and assembled, pre-wired indoor and outdoor units; UL listed, consisting of cabinet, supply fan, evaporator coil, and controls; wired for single power connection with control transformer.

B. Evaporator Coil: Copper tube aluminum fin assembly, galvanized or polymer drain pan angled in all directions to drain, drain connection, refrigerant piping connections, restricted distributor or thermostatic expansion valve.

C. Construction and Ratings: In accordance with ARI 210/240 and UL listed.

2.03 INDOOR UNITS

A. Indoor Units: Self-contained, packaged, factory assembled, pre-wired unit consisting of cabinet, with compressor and condenser.

1. Cabinet: Steel with baked enamel finish, easily removed and secured access doors with safety interlock switches, glass fiber insulation with reflective liner.

2. Construction and Ratings: In accordance with ARI 210/240 with reflecting liner.

B. Components: Self-contained, packaged, factory assembled, pre-wired indoor and outdoor units; UL listed, consisting of cabinet, supply fan, evaporator coil, and controls; wired for single power connection with control transformer.

C. Air Cooled Condenser: ARI 520; Aluminum fin and copper tube coil, with direct drive fan and fan speed control.

D. Accessories: Filter drier, high pressure switch (manual reset), low pressure switch (manual reset), pressure gage ports, thermometer well (N liquid line).

1. Provide thermostatic expansion valves.

2. Provide heat pump reversing valves on all heat pump units.

E. Operating Controls:

1. Control by room thermostat to maintain room temperature setting.

2. Low Ambient Kit: On all systems not provided with economizer controls, provide refrigerant pressure switch to cycle condenser fan on when condenser refrigerant pressure is above 285 psig and off when pressure drops below 140 psig for operation to 0 degrees F.

F. Mounting Pad: Four in square concrete, precast concrete or resin composite pad, minimum 4 inches thick in place.

2.04 ACCESSORY EQUIPMENT

A. Room Thermostat: Wall-mounted, electric solid state microcomputer based room thermostat with remote sensor to maintain temperature setting; low-voltage; with following features:

1. System selector switch (heat-off-cool) and fan control switch (auto-on).

2. Automatic switching from heating to cooling.

3. Preferential rate control to minimize overshoot and deviation from setpoint.

4. Automatic Start Capabilities: Controls shall be capable of automatically adjusting the daily start time of the HVAC system in order to bring each space to the desired occupied temperature immediately prior to scheduled occupancy.

5. Set-up for four separate temperatures per day.

6. Instant override of setpoint for continuous or timed period from one hour to 31 days.

7. Short cycle protection.

8. Programming based on every day of the week.

9. Switch selection features including degree F or degree C display, 12 or 24 hour clock, keyboard disable, remote sensor, fan on-auto.

10. Battery replacement without program loss.

11. Thermostat display:

a. Time of day.

b. Actual room temperature.

c. Programmed temperature.

d. System mode indication: heating, cooling, fan auto, off, and on, auto or on, off.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install in accordance with manufacturer's instructions and requirements of local authorities and utility company requirements.

B. Install in accordance with NFPA 90A and NFPA 90B as applicable.

C. Provide piping within the building shall be Schedule 40 galvanized steel pipe, Type L copper tube, or PVC pipe (non-plenum applications). Contractor shall verify the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected piping material is the sole responsibility of the installing Contractor. Only metallic piping systems will be allowed in return air plenum ceiling space.

D. Provide piping systems in accordance with ASHRAE Std 15. Provide filter drier, sight glass and solenoid valve on outdoor units and sight glass and expansion valve on indoor units.

E. All thermostats, humidistats (if roofed), damper interlock and other low voltage control wiring shall be installed by the Mechanical Contractor. The Electrical Contractor shall provide the wiring for the thermostat, equipment and interlock wiring in the responsibility of the Mechanical Contractor.

END OF SECTION

Bergmeyer

CONSULTANTS:

Schnackel engineers

MEPF ENGINEER
2035 S 72ND ST
OMAHA NE 68124
TEL. 402.391.7880

SEAL SIGNATURE:

GREGORY SCHNACKEL
ENGINEER
No. 37570
Date: 07/20/24

NO.	BY	DATE	DESCRIPTION
2		2024-07-02	FIELD NOTICE 1
1		2024-06-14	IFC
A		2024-05-07	ADDENDUM A
1		2024-03-18	PERMIT / BID SET

SHAKE SHACK

NOVI, MI

43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605

PERMIT / BID SET

MECHANICAL SPECIFICATIONS

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO. 20230420.00

M592

SYSTEM 1 - RTU-1																	
ROOM #	NAME	Az AREA (FT ²)	TABLE 403.3.1.1 OCCUPANCY CATEGORY	TABLE 403.3.1.1 R _p PEOPLE OA (CFM/PERSON)	TABLE 403.3.1.1 R _a AREA OA (CFM/FT ²)	TABLE 403.3.1.1 OCCUPANT DENSITY (#/1000 FT ²)	P _z (ft)	R _h (ft)	R _h (ft)	V _z (CFM)	TABLE 403.3.1.1.2 E _z (CFM)	V _z (CFM)	MAX SUPPLY (CFM)	V _z (CFM)	MIN SUPPLY (CFM)	Z _o	TABLE 403.3.1.1.2.3.2 E _z
100	VESTIBULE	61	NO LISTING	0.0	0.00	0	0	0	0	0.00	0	0	205	205	0.000	1.00	0.80
101	QUEUE	805	SALES	7.5	0.12	15	30	225	0.7	322	0.80	602	1295	1295	0.310	0.84	
102	DINING	398	DINING ROOMS	7.5	0.18	70	42	315	1.08	423	0.80	528	1500	1500	0.352	0.80	
		1,464					72	540	2.04	744		930	3000	3000	0.352	0.80	

OUTDOOR AIR CALCULATIONS PER EQUATION 4-1:
 SYMBOL VALUE DESCRIPTION
 P_s = 72 SYSTEM POPULATION
 SP_z = 72 ZONE POPULATION
 D = 1.00 OCCUPANT DIVERSITY
 V_{ou} = 744 UNCORRECTED OUTDOOR AIR INTAKE
 Z_o (max) = 0.352 ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)
 E_v = 0.80 SYSTEM VENTILATION EFFICIENCY
 SV_z = 3000 ZONE PRIMARY AIRFLOW
 V_{ot} = 933 CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM
 V_{ol} = 1100 DESIGN OUTDOOR AIRFLOW RATE, CFM

SYSTEM 2 - RTU-2																	
ROOM #	NAME	Az AREA (FT ²)	TABLE 403.3.1.1 OCCUPANCY CATEGORY	TABLE 403.3.1.1 R _p PEOPLE OA (CFM/PERSON)	TABLE 403.3.1.1 R _a AREA OA (CFM/FT ²)	TABLE 403.3.1.1 OCCUPANT DENSITY (#/1000 FT ²)	P _z (ft)	R _h (ft)	R _h (ft)	V _z (CFM)	TABLE 403.3.1.1.2 E _z (CFM)	V _z (CFM)	MAX SUPPLY (CFM)	V _z (CFM)	MIN SUPPLY (CFM)	Z _o	TABLE 403.3.1.1.2.3.2 E _z
103	CIRCULATION	68	CORRIDORS	0.0	0.00	0	0	0	0	0.00	0	0	0	0	0.000	1.00	0.80
104	WOMENS RESTROOM	68	NO LISTING	0.0	0.00	0	0	0	0	0.00	0	0	50	50	0.000	1.00	0.80
105	MENS RESTROOM	63	NO LISTING	0.0	0.00	0	0	0	0	0.00	0	0	50	50	0.000	1.00	0.80
106	COOK LINE	336	NO LISTING	0.0	0.00	0	5	0	0	0.00	0	2530	2430	0.000	1.00	0.80	
107	PREP WASH	314	NO LISTING	0.0	0.00	0	2	0	0	0.00	0	790	790	0.000	1.00	0.80	
108	MANAGERS OFFICE	79	OFFICE SPACES	5.0	0.08	5	2	10	5	15	0.80	18	380	380	0.048	1.00	0.80
109	WORK ROOM	480	NO LISTING	0.0	0.00	0	2	0	0	0.00	0	520	520	0.000	1.00	0.80	
110	VOID	37	NO LISTING	0.0	0.00	0	0	0	0	0.00	0	0	0	0.000	1.00	0.80	
111	COLD LINE	1624	NO LISTING	0.0	0.00	0	3	0	0	0.00	0	671	670	0.000	1.00	0.80	
							14	10	8	18		23	4850	4850	0.048	1.00	

OUTDOOR AIR CALCULATIONS PER EQUATION 4-1:
 SYMBOL VALUE DESCRIPTION
 P_s = 14 SYSTEM POPULATION
 SP_z = 14 ZONE POPULATION
 D = 1.00 OCCUPANT DIVERSITY
 V_{ou} = 18 UNCORRECTED OUTDOOR AIR INTAKE
 Z_o (max) = 0.048 ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)
 E_v = 1.00 SYSTEM VENTILATION EFFICIENCY
 SV_z = 4850 ZONE PRIMARY AIRFLOW
 V_{ot} = 18 CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM
 V_{ol} = 1550 DESIGN OUTDOOR AIRFLOW RATE, CFM

1 VENTILATION CALCULATIONS

RTU/FC CONTROL MATRIX			
SETPOINT/CONTROL	RTU-1 DINING	RTU-2 KITCHEN	FC-1 OFFICE
SETPOINTS			
COOLING - OCCUPIED SETPOINT	75 F	75 F	75 F
COOLING - UNOCCUPIED SETPOINT	80 F	80 F	80 F
HEATING - OCCUPIED SETPOINT	70 F	70 F	70 F
HEATING - UNOCCUPIED SETPOINT	60 F	60 F	60 F
ECONOMIZER UPPER LIMIT SETPOINT	70 F	70 F	NA
ACCESSORIES			
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT	YES	YES	YES
REMOTE TEMPERATURE SENSOR	YES	YES	NO
MOTORIZED OUTDOOR AIR DAMPER	YES	YES	NO
INTEGRATED ECONOMIZER	YES	YES	NO
ECONOMIZER FAULT DETECTION	YES	YES	NO
BAROMETRIC RELIEF	YES	NO	NO
POWERED EXHAUST RELIEF	NO	YES	NO
DEHUMIDIFICATION (HOT GAS REHEAT)	YES	YES	NO
SUPPLY FAN			
ON DURING OCCUPIED MODE	YES	YES	YES
VARIABLE VOLUME - MODULATE FAN SPEED	YES	YES	YES
SAFETIES AND INTERLOCKS			
RETURN AIR SMOKE DETECTOR	YES	YES	NO
LOW LIMIT FREEZE/STAT	YES	YES	YES
FIRE ALARM CONTROL PANEL INTERLOCK	YES	YES	YES
KITCHEN EXHAUST SYSTEM INTERLOCK	YES	YES	YES

AIR BALANCE SCHEDULE						
EQUIPMENT TAG	SUPPLY AIRFLOW (CFM)	OUTDOOR AIRFLOW (CFM)	RETURN AIRFLOW (CFM)	EXHAUST AIRFLOW (CFM)	OA/SA (%)	REMARKS
RTU-1	3,000	1,100	1,900		37%	
RTU-2	4,500	1,550	2,950		34%	
FC-1	350	0	350		0%	
EF-1				1,215		HOOD-1
EF-2				860		HOOD-2
EF-3				200		RESTROOMS
TOTAL	7,850	2,650	5,200	2,275		
RESULTING BUILDING PRESSURIZATION = 375 CFM						
PRESSURIZATION PERCENTAGE = 4.8 %						

CARRIER EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. CONTACT CARRIER CORPORATION FOR PROPOSALS:
 KEN REVILLA
 CARRIER RETAIL STRATEGIC ACCOUNTS
 EMAIL: KEN.REVILLA@CARRIER.COM
 PHONE: (954) 218-0070

LANDLORD PROVIDED AIR SOURCE HEAT PUMPS													
MARK	LOCATION	SERVES	NOMINAL COOL (TONS)	HEATING AT 47F (MBH)	ELECTRICAL VOLT	PH	MCA	MOCOP	SEER /EER	HSPF /COP	MANUFACTURER	MODEL NUMBER	REMARKS
ASHP-1	ROOF	FC-1	3/4	10.0	208	1	15.0	15	20.5/13.0	10.8/2.93	CARRIER	38MARB009	[1]

REMARKS:
 1. PROVIDE EQUIPMENT WITH SCOR GREATER THAN THE AVAILABLE FAULT CURRENT AT THE EQUIPMENT OR UPSTREAM PANELBOARD.
 REFER TO THE ELECTRICAL ONE LINE DIAGRAM AND PANEL SCHEDULES FOR AVAILABLE FAULT CURRENT AT UPSTREAM PANELBOARD.

LANDLORD PROVIDED DUCTLESS SPLIT SYSTEMS													
MARK	NOMINAL (TONS)	COOLING TOT (MBH)	HEATING SEN (MBH)	OUT (MBH)	SUPPLY AIR (CFM)	FAN (WATT)	ELECTRICAL VOLT	PH	MCA	MOCOP	SEER /EER	CARRIER MODEL NUMBER	REMARKS
FC-1	3/4	11.73	8.79	10.00	350	45	208	1	0.2	N/A	20.5/13.0	40MBC009	[1-3]

REMARKS:
 1. PROVIDE CONDENSATE PUMP.
 2. INDOOR UNIT POWER PROVIDED FROM OUTDOOR UNIT.
 3. PROVIDE NEW, WIRE, FULLY DIGITAL, 7 DAY PROGRAMMABLE TYPE THERMOSTAT WITH AUTO CHANGE OVER AND AUTO SET BACK.

AIR CURTAINS													
MARK	LENGTH (IN)	AIRFLOW (CFM)	HEATER IN (KW)	OUT (MBH)	TEMP RISE (F)	FANS QTY	HP	ELECTRICAL CIRCUIT (QTY)	VOLT	PH	MANUFACTURER	MODEL NUMBER	REMARKS
AC-1	42.0	1,418	NA	NA	NA	1	1/2	1	115	1	MARS	STD242	[1-3]

REMARKS:
 1. PROVIDE AUTOMATIC DOOR SWITCH.
 2. PROVIDE UNIT MOUNTED CONTROL PANEL.
 3. VERIFY FINAL COLOR/FINISH WITH ARCHITECT.

LANDLORD PROVIDED ROOF TOP UNITS																
MARK	SEN (MBH)	TOT (MBH)	COOL (TON)	IN (MBH)	OUT (MBH)	SUPPLY AIR (CFM)	EXT. S.P. (IN)	FAN (BHP)	ELECTRICAL VOLT	PH	MCA	MOCOP	WEIGHT (LBS)	SEER /EER	CAPTIVEAIRE MODEL NUMBER	REMARKS
RTU-1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	[1,2]
RTU-2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	[1,2]

COOLING CAPACITIES ARE BASED ON AHRI STANDARD 210/240 OR 340/360; 80F DB/ 67F WB INDOOR ENTERING AIR TEMPERATURE, 95F DB AIR ENTERING OUTDOOR FAN. SCHEDULED UNIT MAY DIFFER FROM AHRI STANDARD CFM.
 REFERENCE CAPTIVEAIRE DRAWINGS FOR ADDITIONAL INFORMATION.


EXHAUST FANS												
MARK	LOCATION	SERVICE	AIRFLOW (CFM)	EXTERNAL STATIC (IN H2O)	SONES	MOTOR DATA FAN (HP)	VOLT	PH	RPM	MANUFACTURER	MODEL NUMBER	REMARKS
EF-1	ROOF	HOOD 1	-	-	-	-	-	-	-	-	-	[4]
EF-2	ROOF	HOOD 2	-	-	-	-	-	-	-	-	-	[4]
EF-3	ROOF	RESTROOMS	200	0.50	7.0	1/8	115	1	1,550	GREENHECK	G-095-D	[1-3]

REMARKS:
 1. PROVIDE SOLID STATE SPEED CONTROL.
 2. PROVIDE BACKDRAFT DAMPER.
 3. PROVIDE MINIMUM 12 INCH HEIGHT ROOF CURB.
 4. REFERENCE CAPTIVEAIRE DRAWINGS FOR ADDITIONAL INFORMATION.

DIFFUSERS, GRILLES AND REGISTERS							
MARK	SERVICE	LOCATION	CEILING TYPE	MOUNTING TYPE	MANUFACTURER	MODEL NUMBER	REMARKS
D-1	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	TMS XX 24x24 3 26	[1,2,6,9]
D-2	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	PAR XX 24x24 3 26	[1,2,6]
D-3	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	OMNI XX 12x12 3 26	[1,2,4,6]
D-4	SUPPLY	VARIABLE	NA	SURFACE	TITUS	300RL X X 1 26	[1,5-7]
D-5	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	100 MX 3 24x24 3 26 2	[1,2,6-8]
D-6	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	PAR XX 12x24 3 26	[1,2,6]
G-1	RETURN	CEILING	AC TILE	LAY-IN	TITUS	50F X X 3 26	[1,3,5,6]
G-2	EXHAUST	CEILING	GYP. BOARD	SURFACE	TITUS	50F X X 1 26	[1,3,5-7]

REMARKS:
 1. TITUS IS THE BASE OF DESIGN. KRUEGER, PRICE, NAILOR, CARNES ARE EQUAL. NO EXCEPTIONS.
 2. SEE PLAN FOR NECK SIZE.
 3. PROVIDE 1/2" X 1/2" X 1" CORE.
 4. PROVIDE WITH MODEL TRM FRAME.
 5. SEE PLAN FOR SIZE.
 6. DIFFUSERS SHALL BE FINISHED TO MATCH CEILING/WALL/EXPOSED DUCT COLOR. COORDINATE WITH ARCHITECT.
 7. PROVIDE DIFFUSERS AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.
 8. TO BE CONFIGURED AS TWO WAY OPPOSING THROW.
 9. PROVIDE DIRECTIONAL SECTORING BAFFLE AS INDICATED ON THE PLANS.

UV SYSTEMS												
UNIT NO.	PLACEMENT	PHI CELL MODEL #	UV/CELL SIZE	RANGE	INDOOR PPM TARGET	SIZE	TRANSFORMER	POWER	IN-VOLT	OUT-VOLT	MCA	WEIGHT (LBS.)
RTU-1	BLOWER CABINET	PHI-PKG14-24V	14"	3,000-8000 CFM	< 0.02 PPM	2.25"W x 19.5"L x 1.75"D	SHIP LOOSE	11W	115 VAC	24 VAC	0.50A	2 LBS
RTU-2	BLOWER CABINET	PHI-PKG14-24V	14"	3,000-8000 CFM	< 0.02 PPM	2.25"W x 19.5"L x 1.75"D	SHIP LOOSE	11W	115 VAC	24 VAC	0.50A	2 LBS



NO.	BY	DATE	DESCRIPTION
2		2024-07-02	FIELD NOTICE 1
1		2024-06-14	IFC
A		2024-05-07	ADDENDUM A
		2024-03-18	PERMIT / BID SET




NOVI, MI
 43335 CRESCENT BLVD.
 NOVI TOWN, MI 48375
 SHACK #1605

PERMIT / BID SET

MECHANICAL SCHEDULES

DRAWN BY: RAS
 CHECKED BY: GRS
 JOB NO: 20230425.00

M601



HOOD STYLE / MODEL	450 DEGREES cfm/ft.	600 DEGREES cfm/ft.	700 DEGREES cfm/ft.
CANOPY ND-2	150	200	250
CANOPY ND-2 w/ END PANELS	105	140	175
SLOPED SND-2	228	294	—
ISLAND ND-2W	269	300	350
ISLAND ND-2I	346	422	475

ETL HOOD LISTING DETAIL

EXHAUST CFM = LENGTH OF HOOD X CFM/INLET (LOAD)
 SUPPLY CFM = EXHAUST CFM X PERCENTAGE REQUIRED
 TOTAL DUCT AREA (sq. in.) = 144 X (CFM/INLET)
 DUCT LENGTH = TOTAL DUCT AREA / DUCT WIDTH

* CAPTIVE-AIRE HOODS ARE CALCULATED USING AN EXHAUST VELOCITY OF 1500-1800 FPM AND A SUPPLY VELOCITY OF 1000 FPM.

CALCULATIONS UTILIZED

CAPTIVE-AIRE HOODS BUILT IN COMPLIANCE WITH:

ETL LISTED
 3054804-001 & 3054804-002
 STANDARD 710
 Intertek
 BUILT TO ACCORDANCE WITH IASME No. 96
 Listed under ETL File number 3054804-001/002


BUILDING CODES

CAPTIVE-AIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:

MATERIAL	CLEARANCE REDUCTION SYSTEM
NON-COMBUSTIBLE	NONE REQUIRED
LIMITED-COMBUSTIBLE	3" UNINSULATED STANDOFF
COMBUSTIBLE	1" INSULATED STANDOFF

- CLEARANCE TO COMBUSTIBLES**
- INSTALLATION**
- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
 - ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
 - HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
 - ALL CONNECTIONS FROM CAPTIVE-AIRE HOOD PER MECHANICAL CONTRACTOR'S PLANS.
 - COOKING EQUIPMENT TO SHUT OFF IN EVENT OF FIRE.
 - EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
 - ALL LIGHT FIXTURES SHOWN INSTALLED BY CAPTIVE-AIRE ARE FACTORY PREWIRED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES ARE BY ELECTRICAL CONTRACTOR.
 - LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
 - SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
 - INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTEGRATION, AND ADMINISTRATION OF CODE REQUIREMENTS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.

- BALANCE**
- KITCHEN HOODS MUST BE BALANCED WITH KITCHEN.
 - KITCHEN SHALL BE NEGATIVE WITH RESPECT TO DINING AREA.
 - RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.
- ADDITIONAL**
- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
 - SIGNED AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE RECEIVED BY THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.



FOR QUESTIONS, CALL THE
 Eastern PA Mechanical
 REGION 108
 PHONE: (267) 504 - 4126
 EMAIL: reg108@captiveaire.com

HOOD INFORMATION — JOB#6621005





HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST PLENUM RISER(S)				HOOD CONSTRUCTION	HOOD CONFIG			
										WIDTH	LENG	HEIGHT	DIA		CFM	VEL	SP	END TO END
1	Hood (Grill)	5430 ND-2	CAPTIVEAIRE	7' 11"	450 DEG	I	MEDIUM	150	1188	10'	11'	4'	1188	1555	-0.462'	430 SS WHERE EXPOSED	ALDNE	ALDNE
2	Hood (Fryer)	5430 ND-2	CAPTIVEAIRE	4' 11"	450 DEG	I	MEDIUM	175	860	9'	9'	4'	860	1529	-0.494'	430 SS WHERE EXPOSED	ALDNE	ALDNE

HOOD INFORMATION

HOOD NO	TAG	TYPE	FILTER(S)			LIGHT(S)			UTILITY CABINET(S)			FIRE SYSTEM	HOOD HANGING WEIGHT				
			QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE			TYPE	SIZE	MODEL #	QUANTITY
1	Hood (Grill)	CAPTRATE SOLD FILTER	5	20"	16"	85% SEE FILTER SPEC	3	RECESSED ROUND	NO				YES	484 LBS			
2	Hood (Fryer)	CAPTRATE SOLD FILTER	3	20"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO	LEFT	12"x54"x30"	TANK FS	4.0/4.0/4.0	SC-320110MA	1 LIGHT 1 FAN	YES	756 LBS

HOOD OPTIONS

HOOD NO	TAG	OPTION
1	Hood (Grill)	FIELD WRAPPER 18'00" HIGH FRONT, LEFT, RIGHT. RIGHT END STANDOFF (FINISHED) 1' WIDE 54" LONG INSULATED. RISER SENSOR INSTALL 6IN PLEN. LEFT VERTICAL END PANEL 27" TOP WIDTH, 21" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS. RIGHT WALL AS END PANEL.
2	Hood (Fryer)	FIELD WRAPPER 18'00" HIGH FRONT, LEFT, RIGHT. RIGHT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. LEFT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. INSULATION FOR BACK OF HOOD. RISER SENSOR INSTALL 6IN PLEN.



REVISIONS

NO.	DESCRIPTION	DATE
2		
1		
A		

CAPTIVEAIRE

Eastern PA Mechanical
 PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 504 - 4126 EMAIL: reg108@captiveaire.com

ShakeShack-1605-Novi, MI(Kitchen)_R1
 Novi, MI, 48375

DATE: 2/22/2024
 DWG #: 6621005
 DRAWN BY: joe.shilba
 SCALE: 3/4" = 1'-0"
 MASTER DRAWING
 SHEET NO. 1

Bergmeyer

CONSULTANTS:

Schnackel engineers
 New York • Miami • Chicago • Los Angeles • Seattle • Honolulu
 900-981-0863 www.schnackel.com

MEPF ENGINEER
 3035 S 72ND ST
 OMAHA NE 68124
 TEL 402.391.7680

SEAL SIGNATURE:

DATE: 07/02/24

2	2024-07-02	FIELD NOTICE 1
1	2024-06-14	IFC
A	2024-05-07	ADDENDUM A
	2024-03-18	PERMIT / BID SET

SHAKE SHACK

NOVI, MI


43335 CRESCENT BLVD.
 NOVI TOWN, MI 48375
 SHACK #1605

PERMIT / BID SET


CAPTIVEAIRE DRAWINGS

DRAWN BY: RAS
 CHECKED BY: GRS
 JOB NO: 20230423.00


M701




PLAN VIEW - HOOD #1 (Hood Grill)
7' 11.00" LONG 5430ND-2



PLAN VIEW - HOOD #2 (Hood Fryer)
4' 11.00" LONG 5430ND-2



SECTION VIEW - MODEL 5430ND-2
HOOD - #1 (Hood Grill)



SECTION VIEW - MODEL 5430ND-2
HOOD - #2 (Hood Fryer)

REVISIONS	
DESCRIPTION	DATE

CAPTIVEAIRE
Eastern, PA Mechanical
PO Box 2520, 1 Union Ave., Bala Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg.06@captivaire.com

ShakeShack-1605-Nov,MI(Kitchen)_R1
Novi, MI, 48375

DATE: 2/22/2024
DWG #: 6621005
DRAWN BY: joe.shilka
SCALE: 3/4" = 1'-0"
MASTER DRAWING
SHEET NO. 2

Bergmeyer
LA 800 South Figueroa St. Los Angeles, CA 90017
CO 875 N High St. Columbus, OH 43215
BOS 51 Shepley St. Boston, MA 02210
617.542.1025 380.900.8867 www.bergmeyer.com

CONSULTANTS:
Schnackel engineers
New York • Miami • Chicago • Los Angeles • Seattle • Honolulu
900-981-0963 www.schnackel.com

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL SIGNATURE:

NO.	BY	DATE	DESCRIPTION
2		2024-07-02	FIELD NOTICE 1
1		2024-06-14	IFC
A		2024-05-07	ADDENDUM A
		2024-03-18	PERMIT / BID SET

SHAKE SHACK
NOVI, MI
43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605
PERMIT / BID SET

CAPTIVEAIRE DRAWINGS
DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 20230423.00

M702

FIRE SYSTEM INFORMATION - JOB#6621005

FIRE SYSTEM NO	TAG	TYPE	SIZE	MAX FP	DESIGN FP	INSTALLATION	
						SYSTEM	LOCATION ON HOOD
1		TANK FS	4.0/4.0/4.0	60	46	FIRE CABINET LEFT	LEFT, HOOD 2

CAS VALVE(S)

FIRE SYSTEM NO	TAG	TYPE	SIZE	SUPPLIED BY
1		SC ELECTRICAL	1.000	CAPTIVEAIRE SYSTEMS

NOTES

- FIELD PIPE DROPS AS SHOWN. PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
- FIELD INSTALLED DROP: FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
- SHIP LOOSE DROP: FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
- RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVING, SALAMANDERS, ETC.
- OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
- IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
- FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.

- APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.

- THIS FIRE SYSTEM COMPLIES WITH UL 300 REQUIREMENTS.

- DL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS

JOB #: 6621005.

JOB NAME: SHAKESHACK-1605-NOVI,MI(KITCHEN)_R1.

SYSTEM SIZE: TANK-SP-3 DESIGN FP: 46, MAXIMUM FP: 60.

HOOD # 1 7' 11.00" LONG x 54" WIDE x 30" HIGH.

RISER # 1 SIZE: 10" x 11".

HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.

HOOD # 2 4' 11.00" LONG x 54" WIDE x 30" HIGH.

RISER # 1 SIZE: 9" x 9".



HOOD # 2 METAL BLOW-OFF CAPS INCLUDED.

- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

LEGEND - FIRE CABINET TANK SYSTEM

- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.


- SYSTEM REQUIRES A MINIMUM OF 7 FT OF EQUIVALENT PIPE LENGTH BETWEEN TANK AND NEAREST APPLIANCE NOZZLE FOR MOST APPLIANCES. EACH 90 DEGREE ELBOW ADDS 1.3 FT OF EQUIVALENT LENGTH. SEE MANUAL FOR DETAILS.




ALTERNATE FIELD-CONNECTION POINT

FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.

FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.



REVISIONS	
DESCRIPTION	DATE



ShakeShack-1605-Nov,MI(Kitchen)_R1
Novi, MI, 48375

DATE:	2/22/2024
DWG.#:	6621005
DRAWN BY:	Joe.shiiba
SCALE:	3/4" = 1'-0"
MASTER DRAWING	
SHEET NO.	3

CONSULTANTS:

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL SIGNATURE:

NO.	BY	DATE	DESCRIPTION
2		2024-07-02	FIELD NOTICE 1
1		2024-06-14	IFC
A		2024-05-07	ADDENDUM A
		2024-03-18	PERMIT / BID SET

NOVI, MI

43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605

PERMIT / BID SET

CAPTIVEAIRE DRAWINGS

DRAWN BY:	RAS
CHECKED BY:	GRS
JOB NO.:	20230423.00

M703

EXHAUST FAN INFORMATION - JOB#6621005

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	MANUFACTURER	CFM	ESP	RPM	MOTOR ENCL	HP	BHP	PHASE	VOLT	FLA	DISCHARGE VELOCITY	WEIGHT (LBS)	SDNES
1	KEF(GRILL)	1	DUBSHFA	CAPTIVEAIRE	1212	1.500	1431	TEAD-ECM	0.750	0.5030	1	208	5.2	384 FPM	90	12.7
2	KEF(FRYER)	1	DUBSHFA	CAPTIVEAIRE	860	1.500	1354	TEAD-ECM	0.750	0.4270	1	208	5.2	272 FPM	90	11.4

FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	KEF(GRILL)	1	GREASE BOX
		1	ECM WIRING PACKAGE - EXHAUST - MODBUS CONTROL -MSC- (TELCD), CCW ROTATION
		1	FAN BASE CERAMIC SEAL - DU/DRB5HFA - INSTALLED AT PLANT - FOR GREASE DUCTS
		1	2 YEAR PARTS WARRANTY
2	KEF(FRYER)	1	GREASE BOX
		1	ECM WIRING PACKAGE - EXHAUST - MODBUS CONTROL -MSC- (TELCD), CCW ROTATION
		1	FAN BASE CERAMIC SEAL - DU/DRB5HFA - INSTALLED AT PLANT - FOR GREASE DUCTS
		1	2 YEAR PARTS WARRANTY


FAN ACCESSORIES

FAN UNIT NO	TAG	EXHAUST				SUPPLY		
		GREASE CUP	GRAVITY DAMPER	WALL MOUNT	SIDE DISCHARGE	GRAVITY DAMPER	MOTORIZED DAMPER	WALL MOUNT
1	KEF(GRILL)	YES						
2	KEF(FRYER)	YES						


CURB ASSEMBLIES

NO	DN FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	KEF-1	36 LBS	CURB	23.000"W X 23.000"L X 20.000"H HINGED.
2	# 2	KEF(FRYER)	36 LBS	CURB	23.000"W X 23.000"L X 20.000"H HINGED.

FANS #1 (KEF(GRILL)) #2 (KEF(FRYER)) - DUBSHFA EXHAUST FAN



DUCTWORK BETWEEN EXHAUST RISER ON HOOD AND FAN (BY OTHERS).



TOP VIEW

FEATURES:

- DIRECT DRIVE CONSTRUCTION (NO BELTS/PULLEYS).
- ROOF MOUNTED FANS.
- RESTAURANT MODEL.
- UL705 AND UL762 AND ULC-S645
- VARIABLE SPEED CONTROL.
- INTERNAL WIRING.
- THERMAL OVERLOAD PROTECTION (SINGLE PHASE).
- HIGH HEAT OPERATION 300°F (149°C).
- GREASE CLASSIFICATION TESTING.
- NEMA 3R SAFETY DISCONNECT SWITCH.

NORMAL TEMPERATURE TEST




EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING AIR AT 300°F (149°C) UNTIL ALL FAN PARTS HAVE REACHED THERMAL EQUILIBRIUM, AND WITHOUT ANY DETERIORATING EFFECTS TO THE FAN WHICH WOULD CAUSE UNSAFE OPERATION.

ABNORMAL FLARE-UP TEST

EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING BURNING GREASE VAPORS AT 600°F (316°C) FOR A PERIOD OF 15 MINUTES WITHOUT THE FAN BECOMING DAMAGED TO ANY EXTENT THAT COULD CAUSE AN UNSAFE CONDITION.

OPTIONS

- GREASE BOX.
- ECM WIRING PACKAGE - EXHAUST - MODBUS CONTROL -MSC- (TELCD), CCW ROTATION.
- FAN BASE CERAMIC SEAL - DU/DRB5HFA - INSTALLED AT PLANT - FOR GREASE DUCTS.
- 2 YEAR PARTS WARRANTY.



REVISIONS

NO.	DESCRIPTION	DATE

CAPTIVEAIRE

Eastern, PA, Mechanical
PO Box 2500, Union Ave, Balla Cynwyd, PA, 19004 PHONE: (267) 604-4126 EMAIL: reg.08@captiveaire.com

ShakeShack-1605-NOVI,MI(Kitchen)_R1
Novi, MI, 48375

DATE: 2/22/2024
DWG.#: 6621005
DRAWN BY: Joe.shiiba
SCALE: 3/4" = 1'-0"
MASTER DRAWING
SHEET NO. 4

Bergmeyer

CONSULTANTS:

Schnackel engineers

MEPP ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL SIGNATURE:

GREGORY SCHNACKEL
ENGINEER
No. 37570
Date: 07/02/24

SHAKE SHACK

NOVI, MI

43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605

PERMIT / BID SET


CAPTIVEAIRE DRAWINGS

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 20230423.00

M704

ELECTRICAL PACKAGE - JOB#6621005

NO	TAG	PACKAGE #	LOCATION	SWITCHES		OPTION	FANS CONTROLLED					
				LOCATION	QUANTITY		FAN TAG	TYPE	#	HP	VOLT	FLA
1		SC-320110A	UTILITY CABINET LEFT	UTILITY CABINET LEFT	1 LIGHT	SMART CONTROLS THERMOSTATIC CONTROL W/ RELAY ON/OFF WITH SUPPLY	KEFCGRILL	EXHAUST	1	0.750	208	5.2
				HOOD # 2	1 FAN		KEFCFYER	EXHAUST	1	0.750	208	5.2








CASink Monitor and Control

Head control panel to support communications to cloud-based Building Management System.
 Head Control Panel to allow cloud-based Building Management System to monitor real time parameters outlined as MONITOR on the points list.
 Head Control Panel to allow cloud-based Building Management System to control parameters outlined as CONTROL on the points list.
 Head Control Panel to allow cloud-based Building Management System to implement SYSTEM ECONOMIZER control strategies for fully integrated Building Management.

MONITORING AND CONTROL POINTS LIST

DCV Packages	Function	SC Packages	Function
Room Temperature	MONITOR	Room Temperature(s)	MONITOR
Duct Temperature(s)	MONITOR	Duct Temperature(s)	MONITOR
MHA Discharge Temperature	MONITOR	MHA Discharge Temperature	MONITOR
Kitchen RTU Discharge Temperature	MONITOR	Kitchen RTU Discharge Temperature	MONITOR
Fan Speed	MONITOR	Control Panel Fan	MONITOR
Fan Amperage	MONITOR	Fan Status	MONITOR
Fan Power	MONITOR	Fan Failure	MONITOR
VFD Faults	MONITOR	PCU Filter Clog Percentages	MONITOR
Control Panel Faults	MONITOR	PCU Filter Clog Percentages	MONITOR
Fan Status	MONITOR	Fire Condition	MONITOR
PCU Failure	MONITOR	Building Pressure	MONITOR
PCU Filter Clog Percentages	MONITOR	PCU Filter Clog Percentages	MONITOR
Fire Condition	MONITOR	Light(s) Status	MONITOR
CORE Fire System	MONITOR	Wash Status	MONITOR
Building Pressure	MONITOR	Prep Time Status	MONITOR
Prep Time Status	MONITOR	Fan Status	MONITOR
Fan Status	MONITOR	Wash Status	MONITOR



REVISIONS

NO.	DESCRIPTION	DATE
1		
2		
3		

CAPTIVE
 Eastern, PA Mechanical
 PO Box 2520, 1 Union Ave, Bala Cynwyd, PA, 19004 PHONE: (267) 304-4128 EMAIL: raj108@captivate.com

ShakeShack-1605-Novi, MI (Kitchen)_R1
 Novi, MI, 48375

DATE: 2/22/2024
 DWG #: 6621005
 DRAWN BY: Joe,shiiba
 SCALE: 3/4" = 1'-0"
 MASTER DRAWING

SHEET NO. 5

CONSULTANTS:

MEPF ENGINEER
 3035 S 72ND ST
 OMAHA NE 68124
 TEL 402.391.7680

SEAL SIGNATURE:

DATE: 07/02/24

NO.	BY	DATE	DESCRIPTION
2		2024-07-02	FIELD NOTICE 1
1		2024-06-14	IFC
A		2024-05-07	ADDENDUM A
		2024-03-18	PERMIT / BID SET

NOVI, MI


43335 CRESCENT BLVD.
 NOVI TOWN, MI 48375
 SHACK #1605

PERMIT / BID SET

CAPTIVEAIRE DRAWINGS


DRAWN BY: RAS
 CHECKED BY: GRS
 JOB NO: 20230420.00

M705



1 GALLON GREASE COLLECTION BOX AND WALL MOUNTING BRACKET SHIPPED LOOSE FOR FIELD INSTALLATION BY MECHANICAL CONTRACTOR.

EQUIPMENT BY OTHERS




One Gallon Grease Cup Installation



Instructions below outline single, or dual, one gallon grease cup installation for ND-2 hood models.

The one gallon grease cup comes as an assembly of stainless steel wall mounting bracket and one gallon cup. The mounting bracket should be installed 2" from the edge of the containment plenum and 3"-4" below the bottom of the hood.


Piping from the hood grease drain should route to the opening of the grease cup, but not into the cup, otherwise the cup will not be able to be removed and emptied.



Left & Right hand Grease Cup Install



Gallon Grease Cup Assembly



1 GALLON GREASE COLLECTION BOX AND WALL MOUNTING BRACKET SHIPPED LOOSE FOR FIELD INSTALLATION BY MECHANICAL CONTRACTOR.

REVISIONS	
DESCRIPTION	DATE

CAPTIVE

Eastern, P.A. Mechanical
 PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 504-4128 EMAIL: reg.108@captiveaire.com

ShakeShack-1605-Novi,MI(Kitchen)_R1
 Novi, MI, 48375

DATE:	2/22/2024
DWG #:	6621005
DRAWN BY:	joe.shilka
SCALE:	3/4" = 1'-0"
MASTER DRAWING	
SHEET NO.	6

Bergmeyer

CONSULTANTS:

Schnackel engineers

MEPP ENGINEER
 3035 S 72ND ST
 OMAHA NE 68124
 TEL 402.391.7680

SEAL SIGNATURE:

GREGORY SCHNACKEL
 ENGINEER
 No. 37570
 Date: 07/02/24

SHAKE SHACK

NOVI, MI

4335 CRESCENT BLVD.
 NOVI TOWN, MI 48375
 SHACK #1605

PERMIT / BID SET

NO.	BY	DATE	DESCRIPTION
2		2024-07-02	FIELD NOTICE 1
1		2024-06-14	IFC
A		2024-05-07	ADDENDUM A
		2024-03-18	PERMIT / BID SET

DRAWN BY:	RAS
CHECKED BY:	GRS
JOB NO:	20230423.00

M706

DOAS/RTU FAN SCHEDULE - JOB#6359597

FAN UNIT NO	TAG	QTY	DOAS/RTU MODEL #	FAN INFORMATION				ELECTRICAL INFORMATION					COOLING INFORMATION					REHEAT INFORMATION					GAS HEAT INFORMATION					NOTES									
				MANUFACTURER	BLOWER	RETURN AIR CFM	MAX OUTSIDE AIR CFM	TOTAL CFM	WEIGHT (LBS)	ESP	HP	PHASE	VOLT	MCA	MDCP	DB	WB	DB	WB	DB	WB	DP	TOTAL	SENS.	IEER	ISMRE	DISCHARGE		REHEAT CAPACITY	MOISTURE REMOVAL RATE	GAS TYPE	INPUT BTUS	OUTPUT BTUS	TEMP RISE	REQUIRED INPUT GAS PRESSURE		
1	RTU-1 (DINING)	1	CASRTU3-1200-18-1ST	CAPTIVEAIRE	18P-3	1900	1100	3000	2529	1.000	5.00	3	208	70.3A	80A	88.0°F	73.0°F	79.8°F	66.4°F	52.0°F	52.0°F	52.1°F	124.5 MBH	87.2 MBH	18.8	5.7	70.0°F	59.2°F	59.3 MBH	129.6 MBH	34.3 LBS/HR	NATURAL	200000	162000	49°F	7 IN. W.C. - 14 IN. W.C.	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17
2	RTU-2 (KITCHEN)	1	CASRTU3-1250-24-20T	CAPTIVEAIRE	24MF-3-RTU	2900	1600	4500	2806	1.000	5.00	3	208	92.4A	100A	81.9°F	75.9°F	77.5°F	67.5°F	51.4°F	51.4°F	51.5°F	212.0 MBH	123.5 MBH	18.2	6.0	70.0°F	58.8°F	92 MBH	129.6 MBH	61.2 LBS/HR	NATURAL	250000	202500	41°F	7 IN. W.C. - 14 IN. W.C.	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18

NOTES:

- INVERTER SCROLL COMPRESSOR WITH INTEGRATED OIL SENSOR. DIGITAL OR STAGED SCROLL NOT AN APPROVED EQUAL
- DIRECT DRIVE PLENUM BLOWER. BELT DRIVEN BLOWERS ARE NOT ACCEPTABLE
- INTEGRATED MONITORING VIA CELLULAR CONNECTION BY MANUFACTURER
- REFRIGERATION PRESSURE MONITORING ON HIGH AND LOW PRESSURE SIDE OF SYSTEM INCLUDED THROUGH DIGITAL INTERFACE
- EC MOTOR CONDENSING FANS
- ELECTRONIC EXPANSION VALVE. TXV NOT ACCEPTABLE
- SUCTION LINE ACCUMULATOR
- FACTORY COMMISSIONING WITH 5 YEAR PARTS WARRANTY, 25 YEAR WARRANTY ON STAINLESS STEEL HEAT EXCHANGER
- AVERAGING INTAKE, EVAP AND DISCHARGE TEMPERATURE SENSORS (DISCHARGE SENSOR TO BE FACTORY MOUNTED WITHIN UNIT)
- 2" EXTERIOR DUAL-WALL CONSTRUCTION W/ 8-13 INSULATION-MINIMUM 200A EXTERIOR W/ 14GA BASE
- 81% EFFICIENT FURNACE WITH MODULATING INDUCER TO MAINTAIN CONSTANT COMBUSTION EFFICIENCY ACROSS FIRING RANGE. 6:1 TURNDOWN WITH NG AND 5:1 TURNDOWN WITH LP
- SUPPLY CFM MONITORING INTEGRAL TO UNIT WITH CFM MEASUREMENT INCLUDED THROUGH DIGITAL INTERFACE
- FULLY MODULATING HOT GAS REHEAT
- HAIL GUARD FOR CONDENSING COIL
- RTU ECONOMIZER WITH DIFFERENTIAL ENTHALPY CONTROL
- BAROMETRIC RELIEF DAMPER
- DOWN DISCHARGE/DOWN RETURN


18. 15 DEGREE LOW AMBIENT OPERATION

FOR QUESTIONS, CALL THE

Eastern PA Mechanical
REGION 108
PHONE: (267) 504 - 4126
EMAIL: reg108@captiveaire.com

FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	RTU-1 (DINING)	1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE
		1	RTU TOTAL CFM MONITORING
		1	INTAKE FIRESTAT SET TO 135°F
		1	FREESTAT
		1	DISCHARGE FIRESTAT SET TO 240°F
		1	SHIP LOOSE GAS STRAINER 3/4"
		1	SINGLE POINT ELECTRICAL CONNECTION FOR RTU. 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #2B, #47, #4A, OR #2P PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE
		1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
		1	RTU3 DOWN DISCHARGE
		1	2" MERV 13 FILTERS FOR RTU3 (QTY. 4)
		1	2" MERV 8 FILTERS FOR RTU3 (QTY. 4)
		1	OVERHEAT STAT
		1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
		1	15 TON MODULATING COOLING OPTION, 208/230V. R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS
		1	15 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL
		1	RTU3 CURB DUCT HANGER
		1	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS
		1	OCCUPIED SCHEDULING
		1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI
		1	RTU3 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX
		1	RTU ECONOMIZER - DIFFERENTIAL ENTHALPY CONTROL
		1	RTU3 ECONOMIZER BAROMETRIC RELIEF
		1	RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI
		1	RTU3 HAIL GUARD
1	RTU3 DOWN RETURN		
1	REMOTE TEMPERATURE AND HUMIDITY SPACE SENSOR		
1	VAV PACKAGE W/ MANUAL/DDC CONTROL (S71 VFD INCLUDED)		
1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS)		
2	RTU-2 (KITCHEN)	1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE
		1	RTU TOTAL CFM MONITORING
		1	INTAKE FIRESTAT SET TO 135°F
		1	FREESTAT
		1	DISCHARGE FIRESTAT SET TO 240°F
		1	SHIP LOOSE GAS STRAINER 1"
		1	SINGLE POINT ELECTRICAL CONNECTION FOR RTU. 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #2B, #47, #4A, OR #2P PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE
		1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
		1	RTU3 DOWN DISCHARGE
		1	2" MERV 13 FILTERS FOR RTU3 (QTY. 4)
		1	2" MERV 8 FILTERS FOR RTU3 (QTY. 4)
		1	OVERHEAT STAT
		1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
		1	20 TON MODULATING COOLING OPTION, 208/230V. R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS
		1	20 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL
		1	RTU3 CURB DUCT HANGER
		1	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS
		1	OCCUPIED SCHEDULING
		1	LOW AMBIENT COOLING OPERATION - DOWN TO 0°F AMBIENT
		1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI
		1	RTU3 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX
		1	RTU ECONOMIZER - DIFFERENTIAL ENTHALPY CONTROL
		1	ZIEHL-PHONIX EXHAUST FAN FOR RTU3 - MANUAL CONTROL. 3000 CFM MAX AT 0"
		1	RTU3 ECONOMIZER BAROMETRIC RELIEF
1	RTU3 DOWN RETURN		
1	RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI		
1	RTU3 HAIL GUARD		
1	VAV PACKAGE W/ MANUAL/DDC CONTROL (S71 VFD INCLUDED)		
1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS)		



CURB ASSEMBLIES

NO	DN FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	RTU-1 (DINING)	104 LBS	CURB	59.500"W X 91.000"L X 14.000"H INSULATED.
2	# 2	RTU-2 (KITCHEN)	104 LBS	CURB	59.500"W X 91.000"L X 14.000"H INSULATED.

HMI SCHEDULE

UNIT NUMBER	HMI #	HMI LOCATION	TEMP AVERAGING	MODBUS ADDRESS	
FAN #1	HMI #1 - UNIT	HMI #1	MOUNTED IN UNIT	NOT AVERAGED	55
FAN #1	HMI #2 - SPACE	HMI #1		AVERAGED	56
FAN #2	HMI #1 - UNIT	HMI #1	MOUNTED IN UNIT	NOT AVERAGED	55
FAN #2	HMI #2 - SPACE	HMI #1		AVERAGED	56

REVISIONS

DESCRIPTION	DATE

CAPTIVEAIRE
www.captiveaire.com
Eastern PA Mechanical
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA, 19004 PHONE: (267) 504 - 4126 EMAIL: reg108@captiveaire.com

Shack Shack-1605-NOVI,MI(KHVAC)
NORTHVILLE, MI, 48167

DATE: 2/19/2024

DWG.#: 6359597

DRAWN BY: joe.shilba

SCALE: 1/2" = 1'-0"

MASTER DRAWING

SHEET NO. 1



CONSULTANTS:
Schnackel engineers
MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL SIGNATURE:

NO.	BY	DATE	DESCRIPTION
2		2024-07-02	FIELD NOTICE 1
1		2024-06-14	IFC
A		2024-05-07	ADDENDUM A
		2024-03-18	PERMIT / BID SET

SHAKE SHACK
NOVI, MI
43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605

PERMIT / BID SET


CAPTIVEAIRE DRAWINGS

DRAWN BY: RAS

CHECKED BY: GRS

JOB NO: 20230423.00



M707



CURB OUTLINE
91" x 59 1/2"

RETURN CUTOUT. (738 LBS)

(896 LBS)



LOUVERED OUTSIDE AIR INTAKE.

68 1/4"

52 3/4"


4 1/4"

59 1/2"

65 1/4"

89 3/4"

1" NPT SS EVAPORATOR DRAIN (TRAP REQ'D), 4" MINIMUM TRAP DEPTH.




FACTORY INSTALLED SAFETY DISCONNECT SWITCH.


3/4" NPT SS GAS CONNECTION.

MINIMUM STRAIGHT DUCT PER AMCA*

MIN. 21.5"



14"



9 1/2" DUCT HANGER WIDTH, TYP.

9 5/8"

14 1/2"

59 1/2"

47 3/8"



22"

39 3/8"

15 5/8"

40 3/8"

18 3/8"



FAN #2 CASRTU3-1.250-24MF-20T - HEATER (RTU-2 (KITCHEN))

- NOTES:
- DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
 - () DENOTES CORNER WEIGHT.
 - ROOF OPENING MUST BE 2" SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.
 - CONNECTION FROM BREAKER TO UNITS SAFETY DISCONNECT SWITCH TO BE COPPER WIRE ONLY.

REVISIONS

NO.	DESCRIPTION	DATE

www.captiveaire.com

Eastern, PA Mechanical

PO Box 2520, 1 Union Ave, Bala Cynwyd, PA, 19004 PHONE: (267) 504 - 4126 EMAIL: reg10@captivaire.com

Shake Shack-1605-Novi, MI (HVAC)

NORTHVILLE, MI, 48167

DATE: 2/19/2024

DWG.#: 6359597

DRAWN BY: joe.shilba

SCALE: 1/2" = 1'-0"

MASTER DRAWING

SHEET NO. 3

Bergmeyer

LA 800 South Figueroa St. Los Angeles, CA 90017

CO 875 N High St. Columbus, OH 43210

BOS 51 Shepley St. Boston, MA 02210

617.542.1025 380.900.8867 www.bergmeyer.com

CONSULTANTS:

Schnackel engineers

New York • Miami • Chicago • Los Angeles • Seattle • Honolulu

300-981-0963 www.schnackel.com

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL SIGNATURE:

2	2024-07-02	FIELD NOTICE 1
1	2024-06-14	IFC
A	2024-05-07	ADDENDUM A
	2024-03-18	PERMIT / BID SET

SHAKE SHACK

NOVI, MI

43335 CRESCENT BLVD.
NOVI TOWN, MI 48375
SHACK #1605

PERMIT / BID SET

CAPTIVEAIRE DRAWINGS

DRAWN BY: RAS

CHECKED BY: GRS

JOB NO: 20230423.00

M709