

DEMOLITION NOTES:

1. EXISTING ROUTING AND LOCATION OF DUCTWORK, PIPING, EQUIPMENT, ETC. SHOWN, ARE BASED ON PREVIOUS CONTRACT DOCUMENTS. CONTRACTOR TO VERIFY EXISTING CONDITIONS FOR DISCREPANCIES.
2. ALL EXISTING WALLS, CEILINGS, FLOOR SLABS, ROOF, ETC., BEING CUT OR DAMAGED UNDER THIS CONTRACT TO BE PATCHED BACK TO MATCH EXISTING FINISH AND FIRE PROTECTION RATING. COORDINATE REQUIREMENTS WITH ARCHITECTURAL.
3. PRIOR TO DEMOLITION WORK COMMENCING, CONTRACTOR TO COORDINATE WITH OWNER FOR DISPOSITION OF EXISTING EQUIPMENT TO BE REMOVED. CONTRACTOR TO REMOVE ITEMS TO BE RETAINED BY OWNER AND TRANSPORT THEM TO A PREDETERMINED AREA FOR STORAGE BY OWNER. ALL OTHER ITEMS TO BE REMOVED FROM SITE AND DISPOSED OF AT CONTRACTOR'S EXPENSE.
4. IN AREAS OF RENOVATION, THE EXISTING DUCT MAINS AND BRANCH LINES, PIPING, AND CONDUIT SHALL BE RAISED OR RELOCATED AS NECESSARY TO ALLOW FOR THE INSTALLATION OF NEW DUCTWORK AND PIPING AND MAINTAIN NEW CEILING HEIGHTS AS SET BY THE ARCHITECTURAL PLANS.
5. CONTRACTOR TO REMOVE EXISTING MECHANICAL EQUIPMENT AND APPURTENANCES AS INDICATED FROM EXISTING BUILDING.
6. CONTRACTOR TO COORDINATE WITH ELECTRICAL CONTRACTOR FOR REMOVAL OF EXISTING CONDUIT AND WIRING FEEDING EXISTING MECHANICAL EQUIPMENT TO BE REMOVED.
7. PRIOR TO ANY WORK COMMENCING USE DUCT TRAVERSES TO MEASURE AIRFLOW AT LOCATIONS INDICATED ON PLANS BY ✱. TYPICAL OF 20 LOCATIONS. RECORD READINGS AND FURNISH TO ENGINEER FOR REVIEW. FOR ROOF MOUNTED EQUIPMENT DUCT TRAVERSES TO BE TAKEN IN DUCT ABOVE CEILING ON THE FLOOR BELOW.
8. COORDINATE WITH GENERAL CONTRACTOR AND HOSPITAL STAFF FOR PHASING AND SHUT DOWN OF EXISTING AHUS. NEW UNITS ARE TO BE IN PLACE AND OPERATIONAL BEFORE EXISTING UNIT IS REMOVED.

DEMOLITION LEGEND

— EXISTING TO REMAIN

/// DEMOLITION

3RD FLOOR HVAC DEMOLITION PLAN - PART B
SCALE: 1/8" = 1'-0"



