

- GENERAL NOTES**
- GENERAL CONTRACTOR TO FIELD VERIFY STRUCTURAL ELEVATIONS FOR ADEQUATE SPACE FOR NEW DUCTWORK, PIPING, AND EQUIPMENT ABOVE THE CEILING. NOTIFY OWNER AND DESIGNER IMMEDIATELY OF ANY SUSPECTED INSTALLATION OR FIELD ISSUES RELATING TO THIS SPACE.
 - DRILLING, WELDING, SCREWING, OR SHOOTING INTO LANDLORD'S BUILDING STRUCTURE SHALL NOT BE PERMITTED. ALTERNATIVE METHODS OF ATTACHMENT ONLY. ATTACH REQUIRED EQUIPMENT, NONDESTRUCTIVELY, TO OR SUSPEND FROM THE TOP CHORD OF THE JOIST OR STRUCTURAL STEEL WHICH EXISTS ABOVE THE TENANT SPACE.
 - ALL ROOF PENETRATIONS TO ROOF MUST BE APPROVED BY LANDLORD. ALL ROOF WORK MUST BE DONE BY DOMAIN NORTHSIDE ROOFING CONTRACTOR AS APPROVED BY LANDLORD.
 - ALL ROOFTOP EQUIPMENT SHALL BE MECHANICALLY FASTENED TO ROOF.
 - ALL PIPING ON ROOF SHALL BE SUPPORTED ON PRE-MANUFACTURED PIPE SUPPORTS INSTALLED ON CARRY TREAD, SPACED PROPERLY TO SUPPORT PIPING.

- KEYED NOTES**
- ROUTE SUPPLY AND RETURN DUCTS DOWN FROM THE RTU CONNECTIONS AND TRANSITION THROUGH THE ROOF TO SIZES SHOWN. INSTALL COMPLETE WITH FLEXIBLE CONNECTIONS AT EQUIPMENT. PROVIDE 1/2" INTERNALLY LINED ACOUSTIC INSULATION FOR RETURN DUCTWORK AND THE FIRST 10'-0" OF SUPPLY DUCTWORK.
 - FACTORY AVAILABLE SMOKE DETECTOR CAPABLE OF SHUTTING DOWN THE RESPECTIVE MECHANICAL UNIT UPON ACTIVATION.
 - WALL MOUNTED REMOTE ZONE TEMPERATURE AND HUMIDITY SENSOR SHALL BE MOUNTED AT 48" AFF. AND WIRED BACK TO PROGRAMMABLE THERMOSTAT IN MANAGER'S OFFICE. VERIFY PLACEMENT WITH THE ARCHITECTURAL FLOOR PLAN AND OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.
 - WALL MOUNTED PROGRAMMABLE THERMOSTAT IN MANAGER'S OFFICE. VERIFY PLACEMENT WITH THE ARCHITECTURAL FLOOR PLAN AND OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.
 - ROUTE THE COMBUSTION AIR INTAKE AND EXHAUST PIPING FROM THE WATER HEATERS TO TERMINATION LOCATIONS ON THE ROOF. INSTALL WITH THE MINIMUM ELBOWS AND OFFSETS AS NECESSARY FOR A COMPLETE INSTALLATION PER THE WATER HEATER MANUFACTURER'S REQUIREMENTS. PROVIDE WITH DIRECT VENT CONVERSION KIT. PIPING SHALL BE CLASS 3 STAINLESS STEEL.


- KEYED NOTES**
- MANUAL PULL STATION FOR KITCHEN HOOD FIRE SUPPRESSION SYSTEM ACTIVATION AND GAS SUPPLY SHUT-OFF TO BE PROVIDED BY THE FIRE SUPPRESSION SUBCONTRACTOR. GENERAL CONTRACTOR SHALL PROVIDE RECESSED JUNCTION BOX AND CONDUIT FOR PULL STATION LINKAGE.
 - REFER TO PLUMBING DRAWINGS FOR CONDENSATE PIPE ROUTING. PROVIDE AUXILIARY DRAIN PAN BELOW UNIT. SEE SCHEDULE NOTES.
 - DEHUMIDIFICATION UNIT HUNG FROM STRUCTURE ABOVE CEILING IN BOH. VERIFY MOUNTING LOCATION IN FIELD. COORDINATE COMPLETE INSTALLATION WITH MANUFACTURER'S RECOMMENDATIONS AND LANDLORD STRUCTURAL ATTACHMENT REQUIREMENTS.
 - EXTEND THE GREASE EXHAUST DUCT UP FROM THE HOOD COLLAR AND OFFSET HORIZONTALLY BEFORE ROUTING UP THRU ROOF TO THE EXHAUST FAN. HORIZONTAL DUCTWORK SHALL PITCH A MINIMUM 2% SLOPE TOWARDS THE HOOD ON HORIZONTAL RUNS UP TO 75'-0" AND A MINIMUM 8% SLOPE TOWARDS THE HOOD ON HORIZONTAL RUNS GREATER THAN 75'-0" PER SECTION 510.0 OF THE 2021 UNIFORM MECHANICAL CODE. CONDENSATE EXHAUST DUCTWORK SHALL BE INSTALLED COMPLETE WITH EXTERNAL DUCT INSULATION SIMILAR TO OTHER HVAC DUCTWORK.
 - AIR DEVICE IN HARD LID CEILING SHALL BE INSTALLED COMPLETE WITH OPPOSED BLADE DAMPER FOR MANUAL VOLUME ADJUSTMENT.
 - ROUTE MAKEUP AIR DUCTWORK TO PERFORATED SUPPLY PLENUM COLLAR CONNECTION. MAKEUP AIR DUCT CONNECTION SHALL BE OF THE SAME SIZE AS THE PLENUM COLLAR.
 - ROUTE MAKEUP AIR DUCTWORK DOWN FULL SIZE FROM THE UNIT CONNECTION THROUGH THE ROOF AS SHOWN. PROVIDE FLEXIBLE CONNECTION AND TRANSITION THROUGH THE JOISTS AS REQUIRED.

- KEYED NOTES**
- EXTEND THE 6" RESTROOM EXHAUST RISER UP AND OFFSET HORIZONTALLY BEFORE ROUTING UP THRU ROOF MOUNTED TO EXHAUST FAN. FIELD VERIFY ANY REQUIRED TRANSITIONS OR OFFSETS OF EXHAUST DUCT FROM STRUCTURE.
 - REMOVE HUMIDITY SENSOR/CONTROL FOR DEHUMIDIFICATION UNIT. VERIFY MOUNTING LOCATION IN FIELD. COORDINATE COMPLETE INSTALLATION WITH MANUFACTURER'S RECOMMENDATIONS.
 - ROUTE THE 14X10 CONDENSATE EXHAUST RISER UP TO COMBINED EXHAUST DUCTWORK AND OFFSET HORIZONTALLY AS SHOWN PRIOR TO EXTENDING UP THRU ROOF TO EXHAUST FAN. FIELD VERIFY REQUIRED TRANSITIONS OR OFFSETS OF EXHAUST DUCT FROM STRUCTURE. PITCH HORIZONTAL EXHAUST DUCT A MINIMUM 2% SLOPE TOWARDS THE HOOD ON HORIZONTAL RUNS UP TO 75'-0" AND A MINIMUM 8% SLOPE TOWARDS THE HOOD ON HORIZONTAL RUNS GREATER THAN 75'-0" PER SECTION 510.0 OF THE 2021 UNIFORM MECHANICAL CODE. CONDENSATE EXHAUST DUCTWORK SHALL BE INSTALLED COMPLETE WITH EXTERNAL DUCT INSULATION SIMILAR TO OTHER HVAC DUCTWORK.
 - AIR DEVICE IN HARD LID CEILING SHALL BE INSTALLED COMPLETE WITH OPPOSED BLADE DAMPER FOR MANUAL VOLUME ADJUSTMENT.
 - ROUTE MAKEUP AIR DUCTWORK TO PERFORATED SUPPLY PLENUM COLLAR CONNECTION. MAKEUP AIR DUCT CONNECTION SHALL BE OF THE SAME SIZE AS THE PLENUM COLLAR.
 - ROUTE MAKEUP AIR DUCTWORK DOWN FULL SIZE FROM THE UNIT CONNECTION THROUGH THE ROOF AS SHOWN. PROVIDE FLEXIBLE CONNECTION AND TRANSITION THROUGH THE JOISTS AS REQUIRED.

- KEYED NOTES**
- EXISTING SMOKE DETECTOR SHALL BE EXISTING TO REMAIN. FIELD VERIFY LOCATION.
 - CONNECT NEW SUPPLY AND RETURN DUCTWORK UP THRU ROOF TO EXISTING ROOFTOP UNIT CONNECTIONS. FIELD VERIFY SUPPLY AND RETURN DROP LOCATIONS WITH EXISTING STRUCTURE. FIELD COORDINATE SUPPLY AND RETURN DROPS WITH NEW PANELS AND CONDUIT IN ELECTRICAL ROOM BELOW.
 - RELOCATED WALL MOUNTED THERMOSTAT SHALL BE MOUNTED AT 48" AFF. AND WIRED BACK TO RESPECTIVE EXISTING HVAC UNIT. VERIFY PLACEMENT WITH THE ARCHITECTURAL FLOOR PLAN AND OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.
 - EXTEND THE 12" RESTROOM EXHAUST RISER UP AND OFFSET HORIZONTALLY BEFORE ROUTING UP THRU ROOF MOUNTED TO EXHAUST FAN. FIELD VERIFY ANY REQUIRED TRANSITIONS OR OFFSETS OF EXHAUST DUCT FROM STRUCTURE.
 - EXISTING GAS PATIO HEATER TO REMAIN. FIELD VERIFY SIZE, LOCATION, AND MAINTAIN MANUFACTURER RECOMMENDED CLEARANCES OF HEATERS.
 - RETURN GRILLE AIR QUANTITY LISTED IS FOR PARTIAL RETURN DURING STANDARD OPERATING HOURS. RETURN DUCTS ARE SIZED FOR FULL RETURN DURING NIGHT SETBACK CONDITIONS. REFER TO SHEET M2.0 FOR AIR BALANCE REPORT ON DESIGN AIRFLOW RATES.
 - EXISTING ROOFTOP UNIT SHALL BE EXISTING TO REMAIN. FIELD VERIFY SIZE AND LOCATION.

- KEYED NOTES**
- SIDEWALL MOUNTED RETURN AIR DEVICE WITH FIELD FABRICATED INSULATED PLENUM. MOUNT AIR DEVICE A MINIMUM 10'-10" AND REFER TO ARCHITECTURAL ELEVATIONS FOR FINAL MOUNTING HEIGHT. FIELD COORDINATE FINAL LOCATION WITH ELECTRICAL EQUIPMENT AND WALL FINISHES.
 - NEW ROOFTOP UNIT SHALL BE IN EXISTING ROOFTOP UNIT LOCATION AND SHALL REUSE EXISTING ROOF OPENING. FIELD VERIFY SIZE AND LOCATION PRIOR TO INSTALLATION. FIELD COORDINATE WITH EXISTING STRUCTURE.
 - WALL MOUNTED UTILITY CABINET FOR HOOD FIRE SUPPRESSION TANK SYSTEM. 48" X 12" X 30" CABINET SHALL BE HUNG FROM STRUCTURE USING UNISTRUT. FIELD COORDINATE FINAL LOCATION AND CLEARANCES WITH KITCHEN EQUIPMENT BELOW.
 - AIR DEVICE(S) AND DUCTWORK INTENDED FOR PASSIVE TRANSFER OF POSITIVE PRESSURE AIR. SIZE AS SHOWN.
 - WALL MOUNTED PROGRAMMABLE THERMOSTAT IN OUTDOOR PATIO BAR. VERIFY PLACEMENT WITH ARCHITECTURAL FLOOR PLAN, ARCHITECTURAL ELEVATIONS, AND OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.
 - MOUNT DUCTLESS SPLIT SYSTEM AIR HANDLING UNIT AS HIGH AS POSSIBLE ON EXTERIOR WALL IN OUTDOOR PATIO BAR. MAINTAIN ALL CLEARANCES AND FIELD COORDINATE FINAL LOCATION OF WALL PENETRATIONS FOR POWER, CONDENSATE, AND REFRIGERANT LINES PER MANUFACTURER'S INSTRUCTIONS. COORDINATE AHU PLACEMENT WITH ARCHITECTURAL ELEVATIONS, ELECTRICAL EQUIPMENT, AND EXISTING OPENINGS IN BAR WALL(S). REFER TO PLUMBING DRAWINGS FOR CONDENSATE PIPING AND SEE SCHEDULE NOTES.
 - DUCTWORK CONCEALED BY FINISHED WALLS AND CEILINGS SHALL TRANSITION TO INTERNALLY INSULATED RIGID RIGID DUCT PRIOR TO BEING INSTALLED TO LINE OF SIGHT FROM GUESTS.

- KEYED NOTES**
- ALL TYPE-I GREASE EXHAUST DUCT(S) SHALL BE CONSTRUCTED OF AND SUPPORTED BY NFPA 96 NO. 16 MSG CARBON STEEL OR NO. 18 MSG STAINLESS STEEL AS APPROVED BY SECTION 510.5.3 OF THE 2021 UNIFORM MECHANICAL CODE. GREASE EXHAUST DUCT(S) SHALL BE EXTERNALLY WELDED WITH LIGHT TIGHT JOINTS, SEAMS, AND SMOOTH RADIUS ELBOWS AND TRANSITIONS. GREASE EXHAUST DUCT SHALL BE THE SAME SIZE AS HOOD COLLAR. REFER TO HOOD SHEETS FOR COLLAR DIMENSIONS. FIELD VERIFY REQUIRED TRANSITIONS OR OFFSETS OF EXHAUST DUCT FROM ROOF TO HOOD COLLAR. FIELD COORDINATE NEW GREASE EXHAUST DUCTWORK WITH EXISTING GREASE EXHAUST DUCTWORK.
 - ALL TYPE-I GREASE DUCT(S) SHALL BE DOUBLE WRAPPED WITH UL-LISTED FIRE WRAP 3M FIRE BARRIER DUCT WRAP 204 (OR APPROVED EQUAL) IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS. EACH GREASE DUCT RISER SHALL BE WRAPPED TO THE FULL EXTENT POSSIBLE FROM THE HOOD COLLAR CONNECTION UP TO THE TERMINATION AT THE EXHAUST FAN INLET.
 - SIDEWALL MOUNTED SUPPLY AIR DEVICE WITH FIELD FABRICATED INSULATED PLENUM AND MANUAL VOLUME DAMPER. MOUNT AIR DEVICE A MINIMUM 13'-8" AFF AND REFER TO ARCHITECTURAL ELEVATIONS FOR FINAL MOUNTING HEIGHT. FIELD COORDINATE FINAL LOCATION WITH ELECTRICAL EQUIPMENT AND WALL FINISHES.
 - ALL EXPOSED DUCTWORK IN THE OPEN CEILING DINING AREA SHALL BE INSTALLED AS GALVANIZED INTERNALLY INSULATED SPIRAL DUCT AND FITTINGS FINISHED WITH PANTOPRIP SUITABLE FOR PAINTING. DUCT SIZES SHOWN ARE INTERNAL DIMENSIONS. EXPOSED DUCTWORK SHALL BE ROUTED ABOVE FAUX BEAM SYSTEM AND WITHIN BEAM SPACING AS SHOWN. FIELD COORDINATE FINAL ROUTING MOUNTING HEIGHT WITH FAUX BEAM SYSTEM AND EXISTING STRUCTURE PRIOR TO INSTALLATION. GENERAL CONTRACTOR TO PROVIDE ALTERNATE BID FOR USE OF RECTANGULAR DUCT AND FITTINGS IN PLACE OF SPIRAL DUCT AND FITTINGS. REFER TO ARCHITECTURAL DRAWINGS FOR FINISH COLOR.
 - PROVIDE OPEN-ENDED INTERNALLY INSULATED 42"x26" RETURN AIR BOOT THROUGH FULL HEIGHT WALL AS SHOWN. PAINT INSIDE BLACK FOR LINE-OF-SIGHT. OPENING SHALL BE COVERED BY A 1/4" X 1/4" WIRE MESH SCREEN. RETURN AIR BOOT SHALL PENETRATE FULL HEIGHT WALL AS HIGH AS POSSIBLE. FIELD VERIFY FINAL HEIGHT WITH ARCHITECTURAL ELEVATIONS, WALL FINISHES, AND LIGHT FIXTURES.
 - EXTEND THE GREASE EXHAUST DUCT UP FROM THE HOOD COLLAR AND OFFSET HORIZONTALLY TO GREASE EXHAUST DUCT MAIN. OFFSET GREASE EXHAUST DUCT MAIN HORIZONTALLY BEFORE ROUTING UP THRU ROOF TO EXTERIOR ROOF MOUNTED GREASE EXHAUST DUCTWORK. HORIZONTAL DUCTWORK SHALL PITCH A MINIMUM 2% SLOPE TOWARDS THE HOOD ON HORIZONTAL RUNS UP TO 75'-0" AND A MINIMUM 8% SLOPE TOWARDS THE HOOD ON HORIZONTAL RUNS GREATER THAN 75'-0" PER SECTION 510.0 OF THE 2021 UNIFORM MECHANICAL CODE. GREASE EXHAUST DUCT SHALL BE OF THE SAME SIZE AS THE HOOD COLLAR. FIELD COORDINATE THE REQUIRED TRANSITIONS OF EXHAUST DUCT FROM COMBUSTIBLE MATERIALS TO MAINTAIN THE MINIMUM CLEARANCES REQUIRED PER APPLICABLE CODE(S) AND FIRE WRAP MANUFACTURER'S INSTRUCTIONS.
 - EXTEND THE GREASE EXHAUST DUCT UP FROM THE HOOD COLLAR AND OFFSET HORIZONTALLY TO GREASE EXHAUST DUCT MAIN. OFFSET GREASE EXHAUST DUCT MAIN HORIZONTALLY BEFORE ROUTING UP THRU ROOF TO EXTERIOR ROOF MOUNTED GREASE EXHAUST DUCTWORK. HORIZONTAL DUCTWORK SHALL PITCH A MINIMUM 2% SLOPE TOWARDS THE HOOD ON HORIZONTAL RUNS UP TO 75'-0" AND A MINIMUM 8% SLOPE TOWARDS THE HOOD ON HORIZONTAL RUNS GREATER THAN 75'-0" PER SECTION 510.0 OF THE 2021 UNIFORM MECHANICAL CODE. GREASE EXHAUST DUCT SHALL BE OF THE SAME SIZE AS THE HOOD COLLAR. FIELD COORDINATE THE REQUIRED TRANSITIONS OF EXHAUST DUCT FROM COMBUSTIBLE MATERIALS TO MAINTAIN THE MINIMUM CLEARANCES REQUIRED PER APPLICABLE CODE(S) AND FIRE WRAP MANUFACTURER'S INSTRUCTIONS.



idstudio
600 CAMPS CIRCLE DRIVE E
FRIEDLAND, TEXAS 78720
WWW.IDSTUDIO.COM

HAJ HOSPITALITY
1306 W. OLTORF STREET, SUITE C
AUSTIN, TEXAS 78704
www.hajhospitality.com

TBPE FIRM REGISTRATION# F-11678

JOHN G. SISK
101280
E.N.S.
REGISTERED PROFESSIONAL ENGINEER
NO. 101280
EXPIRES 12/31/2024

05/24/2024
ISSUE FOR CONSTRUCTION

LORO'S ASIAN SMOKEHOUSE & BAR
AUSTIN, TX
11601 DOMAIN DR. #700
AUSTIN, TEXAS 78758

CLIENT: HAJ HOSPITALITY
1306 W. OLTORF STREET, SUITE C
AUSTIN, TEXAS 78704

LORO
ASIAN SMOKEHOUSE & BAR

DATE	DESCRIPTION
10/27/2023	ISSUE FOR PERMIT
04/12/2024	ISSUE FOR CONSTRUCTION

DATE	DESCRIPTION
4	09/19/24 ADDRESS A - CITY COMMENTS
3	08/05/24 OWNER COMMENTS - VE
2	02/07/24 OWNER COMMENTS - VE
1	04/12/24 OWNER COMMENTS - VE

MECHANICAL FLOOR PLAN
SCALE: 1/4" = 1'-0"

1

M1.0
PROJECT NUMBER: LAS23001

FAN SCHEDULE												
MARK	SERVICE	HOOD TYPE	CFM	E.S.P. "WG	RPM	MOTOR HP	VOLTS/PH	MANUFACTURER	MODEL	TYPE	WEIGHT	NOTES
KEF-1	HOOD #1 & #2 (COOKLINE)	TYPE-I	3752	2.00	1410	5.00	208/3	ACCUREX	XUEF-18	ROOF UTILITY SET FAN	314	1,3,5,6,8
KEF-2	HOOD #3 (SMOKER)	TYPE-I	1900	1.50	1488	1.00	208/3	ACCUREX	XUEF-15	ROOF UTILITY SET FAN	188	1,3,5,6,8
KEF-3	HOOD #4 (PREP)	TYPE-I	2000	1.25	1614	1.00	208/3	ACCUREX	XUE-140-A	ROOF UPBLAST FAN	96	1,3,5,6,8
DEF-1	HOOD #5 (DISH)	TYPE-II	1400	1.00	1627	0.50	208/1	ACCUREX	XOUE-120-VG	ROOF UPBLAST FAN	55	2,4,6,8
TEF-1	RESTROOMS	---	400	0.30	1627	0.10	115/1	GREENHECK	G-099-VG	ROOF DOWNBLAST FAN	29	4,10
TEF-2	OUTDOOR RESTROOM	---	100	0.50	1128	0.25	115/1	GREENHECK	G-097-VG	ROOF DOWNBLAST FAN	38	4,10
MAU-1	COOKLINE HOODS	---	6120	1.00	2741	10.00	208/3	ACCUREX	MAU-21-19-C-A	ROOF MAKEUP FAN	2471	1,3,4,6,7,8,9

- NOTES:
- THE UTILITY CABINET SHALL BE FACTORY EQUIPPED WITH A PREWIRE PACKAGE TO INTERLOCK THE EXHAUST FANS WITH THE MAKEUP AIR UNIT.
 - THE FAN SHALL BE FACTORY EQUIPPED WITH AN INDEPENDENT WEATHER PROOF DISCONNECT SWITCH IN SIGHT OF THE EQUIPMENT.
 - WEATHER PROOF DISCONNECT SWITCH AND INTERNAL WIRING SHALL BE FACTORY INSTALLED.
 - THE FAN SHALL BE FACTORY EQUIPPED WITH A GRAVITY BACKDRAFT DAMPER.
 - THE FAN SHALL BE FACTORY EQUIPPED WITH CURB MOUNTED HINGE KITS.
 - FURNISHED WITH HOOD PACKAGE, INSTALLED BY THE MECHANICAL CONTRACTOR.
 - THE MAKEUP AIR UNIT SHALL BE FACTORY EQUIPPED WITH (1) CIRCUITS OF DX COOLING FOR SINGLE STAGE OPERATION, RATED FOR 237.6 MBH TOTAL CAPACITY/ 197.3 MBH SENSIBLE CAPACITY, AND A COOLING W/HEAT THERMOSTAT. THE MECHANICAL CONTRACTOR SHALL FIELD ADJUST TO 75F.
 - ALL EQUIPMENT SHALL BE INSTALLED AND STARTED-UP PER THE MANUFACTURER'S INSTALLATION, OPERATION AND MAINTENANCE MANUALS. THE MECHANICAL CONTRACTOR SHALL COMPLETE ALL FACTORY "START-UP AND MAINTENANCE DOCUMENTATION" INCLUDED WITH THE EQUIPMENT PACKAGE, AND PROVIDE A COPY TO THE LORO ASIAN SMOKEHOUSE CONSTRUCTION MANAGER.
 - THE MAKEUP AIR UNIT IS FACTORY EQUIPPED WITH DIRECT FIRED GAS COMBUSTION HEAT EXCHANGER, RATED FOR 300 MBH INPUT / 243 MBH OUTPUT.
 - ELECTRICAL CONTRACTOR SHALL INTERLOCK WITH RESTROOM LIGHT SWITCH FOR SIMULTANEOUS OPERATION.

DEHUMIDIFICATION UNIT			
AIR HANDLING UNIT	DUH-1		
UNIT TAG	ULTRA-AIRE MODEL NO.	TX205H	
INSTALLED (LBS)	140		
FAN SECTION	RATED CFM	400	
DRIVE	E.S.P. (INCH)	STANDARD	
	E.S.P. (INCH)	0.20	
TOTAL UNIT ELECTRIC DATA	VOLTS/PH/Hz	115/1/60	
	MIN. CIR. AMPS	13.2	
	MOCOP	20	

- NOTES:
- FURNISHED AND INSTALLED BY MECHANICAL CONTRACTOR.
 - PROVIDE WITH ULTRA-AIRE DEH 3000 DIGITAL CONTROLLER.
 - INSTALL PER MANUFACTURER'S RECOMMENDATIONS AND PROVIDE ALL NECESSARY HARDWARE FOR COMPLETE INSTALLATION.

AIR DEVICE SCHEDULE								
MARK	FACE SIZE	TYPE	MOUNTING TYPE	MAXIMUM N.C.	DIRECTION	MANUFACTURER	MODEL	NOTES
HD	24x24	SUPPLY	LAY-IN	30	1-WAY	TITUS	PAS	1,3,4,5
G01	24x24	SUPPLY	SURFACE (GYP. CLG)	30	4-WAY	TITUS	OMNI	2,3,4,6
G02	12x12	SUPPLY	SURFACE (GYP. CLG)	30	4-WAY	TITUS	OMNI	2,3,4,6
OD	24x24	SUPPLY	LAY-IN	30	4-WAY	TITUS	OMNI	1,3,4,5
KR	24x24	RETURN	LAY-IN	30	1-WAY	TITUS	PAR	1,3,5
G01	24x24	EXHAUST	SURFACE (GYP. CLG)	30	1-WAY	TITUS	23RL	2,3,6
G02	12x12	EXHAUST	SURFACE (GYP. CLG)	30	1-WAY	TITUS	23RL	2,3,6
S01	48 INCH (2-SLOT) (1.0" SLOT)	SUPPLY	SURFACE (GYP. CLG)	30	1-WAY	TITUS	FL-10	2,3,7,8
S02	18x12	SUPPLY	SIDEWALL MOUNTED	30	1-WAY	TITUS	300FL	2,3
SR1	12x8	RETURN	SURFACE (GYP. CLG)	30	1-WAY	TITUS	350RL	2,3

- NOTES:
- AIR DEVICES IN THE BACK OF HOUSE SHALL BE INSTALLED WITH FACTORY APPLIED OFF WHITE FINISH.
 - AIR DEVICES IN THE FRONT OF HOUSE SHALL BE PROVIDED WITH FACTORY OFF WHITE FINISH. PRIOR TO INSTALLATION, THE PAINTING CONTRACTOR SHALL EVENLY SAND THE AIR DEVICE AND TRIM, AND APPLY A PAINT GRIP PRIMER SUITABLE FOR A FINAL PAINT FINISH. REFER TO ARCHITECTURAL DRAWINGS FOR FINAL AIR DEVICE FINISH. FOLLOW THE DEVICE MANUFACTURER'S DIRECTION FOR FIELD PAINTING. VERIFY FINAL COLOR WITH THE OWNER'S CONSTRUCTION MANAGER PRIOR TO APPLICATION.
 - PROVIDE NECESSARY MOUNTING HARDWARE AND ACCESSORIES AS REQUIRED FOR INTENDED INSTALLATION.
 - AIR DEVICE SHALL BE INSTALLED WITH MANUFACTURER AVAILABLE MOLDED INSULATION BACKING. FIELD FABRICATED INSULATION BACKING IS NOT ALLOWED (UNLESS FIRST APPROVED BY THE OWNER'S CONSTRUCTION MANAGER).
 - AIR DEVICE SHALL BE INSTALLED COMPLETE WITHOUT SUPPLY AIR FLOW PATTERN CONTROLLERS.
 - AIR DEVICE SHALL BE INSTALLED WITH ACCESSIBLE OPPOSED BLADE DAMPER FOR MANUAL VOLUME ADJUSTMENT.
 - PROVIDE YOUNG REGULATOR CABLE SYSTEM MODEL 270-275 FOR BALANCING/AIR FLOW ADJUSTMENT AT DIFFUSER FACE.
 - PROVIDE WITH BORDER TYPE 22" AND INSULATED PLENUM BOX. SPACKLE BORDER AS NECESSARY FOR FLUSH FINISH OF AIR DEVICE SLOT OPENING WITH CEILING SURFACE (GYP. CLG).

O/A VENTILATION SCHEDULE						
AREA SERVED	VENTILATION (OCCUPANCY)			VENTILATION (AREA)		
	# OF PEOPLE	CFM/PERSON	CFM	SQUARE FEET	CFM/SF	CFM
DINING	138	7.5	1035	2380	0.18	429
KITCHEN	15	7.5	113	1316	0.12	158
RESTROOMS	-	-	-	713	-	-
SUBTOTALS	-	-	1148	29,000	-	587
TOTAL O/A REQUIRED	-	-	-	-	-	1735 CFM

- NOTES:
- CALCULATIONS ARE BASED ON 2021 UMC, TABLE 402.1
 - OUTDOOR AIR DEMAND IS: 1735 CFM
 - OUTDOOR AIR PROVIDED IS: 3465 CFM
 - OUTDOOR AIR DIFFERENCE IS: +1720 CFM

HVAC SEQUENCE OF OPERATION							
MARK	SERVICE	FUNCTION	START TIME	COOLING SETPOINT(°F)	HEATING SETPOINT(°F)	HUMIDITY SETPOINT(%RH)	NOTES
(E)RTU-1	DINING/BAR	OCCUPIED	9:30 AM	72	72	---	1 THRU 3
		UNOCCUPIED	12:30 AM	85	55	---	
RTU-2	KITCHEN/BOH	OCCUPIED	9:35 AM	72	72	50	1 THRU 4
		UNOCCUPIED	12:30 AM	85	55	50	
DHU-1	DINING/BAR	24 HRS	N/A	N/A	N/A	50	5

- NOTES:
- UNIT FAN SHALL RUN CONTINUOUSLY DURING OCCUPIED HOURS, AND CYCLE ON DEMAND DURING UNOCCUPIED HOURS.
 - UPON A CALL FOR COOLING:
 - COMPRESSORS TO CYCLE TO MAINTAIN THE SPACE SETTING, WITH THE GAS HEATER LOCKED OUT.
 - THERE SHALL BE A 2' DEAD BAND (ADJUSTABLE) BETWEEN THE 1ST AND 2ND STAGE OF COOLING.
 - THERE SHALL BE A 5 MINUTE (ADJUSTABLE) TIME DELAY BETWEEN THE 1ST AND 2ND STAGE OF COOLING.
 - UPON A CALL FOR HEATING:
 - GAS FURNACE TO CYCLE TO MAINTAIN THE SPACE SETTING, WITH THE COMPRESSORS LOCKED OUT.
 - THERE SHALL BE A 2' DEAD BAND (ADJUSTABLE) BETWEEN THE 1ST AND 2ND STAGE OF HEATING.
 - THERE SHALL BE A 5 MINUTE (ADJUSTABLE) TIME DELAY BETWEEN THE 1ST AND 2ND STAGE OF HEATING.
 - UPON A CALL FOR HUMIDITY CONTROL:
 - GAS FURNACE TO CYCLE TO MAINTAIN THE SPACE SETTING, WITH THE COMPRESSORS LOCKED OUT.
 - DURING UNOCCUPIED TIMES WHEN HUMIDISTAT INDICATES AN INCREASE IN HUMIDITY ABOVE THE SET POINT, THE HUMIDISTAT SYSTEM SHALL ACTIVATE TO REDUCE THE SPACE HUMIDITY TO BELOW SET POINT.
 - DURING UNOCCUPIED TIMES WHEN HUMIDISTAT INDICATES AN INCREASE IN HUMIDITY ABOVE THE SET POINT, THE FAN SHALL TURN ON AND THE HUMIDISTAT SYSTEM SHALL ACTIVATE TO REDUCE THE SPACE HUMIDITY TO BELOW SETPOINT.
 - UPON A CALL FOR HUMIDITY CONTROL:
 - DURING OCCUPIED TIMES WHEN HUMIDISTAT INDICATES AN INCREASE IN HUMIDITY ABOVE THE SET POINT, THE DEHUMIDIFICATION UNIT SHALL ACTIVATE TO REDUCE THE SPACE HUMIDITY TO BELOW SET POINT.
 - DURING UNOCCUPIED TIMES WHEN HUMIDISTAT INDICATES AN INCREASE IN HUMIDITY ABOVE THE SET POINT, THE FAN SHALL TURN ON AND THE DEHUMIDIFICATION UNIT SHALL ACTIVATE TO REDUCE THE SPACE HUMIDITY TO BELOW SETPOINT.

PACKAGED ROOFTOP UNIT SCHEDULE			
	(E)RTU-1	RTU-2	
GENERAL			
SERVING	DINING/BAR	KITCHEN/BOH	
MANUFACTURER	RUUD	CARRIER	
MODEL NO.	RLNL-B300CL	48CEN20K2M5	
TYPE	ELEC	GAS/ELEC	
OPERATING WEIGHT, LBS.	EXIST - VERIFY	2388	
LENGTH, WIDTH, HEIGHT	EXIST - VERIFY	128"x86"x48"	
MINIMUM EER/SEER	EXIST - VERIFY	10.8/14.5	
ELECTRICAL			
VOLTS/ PH/ HZ	208/3/60	208/3/60	
MCA (AMPS)	100.0	80.2	
MOCOP (AMPS)	110.0	100.0	
SUPPLY FAN			
SUPPLY AIR CFM	9500	6650	
OUTSIDE AIR CFM	2000	1455	
ESP (W.G.)	EXIST - VERIFY	0.80	
FAN RPM	EXIST - VERIFY	1665	
MOTOR HP	EXIST - VERIFY	3.35	
COOLING			
NOMINAL SIZE TONS	25.0	17.5	
TOTAL CAPACITY (MBH)	EXIST - VERIFY	207.2	
SENSIBLE CAPACITY (MBH)	EXIST - VERIFY	156.5	
OUTSIDE AIR DB/WB, °F.	98	98	
ENTERING AIR DB/WB, °F.	80/67	80/67	
HEATING			
TYPE OF HEAT	ELEC	GAS	
HEATING INPUT (MBH)	EXIST - VERIFY	310.0	
HEATING OUTPUT (MBH)	EXIST - VERIFY	251	
OUTSIDE AIR DB/WB, °F.	25	25	
LEAVING AIR DB/WB, °F.	EXIST - VERIFY	97.6	
NOTES	11-15	1-10	-

- NOTES:
- UNIT TO BE INSTALLED AT SAME LOCATION AS PREVIOUS UNIT BEING REMOVED. THE EXISTING OPENING SHALL BE REUSED. PROVIDE A FACTORY AVAILABLE UN-INSULATED FLAT ROOF CURB THAT SHALL BE FIELD ASSEMBLED AND SHIMMED SUCH THAT THE TOP OF THE CURB SETS LEVEL. ROOF CURBS TO BE INSTALLED BY THE GENERAL CONTRACTOR, AND FIELD INSULATED BY THE MECHANICAL CONTRACTOR.
 - PROVIDE WITH LOW AMBIENT CONTROLS, MICROPROCESSOR CONTROLS, CONDENSER COIL HAIL GUARD (FOR 'A' AND 'B' CABINETS), HINGED ACCESS PANELS, CRANK CASE HEATER, FRESH AIR TEMPERING KIT, AND FROSTAT.
 - PROVIDE WITH MANUFACTURER'S PROGRAMMABLE 24/7 THERMOSTAT, REMOTE TEMPERATURE AND HUMIDITY SENSORS CAPABLE OF AUTOMATIC COOLING/ HEATING CHANGEOVER.
 - CONTROL WIRING FOR THE THERMOSTAT SHALL BE 18AWG STRANDED, SINGLE TWISTED PAIR, INDIVIDUALLY SHIELDED, 100% ALUMINUM SHIELD DRAIN WIRE AND PLENUM RATED TEFLOX JACKET (BELDEN 88760).
 - CONTROL WIRING FOR THE HUMIDISTAT SHALL BE 22AWG STRANDED, TWO TWISTED PAIRS, INDIVIDUALLY SHIELDED, 100% ALUMINUM SHIELD DRAIN WIRE AND PLENUM RATED TEFLOX JACKET (BELDEN 88723).
 - REFER TO THE PLAN SHEETS FOR PROPOSED MOUNTING LOCATIONS OF CONTROL DEVICES.
 - PROVIDE FACTORY INSTALLED OUTDOOR ENTHALPY CONTROLLED ECONOMIZER WITH FULL MODULATING MOTORIZED OUTSIDE AIR DAMPER. FIELD ADJUST BOTH DIP SWITCHES TO THE RIGHT FOR ODE SETTING.
 - MECHANICAL CONTRACTOR SHALL PROVIDE A FIELD INSTALLED SUPPLY AIR SMOKE DETECTOR 10'-0" DOWNSTREAM OF THE UNIT PRIOR TO RETURN AIR GRILL DUCT CONNECTIONS, CAPABLE OF SHUTTING DOWN THE ROOFTOP UNIT UPON ACTIVATION. INSTALL COMPLETE WITH A KEYED REMOTE DETECTOR (BLACK) INSTALLED IN THE RETURN AIR DUCT.
 - PROVIDE FACTORY INSTALLED ELECTRICAL DISCONNECT. CONVENIENCE RECEPTACLE SHALL BE FIELD WIRED BY THE E.C. AND POWERED SEPARATELY FROM THE UNIT.
 - PROVIDE SINGLE POINT ELECTRICAL POWER CONNECTION INCLUDING STARTERS AND CONTROLS.
 - PROVIDE WITH SUPPLEMENTAL DEHUMIDIFICATION OPTION FOR HOT GAS REHEAT, AND MANUFACTURER'S ADJUSTABLE REMOTE HUMIDITY SENSOR CAPABLE OF AUTOMATIC OPERATION OF THE COOLING CYCLE (ONCE THE DEMAND FOR COOLING IS SATISFIED BY THE T-STAT) FOR SUPPLEMENTAL DEHUMIDIFICATION.
 - UNIT SELECTIONS ARE BASED ON R-410A REFRIGERANT.
 - FOR EQUIPMENT ORDERING, CONTACT MR. JARMALE LEWIS AT (972) 281-6541.
 - ROOFTOP UNIT IS EXISTING TO REMAIN. CONTRACTOR SHALL VERIFY ACTUAL CONDITION OF THE EXISTING ROOFTOP UNIT CURB FOR INTENDED REUSE.
 - UNIT SELECTIONS ARE BASED ON R-410A REFRIGERANT.
 - CONDITION: REPLACE ALL WORK PARTS, BELTS, AND FILTERS. PROVIDE ACCESSORIES TO UTILIZE OUTSIDE AIR INTAKES OF UNITS FOR BALANCING AIRFLOWS AS SHOWN. PROVIDE ALL DAMPERS, HOOD, ETC.
 - FIELD VERIFY REFRIGERANT CHARGE AND FILL SYSTEM AS REQUIRED. IN THE EVENT THE SYSTEM IS EXTREMELY LOW, VACUUM AND CAPTURE THE EXISTING REFRIGERANT PRIOR TO RECHARGING THE LINES. IDENTIFIED REPAIR LEAKS AS REQUIRED.
 - PROVIDE ACCESSORIES TO UTILIZE OUTDOOR AIR INTAKES (DAMPERS, HOODS, ETC).
 - THE OUTDOOR AIR FOR THE EXISTING RTU SHALL BE BALANCE TO THE CFM SHOWN IN THE SCHEDULE.

MECHANICAL LEGEND		
SYMBOL	ABBR.	DESCRIPTION
	CD	CEILING DIFFUSER - SUPPLY
	CD	CEILING DIFFUSER BELOW DUCT - SUPPLY
	SAD	RISER - SUPPLY AIR DUCT
	SAD	DROP - SUPPLY AIR DUCT
	CR	CEILING REGISTER - RETURN
	CR	CEILING REGISTER BELOW DUCT - RETURN
	RAD	RISER - RETURN AIR DUCT
	RAD	DROP - RETURN AIR DUCT
	CE	CEILING REGISTER - EXHAUST
	CE	CEILING REGISTER BELOW DUCT - EXHAUST
	EAD	RISER - EXHAUST AIR DUCT
	(L)	LINE DUCTWORK
	VD	MANUAL VOLUME DAMPER
	MD	MOTORIZED VOLUME DAMPER
	FC	FLEXIBLE CONNECTION
		NEW DUCT
		AIR DEVICE DESIGNATION
	TSTAT	PROGRAMMABLE THERMOSTAT
	SENS	REMOTE TEMPERATURE SENSOR
	SD	SMOKE DETECTOR
	POC	POINT OF CONNECTION
	CFM	CUBIC FEET PER MINUTE
	S/A	SUPPLY AIR
	O/A	OUTSIDE AIR
	E/A	EXHAUST AIR
	S.P.	STATIC PRESSURE
	FOH	FRONT OF HOUSE
	BOH	BACK OF HOUSE

AIR BALANCE SCHEDULE						
MARK	DINING (CFM)			KITCHEN (CFM)		
	S/A	O/A	E/A	S/A	O/A	E/A
(E)RTU-1	9500	2000	---	---	---	---
RTU-2	---	---	---	6650	1580	---
KEF-1	---	---	---	---	---	3752
KEF-2	---	---	---	---	---	1900
KEF-3	---	---	---	---	---	2000
DEF-1	---	---	---	---	---	1400
TEF-1	---	---	600	---	---	---
MAU-1	---	---	---	---	6120	---
TOTAL	9500	2280	600	6650	7575	9052


DINING PRESSURIZATION (O/A) - (E/A) = +1680 CFM
 KITCHEN PRESSURIZATION (O/A) - (E/A) = -1352 CFM
 NET BUILDING PRESSURIZATION (DINING + KITCHEN) = +328 CFM

DUCTLESS HEAT PUMP SPLIT SYSTEM SCHEDULE										
MARK	MAKE/ MODEL	RATED COOLING CAPACITY (BTU/H)	RATED HEATING CAPACITY (BTU/H)	SEER/SEER	CFM	VOLTS/PH/Hz	MCA/MOCOP	DIMENSIONS (W,D,H)	WEIGHT (LBS)	NOTES
AHU-1	CARRIER 40MAH024XA3	24,000	29,000	13.0/21.5	715	POWERED FROM CONDENSER	POWERED FROM CONDENSER	44x108x14.6	44	2,3,4,5,6
CU-1	CARRIER 38MAR024AA3	---	---	R410A	---	208/1/60	25.0/35.0	37.2x16.1x31.9	135	1,2,3,4


- NOTES: (NOT ALL MAY APPLY)
- CONDENSING UNIT SHALL BE FACTORY EQUIPPED WITH THE FOLLOWING OPTIONS/ ACCESSORIES: DX COIL, HAIL GUARD, THERMAL EXPANSION VALVE, DRAIN PAN, SIGHT GLASS, LIQUID LINE FILTER, LOW AMBIENT CONTROL KIT, AND ANTI-SHORT CYCLE TIMER.
 - COORDINATE REFRIGERANT SUCTION AND LIQUID LINE SIZING WITH MANUFACTURER REQUIREMENTS, AGAINST THE MAXIMUM DEVELOPED HORIZONTAL AND VERTICAL LINE LENGTHS REQUIRED WITH SITE CONDITIONS.
 - COOLING LOADS LISTED ARE AT A.R.I. STANDARD.
 - CONTACT MR. JARMALE LEWIS (CARRIER) AT (972)281-6541 FOR PRICING AND VERIFY FINAL SELECTIONS FOR EQUIPMENT SELECTION INFORMATION AND ORDERING.
 - PROVIDE 7-DAY PROGRAMMABLE THERMOSTAT WITH AHU.
 - AHU SHALL BE PROVIDED WITH INTEGRAL CONDENSATE PUMP.

- NOTES:
- ALL TYPE I COOKLINE GREASE EXHAUST DUCTWORK SHALL BE DOUBLE WRAPPED WITH UL LISTED FIRE WRAP SIMILAR TO 3M FIRE BARRIER DUCT WRAP 200 IN ACCORDANCE WITH MANU'S INSTALLATION INSTRUCTIONS. TYPE I COOKLINE GREASE DUCT RISER SHALL BE WRAPPED TO THE FULL EXTENT POSSIBLE FROM THE HOOD COLLAR CONNECTION UP TO THE TERMINATION AT THE EXHAUST FAN INLET. ALL GREASE EXHAUST FAN ROOF CURBS SHALL BE VENTED PER NFPA 96. PROVIDE REQUIRED ACCESS FOR SERVICING AND CLEANING, VERIFY THE HINGED CURB OPENING OPERATES PROPERLY.
 - EACH GREASE EXHAUST DUCT RISER BETWEEN THE HOOD COLLAR AND EXHAUST FAN SHALL BE OF THE SAME SIZE AS THE RESPECTIVE HOOD COLLAR SIZE. UNO. REFER TO THE HOOD SHEETS FOR THE HOOD COLLAR SIZES AS SPECIFIED BY THE HOOD MANUFACTURER.
 - ALL GREASE EXHAUST FAN ROOF CURBS SHALL BE VENTED PER NFPA 96. PROVIDE REQUIRED ACCESS FOR SERVICING AND CLEANING, VERIFY THE HINGED CURB OPENING OPERATES PROPERLY.
 - ROOF CURBS FOR EXHAUST FANS AND THE MAKEUP AIR UNIT SHALL BE FACTORY FABRICATED AND FURNISHED WITH THE HOOD PACKAGE. VERIFY REQUIREMENTS FOR THE ROOF CURBS WITH THE EQUIPMENT SUPPLIER. THE GENERAL CONTRACTOR SHALL FIELD ASSEMBLE THE ROOF CURBS, FLASH AND SHIM DEAD LEVEL. COORDINATE EXACT SIZE AND LOCATION OF ROOF OPENINGS WITH THE STRUCTURAL FRAMING. CUTTING OF STRUCTURAL MEMBERS IS NOT PERMITTED.
 - ROOF CURBS FOR ROOFTOP UNITS SHALL BE FACTORY FABRICATED OF FULL WELDED STEEL CONSTRUCTION WITH WOOD NAILER, AND FURNISHED WITH THE HVAC EQUIPMENT PACKAGE. VERIFY REQUIREMENTS FOR THE ROOF CURBS WITH THE EQUIPMENT SUPPLIER. THE GENERAL CONTRACTOR SHALL FIELD ASSEMBLE THE ROOF CURBS, FLASH AND SHIM DEAD LEVEL. COORDINATE EXACT SIZE AND LOCATION OF ROOF OPENINGS WITH THE STRUCTURAL FRAMING. CUTTING OF STRUCTURAL MEMBERS IS NOT PERMITTED.
 - THE KITCHEN EXHAUST HOODS SHALL BE INSTALLED AT 6"-8" AFF (UNO). COORDINATE INSTALLATION AND PLACEMENT OF EXHAUST HOODS WITH ARCHITECTURAL REFLECTED CEILING PLAN.
 - THE KITCHEN HOOD PACKAGE WILL BE FURNISHED WITH UTILITY END CABINETS HOUSING THE FIRE SUPPRESSION TANKS, ELECTRICAL PREWIRE PACKAGE, AND EXHAUST FAN. EXISTING SYSTEMS SHALL BE CAPABLE TO HANDLE ANY AND ALL CHANGES IN LOAD.
 - REFER TO MANUFACTURER SHEETS FOR THE HOOD CONTROL WIRING DIAGRAM FOR OPERATION OF THE KITCHEN HOOD EQUIPMENT.
 - THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACING THE AIR FILTERS AT THE ROOFTOP UNITS WITH 2" THICK FILTERED MERV 8 THRU MERV 10 AIR FILTERS AT THE COMPLETION OF CONSTRUCTION AND PRIOR TO AIR BALANCING AND STORE TURNOVER.
 - PER THE 2021 UNIFORM MECHANICAL CODE, WITH LOCAL AMENDMENTS WHEN REQUIRED, EACH SINGLE STAGE PROVIDING HEATING OR COOLING AIR SHALL BE EQUIPPED WITH A CURB PER MINUTE SHALL BE EQUIPPED WITH AN AUTOMATIC SHUTOFF. AUTOMATIC SHUTOFF SHALL BE ACCOMPLISHED BY INTERRUPTING THE POWER SOURCE OF AIR MOVING EQUIPMENT DEVICES WHICH WILL DETECT PRODUCTS OF COMBUSTION OTHER THAN HEAT, AND WHICH COMPLY WITH THE APPLICABLE BUILDING CODE. SHALL BE LABELLED BY AN APPROVED AGENCY FOR AIR DUCT INSTALLATION AND SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS. SUCH DEVICES SHALL BE COMPATIBLE WITH OPERATING VELOCITIES, PRESSURES, TEMPERATURES AND HUMIDITIES OF THE SYSTEM WHERE FIRE DETECTION OR ALARM SYSTEMS ARE PROVIDED FOR THE BUILDING. SMOKE DETECTORS SHALL BE SERVICED BY SUCH SYSTEMS.
 - MC SHALL BE ON SITE AND PRESENT AT THE DATE OF STORE TURNOVER.


- LANDLORD DESIGN CRITERIA REQUIREMENTS
- ANY CHANGES AND/OR UPDATES TO TENANT'S EXISTING MECHANICAL SYSTEMS SHALL COMPLY WITH ALL CODES AND LANDLORD CRITERIA. EXISTING SYSTEMS SHALL BE CAPABLE TO HANDLE ANY AND ALL CHANGES IN LOAD.
 - NO PITCH POCKETS PERMITTED ON ROOF FOR ANY CONDENSATE DRAINS, REFRIGERANT PIPING, POWER OR CONTROL WIRING. ALL CONNECTIONS ARE TO BE MADE INSIDE THE EQUIPMENT CURB OR THROUGH PRE-MANUFACTURED PIPING CURB.
 - NOTHING IS PERMITTED TO BE ATTACHED TO, SUSPENDED FROM, OR PENETRATE LANDLORD'S STRUCTURE, FLOOR DECK, OR ROOF DECK. YOU MAY ATTACH, NON-DESTRUCTIVELY, TO OR SUSPEND FROM THE JOISTS OR THE STRUCTURAL STEEL WHICH EXISTS ABOVE TENANT SPACE, WHEN ATTACHING TO LANDLORD'S STRUCTURE, DO NOT DRILL, NAIL, SCREW, OR SHOOT INTO STRUCTURE. ALTERNATIVE METHODS OF ATTACHMENT ONLY, NOTHING TO DAMAGE LANDLORD'S BASE BUILDING STRUCTURE.
 - ALL PENETRATIONS TO ROOF MUST BE APPROVED BY LANDLORD. ALL RELATED ROOF WORK MUST BE DONE BY DOMAIN NORTHWEST'S DESIGNATED ROOFING CONTRACTOR, AT TENANT'S EXPENSE. COORDINATE ALL WORK WITH PROPERTY MANAGER'S ON SITE.
 - GO TO LABEL ALL ROOFTOP EQUIPMENT WITH TENANT NAME, SPACE NUMBER, AND EQUIPMENT IDENTIFICATION, PER DOMAIN NORTHWEST SPECIFICATIONS AND STANDARDS.
 - ALL ROOFTOP EQUIPMENT REQUIRED TO BE MECHANICALLY FASTENED TO ROOF.
 - ALL PIPING ON ROOF SHALL BE SUPPORTED ON PRE-MANUFACTURED PIPE SUPPORTS INSTALLED ON CARRY TREAD, SPACED PROPERLY TO SUPPORT PIPING




ROOFTOP UNIT DETAIL
SCALE: NONE 1




BRANCH TAKE-OFF FITTING DETAIL
SCALE: NONE 2




SUPPLY DUCT TAKE-OFF DETAIL
SCALE: NONE 3




PACKAGED ROOFTOP UNIT CURB BASE DETAIL
SCALE: NONE 4




KITCHEN UPBLAST GREASE EXHAUST FAN DETAIL
SCALE: NONE 5




CEILING MNTD. RETURN AIR GRILLE DETAIL
SCALE: NONE 6




PIPING AND CONDUIT ROOF PENETRATION DETAIL
SCALE: NONE 7




VERTICAL REFRIGERANT PIPE SUPPORT DETAIL
SCALE: NONE 8




HORIZONTAL REFRIGERANT PIPE SUPPORT DETAIL
SCALE: NONE 9




UL LISTED GREASE EXHAUST DUCT WRAP DETAIL
SCALE: NONE 10




UL LISTED GREASE EXHAUST DUCT ACCESS DOOR DETAIL
SCALE: NONE 11




RESTROOM DOWNBLAST EXHAUST FAN DETAIL
SCALE: NONE 12




DISHMACHINE UPBLAST EXHAUST FAN DETAIL
SCALE: NONE 13



SUSPENDED DEHUMIDIFICATION UNIT DETAIL
SCALE: NONE 14



EXPOSED DUCTWORK LAYOUT SCHEMATIC
SCALE: NONE 15



LINEAR SLOT DIFFUSER WITH SIDE CONNECTION DETAIL
SCALE: NONE 16



DATE	DESCRIPTION
10/27/2023	ISSUE FOR PERMIT
04/12/2024	ISSUE FOR CONSTRUCTION

DATE	DESCRIPTION
A	05/15/24 ADDENDUM A - CITY COMMENTS
1	05/20/24 OWNER COMMENTS - VE

SHEET TITLE:
MECHANICAL DETAILS

SHEET NUMBER:
M3.0

PROJECT NUMBER:
LAS23001



COMMERCIAL KITCHEN UTILITY EXHAUST FAN DETAIL
SCALE: NONE 1

COMPRESSOR CURB DETAIL
SCALE: NONE 2

NOT USED
SCALE: NONE 3

NOT USED
SCALE: NONE 4

NOT USED
SCALE: NONE 5

NOT USED
SCALE: NONE 6

NOT USED
SCALE: NONE 7

NOT USED
SCALE: NONE 8

NOT USED
SCALE: NONE 9

NOT USED
SCALE: NONE 10

NOT USED
SCALE: NONE 11

NOT USED
SCALE: NONE 12

NOT USED
SCALE: NONE 13


NOT USED
SCALE: NONE 14

NOT USED
SCALE: NONE 15



CORPORATE:
HAI HOSPITALITY
1306 W. OLTORF STREET, SUITE C
AUSTIN, TEXAS 78704
www.haihospitality.com

TBPE FIRM REGISTRATION# F-11678



05/24/2024
ISSUE FOR CONSTRUCTION

**LORO'S ASIAN SMOKEHOUSE & BAR
AUSTIN, TX**
11601 DOMAIN DR. #700
AUSTIN, TEXAS 78758

CLIENT: HAI HOSPITALITY
1306 W. OLTORF STREET, SUITE C
AUSTIN, TEXAS 78704

LORO
ASIAN SMOKEHOUSE & BAR

DATE	DESCRIPTION
10/27/2023	ISSUE FOR PERMIT
04/12/2024	ISSUE FOR CONSTRUCTION

DATE	DESCRIPTION
3	05/23/24 OWNER COMMENTS - VE
4	05/23/24 OWNER COMMENTS - VE

**MECHANICAL
DETAILS**


M3.1

PROJECT NUMBER:
LAS23001


HOOD INFORMATION									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188
HOOD INFORMATION									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188

HOOD OPTIONS									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188


HOOD OPTIONS									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188




MARK: 132 - DISH HOOD - SECTION 1
PLAN VIEW



MARK: 132 - DISH HOOD - SECTION 1
SECTION VIEW



MARK: 132 - DISH HOOD - SECTION 1
ELEVATION VIEW



PROJECT: LORO AUSTIN TX (THE DOMAIN)
REV: 6
MARK: 132 - DISH HOOD
ACUREX SOUTHERN CA & HAWAII - 2297
AMER TILLMAN@ACCUREX.COM
(909)430-5328

ACCUREX
AMER TILLMAN
ACUREX SOUTHERN CA & HAWAII - 2297
(909)430-5328

HOOD INFORMATION									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188

HOOD INFORMATION									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188

HOOD INFORMATION									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188

HOOD INFORMATION									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188

HOOD INFORMATION									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188

HOOD INFORMATION									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188


HOOD INFORMATION									
HOOD NO.	MARK	MODEL	HOOD DIMENSIONS (IN.)	HOOD LOAD/CONSTR.	EXHAUST DIMENSIONS (IN.)	EXHAUST MARKS	SUPPLY DIMENSIONS (IN.)	HANGING DIMENSIONS (IN.)	SECTION
1	132 - DISH HOOD	XO-96-S	LENGTH: 96.00 WIDTH: 48.00 HEIGHT: 30.00	96.00 48.00 30.00	CONSTR: 100 SS 100%	TOTAL CFM: 1400.0 DIA: 6.0 LENGTH: 10.0	CFM: 350.0 S.P.: 0.339 DIA: 7.00	18.00 18.00 18.00	188

CONTROL INFORMATION									
MARK	ELECTRICAL CONTROL PACKAGE MODEL	USER INTERFACE LOCATION	TYPE	FULL COLOR TOUCHSCREEN	SHIP LOOSE CABINET				
231D - CONTROLS	XXC-DOV-S-31-41-10	SHIP LOOSE CABINET	TOUCHSCREEN	YES	NO				

CONTROL FEATURES:
HOOD LIGHT CONTROL
TEMP SENSORS (FACTORY INSTALLED) - QTY: 4
DRY FIRE CONTACTS - QTY: 2
EXHAUST MAX DURING FIRE
SUPPLY OFF DURING FIRE
GAS RESET

FANS CONTROLS									
ZONE #	ZONE	ROOM TEMP	HOOD CONFIGURATION	HOOD MARK	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY
1	21	PRESET	HOOD 1	TS-1A	TS-1B	TS-1C	TS-1D	TS-1E	TS-1F
2	22	PRESET	HOOD 2	TS-2A	TS-2B	TS-2C	TS-2D	TS-2E	TS-2F
3	23	PRESET	HOOD 3	TS-3A	TS-3B	TS-3C	TS-3D	TS-3E	TS-3F
4	24	PRESET	HOOD 4	TS-4A	TS-4B	TS-4C	TS-4D	TS-4E	TS-4F


WIRING DIAGRAM									
WIRING DIAGRAM CODE	WDC#	WIRING DIAGRAM CODE	WDC#	WIRING DIAGRAM CODE	WDC#				
WIRING DIAGRAM CODE	WDC#	WIRING DIAGRAM CODE	WDC#	WIRING DIAGRAM CODE	WDC#				



POWER WIRING FROM BREAKER PANEL DIRECT TO FANS (WIRING TO BE DONE BY ELECTRICIAN)
WIRING TO BE DONE BY ELECTRICIAN



DRY FIRE CONTACTS (WIRING TO BE DONE BY ELECTRICIAN)




TEMP SENSORS (WIRING TO BE DONE BY ELECTRICIAN)




EXHAUST FANS (WIRING TO BE DONE BY ELECTRICIAN)




SUPPLY FANS (WIRING TO BE DONE BY ELECTRICIAN)




CABINET DETAILS (DRAWING NOT TO SCALE)
MOUNTING LOCATION: SHIP LOOSE UTILITY CABINET (MINOR CONTROL: 60K, 12 X 20 X 6)
NOTES: 1) CONTROLS ARE MOUNTED IN HOOD MOUNTED OR WALL MOUNTED UTILITY CABINET FOR HOOD OR WALL MOUNTED UTILITY CABINETS. DIMENSIONS SEE HOOD SUBMITTAL.
2) MINIMUM OF 3\"/>



USER INTERFACE DETAILS (DRAWING NOT TO SCALE)
MOUNTING TYPE: RECESSED INTO WALL
USER INTERFACE CONTROL: FANS AND LIGHTS
INTERFACE CABLE LENGTH: SHIP (FACTORY PROVIDED)




POWER WIRING FROM BREAKER PANEL DIRECT TO FANS (WIRING TO BE DONE BY ELECTRICIAN)



DRY FIRE CONTACTS (WIRING TO BE DONE BY ELECTRICIAN)



TEMP SENSORS (WIRING TO BE DONE BY ELECTRICIAN)



EXHAUST FANS (WIRING TO BE DONE BY ELECTRICIAN)

ZONE CONFIGURATION									
ZONE #	ZONE	ROOM TEMP	HOOD CONFIGURATION	HOOD MARK	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY
1	21	PRESET	HOOD 1	TS-1A	TS-1B	TS-1C	TS-1D	TS-1E	TS-1F
2	22	PRESET	HOOD 2	TS-2A	TS-2B	TS-2C	TS-2D	TS-2E	TS-2F
3	23	PRESET	HOOD 3	TS-3A	TS-3B	TS-3C	TS-3D	TS-3E	TS-3F
4	24	PRESET	HOOD 4	TS-4A	TS-4B	TS-4C	TS-4D	TS-4E	TS-4F

HOOD CONFIGURATION									
HOOD #	HOOD	HOOD MARK	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY	HOOD EXHAUST SUPPLY
1	HOOD 1	TS-1A	TS-1B	TS-1C	TS-1D	TS-1E	TS-1F	TS-1G	TS-1H
2	HOOD 2	TS-2A	TS-2B	TS-2C	TS-2D	TS-2E	TS-2F	TS-2G	TS-2H
3	HOOD 3	TS-3A	TS-3B	TS-3C	TS-3D	TS-3E	TS-3F	TS-3G	TS-3H
4	HOOD 4	TS-4A	TS-4B	TS-4C	TS-4D	TS-4E	TS-4F	TS-4G	TS-4H

FAN CONFIGURATION									
FAN #	FAN	FAN MARK	FAN EXHAUST SUPPLY	FAN EXHAUST SUPPLY	FAN EXHAUST SUPPLY	FAN EXHAUST SUPPLY	FAN EXHAUST SUPPLY	FAN EXHAUST SUPPLY	FAN EXHAUST SUPPLY
1	FAN 1	TS-1A	TS-1B	TS-1C	TS-1D	TS-1E	TS-1F	TS-1G	TS-1H
2	FAN 2	TS-2A	TS-2B	TS-2C	TS-2D	TS-2E	TS-2F	TS-2G	TS-2H
3	FAN 3	TS-3A	TS-3B	TS-3C	TS-3D	TS-3E	TS-3F	TS-3G	TS-3H
4	FAN 4	TS-4A	TS-4B	TS-4C	TS-4D	TS-4E	TS-4F	TS-4G	TS-4H

SUPPLY CONFIGURATION									
SUPPLY #	SUPPLY	SUPPLY MARK	SUPPLY EXHAUST SUPPLY	SUPPLY EXHAUST SUPPLY	SUPPLY EXHAUST SUPPLY	SUPPLY EXHAUST SUPPLY	SUPPLY EXHAUST SUPPLY	SUPPLY EXHAUST SUPPLY	SUPPLY EXHAUST SUPPLY
1	SUPPLY 1	TS-1A	TS-1B	TS-1C	TS-1D	TS-1E	TS-1F	TS-1G	TS-1H
2	SUPPLY 2	TS-2A	TS-2B	TS-2C	TS-2D	TS-2E	TS-2F	TS-2G	TS-2H
3	SUPPLY 3	TS-3A	TS-3B	TS-3C	TS-3D	TS-3E	TS-3F	TS-3G	TS-3H
4	SUPPLY 4	TS-4A	TS-4B	TS-4C	TS-4D	TS-4E	TS-4F	TS-4G	TS-4H

TOTAL WEIGHT									
ITEM	QUANTITY	WEIGHT (LBS)	TOTAL WEIGHT (LBS)						
HOOD	4	21.5	86.0						
EXHAUST	4	21.5	86.0						
SUPPLY	4	21.5	86.0						
TOTAL			258.0						

TOTAL WEIGHT: 258.0 LBS

NOTE: 1) INFORMATION PRESENTED HERE IS PROVIDED FOR REFERENCE ONLY AND NOT PREPARED BY ENGINEER OF RECORD. AS SUCH, THE EOR ASSUMES NO RESPONSIBILITY FOR ERRORS, OMISSIONS, OR CODE COMPLIANCE ISSUES IN THE EXHAUST HOOD MANUFACTURER'S DOCUMENTS.

NOTE: 2) INFORMATION PRESENTED HERE IS PROVIDED FOR REFERENCE ONLY AND NOT PREPARED BY ENGINEER OF RECORD. AS SUCH, THE EOR ASSUMES NO RESPONSIBILITY FOR ERRORS, OMISSIONS, OR CODE COMPLIANCE ISSUES IN THE EXHAUST HOOD MANUFACTURER'S DOCUMENTS.

NOTE: 3) INFORMATION PRESENTED HERE IS PROVIDED FOR REFERENCE ONLY AND NOT PREPARED BY ENGINEER OF RECORD. AS SUCH, THE EOR ASSUMES NO RESPONSIBILITY FOR ERRORS, OMISSIONS, OR CODE COMPLIANCE ISSUES IN THE EXHAUST HOOD MANUFACTURER'S DOCUMENTS.

NOTE: 4) INFORMATION PRESENTED HERE IS PROVIDED FOR REFERENCE ONLY AND NOT PREPARED BY ENGINEER OF RECORD. AS SUCH, THE EOR ASSUMES NO RESPONSIBILITY FOR ERRORS, OMISSIONS, OR CODE COMPLIANCE ISSUES IN THE EXHAUST HOOD MANUFACTURER'S DOCUMENTS.



NOTE: 5) INFORMATION PRESENTED HERE IS PROVIDED FOR REFERENCE ONLY AND NOT PREPARED BY ENGINEER OF RECORD. AS SUCH, THE EOR ASSUMES NO RESPONSIBILITY FOR ERRORS, OMISSIONS, OR CODE COMPLIANCE ISSUES IN THE EXHAUST HOOD MANUFACTURER'S DOCUMENTS.

MARK INFORMATION		FAN INFORMATION		OPERATING INFORMATION		MOTOR INFORMATION							
QTY	MARK	MODEL	VOLUME TOTAL (CFM)	RPM	OPERATING RPM	WEIGHT (LB)	SIZE (HP)	VICP	ENCLOSURE	MOTOR	WINDINGS	NEC FLA*	
1	2B - KEF-3	XUEF-15	1,900	1,5	1,408	0.72	188	1	208/80/3	TF	1725	1	4.6

*NEC FLA - Based on table 430.250 or 430.245 of National Electrical Code 2020. Actual motor FLA may vary for sizing thermal overload, consult factory.

2B - KEF-3 - SELECTED OPTIONS AND ACCESSORIES

Finish - Coated
 Coating - Permeator, Concrete Gray-RAL 7023, Mill Finish on Aluminum Components
 Isolators, Isolator-Spring, Restaurant, 1 Inch, Indoor / Outdoor Use, Base Coating - N/A
 Bearings - CM
 Bearings - 1/10 Standard Life, 1000h hours at Operating Point
 Discharge Position - UB
 ULULU-762 Outdoor - Power Vent, for Restaurant Exhaust Appliances
 Polished Steel Shaft
 Drain Connection - 1 inch threaded male
 Extended Lubrication Lines - Nylon
 Inlet Flange, Punched
 Outlet Connection, Slip Fit
 Weatherhood - Steel Construction
 Grease Trap, Shipped Loose
 Fasteners - Standard





MARK INFORMATION		FAN INFORMATION		OPERATING INFORMATION		MOTOR INFORMATION							
QTY	MARK	MODEL	VOLUME TOTAL (CFM)	RPM	OPERATING RPM	WEIGHT (LB)	SIZE (HP)	VICP	ENCLOSURE	MOTOR	WINDINGS	NEC FLA*	
1	231B - KEF-1	XUEF-18	3,752	2	1,410	1.85	314	5	208/80/3	OP	1170	1	4.6

*NEC FLA - Based on table 430.250 or 430.245 of National Electrical Code 2020. Actual motor FLA may vary for sizing thermal overload, consult factory.

231B - KEF-1 - SELECTED OPTIONS AND ACCESSORIES

Finish - Coated
 Coating - Permeator, Concrete Gray-RAL 7023, Mill Finish on Aluminum Components
 Isolators, Isolator-Spring, Restaurant, 1 Inch, Indoor / Outdoor Use, Base Coating - N/A
 Bearings - CM
 Bearings - 1/10 Standard Life, 1000h hours at Operating Point
 Discharge Position - UB
 ULULU-762 Outdoor - Power Vent, for Restaurant Exhaust Appliances
 Polished Steel Shaft
 Drain Connection - 1 inch threaded male
 Extended Lubrication Lines - Nylon
 Inlet Flange, Punched
 Outlet Connection, Slip Fit
 Motor Cover - Steel Construction
 Shaft Seal - Standard
 Grease Trap, Shipped Loose
 Fasteners - Standard



NOTE: THE INFORMATION PRESENTED HERE IS PROVIDED FOR REFERENCE ONLY AND WAS NOT PREPARED BY ENGINEER OF RECORD. AS SUCH, THE EOR ASSUMES NO RESPONSIBILITY FOR ERRORS, OMISSIONS, OR CODE COMPLIANCE ISSUES IN THE EXHAUST HOOD MANUFACTURER'S DOCUMENTS.

idstudio
 600 CAMPUS CIRCLE DRIVE E
 AUSTIN, TEXAS 78705
 TEL: 512.707.0288
 WWW.IDSTUDIO.COM

CORPORATE:
HAI HOSPITALITY
 1306 W. OLTORF STREET, SUITE C
 AUSTIN, TEXAS 78704
 www.haihospitality.com

TBPE FIRM REGISTRATION# F-11678

 05/24/2024
ISSUE FOR CONSTRUCTION

LORO'S ASIAN SMOKEHOUSE & BAR
 AUSTIN, TX
 11601 DOMAIN DR. #700
 AUSTIN, TEXAS 78758
 CLIENT: HAI HOSPITALITY
 1306 W. OLTORF STREET, SUITE C
 AUSTIN, TEXAS 78704

LORO
 ASIAN SMOKEHOUSE & BAR

DATE	DESCRIPTION
10/27/2023	ISSUE FOR PERMIT
04/12/2024	ISSUE FOR CONSTRUCTION

DATE	DESCRIPTION
1	ISSUE FOR CONSTRUCTION
2	OWNER COMMENTS - VE
3	OWNER COMMENTS - VE

SHEET TITLE:
HOOD DRAWINGS

SHEET NUMBER:
M4.3

PROJECT NUMBER:
LAS23001


EQUIPMENT SCHEDULE

Main Name		Qty		Packaging		Mounting Location		Weight	
MAU-1		1		30X30-30-1AT		Outdoor		2,471.5	
Supply Volume		Supply ESP	Supply TSP	Frequency	Phase	MA	MDP	MD	MDP
4,132 CFM		3.1 in. wg	2.972 in. wg	2741	3	103.4	1	103.4	1
Cooling Section		Total Capacity		Sensible Capacity		Latent Capacity		Total Capacity	
4,132 Btu/h		237.2 MBH		137.2 MBH		237.2 MBH		474.4 MBH	
4,132 Btu/h		49.8 F		49.8 F		49.8 F		49.8 F	
Fan Section		Total Capacity		Sensible Capacity		Latent Capacity		Total Capacity	
4,132 Btu/h		237.2 MBH		137.2 MBH		237.2 MBH		474.4 MBH	
4,132 Btu/h		49.8 F		49.8 F		49.8 F		49.8 F	
Control Section		Total Capacity		Sensible Capacity		Latent Capacity		Total Capacity	
4,132 Btu/h		237.2 MBH		137.2 MBH		237.2 MBH		474.4 MBH	
4,132 Btu/h		49.8 F		49.8 F		49.8 F		49.8 F	
Accessories		Total Capacity		Sensible Capacity		Latent Capacity		Total Capacity	
4,132 Btu/h		237.2 MBH		137.2 MBH		237.2 MBH		474.4 MBH	
4,132 Btu/h		49.8 F		49.8 F		49.8 F		49.8 F	


Curb Installation Instructions

1. Ensure correct GND (GROUND) connections. The curbs are model GND which ship in a knockdown assembly (by others) on all units except the curbs. Assembly instructions are included with the curb kit.
2. Install curb. Locate curb over roof.
3. Shim the curb to level. Shim the curb so that the diagonal dimensions are within ± 1/8 inch of each other and adjust as necessary. For proper coil drainage and unit operation, it is important that the curb be level. Shim the curb as required to level. Install gasketing on top surface of curb (provided by others).
4. Seal the unit. Lift unit to a point directly above the curb and duct openings. Guide unit while lowering to align with duct openings. Make sure the unit is properly seated on the curb and level.
5. Fasten the unit. Fasten the unit to the curb using the provided fasteners. The installer is responsible for determining appropriate support and fastening methods to ensure proper operation of the unit.
6. Install vestibule. If unit was ordered with a vestibule and it has not yet been attached to the unit, caulk and attach the vestibule at this time.

Curb Specifications			
Height (in)	Length (in)	Width (in)	Material
14	81.9	45.9	Galvanized
			Galvanized
			Weight (lb)
			223




Back Right Isometric




Service Clearances

Front Left Isometric


Curb Detail




Dimensional Overview




Plan



Right End



Elevation



Left End

NOTE:
 THE INFORMATION PRESENTED HERE IS PROVIDED FOR REFERENCE ONLY AND WAS NOT PREPARED BY ENGINEER OF RECORD. AS SUCH, THE EOR ASSUMES NO RESPONSIBILITY FOR ERRORS, OMISSIONS, OR CODE COMPLIANCE ISSUES IN THE EXHAUST HOOD MANUFACTURER'S DOCUMENTS.

DATE	DESCRIPTION
10/27/2023	ISSUE FOR PERMIT
04/12/2024	ISSUE FOR CONSTRUCTION

SHEET TITLE:
HOOD DRAWINGS

SHEET NUMBER:
M4.5

PROJECT NUMBER:
LAS23001

LORO ASIAN SMOKEHOUSE & BAR
 11601 DOMAIN DR. #700
 AUSTIN, TEXAS 78758
 CLIENT: HAI HOSPITALITY
 1306 W. OLTORF STREET, SUITE C
 AUSTIN, TEXAS 78704


TBPE FIRM REGISTRATION# F-11678
JOHN G. SISK
 101260
 05/24/2024
ISSUE FOR CONSTRUCTION

HAI HOSPITALITY
 1306 W. OLTORF STREET, SUITE C
 AUSTIN, TEXAS 78704
 www.haihospitality.com

idstudio
 6307 CAMPUS CIRCLE DRIVE E
 AUSTIN, TEXAS 78752
 WWW.IDSTUDIO.COM




ACCUREX



ACCUREX
 AMK51P1RX0052GSZ2
 ACCUREX, INC. 11601 DOMAIN DR. #700 AUSTIN, TX 78758
 TEL: 512.370.0288 WWW.ACCUREX.COM

NOTE:
 THE INFORMATION PRESENTED HERE IS PROVIDED FOR REFERENCE ONLY AND WAS NOT PREPARED BY ENGINEER OF RECORD. AS SUCH, THE EOR ASSUMES NO RESPONSIBILITY FOR ERRORS, OMISSIONS, OR CODE COMPLIANCE ISSUES IN THE EXHAUST HOOD MANUFACTURER'S DOCUMENTS.

ACCUREX
 ACCUREX SOUTHERN GA HWY 111 - 2297
 AMER TILLMAN@ACCUREX.COM
 AMER TILLMAN
 (909) 430-5328
 MARK
 PROJECT LORO AUSTIN TX (THE DOMAIN)
 MAU-1
 REV.6
 4/11/2024



SENSORS
 SAD: Supply air discharge temperature
 OAI: Outdoor air intake temperature
 CS: Condensate overflow switch
 CGCT: Cooling coil temperature
 OARH: Outdoor air intake relative humidity
 ST: Space temperature



HAI HOSPITALITY
 1306 W. OLTORF STREET, SUITE C
 AUSTIN, TEXAS 78704
 www.haihospitality.com



05/24/2024
ISSUE FOR CONSTRUCTION

LORO'S ASIAN SMOKEHOUSE & BAR
 AUSTIN, TX
 11601 DOMAIN DR. #700
 AUSTIN, TEXAS 78758
 CLIENT: HAI HOSPITALITY
 1306 W. OLTORF STREET, SUITE C
 AUSTIN, TEXAS 78704

LORO
 ASIAN SMOKEHOUSE & BAR

DATE	DESCRIPTION
10/27/2023	ISSUE FOR PERMIT
04/12/2024	ISSUE FOR CONSTRUCTION

HOOD DRAWINGS

M4.6
 PROJECT NUMBER:
 LAS23001

GENERAL NOTES	
A.	ALL OUTDOOR AIR INTAKES BY MECHANICAL EQUIPMENT SHALL HAVE A MINIMUM 10'-0" HORIZONTAL CLEARANCE FROM THE DISCHARGE OF ANY EXHAUST FAN, COMBUSTION EXHAUST OR PLUMBING VENT.
B.	PROVIDE VIBRATION ISOLATION DEVICES AND FLEXIBLE DUCT/PIPING CONNECTIONS TO ALL MOVING MACHINERY NOT INTERNALLY ISOLATED.
C.	ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR ALL ELECTRICAL WORK SHOWN ON THE MECHANICAL DRAWINGS.
D.	ALL METALLIC NATURAL GAS PIPING EXPOSED ON THE ROOF SHALL BE FIELD PAINTED YELLOW WITH WEATHER RESISTANT PAINT, BY THE INSTALLING CONTRACTOR.
E.	GENERAL CONTRACTOR TO FIELD VERIFY STRUCTURAL ELEVATIONS FOR ADEQUATE SPACE FOR NEW DUCTWORK, PIPING, AND EQUIPMENT ABOVE THE CEILING. NOTIFY OWNER AND DESIGNER IMMEDIATELY OF ANY SUSPECTED INSTALLATION OR FIELD ISSUES RELATING TO THIS SPACE.

GENERAL NOTES	
A.	ALL ROOFTOP EQUIPMENT SHALL BE SURROUNDED BY WALKWAY PADS AS APPROVED BY LANDLORD. COORDINATE FINAL LOCATION, MATERIAL, AND INSTALLATION OF PADS WITH THE OPERATIONS TEAM PRIOR TO START OF ANY WORK.
B.	ALL ROOF PENETRATIONS TO ROOF MUST BE APPROVED BY LANDLORD. ALL ROOF WORK MUST BE DONE BY DOMAIN NORTHSIDE ROOFING CONTRACTOR AS APPROVED BY LANDLORD.
C.	ALL ROOFTOP EQUIPMENT SHALL BE MECHANICALLY FASTENED TO ROOF.
D.	ALL PIPING ON ROOF SHALL BE SUPPORTED ON PRE-MANUFACTURED PIPE SUPPORTS INSTALLED ON GARRY TREAD, SPACED PROPERLY TO SUPPORT PIPING.
E.	ALL CONDENSATION, ELECTRICAL, AND DUCTWORK SHALL BE SET INSIDE THE PERIMETER OF THE CURB AS APPROVED BY LANDLORD. CONDENSATE SHALL DRAIN INTO AN INTERIOR FLOOR DRAIN OR MOP SINK LOCATION WITHIN THE SPACE.
F.	ALL ROOFTOP EQUIPMENT SHALL BE LABELED IN ACCORDANCE WITH LANDLORD DESIGN CRITERIA. LABEL SHALL INCLUDE TENANT NAME, SPACE NUMBER, AND EQUIPMENT IDENTIFICATION.


KEYED NOTES	
1.	INTERWIRE SERVICE FROM COOLER COMPRESSOR AND TIMECLOCK TO BLOWER COIL FOR AUTOMATIC DEFROST SYSTEM TO STOP COMPRESSOR BLOWER COIL FANS AND START HEATERS IN COIL. RUN CONDUIT ABOVE CEILING. THESE ITEMS ARE NOT PRE-WIRED AND WILL REQUIRE CONNECTIONS BY ELECTRICIAN AND FIELD WIRING.
2.	INTERWIRE SERVICE FROM BEER COOLER COMPRESSOR AND TIMECLOCK TO BLOWER COIL FANS AND START HEATERS IN COIL. RUN CONDUIT ABOVE CEILING. THESE ITEMS ARE NOT PRE-WIRED AND WILL REQUIRE CONNECTIONS BY ELECTRICIAN AND FIELD WIRING.
3.	ELECTRICAL CONTRACTOR SHALL RUN CONTROL WIRING TO ROOF TOP UNITS, SENSORS, AND THERMOSTATS. COORDINATE WITH MECHANICAL CONTRACTOR.
4.	WEATHERPROOF MOTOR RATED SWITCH. PROVIDE 24" FLEXIBLE LOOP CONNECTION TO UNIT FOR MAINTENANCE.
5.	VERIFY LOCATION & NUMBER OF SIGNS WITH SIGN VENDOR. RUN SIGN CIRCUITS THROUGH RELAY. REFER TO EXTERIOR LIGHTING CONTROL DIAGRAM. REFER TO 6/E3.0. PROVIDE FLUSH MOUNTED WP J-BOX IN EXTERIOR FACE OF WALL. PROVIDE DISCONNECTING MEANS PER NEC AND LOCAL AUTHORITY HAVING JURISDICTION.

KEYED NOTES	
6.	CONDENSATE DRAIN PIPING FROM THE HVAC UNIT SHALL BE ROUTED ON THE ROOF AS SHOWN, AT A MINIMUM PITCH OF 1/4" PER FOOT IN THE DIRECTION OF FLOW. REFER TO THE PLUMBING DW PLAN FOR CONTINUATION OF CONDENSATE DRAINAGE PIPING BELOW THE ROOF.
7.	GAS PIPING TO THE MECHANICAL UNIT SHALL BE COMPLETE WITH GAS COCK, UNION, PRESSURE REGULATOR & 6" DIRT LEG.
8.	ALL PIPING INSTALLED ON THE ROOF SHALL BE SUPPORTED WITH PRE-MANUFACTURED ADJUSTABLE PIPE SUPPORTS AT MAXIMUM 5'-0" ON CENTER AND EVERY CHANGE OF DIRECTION.
9.	ROOF MOUNTED VTR, SIZED AS SHOWN. INSTALLED LOCATION SHALL BE A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE. TOP OF VTR STACK SHALL BE EVEN WITH PARAPET WALL.
10.	INSTALL COMPLETE WITH MANUFACTURER FURNISHED WINDBAND EXTENSION COLLAR TO PROVIDE A MINIMUM 36" VERTICAL SEPARATION PER SECTION 401.4 OF THE 2021 IMC. FROM THE EXHAUST TERMINATION ABOVE THE INTAKE OF ANY ADJACENT MECHANICAL EQUIPMENT.

KEYED NOTES	
11.	PRE-MANUFACTURED ROOF JACK FOR REFRIGERATION PIPING AND POWER CONDUIT(S) SHALL BE PROVIDED BY THE GENERAL CONTRACTOR. REFER TO ARCHITECTURAL DETAILS FOR DIRECTION. THE MC, EA AND GC SHALL COORDINATE FOR A COMPLETE INSTALLATION.
12.	CONDENSING UNIT SHALL BE INSTALLED PER MANUFACTURER'S CURB INSTALLATION INSTRUCTIONS (AS APPROVED BY THE MANUFACTURER). FIELD COORDINATE THE COMPLETE INSTALLATION. REF 2/M3.1 FOR PROPOSED MOUNTING.
13.	MANUFACTURER'S AVAILABLE CONCENTRIC COMBUSTION AIR VENT FOR THE GAS FIRED TANK WATER HEATERS BELOW. COORDINATE THE ROOF PENETRATIONS, FLASHINGS AND COUNTER-FLASHINGS WITH THE GENERAL CONTRACTOR.
14.	GAS PIPING SHALL BE ROUTED DOWN THROUGH THE ROOF. PROVIDE WEATHER TIGHT SEAL AT PIPE PENETRATION. REFER TO THE GAS PLUMBING PLAN FOR CONTINUATION OF PIPING BELOW THE ROOF.
15.	HVAC CONDENSATE DRAIN PIPING SHALL BE ROUTED DOWN THROUGH THE ROOF TO TERMINATION BELOW. REFER TO THE PLUMBING DW PLAN FOR CONTINUATION OF CONDENSATE DRAINAGE PIPING BELOW THE ROOF.
16.	PROVIDE AND INSTALL A WEATHERPROOF JUNCTION BOX FOR MOTORIZED DAMPER WITHIN MUA UNIT. VERIFY EXACT LOCATION PRIOR TO ROUGH IN.

KEYED NOTES	
17.	CONTRACTOR SHALL PROVIDE ALL ELECTRICAL CONNECTIONS, WIRING AND CONDUITS NECESSARY FOR THE INTERLOCKING OF KITCHEN EXHAUST FANS AND MAKEUP AIR UNIT THROUGH THE KITCHEN CONTROL PANEL.
18.	NEW ROOFTOP UNIT SHALL BE LOCATED IN EXISTING ROOFTOP UNIT LOCATION AND SHALL REUSE EXISTING ROOF OPENING. FIELD VERIFY SIZE AND LOCATION PRIOR TO INSTALLATION. FIELD COORDINATE WITH EXISTING STRUCTURE.
19.	WEATHER PROOF DISCONNECT SWITCH, SIZE AS NOTED. ROUTE FEEDER DOWN TO PRE-WIRED ELECTRICAL CONTROL PANEL ON KITCHEN HOOD. DISCONNECT SWITCH TO ARRIVE FACTORY INSTALLED ON FAN.
20.	WEATHER PROOF DISCONNECT SWITCH TO ARRIVE FACTORY INSTALLED ON RTU.
21.	ROUTE ELECTRICAL POWER FROM EXHAUST FAN THROUGH DISHWASHER CONTROLLER. REFER TO DISHWASHER EXHAUST ELECTRICAL SCHEMATIC DIAGRAM.
22.	ROUTE 3/4" COLD WATER UP THROUGH ROOF AND CONNECT TO ROOF HYDRANT. REFER TO THE WATER AND GAS PLUMBING PLAN FOR CONTINUATION OF PIPING BELOW THE ROOF.
23.	EXISTING ROOFTOP UNIT SHALL BE EXISTING TO REMAIN. FIELD VERIFY SIZE AND LOCATION.

KEYED NOTES	
24.	FIELD ROUTE GAS SERVICE PIPING UP FROM EXISTING GAS METER AND MANIFOLD. ROUTE ON THE ROOF AS SHOWN. REFER TO SHEET P1.3 PLAN FOR CONTINUATION.
25.	24" X 24" ROOF JACK FOR BLIZZARD BEER SYSTEM. OPENING IN ROOF BY GC. ROOF JACK BY BLIZZARD. BEER SYSTEM GLYCOL AND POWER TO BE ROUTED THROUGH BLIZZARD ROOF JACK.
26.	EXISTING DISCONNECT SWITCH AND CIRCUIT TO REMAIN.
27.	EXISTING GAS MANIFOLD.
29.	REMOTE ROOF MOUNTED CONDENSING UNIT FOR WALL MOUNTED DUCTLESS AIR HANDLING UNIT IN OUTDOOR BAR BELOW.
30.	FIELD ROUTE GAS SERVICE PIPING DOWN TO PATIO. REFER TO SHEET P1.3 PLAN FOR CONTINUATION.
31.	EXISTING PARAPET EXCEEDS 42" IN HEIGHT. NO SAFETY RAIL GUARDS REQUIRED PER SECTION 303.8.4 OF THE 2021 UNIFORM MECHANICAL CODE.
32.	ROUTE GREASE EXHAUST DUCT FROM ROOF MOUNTED EXHAUST FAN DOWN THRU ROOF. COORDINATE ROOF PENETRATION AND FLASHING WITH ROOFING CONTRACTOR. REFER TO M2.0 FOR PROPOSED MATERIALS OF THE ROOF MOUNTED DUCTWORK.
33.	EXISTING ROOF MOUNTED CONDENSING UNIT FOR ADJACENT TENANT SHALL BE RELOCATED TO LOCATION SHOWN AS APPROVED BY LANDLORD. FIELD VERIFY CONDITION OF UNIT PRIOR TO RELOCATION. EXISTING CONDITION OF CONDENSING UNIT SHALL BE MAINTAINED DURING AND AFTER RELOCATION OF UNIT. FIELD COORDINATE COMPLETE INSTALLATION WITH LANDLORD'S REQUIREMENTS AND MANUFACTURER'S INSTALLATION INSTRUCTIONS. MAINTAIN ACCESS FOR REQUIRED CLEARANCE(S) FOR MAINTENANCE AND CLEANING. FIELD VERIFY FINAL LOCATION WITH NEW ROOFTOP EQUIPMENT.
34.	EXISTING REFRIGERANT LINES AND CONDUIT TO BE MAINTAINED THROUGH RELOCATION OF EXISTING CONDENSING UNITS. REMOVE REFRIGERANT FROM EXISTING REFRIGERANT LINES AND DISCONNECT POWER FROM ADJACENT TENANT PANEL PRIOR TO CONDENSING UNIT DISCONNECTION. COORDINATE EXISTING ROOF PENETRATION LOCATION WITH NEW ROOFTOP EQUIPMENT AND RELOCATE AS NECESSARY. PROVIDE NEW REFRIGERANT LINES AND CONDUIT AS NECESSARY TO RECONNECT RELOCATED CONDENSING UNITS TO EXISTING REFRIGERANT LINES AND CONDUIT. FIELD COORDINATE COMPLETE INSTALLATION WITH LANDLORD AND MANUFACTURER'S INSTALLATION INSTRUCTIONS.



id studio
6300 CAMPOS CIRCLE DRIVE E
AUSTIN, TEXAS 78705
WWW.IDSTUDIO.COM

HAI HOSPITALITY
1306 W. OLTORF STREET, SUITE C
AUSTIN, TEXAS 78704
www.haihospitality.com

TBPE FIRM REGISTRATION# F-11678

JOHN G. SISK
101280
ENR 0000000000

05/24/2024
ISSUE FOR CONSTRUCTION

LORO'S ASIAN SMOKEHOUSE & BAR
AUSTIN, TX
11601 DOMAIN DR #700
AUSTIN, TEXAS 78758

CLIENT: HAI HOSPITALITY
1306 W. OLTORF STREET, SUITE C
AUSTIN, TEXAS 78704

LORO
ASIAN SMOKEHOUSE & BAR

DATE	DESCRIPTION
10/27/2023	ISSUE FOR PERMIT
04/12/2024	ISSUE FOR CONSTRUCTION

DATE	DESCRIPTION
A	05/15/24 ADDRESS/A - CITY COMMENTS
B	04/15/24 OWNER COMMENTS - VE
C	05/15/24 OWNER COMMENTS - VE

MEP ROOF PLAN

MEP1.0