

NIKE INC.
ONE BOWERMAN DRIVE
BEAVERTON, OR 97005



MBH PROJECT: 55391

HENDERSON
ENGINEERS
8345 LENEXA DRIVE, SUITE 300
LENEXA, KS 66214
TEL 913.742.5000 FAX 913.742.5001
WWW.HENDERSONENGINEERS.COM
2150003353
MO. CORPORATE NO. E-6360
EXPRES 02/01/2022

Date	No.	Description
03/14/2022		75% SET
04/14/2022		PERMIT/BID/LL SET

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF PRELIMINARY SUBMITTAL. BRADLEY E. CHAMBERN LICENSE # 028603

IT IS NOT TO BE USED FOR CONSTRUCTION PURPOSES

BRADLEY E. CHAMBERN
LICENSE # 028603

NIKE BY KANSAS CITY
COUNTRY CLUB PLAZA
450 NICHOLS RD,
KANSAS CITY, MO 64112

Project Number
Config: R/L
Drawn By HENDERSON
Checked By HENDERSON

MECHANICAL HVAC
PLAN

M-100

THE DUCTWORK LAYOUT INDICATED ON THE DRAWINGS IS SCHEMATIC AND SHOWS DESIGNED INTENT ONLY. PRIOR TO FABRICATION AND INSTALLATION OF DUCTWORK, DIVISION 23 SHALL HAVE A QUALIFIED, EXPERIENCED SKETCHER PREPARE AND SUBMIT SHEET METAL SHOP DRAWINGS. SHOP DRAWINGS SHALL TAKE INTO ACCOUNT ALL EXISTING CONDITIONS, INCLUDING BUT NOT LIMITED TO, STRUCTURAL MEMBERS, CONDUITS AND PIPING TO REMAIN. SHOP DRAWINGS SHALL ALSO TAKE INTO ACCOUNT ALL NEW DESIGN CONDITIONS, INCLUDING BUT NOT LIMITED TO, STRUCTURAL MEMBERS, PIPING, CEILINGS, SOFFIT HEIGHTS, AND LIGHT FIXTURES.

GENERAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING TO ARCHITECT, ENGINEER, LANDLORD, AND BUILDING OFFICIAL INSPECTOR A FINAL TEST AND BALANCE REPORT PER THE SPECIFICATIONS. PROVIDE TEST AND BALANCE REPORT TO ARCHITECT, ENGINEER, AND LANDLORD PRIOR TO THE FINAL BUILDING INSPECTION.

LANDLORD REQUIREMENTS:
LANDLORD APPROVED ROOFING CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING ALL CUTS THROUGH THE EXISTING ROOF, MODIFYING EXISTING OPENINGS, AND/OR ALTERING CURB FLASHING AT GENERAL CONTRACTOR'S EXPENSE. COORDINATE WITH GENERAL CONTRACTOR.

EMS CONTROLS:
CONTRACTORS ARE RESPONSIBLE FOR COORDINATING ALL EQUIPMENT CONTROLS WITH EMS VENDOR PRIOR TO PURCHASE AND INSTALLATION. CONTRACTORS SHALL COORDINATE WITH EMS VENDOR TO PROVIDE ALL NECESSARY EQUIPMENT AND ACCESSORIES FOR A FULLY FUNCTIONING SYSTEM.

TEMPERATURE CONTROLS:
EMS VENDOR SHALL FURNISH SENSORS AND CONTROL COMPONENTS AS INDICATED ON PLANS AND AS NECESSARY TO ACCOMPLISH THE INTENT OF THE DRAWINGS. ALL CONTROLS SHALL BE TIED INTO THE EMS SYSTEM UNLESS NOTED OTHERWISE.

GENERAL CONTRACTOR SHALL INSTALL CARRIER FURNISHED TEMPORARY THERMOSTATS AND FEED THE WIRING DOWN INTO THE SPACE FOR START UP AND CONTROL OF RTU(S) UNTIL THE EMS SYSTEM IS OPERABLE. REFER TO M3.0 FOR CARRIER CONTACT INFORMATION.


PROVIDE RFID DUCTWORK MESH OVER TRANSFER GRILLS BELOW 15'-0" AFF BETWEEN THE STOCKROOM AND THE SALES FLOOR, IF APPLICABLE.

KEYNOTES ARE PROTOTYPICAL. MISSING KEYNOTE NUMBERS INDICATE A PROTOTYPICAL NOTE IS NOT USED OR REMOVED.

MECHANICAL PLAN NOTES


- M01 ALL THERMOSTATS AND SENSORS ARE FURNISHED BY EMS VENDOR AND INSTALLED BY DIVISION 26. UNLESS NOTED OTHERWISE.
- M02 DO NOT INSTALL SENSORS ON WALL GRAPHICS. CONFIRM LOCATIONS OF SENSORS WITH PM PRIOR TO INSTALLATION.
- M03 INSTALL DAMPER AND ACTUATOR IN LOCATION INDICATED. DAMPER FURNISHED BY DIVISION 23. ACTUATOR FURNISHED BY EMS VENDOR.
- M10 PROVIDE NEW DX SPLIT SYSTEM UNITS AS SCHEDULED SUPPORTED FROM STRUCTURE ABOVE. PROVIDE A NEW SET OF MERV 13 AIR FILTERS IN UNIT BEFORE TURNING SYSTEM OVER TO OWNER. COORDINATE CONDENSATE PIPING WITH DIVISION 25.
- M18 ACCESS TO HVAC EQUIPMENT SHALL BE FROM LAY-IN CEILING. NO CEILING DEVICES SHALL BE PLACED IN THIS LOCATION. COORDINATE FINAL INSTALLED LOCATION SUCH THAT THE HVAC EQUIPMENT REMAINS ACCESSIBLE. VERIFY NO OTHER PIPING, ELECTRICAL CONDUIT, STRUCTURE, AND/OR CEILING SUPPORTS IMPEDE ACCESS IN ANY WAY. INSTALL HVAC EQUIPMENT WITHIN 24" ABOVE CEILING FOR SERVICEABILITY.
- M19 SMOKE DETECTORS AND WIRING IN RETURN AIR DUCTS SHALL BE PROVIDED BY DIVISION 26 CONTRACTOR. SMOKE DETECTORS SHALL SHUT-DOWN UNIT UPON ALARM.
- M22 PROVIDE NEW IN-LINE EXHAUST FAN AS SCHEDULED FOR GENERAL RESTROOM EXHAUST. INSTALL NEAR EXISTING EXHAUST DUCT PENETRATION TO LEASE SPACE. COORDINATE EXACT LOCATION PRIOR TO CONSTRUCTION.
- M23 EXHAUST FAN SERVES TO PROVIDE TRANSFER AIR ONLY AND SHALL DISCHARGE AIR INTO THE STOCKROOM PLENUM.
- M24 INSTALL VAV POWER MODULE FOR CONTROL OF OFFICE VAV DIFFUSERS IN AN ACCESSIBLE LOCATION ABOVE THE CEILING. DIVISION 26 CONTRACTOR SHALL PROVIDE 120V POWER TO MODULE. REFER TO ELECTRICAL DRAWINGS FOR DETAILS.
- M34 DO NOT ROUTE DUCTWORK OVER ELECTRICAL EQUIPMENT. NOTIFY ENGINEER OF CONFLICTS IN FIELD.
- M48 COORDINATE DUCTWORK WITH EXISTING STRUCTURE, LANDLORD PIPES, AND OTHER OBSTACLES PRIOR TO CONSTRUCTION. DUCTWORK SHALL BE ROUTED WITHIN BEAMS AT THE SAME HEIGHT AS THE EXISTING DUCTWORK. TRANSITION AS NEEDED TO AVOID CONFLICTS AND RELOCATE OBSTACLES WHEREVER FEASIBLE.
- M65 LOUVERED DOOR FOR [RELIEF/MAKEUP] AIR BY GENERAL CONTRACTOR. REFER TO ARCHITECTURAL DRAWINGS FOR MORE INFORMATION.
- M66 PROVIDE GRILLE ON WALL FOR TRANSFER AIR. MOUNT AS HIGH AS POSSIBLE WITHIN STRUCTURE AND INSTALL WITH BLADES ANGLED UP TOWARDS STRUCTURE FOR REDUCED VISIBILITY.
- M67 COORDINATE LOCATION OF FITTING ROOM DIFFUSERS WITH LIGHTS, SPRINKLERS, SPEAKERS, AND OTHER CEILING DEVICES FOR A NEAT AND ORDERLY INSTALLATION. INSTALL CEILING DEVICES IN-LINE WITH EACH OTHER WHERE POSSIBLE.
- M69 INSTALL DUCT-MOUNTED DIFFUSERS WITH BLADES ANGLED AT 45° TOWARDS THE SALES FLOOR. DUCT-MOUNTED DIFFUSERS SHALL HAVE INTEGRAL DAMPER ADJUSTABLE FROM FACE OF DEVICE.

INSTALL DUCTWORK AND PIPING AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS. COORDINATE INSTALLATION OF DUCTWORK AND PIPING TO AVOID CONFLICTS WITH ELECTRICAL PANELS, LIGHTING FIXTURES, ETC. NOTIFY CONSTRUCTION PROJECT MANAGER OF CONFLICTS.




1 HVAC PLAN
3/16" = 1'-0"







④ CONDENSATE OVERFLOW DRAIN PAN NTS




③ HORIZONTAL FAN COIL UNIT DETAIL NTS




② ROOF SUPPORT RAIL - VIBRATION ISOLATION DETAIL NTS




① CONDENSING UNIT SUPPORT DETAIL NTS




⑥ IN-LINE DUCT-MOUNTED FAN DETAIL NTS




⑤ ADJUSTABLE PIPE HANGER DETAIL NTS




⑦ SPLIT SYSTEM PIPING DETAIL NTS




⑧ DUCT HANGER - LOWER ATTACHMENT DETAILS NTS




⑧ PIPE PORTAL ROOF PENETRATION DETAILS NTS




⑬ REGISTER MOUNTING TO RECTANGULAR DUCT DETAIL NTS




⑬ LAY-IN CEILING DIFFUSER DETAIL NTS



⑬ HARD CEILING DIFFUSER DETAIL NTS



⑩ DAMPER AND FLEX DUCTWORK CONNECTION DETAIL NTS



NIKE INC.
ONE BOWERMAN DRIVE
BEAVERTON, OR 97005



MBH PROJECT: 55391

HENDERSON ENGINEERS
8345 LENEXA DRIVE, SUITE 300
LENEXA, KS 66214
TEL 913.742.5000 FAX 913.742.5001
WWW.HENDERSONENGINEERS.COM
2150003353
MO. CORPORATE NO. E-6960
EXPRES 02310202

Date	No.	Description
03/14/2022		75% SET
04/14/2022		PERMIT/BID/LL SET

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF PRELIMINARY SUBMITTAL. BRADLEY E. CHAMBLON LICENSE # 028603

IT IS NOT TO BE USED FOR CONSTRUCTION PURPOSES.

BRADLEY E. CHAMBLON
LICENSE # 028603

NIKE BY KANSAS CITY

COUNTRY CLUB PLAZA
450 NICHOLS RD,
KANSAS CITY, MO 64112

Project Number

Config: R/L
Drawn By: HENDERSON
Checked By: HENDERSON

MECHANICAL
DETAILS

M-200

PROJECT DESIGN CONDITIONS

CLIMATE CONDITIONS				BUILDING OPERATING HOURS:			
WEATHER STATION:	KANSAS CITY WHEELER, MO, USA			MONDAY - FRIDAY	TBD BY OWNER		
CLIMATE ZONE:	4A			SATURDAY	TBD BY OWNER		
HEATING (DB):	99.8%	5.8	"F	SUNDAY	TBD BY OWNER		
DESIGN HEATING CONDITIONS (DB):	4.0 "F			HOLIDAY	TBD BY OWNER		
HUMIDIFICATION (DP/HR MCBDB):	99.6%	-5.2	"F/ 4.3 grlb 9.2 "F				
COOLING (DB/MCBW):	0.4%	97.2	"F 76.4 "F				
DESIGN COOLING CONDITIONS (DB/MCBW):	97.2 "F 76.4 "F						
DEHUMIDIFICATION (DP/HR MCBDB):	0.4%	75.8	"F/ 138.7 grlb 87.0 "F				

UNIT / SPACE	SET POINTS										SPACE OPERATING HOURS			NOTES	
	COOLING / DE-HUMIDIFICATION				HEATING		HUMIDIFICATION		ZONE VENTILATION RESET		OCCUPIED / UNOCCUPIED				
DESCRIPTION	°C	UNOCC °F	MAX RH %	MIN RH %	OCC °F	UNOCC °F	MIN RH %	MAX RH %	CONTROL METHOD	BASE PPM	MAXIMUM PPM	M.F	SAT	SUN	
FCU-1 BACK OF HOUSE	72	77	60%	NA	70	60	NA	NA	CO2	400	750	TBD	TBD	TBD	A-D
FCU-2 STOCKROOM	72	77	60%	NA	70	60	NA	NA	CO2	400	750	TBD	TBD	TBD	A-D
FCU-3 SALES FLOOR	72	77	60%	NA	70	60	NA	NA	CO2	400	750	TBD	TBD	TBD	A-D
FCU-4 SOLAR AREA	72	77	60%	NA	70	60	NA	NA	NA	NA	NA	TBD	TBD	TBD	B-D

NOTES:
A. ZONE LEVEL VENTILATION RESET / DEMAND CONTROL VENTILATION (DCV) CONTROL METHOD: CARBON DIOXIDE SENSOR (CO2).
B. ZONE LEVEL SET POINT CONDITIONS SHALL BE AS SCHEDULED UNLESS OTHERWISE SCHEDULED OR NOTED ON THE DRAWINGS FOR ROOM SPECIFIC SPACE CONDITIONS.
C. MULTI-ZONE OCCUPANCY HOUR SCHEDULE SHALL BE PER BUILDING OPERATING HOURS UNLESS OTHERWISE SCHEDULED.
D. ZONE LEVEL CONTROLS SHALL BE CAPABLE OF OPERATING WITH INDEPENDENT OCCUPANCY SCHEDULES.

SPLIT SYSTEM CONTROL MATRIX

CONTROL FEATURE	UNITS	AHU-1				AHU-2				AHU-3				AHU-4				POINT TYPE INTERFACE WITH DDC (READ/WRITE)	NOTES
		SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N	SETPOINT OR Y/N			
BUILDING AUTOMATION SYSTEM (BAS)																			
ENERGY MANAGEMENT SYSTEM INTERFACE		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	BACNET	A	
SETPOINTS																			
COOLING - OCCUPIED SETPOINT	"F	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	72	READWRITE
COOLING - UNOCCUPIED SETPOINT	"F	77	77	77	77	77	77	77	77	77	77	77	77	77	77	77	77	77	READWRITE
DEAD BAND - MINIMUM HEATING AND COOLING TEMPERATURE SETPOINT DIFFERENCE	"F	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	READWRITE
HEATING - OCCUPIED SETPOINT	"F	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	70	READWRITE
HEATING - UNOCCUPIED SETPOINT	"F	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	READWRITE
HEATING - SUPPLY AIR TEMPERATURE SETPOINT	"F	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	READWRITE
PROGRAMMED CONTROL METHODS																			
REMOTE TEMPERATURE SENSOR		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	READ
DEMAND CONTROL VENTILATION - CO2 SENSOR FEEDBACK	PPM	750	750	750	750	750	750	750	750	750	750	750	750	750	750	750	750	750	READWRITE
EQUIPMENT ACCESSORIES AND CONTROL MODULES																			
OUTSIDE AIR DAMPER - MOTOR OPERATED (MODULATING)		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	READ POSITION
HEAT PUMP - REVERSING VALVE		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	READ STATUS
AUXILIARY HEAT KIT (ELECTRIC)		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	READ STATUS
SUPPLY FAN CONTROL METHODS																			
ON DURING OCCUPIED HOURS		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	
CYCLE WITH LOADS DURING UNOCCUPIED HOURS		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	
OPTIMUM START SEQUENCE		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	
CONSTANT VOLUME FAN CONTROL		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	READ STATUS
SAFETIES, INTERLOCKS, AND ALARMS		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	
RETURN AIR SMOKE DETECTOR - UNIT SHUTDOWN		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	READ
AUXILIARY DRAIN PAN FLOOD DETECTOR - UNIT SHUTDOWN		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	READ
DIFFERENTIAL PRESSURE SWITCH - FILTER CHANGE ALARM		Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	READ

NOTES:
DIV 23 CONTRACTOR SHALL PROVIDE CONTROL PANEL(S), WIRING, THERMOSTAT(S), TEMPERATURE SENSOR(S), HUMIDISTAT(S), AND/OR CO2 SENSOR(S) WHERE SHOWN ON THE DRAWINGS AND AS REQUIRED TO FACILITATE THE SCHEDULED CONTROL MODULES AND SEQUENCES OF OPERATION. EACH UNIT SHALL CONTROL BASED ON ITS OWN INTERNAL SAFETIES, TIME DELAYS, AND SEQUENCES UNLESS NOTED OTHERWISE. COORDINATE WITH OWNER FINAL BUILDING AND EQUIPMENT SCHEDULES DURING STARTUP. REFERENCE DIVISION SPECIFICATIONS FOR INDIVIDUAL DEVICE REQUIREMENTS.

NOTES:
A. PROVIDE UNIT WITH TERMINAL STRIP TO RECEIVE CONTROL INPUT(S) COMMUNICATED FROM A CENTRAL DDC CONTROLLER. EMS SHALL PROVIDE REMOTE SETPOINT ADJUSTMENT, SCHEDULING, AND MONITORING OF THE POINTS LISTED IN THE SCHEDULE FOR EACH UNIT.
B. LISTED IN THE SCHEDULE FOR EACH UNIT.
C. DIVISION 23 CONTRACTOR SHALL PROVIDE DEVICE.
D. DIVISION 28 CONTRACTOR SHALL PROVIDE DEVICE.
E. DEVICE SHALL BE FACTORY MOUNTED AND PRE-WIRED FOR OPERATION SUBJECT TO THE ONBOARD CONTROLLER.
F. MODULATE AND/OR CYCLE SUPPLY FAN SPEED SETTING AND COIL CAPACITY STAGES SUBJECT TO THE INTERNAL SAFETIES AND SEQUENCES TO MAINTAIN SCHEDULED SETPOINTS.
G. DIVISION 23 SHALL PROVIDE MODULATING DAMPER AND EMS CONTRACTOR SHALL PROVIDE CONTROLS CAPABLE OF ADJUSTING THE DAMPER POSITION TO MAINTAIN THE SCHEDULED OUTSIDE AIR ON THE DRAWINGS. EMS CONTRACTOR SHALL PROGRAM MULTIPLE DAMPER POSITION SETPOINTS IN THE FIELD DURING TESTING AND BALANCING TO MAINTAIN MINIMUM PROGRAM MULTIPLE DAMPER POSITION SETPOINTS IN THE FIELD DURING TESTING. DAMPER SHALL ADJUST BASED ON DEMAND CONTROL VENTILATION.
H. 4800 HEAT KIT PROVIDED BY DIVISION 23. CYCLE COIL CAPACITY STAGES FOR MORNING DEFOST AND AS SUPPLEMENTAL HEATING TO MAINTAIN SCHEDULED SETPOINTS.
I. DURING OPTIMUM START SEQUENCE, THE UNIT SHALL SUPPLY THE LESSER OF THE MINIMUM RATE OF OUTDOOR AIR OR SUPPLY 3 COMPLETE AIR CHANGES DURING THE 1-HOUR PERIOD BEFORE NORMAL OCCUPIED MODE.

HVAC UNIT STARTUP REQUIREMENTS

INSTALLING CONTRACTOR SHALL COMPLETE THE PRE-START CHECKLIST AND EMAIL JENNIFER.TYE@COMFORTSYSTEMSUSA.COM MINIMUM OF TWO (2) WEEKS PRIOR TO SCHEDULING EQUIPMENT STARTUP.

COORDINATE EQUIPMENT STARTUP WORK WITH COMFORT SYSTEMS USA. EMAIL: JENNIFER.TYE@COMFORTSYSTEMSUSA.COM OFFICE: 317-246-5176

DEPARTMENT MANAGER
EMAIL: KLORI.KARAKIRIDIS@COMFORTSYSTEMSUSA.COM OFFICE: 317-246-4656

TECHNICAL SUPPORT
EMAIL: RICK.FARRIS@COMFORTSYSTEMSUSA.COM MOBILE: 317-638-5363 X4454

PRE-START CHECKLIST (VERIFY FOR ALL UNITS)

- VERIFY ALL ITEMS ON THE EQUIPMENT ORDER RECEIVED.
- VERIFY ALL PACKAGING MATERIAL REMOVED FROM THE UNIT.
- VERIFY CURB GASKETS PROPERLY INSTALLED, IF APPLICABLE.
- VERIFY HVAC UNIT(S) INSTALLED AND PROPERLY SUPPORTED PER MECHANICAL PLANS.
- VERIFY DUCTWORK/FABRIC DUCT COMPLETELY INSTALLED PER MECHANICAL PLANS.
- VERIFY OA HOOD INSTALLED, IF APPLICABLE. VERIFY AIR INLET SCREEN INSTALLED.
- VERIFY POWER EXHAUST ACCESSORY INSTALLED, IF APPLICABLE.
- VERIFY CLEAN FLEATED FILTERS INSTALLED. MINIMUM MERV 13 RATING.
- VERIFY CONDENSATE DRAIN LINE INSTALLED. MINIMUM 2" DEEP TRAP. DRAIN PAN CHECKLEVEL.
- VERIFY SUPPLY FAN ROTATES FREELY IN THE HOUSING.
- VERIFY PULLEYS ALIGNED AND BELT TENSION CORRECT.
- VERIFY SMOKE DETECTORS INSTALLED IN DUCTWORK, CLEANED AND TESTED.
- VERIFY GAS METER INSTALLED AND GAS AVAILABLE FROM THE UTILITY. GAS PIPING COMPLETED. CHECKED FOR LEAKS AND PURGED, IF APPLICABLE.
- VERIFY GAS PIPING DRIP LEG INSTALLED PROPERLY (DOWNSTREAM OF SHUTOFF VALVE AND NO INTERFERENCE WITH ACCESS DOOR), IF APPLICABLE.
- VERIFY FLUE HOOD INSTALLED, IF APPLICABLE.
- VERIFY JOBSITE POWER SUPPLY MATCHES THE VOLTAGE ON THE UNIT DATA PLATE.
- VERIFY ELECTRIC POWER CONNECTED TO UNIT VIA THE ACCESS PROVIDED. IF NOT, DATE POWER WILL BE AVAILABLE.
- VERIFY NO WIRES TOUCHING REFRIGERANT LINES OR SHARP EDGES.
- VERIFY ELECTRIC CONNECTORS AND TERMINALS TIGHT.
- VERIFY THRU-THE-CURB UTILITY CONNECTIONS COMPLETE, IF APPLICABLE.
- VERIFY UNIT TRANSFORMER PRIMARY TAPPED FOR JOBSITE VOLTAGE.

EMS INSTALLATION CHECKLIST

ITEMS ON EMS CHECK-OFF LIST MUST BE COMPLETED PRIOR TO EMS AND GBS COMMISSIONING AT THE END OF THE JOB. SOME ITEMS LISTED BELOW MAY NOT BE APPLICABLE.

COORDINATE EQUIPMENT STARTUP WORK WITH COMFORT SYSTEMS USA. EMAIL: PAUL.SAWYER@COMFORTSYSTEMSUSA.COM OFFICE: 317-246-5176

EMS CHECKLIST

- REVIEW EMS PRINT SET AND INSTALL EMS OPUS PANEL AND LCP AS DESCRIBED IN THE EMS PRINT SET.
- REVIEW EMS PRINT SET AND PULL ALL WIRE AND TERMINATE ON DEVICES AS DESCRIBED IN THE EMS PRINT SET.
- REVIEW EMS PRINT SET AND INSTALL ALL EMS HVAC CONTROLS AS DESCRIBED IN THE EMS PRINT SET.
- REVIEW EMS PRINT SET AND INSTALL ALL EMS LIGHTING CONTROLS AS DESCRIBED IN THE EMS PRINT SET.
- REVIEW EMS PRINT SET AND WATSTOPPER SUBMITTAL AND INSTALL THE WATSTOPPER LIGHTING SYSTEM AND PULL ALL WIRE AS DESCRIBED IN THE EMS PRINT SET AND WATSTOPPER SUBMITTAL.

EMS CONTROLS:

CONTRACTORS ARE RESPONSIBLE FOR COORDINATING ALL EQUIPMENT CONTROLS WITH EMS VENDOR PRIOR TO PURCHASE AND INSTALLATION. CONTRACTORS SHALL COORDINATE WITH EMS VENDOR TO PROVIDE ALL NECESSARY EQUIPMENT AND ACCESSORIES FOR A FULLY FUNCTIONING SYSTEM.

OUTSIDE AIR REQUIREMENTS, IMC-2018 W/ AMENDMENTS (IP)

SYSTEM DESIGNATION	SYSTEM TYPE:	SINGLE-ZONE SYSTEMS		MULTI-ZONE SYSTEMS		FLOOR AREA SERVED BY SYSTEM [Aa] (SF)	SYSTEM AVERAGED AREA-BASED OUTDOOR AIR RATE (CFM/SF)	SYSTEM POPULATION (PEOPLE)	CODE REQUIREMENTS			NOTES	
		VENTILATION ZONE ASSOCIATED WITH SYSTEM	WORST CASE ZONE AIR DISTRIBUTION EFFECTIVENESS [Ez]	SYSTEM VENTILATION EFFICIENCY [Ev]	REQUIRED DCV/OIA INTAKE FLOW [Voi]				MIN OIA INTAKE FLOW [Voi] (CFM)	ABS MIN OIA INTAKE FLOW [Voi] (CFM)			
FCU-1	MULTI-ZONE	-	-	0.84	1.297	1,87	0.086	8.12	182	133	200	140	ALL
FCU-2,3,4	MULTI-ZONE	-	-	0.52	3.674	3,674	0.113	38.42	732	434	800	450	ALL
TOTALS									1,541	936	1,000	590	

NOTES:
A. VENTILATION CALCULATIONS BASED ON 2018 INTERNATIONAL MECHANICAL CODE.
B. SYSTEM POPULATIONS BASED ON MAX SEATING AND/OR CODE MAXIMUM VALUES.
C. MULTI-ZONE RECIRCULATING SYSTEMS: CALCULATOR TAKES THE MAXIMUM OUTSIDE AIRFLOW REQUIRED BY IMC ON A SYSTEM LEVEL. THE CALCULATION USED TO DETERMINE VENTILATION AIRFLOW IN COMPLIANCE WITH VRP AND SECTION 404.0.
D. VENTILATION RATE SHOWN IS ACTUAL CALCULATED WITH CORRECTION FACTORS INCLUDED. EACH ZONE IS CALCULATED WITH ITS WORST CASE ZONE AIR DISTRIBUTION EFFECTIVENESS (HEATING/COOLING) AS PART OF CALCULATIONS TO FIND EV.
E. THE ABSOLUTE MINIMUM OUTSIDE AIRFLOW (ABS MIN OIA) DESIGN VALUE IS THE DEMAND CONTROL VENTILATION (DCV) DESIGN AIRFLOW VALUE.

HEAT PUMP FAN COIL UNIT SCHEDULE (W/ AUX ELECTRIC HEATING)

MARK	MANUFACTURER	MODEL	SUPPLY FAN				COOLING COIL				REFR TYPE	TOTAL CAP (MMBh)	HEAT PUMP COIL				AUXILIARY HEAT KIT				MIN OIA (CFM)	ABS OIA (CFM)	ELECTRICAL V/PH	MCA	MOCP	WEIGHT (LBS)	NOTES		
			CFM	ESP (IN)	NOM HP	TH (MMH)	SH (MMH)	EAT (°F DB)	LAT (°F WB)	MIN (°F DB)			MAX (°F WB)	MIN OUT (MMH)	EAT (°F DB)	LAT (°F DB)	MIN NO OF STAGES	MIN OUT (MMH)	EAT (°F DB)	LAT (°F DB)								MIN NO OF STAGES	
FCU-1	CARRIER	FV4HCN806	1,750	0.90	3/4	44.2	36.7	74.9	63.4	55.8	54.9	R-410A	300	40	60	90	2	40	5	60	90	2	300	170	480/3	12	15	200	ALL
FCU-2	CARRIER	FV4HCN806	1,800	1.10	3/4	52.9	38.9	79.5	65.3	56.4	54.9	R-410A	300	40	60	90	2	40	5	60	90	2	300	175	480/3	12	15	200	ALL
FCU-3	CARRIER	FV4HCN806	1,600	1.10	3/4	52.6	36.8	78.9	66.3	56.4	54.9	R-410A	300	40	60	90	2	40	5	60	90	2	300	175	480/3	12	15	200	ALL
FCU-4	CARRIER	FV4HCN806	1,750	0.90	3/4	42.1	40.2	72.0	59.5	50.9	50.8	R-410A	300	40	70	90	2	40	5	70	90	2	300	175	480/3	12	15	200	ALL

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
A. ASSOCIATED CONDENSING UNIT SHALL BE BY THE SAME MANUFACTURER.
B. EQUIPMENT SIZED FOR 105°F AMBIENT TEMPERATURE.
C. PROVIDE 2" MERV 13, PLEATED THROWAWAY AIR FILTERS.
D. PROVIDE WITH BACK INLET CONNECTION.
E. PROVIDE WITH FRONT OUTLET CONNECTION.
F. PROVIDE WITH 7-DAY PROGRAMMABLE THERMOSTAT WITH STAGED HEATING AND COOLING CAPABILITY AS REQUIRED FOR OPERATION OF AUXILIARY HEATING AND COOLING CONTROLS.
G. PROVIDE FACTORY MOUNTED DISCONNECT INSTALLED ON SERVICE SIDE OF UNIT.
H. SPECIFIED FAN ESP ACCOUNTS FOR DUCT LOSSES EXTERNAL TO UNIT. FILTER LOSS IS AT A MAXIMUM OF 400 FPM FACE VELOCITY.
I. PROVIDE MOTOR HORSEPOWER TO OVERCOME INTERNAL UNIT STATIC PRESSURE DROP PLUS SPECIFIED EXTERNAL STATIC PRESSURE DROP.
J. NOMINAL MOTOR HP SHALL BE NO LARGER THAN THE FIRST AVAILABLE NOMINAL MOTOR SIZE GREATER THAN THE REQUIRED BHP.
K. DIVISION 23 CONTRACTOR SHALL PROVIDE SMOKE DETECTORS IN RETURN AIR DUCT(S).
L. PROVIDE WITH SPRING VIBRATION ISOLATION AND ALL-THREAD HANGING RODS.
M. PROVIDE SEPARATE ELECTRIC HEAT KIT BY WARREN TECHNOLOGY. MODEL NUMBER WPKWJ05A, OR EQUIVALENT. ELECTRIC HEAT KIT SHALL PROVIDE A SINGLE-POINT 480V POWER CONNECTION FOR THE ELECTRIC HEATER AND FAN COIL UNIT. NOMINAL KW IS BASED ON LISTED MANUFACTURER'S STANDARD PRODUCT. COORDINATE EQUIPMENT POWER SUPPLY WITH ELECTRICAL CONTRACTOR IF DIFFERENT FROM THAT SCHEDULED.
N. PROVIDE AUXILIARY DRAIN PAN WITH FLOOD DETECTOR SWITCH TO SHUT OFF UNIT WHEN WATER IS PRESENT IN DRAIN PAN.

CARRIER NATIONAL ACCOUNT CONTACT
MATT MURPHY
STRATEGIC ACCOUNT MANAGER
CARRIER CORPORATION
MOBILE: (820) 235-1616
EMAIL: MATT.MURPHY@CARRIER.COM

SEQUENCE OF OPERATION

A. DX SPLIT SYSTEM UNIT CONTROL (FCU/CU-X)
Refer to Split System Control Matrix for sequence of operations.

B. VAV DIFFUSER CONTROL (CSD1)
In occupied mode, the VAV diffuser shall modulate airflow to maintain the room temperature setpoint (adjustable). Set VAV diffuser minimum position to maintain 30% of the maximum airflow.

The room occupancy sensor, upon sensing the space to be vacant for 15 minutes (adjustable), shall signal the diffuser through the EMS to maintain an unoccupied temperature setpoint (adjustable). When occupancy is detected, the EMS shall direct the diffuser to control to the room temperature setpoint.

The room CO2 sensor, upon reading a CO2 level above 100 PPM (adjustable) above ambient CO2 level (400 PPM), shall signal the diffuser through the EMS to modulate the zone damper between its minimum and maximum position. The system shall start to modulate the damper open when CO2 level rises 100 PPM above ambient CO2 level and continue to open to its maximum position as CO2 level rises to and above 700 PPM (adjustable) above ambient CO2 levels. As the CO2 level drops, the system shall start to modulate the dampers to the minimum position.

In unoccupied mode, VAV diffuser control shall be disabled unless occupancy is detected. When occupancy is detected, the EMS shall direct the diffuser to control to the room temperature setpoint.

C. MOTORIZED DAMPER SERVING IT ROOM CONTROL (MD)
When FCU-1 is in heating mode, the motorized damper shall be closed.

When FCU-1 is in cooling mode and the supply air temperature drops below 55 degrees Fahrenheit (adjustable), the motorized damper shall open.

HEAT PUMP CONDENSING UNIT SCHEDULE

MARK	SERVICE	MANUFACTURER	MODEL	REFR TYPE	TH (MMH)	MIN NO OF STAGES	NO OF CIRCUITS	MIN EFF		ELECTRICAL		WEIGHT (LBS)	NOTES		
								(EER)	(IEER)	(HSPF)	V/PH			MCA	MOCP
CU-1	FCU-1	CARRIER	25HC448	R-410A	44.3	1	1	12.5	15	8.5	480/3	8.5	15	200	ALL
CU-2	FCU-2	CARRIER	25HC460	R-410A	52.6	1	1	11.5	14	8.2	480/3	10.5	15	225	ALL
CU-3	FCU-3	CARRIER	25HC460	R-410A	52.6	1	1	11.5	14	8.2	480/3	10.5	15	225	ALL
CU-4	FCU-4	CARRIER	25HC448	R-410A	42.1	1	1	12.5	15	8.5	480/3	8.5	15	200	ALL

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

