

SHEET NUMBER	SHEET NAME
M001	MECHANICAL ABBREVIATIONS AND SYMBOLS
M101	MECHANICAL FLOOR PLAN
M102	MECHANICAL REFRIGERANT PIPING LAYOUT PLAN
M501	MECHANICAL DETAILS
M502	MECHANICAL DETAILS
M590	MECHANICAL SPECIFICATIONS
M591	MECHANICAL SPECIFICATIONS
M592	MECHANICAL SPECIFICATIONS
M593	MECHANICAL SPECIFICATIONS
M601	MECHANICAL SCHEDULE
M701	HALTON DRAWINGS
M702	HALTON DRAWINGS
M703	HALTON DRAWINGS
M704	HALTON DRAWINGS
M705	HALTON DRAWINGS
M706	HALTON DRAWINGS
M801	CAPTIVEAIRE DRAWINGS
M802	CAPTIVEAIRE DRAWINGS

**2018 APPENDIX B
BUILDING CODE SUMMARY FOR ALL COMMERCIAL PROJECTS
MECHANICAL DESIGN
(PROVIDE ON THE MECHANICAL SHEETS IF APPLICABLE)**

**MECHANICAL SUMMARY
MECHANICAL SYSTEMS, SERVICE SYSTEMS AND EQUIPMENT**

Thermal Zone

winter dry bulb: 18°F
summer dry bulb: 91°F

Interior design conditions

winter dry bulb: 72°F
summer dry bulb: 74°F
relative humidity: 50%

Building heating load: 59.6 MBH

Building cooling load: 86.9 MBH

Mechanical Spacing Conditioning System

Unitary

description of unit: SEE HVAC SCHEDULES AND DETAILS – SHEET M200
heating efficiency: SEE HVAC SCHEDULES AND DETAILS – SHEET M200
cooling efficiency: SEE HVAC SCHEDULES AND DETAILS – SHEET M200
size category of unit: SEE HVAC SCHEDULES AND DETAILS – SHEET M200

Boiler

Size category. If oversized, state reason.: N/A

Chiller

Size category. If oversized, state reason.: N/A

List equipment efficiencies: SEE HVAC SCHEDULES AND DETAILS – SHEET M200

2018 NC Administrative Code and Policies

RESPONSIBILITY MATRIX

THIS SCHEDULE IS PROVIDED FOR QUICK REFERENCE ONLY.
THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ALL WORK DESCRIBED IN THE CONSTRUCTION DOCUMENTS.
CONFLICTS BETWEEN THIS SCHEDULE AND THE REST OF THE CONTRACT DOCUMENTS SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION PRIOR TO BEGINNING WORK.

DESCRIPTION	FURNISHED			INSTALLED			REMARKS
	GENERAL CONTRACTOR	OWNER	LANDLORD	GENERAL CONTRACTOR	OWNER	LANDLORD	
DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING							
23.1 HVAC DUCTWORK AND PIPING IDENTIFICATION							
23.1.1 HVAC DUCTWORK SYSTEM IDENTIFICATION	X			X			
23.1.2 PIPING SYSTEM IDENTIFICATION	X			X			
23.1.3 UTILITY SHUT OFF IDENTIFICATION IN KITCHEN	X			X			
23.1.4 VALVE TAGS AND CHART	X			X			
23.1.5 HVAC DAMPER IDENTIFICATION	X			X			
23.2 ROOF CURBS							
23.2.1 EXHAUST FAN CURBS	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.2 ROOFTOP UNIT CURBS	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.3 CONDENSING UNIT CURBS	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.4 MAKE UP AIR AND DOAS UNIT CURBS			X	X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.5 KITCHEN EXHAUST FAN CURBS			X	X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.3 HVAC DUCTWORK SYSTEM COMPONENTS							
23.3.1 HVAC DUCTWORK	X			X			
23.3.2 INSULATION AND FIRE WRAP	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE TENANT FIT OUT FROM LANDLORD POINT OF CONNECTION
23.3.3 DAMPERS	X			X			
23.3.4 SMOKE DETECTORS	X			X			
23.3.5 SUPPLY, RETURN, AND EXHAUST GRILLS AND REGISTERS	X			X			
23.4 MECHANICAL PIPING SYSTEM COMPONENTS							
23.4.1 WALK-IN COOLER AND FREEZER REFRIGERATION			X	X			WALK-IN COOLER AND FREEZER SUPPLIED BY VENDOR NO. 27 GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE PIPING INSTALLATION AND FINAL CONNECTION
23.4.2 REFRIGERATION FOR OTHER HVAC EQUIPMENT	X			X			
23.4.3 CHILLED WATER	X			X			
23.4.4 CONDENSER WATER	X			X			
23.4.5 HEATING HOT WATER	X			X			
23.4.6 VALVES AND ACCESSORIES (E.G. AIR VENTS)	X			X			
23.5 HVAC EQUIPMENT							GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING FOR ALL ROOFTOP EQUIPMENT
23.5.1 SUPPLY FAN	X			X			
23.5.2 TOILET EXHAUST FAN	X			X			
23.5.3 KITCHEN EXHAUST FAN			X	X			SUPPLIED BY VENDOR NO. 26
23.5.4 DUCTED AND NON-DUCTED HEATING AND COOLING UNITS	X			X			
23.5.5 MAKE UP AIR AND DOAS UNITS			X	X			SUPPLIED BY VENDOR NO. 26
23.5.6 ELECTRIC PATIO HEATERS	X			X			
23.5.7 HVAC CONDENSING UNITS	X			X			
23.5.8 REFRIGERATION CONDENSING UNITS			X	X			
23.5.9 RGF PHI SYSTEM	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 12 VENDOR SUBSTITUTION IS NOT PERMITTED
23.6 KITCHEN EXHAUST WITH FIRE SUPPRESSION SYSTEM							
23.6.1 HOOD CONTROL PANEL			X	X			SUPPLIED BY VENDOR NO. 26
23.6.2 KITCHEN EXHAUST HOOD			X	X			SUPPLIED BY VENDOR NO. 26
23.6.3 STRUCTURAL SUPPORT	X			X			
23.6.4 ELECTRICAL AND CONTROL WIRING	X			X			
23.6.5 ANSUL SYSTEM			X	X			SUPPLIED BY VENDOR NO. 26 GENERAL CONTRACTOR TO COORDINATE AND FACILITATE SYSTEM SIGN-OFF
23.6.6 ANSUAL WIRING AND UTILITIES CONNECTION	X			X			
23.6.7 ANSUAL GAS VALVE			X	X			SUPPLIED BY VENDOR NO. 26
23.7 COMMISSIONING ACTIVITIES							
23.7.1 GREASE EXHAUST WATER LEAKAGE TEST	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 10 VENDOR SUBSTITUTION IS NOT PERMITTED
23.7.2 TESTING AIR BALANCE (TAB) REPORT	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 12 VENDOR SUBSTITUTION IS NOT PERMITTED

SUBMITTAL MATRIX

GENERAL CONTRACTORS TO ALSO REVIEW ARCHITECTURAL SPECIFICATIONS AS NOTED IN PLANS IN PLAN SECTION 700 OF THE ARCHITECTURAL PACKAGE FOR REQUIRED SUBMITTALS THAT MIGHT NOT BE LISTED BELOW.

SUBMITTAL DESCRIPTION	Required Review Time (Business Days)	Physical Sample Submitted for Record	Shop Drawings	Physical Sample Submitted for Record	Submitted for Record Only
Anchor Bolts Shops	5	X			X
ATAS-Detailed Shop DWGS(Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X			X
Concrete Mix Design	5	X			X
Construction Prefunctional Checklists	5	X			X
Decorative Metal Shop Drawings	5	X			
Diffusers, Grills & Registers	5	X		X	
Doors, Frames & Hardware	7	X		X	
Ductwork Layout (if there are significant changes in field)	5	X		X	
Electrical Distribution Equipment	5	X			
Elevator & Vertical Transportation Shop Drawings	5	X			X
Epoxy Floor	5	X			
Fire Alarm Shop Drawings & Device Cut Sheets	5	X		X	X
Fire Sprinkler Shop Drawings, Hydraulic Calculations & Device Cut Sheets	5	X			X
HVAC Equipment(if Carrier - Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X		X	
Light Fixtures(Submitted by Owner Vendor to Owner/AOR prior to construction)	5	X		X	
M&P Tests, Start-Up, and Programming Reports	5	X		X	
Millwork - Material Submittals (if differs from spec)	5	X	X	X	
Millwork - Shop Drawings (custom items & design features only)	5	X			
Restroom Partitions	5	X		X	
Plumbing Fixtures	5	X		X	
Railing Shop Drawings	5	X			X
Rebar	5	X		X	
Stair Shop Drawings	5	X		X	
Structural Steel Shop Drawings	7	X		X	
Storefront - product data Submittal (if different from specified)	5	X			
Storefront - Shop Drawings	5	X			
Tile (if differs from spec)	5	X		X	
Window Film	5	X			

SYMBOLS

HEATING - VENTILATING - AIR CONDITIONING

SYMBOL	DESCRIPTION
	THERMOSTAT
	REMOTE SENSOR
	SUPPLY DIFFUSER
	RETURN OR EXHAUST GRILLE
	SUPPLY OR FRESH AIR DUCT (SA OR FA)
	RETURN OR EXHAUST AIR DUCT (RA OR EA)
	RECTANGULAR AIR DUCT (FIRST FIGURE IS SIDE SHOWN)
	ROUND DUCT
	VOLUME DAMPER (ELEV AND PLAN)
	TURNING VANES
	SUPPLY REGISTER OR GRILLE (R OR G)
	RETURN REGISTER OR GRILLE (R OR G)
	FRESH AIR INTAKE (FA)
	SQUARE CEILING DIFFUSER (SUPPLY)
	FAN COIL UNIT AND MARK
	MOTORIZED DAMPER
	CHILLED WATER SUPPLY
	CHILLED WATER RETURN
	REFRIGERANT LIQUID LINE
	REFRIGERANT SUCTION LINE
	CONDENSATE OR VACUUM PUMP DISCHARGE
	GAS LINE
	REFRIGERANT LIQUID LINE
	REFRIGERANT SUCTION LINE
	MOTORIZED DAMPER



NC - 1414 - CHAPEL HILL

1800 E FRANKLIN STREET,
UNIT 40
CHAPEL HILL, NC 27514

Gensler

LIC. NO. AA0002837
45 FREMONT ST
SUITE 1500
SAN FRANCISCO, CA 94105
UNITED STATES

TEL 415.433.3700
FAX 415.836.4599

SATELLITE OFFICE:
400 N ASHLEY DRIVE
SUITE 0400
TAMPA, FL 33602
UNITED STATES

TEL 813.204.9000
FAX 813.223.6948



ST ENGINEER
700 S FLOWER ST
SUITE 2100
LOS ANGELES, CA 90017
TEL 213.418.0201



MEFP ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680



FOODSERVICE CONSULTANT
505 COLLINS ST
PO BOX 3505
SOUTH ATTLEBORO
MA 02703
TEL 508.399.6000
FAX 508.761.3620

Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AHJ COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



Seal / Signature

ISSUE FOR CONSTRUCTION

Project Name

CHAPEL HILL

Project Number

69.6562.000

Description

MECHANICAL ABBREVIATIONS & SYMBOLS

Scale

1/4" = 1'-0"

M001

- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTAL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E. BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOKE AND HAZARD RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - EXPOSED SPIRAL DUCT TO BE GALVANIZED FINISH, FREE FROM SCRATCHES, DENTS OR BLEMISHES AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT SHALL BE INTERNALLY LINED AND SEALED WITH DUCT SEALER COMPLETELY CONCEALED WITHIN THE DUCT JOINT. NO EXPOSED SEALER OR TAPE WILL BE ACCEPTED.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE OR THRU JOIST.
 - AT THE START OF CONSTRUCTION, THE MECHANICAL CONTRACTOR SHALL INSPECT AND RUN TEST ALL EXISTING HVAC UNITS DESIGNATED FOR REUSE. CONTRACTOR SHALL INFORM ARCHITECT OF ANY NECESSARY REPAIRS FOR APPROVAL IN A TIMELY MANNER, AS TO NOT DELAY THE PROJECT OPENING DATE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITS OVERSEEN FOR DAMPERS LOCATED ABOVE UNACCESSIBLE CEILINGS. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL REPAIRS RELATING TO DAMAGE TO REPAIR OR DAMAGE TO EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY CONTRACTOR'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE. IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. WARRANTY SHALL INCLUDE LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AARC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR TRAINING BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNROURH AT WILL@NATIONTAB.COM OR 314-954-6244.
 - THE CONTRACTOR SHALL OBTAIN A COPY OF THE LANDLORD'S TENANT CRITERIA MANUAL. TENANT CRITERIA MANUAL IS AN INTEGRAL PART OF THIS CONTRACT. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING WITH LANDLORD REQUIREMENTS AT NO ADDITIONAL COST TO THE TENANT.

- HVAC NOTES:**
- NEW HALTON GREASE EXHAUST HOOD TO BE FURNISHED BY OWNER FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. SEE SHEETS M201 THROUGH M206 FOR ADDITIONAL INFORMATION. BALANCE HOOD MAKE-UP AIR AND EXHAUST COLLARS AS NOTED ON THE HOOD SCHEDULE. PROVIDE FULL SIZE TRANSITION WAREHOUSE AIR DUCT FROM COLLAR TO MAKE-UP AIR MAIN DUCT AS INDICATED ON PLANS.
 - TRANSITION FROM HOOD EXHAUST COLLAR AS INDICATED ON PLANS AND EXTEND 8" KITCHEN HOOD DUCTWORK UP TO GREASE EXHAUST FAN ON ROOF. SEE SHEET M206 FOR CONTINUATION. GREASE DUCT SHALL BE WRAPPED WITH TWO (2) LAYERS OF THERMAL CERAMICS FAST WRAP XL, 1 1/2" THICK WITH 3" PERIMETER AND LONGITUDINAL OVERLAP OF EQUIVALENT LISTED GREASE DUCT WRAP FOR ZERO CLEARANCE TO COMBUSTIBLES. REFER TO DETAIL ON SHEET M201 FOR ADDITIONAL INFORMATION.
 - TRANSITION FROM HOOD EXHAUST COLLAR AS INDICATED ON PLANS AND EXTEND 12" KITCHEN HOOD GREASE EXHAUST DUCTWORK UP TO GREASE EXHAUST FAN ON ROOF. SEE SHEET M206 FOR CONTINUATION. GREASE DUCT SHALL BE WRAPPED WITH TWO (2) LAYERS OF THERMAL CERAMICS FAST WRAP XL, 1 1/2" THICK WITH 3" PERIMETER AND LONGITUDINAL OVERLAP OF EQUIVALENT LISTED GREASE DUCT WRAP FOR ZERO CLEARANCE TO COMBUSTIBLES. REFER TO DETAIL ON SHEET M201 FOR ADDITIONAL INFORMATION.
 - PROVIDE ACCESS OPENINGS FOR CLEANING, MAINTENANCE, AND INSPECTION FOR THE GREASE EXHAUST DUCTS AS REQUIRED BY CODE. TYPICAL OF GREASE EXHAUST DUCTWORK. REFERENCE SHEET M201, DETAIL 5 FOR ADDITIONAL INFORMATION.
 - PROVIDE RETRICKER FROM ASH-1 ON ROOF TO CU-1 IN ROOM 107. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - PROVIDE NEW FULLY DIGITAL 7 DAY PROGRAMMABLE TYPE THERMOSTAT WITH REMOTE SENSING AND AUTO CHANGE OVER AND SET BACK MOUNT THERMOSTAT AT 48" ABOVE FINISHED FLOOR. THERMOSTATS SERVING THE SAME TEMPERATURE ZONE SHALL BE INTERLOCKED TO PREVENT SIMULTANEOUS HEATING AND COOLING. PROVIDE REMOTE TEMPERATURE SENSORS AS INDICATED ON PLAN. COORDINATE WITH WALL GRAPHICS LAYOUT.
 - DUCT SMOKE DETECTOR ON RETURN SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
 - PROVIDE NEW FAN COIL AS NOTED ON PLANS AND AS SCHEDULED ON SHEET M201.
 - PROVIDE REMOTE VOLUME DAMPER AS INDICATED ON PLANS. REFERENCE SHEET M202, DETAIL 5, FOR ADDITIONAL INFORMATION.
 - DIFFUSER TO BE POINTED DOWN.
 - PROVIDE LOW LEAKAGE MOTORIZED OUTDOOR AIR DAMPER. INTERLOCK THE DAMPER WITH THE SUPPLY FAN FOR ACU-1. BALANCE THE DAMPER TO PROVIDE A MAXIMUM OF 15 CFM OF OUTDOOR AIR.
 - ALL DUCTWORK LOCATED WITHIN THE DINING ROOM OR QUEUING SPACE IS TO BE INSTALLED THRU JOIST SPACE, ABOVE THE ARCHITECTURAL CEILING FEATURES. NOTIFY ARCHITECT OF ANY CONFLICTS. TYPICAL THROUGHOUT SPACE.
 - ROOF RENE HALO 24V AIR PURIFICATION SYSTEM TO BE PROVIDED AND INSTALLED BY INAB. REFER TO RESPONSIBILITY MATRIX ON SHEET M201 FOR ADDITIONAL INFORMATION. SHEET M201 FOR SCHEDULE, AND SHEET M202 FOR SPECIFICATIONS.
 - WRITE AND TRANSITION DUCTWORK AS REQUIRED IN SOFFIT AND ABOVE CEILING SPACE TO AVOID CONFLICTS WITH STRUCTURAL COMPONENTS, FRAMING, OR OTHER BUILDING FEATURES.
 - PROVIDE LOW LEAKAGE MOTORIZED OUTDOOR AIR DAMPER. INTERLOCK THE DAMPER WITH FC-1 SUPPLY FAN AND RELIEF AIR AND RETURN AIR MOTORIZED DAMPERS FOR 100% OUTDOOR AIR ECONOMIZER OPERATION.
 - CONTRACTOR SHALL UNDERCUT DOOR 3/4"
 - PROVIDE 8" EXHAUST AIR DUCT UP TO EF-3 ON ROOF.
 - TOP OPEN RETURN AIR DUCT. PROVIDE OPENING WITH 1/4" MESH GALVANIZED SCREEN.
 - PROVIDE CEILING MOUNTED REMOTE TEMPERATURE SENSOR AS INDICATED ON PLANS. COORDINATE LOCATION WITH ARCHITECT AND CONSTRUCTION MANAGER. EXISTING BURNER AIR CURTAIN TO REMAIN. CONTRACTOR SHALL CLEAN AND REPAIR DEVICE TO A LIKE NEW CONDITION. IF THE DEVICE CANNOT BE REPAIRED TO A LIKE NEW CONDITION, IT SHALL BE REPLACED WITH A NEW UNIT THAT MATCHES THE EXISTING DEVICE IN EVERY RESPECT. VERIFY UNIT IS EQUIPPED WITH AN AUTOMATIC DOOR SWITCH. IF NOT, THE CONTRACTOR SHALL PROVIDE.
 - HOOD CONTROL PANEL FOR HALTON HOOD SYSTEM. INSTALL AS SPECIFIED BY THE MANUFACTURER. SEE HALTON SHEETS M201 THROUGH M206 FOR ADDITIONAL INFORMATION. UNIT TO BE INSTALLED ON WALL IN KITCHEN SPACE. NOTIFY CONSTRUCTION MANAGER AND ARCHITECT WITH ANY CONFLICTS.
 - RETURN DRILLS TO BE INSTALLED ABOVE RESTROOM SIGN. NOTIFY ARCHITECT AND CONSTRUCTION MANAGER WITH ANY CONFLICTS.
 - HOOD MANUFACTURER TO PROVIDE A "KIT" TO FASTEN THE BOTTOM FLANGE OF THE HOOD TO THE WALL. WITH ONE FASTENER PER 36" HALL. S1L-5000 RTV 4500 ALUMINUM SILICONE SEALANT OR APPROVED SIMILAR, TO BE APPLIED BY GENERAL CONTRACTOR / HOOD INSTALLER FOR ANY REMAINING SMALL GAPS. HOOD FASTENING "KIT" DETAIL TO BE INCLUDED IN MANUFACTURER DRAWINGS. REFERENCE SHEET M201, DETAIL 2, FOR ADDITIONAL INFORMATION.

Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AJH COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



Seal / Signature

ISSUE FOR CONSTRUCTION


Project Name
CHAPEL HILL

Project Number
69.6562.000

Description
MECHANICAL FLOOR PLAN

Scale
1/4" = 1'-0"

M101




- DUCT DETECTORS MUST BE TESTED WITH SMOKE SUPPLIED BY THE MECHANICAL CONTRACTOR. THE FIRE AND MECHANICAL INSPECTORS MUST BE PRESENT TO WITNESS TEST.


1 MECHANICAL FLOOR PLAN
SCALE: 1/4" = 1'-0"

- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT. CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.e. BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOKE AND HAZARD RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - EXPOSED SPIRAL DUCT TO BE GALVANIZED FINISH, FREE FROM SCRATCHES, DENTS OR BLEMISHES AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT SHALL BE INTERNALLY LINED AND SEALED WITH DUCT SEALER COMPLETELY CONCEALED WITHIN THE DUCT JOINT. NO EXPOSED SEALER OR TAPE WILL BE ACCEPTED.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE OR THRU JOIST SPACE.
 - AT THE START OF CONSTRUCTION, THE MECHANICAL CONTRACTOR SHALL INSPECT AND RUN TEST ALL EXISTING HVAC UNITS DESIGNATED FOR REUSE. CONTRACTOR SHALL INFORM THE ENGINEER OF ANY NECESSARY REPAIRS FOR APPROVAL IN A TIMELY MANNER, AS TO NOT DELAY THE PROJECT OPENING DATE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITS EQUIPPED FOR DAMPERS LOCATED ABOVE UNACCESSIBLE CEILINGS. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL ROOFING RELATED TO THE RELATIONSHIP OF DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE. IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AARC OR TABS CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURGH AT WILL@NATIONTAB.COM OR 314-954-6244.
 - THE CONTRACTOR SHALL OBTAIN A COPY OF THE LANDLORD'S TENANT CRITERIA MANUAL. TENANT CRITERIA MANUAL IS AN INTEGRAL PART OF THIS CONTRACT. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING WITH LANDLORD REQUIREMENTS AT NO ADDITIONAL COST TO THE TENANT.

- HVAC NOTES:**
- PROVIDE REFRIGERANT LINES FROM ASPH ON ROOF TO ACU-1 IN ROOM 107 AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES.
 - PROVIDE REFRIGERANT LINES FROM CONDENSING UNIT ON ROOF TO KITCHEN EQUIPMENT AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. REFER TO KITCHEN EQUIPMENT VENDOR DRAWINGS FOR ADDITIONAL INFORMATION. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES.
 - PROVIDE REFRIGERANT LINES FROM COND-1 ON ROOF TO FC-1 ABOVE KITCHEN SPACE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.



1 MECHANICAL REFRIGERANT PIPING LAYOUT PLAN
SCALE: 1/4" = 1'-0"



Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AHJ COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



Seal / Signature
Date: 07/22/22
COM # C-3262

ISSUE FOR CONSTRUCTION

Project Name
CHAPEL HILL

Project Number
69.6562.000


Description
MECHANICAL REFRIGERANT PIPING LAYOUT PLAN

Scale
1/4" = 1'-0"

M102


- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER AND/OR LIMITED FIELD VERIFICATION BY OTHERS. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.e. BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOKE AND HALON RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - EXPOSED SPIRAL DUCT TO BE GALVANIZED FINISH, FREE FROM SCRATCHES, DENTS OR BLEMISHES AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT SHALL BE INTERNALLY LINED AND SEALED WITH DUCT SEALER COMPLETELY CONCEALED WITHIN THE DUCT JOINT. NO EXPOSED SEALER OR TAPE WILL BE ACCEPTED. ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE OR THRU JOIST.
 - AT THE START OF CONSTRUCTION, THE MECHANICAL CONTRACTOR SHALL INSPECT AND RUN TEST ALL EXISTING HVAC UNITS DESIGNATED FOR REUSE. CONTRACTOR SHALL INFORM THE ENGINEER OF ANY NECESSARY REPAIRS FOR APPROVAL IN A TIMELY MANNER, AS TO NOT DELAY THE PROJECT OPENING DATE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITED QUERTCH FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILINGS. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE PROTECTION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE. IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AARC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW IF APPROVED. THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURGH AT WILL@NATIONTAB.COM OR 314-954-6244.
 - THE CONTRACTOR SHALL OBTAIN A COPY OF THE LANDLORD'S TENANT CRITERIA MANUAL. TENANT CRITERIA MANUAL IS AN INTEGRAL PART OF THIS CONTRACT. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING WITH LANDLORD REQUIREMENTS AT NO ADDITIONAL COST TO THE TENANT.

- HVAC NOTES:**
- PROVIDE NEW EXHAUST FAN AS NOTED ON PLANS AND SCHEDULED ON SHEET M-601. THE CONTRACTOR SHALL FIELD VERIFY THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE.
 - NEW HALTON GREASE EXHAUST FAN TO BE PROVIDED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE HALTON SHEETS M-611 THROUGH M-619 FOR ADDITIONAL INFORMATION. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE. PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO ACU-1 IN ROOM 107. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - ROF PH1-PKG14-24V AIR PURIFICATION SYSTEM TO BE PROVIDED AND INSTALLED BY NTAB. REFER TO RESPONSIBILITY MATRIX ON SHEET M-701 FOR ADDITIONAL INFORMATION. SHEET M-601 FOR SCHEDULE, AND SHEET M-603 FOR SPECIFICATIONS.
 - PROVIDE ASHP AS NOTED ON PLANS AND SCHEDULED ON SHEET M-601.
 - NEW HALTON MAKE-UP AIR UNIT TO BE PROVIDED BY OWNER FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY EXHAUST/FUE TERMINATION.
 - PROVIDE GOOSENECK TERMINATION FOR OUTDOOR AIR INTAKE FOR ACU-1. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION IS A MINIMUM OF 10'-0" FROM ANY EXHAUST/FUE TERMINATION. PROVIDE WITH BUG SCREEN.
 - DUCT SMOKE DETECTOR ON RETURN SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
 - EXISTING TRANE, YHC02E3, 6 TON ROOFTOP UNIT TO REMAIN. CONTRACTOR SHALL BALANCE EXISTING UNIT TO PROVIDE 2,400 CFM OF SUPPLY AIR AND OUTDOOR AIR AS INDICATED ON THE PLANS. FIELD VERIFY EXACT LOCATION.
 - EXISTING TRANE YCD150E3 ROOFTOP UNIT TO BE REPLACED, RE-USE EXISTING CURB. VERIFY EXACT LOCATION IN THE FIELD. SEE SHEET M-601 FOR ROOFTOP UNIT SCHEDULE. INSTALLATION MAY REQUIRE TRANSITION CURB ADAPTOR, RETAIL AIR SYSTEMS, CUSTOM CURB, OR EQUAL MANUFACTURER. CONTRACTOR SHALL BALANCE NEW UNIT TO PROVIDE SUPPLY AIR AS INDICATED IN THE SCHEDULE ON SHEET M-601 AND OUTDOOR AIR AS INDICATED ON THE PLANS.
 - EXISTING TRANE, YHC03E3, 3 TON ROOFTOP UNIT TO REMAIN. CONTRACTOR SHALL BALANCE EXISTING UNIT TO PROVIDE 1,200 CFM OF SUPPLY AIR AND OUTDOOR AIR AS INDICATED ON THE PLANS. FIELD VERIFY EXACT LOCATION. PROVIDE CONDENSING UNIT AS NOTED ON PLANS AND SCHEDULED ON SHEET M-601. PROVIDE REFRIGERANT LINES FROM COND-1 ON ROOF TO FC-1 ABOVE KITCHEN SPACE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - VERIFY EXISTING CONDITIONS. IF NOT PRESENT, DUCT SMOKE DETECTOR ON RETURN SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
 - INSTALL KITCHEN EQUIPMENT CONDENSING UNIT PER MANUFACTURER'S INSTRUCTIONS. COORDINATE WITH ARCHITECT AND STRUCTURAL FOR EXACT LOCATION.
 - GRV-1 TO BE EQUIPPED WITH FACTORY PROVIDED MOTORIZED DAMPER. INTERLOCK DAMPER WITH FC-1 SUPPLY FAN, RELIEF AIR, AND RETURN AIR MOTORIZED DAMPERS FOR 100% OUTDOOR AIR ECONOMIZER OPERATION.




DUCT DETECTORS MUST BE TESTED WITH SMOKE SUPPLIED BY THE MECHANICAL CONTRACTOR. THE FIRE AND MECHANICAL INSPECTORS MUST BE PRESENT TO WITNESS TEST.

1 MECHANICAL ROOF PLAN
SCALE: 1/4" = 1'-0"



Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AJH COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



Seal / Signature Date: 07/22/22
024 # C-3262

ISSUE FOR CONSTRUCTION


Project Name
CHAPEL HILL

Project Number
69.6562.000


Description
MECHANICAL ROOF PLAN

Scale
1/4" = 1'-0"


M150




7 CONDENSER REFRIGERANT LINE PIPING AND POWER THROUGH ROOF DECK
NOT TO SCALE



8 AHU DRAIN PAN DETAIL
NOT TO SCALE



9 ROOF EXHAUST FAN DETAIL
NOT TO SCALE




10 DUCT MOUNTED DIFFUSER DETAIL
NOT TO SCALE

MAXIMUM HALF OF DUCT PERIMETER	PAIR AT 10 FT. SPACING		PAIR AT 8 FT. SPACING		PAIR AT 5 FT. SPACING		PAIR AT 4 FT. SPACING	
	STRAP	WIRE/ROD	STRAP	WIRE/ROD	STRAP	WIRE/ROD	STRAP	WIRE/ROD
P/2 = 30"	1" x 22 GA.	10 GA. (.135")	1" x 22 GA.	10 GA. (.135")	1" x 22 GA.	12 GA. (.106")	1" x 22 GA.	12 GA. (.106")
P/2 = 72"	1" x 18 GA.	3/8"	1" x 20 GA.	1/4"	1" x 22 GA.	1/4"	1" x 22 GA.	1/4"
P/2 = 96"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"	1" x 20 GA.	3/8"	1" x 22 GA.	1/4"
P/2 = 120"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"	1" x 20 GA.	1/4"
P/2 = 168"	1 1/2" x 16 GA.	1/2"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"
P/2 = 192"	---	1/2"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 16 GA.	3/8"
P/2 = 193" UP	SPECIAL ANALYSIS REQUIRED							


WHEN STRAPS ARE LAP JOINED USE THESE MINIMUM FASTENERS:	SINGLE HANGER MAXIMUM ALLOWABLE LOAD	
	STRAP	WIRE OR ROD (DIA.)
1" x 18, 20, 22 GA. - TWO #10 OR ONE 1/4" BOLT	1" x 22 GA. - 80 LBS.	0.106" - 80 LBS.
1" x 16 GA. - TWO 1/4" DIA.	1" x 20 GA. - 320 LBS.	0.135" - 120 LBS.
1" x 16 GA. - TWO 3/8" DIA.	1" x 18 GA. - 420 LBS.	0.162" - 160 LBS.
1" x 16 GA. - TWO 3/8" DIA.	1" x 16 GA. - 700 LBS.	1/4" - 270 LBS.
1 1/2" x 16 GA. - 1100 LBS.	1 1/2" x 16 GA. - 1100 LBS.	3/8" - 680 LBS.
		1/2" - 1250 LBS.
		5/8" - 2000 LBS.
		3/4" - 3000 LBS.

4 RECTANGULAR DUCT HANGER TABLE
NOT TO SCALE


- NOTES:**
- THERMAL CERAMICS FIREMASTER FASTWRAP XL IS TESTED TO ASTM E2336 AND UL LISTED PER AHK1018 TO PROVIDE ZERO CLEARANCE TO COMBUSTIBLES AND TO PROVIDE A 1 OR 2 HOUR EXPOSURE. THROUGH PENETRATIONS FIRESTOP SYSTEMS ARE TESTED IN ACCORDANCE WITH ASTM E 814 (UL 1479). ICC-ES APPROVAL PER REPORT ESR 2213 OR EST 2832.
 - COMPLIANT TO THE FOLLOWING CODES: NFPA 96, INTERNATIONAL MECHANICAL CODES, UNIFORM MECHANICAL CODE, CALIFORNIA MECHANICAL CODE.
 - INSULATION APPLIED IN TWO LAYERS WITH TIGHT COMPRESSION JOINT ON BOTH LAYERS AT ALL JOINTS.
 - MINIMUM 16 GAUGE CARBON STEEL (OR 18 GAUGE STAINLESS STEEL) RECTANGULAR OR ROUND GREASE EXHAUST DUCT.
 - INSTALL UL LISTED AND LIQUID TIGHT THERMAL CERAMICS FASTDOOR XL ACCESS DOORS AT ALL CHANGES IN DIRECTION AND AT MINIMUM EVERY 20 FT ON HORIZONTAL RUNS.
 - SUPPORT HANGER SYSTEMS DO NOT NEED TO BE WRAPPED PROVIDED THE HANGER RODS ARE MINIMUM OF 3/8" IN. DIAMETER AND SUPPORTS ARE MINIMUM 2 2 x 1/8 IN. STEEL ANGLE OR SMACNA EQUIVALENT SUPPORT SYSTEM.
 - THERMAL CERAMICS DUCT WRAP SHALL BE INSTALLED DIRECTLY ONTO THE DUCT AND APPLIED FROM THE HOOD CONNECTION TO THE CONNECTION OF THE PAN.
 - THERMAL CERAMICS DUCT ENCLOSURE SYSTEM SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS AND UL LISTINGS.




5 FIREMASTER FASTWRAP XL DETAIL
NOT TO SCALE




6 TYPICAL DX HORIZONTAL UNIT SUSPENSION DETAIL
NOT TO SCALE



1 DUCTWORK DETAILS
NOT TO SCALE



2 DUCT HANGER DETAIL
NOT TO SCALE



2 EQUIPMENT BASE RAIL SUPPORT DETAIL
NOT TO SCALE

SHAKE SHACK
NC - 1414 - CHAPEL HILL
1800 E FRANKLIN STREET,
UNIT 40
CHAPEL HILL, NC 27514


Gensler
LIC. NO. AA0002837
45 FREMONT ST
SUITE 1500
SAN FRANCISCO, CA 94105
UNITED STATES
TEL 415.433.3700
FAX 415.836.4599

SATELLITE OFFICE:
400 N ASHLEY DRIVE
SUITE 0400
TAMPA, FL 33602
UNITED STATES
TEL 813.204.9000
FAX 813.223.6948

Schnackel
MEFP ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

TriMark
FOODSERVICE CONSULTANT
505 COLLINS ST
PO BOX 3505
SOUTH ATTLEBORO
MA 02703
TEL 508.399.6000
FAX 508.761.3620

Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AHJ COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



Seal / Signature

ISSUE FOR CONSTRUCTION


Project Name
CHAPEL HILL

Project Number
69.6562.000


Description
MECHANICAL DETAILS

Scale
1/4" = 1'-0"


M501



13 TYPICAL ROOF TOP UNIT DETAIL
NOT TO SCALE



14 ROOF TOP UNIT CONDENSATE DETAIL
NOT TO SCALE






15 CONDENSING UNIT SUPPORT DETAIL
NOT TO SCALE


DIA.	WIRE DIA.	ROD	STRAP
10" DN	ONE 12 GA.	1/4"	1" x 22 GA.
11-18"	TWO 12 GA. OR ONE 8 GA.	1/4"	1" x 22 GA.
19-24"	TWO 10 GA.	1/4"	1" x 22 GA.
25-36"	TWO 8 GA.	3/8"	1" x 20 GA.
37-50"	-	TWO 3/8"	TWO 1" x 20 GA.
51-60"	-	TWO 3/8"	TWO 1" x 18 GA.
61-84"	-	TWO 3/8"	TWO 1" x 16 GA.
85-96"	-	TWO 1/2"	TWO 1 1/2" x 16 GA.

NOTES:
1. STRAPS ARE GALVANIZED STEEL; RODS ARE UNCOATED OR GALVANIZED STEEL; WIRE IS BLACK ANNEALED, BRIGHT BASIC OR GALVANIZED STEEL. ALL ARE ALTERNATIVES.
2. TABLE ALLOWS FOR CONVENTIONAL WALL THICKNESS, AND JOINT SYSTEMS PLUS ONE LB/SF OF INSULATION WEIGHT. IF HEAVIER DUCTS ARE TO BE INSTALLED, ADJUST HANGER SIZES TO BE WITHIN THEIR LOAD LIMITS.


16 ROUND DUCT HANGER TABLE
NOT TO SCALE




9 EXPOSED ROUND DUCT SUPPORT DETAIL
NOT TO SCALE




10 CURB ADAPTER
NOT TO SCALE




11 EXPOSED RECTANGULAR DUCT SUPPORT DETAIL
NOT TO SCALE



12 CURB FLASHING DETAIL
NOT TO SCALE




5 REMOTE VOLUME DAMPER CONTROLLER
NOT TO SCALE




NOTE:
1. DUCT SMOKE DETECTOR ON RETURN AND/OR SUPPLY SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.


6 DUCT SMOKE DETECTOR DETAIL
NOT TO SCALE




7 FLEXIBLE DUCT SUPPORTS
NOT TO SCALE




8 CONDENSING UNIT ANCHOR DETAIL (METAL)
NOT TO SCALE




1 TYPICAL DIFFUSER CONNECTION
NOT TO SCALE



2 KITCHEN HOOD EXHAUST FAN
NOT TO SCALE




3 TYPICAL DRYWALL MOUNTING FRAME DETAIL
NOT TO SCALE



4 TYPICAL ROUND DUCT FITTINGS
NOT TO SCALE

Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AHJ COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



Seal / Signature

ISSUE FOR CONSTRUCTION

Project Name
CHAPEL HILL
Project Number
69.6562.000
Description
MECHANICAL DETAILS

Scale
1/4" = 1'-0"

M502

SPECIFICATIONS TABLE OF CONTENTS

SECTION 230000 - HVAC GENERAL CONDITIONS
SECTION 230548 - VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT
SECTION 230563 - TESTING, ADJUSTING, AND BALANCING FOR HVAC
SECTION 230713 - DUCT INSULATION
SECTION 230713.13 - GREASE DUCT FIREPROOFING
SECTION 230719 - HVAC FIRING INSULATION
SECTION 230860 - COMMISSIONING OF HVAC
SECTION 230963 - SEQUENCE OF OPERATIONS FOR HVAC CONTROLS
SECTION 231000 - HVAC DUCTS AND CASINGS
SECTION 231000 - AIR DUCT ACCESSORIES
SECTION 231423 - HVAC POWER VENTILATORS
SECTION 231700 - HEATS
SECTION 232613 - PACKAGED AIR-COOLED REFRIGERANT COMPRESSOR AND CONDENSER UNITS
SECTION 233713 - MODULAR INDOOR CENTRAL-STATION AIR-HANDLING UNITS
SECTION 237413 - PACKAGED OUTDOOR AIR-FIRED
SECTION 238127 - SMALL SPLIT-SYSTEM HEATING AND COOLING

SECTION 230000 - HVAC GENERAL CONDITIONS

- PART 1 GENERAL**
1.01 APPLICABILITY
 A. This section supplements all sections of the Specifications for Division 23 and shall apply to all phases of work hereinafter specified, shown on the Drawings, or required to provide a complete installation of approved HVAC systems.
1.02 DEFINITIONS
 A. "Work" is hereby defined as: "The construction and services required by the Contract Documents and includes all labor, materials, equipment, and services provided or to be provided by the Contractor to fulfill the Contractor's obligations. The work may constitute the whole or a part of the project."
 B. "Furnish" is hereby defined as: "To supply, deliver, unload, and inspect for damage."
 C. "Install" is hereby defined as: "To unpack, assemble, erect, apply, place, finish, cure, protect, clean, connect, and place into operation in accordance with the Contract Documents."
 D. "Provide" is hereby defined as: "To furnish and install."
 E. "Connect" is hereby defined as: "To bring service to the equipment and make final attachment including necessary ductwork, piping, wiring, etc."
 F. "Concealed" is hereby defined as: "Hidden from sight in chases, formed spaces, soffits, and ceilings installed by the architect, where wiring or disfigurement has occurred. All pipe, equipment, and accessories shall be new."
 G. "Exposed" is hereby defined as: "Not installed underground nor concealed as defined on the Specifications."
 H. "Drawings" is hereby defined as: "All plans, details, equipment schedules, diagrams, sketches, etc. issued for the construction of the work."
1.03 CODES AND STANDARDS
 A. Perform work in accordance with the applicable Building Code, Electrical Code, Fire Code, Mechanical Code, Energy Code, and other applicable codes, amendments, and ordinances. Also perform all work in accordance with the Americans with Disabilities Act (ADA) and the Authority Having Jurisdiction (AHJ) including Fire Marshal(s).
 B. Perform work in accordance with Landlord requirements, including any Tenant, Criteria Manuals and Lease Exhibits, where applicable.
 C. Perform work in accordance with the applicable utility companies serving the project. Make all arrangements with the utility companies for proper coordination of the work.
 D. Recognized Standards: Design, manufacture, testing and method of installation of all apparatus and materials furnished under the requirements of these Specifications shall conform to the applicable standards of the American Society of Underwriters Laboratories, Inc. (U.L.), American Society for Testing and Materials (ASTM), American National Standards Institute (ANSI), and National Electrical Code (NEC), National Fire Protection Association (NFPA), American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE), and the Sheet Metal and Air Conditioning Contractors' National Association (SMACNA).
 E. The Contract Documents shall take precedence where the Contract Documents exceed code, Landlord, utility, or recognized standards requirements.
1.04 PERMITS AND FEES
 A. Permits, licenses, fees, inspections and arrangements required for the work under this Contract shall be obtained by the Contractor at his expense, unless otherwise indicated.
1.05 CONTRACT DRAWINGS
 A. The Contractor is responsible to obtain, fully understand, and coordinate the work with the complete set of Contract Documents including all associated costs, arising from issues caused by the Contractor's failure to understand and/or coordinate the work with the complete set of Contract Documents or the Contractor's sole responsibility.
 B. Work under these sections is diagrammatic unless indicated otherwise and is intended to convey the intent of the architect. Follow these drawings in laying out ductwork, piping, equipment, and accessories. Follow these drawings in laying out the work and verify that all equipment, materials, and accessories are correct. Where a question exists as to the exact intended location of ductwork, piping, or equipment, obtain instructions from the Architect before proceeding with the work.
 C. Notify the Architect for resolution if a discrepancy is discovered within the Contract Documents. Failure of the Contractor to notify the Architect of discrepancies shall result in the resolution becoming the Contractor's responsibility and subject to the Architect's final decision. The Contractor shall resolve a discrepancy resolution of which they were not notified, the Contractor is fully responsible to correct the installation, including all associated costs, with the approval of the installation given by the Architect.
1.06 EXISTING CONDITIONS
 A. Verify all existing conditions prior to beginning work.
 B. Any existing conditions indicated on the Contract Documents are based on information drawings provided by others and possibly limited field verification. The Contractor shall adjust for actual field conditions at no additional expense to the Owner.
 C. The Contractor shall visit the project site, review existing conditions against the Contract Documents and schedules. Indicate catalog number on the cut sheets, and start of the work. By signing the Contract, the Contractor acknowledges the site visit has been completed and that the Contractor is aware of all existing conditions.
 D. The Contractor shall notify the Architect of major discrepancies in writing so the appropriate modifications to the design can be made without delay to the project. The Contractor assumes full responsibility for discrepancies of which the Architect is not informed.
1.07 SUBMITTALS
 A. Shop Drawings:
 1. Furnish the following submittals to the Architect for review by the Engineer:
 a. Provide product data and shop drawings for vibration isolation.
 b. Provide balancing firm qualifications and final test report for testing, adjusting, and balancing.
 c. Provide product data for duct insulation.
 d. Provide product data for duct fireproofing (if specified).
 e. Provide product data for HVAC piping insulation.
 f. Provide product data and shop drawings for air duct ductwork.
 g. Provide product data for air duct accessories.
 h. Provide product data and shop drawings for HVAC power ventilators.
 i. Provide product data and shop drawings for packaged roof top units.
 j. Provide product data and shop drawings for packaged rooftop units.
 2. Submittals other than those listed above shall not be reviewed, but will be returned stating as such.
 3. Shop drawings shall be prepared by a manufacturer's representative, and shall contain names of the manufacturer and cut sheets of equipment to be used on the project. Use manufacturer's specification sheets identified by number on the cut sheets. As applicable, provide construction data, weight and dimensional data, voltage ratings, performance data, and other data as required on the cut sheets and sound data as part of the shop drawing submittal.
 4. Submittals are reviewed for general compliance with the Contract Documents. Dimensions, quantities and details are not checked during submittal review. Review of the submittals does not relieve the Contractor of the responsibility for providing all materials, equipment and accessories necessary for a complete and operational system meeting the requirements of the project and the intent of the Contract Documents. The Contractor is responsible for coordination of substituted materials and equipment lies solely with the substituting contractor(s).
 5. Electrical Characteristics: Verify that proper power supply is available prior to ordering equipment. Verify proper voltage, phase and current rating of power supply and inform Engineer of any deviations prior to order. Connection of equipment or start-up. Responsibility for verification of proper power supply voltage and any other return damage resulting from incorrect connections shall rest with this Contractor.
 B. Test Reports: Provide testing, adjusting, and balancing (TAB) and Commissioning reports to the Architect for review by the Engineer. All other reports shall be provided to the Owner.
1.08 QUALITY ASSURANCE
 A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum five years experience.
 B. Installer Qualifications: Company specializing in performing the work of this section, with minimum five years experience.
 C. Products:
 1. Listed and classified by Underwriters Laboratories Inc. as suitable for the purpose specified and indicated.
 D. All equipment and components shall be free of oil rust/corrosion or any visible damage. All items not meeting the requirements shall be substituted with no change in the Contract amount.
 E. Equipment performance and accessories shall be as scheduled on the Drawings and specified herein. Inclusion in both locations is not a prerequisite to inclusion in the Contract. Equipment and accessories specified in either location shall be included in the Contract. Provide all necessary accessories and connections required for a complete, functional system, including all required components reasonably inferred to be necessary although such components may or may not be specifically indicated in the Contract Documents.
 F. Code or utility company requirements shall supersede any conflicting requirements of this section.
1.09 DELIVERY, STORAGE, AND HANDLING
 A. Roof top equipment: Protect units from physical damage by storing off site until roof mounting curbs are in place, ready for immediate installation of units.
 B. Protect equipment from weather damage by covering with weather proof, chemical, and mechanical damage, by storing in original wrapping.
 C. Protect dampers and accessories from damage by wrapping linkages, blades and finishes.
 D. Provide temporary and caps and closures on piping and fittings. Maintain in place until installation.
 E. Protect motors stored on site from weather and moisture by maintaining factory covers and labels weather proof covering. For extended outdoor storage, remove motors from equipment and store separately.
1.10 WARRANTY AND GUARANTEE
 A. Submit manufacturer's warranty and ensure forms have been filled out in Owner's name and registered with manufacturer.
 B. Provide one year manufacturer warranty for pumps.
 C. Provide five year manufacturer warranty for solid state ignition modules.
 D. Provide five year manufacturer warranty for compressors, heat exchangers, condensing units, and electronic air cleaners.

- PART 2 PRODUCTS**
2.01 MANUFACTURERS
 A. Isolation Technology, Inc.; Kinetics Noise Control, Inc.; Mason Industries.
2.02 VIBRATION ISOLATORS
 A. Restraint: Spring Mount or Spring Isolators:
 1. Springs: Minimum horizontal stiffness equal to 75 percent vertical stiffness, with working deflection between 0.3 and 0.6 of maximum deflection. Color code springs for load carrying capacity.
 2. Spring Mounts: Provide with leveling devices, minimum 0.25 inch thick neoprene sound pads, and zinc chromate plated steel.
 3. Sound Pads: Size for minimum deflection of 0.05 inch, meet requirements for neoprene pad isolators.
 4. Restraint: Provide heavy mounting frame and limit stops.
 5. For Exterior and Humid Areas: Not dipped galvanized housings and neoprene coated springs.
 B. Spring Hanger:
 1. Springs: Minimum horizontal stiffness equal to 75 percent vertical stiffness, with working deflection between 0.3 and 0.6 of maximum deflection. Color code springs for load carrying capacity.
 2. Housings: Incorporate neoprene isolation pad meeting requirements for neoprene pad isolators or rubber hangers with threaded inserts.
 3. Misalignment: Capable of 20 degree hanger rod misalignment.
 4. For Exterior and Humid Areas: Not dipped galvanized housings and neoprene coated springs.
 C. Neoprene Pad Isolators:
 1. Rubber or neoprene waffle pad:
 a. Hardness: 30 durometer.
 b. Thickness: Minimum 1/2 inch.
 c. Maximum Loading: 50 psi.
 d. Rib Height: Maximum 0.7 times width.
 2. Rubber Mount or Hanger: Molded rubber designed for 0.4 inch deflection with threaded insert.
 3. Glass Fiber Pads: Neoprene jacketed pre-compressed molded glass fiber.
PART 3 EXECUTION
3.01 INSTALLATION
 A. Install in accordance with manufacturer's instructions.
 B. On closed spring isolators, adjust so side stabilizers are clear under normal operating conditions.
 C. Prior to making piping connections to equipment with operating weights substitute oil filled from isolation system with temporary shims to fill piping. When full load is applied, adjust isolators to level to allow shim removal.
 D. Support piping connections to equipment mounted on isolators using isolators or resilient hangers to nearest flexible pipe connector.
 E. Refer to other sections of this Specification for the acceptable types of flexible connectors to be used in conjunction with the equipment.
3.02 SCHEDULES
 A. Equipment Isolation Schedule: (Minimum deflection as sized by the isolation equipment manufacturer.)
 1. Fans, axial and centrifugal:
 a. Small fans up to 22 diameter wheel:
 1. Rubber Mount or Hanger
 2. Packaged roof top equipment
 a. Above grade roof structures:
 1. Base: Roof Curbs
 2. Isolation: Full perimeter Neoprene Pad between curb and units.
 b. 2 inch Thickness: 0.45
 c. 1-1/2 inches Thickness: 0.60
 2. Fans, axial and centrifugal:
 a. Floor mounted (all locations):
 1. Base: Concrete Heavykeeping Pad
 2. Isolation: Rubber or Spring Hanger
 b. Suspended:
 1. Isolation: Rubber or Spring Hanger
END OF SECTION

SECTION 230548 - VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT

- PART 1 GENERAL**
1.01 SECTION INCLUDES
 A. Vibration Isolators.
 B. Equipment:
 1. Fans, axial and centrifugal
 2. Packaged roof top equipment
 3. Furnaces and fan coil units.
1.02 SUBMITTALS
 A. Product Data: Provide schedule of vibration isolator type with location and load on each.
PART 2 PRODUCTS
2.01 MANUFACTURERS
 A. Isolation Technology, Inc.; Kinetics Noise Control, Inc.; Mason Industries.
2.02 VIBRATION ISOLATORS
 A. Restraint: Spring Mount or Spring Isolators:
 1. Springs: Minimum horizontal stiffness equal to 75 percent vertical stiffness, with working deflection between 0.3 and 0.6 of maximum deflection. Color code springs for load carrying capacity.
 2. Spring Mounts: Provide with leveling devices, minimum 0.25 inch thick neoprene sound pads, and zinc chromate plated steel.
 3. Sound Pads: Size for minimum deflection of 0.05 inch, meet requirements for neoprene pad isolators.
 4. Restraint: Provide heavy mounting frame and limit stops.
 5. For Exterior and Humid Areas: Not dipped galvanized housings and neoprene coated springs.
 B. Spring Hanger:
 1. Springs: Minimum horizontal stiffness equal to 75 percent vertical stiffness, with working deflection between 0.3 and 0.6 of maximum deflection. Color code springs for load carrying capacity.
 2. Housings: Incorporate neoprene isolation pad meeting requirements for neoprene pad isolators or rubber hangers with threaded inserts.
 3. Misalignment: Capable of 20 degree hanger rod misalignment.
 4. For Exterior and Humid Areas: Not dipped galvanized housings and neoprene coated springs.
 C. Neoprene Pad Isolators:
 1. Rubber or neoprene waffle pad:
 a. Hardness: 30 durometer.
 b. Thickness: Minimum 1/2 inch.
 c. Maximum Loading: 50 psi.
 d. Rib Height: Maximum 0.7 times width.
 2. Rubber Mount or Hanger: Molded rubber designed for 0.4 inch deflection with threaded insert.
 3. Glass Fiber Pads: Neoprene jacketed pre-compressed molded glass fiber.
PART 3 EXECUTION
3.01 INSTALLATION
 A. Install in accordance with manufacturer's instructions.
 B. On closed spring isolators, adjust so side stabilizers are clear under normal operating conditions.
 C. Prior to making piping connections to equipment with operating weights substitute oil filled from isolation system with temporary shims to fill piping. When full load is applied, adjust isolators to level to allow shim removal.
 D. Support piping connections to equipment mounted on isolators using isolators or resilient hangers to nearest flexible pipe connector.
 E. Refer to other sections of this Specification for the acceptable types of flexible connectors to be used in conjunction with the equipment.
3.02 SCHEDULES
 A. Equipment Isolation Schedule: (Minimum deflection as sized by the isolation equipment manufacturer.)
 1. Fans, axial and centrifugal:
 a. Small fans up to 22 diameter wheel:
 1. Rubber Mount or Hanger
 2. Packaged roof top equipment
 a. Above grade roof structures:
 1. Base: Roof Curbs
 2. Isolation: Full perimeter Neoprene Pad between curb and units.
 b. 2 inch Thickness: 0.45
 c. 1-1/2 inches Thickness: 0.60
 2. Fans, axial and centrifugal:
 a. Floor mounted (all locations):
 1. Base: Concrete Heavykeeping Pad
 2. Isolation: Rubber or Spring Hanger
 b. Suspended:
 1. Isolation: Rubber or Spring Hanger
END OF SECTION

SECTION 230563 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

- PART 1 GENERAL**
1.01 SECTION INCLUDES
 A. Testing, adjusting, and balancing of air systems:
 1. Air handling units; Packaged heating and/or cooling equipment; Fans, (Exhaust and supply); Coils; Terminal equipment; Air inlets and outlets; Diffusers, grilles, louvers, etc.)
 B. Measurement and balancing of air inlets and outlets, (Diffusers, grilles, louvers, etc.)
 C. Independent agency requirements.
1.02 SUBMITTALS
 A. Qualifications: Submit name of adjusting and balancing agency and TAB supervisor for approval within 30 days after award of Contract. Provide TAB Agency:
 1. Final Report: Indicate deficiencies in systems that would prevent proper testing, adjusting, and balancing of systems and equipment loadings.
 2. Provide temporary and caps and closures on piping and fittings. Maintain in place until installation.
 3. Provide reports in bound manuals, complete with index page and indexing tabs, covers and labels weather proof covering. For extended outdoor storage, remove motors from equipment and store separately.
1.03 WARRANTY
 A. Submit manufacturer's warranty and ensure forms have been filled out in Owner's name and registered with manufacturer.
 B. Provide one year manufacturer warranty for pumps.
 C. Provide five year manufacturer warranty for solid state ignition modules.
 D. Provide five year manufacturer warranty for compressors, heat exchangers, condensing units, and electronic air cleaners.

SECTION 230713 - DUCT INSULATION

- PART 1 GENERAL**
1.01 SECTION INCLUDES
 A. Duct Insulation.
 B. Duct Liner.
 C. Insulation Joints.
 D. Supply, return or exhaust ducts in ceiling spaces.
 E. Supply, return or exhaust ducts in interior unconditioned areas.
 F. Supply, return or exhaust ducts in exposed locations.
1.02 FIELD CONDITIONS
 A. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and sealants.
 B. Maintain temperature during and after installation for minimum period of 24 hours.
PART 2 PRODUCTS
2.01 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION
 A. Surface Burning Characterization: Flame spread/smoke developed index of 25/50, maximum, when tested in accordance with ASTM E 84, NFA 255, or UL 723.
 B. Manufacturer: Knaflex Fiberglass; Johns Manville Corporation; Owens Corning Corp.; CertainTeed Corporation.
2.02 CLASS FIBER, FLEXIBLE
 A. Insulation: ASTM C 553; Flexible, noncombustible blanket.
 1. "K" value: 0.31 at 75 degrees F, when tested in accordance with ASTM C 518.
 2. Maximum Service Temperature: 450 degrees F.
 3. Maximum Water Vapor Sorption: 0.0 percent by weight.
 B. Vapor Barrier Jacket:
 1. Kraft paper with glass fiber yarn and bonded to aluminumized film.
 2. Moisture Vapor Permeability: 0.029 ngPa s m (0.02 perm inch), when tested in accordance with ASTM 96/E 96M.
 3. Secure with pressure sensitive tape.
 C. Vapor Barrier Tape:
 1. Kraft paper reinforced with glass fiber yarn and bonded to aluminumized film, with pressure sensitive rubber based adhesive.
 D. Outdoor Vapor Barrier Mastic:
 1. Vinyl emulsion type acrylic or mastic, compatible with insulation, block color.
 E. Tie Wire: Annealed steel, 16 gage.
2.03 DUCT LINER
 A. Insulation: Incombustible glass fiber complying with ASTM C 107; flexible blanket, rigid board, and preformed round liner board. Impregnated surface and edges coated with acrylic polymer slush to be fungus and bacteria resistant by testing to ASTM C 21.
 1. Apparent Thermal Conductivity: Maximum of 0.31 at 75 degrees F.
 2. Service Temperature: Up to 250 degrees F.
 3. Initial Velocity on Contact (Air Side) for Air Erosion: 5,000 fpm, minimum.
 4. Minimum Moisture Reduction Coefficient:
 a. 1/2 inch Thickness: 0.45
 b. 1 inch Thickness: 0.45
 c. 1-1/2 inches Thickness: 0.60
 5. Density: 1.0 lb/cu ft density.
 B. Adhesive: Waterproof, fire-retardant type.
 C. Liner Fasteners: Galvanized steel, self-adhesive pad or impact applied with integral, or press-on head.
PART 3 EXECUTION
3.01 INSTALLATION
 A. Install in accordance with manufacturer's instructions and NAIMA National Insulation Standards.
 B. Insulated ducts conveying air below ambient temperature:
 1. Provide insulation with vapor barrier jackets.
 2. Finish with tape and vapor barrier jacket.
 3. Continue insulation through walls, sleeves, hangers, and other duct penetrations.
 4. Insulate entire system including fittings, joints, flanges, pipe dampers, flexible connections, and expansion joints.
 C. Insulated ducts conveying air above ambient temperature:
 1. Provide with or without standard vapor barrier jacket.
 2. Insulate fittings and joints. Where service access is required, bevel and seal ends of insulation.
 D. Exterior Duct Installation:
 1. Secure insulation with vapor barrier with wires and seal jacket joints with vapor barrier adhesive tape to match jacket.
 2. Secure insulation without vapor barrier with staples, tape, or wires.
 3. Install without sag under underside of duct. Use adhesive or mechanical fasteners where necessary to prevent sagging.
 4. Seal and smooth joints. Seal and coat fasteners joints.
 5. Seal and smooth joints. Seal and coat fasteners joints.
 6. Seal and smooth joints. Seal and coat fasteners joints.
 7. Seal and smooth joints. Seal and coat fasteners joints.
 8. Seal and smooth joints. Seal and coat fasteners joints.
 9. Seal and smooth joints. Seal and coat fasteners joints.
 10. Seal and smooth joints. Seal and coat fasteners joints.
3.02 SCHEDULES
 A. The Contractor may use any of the following insulating materials, at his option, provided the selected material meets with the approval of all State, local, and utility company requirements. Verification of compliance of the selected insulating material and thickness with all State and local codes and utility company requirements is the sole responsibility of the installing Contractor.
 B. Supply air ducts in ceiling spaces:
 1. Flexible Glass Fiber Duct Insulation: 1-1/2 inches thick.
 2. Flexible Glass Fiber Duct Liner Insulation: 1 inch thick.
 C. Supply, return or exhaust air ducts in crawl spaces, attics or other unconditioned areas:
 1. Flexible Glass Fiber Duct Insulation: 3 inches thick.
 2. Supply air ducts exposed in finished areas:
 1. Flexible Glass Fiber Duct Liner Insulation: 1 inches thick.
 E. Return or exhaust air ducts exposed in finished areas: None.
END OF SECTION

SECTION 230713.13 - GREASE DUCT FIREPROOFING


- PART 1 GENERAL**
1.01 SECTION INCLUDES
 A. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts).
 B. Fireproofing at duct penetrations through fire rated walls and floors.
PART 2 PRODUCTS
2.01 MANUFACTURERS
 A. Fire Protection Products, Inc.; Unifrax Firewrap; Morgan Thermal Ceramics.
2.02 MATERIALS
 A. Grease Duct Fireproofing: Material applied directly to metal ducts and achieving two-hour fire rated separation when tested in accordance with UL 2221 or ASTM E2336.
 1. Surface Burning Characteristics: Flame spread index of 0 and smoke developed index of 0.
 2. Combustibility: Non-combustible, when tested in accordance with ASTM 136.
 3. Flexibility: Capable of being formed around corners and shapes by hand.
 4. Surface: Fall or other resistant surface. Fiber not exposed after installation.
 5. Accommodator: For Duct Access Doors and Panels: Capable of being installed to achieve fire rating without impeding access.
 6. Accommodator: For Duct Access Doors and Panels: Capable of being installed to achieve fire rating without impeding access.
 B. Fasteners: Non-combustible; use one or both of the following to attach fiber to ducts:
 1. Banding: Steel or stainless steel, 1/2 inch wide, minimum, and 0.015 inch thick, minimum.
 2. Insulation Pins: Copper-coated steel impalement pins, minimum 12 gage, for wall and ceiling applications with self-healing washers, 1-1/2 inch square or diameter, or equivalent sized cup-head pins.
 C. Access Panel Hardware: Galvanized threaded rods, sleeves, washers, and wing nuts as specified on the Drawings.
 D. Tape: Aluminum foil tape for sealing exposed fiber edges and repairing tears in fabric.
 E. Fireproofing: Material tested in conjunction with fireproofing, in accordance with ASTM E 814, to achieve fire rated penetration seal at duct penetrations through fire rated assemblies.
 1. Fire Rating: Same or greater than rating of penetrating assembly.
 2. Acceptable Products: 3M Fire Barrier 1000 N/S, 1000 S/L, and 2000+ Silicone Sealants, as required by tested assembly.
PART 3 EXECUTION
3.01 EXAMINATION
 A. Do not begin installation until substrates have been properly prepared.
 B. If substrate preparation is the responsibility of another installer, notify Engineer of unsatisfactory preparation before proceeding.
3.02 PREPARATION
 A. Clean surfaces thoroughly prior to installation.
 B. Prime, seal, and other details per the manufacturer for achieving the best result for the substrate under the project conditions.
3.03 INSTALLATION
 A. Install in strict accordance with manufacturer's instructions and as indicated on the Drawings.
 B. Where required, provide required duct leakage and weld tests in the presence of the official, including but not limited to light tests and smoke tests, to determine the integrity of the installation. The Contractor shall be responsible for the cost of all additional testing and the cost of rework.
 C. Install fireproofing on entire surface of ducts indicated, except where Contract Documents indicate otherwise.
 D. At penetrations of ducts through fire rated assemblies (walls, floors, roofs), extend the fireproofing through the opening until sealant or space between fireproofing and edge of opening with fireproofing.
 E. Seal fireproofing around penetrations with fireproofing or insulation pins welded directly to surface of duct; do not use adhesives.
 F. Install fireproofing on supports and hangers unless hanger rods are at least 3/8 inch diameter and hangers are at least 2 by 1/4 inch angle or equivalent horizontal supports are at least 2 by 1/4 inch hanger steel or equivalent.
 G. Access Panels: Do not cut blocks access; install fireproofing so that panel can be removed without disturbing fireproofing.
 H. Seal all duct end edges and repair tears in facing using aluminum foil tape.
END OF SECTION

SECTION 230860 - COMMISSIONING OF HVAC



- PART 1 GENERAL**
1.01 SUMMARY
 A. See Section 01 9113 - General Commissioning Requirements for overall objectives; Commissioning of HVAC systems.
 B. This section covers the Contractor's responsibilities for commissioning, each subcontractor's responsibilities for commissioning, and the Contractor's overall responsibility for the commissioning activities required by the Contract Documents.
 C. The Commissioning Authority (CA) directs and coordinates all commissioning activities and Functional Test Procedures for Contractor's use.
 D. Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning activities for the following specific items:
 1. Major and minor equipment items.
 2. Variable frequency drives.
 3. Sound control devices.
 4. Ductwork and accessories.
 5. Terminal units.
 6. Vibration control devices.
 7. Special Ventilation: Hoods, pressurization, exhaust, etc.
 8. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts), as required by testing and approved by the Authority Having Jurisdiction (AHJ) as required by testing and approved by the Authority Having Jurisdiction (AHJ).
 9. Indoor Air Quality Procedures: The Commissioning Authority will coordinate; the Contractor shall coordinate with the CA to ensure that all commissioning

RESERVED FOR DOCUMENT BINDING

ANSUL R-102 FIRE SUPPRESSION SYSTEM FIRE SYSTEM IS INTEGRAL WITH FACTORY DESIGN/PIPING/FIELD CERTIFICATION



ANSUL R-102 SYSTEM
MOUNTED IN FIRE CABINET:
(1) OEM REGULATED RELEASE
(3) 3 GALLON TANKS



FLOW POINT CHART
ANSUL R-102 FLOW POINT CALCULATION

NOZZLE TYPE	NOZZLE FLOW PT.	NOZZLE QUANTITY	TOTAL FLOW PT.
3N	3	0	#
290	2	0	#
260	2	6	#
245	2	2	#
230	2	0	#
23V	2	0	#
2120	2	0	#
1W	1	2	#
1E	1	2	#
1E	1	0	#
1/2N	1/2	0	#
TOTAL FLOW POINTS USED			#
MAX. SYSTEM FLOW POINTS			24 (12 GALLON)

NOTE:
HALTON COMPANY WILL SUPPLY ANSUL COMPONENTS AND PRE-PIPED HOODS PER PUBLISHED ANSUL GUIDELINES AND RECOMMENDATIONS. IT IS THE RESPONSIBILITY OF THE F.S.E.C. TO INFORM HALTON OF ANY SPECIAL REQUIREMENTS OF THE LOCAL JURISDICTION PRIOR TO RELEASE OF EQUIPMENT.




ANSUL NOTES

GENERAL NOTES:

- THIS INSTALLATION IS TO BE MADE IN ACCORDANCE WITH THE R-102 INSTALLATION MANUAL AND IN ACCORDANCE WITH ALL STATE AND LOCAL CODES.
- THE WIRE ROPE FOR THE DETECTOR AND REMOTE PULL STATION IS TO BE INSTALLED BY AN AUTHORIZED AND FACTORY TRAINED DISTRIBUTOR OR SERVICE REPRESENTATIVE.
- THIS INSTALLATION IS TO BE INSPECTED, PUT INTO OPERATION AND CERTIFIED BY AN AUTHORIZED AND FACTORY TRAINED DISTRIBUTOR OR SERVICE REPRESENTATIVE.
- ELECTRICAL CONTACTS AND WIRING FOR APPLIANCE SHUT OFF TO BE PROVIDED BY THE ELECTRICAL CONTRACTOR.
- ANSUL R-102 RESTAURANT FIRE SUPPRESSION SYSTEMS HAVE BEEN TESTED AND ARE LISTED BY UNDERWRITERS LABORATORIES INC. AS PRE-ENGINEERED SYSTEMS, AND WHEN INSTALLED AS SHOWN ON THIS DRAWING SHALL COMPLY WITH ALL RELEVANT ANSUL INSTALLATION RECHARGE INSPECTION AND MAINTENANCE MANUALS AND SHALL COMPLY WITH NFPA 96 WHEN INSTALLED AND CERTIFIED BY AUTHORIZED TRAINED ANSUL DISTRIBUTORS IN ACCORDANCE WITH THE MANUAL.
- ALL AGENT DISTRIBUTION PIPING AND DETECTION CONDUIT HOOD PENETRATIONS MUST BE PROPERLY SEALED IN ACCORDANCE WITH NFPA 96.

DISTRIBUTION PIPING REQUIREMENT NOTES:

- PIPE SHALL BE 3/8" SCHEDULE 40 BLACK IRON, CHROME PLATED OR STAINLESS STEEL UNLESS OTHERWISE NOTED.
- FINAL NOZZLE LOCATION MAY NOT VARY FROM LOCATION SHOWN.



NOTE:
ALL PIPING FOR LOW PROXIMITY APPLIANCE PROTECTION SHALL BE PROVIDED & INSTALLED BY THE INSTALLING ANSUL DISTRIBUTOR & NOT BY HALTON.

NOTE:
HAND HELD EXTINGUISHERS, IF REQUIRED, ARE TO BE PROVIDED BY OTHERS.

- ANSUL R-102 FIRE SYSTEM
- THREE TANK SYSTEM (9 GALLON)
- 3/8" S.S. APPLIANCE DROPS (EXPOSED)
- MECHANICAL GAS VALVE - (ADVISE SIZE)

ALL APPLIANCE DROPS TO HAVE SWIVELS

****NOTE****
ANSUL R-102 OVERLAPPING SYSTEM

THIS DRAWING MUST BE CHECKED, SIGNED AND RETURNED TO THE APPROPRIATE FACTORY. PLEASE VERIFY THE FOLLOWING:

- ALL DIMENSIONAL INFORMATION, MOUNTING POSITIONS
- THE LOCATION AND TYPE OF COOKING EQUIPMENT.

NOTE TO APPROVER:
REVISIONS TO THIS DRAWING SHALL BE MADE ONLY BY THE ORIGINAL DESIGNER. ANY CHANGES TO THE DRAWING SHALL BE MADE BY THE ORIGINAL DESIGNER. ANY CHANGES TO THE DRAWING SHALL BE MADE BY THE ORIGINAL DESIGNER. ANY CHANGES TO THE DRAWING SHALL BE MADE BY THE ORIGINAL DESIGNER.

APPROVED FOR FABRICATION: WITH CHANGES AS NOTED
APPROVED FOR INSTALLATION: WITH NO CHANGES

DATE: _____

WEBSITE: www.halton.com

HALTON CO. (USA)
1270 237-5600
SCOTTSDALE, AZ 85254

HALTON CO. (CANADA)
1-800-524-0301
MISSISSAUGA, ON L4X 1L7

MAIL APPROVED DRAWINGS TO APPROPRIATE FACTORY BELOW:

REV.	DESCRIPTION	DATE	BY
1	NO CHANGE	11.09.21	SKM

PROJECT: SHAKE SHACK 1414 CHAPEL HILL
LOCATION: CHAPEL HILL, NC
DRAWN BY: SKM
SCALE: NOT TO SCALE
DATE: 10.22.21
CONSULTANT: Halton

DRAWING TITLE: HOOD DETAILS
DRAWING No.: U21-722
REV. NO.: 1 SHEET NO.: 2 of 6

SHAKE SHACK
NC - 1414 - CHAPEL HILL
1800 E FRANKLIN STREET,
UNIT 40
CHAPEL HILL, NC 27514

Gensler
LIC. NO. AA0002837 TEL 415.433.3700
45 FREMONT ST. FAX 415.836.4599
SUITE 1500
SAN FRANCISCO, CA 94105
UNITED STATES

SATELLITE OFFICE: TEL 813.204.9000
400 N ASHLEY DRIVE
SUITE 0400 FAX 813.223.6948
TAMPA, FL 33602
UNITED STATES

Schnackel
MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

TriMark
FOODSERVICE CONSULTANT
505 COLLINS ST
PO BOX 3505
SOUTH ATTLEBORO
MA 02703
TEL 508.399.6000
FAX 508.761.3620

Seal / Signature
Date: 07/22/22
CMA # C-3262

ISSUE FOR CONSTRUCTION

Project Name: CHAPEL HILL

Project Number: 69.6562.000


Description: HALTON DRAWINGS

Scale: 1/4" = 1'-0"

M702

© 2021 Gensler


ITEM #CU-1



SEE NOTE 4
SERVICE CLEARANCE
48" (SEE NOTE 2
FOR CLEARANCE)


Notes:

1. Access opening is for field installed Bayloam accessory.
2. Minimum clearance for proper operation is 36" from walls, shrubbery, privacy fences, etc. Minimum clearance between adjacent units is 72". Recommended service clearance is 48".
3. Top discharge area should be unrestricted for 100" minimum. Unit should be placed so roof run-off water does not pour directly on unit.
4. Outdoor Air Temperature Sensor opening (Do Not Block Opening)



**6 TON COOLING CONDENSER (DUAL COMPRESSOR)
DIMENSIONAL DRAWING**

Hailguards - TTA
Condenser Coil Protection from Hail, Vandals, Etc. Perforated, Painted Galvanized Steel Factory Installed.
TTA Microchannel - General
Weatherproofed steel mounting/lifting rails Hermetic scroll compressors Microchannel condenser coils on select models Plate fin condenser coils Fans and motors Standard operating range 50-125°F (min. 0°F with low ambient accessory) Nitrogen holding charge Certified and rated in accordance with AHRI and DOE standards Certified to UL 1995
TTA Microchannel - Casing
Zinc coated, heavy gauge, galvanized steel Weather resistant baked enamel finish Meets ASTM B117, 672 hour spray test Removable single side maintenance access panels Lifting handles in maintenance access panels Unit base provisions for forklift and/or crane lifting
Refrigerations System - Dual Compressor
Two (2) separate and independent refrigerant circuits Each refrigeration circuit equipped with integral subcooling circuit Front or rear refrigerant line connections
Two (2) direct drive hermetic scroll compressors Suction gas-cooled motors w ± 10% voltage utilization range of unit nameplate voltage Crankcase Heaters Internal temperature and current sensitive motor overloads No compressor suction and/or discharge valves (reduced vibration/sound) Factory installed liquid line filter drier Phase loss/reverse rotation monitor Liquid line service ports Suction line service ports External high pressure cutout devices
TTA Microchannel - Condenser Coil (Microchannel)
Microchannel coils burst tested by the manufacturer Coils shall be leak tested to ensure the pressure integrity Factory pressure and leak tested to 660 psig Perforated steel hail guards factory installed
TTA Microchannel - Condenser Fan
26" or 28" propeller fan(s) Direct drive Statically and dynamically balanced
TTA Microchannel - Condenser Motor(s)
Permanently lubricated totally enclosed or open construction Built-in current and thermal overloads Ball or sleeve bearing type
TTA Microchannel - Controls
Choice of electromechanical or microprocessor Completely internally wired Numbered and colored wires Contactor pressure lugs or terminal block Unit external mounting location for disconnect device Single point power entry
TTA Controls: Electro-Mechanical
24V control circuit Control transformer Thermostat compatible Anti-Short Cycle Timer



WEIGHTS AND CORNER WEIGHTS
Shipping: 348.0 lb
Net: 279.0 lb
Corner 1: 90.0 lb
Corner 2: 82.0 lb
Corner 3: 54.0 lb
Corner 4: 53.0 lb

**WEIGHTS AND LOAD POINT LOCATION FOR CONDENSER
WEIGHT AND RIGGING**

CONDENSER COIL SPECIFICATIONS

6 Ton Trane TTA 208V

Unit Function	Cooling
Voltage	208-230/60/3
Refrigeration Circuit/Stage	Dual Compressors/Dual Circuit
Unit Tonnage	6 Tons
Refrigerant	R-410A Refrigerant
Controls	Electromechanical

Factory Installed Accessories
Condenser Coil Hail/Vandal Guard Kit

Electrical Data Condenser

Model:	TTA07243D
Unit Operating Voltage:	187-253
Minimum Circuit Ampacity:	23.0
Maximum Fuse Size:	30.0
Maximum Circuit Breaker:	30.0
Compressor Motor	
No.:	2
Volts:	208-230
Phase:	3
Amp-RLA:	9.0/9.0
Amp-LRA:	71.0/71.0
Condenser Fan Motor	
No.:	1
Volts:	208-230
Phase:	1
Amp-FLA:	3.1
Amp-LRA:	8.1

Compressor

Number:	Scroll
No. Compressor/Tons:	2/2.4
Cooling Stages per Compressor:	1


System Data (7)

No. Refrigerant Circuits:	2
Suction Line (in.) OD	3/4" Horizontal & Vertical
Liquid Line (in.) OD	3/8"

ELECTRICAL SCHEDULE

CONNECTION #	CONNECTION DESCRIPTION	FROM	TO
E1-MUA	208/3/60 - FAN MOTOR POWER - 3 WIRES	BUILDING SOURCE	CU-1

THIS DRAWING MUST BE CHECKED, SIGNED AND RETURNED TO THE APPROPRIATE FACTORY.
PLEASE VERIFY THE FOLLOWING:
1. ALL DIMENSIONAL INFORMATION, MOUNTING POSITIONS
2. THE LOCATION AND TYPE OF COOKING EQUIPMENT.
NOTE TO APPROVER:
POSITIONS AND DIMENSIONS FOR THE EQUIPMENT MUST BE SPECIFIED IN ANY OF THE CHANGES OCCUR. A RECALCULATION EXHAUST AIRFLOW MAY BE REQUIRED.
 RETIRE AND RESUBMIT
 APPROVED FOR FABRICATION
 WITH NO CHANGES
 WITH CHANGES AS NOTED
APPROVED BY: _____ DATE: _____



REV.	NO CHANGE	REVISION DESCRIPTION	BY	DATE
1		NO CHANGE	SKM	11/09/21

WEBSITE: www.halton.com
HALTON CO. (USA)
 107 INDUSTRIAL DRIVE
 SOUTH ATTLEBORO, MA 01937
 1-270-237-5800

PROJECT: **SHAKE SHACK 1414 CHAPEL HILL**
 LOCATION: CHAPEL HILL, NC
 DRAWN BY: SKM DATE: 10.26.21
 SCALE: NOT TO SCALE
 CONSULTANT:
Halton

DRAWING TITLE:
MUA-DGX-4600

DRAWING No.:
U21-722

REV. NO.: 1 SHEET NO.: 4 of 6

SHAKE SHACK
 NC - 1414 - CHAPEL HILL
 1800 E FRANKLIN STREET,
 UNIT 40
 CHAPEL HILL, NC 27514

Gensler
 LIC. NO. A40002837 TEL 415.433.3700
 45 FREMONT ST SUITE 1500 FAX 415.836.4599
 SAN FRANCISCO, CA 94105 UNITED STATES


SATELLITE OFFICE: TEL 813.204.9000
 400 N ASHLEY DRIVE SUITE 2400 FAX 813.223.6948
 TAMPA, FL 33602 UNITED STATES

ST ENGINEER
 700 S FLOWER ST SUITE 2100
 LOS ANGELES, CA 90017
 TEL 213.418.0201

Schnackel
 MEFF ENGINEER
 3035 S 72ND ST OMAHA NE 68124
 TEL 402.391.7680

TriMark
 FOODSERVICE CONSULTANT
 505 COLLINS ST PO BOX 3505
 SOUTH ATTLEBORO MA 02703
 TEL 508.399.6000 FAX 508.761.3620

Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AHJ COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



ISSUE FOR CONSTRUCTION

Project Name:
CHAPEL HILL

Project Number:
69.6562.000

Description:
HALTON DRAWINGS

Scale:
1/4" = 1'-0"

M704

RESERVED FOR DOCUMENT BINDING

FAN INFORMATION TABLE

FAN NO	MODEL	QTY	CFM	S.P.	H.P.	VOLTAGE	AMPS	ACCESSORIES
EF-1	VCR-D	1	767	0.67"	1/3	115/1/60	7.2	DISCONNECT NEMA 3 PRE-WIRED, ROOF CURB RCG 22, LABEL UL762, HINGED BASE KIT, KEYWAY GREASE TROUGH, FAN SPEED CONTROLLER
EF-2	VCR-D	1	1708	0.91"	3/4	115/1/60	13.8	DISCONNECT NEMA 3 PRE-WIRED, ROOF CURB RCG 22, LABEL UL762, HINGED BASE KIT, KEYWAY GREASE TROUGH, FAN SPEED CONTROLLER


NOTE:

ON ROOF UNITS, ANCHOR THE FAN SECURELY TO THE CURB. ANCHORING THROUGH THE VERTICAL PORTION OF THE CURB CAP FLANGE IS RECOMMENDED. USE A MINIMUM OF FOUR LAG BOLTS OR OTHER SUITABLE FASTENERS.


NOTE:

ELECTRICAL CONNECTIONS TO BE MADE ON HINGE SIDE OF FAN.

VCR-D




TAG	A	B	C	D	G	T Sq.	Roof Opening Sq.	SHIP'G WEIGHT
EF-1	20 15/16"	34 11/16"	30 1/4"	23 13/16"	2"	24"	19 1/2"	180
EF-2	20 15/16"	34 11/16"	30 1/4"	23 13/16"	2"	24"	19 1/2"	180



CURB

CURB TYPE: RCG



TAG	QTY	DESCRIPTION	MATERIAL GAUGE	A	F Sq.	V Sq.	W Sq.	ROOF OPENING	OPTIONS
EF-1	1	RCG 22	18	1.5"	22.5"	26.5"	15.75"	19.5"	1
EF-2	1	RCG 22	18	1.5"	22.5"	26.5"	15.75"	19.5"	1

THIS DRAWING MUST BE CHECKED, SIGNED AND RETURNED TO THE APPROPRIATE FACTORY. PLEASE VERIFY THE FOLLOWING:

- ALL DIMENSIONAL INFORMATION, MOUNTING POSITIONS
- THE LOCATION AND TYPE OF COOKING EQUIPMENT.

NOTE TO APPROVER: APPROVER'S SIGNATURE, DATE, AND PROJECT NO. MUST BE NOTED IF ANY OF THESE CHANGES OCCUR. A RECALCULATION OF EXHAUST AIRFLOW MAY BE REQUIRED.

REVISE AND RESUBMIT
 APPROVED FOR FABRICATION
 WITH NO CHANGES
 WITH CHANGES AS NOTED

APPROVED BY: _____ DATE: _____

MAIL APPROVED DRAWINGS TO APPROPRIATE FACTORY BELOW:

REV.	NO CHANGE	DESCRIPTION	DATE
1	NO CHANGE	SKM 11.09.21	11.09.21
2			
3			
4			
5			
6			
7			

WEBSITE: www.halton.com

HALTON CO. (CANADA) HALTON CO. (USA)

BRICK FIVE DRIVE
SCOTTSDALE, AZ 85254
1-480-370-5800

BY: SKM DATE: 11.09.21

PROJECT: SHAKE SHACK 1414 CHAPEL HILL

LOCATION: CHAPEL HILL, NC

DRAWN BY: SKM DATE: 10.22.21

SCALE: NOT TO SCALE

CONSULTANT:

Halton

DRAWING TITLE: FAN DETAILS

U21-722

REV. NO.: 1 SHEET NO.: 5 of 6

SHAKE SHACK

NC - 1414 - CHAPEL HILL

1800 E FRANKLIN STREET,
UNIT 40
CHAPEL HILL, NC 27514

Gensler

LIC. NO. A40002837 TEL 415.433.3700
 45 FREMONT ST FAX 415.836.4599
 SUITE 1500
 SAN FRANCISCO, CA 94105
 UNITED STATES

SATELLITE OFFICE: TEL 813.204.9000
 400 N ASHLEY DRIVE FAX 813.223.6948
 SUITE 2400
 TAMPA, FL 33602
 UNITED STATES

Schnackel

MEPF ENGINEER
 3035 S 72ND ST
 OMAHA NE 68124
 TEL 402.391.7680

TriMark

FOODSERVICE CONSULTANT
 505 COLLINS ST
 PO BOX 3505
 SOUTH ATTLEBORO
 MA 02703
 TEL 508.399.6000
 FAX 508.761.3620

Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AHJ COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



Seal / Signature

ISSUE FOR CONSTRUCTION

Project Name
CHAPEL HILL


Project Number
69.6562.000

Description
HALTON DRAWINGS


Scale
1/4" = 1'-0"

M705

RESERVED FOR DOCUMENT BINDING



CONNECTION #	CONNECTION DESCRIPTION	FROM	TO
E1-H	120V, 15AMP - CONTROL PANEL POWER - 3 WIRES	BUILDING SOURCE	HOOD 2-1
E2-H	FIELD CONNECTION FOR HOOD LIGHTS	HOOD 2-1	HOOD 1-1
E3-H	CONNECTION FOR PRESSURE TRANSDUCER - 2 WIRES	CONTROL PANEL	HOOD 1-1
E4-H	CONNECTION FOR TEMP SENSOR - 2 WIRES	CONTROL PANEL	HOOD 1-1
E5-H	FIELD CONNECTION FOR PRESSURE TRANSDUCER - 2 WIRES	CONTROL PANEL	HOOD 1-2
E6-H	FIELD CONNECTION FOR TEMP SENSOR - 2 WIRES	CONTROL PANEL	HOOD 1-2
E7-H	START/STOP TO MUA UNIT - 2 WIRES	CONTROL PANEL	MUA UNIT
E8-H	FIELD CONNECTION TO MUA PRESSURE TRANSDUCER - 2 WIRES	CONTROL PANEL	MUA UNIT
E9-H	FIELD CONNECTION TO MUA TEMP SENSOR - 2 WIRES	CONTROL PANEL	MUA UNIT
E10-H	FIELD CONNECTION TO MUA TEMP SENSOR - 2 WIRES	CONTROL PANEL	MUA UNIT
E11-H	208V/3PH - MOTOR STARTER POWER	BUILDING SOURCE	CONTROL PANEL
E12-H	FIELD CONNECTION TO NORMALLY OPEN MICRO-SWITCH	ANSUL SYSTEM	CONTROL PANEL
E13-H	FIELD CONNECTION TO NORMALLY CLOSED MICRO-SWITCH	ANSUL SYSTEM	CONTROL PANEL
E14-H	FIELD CONNECTION FOR FAN SWITCH - 3 WIRES 120V	HOOD 1-1	CONTROL PANEL




THIS DRAWING MUST BE CHECKED, SIGNED AND RETURNED TO THE APPROPRIATE FACTORY. PLEASE VERIFY THE FOLLOWING:

1. ALL DIMENSIONAL INFORMATION, MOUNTING POSITIONS
2. THE LOCATION AND TYPE OF COOKING EQUIPMENT.

NOTE TO APPROVER: THIS DRAWING IS AN INSTRUMENT OF SERVICE. ANY CHANGES TO THE DRAWING MUST BE APPROVED BY HALTON. ANY CHANGES TO THE DRAWING MUST BE APPROVED BY HALTON. ANY CHANGES TO THE DRAWING MUST BE APPROVED BY HALTON. ANY CHANGES TO THE DRAWING MUST BE APPROVED BY HALTON.

APPROVED FOR FABRICATION: WITH CHANGES AS NOTED

APPROVED BY: _____ DATE: _____



REV.	DESCRIPTION	DATE	BY	SKM
1	NO CHANGE	11.08.21		
2				
3				
4				
5				
6				
7				
8				
9				
10				

PROJECT: SHAKE SHACK 1414 CHAPEL HILL
 LOCATION: CHAPEL HILL, NC
 DRAWN BY: SKM
 DATE: 10.22.21
 SCALE: NOT TO SCALE
 CONSULTANT: Halton

DRAWING TITLE: DEMAND CONTROL DETAILS
 DRAWING NO.: U21-722
 REV. NO.: 1 SHEET NO.: 6 of 6

SHAKE SHACK
 NC - 1414 - CHAPEL HILL
 1800 E FRANKLIN STREET,
 UNIT 40
 CHAPEL HILL, NC 27514


Gensler
 LIC. NO. A40002837 TEL 415.433.3700
 45 FREMONT ST SUITE 1500 FAX 415.836.4599
 SAN FRANCISCO, CA 94105
 UNITED STATES

SATELLITE OFFICE: TEL 813.204.9000
 400 N ASHLEY DRIVE FAX 813.223.6948
 SUITE 2400
 TAMPA, FL 33602
 UNITED STATES

Schnackel
 MEPP ENGINEER
 3035 S 72ND ST
 OMAHA NE 68124
 TEL 402.391.7680

TriMark
 FOODSERVICE CONSULTANT
 505 COLLINS ST
 PO BOX 3505
 SOUTH ATTLEBORO
 MA 02703
 TEL 508.399.6000
 FAX 508.761.3620

Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AHJ COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



ISSUE FOR CONSTRUCTION

Project Name: CHAPEL HILL
 Project Number: 69.6562.000
 Description: HALTON DRAWINGS

Scale: 1/4" = 1'-0"

M706



ST ENGINEER
700 S FLOWER ST
SUITE 2100
LOS ANGELES, CA 90017
TEL 213.418.0201



MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680



FOODSERVICE CONSULTANT
505 COLLINS ST
PO BOX 3505
SOUTH ATL BORO
MA 02703
TEL 508.399.6000
FAX 508.761.3620

Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AHJ COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION



Seal / Signature

ISSUE FOR CONSTRUCTION

Project Name
CHAPEL HILL


Project Number
69.6562.000

Description
CAPTIVEAIRE DRAWINGS

Scale
1/4" = 1'-0"

M801

REVISIONS	
DESCRIPTION	DATE



Shake Shack-1414-Chapel Hill, NC
1800 E Franklin St,
Chapel Hill, NC, 27514

DATE: 7/21/2022
DWG.#: 5533853
DRAWN BY: Joe Shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING

SHEET NO.
1

FOR QUESTIONS, CALL THE
Eastern PA Mechanical
REGION 108
PHONE: (267) 504-4126
EMAIL: reg108@captiveaire.com

DOAS/RTU FAN SCHEDULE - JOB#5533853

FAN UNIT NO	TAG	QTY	DOAS/RTU MODEL #	FAN INFORMATION						ELECTRICAL INFORMATION						COOLING INFORMATION						REHEAT INFORMATION				GAS HEAT INFORMATION				NOTES						
				MANUFACTURER	BLOWER	RETURN AIR CFM	MAX OUTSIDE AIR CFM	TOTAL CFM	WEIGHT (LBS)	ESP	HP	Ø	VOLT	MCA	MDCP	OUTSIDE AIR DB	MIXED AIR DB	LEAVING AIR DB	W/B	W/B	DP	TOTAL	SENS.	IEER	ISMRE	DISCHARGE DB	W/B	DESIRED	MAX		MOISTURE REMOVAL RATE	GAS TYPE	INPUT BTUS	OUTPUT BTUS	TEMP RISE	
1	RTU-2	1	CASRTU2-1250-18-8T-DOAS	CAPTIVEAIRE	18P-2	2485	515	3000	1967	0.700	5.00	3	208	48.8A	60A	95.0°F	78.0°F	79.2°F	66.7°F	56.1°F	55.8°F	55.7°F	101.8 MBH	75.4 MBH	20.2	9.8	73.4°F	62.6°F	57.3 MBH	60 MBH	23.1 LBS/HR	NATURAL	227160	184000	53°F	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18



- NOTES:**
1. INVERTER SCROLL COMPRESSOR WITH INTEGRATED OIL SENSOR. DIGITAL OR STAGED SCROLL NOT AN APPROVED EQUAL
 2. DIRECT DRIVE PLENUM BLOWER. BELT DRIVEN BLOWERS ARE NOT ACCEPTABLE
 3. INTEGRATED MONITORING VIA CELLULAR CONNECTION BY MANUFACTURER
 4. REFRIGERATION PRESSURE MONITORING ON HIGH AND LOW PRESSURE SIDE OF SYSTEM INCLUDED THROUGH DIGITAL INTERFACE
 5. EC MOTOR CONDENSING FANS
 6. ELECTRONIC EXPANSION VALVE. TXV NOT ACCEPTABLE
 7. SUCTION LINE ACCUMULATOR
 8. FACTORY COMMISSIONING WITH 5 YEAR PARTS WARRANTY, 25 YEAR WARRANTY ON STAINLESS STEEL HEAT EXCHANGER
 9. AVERAGING INTAKE, EVAP AND DISCHARGE TEMPERATURE SENSORS (DISCHARGE SENSOR TO BE FACTORY MOUNTED WITHIN UNIT)
 10. 2" EXTERIOR DUAL-WALL CONSTRUCTION W/ R-13 INSULATION-MINIMUM 20GA EXTERIOR W/ 14GA BASE
 11. 80% EFFICIENT FURNACE, WITH MODULATING INDUCER TO MAINTAIN CONSTANT COMBUSTION EFFICIENCY ACROSS FIRING RANGE. 6:1 TURNDOWN WITH NG AND 5:1 TURNDOWN WITH LP
 12. SUPPLY CFM MONITORING INTEGRAL TO UNIT WITH CFM MEASUREMENT INCLUDED THROUGH DIGITAL INTERFACE
 13. FULLY MODULATING HOT GAS REHEAT
 14. 15 DEGREE LOW AMBIENT OPERATION
 15. HAIL GUARD FOR CONDENSING COIL
 16. RTU ECONDMIZER WITH DIFFERENTIAL ENTHALPY CONTROL
 17. BAROMETRIC RELIEF DAMPER










FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	RTU-2	1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE
		1	RTU TOTAL CFM MONITORING
		1	SHIP LOOSE GAS STRAINER 3/4"
		1	SINGLE POINT ELECTRICAL CONNECTION FOR RTU. 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #28, #47, "MA", OR "E2" PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE
		1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
		1	LOW AMBIENT COOLING OPERATION - DOWN TO 15F AMBIENT
		1	RTU2 DOWN DISCHARGE
		1	2" MERV 8 FILTERS FOR RTU2 (QTY. 4)
		1	OVERHEAT STAT
		1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
		1	8 TON MODULATING COOLING OPTION, 208/230V. R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS
		1	8 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL
		1	REMOTE TEMPERATURE AND HUMIDITY SPACE SENSOR
		1	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS
		1	OCCUPIED SCHEDULING
		1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI
		1	RTU2 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX
		1	RTU ECONDMIZER - DIFFERENTIAL ENTHALPY CONTROL
		1	RTU2 ECONDMIZER BAROMETRIC RELIEF
		1	RTU2 HAIL GUARD
		1	RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI
		1	RTU2 DOWN RETURN
		1	VAV PACKAGE W/ MANUAL/DDC CONTROL (S71 VFD INCLUDED)
		1	LOAD REACTOR MOUNTED IN FAN
1	FUSED DISCONNECT SWITCH FOR RTU2		
1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS)		

CURB ASSEMBLIES

NO	DN FAN	WEIGHT	ITEM	SIZE
1		250 LBS	RTU ADAPTER	FROM 67.625" X 102.875" TO 49.500" X 75.000" X 20.000"H.





FAN #1 CASRTU2-I,250-18-8T-DOAS - HEATER (RTU-2)

NOTES:

- DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
- DENOTES CORNER WEIGHT.

REVISIONS

NO.	DESCRIPTION	DATE

CAPTIVE

Eastern PA Mechanical

www.captiveaire.com

PO Box 2520, 1 Union Ave, Babo Compyd PA, 19004 PHONE: (267) 504-4126 EMAIL: reg106@captiveaire.com

Shake Shack-1414-Chapel Hill, NC
1800 E Franklin St,
Chapel Hill, NC, 27514

DATE: 7/21/2022

DWG.#: 5533853

DRAWN BY: Joe Shilba

SCALE: 3/4" = 1'-0"

MASTER DRAWING

SHEET NO. 2

SHAKE SHACK

NC - 1414 - CHAPEL HILL

1800 E FRANKLIN STREET,
UNIT 40
CHAPEL HILL, NC 27514

Gensler

LIC. NO. AA0002837 TEL 415.433.3700
45 FREMONT ST. FAX 415.836.4599
SUITE 1500
SAN FRANCISCO, CA 94105
UNITED STATES

SATELLITE OFFICE: TEL 813.204.9000
400 N ASHLEY DRIVE FAX 813.223.6948
SUITE 0400
TAMPA, FL 33602
UNITED STATES

Schnackel

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

TriMark
Foodservice Equipment, Supplies and Design

FOODSERVICE CONSULTANT
505 COLLINS ST
PO BOX 3505
SOUTH ATRI LEBORO
MA 02703
TEL 508.399.6000
FAX 508.761.3620

Date	Description
03/14/2022	PERMIT & BID
06/21/2022	AHJ COMMENTS
07/22/2022	ISSUE FOR CONSTRUCTION

Seal / Signature

North Carolinian Seal
SEAL 024849
Date: 07/22/22
COM # C-3262

ISSUE FOR CONSTRUCTION

Project Name
CHAPEL HILL

Project Number
69.6562.000

Description
CAPTIVEAIRE DRAWINGS

Scale
1/4" = 1'-0"

M802

© 2021 Gensler