



MEAL DELIVERY CANOPY.  
SEE ARCHITECTURAL.

MOUNT AC#1 MAIN TRUNK  
LINE AS TIGHT AS  
POSSIBLE TO STRUCTURE.

MOUNT AIR DOOR IN CEILING  
CENTERED ON DRIVE THRU  
DOOR. AIR DOOR TO BE  
ALIGNED WITH WALL FINISH.

GAS-FIRED INFRARED HEATER, MC TO ATTACH TO MOUNTING  
PLATE ON CANOPY. MOUNTING PLATE IS PROVIDED AND  
INSTALLED BY THE CANOPY MFR. TYPICAL AT ALL IR HEATERS.  
MECHANICAL CONTRACTOR TO PROVIDE SS HEAT SHIELD.  
HEAT SHIELD TO SET ON TOP OF IR HEATER ON THE FACTORY  
HEATER MOUNTING STUDS. SHIELD TO BE ORIENTED SO  
EDGE IS TURNED DOWN. TYPICAL AT ALL IR HEATERS.

SEAL PENETRATIONS IN SMOKE  
DRAFT CURTAIN AIR TIGHT. SEE  
ARCH PLANS FOR CONSTRUCTION.

LOCATE BOTTOM OF HEATER FRAME 12" AFF.

WATER HEATER AND  
FLUE BY PLUMBER.

C

D

E

4

3

2