


ND-2 HANGING ANGLE DETAIL

1/2" DIA. ALL THREAD ROD CONNECTED TO ROOF JOIST THROUGH ANOTHER HANGING ANGLE



*ROD AND NUTS TO BE SUPPLIED BY INSTALLING CONTRACTOR HANGING ANGLE IS PRE-FINISHED AT FACTORY

HANGING ANGLE LOCATIONS

HOOD STYLE	DIM FROM REAR	DIM FROM (24" H)	DIM FROM FRONT (30" H)
CANOPY ND2	4.166"	2.246"	2.246"
ND2-PSP-F	4.166"	2.246"	2.246"
BACKSHELF BD-2	4.166"	2.246"	-
VHB/VHB-G	36"x36"	42"x42"	48"x48"
FRONT/BACK DIMS BY SIZE	2.246"	2.246"	2.246"


CALCULATIONS UTILIZED

EXHAUST CFM=LENGTH OF HOOD X CFM/LIN.FT. (LOAD)
 SUPPLY CFM=EXHAUST CFM X PERCENTAGE REQUIRED
 TOTAL DUCT AREA=144 X CFM (FPM)
 DUCT LENGTH= TOTAL DUCT AREA / DUCT DEPTH

*CAPTIVE-AIRE DUCT CONNECTION SIZES ARE CALCULATED USING AN EXHAUST VELOCITY OF 1500-1800 FPM AND A SUPPLY VELOCITY OF 300-400 FPM

BUILDING CODES

CAPTIVE-AIRE HOODS ARE BUILT IN COMPLIANCE WITH:



CLEARANCE TO COMBUSTIBLES

CAPTIVE-AIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:

MATERIAL	CLEARANCE REDUCTION SYSTEM
NON-COMBUSTIBLE	NONE REQUIRED
LIMITED-COMBUSTIBLE	3" UNINSULATED STANDOFF
COMBUSTIBLE	1" INSULATED STANDOFF

GENERAL NOTES

INSTALLATION

- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
- ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
- HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
- ALL CONNECTIONS FROM CAPTIVE-AIRE DUCT PER MECHANICAL CONTRACTOR'S PLANS.
- COOKING EQUIPMENT TO SHUTOFF IN EVENT OF FIRE.
- EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
- ALL LIGHTS FIXTURE SHOWN INSTALLED BY CAPTIVE-AIRE ARE FACTORY PREWIRED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES BY ELECTRICAL CONTRACTORS.
- LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
- SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
- INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTEGRATION, AND ADMINISTRATION OF CODE REQUIREMENTS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.



BALANCE

- KITCHEN HOODS MUST BE BALANCED WITH KITCHEN.
- KITCHEN SHALL BE NEGATIVE WITH RESPECT TO DRINK AREA.
- RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.

ADDITIONAL

- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
- SIGNED AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE RECEIVED BY THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

FILTER DETAIL



CaptiveAire Captrate Solo Filter
 ETL Listed Grease Extracting Filter
 Made From 430 Stainless Steel

HOOD INFORMATION - JOB#5254570

HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST PLENUM RISES					HOOD CONSTRUCTION	HOOD CONFIG	PATENT NUMBERS
										WIDTH	LENG	HEIGHT	DIA	CFM			
1	GRIDDLE HD	5424 ND-2	CAPTIVEAIRE	8' 0"	450 DEG	I	MEDIUM	200	1600	4"	14"	1600	1497	-0.734"	430 SS WHERE EXPOSED	ALONE FRONT	EXHAUST HOODS ND-2/BD-2/SND-2 (CANADA) - CA PATENT 2520435 C.
2	FRY HD	5424 ND-2	CAPTIVEAIRE	5' 0"	450 DEG	I	MEDIUM	155	775	4"	10"	775	1421	-0.436"	430 SS WHERE EXPOSED	ALONE ALONE	

HOOD INFORMATION

HOOD NO	TAG	TYPE	QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE	UTILITY CABINET(S)		ELECTRICAL	SWITCHES	FIRE SYSTEM	HOOD HANGING WEIGHT
												PIPE	SIZE				
1	GRIDDLE HD	CAPTRATE SOLO FILTER	5	16"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO	LEFT	12"x54"x24"			DCV-2011	1 LIGHT 1 FAN	NO	510 LBS
2	FRY HD	CAPTRATE SOLO FILTER	3	16"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO							NO	339 LBS

HOOD OPTIONS

HOOD NO	TAG	FIELD WRAPPER	18.00" HIGH	FRONT, LEFT, RIGHT.	OPTION
1	GRIDDLE HD	RIGHT QUARTER END PANEL	23" TOP WIDTH, 0" BOTTOM WIDTH,	23" HIGH	430 SS.
		LEFT QUARTER END PANEL	23" TOP WIDTH, 0" BOTTOM WIDTH,	23" HIGH	430 SS.
2	FRY HD	LEFT QUARTER END PANEL	23" TOP WIDTH, 0" BOTTOM WIDTH,	23" HIGH	430 SS.
		RIGHT VERTICAL END PANEL	27" TOP WIDTH, 21" BOTTOM WIDTH,	80" HIGH	INSULATED 430 SS.

SPECIFICATION: CAPTRATE GREASE-STOP SOLO FILTER

THE CAPTRATE GREASE-STOP SOLO FILTER IS A SINGLE-STAGE FILTER FEATURING A UNIQUE S-BAFFLE DESIGN IN CONJUNCTION WITH A SLOTTED REAR BAFFLE DESIGN, TO DELIVER EXCEPTIONAL FILTRATION EFFICIENCY.


FILTER IS STAINLESS STEEL CONSTRUCTION, AND SIZED TO FIT INTO STANDARD 2-INCH DEEP HOOD CHANNEL(S).

UNITS SHALL INCLUDE STAINLESS STEEL HANDLES AND A FASTENING DEVICE TO SECURE THE TWO COMPONENTS WHEN ASSEMBLED.


GREASE EXTRACTION EFFICIENCY PERFORMANCE SHALL REMOVE AT LEAST 70% OF GREASE PARTICLES FIVE MICRONS IN SIZE, AND 80% GREASE PARTICLES SEVEN MICRONS IN SIZE AND LARGER, WITH A CORRESPONDING PRESSURE DROP NOT TO EXCEED 10 INCHES OF WATER GAUGE.

THE CAPTRATE GREASE-STOP SOLO WAS TESTED TO ASTM STANDARD ASTM F2519-05, MANUFACTURER APPROVED FOR USE IN SOLID FUEL APPLICATIONS AS A SPARK ARRESTER.


EFFICIENCY VS. PARTICLE DIAMETER




PRESSURE DROP VS. FLOW RATE




CAPTIVE FILTERS ARE BUILT IN COMPLIANCE WITH:




PLAN VIEW - HOOD #1 (GRIDDLE HD)
 8' 0.00" LONG 5424ND-2



PLAN VIEW - HOOD #2 (FRY HD)
 5' 0.00" LONG 5424ND-2



SECTION VIEW - MODEL 5424ND-2
 HOOD - #1 (GRIDDLE HD)



SECTION VIEW - MODEL 5424ND-2
 HOOD - #2 (FRY HD)

FOR QUESTIONS, CALL THE:
 KANSAS CITY REGIONAL OFFICE
 1126 SWIFT STREET, KANSAS CITY, MO 64116
 PHONE: (816) 221-8575
 FAX: (816) 221-8311

CUSTOMER APPROVAL TO MANUFACTURE:

Approved as Noted

Approved with NO Exception Taken

Revise and Resubmit

SIGNATURE _____ Date _____

Your Title _____


***** NOTE *****
 ALL WALLS AND STRUCTURES THAT COME WITHIN 18" OF HOOD MUST BE METAL STUDS AND SHEETROCK. WOOD STUDS OR ANY OTHER COMBUSTIBLE MATERIAL WITHIN 18" OF HOOD NO ALLOWED.

***** NOTE *****
 HOOD MANUFACTURER RECOMMENDS NO RETURNS OR 4-WAY DIFFUSERS WITHIN 10 FEET OF HOOD IN ALL DIRECTION.


***** NOTE *****
 MAKEUP AIR SHALL BE DELIVERED INTO SPACE IN MANNER THAT WILL NOT DISRUPT HOODS ABILITY TO CAPTURE AND CONTAIN.

REVISIONS

DESCRIPTION	DATE:



www.captiveaire.com
 www.captiveaire.com



HBT Foodservice

104 W 8th St Suite 204, Kansas City, MO. 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: reg9@capitveaire.com

Freddy's - Jasper, AL
 JASPER, AL, 35501

DATE: 8/19/2022

DWG.#:
 5254570

DRAWN BY:
 michael.co

SCALE:
 1/2" = 1'-0"

MASTER DRAWING

SHEET NO.
 1



Highway 78 Jasper, AL 35501

SEAL



1721 4th AVENUE NORTH SUITE 101 BIRMINGHAM, AL 35203 www.studio2hd.com

OFFICE: 205-264-9988 FAX: 205-264-9992

NOT FOR CONSTRUCTION

RELEASED FOR CONSTRUCTION

DATE: 13 MAY 2022

DRAWN BY: TLM

REVIEWED BY: KRM

REUSE OF DOCUMENTS

THIS DOCUMENT, THE IDEAS AND DESIGNS INCORPORATED HEREIN, IS AN INSTRUMENT OF STUDIO 2H DESIGN, LLC AND MUST NOT BE USED IN WHOLE OR IN PART...

REVISIONS

Table with 3 columns: NO, DATE, Description. Row 1: 1, 09/15/22, OWNER REQUESTED REVISIONS

ISSUED for CONSTRUCTION

SHEET TITLE HVAC SCHEDULES & SPECIFICATIONS

DRAWING NUMBER

M1.0

PROJECT NUMBER

202119

PACKAGED ROOFTOP OUTSIDE AIR UNIT SCHEDULE

Table with columns: SYMBOL, MANUFACTURER/MODEL NO., SERVICE, SUPPLY CFM, O.A. CFM, ESP, SUPPLY FAN, COOLING CAPACITY, HOT GAS REHEAT, NAT. GAS HEAT, FILTERS, ELECTRICAL, NOTES

NOTES:

- 1. INVERTER SCROLL COMPRESSOR WITH INTEGRATED OIL SENSOR. DIGITAL OR STAGED SCROLL NOT AN APPROVED EQUAL... 2. DIRECT DRIVE PLENUM BLOWER. BELT DRIVEN BLOWERS ARE NOT ACCEPTABLE...

NOTE: HVAC ROOFTOP UNITS AND CURBS ARE FURNISHED BY OWNER, INSTALLED BY CONTRACTOR.

ADDITIONAL NOTES:

CONTRACTOR SHALL NOT ORDER ANY EQUIPMENT UNTIL DRAWINGS AND EQUIPMENT SUBMITTALS HAVE BEEN REVIEWED AND FINAL APPROVAL HAS BEEN OBTAINED FROM THE HEALTH DEPARTMENT AND LOCAL AUTHORITY HAVING REVIEW/APPROVAL RESPONSIBILITY FOR THIS PROJECT.

ALL WORK SHALL BE INSTALLED IN ACCORDANCE WITH THE DESIGN DRAWINGS. ANY FIELD CHANGES MUST BE APPROVED BY THE ARCHITECT OR ENGINEER PRIOR TO INSTALLATION. CONTRACTOR SHALL PAY IN ADVANCE FOR ALL COSTS ASSOCIATED WITH DRAWING REVISIONS REQUIRED BY FIELD CHANGES MADE WITHOUT PRIOR APPROVAL BY THE ARCHITECT OR ENGINEER.

HVAC TEST & BALANCE AND COMMISSIONING:

THE OWNER WILL HIRE AND PAY NATIONAL TRUE-TEST, INC. TO FIELD VERIFY THAT THE HVAC SYSTEMS, DUCTS, CONTROLS, HOODS AND VENTILATION SYSTEMS, ETC. HAVE BEEN INSTALLED, PROGRAMMED, BALANCED AND ARE FULLY OPERATIONAL AS DESIGNED AND SPECIFIED.

NATIONAL TRUE-TEST, INC. www.NationalTrue-Test.com, (205)681-9050 5757 Carrington Lake Parkway, Trussville, AL 35173 Billy C. Bivens, III President

DISCREPANCIES WILL BE CORRECTED BY THE CONTRACTOR AT THEIR EXPENSE.

FURTHER WORK BY NATIONAL TRUE-TEST (OR ANY COMMISSIONING COMPANY OR AGENT) REQUIRED TO TROUBLE SHOOT OR VERIFY THAT THE SYSTEMS ARE FULLY OPERATIONAL &/OR THE DISCREPANCIES HAVE BEEN PROPERLY CORRECTED WILL BE PAID FOR BY THE CONTRACTOR.

HVAC SPECIFICATIONS

- 1. Contractor shall visit the site and verify existing conditions prior to bidding or beginning work. 2. Obtain permits and notify authorities for inspections. 3. Perform all work in accordance with: A. International Mechanical Code - 2015 B. International Energy Conservation Code - 2015 C. National Fire Protection Association (NFPA) Applicable Sections D. Sheet Metal and Air Conditioning Contractor's National Association (SMACNA) E. Manufacturer's Standardization Society of the Valve and Fittings Industry, Inc. (MSS) F. Owner's Criteria for Mechanical and Plumbing Work

- 19. Dampers: A. Fire Dampers (1 1/2 hour): U.L. 555 labeled, Style B or C. Ruskin DIBD2 or approved equal. B. Single Blade Volume Dampers: 22 gauge galvanized steel (blade and frame), maximum 12" high blade. C. Multi-Blade Volume Dampers: 16 gauge galvanized steel (blades and frame), maximum 8" wide blades. D. Motorized Control Dampers: Heavy gauge extruded aluminum construction with max. 6" wide airfoil blades. 20. Ceiling Air Devices: Diffusers, Grilles and Registers are identified on the plan by type, size and air flow quantities (CFM) inside the octagonal symbols.

- 14. Low Pressure Ductwork: A. Low pressure ductwork shall be Galvanized Steel Sheetmetal fabricated and installed in accordance with SMACNA HVAC Duct Construction Standards, Metal and Flexible and TMA Duct Construction Manual. B. Ducts 18 inches and larger on any side shall be stiffened by beading on min. 12 inch centers or shall be cross-broken. C. Make rectangular branch connections using 45° fitting with volume damper per detail. D. Provide conical spin-in fittings with balancing dampers at each diffuser run-out unless shown otherwise. E. Flexible duct connectors on supply run-outs shall be U.L. 181 listed as Class 1 Air Duct. Lengths shall not exceed 6 ft. and bends shall not exceed 45°. Flexmaster Type 3 or equal by Thermatec. F. Seal all transverse and longitudinal seams with Duct Sealer. G. Provide transitions from run-out size to air device neck size where required. H. Provide duct access doors for each fire damper or other duct mounted equipment requiring service access. Access doors shall be double-latch with 3/4"x1/8" neoprene seals at connections to duct and at door-to-frame connection. I. Dimensions shown for ductwork are clear inside dimensions. Where lined ductwork is used (Return Air only) increase the dimensions of duct to allow for insulation as necessary. J. Provide flexible connectors between ductwork and motorized equipment for vibration isolation.

- 21. Kitchen Exhaust Hoods: A. Kitchen hoods shall be constructed entirely of 18 gauge, type 304 stainless steel with welded joints and seams to make liquid tight. B. Vapor-Proof U.L. Listed marine lights on max. 3 ft. centers shall be factory wired to a junction box on top of the hood in accordance with N.E.C. requirements. C. A fully recessed control panel on the face of the hood shall control hood lights, exhaust fan, and makeup air unit (where applicable). D. Hood shall be equipped with factory installed Ansul R102 wet chemical fire suppression system, U.L. approved for installation over food service equipment. E. Hood assembly shall be fabricated in accordance with NFPA 96, shall be U.L. listed and NSF approved. 22. Mount thermostats 48" AFF and room temperature sensors 72" AFF. Coordinate exact location with Architect. Run wiring in conduit from the wall box to above the ceiling and where exposed. Use only plenum rated wiring. 23. Cooling Coil Condensate Drain Piping: Type L hard drawn copper tubing with solder joints or Sch. 40 PVC. 24. Controls: A. All control wiring shall be plenum rated cable. Run in conduit from wall mounted devices to above ceiling and where exposed. B. Provide 7-day programmable thermostat with remote room sensor to control each AC unit. C. Provide Duct Smoke Detectors for each unit for automatic shutdown. D. AC unit supply fans shall run continuously during occupied time period and intermittently during unoccupied times. Motorized O.A. dampers shall close when supply fan is "OFF". E. Interlock kitchen hood exhaust fans and DOAS-1 with hood mounted switches. Upon activation of hood fire suppression system the hood exhaust fans shall continue to run. Refer to Captiveaire drawings for detailed hood controls sequence. F. Economizer controllers shall modulate O.A. damper and Return air damper for each unit inversely between min. set position and 100% O.A. position upon a call for cooling when the enthalpy of the outside air is lower than the return air. Economizer mode shall only be available while hoods are in operation (occupied time periods). G. Dehumidification cycle including hot gas reheat coil shall be activated when the space relative humidity rises above setpoint (50% RH adj.). Unit shall operate in full cooling coil as required to maintain space relative humidity at setpoint, and hot gas reheat coil shall activate to maintain space temperature at setpoint. H. Toilet Exhaust Controls: 1. DOAS-1 a. Occupied Time Periods: Interlock unit controls with Hood Switch to operate at 100% O.A. setting when hood exhaust fans are "ON". When hood exhaust fans are "OFF", the O.A. damper shall adjust to min. set position to maintain required ventilation rate. Reference Captiveaire drawings for more detailed hood exhaust fan controls sequence. b. Unoccupied Time Periods: Motorized O.A. damper shall remain closed during unoccupied time periods. 2. DOAS-2 a. Occupied Time Periods: CO2 sensor with integral digital controller shall modulate O.A. damper between min. set position and max. set position to maintain space CO2 level below setpoint (1000 ppm). b. Unoccupied Time Periods: Motorized O.A. damper shall remain closed during unoccupied time periods. H. Toilet Exhaust Fans EF-1 & 2 shall each be controlled by a room motion sensor. Upon activation of sensor fan shall run for period of 30 minutes (adjustable).

KITCHEN EXHAUST HOOD SCHEDULE

Table with columns: SYMBOL, MANUFACTURER/MODEL NO., SERVICE, EXHAUST AIR, MAKEUP AIR, TYPE, CANOPY DIMENSIONS (IN.), ELECTRICAL, NOTES

COORDINATE EXACT HOOD DIMENSIONS WITH ARCHITECTURAL DRAWINGS. HOODS SHALL OVERHANG COOKING EQUIPMENT 6 INCHES ON ALL OPEN SIDES AND SHALL EXTEND FROM 6"-4" AFF TO 2" ABOVE CEILING. PROVIDE SS CLOSURE PANELS AS REQUIRED. KITCHEN HOODS SHALL BE FURNISHED BY OWNER AND INSTALLED BY G.C. AIR FLOW QUANTITIES MUST BE EQUAL TO BASIS OF DESIGN.

EXHAUST FAN SCHEDULE

Table with columns: SYMBOL, MANUFACTURER/MODEL NO., CFM, SP (IN. W.C.), RPM, MAX. SONES, LOCATION, TYPE, DRIVE, VIBRATION ISOLATION, ELECTRICAL, NOTES

APPROVED MANUFACTURERS FOR EF-1 & 2 ARE GREENHECK, BREIDERT, COOK, AND TWIN CITY. KEF-1 & 2 FURNISHED BY HOOD SUPPLIER, INSTALLED BY G.C. ROOF CURBS FOR HOOD EXHAUST FANS KEF-1 & KEF-2 SHALL BE SIZED TO ACCOMMODATE TWO LAYERS OF FIRE RATED DUCT WRAP.

AIR DEVICE SCHEDULE

Table with columns: SYMBOL, MANUFACTURER/MODEL NO., TYPE, BORDER, CONSTRUCTION, SIZE (IN.), FINISH, EQUALIZING GRID, ACCESSORIES, NOTES

APPROVED MANUFACTURERS ARE TITUS, TUTTLE & BAILEY, KRUEGER, PRICE AND METALAIR

FLY FAN SCHEDULE

Table with columns: SYMBOL, MANUFACTURER/MODEL NO., AIR FLOW, LENGTH (IN.), MAX. SOUND LEVEL (DB), LOCATION, DRIVE, VIBRATION ISOLATION, ELECTRICAL, NOTES


THERMOSTAT SCHEDULE

Table with columns: MARK, SERVES, SUPPLY FAN, COOLING SETPOINT, HEATING SETPOINT, HUMIDITY SETPOINT

IT IS THE MECHANICAL CONTRACTOR'S RESPONSIBILITY TO PROGRAM ALL THERMOSTATS AND CONTROLLERS TO THIS SCHEDULE AND THESE SETPOINTS AND TO VERIFY PROPER OPERATION.


























MICHAELS ENGINEERING, LLC MECHANICAL CONSULTING & DESIGN 3305 PARK LANE DRIVE • BIRMINGHAM, ALABAMA 35226 (205)978-1332 • www.michaelsengineering.net



HVAC FLOOR PLAN
1/4" = 1'-0"
Project North

HVAC LEGEND

-  14x10 RECTANGULAR DUCTWORK (14" SIDE DRAWN)
-  12" RIGID, ROUND DUCTWORK (12" DIAMETER)
-  FLEXIBLE DUCTWORK
-  EXISTING DUCTWORK
-  MANUAL VOLUME DAMPER
-  FIRE DAMPER AND ACCESS DOOR
-  45° BRANCH CONNECTION WITH VOLUME DAMPER
-  CONICAL SPIN-IN FITTING WITH BUTTERFLY DAMPER
-  SQUARE-TO-ROUND DUCT TRANSITION
-  DUCT TRANSITION (30" MAXIMUM)
-  RECTANGULAR 90° ELBOW WITH TURNING VANES
-  ROUND 90° DUCT ELBOW
-  REFRIGERANT PIPING (SUCTION AND LIQUID LINE)
-  CONDENSATE DRAIN PIPING
-  EXIST. PIPING TO BE REMOVED
-  BALL VALVE
-  GATE VALVE
-  REMOTE PROGRAMMABLE ROOM THERMOSTAT
-  ROOM TEMPERATURE SENSOR
-  DIGITAL CO2 SENSOR
-  DIGITAL ROOM HUMIDITY SENSOR
-  DUCT SMOKE DETECTOR
-  EXISTING

TAGGED DRAWING NOTES


- ① 10" STAINLESS STEEL GREASE EXHAUST DUCT PROVIDED BY KITCHEN SUPPLIER FROM KEF-2 DOWN TO HOOD EXHAUST CONNECTION. DUCT SHALL BE WRAPPED WITH 2 HR. FIRE RATED DUCT WRAP FROM HOOD CONNECTION UP TO ROOF PENETRATION. SEE EXHAUST FAN DETAIL. TRANSITION AS REQUIRED. (775 CFM)
- ② -
- ③ 14" STAINLESS STEEL GREASE EXHAUST DUCT PROVIDED BY KITCHEN SUPPLIER FROM KEF-1 DOWN TO HOOD EXHAUST CONNECTION. DUCT SHALL BE WRAPPED WITH 2 HR. FIRE RATED DUCT WRAP FROM HOOD CONNECTION UP TO ROOF PENETRATION. SEE EXHAUST FAN DETAIL. TRANSITION AS REQUIRED. (1600 CFM)
- ④ -
- ⑤ -
- ⑥ COORDINATE EXACT LOCATIONS OF ROOFTOP UNITS AND MAKEUP AIR UNIT WITH ROOF STRUCTURE. SEE STRUCTURAL DRAWINGS. OFFSET AND TRANSITION DUCTS AS REQUIRED TO PASS BETWEEN ROOF TRUSSES/JOISTS AND CONNECT TO RTU DUCT CONNECTIONS. TRANSITION WITHIN ROOF CURB AS NEEDED. (TYP.)
- ⑦ RUN RETURN DUCT BETWEEN ROOF TRUSSES. PROVIDE OPENING IN TOP OF DUCT. (SEE PLAN FOR SIZES).
- ⑧ 18x18 SUPPLY DUCT UP BETWEEN TRUSSES. TRANSITION INSIDE CURB TO UNIT CONNECTION SIZES.

GENERAL NOTES

THESE NOTES APPLY TO ALL HVAC DRAWINGS

1. DRAWINGS ARE DIAGRAMMATIC ONLY AND DO NOT SHOW ALL DETAILS, OFFSETS NOR CHANGES IN ELEVATIONS NECESSARY FOR COMPLETE INSTALLATION.
2. PROVIDE NECESSARY OFFSETS IN PIPING AND DUCTWORK AS REQUIRED TO ACCOMMODATE WORK. CONTRACTOR SHALL COORDINATE WITH OTHER TRADES AND ALLOW FOR ANY CONFLICTS ENCOUNTERED.
3. DUCT SIZES SHOWN ARE CLEAR INSIDE DIMENSIONS. INCREASE OVERALL DIMENSIONS AS REQUIRED TO ALLOW FOR INSULATION THICKNESS.
4. CONDENSATE DRAIN LINES AND AUXILIARY CONDENSATE DRAIN LINES SHALL BE 1" SIZE UNLESS NOTED OTHERWISE. DISCHARGE INTO ROOF DRAIN OR GUTTER.
5. FLEXIBLE DUCT RUNOUTS SHALL NOT EXCEED 6 FT. IN LENGTH. BENDS SHALL NOT EXCEED 45°.
6. TRANSITION TO EQUIPMENT DUCT CONNECTIONS AS REQUIRED.
7. MAINTAIN MIN. 10 FT. CLEARANCE BETWEEN ALL OUTSIDE AIR INTAKES AND ALL EXHAUST DISCHARGE LOCATIONS AND/OR PLUMBING VENTS.
8. MAINTAIN REQUIRED CLEARANCES FROM COMBUSTIBLE AND NON-COMBUSTIBLE MATERIALS FOR KITCHEN HOOD EXHAUST DUCTWORK.
9. MAINTAIN MIN. 5 FT. CLEARANCE BETWEEN ROOF MOUNTED EQUIPMENT AND PARAPET WALLS.
10. COORDINATE EXACT LOCATIONS OF ALL ROOF MOUNTED EQUIPMENT AND ROOF PENETRATIONS WITH STRUCTURAL DRAWINGS. ADJUST DUCTWORK AS REQUIRED TO FIT BETWEEN TRUSSES.
11. CEILING DIFFUSERS IN KITCHEN AREAS SHALL DIRECT AIR FLOW AWAY FROM HOODS.
12. DUCTWORK SHALL NOT BE INSTALLED ABOVE ELECTRICAL PANELS.

PROJECT TITLE
Freddy's
FROZEN CUSTARD
STEAKBURGERS
JASPER, AL
Highway 78
Jasper, AL 35501



STUDIO 2H DESIGN
STUDIO 2H DESIGN, LLC
1721 4th AVENUE NORTH
SUITE 101
BIRMINGHAM, AL 35203
www.studio2hd.com
OFFICE: 205-264-9988
FAX: 205-264-9992

NOT FOR CONSTRUCTION
RELEASED FOR CONSTRUCTION

DATE: 13 MAY 2022

DRAWN BY: TLM

REVIEWED BY: KRM

REUSE OF DOCUMENTS
THIS DOCUMENT, THE IDEAS AND DESIGNS INCORPORATED HEREIN, IS AN INSTRUMENT OF STUDIO 2H DESIGN, LLC AND MUST NOT BE USED IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF STUDIO 2H DESIGN, LLC.
NOLANDA HATCHER & CREG HOBKINS

REVISIONS		
NO	DATE	Description
1	09/15/22	OWNER REQUESTED REVISIONS REVISE ENTIRE SHEET


ISSUED for
CONSTRUCTION

SHEET TITLE
HVAC FLOOR PLAN

DRAWING NUMBER
M2.0


PROJECT NUMBER
202119

ME
MICHAELS ENGINEERING, LLC
MECHANICAL CONSULTING & DESIGN
3305 PARK LANE DRIVE • BIRMINGHAM, ALABAMA 35226
(205) 978-1332 • www.michaelsengineering.net




NOTE:
DUCT STRAPS SHALL BE KEPT STRAIGHT, TIGHT AND WITHOUT DENTS, KINKS OR OTHER VISIBLE IMPERFECTIONS. SUPPORT CLIPS SHALL BE LOCATED ON THE TOP SIDE ONLY.


EXPOSED SPIRAL DUCT HANGER DETAIL
NO SCALE



DIFFUSER RUN-OUT DETAIL
NO SCALE




TYPICAL LINEAR SLOT DIFFUSER RUN-OUT DETAIL
NO SCALE




* S CLIP OR C CLIP OPTIONAL. ALL SUCH CONNECTIONS TO BE SEALED.

PROPORTIONAL SPLITTER DETAIL
NO SCALE




- GENERAL NOTES:
1. PREFABRICATED ROOF CURB INSULATION SHALL BE NOT LESS THAN 1 1/2 IN. THICK.
 2. SEE SPECIFICATIONS FOR HOOD PERFORMANCE CRITERIA.
 3. REFER TO ARCHITECTURAL DRAWINGS FOR ROOFING REQUIREMENTS INCLUDING INSULATION, FLASHING, ETC.
 4. SECURE HOOD TO ROOF CURB IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING CODE.


GRAVITY ROOF HOOD DETAIL
NO SCALE




AIR CONDITIONING UNIT DRAIN TRAP DETAIL
NO SCALE



45° BRANCH DUCT CONNECTION DETAIL
RECTANGULAR BRANCH
NO SCALE




EXPOSED DIFFUSER RUN-OUT DETAIL
NO SCALE



- GENERAL NOTES:
1. PREFABRICATED ROOF CURB INSULATION SHALL BE NOT LESS THAN 1 1/2 IN. THICK.
 2. SEE EXHAUST FAN SCHEDULE FOR PERFORMANCE CRITERIA.
 3. EXHAUST DUCT SHALL MAINTAIN A CLEARANCE OF 18 INCHES TO COMBUSTIBLE MATERIALS, 3 INCHES TO COMBUSTIBLE MATERIALS PROTECTED WITH MATERIALS AS APPROVED FOR 1 HOUR FIRE RESISTANCE ON THE DUCT SIDE.

KITCHEN HOOD EXHAUST FAN DETAIL
NO SCALE



KITCHEN EXHAUST HOOD DETAIL
COMPENSATING TYPE
NO SCALE




NOT FOR CONSTRUCTION
RELEASED FOR CONSTRUCTION

DATE: 13 MAY 2022
DRAWN BY: TLM
REVIEWED BY: KRM

REUSE OF DOCUMENTS
THIS DOCUMENT, THE IDEAS AND DESIGNS INCORPORATED HEREIN, IS AN INSTRUMENT OF STUDIO 2H DESIGN, LLC AND MUST NOT BE USED IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF STUDIO 2H DESIGN, LLC.
NOLANDA HATCHER & CREGG HOBKINS

NO	DATE	Description
1	09/15/22	OWNER REQUESTED REVISIONS

ISSUED for
CONSTRUCTION



COMcheck Software Version 4.1.5.4
Mechanical Compliance Certificate

Project Information
 Energy Code: 2015 IECC
 Project Title: Freddy's
 Location: Jasper, Alabama
 Climate Zone: 3a
 Project Type: New Construction

Construction Site: Hwy 78 Jasper, AL 35501
 Owner/Agent: Bill Pyle Bama Custard, LLC 800 Shades Creek Pkwy Birmingham, AL 35209 205-264-9988 3166502286
 Designer/Contractor: Gary Nash Studio 2H Design, LLC 1721 4th Ave North Birmingham, AL 35203 205-264-9988 gary@studio2hd.com

Additional Efficiency Package(s)

Credits: 1.0 Required 1.0 Proposed
 Reduced Lighting Power, 1.0 credit

Mechanical Systems List

Quantity System Type & Description

1 DOAS-1 (Single Zone):
 Heating: 1 each - Central Furnace, Gas, Capacity = 137 kBtu/h
 Proposed Efficiency = 80.00% Et, Required Efficiency: 80.00 % Et or 78% AFUE
 Cooling: 1 each - Single Package DX Unit, Capacity = 186 kBtu/h, Air-Cooled Condenser, Air Economizer
 Proposed Efficiency = 10.80 EER, Required Efficiency: 10.80 EER + 12.2 IEER
 Fan System: FAN SYSTEM 1 | Kitchen - Compliance (Motor nameplate HP method) : Passes
 Fans:
 FAN 1 Supply, Constant Volume, 2100 CFM, 2.0 motor nameplate hp, 60.0 fan efficiency grade

1 DOAS-2 (Single Zone):
 Heating: 1 each - Central Furnace, Gas, Capacity = 104 kBtu/h
 Proposed Efficiency = 80.00% Et, Required Efficiency: 80.00 % Et or 78% AFUE
 Cooling: 1 each - Single Package DX Unit, Capacity = 141 kBtu/h, Air-Cooled Condenser, Air Economizer
 Proposed Efficiency = 10.80 EER, Required Efficiency: 10.80 EER + 12.2 IEER
 Fan System: FAN SYSTEM 2 | Dining - Compliance (Motor nameplate HP method) : Passes
 Fans:
 FAN 2 Supply, Constant Volume, 4800 CFM, 5.0 motor nameplate hp, 60.0 fan efficiency grade

1 Water Heater 1:
 Gas Storage Water Heater, Capacity: 80 gallons, Input Rating: 200 kBtu/h w/ Circulation Pump
 Proposed Efficiency: 94.00 % Et, Required Efficiency: 80.00 % Et

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2015 IECC requirements in COMcheck Version 4.1.5.4 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Kenneth R. Michaels, P.E. - Engineer
 Name - Title Signature Date 9/15/22

Project Title: Freddy's Report date: 09/15/22
 Data filename: C:\Users\Tiffany\Dropbox\ME Projects\22\2015 - Freddy's - Jasper\HVAC Calcs\Freddy's Jasper Page 1 of 10
 DOAS Rev.cck

OUTSIDE AIR CALCULATIONS - RTU-1										EXHAUST AIR REQUIREMENTS				
Space	Area (ft²)	EMO (P/1000 ft²)	Occupancy (People)	A/C SYSTEM			OA Required (cfm)	EXHAUST AIR REQUIREMENTS						
				(cfm/person)	(cfm)	(cfm/ft²)		(cfm/ft²)	(cfm)	(cfm)	(ACH)	(cfm)	EA Required (cfm)	
Dining Room	877	70	62	7.5	465	0.18	158	623	0	0	0	0	0	0
Vestibule	51	0	0	0	0	0.06	4	4	0	0	0	0	0	0
Passage	67	0	0	0	0	0.06	5	5	0	0	0	0	0	0
Storage (RR)	39	0	0	0	0	0.06	3	3	0	0	0	0	0	0
Men	58	0	0	0	0	0	0	0	0	0	0	0	0	140
Women	101	0	0	0	0	0	0	0	0	0	0	0	0	70
Orders	82	0	2	5	10	0.06	5	15	0	0	0	0	0	0
Totals	1,275		64					650						210

Note: O.A. for restrooms provided by transfer air per paragraph 403.2.2 of the 2015 IMC.

OUTSIDE AIR CALCULATIONS - RTU-2										EXHAUST AIR REQUIREMENTS				
Space	Area (ft²)	EMO (P/1000 ft²)	Occupancy (People)	A/C SYSTEM			OA Required (cfm)	EXHAUST AIR REQUIREMENTS						
				(cfm/person)	(cfm)	(cfm/ft²)		(cfm/ft²)	(cfm)	(cfm)	(ACH)	(cfm)	EA Required (cfm)	
Pay	99	0	1	5	5	0.06	6	11	0	0	0	0	0	0
Custard	176	0	3	0	0	0.7	124	124	0	0	0	0	0	0
Cookline	400	0	5	0	0	0.7	280	280	0	0	0	0	0	0
Clean Up	215	0	2	0	0	0.7	151	151	0	0	0	0	0	0
Office	47	5	1	5	5	0.06	3	8	0	0	0	0	0	0
Cooler/Freezer	222	0	0	0	0	0.06	14	14	0	0	0	0	0	0
Storage (Cookline)	58	0	0	0	0	0.06	4	4	0	0	0	0	0	0
Storage (Drive Thru)	169	0	0	0	0	0.06	11	11	0	0	0	0	0	0
Totals	1,386		12					603						0

Note: O.A. for restrooms provided by transfer air per paragraph 403.2.2 of the 2015 IMC.


AIR BALANCE SCHEDULE							
MARK	SERVES	A/C SYSTEM			KITCHEN HOODS		GEN. EXH.
		SUPPLY AIR CFM	RETURN AIR CFM	OUTSIDE AIR CFM	EXHAUST CFM	MAKE-UP CFM	EXHAUST CFM
DOAS-1	KITCHEN	2100	0	2100			
DOAS-2	DINING	4800	4080	720			
KEF-1	KH-1				1600	0	
KEF-2	KH-2				775	0	
EF-1	WOMEN						90
EF-2	MEN						150
TOTALS		6900	4080	2820	2375	0	240

AIR BALANCE CALCULATION		
OUTSIDE AIR THRU A/C SYSTEM (MIN.):		2820
MAKE-UP AIR THRU KITCHEN EXH. HOOD:		0
TOTAL OUTSIDE AIR:		2820
EXHAUST AIR FROM KITCHEN EXH. HOODS:		2375
EXHAUST AIR GENERAL EXHAUST:		240
TOTAL EXHAUST AIR:		2615
TOTAL OUTSIDE AIR:		2820
TOTAL EXHAUST AIR:		-2615
NET POSITIVE BUILDING PRESSURE (MIN.):		+ 205

*EXCESS AIR REILEF THROUGH RTU BAROMETRIC DAMPERS.

PROJECT TITLE
Freddy's
 FROZEN CUSTARD
STEAKBURGERS
JASPER, AL

Highway 78
 Jasper, AL 35501



STUDIO 2H DESIGN
 1721 4th AVENUE NORTH SUITE 101 BIRMINGHAM, AL 35203 www.studio2hd.com
 OFFICE: 205-264-9988 FAX: 205-264-9992

NOT FOR CONSTRUCTION
 RELEASED FOR CONSTRUCTION

DATE: 13 MAY 2022

DRAWN BY: TLM

REVIEWED BY: KRM

REUSE OF DOCUMENTS
 THIS DOCUMENT, THE IDEAS AND DESIGNS INCORPORATED HEREIN, IS AN INSTRUMENT OF STUDIO 2H DESIGN, LLC AND MUST NOT BE USED IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF STUDIO 2H DESIGN, LLC.
 NOLANDA HATCHER & CREGG HOBKINS

REVISIONS		
NO	DATE	Description
1	09/15/22	OWNER REQUESTED REVISIONS


ISSUED for CONSTRUCTION

SHEET TITLE
HVAC CALCULATIONS & COMCHECK

DRAWING NUMBER
M4.0

PROJECT NUMBER
202119

ME
 MICHAELS ENGINEERING, LLC
 MECHANICAL CONSULTING & DESIGN
 3305 PARK LANE DRIVE • BIRMINGHAM, ALABAMA 35226
 (205) 975-1332 • www.michaelsengineering.net



NOT FOR CONSTRUCTION
 RELEASED FOR CONSTRUCTION

DATE: 13 MAY 2022

DRAWN BY: GAN

REVIEWED BY: GAN

REUSE OF DOCUMENTS
 THIS DOCUMENT, THE IDEAS AND DESIGNS INCORPORATED HEREIN, IS AN INSTRUMENT OF STUDIO 2H DESIGN, LLC AND MUST NOT BE USED IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF STUDIO 2H DESIGN, LLC.
 NOLANDA HATCHER & CREIG HOSKINS

REVISIONS



NO	DATE	Description
1	12 SEP 2022	OWNER REQ'd REVs

ISSUED for
 CONSTRUCTION

SHEET TITLE
ROOF PLAN & DETAILS

DRAWING NUMBER
A3

PROJECT NUMBER
 202119



A ROOF PLAN SCALE: 1/4" = 1'-0"




GENERAL ROOF NOTES:

- THE NEW ROOF MEMBRANE IS A 50 MIL REINFORCED THERMOPLASTIC ROOFING MEMBRANE SYSTEM AS MANUFACTURED BY DURO-LAST ROOFING, INC. EXPOSED FACE COLOR: WHITE - NO EXCEPTIONS
- PROVIDE RIGID ROOF INSULATION COMPOSED OF EITHER A CLOSED CELL POLYISOCYANURATE OR EXPANDED POLYSTYRENE (EPS) FOAM CORE BONDED TO A FIBER REINFORCED GLASS OR FELT FACER. PROVIDE MINIMUM PERFORMANCE VALUE(S) AS INDICATED IN ENERGY CODE INFO ON SHT A0.
- ROOF SYSTEM SHALL BE MECHANICALLY FASTENED AND FIELD SEAMS HEAT WELDED PER MANUFACTURER'S SPECIFICATIONS. FASTENERS: FACTORY-COATED STEEL FASTENERS AND METAL PLATES MEETING FMG 4470, DESIGNED FOR FASTENING SUBSTRATE PANELS TO SUBSTRATE AND ACCEPTABLE TO ROOFING SYSTEM MANUFACTURER.
- PROVIDE AND INSTALL NEW FACTORY FORMED SLIP RESISTANT WALKWAY PADS MADE FROM ROOFING MEMBRANE MATERIAL ON ROOF FROM LADDER ACCESS AREA TO, BETWEEN AND AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT. INSTALL PER MANUFACTURER'S INSTALLATION INSTRUCTIONS, SOLIDLY SECURED TO ROOF.
- PROVIDE TEST ON ROOF. DAMP AREAS MUST BE CUT OUT, REMOVED, FILLED AND REROOFED.
- VERIFY ALL DIMENSIONS, EQUIPMENT CONFIGURATIONS AND LOCATIONS, EXISTING CONDITIONS AND ALL INFORMATION GIVEN OR NOT GIVEN ON DRAWINGS. CONTRACTOR SHALL VERIFY CONDITIONS ON SITE AND SHALL BE RESPONSIBLE FOR QUANTITIES, DIMENSIONS AND EXISTING CONDITIONS RELATED TO THE WORK REQUIRED UNDER THIS CONTRACT. FAILURE TO DO SO WILL NOT BE CAUSE FOR ADDITIONAL FUNDS OR CHANGE ORDERS FOR ITEMS NOT INCLUDED IN CONTRACTOR'S BID.
- THE ROOF ASSEMBLY SHALL COMPLY WITH UL-1 90 AND FM CLASS "B" RATINGS INCLUDING BUT NOT LIMITED TO COPINGS, FLASHING, PARAPET WALL COVERINGS, AND ENTIRE ROOF SURFACE.
- ALL ROOF CRICKETS ARE TO BE BUILT WITH TAPERED RIGID INSULATION & PROVIDE THE SLIP SHEET, PER MANUFACTURER'S RECOMMENDATIONS, ROOFING TO POSITIVE 1/4" PER FOOT SLOPE TO THE ROOF SCUPPERS. INSULATION SHALL BE APPROVED BY ROOFING MANUFACTURER AS COMPATIBLE WITH ROOFING ASSEMBLY.
- ALL MECHANICAL EQUIPMENT OPENINGS TO BE COORDINATED WITH MECHANICAL AND/OR ALL OTHER RELATED DRAWINGS
- TALL PARAPET WALLS TO RECEIVE VERTICAL APPLICATION OF MEMBRANE ROOFING SYSTEM SECURED TO PLYWOOD DECK/SHEATHING. ROOFING INSTALLER SHALL PROVIDE MANUFACTURER'S GUARANTEE OF COMPLETE ROOFING SYSTEM, INCLUDING ALL FLASHING, COPINGS AND PARAPET ASSEMBLIES.
 ALL VERTICAL APPLICATIONS SHALL BE FULLY ADHERED TO THE SUBSTRATE
- INSTALLER QUALIFICATIONS: A QUALIFIED INSTALLER, CERTIFIED AS A "MASTER INSTALLER" BY THE ROOFING SYSTEM MANUFACTURER, APPROVED BY MANUFACTURER TO INSTALL MANUFACTURER'S PRODUCTS AND IS ELIGIBLE TO RECEIVE MANUFACTURER'S WARRANTY.
- ALL CURB AND EQUIPMENT FLASHING SHALL BE A PRODUCT OF DURO-LAST ROOFING INC. FLASHING & COPING CAP SHALL BE INSTALLED PER ROOFING MANUFACTURER'S CRITERIA TO PROVIDE FULL MANUFACTURER'S GUARANTEE OF COMPLETE ROOFING ASSEMBLY.
- THE ROOFING CONTRACTOR IS TO COORDINATE ALL ROOF PENETRATIONS WITH ALL OTHER TRADES TO PROVIDE PROPER FLASHING AND COMPLETE, WEATHER-TIGHT ROOF. ALSO INCLUDES PENETRATION FOR THE SIRIUS ANTENNA AND WIRE PROVIDED BY OWNER AND INSTALLED PER MFGR SPECS BY ROOFING CONTRACTOR.
- PROVIDE A COPING CAP WITH FRONT AND BACK DRIP EDGES ALONG ENTIRE PARAPET WALL. REFER EXTERIOR ELEVATIONS AND WALL SECTIONS. ("DURO-LAST" ALUM. REGAL RED)
- THE ROOF STRUCTURE SHALL NOT BE USED FOR STOCK-PIILING OF EQUIPMENT OR MATERIALS UNLESS APPROVED BY THE ARCHITECT, STRUCTURAL ENGINEER AND THE TRUSS MANUFACTURER.


CRRC PROD. ID	MANUF.: BRAND MODEL
1610-0001	DURO-LAST ROOFING INC. DURO-LAST WHITE

SOLAR REFLECTANCE		THERMAL EMITTANCE		SRI	
INITIAL	3 YEAR	INITIAL	3 YEAR	INITIAL	3 YEAR
0.88	0.68	0.87	0.84	111	82




4 REFIG PIPE PENETRATION SCALE: 1" = 1'-0"

- GC PROVIDE WEATHERPROOF, SURFACE MTD J-BOXES for LED PARAPET LIGHT SYSTEM
- GC PROVIDE 1/2" CONDUIT in PARAPET WALL CONNECTg J-BOXES
- ROOFER PROVIDE WEATHERPROOF PENETRATIONS in ACCORDANCE w/ THE ROOF MFG as REQ'd to MAINTAIN WARRANTY
- SEE ALSO SHT A2.1, WALL SECTIONS & ELEC DWGS, COORD w/ LIGHTg VENDOR



2 ELEV at SCUPPER SCALE: 1/2" = 1'-0"



3 SECTION at SCUPPER SCALE: 1/2" = 1'-0"

F
E
D
C
B
A

F
E
D
C
B
A

EXHAUST FAN INFORMATION - JOB#5254570

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	MANUFACTURER	CFM	ESP	RPM	MOTOR ENCL.	HP	BHP	PHASE	VOLT	FLA	DISCHARGE VELOCITY	WEIGHT (LBS)	SDNES
1	EF-1 (GRIDDLE)	1	CASRE18DD	CAPTIVEAIRE	1600	1.400	1095	DDP-PREMIUM	1.000	0.6250	3	208	3.8	928 FPM	282	15.4795751219348
2	EF-2 (FRYER)	1	DUS0HFA	CAPTIVEAIRE	775	1.250	1532	TEAD-ECM	0.500	0.3950	1	115	6.3	295 FPM	105	16.3627170956522


DDAS/RTU FAN SCHEDULE - JOB#5254570

FAN UNIT NO	TAG	QTY	DDAS/RTU MODEL #	MANUFACTURER	BLOWER	RETURN AIR CFM	MAX OUTSIDE AIR CFM	TOTAL CFM	WEIGHT (LBS)	ELECTRICAL INFORMATION				COOLING INFORMATION				REHEAT INFORMATION				GAS HEAT INFORMATION				NOTES											
										ESP	HP	PHASE	VOLT	MCA	MOPC	OUTSIDE AIR DB	MIXED AIR DB	LEAVING AIR DB	TOTAL CAPACITY	ICEER	ISURE	DISCHARGE DB	DESIRED DB	CAPACITY	MOISTURE REMOVAL RATE		GAS TYPE	INPUT BTUS	OUTPUT BTUS	TEMP RISE							
3	DDAS-1	1	CASRTU3-1200-15-15T-DDAS	CAPTIVEAIRE	15P-3	0	2100	2100	2432	0.500	2.00	3	208	59.2A	60A	82.8°F	77.8°F	82.8°F	77.8°F	53.6°F	50.9°F	48.8°F	186.0 MBH	65.4 MBH	18.8	5.7	70.0°F	57.7°F	38.2 MBH	129.6 MBH	108.6	LBS/HR	NATURAL	169158	137018	56°F	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15
4	DDAS-2 (DINING)	1	CASRTU3-1200-24-12.5T-DDAS	CAPTIVEAIRE	24NF-3-RTU	4080	720	4800	2375	0.500	5.00	3	208	68.8A	80A	82.8°F	77.8°F	76.2°F	64.8°F	54.9°F	54.8°F	54.8°F	140.6 MBH	108.9 MBH	21.3	4.1	70.0°F	60.6°F	80.3 MBH	101 MBH	29.0	LBS/HR	NATURAL	128395	104000	19°F	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18

FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	EF-1 (GRIDDLE)	1	UTILITY SET GREASE CUP
		1	RE18 - DISCHARGE EXTENSION ASSEMBLY WITH HARDWARE
		1	2 YEAR PARTS WARRANTY
		1	GREASE BOX
		1	UPPLAST FAN WHEEL ACCESS PORT
		1	36" TALL STRAIGHT WIND BAND EXTENSION 13 (SHIPS LOOSE)
		1	FAN BASE CERAMIC SEAL - SHIP LOOSE - FOR GREASE DUCTS
		1	ECM WIRING PACKAGE - PWM SIGNAL FROM ECM/D3 PREWIRE (TELCO MOTOR), CCW ROTATION
		1	2 YEAR PARTS WARRANTY
		1	OVERHEAT STAT
2	EF-2 (FRYER)	1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE
		1	RTU TOTAL CFM MONITORING
		1	SINGLE POINT ELECTRICAL CONNECTION FOR RTU, 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #28, #47, #49, OR #51 PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE.
		1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
		1	RTU3 DOWN DISCHARGE
		1	2" MERV 13 FILTERS FOR RTU3 (QTY. 4)
		1	2" MERV 8 FILTERS FOR RTU3 (QTY. 4)
		1	OVERHEAT STAT
		1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
3	DDAS-1	1	REMOTE TEMPERATURE AND HUMIDITY SPACE SENSOR
		1	15 TON MODULATING COOLING OPTION, 208/230V, R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS
		1	15 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL
		1	RTU3 CURB DUCT HANGER
		1	OCCUPIED SCHEDULING
		1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI
		1	RTU INTAKE/RETURN DAMPER - SCHEDULED DA PERCENTAGE CONTROL
		1	RTU3 HAIL GUARD
		1	RTU3 DOWN RETURN
		1	VAV PACKAGE W/ 0-10VDC INPUT CONTROL (S71 VFD INCLUDED)
4	DDAS-2 (DINING)	1	RTU RETURN MOUNTED SMOKE DETECTOR AND SAMPLING TUBE - FACTORY INSTALLED
		1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY. (SEE ADDITIONAL DETAILS)
		1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE
		1	RTU TOTAL CFM MONITORING
		1	SHIP LOOSE GAS STRAINER 3/4"
		1	SINGLE POINT ELECTRICAL CONNECTION FOR RTU, 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #28, #47, #49, OR #51 PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE.
		1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
		1	LOW AMBIENT COOLING OPERATION - DOWN TO OF AMBIENT
		1	RTU3 DOWN DISCHARGE

FAN #1 CASRE18DD - EXHAUST FAN (EF-1 (GRIDDLE))



FEATURES:

- ROOF MOUNTED FANS.
- RESTAURANT MODEL.
- UL765 AND UL768 AND ULC-S645.
- HIGH HEAT OPERATION DIRECT DRIVE 300°F (149°C).
- HEAT SLINGER.
- GREASE CLASSIFICATION TESTING.
- TILT OUT WHEEL.
- LOCKING PIN FOR POWER PACK.
- MOTOR WEATHER COVER.
- INTERLOCKED DISCONNECT SWITCH.
- NEMA 4X SAFETY DISCONNECT SWITCH.


NORMAL TEMPERATURE TEST BELT & DIRECT DRIVE EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING AIR AT 300°F (149°C) UNTIL ALL FAN PARTS HAVE REACHED THERMAL EQUILIBRIUM AND WITHOUT ANY DETERIORATING EFFECTS TO THE FAN WHICH WOULD CAUSE UNSAFE OPERATION.

ABNORMAL FLARE-UP TEST BELT & DIRECT DRIVE EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING BURNING GREASE VAPORS AT 600°F (316°C) FOR A PERIOD OF 15 MINUTES WITHOUT THE FAN BECOMING DAMAGED TO ANY EXTENT THAT COULD CAUSE AN UNSAFE CONDITION.

OPTIONS

- UTILITY SET GREASE CUP.
- RE18 - DISCHARGE EXTENSION ASSEMBLY WITH HARDWARE.
- 2 YEAR PARTS WARRANTY.

FAN #2 DUS0HFA - EXHAUST FAN (EF-2 (FRYER))



FEATURES:

- DIRECT DRIVE CONSTRUCTION (NO BELTS/PULLEYS).
- ROOF MOUNTED FANS.
- RESTAURANT MODEL.
- UL765 AND UL768 AND ULC-S645.
- VARIABLE SPEED CONTROL.
- INTERNAL WIRING.
- THERMAL OVERLOAD PROTECTION (SINGLE PHASE).
- HIGH HEAT OPERATION 300°F (149°C).
- GREASE CLASSIFICATION TESTING.
- NEMA 3R SAFETY DISCONNECT SWITCH.

NORMAL TEMPERATURE TEST EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING AIR AT 300°F (149°C) UNTIL ALL FAN PARTS HAVE REACHED THERMAL EQUILIBRIUM AND WITHOUT ANY DETERIORATING EFFECTS TO THE FAN WHICH WOULD CAUSE UNSAFE OPERATION.

ABNORMAL FLARE-UP TEST EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING BURNING GREASE VAPORS AT 600°F (316°C) FOR A PERIOD OF 15 MINUTES WITHOUT THE FAN BECOMING DAMAGED TO ANY EXTENT THAT COULD CAUSE AN UNSAFE CONDITION.

OPTIONS



- GREASE BOX.
- UPPLAST FAN WHEEL ACCESS PORT.
- 36" TALL STRAIGHT WIND BAND EXTENSION 13 (SHIPS LOOSE).
- FAN BASE CERAMIC SEAL - SHIP LOOSE - FOR GREASE DUCTS.
- ECM WIRING PACKAGE - PWM SIGNAL FROM ECM/D3 PREWIRE (TELCO MOTOR), CCW ROTATION.
- 2 YEAR PARTS WARRANTY.

FAN ACCESSORIES

FAN UNIT NO	TAG	EXHAUST			SUPPLY		
		GREASE CUP	GRAVITY DAMPER	SIDE MOUNT	GRAVITY DAMPER	MOTORIZED DAMPER	WALL MOUNT
1	EF-1 (GRIDDLE)	YES					
2	EF-2 (FRYER)	YES					


CURB ASSEMBLIES

NO	DN FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	EF-1 (GRIDDLE)	38 LBS	CURB	26.500"W X 26.500"L X 24.000"H ALONG LENGTH, RIGHT VENTED HINGED.
2	# 2	EF-2 (FRYER)	31 LBS	CURB	19.500"W X 19.500"L X 20.000"H ALONG LENGTH, RIGHT VENTED HINGED.
3	# 3	DDAS-1	78 LBS	CURB	59.500"W X 91.000"L X 14.000"H ALONG WIDTH, RIGHT INSULATED.
4	# 4	DDAS-2 (DINING)	78 LBS	CURB	59.500"W X 91.000"L X 14.000"H ALONG WIDTH, RIGHT INSULATED.



REVISIONS

DESCRIPTION	DATE



www.captiveaire.com
www.hbtfoodservice.com



Freddy's - Jasper, AL
JASPER, AL, 35501






DATE: 8/19/2022
DWG.#: 5254570
DRAWN BY: michael.co
SCALE: 1/2" = 1'-0"
MASTER DRAWING

SHEET NO. 2

NOTES:




- DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
- DENOTES CORNER WEIGHT.
- ROOF OPENING MUST BE 2" SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.

*NOTE: SUPPLY DUCT MUST BE INSTALLED TO MEET SMACNA STANDARDS. A MINIMUM STRAIGHT DUCT LENGTH MUST BE MAINTAINED DOWNSTREAM OF UNIT DISCHARGE AS OUTLINED IN AMCA PUBLICATION 201. WHEN USING RECTANGULAR DUCTWORK, ELBOWS MUST BE RADIUS THROAT, RADIUS BACK WITH TURNING VANES. FLEXIBLE DUCTWORK AND SQUARE THROAT/SQUARE BACK ELBOWS SHOULD NOT BE USED. ANY TRANSITION AND/OR TURNS IN THE DUCTWORK WILL CAUSE SYSTEM EFFECT. SYSTEM EFFECT WILL DRASTICALLY INCREASE STATIC PRESSURE AND REDUCE AIRFLOW. DO NOT RELY ON UNIT TO SUPPORT DUCT IN ANY WAY. FAILURE TO PROPERLY SIZE DUCTWORK MAY CAUSE SYSTEM EFFECTS AND REDUCE PERFORMANCE OF THE EQUIPMENT. SUGGESTED STRAIGHT DUCT SIZE IS 21.5" x 39".



OPTIONS

- INLET PRESSURE GAUGE, 0-35".
- MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE.
- RTU TOTAL CFM MONITORING.
- SINGLE POINT ELECTRICAL CONNECTION FOR RTU. 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #28, #47, "MA", OR "E2" PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE.
- CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED.
- RTU3 DOWN DISCHARGE.
- 2" MERV 13 FILTERS FOR RTU3 (QTY. 4).
- 2" MERV 8 FILTERS FOR RTU3 (QTY. 4).
- OVERHEAT STAT.
- VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE.
- REMOTE TEMPERATURE AND HUMIDITY SPACE SENSOR.
- 15 TON MODULATING COOLING OPTION, 208/230V. R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS.
- 15 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL.
- RTU3 CURB DUCT HANGER.
- OCCUPIED SCHEDULING.
- CLOGGED FILTER SWITCH - NOTIFICATION ON HMI.
- RTU INTAKE/RETURN DAMPER - SCHEDULED ON PERCENTAGE CONTROL.
- RTU3 HAIL GUARD.
- RTU3 DOWN RETURN.
- VAV PACKAGE W/ 0-10VDC INPUT CONTROL (571 VFD INCLUDED).
- RTU RETURN MOUNTED SMOKE DETECTOR AND SAMPLING TUBE - FACTORY INSTALLED.
- 5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS).



REVISIONS

DESCRIPTION	DATE:

CAPTIVEAIRE

www.captiveaire.com

HBT Foodservice

104 W 8th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: reg9@captveaire.com

Freddy's - Jasper, AL

JASPER, AL, 35501

DATE: 8/19/2022

DWG.#: 5254570

DRAWN BY: michael.co


SCALE: 1/2" = 1'-0"

MASTER DRAWING










SHEET NO. 3

FAN #4 CASRTU3-1.200-24MF-12.5T-DOAS - HEATER (DOAS-2 (DINING))

NOTES:


- DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
-  DENOTES CORNER WEIGHT.
- ROOF OPENING MUST BE 2' SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.

*NOTE: SUPPLY DUCT MUST BE INSTALLED TO MEET SMACNA STANDARDS. A MINIMUM STRAIGHT DUCT LENGTH MUST BE MAINTAINED DOWNSTREAM OF UNIT DISCHARGE AS OUTLINED IN AMCA PUBLICATION 201. WHEN USING RECTANGULAR DUCTWORK, ELBOWS MUST BE RADIUS THROAT, RADIUS BACK WITH TURNING VANES. FLEXIBLE DUCTWORK AND SQUARE THROAT/SQUARE BACK ELBOWS SHOULD NOT BE USED. ANY TRANSITION AND/OR TURNS IN THE DUCTWORK WILL CAUSE SYSTEM EFFECT. SYSTEM EFFECT WILL DRASTICALLY INCREASE STATIC PRESSURE AND REDUCE AIRFLOW. DO NOT RELY ON UNIT TO SUPPORT DUCT IN ANY WAY. FAILURE TO PROPERLY SIZE DUCTWORK MAY CAUSE SYSTEM EFFECTS AND REDUCE PERFORMANCE OF THE EQUIPMENT. SUGGESTED STRAIGHT DUCT SIZE IS 21.5" x 39".



REVISIONS

DESCRIPTION	DATE



CAPTIVE AIR
www.captiveair.com

HBT Foodservice
www.hbtfoodservice.com

Freddy's - Jasper, AL
JASPER, AL, 35501

DATE: 8/19/2022

DWG.#:
5254570

DRAWN BY: michael.co



SCALE:
1/2" = 1'-0"

MASTER DRAWING

SHEET NO.


ELECTRICAL PACKAGE # - JOB#5254570

Table with columns: NO, TAG, PACKAGE #, LOCATION, SWITCHES, OPTION, FANS CONTROLLED. Includes details for DCV-2011 and EF-1/2 (GR/FRY) units.



DEMAND CONTROL VENTILATION HOOD CONTROL PANEL SPECIFICATIONS:


- CONTROLS SHALL BE LISTED BY ETL (UL 508A) AND SHALL COMPLY WITH DEMAND VENTILATION SYSTEM TURNDOWN REQUIREMENTS OUTLINED IN IECC 403.2-8 (2015).
- THE CONTROL ENCLOSURE SHALL BE NEMA 1 RATED AND LISTED FOR INSTALLATION INSIDE OF THE EXHAUST HOOD UTILITY CABINET...



TYPICAL HOOD CONTROL PANEL INSTALLATION

SEQUENCE OF OPERATIONS:

- THE HOOD CONTROL PANEL IS CAPABLE OF OPERATING IN ONE OR MORE OF THE FOLLOWING STATES AT ANY GIVEN TIME:
- AUTOMATIC: THE SYSTEM OPERATES BASED ON THE DIFFERENTIAL BETWEEN ROOM TEMPERATURE AND THE TEMPERATURE AT THE HOOD CAVITY OR EXHAUST DUCT COLLAR...



TYPICAL ANSUL R-102 SYSTEM LAYOUT

SPECIFICATIONS

THE RESTAURANT FIRE SUPPRESSION SYSTEM SHALL BE THE PRE-ENGINEERED TYPE WITH A FIXED NOZZLE AGENT DISTRIBUTION NETWORK. IT SHALL BE LISTED WITH UNDERWRITERS LABORATORIES, INC. (UL).
- THE SYSTEM SHALL BE CAPABLE OF AUTOMATIC DETECTION AND ACTUATION WITH LOCAL OR REMOTE MANUAL ACTUATION...

REVISIONS table, CAPTIVE logo, HBT Foodservice logo, Freddy's - Jasper, AL, JASPER, AL, 35501, DATE: 8/19/2022, DWG#: 5254570, DRAWN BY: michael.co, SCALE: 1/2" = 1'-0", MASTER DRAWING, SHEET NO. 5.