

Project Summary

The summary below provides a quick understanding of our scope of work and general testing procedures. Enclosed in the report are further details about your building performance including recommendations, asset data, and pictures. Our focus is to work with the trades to remedy any issues or deficiencies during the actual field balancing and not after the balancing has occurred to achieve a positive environment and outcome. The level of success is determined by the availability of the trades, possible parts needed, or time constraints.
report.

DOAS

The DOAS supply air was measured at their terminal devices or via traverse to establish a total flow for that unit. The fans were adjusted to within tolerance of the engineer's total design flow. Each outlet was then adjusted to within tolerance of the design flow. Any equipment that fell outside of that tolerance is noted throughout the report.