

1 HVAC FLOOR PLAN
M1.0
14" = 1'-0"

- KEY NOTES:**
- REMOTE SMOKE DETECTOR TEST STATIONS FOR RTU-1, 2, & 3. TEST STATIONS TO BE MOUNTED ON THE MANAGERS OFFICE WALL. SECURITY CONTRACTOR SHALL WIRE RTU FACTORY MOUNTED SMOKE DETECTORS TO SECURITY/FIRE ALARM PANEL. MECHANICAL CONTRACTOR SHALL PROVIDE TEST STATION AND WIRING BETWEEN COMPONENTS AS WELL AS WIRING TO SHUT DOWN THE A/C FAN UPON ACTIVATION OF THE SMOKE DETECTOR. G.C. TO TEST THE SMOKE DETECTOR FUNCTIONS WITH THE WAWA PROJECT MANAGER.
 - WALL MOUNTED SENSOR(S) FOR EACH MECHANICAL UNIT PER ROOFTOP UNIT SCHEDULE ON SHEET M3.0. G.C. SHALL INSTALL AND WIRE TO UNIT. BAS CONTRACTOR SHALL CONNECT TO MECHANICAL UNIT ONLY.
 - COORDINATE EXACT LOCATION OF EXHAUST FAN PENETRATION WITH ARCHITECTURAL ROOF PLAN. INSTALL GALVANIZED DUCT WORK DOWN FROM FAN, INTO CEILING/JOIST SPACE, AND CONNECT TO CEILING GRILLES.
 - REFER TO TYPICAL DUCT PLENUM DETAIL ON SHEET M3.0.
 - COORDINATE DUCT WITH STRUCTURE IN THIS LOCATION. COORDINATE TAKEOFF LOCATIONS WITH ANGLED WEB MEMBERS.
 - PROVIDE SURFACE MOUNT ADAPTER FRAME TO ALLOW ACCESS TO CEILING ABOVE THROUGH DIFFUSER OPENING. SEE AIR DEVICE SCHEDULE.
 - ROUTE DUCT UNDER STRUCTURAL MEMBERS AT THIS LOCATION.
 - DUCTWORK TO RUN WITHIN JOIST SPACING. MECHANICAL CONTRACTOR TO COORDINATE MECHANICAL WORK WITH ALL TRADES PRIOR TO INSTALLATION.
 - DUCT TAKEOFF WITH DAMPER FROM BOTTOM OF MAIN DUCT.
 - TRANSFER DUCT ASSEMBLY.
 - PROVIDE SEALED 20"x20" PLENUM BOX ASSEMBLY ABOVE TRANSFER GRILLES TO ALLOW FLEX TRANSFER DUCT CONNECTIONS.
 - GRILLE OPEN TO ABOVE CEILING.
 - INSTALL EXHAUST FAN ABOVE CEILING PER DETAIL SHEET M3.0. FAN SHALL BE WIRED TO EMERGENCY SHUT-OFF SWITCH PROVIDED BY OTHERS. REFERENCE ARCHITECTURAL AND ELECTRICAL DRAWINGS.
 - MOUNT CENTER OF EXHAUST GRILLE AT 12" ABOVE FINISHED FLOOR. ROUTE DUCT SIZES AS SHOWN FROM GRILLE UP IN WALL CAVITY TO ABOVE CEILING. THEN TO EXHAUST FAN AND OUT TO EXTERIOR WALL LOUVER. COORDINATE DUCT ROUTING WITH ALL OTHER TRADES.
 - 12"x12" EXTERIOR WALL LOUVER MODEL EHH-601D AS MANUFACTURED BY GREENHECK. INSTALL PER MANUFACTURER'S RECOMMENDED INSTALLATION INSTRUCTIONS. FLORIDA PRODUCT APPROVAL #10089-1. PROVIDE WITH BIRD SCREEN, 1-1/2" FLANGE, AND ALUMINUM MULL FINISH.
 - EMERGENCY SHUT-OFF SWITCH AND WALL PLACARD INDICATING VENTILATION SYSTEM. EMERGENCY SHUT-OFF PROVIDED BY OTHERS REFERENCE ELECTRICAL AND ARCHITECTURAL DRAWINGS.

SHEET GENERAL NOTE:

A. MECHANICAL CONTRACTOR SHALL ADJUST ALL LINEAR SLOT DIFFUSERS TO A GENERALLY VERTICAL FLOW. ADJUSTMENT SHALL BE MADE SO AS TO AVOID AIRFLOWS ON SENSORS, REFRIGERATION CASES, OR OPEN FOOD REFRIGERATION EQUIPMENT.

HVAC LEGEND	
SYMBOL	DESCRIPTION
	NEW RECTANGULAR OR ROUND DUCT
	FLEXIBLE DUCT
	SUPPLY AIR DUCTWORK UP THROUGH PLAN
	RETURN AIR DUCTWORK UP THROUGH PLAN
	EXHAUST AIR DUCTWORK UP THROUGH PLAN
	90° ELBOW WITH TURNING VANES
	MANUAL AIR VOLUME CONTROL DAMPER
	4 WAY SUPPLY DIFFUSER
	3 WAY SUPPLY DIFFUSER
	2 WAY OPPOSED SUPPLY DIFFUSER
	2 WAY CORNER SUPPLY DIFFUSER
	RETURN AIR DEVICE
	EXHAUST AIR DEVICE
	AIR CURTAIN
	LINEAR SLOT DIFFUSER WITH PLENUM
	COMBINATION TEMPERATURE/HUMIDITY SENSOR
	TEMPERATURE SENSOR
	CO2 SENSOR
	SWITCH
	TYPE MARK
	MECHANICAL EQUIPMENT TAG
	CONDENSATE PIPING
	ROOF MOUNTED EXHAUST FAN
	INLINE EXHAUST FAN
	PACKAGED ROOFTOP AIR CONDITIONER


2600 Mailand Center Parkway
Suite #200
Mailand, FL 32751
P (407) 661-9100
F (407) 661-9101
c-p.com
FROM: COLUMBIA UNIVERSITY

CUHACI PETERSON

Copyright © All rights reserved. No part of this document may be reproduced without the prior written permission of the copyright owner.

CLIENT NAME
WAWA
260 WEST BALTIMORE PIKE
WAWA, PENNSYLVANIA 19063

PROJECT NAME
WAWA F88FF V2021.3
STORE #5452
S. JOHN YOUNG PKWY & DESTINATION PKWY, ORLANDO, FL




Digitally signed by Jose J. Diaz-Velasquez
Reason: This document has been digitally signed and sealed on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Date: 2023.08.07 09:45:47 -04'00'


Revision Schedule	Date
PERMIT SET	06/07/2023

ORANGE COUNTY BUILDING SAFETY
This document must be submitted to the Building Department for review and approval. This document is not valid until it has been reviewed and approved by the Building Department. This document is not valid until it has been reviewed and approved by the Building Department.
Permit # B23903297
Date: 03/01/24
M1.0


BUILDING LOCATION DESTINATION PKWY, ORLANDO, FL	WIND SPEED ZONE (FBC FIGURE 1609A) 135 MPH
--	--




1 RTU TIE-DOWN DETAIL
M3.0 NOT TO SCALE




2 CEILING DIFFUSER RUNOUT DETAIL
M3.0 NOT TO SCALE




3 CEILING MOUNTED AIR DIFFUSER SUPPORT DETAIL
M3.0 NOT TO SCALE




4 TYPICAL DUCT PLENUM DETAIL
M3.0 NOT TO SCALE




5 CONDENSATE DRAIN TRAP DETAIL
M3.0 NOT TO SCALE




6 FLEX DUCT SUPPORT DETAIL
M3.0 NOT TO SCALE




7 ROOF FAN MOUNTING DETAIL
M3.0 NOT TO SCALE




8 CONDENSATION TERMINATION DETAIL
M3.0 NOT TO SCALE



9 CONDENSATE PIPE ROOF SUPPORT DETAIL
M3.0 NOT TO SCALE



10 AIR CURTAIN INSTALLATION DETAIL
M3.0 NOT TO SCALE



11 INLINE FAN MOUNTING DETAIL
M3.0 NOT TO SCALE

HVAC GENERAL NOTES

- ALL MECHANICAL WORK SHALL BE IN STRICT ACCORDANCE WITH THE 2020 FLORIDA BUILDING CODE - MECHANICAL, SMACNA, UL, LOCAL CODES, MANUFACTURER'S RECOMMENDATIONS, AND ALL AUTHORITIES HAVING JURISDICTION.
- CONTRACTOR TO VISIT SITE AND VERIFY ALL CLEARANCES BEFORE FABRICATION OF DUCTWORK AND PROVIDE ADDITIONAL OFFSET AND/OR CHANGES IN DUCT SIZES TO MEET FIELD CONDITIONS AND COORDINATE WITH ELECTRICAL, PLUMBING AND FIRE PROTECTION SUBCONTRACTOR BEFORE ANY CONSTRUCTION WORK.
- SUPPLY AIR, RETURN AIR, OUTSIDE AIR AND EXHAUST AIR DUCTWORK SHALL BE SHEET METAL CONSTRUCTION. DUCT SHALL BE INSTALLED SECURELY SUPPORTED, HUNG OR SUSPENDED FROM THE STRUCTURE. JOINTS SHALL BE SEALED WITH 3\"/>

HVAC ROOFTOP UNIT SCHEDULE

MARK	AREA SERVED	NOMINAL TONS	SUPPLY AIR FAN DATA				ELECTRIC HEAT		UNIT POWER		WEIGHT (LBS. RTU ONLY)	COOLING CAPACITY			BASIS OF DESIGN		MODEL	NOTES				
			SUPPLY AIR CFM	OUTSIDE AIR (IN)	E.S.P. (IN)	HP	KW	CONTROL STAGES	VOLTAGE	PHASE		MCA	MOCP	TOTAL COOLING MBH	SENSIBLE COOLING MBH	EDB (F)			EWB (F)	AMBIENT (F)	EER (EER)	MANUFACTURER
RTU-1	RETAIL	8.5	3400	610	0.5	3.75	22.5	1	208 V	3	44	50	1357	98.1	75.4	76.5	63.9	95/79	12.3 (15.7)	LENNOX ENLIGHT	LCT102H4E	1-20
RTU-2	FOOD SERVICE	12.5	5000	900	0.5	3.75	N/A	N/A	208 V	3	64	80	1342	146.1	136	75.2	62.5	95/79	11.0 (14.6)	LENNOX ENLIGHT	LCT150H4E	2-20
RTU-3	RETAIL	7.5	3000	540	0.5	3.75	22.5	1	208 V	3	43	50	1350	91.8	68.7	76.1	63.5	95/79	12.5 (15.7)	LENNOX ENLIGHT	LCT092H4E	2-20

- NOTES:
- PROVIDE CO2 SENSOR FOR INTERLINK WITH BUILDING AUTOMATION SYSTEM.
 - PROVIDE LENNOX HUMIDITROL HOT GAS REHEAT OPTION.
 - PROVIDE REMOTE WALL MOUNTED COMBINATION TEMPERATURE/HUMIDITY SENSOR MODEL 21W66
 - REFER TO CONTROL SYSTEM NOTES FOR CONTROL COMPONENTS REQUIREMENTS.
 - PROVIDE 5MINUTE ANTI-SHORT CYCLE TIMER.
 - PROVIDE THRU THE BASE ELECTRICAL AND SINGLE POINT CONNECTION.
 - FACTORY SHALL HAVE EACH SYSTEM TESTED, ADJUSTED, AND BALANCED BY AN INDEPENDENT TESTING AND BALANCING CONTRACTOR.
 - PROVIDE WITH 18\"/>

OUTSIDE AIR CALCULATION

AREA SERVED	AREA (SQFT)	PEOPLE / 1000 SQFT	# PEOPLE	CFM PERSON	PEOPLE O.A. RECD (CFM)	CFM SOFT	CFM HARD	TOTAL CFM CALCULATED	CFM SUPPLIED
OFFICE	70	5	2	5	10	0.06	5	15	
ASSOCIATE	100	5	2	5	10	0.06	6	16	
DELIVERY	78	2	1	10	10	0.12	10	20	
RETAIL	1904	15	29	7.5	218	0.12	229	447	610
RTU-1									498
RTU-2									91
RTU-3									76
RTU-4									40
RTU-5									900

HVAC EXHAUST FAN SCHEDULE

MARK	CFM	EXT. STATIC PRESSURE	FAN TYPE	DRIVE TYPE	SONES	HP	FAN RPM	VOLTAGE	PHASE	BASIS OF DESIGN		MODEL	NOTES
										MANUFACTURER	FACE SIZE		
EF-1	1550 CFM	0.250 (h-wg)	DOWNBLAST	DIRECT	6.9	3/4	700	120 V	1	GREENHECK	G-160	1-2	
EF-2	60 CFM	0.125 (h-wg)	INLINE	DIRECT	0.3	21 WATTS	584	120 V	1	GREENHECK	CSP-B10	3	

- NOTES:
- NO SUBSTITUTIONS PERMITTED-
 - PROVIDE WITH FACTORY DISCONNECT, FACTORY WIRED SOLID STATE SPEED CONTROLLER, 18\"/>

HVAC AIR DEVICE SCHEDULE

TYPE MARK	MANUFACTURER	MODEL	SERVICE	DESCRIPTION	MOUNTING TYPE	MATERIAL	NECK SIZE	FACE SIZE	NOTES
CD-1	PRICE	AMD	SUPPLY	LOUVERED FACE DIRECTIONAL DIFFUSER	LAY-IN	ALUMINUM	18\"/>		

RTU-1, 2, & 3 TEST AND BALANCE NOTES

- TEST AND BALANCE CONTRACTOR TO OBTAIN INITIAL BALANCE OF COOLING CFM FOR RTU USING FAN SHEAVE ADJUSTMENT TO WITHIN +3% SCHEDULED COOLING CFM. PRODIGY CONTROLLER MAY BE USED FOR FINAL 5% TO OBTAIN SCHEDULED COOLING CFM.
- SET MINIMUM OUTSIDE AIR DAMPER POSITION FOR COOLING AND VERIFY OUTSIDE AIR CFM PER RTU SCHEDULE.
- NOT USED
- NOT USED
- USING PRODIGY CONTROLLER, VERIFY HEATING CFM EQUALS COOLING CFM.
- ALL PRODIGY CONTROLLER SETTINGS OTHER THAN THOSE MENTIONED ABOVE SHALL REMAIN AS THEIR DEFAULT VALUE AS SET FROM THE FACTORY.
- VERIFY POSITIVE BUILDING PRESSURE.

AIR BALANCE SCHEDULE

SYSTEM	CFM
RTU-1	+610
RTU-2	+900
RTU-3	+540
EF-1	-1550
EF-2	-60
BUILDING POSITIVE PRESSURE	+500

RTU-1, 2, & 3 SEQUENCE OF OPERATION

- SUPPLY AIR BLOWER SPEED
- UNIT HAS FOLLOWING SUPPLY AIR BLOWER SPEED SETTINGS THAT PERTAIN TO THIS INSTALLATION:
- COOLING AIR BLOWER SPEED
 - HEATING AIR BLOWER SPEED
- COOLING MODE
- Y1 DEMAND: COMPRESSOR 1 OPERATES AND SUPPLY AIR BLOWER OPERATES AT COOLING SPEED.
 - Y2 DEMAND: ALL COMPRESSORS OPERATE AND SUPPLY AIR BLOWER OPERATES AT COOLING SPEED.
- DEHUMIDIFICATION MODE
- IF THE UNIT RECEIVES A CALL FOR DEHUMIDIFICATION, ECONOMIZER FREE COOLING IS LOCKED OUT (ON UNITS EQUIPPED WITH ECONOMIZER).
 - CALL FOR DEHUMIDIFICATION, NO Y1, Y2 DEMAND: 1ST STAGE COMPRESSOR OPERATES, SUPPLY AIR BLOWER OPERATES AT COOLING SPEED, AND THE REHEAT VALVE IS ENERGIZED.
 - Y1 DEMAND WITH A CALL FOR DEHUMIDIFICATION: ALL COMPRESSORS OPERATE, SUPPLY AIR BLOWER OPERATES AT COOLING SPEED AND THE REHEAT VALVE IS ENERGIZED.
 - Y2 DEMAND WITH A CALL FOR DEHUMIDIFICATION: ALL COMPRESSORS OPERATE, SUPPLY AIR BLOWER OPERATES AT COOLING SPEED, AND THE REHEAT VALVE IS DE-ENERGIZED.
- HEATING MODE (ELECTRIC HEAT)
- Y1 DEMAND: 1ST STAGE ELECTRIC HEAT IS ENERGIZED AND THE SUPPLY AIR BLOWER OPERATES AT HEATING SPEED.
 - Y2 DEMAND: 2ND STAGE ELECTRIC HEAT IS ENERGIZED AND THE SUPPLY AIR BLOWER OPERATES AT HEATING SPEED.
- MODULATING OUTDOOR AIR DAMPER
- THE MINIMUM DAMPER POSITION FOR 'OCCUPIED HIGH BLOWER' IS ADJUSTED DURING UNIT SETUP TO PROVIDE MINIMUM FRESH AIR REQUIREMENTS PER RTU SCHEDULE.
 - WHEN SUPPLY AIR BLOWER IS OFF, THE OUTDOOR AIR DAMPER IS CLOSED.
 - WHEN UNIT IS IN OCCUPIED MODE AND SUPPLY AIR BLOWER IS OPERATING, THE OUTDOOR AIR DAMPER IS AT MINIMUM 'HIGH BLOWER' POSITION.

HVAC AIR CURTAIN SCHEDULE

MARK	AREA SERVED	BASIS OF DESIGN		UNIT POWER		MOUNTING HEIGHT	NOTES
		MANUFACTURER	MODEL	VOLTAGE	PHASE		
AC-1	STAGING	POWERED AIRE	BCE-1-48	2155 CFM	0.5	120 V	1-4
AC-2	DELIVERY VESTIBULE	POWERED AIRE	BCE-1-48	2155 CFM	0.5	120 V	1-4

LENNOX SETUP PARAMETERS - FLORIDA STORES (R2)

- UNIT ID CONFIGURATIONS (MECHANICAL CONTRACTOR TO DEFINE / AS APPLICABLE):
- BACNET CONFIGURATION: GO TO SETTINGS-GENERAL-CONFIGURATION ID POSITION 5 SET TO 'B'.
 - NETWORK CONFIGURATION: GO TO SETUP-NETWORK INTEGRATION, SET TO BACNET.
 - CONTROL MODE: SET CONTROL MODE TO ROOM SENSOR, CO2, TEMP & HUMIDITY (PER UNIT, AS NEEDED).
- INDIVIDUAL PARAMETER CONFIGURATIONS (MECHANICAL CONTRACTOR TO DEFINE / AS APPLICABLE):
- PARAMETER 105 DEHUMID MODE: 7 NO CONDITIONS.
 - PARAMETER 106 DEMAND SETPOINT: 50. THIS IS A CENTERED SET POINT (H).
 - PARAMETER 107 DEHUMID DEADBAND: 3 (DEFAULT) THIS IS THE ACTUAL +/- VALUE.
 - PARAMETER 117 CO2 DAMPER MAX OPEN %: 50.
 - PARAMETER 118 CO2 START OPEN PPM: 1200.
 - PARAMETER 119 CO2 FULL OPEN PPM: 1500.
 - PARAMETER 137 CO2 HEAT SET POINT: 68 (BACK UP).
 - PARAMETER 139 CO2 COOLING SET POINT: 72 (BACK UP).
 - PARAMETER 154 CO2 BLOWER MODE: ON CONTINUOUS.

CFM VALUES / MS&V FAN SPEEDS (AIR BALANCER TO DEFINE / IF APPLICABLE):

- HIGH COOL CFM VALUE: PER THE HVAC SCHEDULE.
- LOW COOL CFM VALUE: MATCH THE HIGH COOL CFM VALUE.
- VENTILATION CFM VALUE: MATCH THE HIGH COOL CFM VALUE.

2600 Mainland Center Parkway
Suite #200
Maitland, FL 32751
P (407) 661-9100
F (407) 661-9101
c-p.com

CUHACI PETERSON

Copyright © All rights reserved. No part of this document may be reproduced without the written permission of the copyright owner. This document is the property of C. P. Peterson & Associates, Inc. and is loaned to you for your use only. It is not to be distributed, copied, or otherwise used in any way without the written permission of the copyright owner. Any use or reproduction of this document without the written permission from C. P. Peterson & Associates, Inc. is strictly prohibited.

CLIENT NAME
WAWA
260 WEST BALTIMORE PIKE
WAWA, PENNSYLVANIA 19063

PROJECT NAME
WAWA F88FB V2021.3
STORE #5452
S. JOHN YOUNG PKWY & DESTINATION PKWY, ORLANDO, FL

PROFESSIONAL ENGINEER
No. 78474
STATE OF FLORIDA
Professional Engineer
06/01/2023

Digitally signed by Jose J Diaz-Velazquez
This document has been digitally signed and sealed on the date adjacent to the text. Printed copies of this document are not considered signed and sealed on the signature must be verified on any electronic copies.
Date: 2023.06.07 09:59:35-04'00'

Revision Schedule
Date: 06/07/2023
Description: PERMIT SET

ORANGE COUNTY
GOVERNMENT
Permit # B23903297
Date: 03/01/24
M3.0