



ELECTRIC HEATER, EHH, CENTERED OVER DOOR, AC TO MEET ARCH RECOMMENDATIONS.

MONUMENT AIR DOOR IN CEILING, CENTERED ON DRIVE THRU DOOR DIVERTER, AT APPROX 4' OFF EXTERIOR WALL. PROVIDE WITH COA DIVERTER BOX MOUNTED PER INSTALLATION INSTRUCTIONS. DIVERTER BOX AND INSTALLATION INSTRUCTIONS MUST BE PROVIDED TO CONTRACTOR. SEE WIRING DIAGRAM ON SHEET 16501 FOR MORE INFORMATION.

MEAL DELIVERY CANOPY. SEE ARCHITECTURAL.

MOUNT AC# MAIN TRUNK LINE AS TIGHT AS POSSIBLE TO STRUCTURE.

SEAL PENETRATIONS IN SMOKE DRAFT CURTAIN. AIR TIGHT. SEE ARCH PLANS FOR CONSTRUCTION.

Architect