





FAN SCHEDULE											
MARK	SERVICE	CFM	E.S.P. "WG	RPM	MOTOR HP	VOLTS/PH	MANUFACTURER	MODEL	TYPE	WEIGHT	NOTES
KEF-1	HOOD #1	3583	1.875	968	5.00	208/3	CAPTIVEARE	DU240FA	ROOF UPBLAST FAN	300	1,3,5,6,9
KEF-2	HOOD #2	1800	1.20	1064	1.00	208/3	CAPTIVE ARE	DU180FA	ROOF UPBLAST FAN	150	1,3,5,6,9
KEF-3	HOOD #3	1875	1.25	1089	1.50	208/3	CAPTIVEARE	DU180FA	ROOF UPBLAST FAN	176	1,3,5,6,9
DEF-1	DISH MACHINE	600	0.50	1255	0.33	115/1	CAPTIVEARE	DU039FA	ROOF UPBLAST FAN	69	3,4,6,9
TEF-1	RESTROOMS	150	0.20	765	0.09	115/1	CAPTIVE ARE	CFA-0200-CA	CEILING CABINET FAN	13	2,4,7,9
TEF-2	RESTROOMS	150	0.20	765	0.09	115/1	CAPTIVE ARE	CFA-0200-CA	CEILING CABINET FAN	13	2,4,7,9
MAU-1	COOKLINE HOODS	5806	0.55	1531	10.00	208/3	CAPTIVEARE	A3-0500	ROOF MAKEUP FAN	1957	1,3,4,6,8,9

NOTES:

- THE UTILITY CABINET SHALL BE FACTORY EQUIPPED WITH A PREWIRE PACKAGE TO INTERLOCK THE EXHAUST FANS WITH THE MAKEUP AIR UNIT.
- THE FAN SHALL BE FACTORY EQUIPPED WITH AN INDEPENDENT WEATHER PROOF DISCONNECT SWITCH IN SIGHT OF THE EQUIPMENT.
- WEATHER PROOF DISCONNECT SWITCH AND INTERNAL WIRING SHALL BE FACTORY INSTALLED.
- THE FAN SHALL BE FACTORY EQUIPPED WITH A GRAVITY BACKDRAFT DAMPER.
- THE FAN SHALL BE FACTORY EQUIPPED WITH CURB MOUNTED HINGE KITS.
- FURNISHED WITH HOOD PACKAGE, INSTALLED BY THE MECHANICAL CONTRACTOR.
- FURNISHED AND INSTALLED BY THE MECHANICAL CONTRACTOR.
- THE MAKEUP AIR UNIT SHALL BE FACTORY EQUIPPED WITH (2) CIRCUITS OF DX COOLING FOR DUAL STAGE OPERATION, RATED FOR 1124 MBH TOTAL CAPACITY/ 73.0 MBH SENSIBLE CAPACITY, AND A COOLING INTAKE THERMOSTAT. THE MECHANICAL CONTRACTOR SHALL FIELD ADJUST TO 75F.
- ALL EQUIPMENT SHALL BE INSTALLED AND STARTED-UP PER THE MANUFACTURER'S "INSTALLATION, OPERATION, AND MAINTENANCE MANUALS". THE MECHANICAL CONTRACTOR SHALL COMPLETE ALL FACTORY "START-UP AND MAINTENANCE DOCUMENTATION" INCLUDED WITH THE EQUIPMENT PACKAGE, AND PROVIDE A COPY TO THE BARTACO CONSTRUCTION MANAGER.
- THE MAKEUP AIR UNIT IS FACTORY EQUIPPED WITH DIRECT FIRED GAS COMBUSTION HEAT EXCHANGER, RATED FOR 313 MBH INPUT / 288 MBH OUTPUT.

HVAC SEQUENCE OF OPERATION						
MARK	SERVICE	FUNCTION	START TIME	COOLING SETPOINT(°F)	HEATING SETPOINT(°F)	NOTES
AHU-1	DINING	OCCUPIED	9:30 AM	72	72	1 THRU 3
		UNOCCUPIED	12:30 AM	85	55	
AHU-2	DINING	OCCUPIED	9:30 AM	72	72	1 THRU 3
		UNOCCUPIED	12:30 AM	85	55	
AHU-3	KITCHEN	OCCUPIED	9:40 AM	72	72	1 THRU 3
		UNOCCUPIED	12:30 AM	85	55	
AHU-4	KITCHEN	OCCUPIED	8:00 AM	72	72	1 THRU 3
		UNOCCUPIED	1:00 AM	85	55	

NOTES:

- UNIT FAN SHALL RUN CONTINUOUSLY DURING OCCUPIED HOURS, AND CYCLE ON DEMAND DURING UNOCCUPIED HOURS.
- UPON A CALL FOR COOLING:
  - COMPRESSORS TO CYCLE TO MAINTAIN THE SPACE SETTING, WITH THE GAS HEATER LOCKED OUT.
  - THERE SHALL BE A 2' DEAD BAND (ADJUSTABLE) BETWEEN THE 1ST AND 2ND STAGE OF COOLING.
  - THERE SHALL BE A 5 MINUTE (ADJUSTABLE) TIME DELAY BETWEEN THE 1ST AND 2ND STAGE OF COOLING.
- UPON A CALL FOR HEATING:
  - GAS FURNACE TO CYCLE TO MAINTAIN THE SPACE SETTING, WITH THE COMPRESSORS LOCKED OUT.
  - THERE SHALL BE A 2' DEAD BAND (ADJUSTABLE) BETWEEN THE 1ST AND 2ND STAGE OF HEATING.
  - THERE SHALL BE A 5 MINUTE (ADJUSTABLE) TIME DELAY BETWEEN THE 1ST AND 2ND STAGE OF HEATING.

FLY FAN SCHEDULE										
MARK	SERVICE	LENGTH	CFM	VOLTS/ PH	AMPS/HP	MANUFACTURER	MODEL	TYPE	WEIGHT	NOTES
FF-1	SERVICE DOOR	36"	1200	115/1	2.4 / 1/5	MARS	LRQ23F-1U-GR	WALL MNTD, DOWNBLAST	32	1 THRU 3
FF-2,3,4	DINING GARAGE DOOR	84"	2080	115/1	6.8 / 1/5	BERNER	PE06-C-2084A	WALL MNTD, DOWNBLAST	76	1 THRU 3

NOTES:

- INSTALL COMPLETE WITH MANUFACTURER AVAILABLE DOOR LIMIT MICRO SWITCH.
- UNIT SHALL HAVE A LOUVERED FACE.
- FAN SHALL BE FURNISHED AND INSTALLED BY THE GENERAL CONTRACTOR.

AIR DEVICE SCHEDULE										
MARK	PICTURE	FACE SIZE	TYPE	MOUNTING TYPE	MAXIMUM N.C.	DIRECTION	MANUFACTURER	MODEL	NOTES	
CD1		24x24	SUPPLY	LAY-IN	30	4-WAY	TITUS	OMNI	2,3,4,6,7	
DL		18x6	SUPPLY	DUCT MOUNTED				DL	1,2,7	
GD1		24x24	SUPPLY	SURFACE (GYP. CLG)	30	4-WAY	TITUS	TMSA-AA	2,3,4,6,7	
GD2		12x12	SUPPLY	SURFACE (GYP. CLG)	30	4-WAY	TITUS	TMSA-AA	2,3,4,6,7	
KD		24x24	SUPPLY	LAY-IN	30	1-WAY	TITUS	PAS-AA	1,3,7	
KR		24x24	RETURN	LAY-IN	30	1-WAY	TITUS	PAR-AA	1,3,7	
OD		24x24	SUPPLY	LAY-IN	30	4-WAY	TITUS	TMSA-AA	1,3,4,7	
SR1		24x16	RETURN	SURFACE (SDBCMALL)	30	1-WAY	TITUS	350RS	1,3,7	
RD		22"	SUPPLY	12"Ø EXPOSED DUCT	30	RADIAL	TITUS	TMR	2,3,7	

NOTES:

- AIR DEVICES MOUNTED ON A WHITE SURFACE IN BACK OF HOUSE SHALL BE INSTALLED WITH FACTORY APPLIED OFF WHITE FINISH.
- AIR DEVICES IN THE FRONT OF HOUSE SHALL BE INSTALLED WITH FACTORY MIL FINISH. THE PAINTING CONTRACTOR SHALL APPLY PAINT GRIP PRIMER.
- PROVIDE NECESSARY MOUNTING HARDWARE AND ACCESSORIES AS REQUIRED FOR INTENDED INSTALLATION.
- AIR DEVICE SHALL BE INSTALLED WITH MANUFACTURER AVAILABLE MOLDED INSULATION BACKING. FIELD FABRICATED INSULATION BACKING IS NOT ALLOWED (UNLESS FIRST APPROVED BY THE OWNER'S CONSTRUCTION MANAGER).
- AIR DEVICE NEAR THE EXHAUST HOOD CANOPY SHALL BE INSTALLED COMPLETE WITHOUT SUPPLY AIR FLOW PATTERN CONTROLLERS, TO PREVENT INTERFERENCE WITH EXHAUST CAPTURE AND CONTAINMENT.
- AIR DEVICE SHALL BE INSTALLED WITH ACCESSIBLE OPPOSED BLADE DAMPER FOR MANUAL VOLUME ADJUSTMENT.
- ACCEPTABLE MANUFACTURER FOR INSTALLED AIR DEVICE IS AS LISTED ONLY.

O/A VENTILATION SCHEDULE						
AREA SERVED	VENTILATION (OCCUPANCY)		VENTILATION (AREA)			
	# OF PEOPLE	CFM/PERSON	CFM	SQUARE FEET	CFM/SP	CFM
DINING	127	7.5	953	2109	0.18	380
KITCHEN	24	-	-	2002	-	-
RESTROOMS	-	-	-	494	-	-
SUBTOTALS	-	-	953	-	-	380
TOTAL O/A REQUIRED			1333 CFM			

NOTES:

CALCULATIONS ARE BASED ON 2018 IMC, TABLE 402.1

- OUTDOOR AIR DEMAND IS: - 1333 CFM
- OUTDOOR AIR PROVIDED IS: + 1440 CFM
- OUTDOOR AIR DIFFERENCE IS: + 107 CFM

TEST AND BALANCE NOTES	
1.	THE GENERAL CONTRACTOR SHALL SUBCONTRACT TO AN INDEPENDENT AIR TEST AND BALANCE CONTRACTOR FOR THE TESTING, ADJUSTING AND BALANCING OF ALL ENVIRONMENTAL SYSTEMS SHOWN OR SPECIFIED ON THE CONTRACT DOCUMENTS. THIS SHALL INCLUDE EQUIPMENT OPERATION IN COOLING, HEATING, AND DEHUMIDIFICATION OPERATIONAL MODES. THE WORK SHALL BE PERFORMED BY A FIRM CERTIFIED BY EITHER ABC OR NEBB, AND FOUR (4) COPIES OF THE FINAL REPORT, SUBMITTED ON CERTIFYING AGENCY FORMS, SHALL BE SUBMITTED TO THE BARTACO CONSTRUCTION MANAGER FOR APPROVAL. THE REPORT SHALL BEAR THE CERTIFICATION SEAL OF THE TAB SUPERVISOR IN CHARGE. REPORTS SHALL CONTAIN ALL AIR SIDE BALANCE DATA, INSTRUMENTS USED AND THEIR LATEST CALIBRATION DATES, PERSON(S) PERFORMING THE WORK AND A WRITTEN GUARANTEE THAT ALL TAB WORK WAS PERFORMED IN ACCORDANCE WITH THE CERTIFYING AGENCY STANDARDS AND PROCEDURES.
2.	THE TEST AND BALANCE REPORT SHALL INCLUDE OPERATIONAL DATA FOR EVERY COMPONENT OF THE COMPLETE MECHANICAL SYSTEM INCLUDING HVAC EQUIPMENT, HVAC AIR DEVICES, KITCHEN FANS, RESTROOM FANS, ETC. THIS DATA SHALL INCLUDE THE BALANCED OPERATING DATA FOR EQUIPMENT AS COMPARED TO THE DESIGN AIR BALANCE SCHEDULE ON THIS SHEET.
3.	FOR CLARIFICATION, THE ENGINEER OF RECORD WILL NOT BE ABLE TO REVIEW THE INSTALLED MECHANICAL SYSTEMS FOR POTENTIAL OPERATIONAL ISSUES OR INSTALLATION DEFICIENCIES WITHOUT THE FULL AND COMPLETE TEST AND BALANCE REPORT.

AIR BALANCE SCHEDULE						
MARK	DINING (CFM)			KITCHEN (CFM)		
	S/A	O/A	E/A	S/A	O/A	E/A
AHU-1	3600	720	-	-	-	-
AHU-2	3600	720	-	-	-	-
AHU-3	-	-	-	3600	720	-
AHU-4	-	-	-	2700	540	-
KEF-1	-	-	-	-	-	3583
KEF-2	-	-	-	-	-	1800
KEF-3	-	-	-	-	-	1975
DEF-1	-	-	-	-	-	600
TEF-1	-	-	-	150	-	-
TEF-2	-	-	-	150	-	-
MAU-1	-	-	-	-	-	5806
TOTAL	7200	1440	500	6300	7066	7858

DINING PRESSURIZATION (O/A) - (E/A) = 1140 CFM      KITCHEN PRESSURIZATION (O/A) - (E/A) = -792 CFM

NET BUILDING PRESSURIZATION (DINING + KITCHEN) = +348 CFM

ELECTRIC HEATER SCHEDULE								
MARK	TYPE	AREA SERVED	HEATING CAPACITY	MAXIMUM CFM	ELECTRICAL VOLT / PH	MANUFACTURER	MODEL	NOTES
PH-1,2,3,4	UNIT/CABINET	PATIO	6.0 kW	---	208/ 1	BROMIC	BH0420035	1,5,7,8

NOTES:

- COORDINATE POWER AND DISCONNECT REQUIREMENTS WITH THE ELECTRICAL CONTRACTOR.
- INSTALL COMPLETE WITH MANUFACTURER AVAILABLE SUSPENSION MOUNTING BRACKET.
- INCLUDE MANUFACTURER AVAILABLE INTEGRAL THERMOSTAT TO PREVENT FREEZING.
- INSTALL PER MANUFACTURER'S RECOMMENDATIONS FURNISHED BY OWNER, INSTALLED BY CONTRACTOR. STAINLESS STEEL CONSTRUCTION.
- POST MOUNT/WALL MOUNT.
- MANUAL IGNITION.
- PROVIDE WITH OPTIONAL MOUNTING KIT.
- INSTALL PER MANUFACTURER'S RECOMMENDATIONS FURNISHED AND INSTALLED BY CONTRACTOR.
- STAINLESS STEEL CONSTRUCTION.

SPLIT SYSTEM ELEC. COOLING/HEATING SCHEDULE				
AIR HANDLING UNIT	AHU-1	AHU-2	AHU-3	AHU-4
UNIT TAG	DINING	DINING	KITCHEN/BOH	KITCHEN/BOH
AREA SERVED	CARRIER	CARRIER	CARRIER	CARRIER
MANUFACTURER	40RUA	40RUA	40RUA	40RUA
MODEL NO.	40RUA	40RUA	40RUA	40RUA
INSTALLED (LBS)	425	425	425	404
FAN SECTION				
MOTOR HP	2.40	2.40	2.40	2.40
RATED CFM	3600	3600	3600	2700
DRIVE	STATIC	STATIC	STATIC	STATIC
E.S.P. (IWG)	0.80	0.80	0.80	0.80
MIN. OUTDOOR AIR (CFM)	720	720	720	540
ELECTRIC HEATING				
AMBIENT DB (°F)	18	18	18	18
M.A.T. DB (°F)	61.2	61.2	61.2	61.2
ELEC HEAT (KW@208V)	25.0	25.0	25.0	25.0
TEMPERATURE DIFF. (°F)	16.5	16.5	16.5	22.0
LEAVING AIR TEMP. (°F)	76.5	76.5	76.5	82.0
TOTAL UNIT ELECTRIC DATA				
VOLTS/PH/Hz	208/3/60	208/3/60	208/3/60	208/3/60
MCA (AMPS)	74.0	74.0	74.0	74.0
MOCP (AMPS)	80.0	80.0	80.0	80.0
MIN. COOLING PERFORMANCE				
NUMBER OF CIRCUITS	2	2	2	1
ENTERING DB/WB (°F)	80/67	80/67	80/67	80/67
AMBIENT DB (°F)	95	95	95	95
TOTAL CAP. (MBH)	123.2	123.2	123.2	94.0
SENSIBLE CAP. (MBH)	92.8	92.8	92.8	69.6
AIR COOLED CONDENSER UNIT				
UNIT TAG	CU-1	CU-2	CU-3	CU-4
MANUFACTURER	CARRIER	CARRIER	CARRIER	CARRIER
MODEL NO.	38AUD	38AUD	38AUD	38AUD
NOMINAL CAPACITY (TONS)	10.0	10.0	10.0	7.5
NUMBER OF CIRCUITS	2	2	2	1
INSTALLED (LBS)	516	516	516	391
EER/SEER	10.3/13.0	10.3/13.0	10.3/13.0	11.2/14.0
ELECTRIC DATA				
VOLTS/PH/Hz	208/3/60	208/3/60	208/3/60	208/3/60
MIN. OKT AMPS	39.0	39.0	39.0	37.0
MOCP	50.0	50.0	50.0	60.0

NOTES:

- CONDENSING UNIT SHALL BE FACTORY EQUIPPED WITH THE FOLLOWING OPTIONS/ ACCESSORIES: DX COIL, CONDENSER COIL HALL GUARD, THERMAL EXPANSION VALVE, DRAIN PAN, SIGHT GLASS, LIQUID LINE FILTER, LOW AMBIENT CONTROL KIT, AND ANTI-SHORT CYCLE TIMER.
- PROVIDE FIELD FABRICATED 20 GA. GALVANIZED STEEL AUXILIARY DRIP PAN WITH WATERIGHT SOLDERED CORNERS. PAN SHALL BE 2" DEEP AND EXTEND 2" BEYOND THE AIR HANDLING UNIT IN EACH DIRECTION.
- PROVIDE DUCT MOUNTED SUPPLY AIR SMOKE DETECTOR, CAPABLE OF SHUTTING DOWN THE AIR HANDLING UNIT UPON ACTIVATION. COORDINATE POWER AND DISCONNECT REQUIREMENTS WITH THE ELECTRICAL CONTRACTOR.
- COORDINATE REFRIGERANT SUCTION AND LIQUID LINE SIZING WITH MANUFACTURER REQUIREMENTS, AGAINST THE MAXIMUM DEVELOPED HORIZONTAL AND VERTICAL LINE LENGTHS REQUIRED WITH SITE CONDITIONS.
- COOLING LOADS LISTED ARE AT A.R.I. STANDARD.
- PROVIDE MANUFACTURER SUITABLE 24/7 AUTO CHANGEOVER DIGITAL THERMOSTAT WITH NIGHT SETBACK PROGRAMMING, AND CLEAR ACRYLIC LOCKABLE COVER. COORDINATE INSTALLED LOCATION WITH DECOR.
- FOR AIR HANDLERS INCLUDE TRANE CONDENSATE DRIP PANEL KITS, FIELD INSTALLED BY MECHANICAL CONTRACTOR.
- CONTACT MR. BOB VAN GUILDER (TRANE) AT (214) 957-3692 FOR PRICING AND VERIFY FINAL SELECTIONS FOR EQUIPMENT SELECTION INFORMATION AND ORDERING.

MECHANICAL LEGEND		
SYMBOL	ABBR.	DESCRIPTION
	CD	CEILING DIFFUSER - SUPPLY
	CD	CEILING DIFFUSER BELOW DUCT - SUPPLY
	SAD	RISER - SUPPLY AIR DUCT
	SAD	DROP - SUPPLY AIR DUCT
	CR	CEILING REGISTER - RETURN
	CR	CEILING REGISTER BELOW DUCT - RETURN
	RAD	RISER - RETURN AIR DUCT
	RAD	DROP - RETURN AIR DUCT
	CE	CEILING REGISTER - EXHAUST
	CE	CEILING REGISTER BELOW DUCT - EXHAUST
	EAD	RISER - EXHAUST AIR DUCT
	(L)	LINED DUCTWORK
	VD	MANUAL VOLUME DAMPER
	MD	MOTORIZED VOLUME DAMPER
	FC	FLEXIBLE CONNECTION
		NEW DUCT
	(C/D)	AIR DEVICE DESIGNATION
	TSTAT	PROGRAMMABLE THERMOSTAT
	SENS	REMOTE TEMPERATURE SENSOR
	SD	SMOKE DETECTOR
	POC	POINT OF CONNECTION
	CFM	CUBIC FEET PER MINUTE
	S/A	SUPPLY AIR
	O/A	OUTSIDE AIR
	E/A	EXHAUST AIR
	S.P.	STATIC PRESSURE
	FOH	FRONT OF HOUSE
	BOH	BACK OF HOUSE

MECHANICAL GENERAL NOTES	
1.	NOTE: FOR THE PURPOSE OF CLARITY AND LEGIBILITY, THE DRAWINGS ARE ESSENTIALLY DIAGRAMMATIC AND ALTHOUGH SIZES AND LOCATIONS OF EQUIPMENT ARE DRAWN TO SCALE WHEREVER POSSIBLE, THE CONTRACTOR SHALL MAKE USE OF ALL DATA IN ALL OF THE CONTRACT DOCUMENTS AND VERIFY THIS INFORMATION PRIOR TO ORDERING, FABRICATING OR INSTALLING ANY MATERIALS.
2.	THE MECHANICAL CONTRACTOR SHALL PROVIDE COMPLETE INFORMATION AND COORDINATE WITH THE OTHER CONTRACTORS AND TRADES AS REQUIRED FOR THE COMPLETION AND COORDINATION OF THE COMPLETE PROJECT.
3.	THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ADMINISTERING ALL WARRANTIES ON EQUIPMENT WHICH THEY FURNISH AND INSTALL.
4.	PROVIDE WRITTEN WARRANTY TO REPLACE ALL FAULTY MATERIALS AND/OR LABOR, AT NO COST TO TENANT, FOR A PERIOD OF ONE YEAR FROM DATE OF PERFORMANCE.
5.	ALL OUTDOOR AIR INTAKE BY MECHANICAL EQUIPMENT SHALL HAVE A MINIMUM 10'-0" HORIZONTAL CLEARANCE FROM THE DISCHARGE OF ANY EXHAUST FAN, RTU GAS EXHAUST OR PLUMBING VENT.
6.	PROVIDE VIBRATION ISOLATION DEVICES AND FLEXIBLE DUCT/ PIPING CONNECTIONS TO ALL MOVING MACHINERY NOT INTERNALLY ISOLATED.
7.	ALL DUCT DIMENSIONS SHOWN ON DRAWINGS ARE CLEAR INSIDE DIMENSIONS.
8.	THE MECHANICAL CONTRACTOR SHALL COORDINATE ALL DUCT AND DIFFUSER LOCATIONS WITH SPRINKLER PIPING, SPRINKLER HEADS AND LIGHT FIXTURES AS REQUIRED FOR A COMPLETE INSTALLATION.
9.	THE MECHANICAL CONTRACTOR SHALL COORDINATE WITH THE GENERAL CONTRACTOR AND OTHER TRADES ALL REQUIRED OPENINGS AND PENETRATIONS. ALL REQUIRED OPENINGS IN FOUNDATIONS, FLOORS, WALLS AND ROOF SHALL BE CONSTRUCTED INTO THE STRUCTURE WITH THE USE OF SLEEVES, CURBS, ETC. CUTTING AND PATCHING SHALL BE HELD TO A MINIMUM.
10.	ALL ITEMS PROJECTING THROUGH THE ROOF SHALL BE FLASHED THROUGH CURBS OR PIPE SEALS A MINIMUM OF 12" ABOVE THE ROOF. THE PIPE CURBS AND SEALS SHALL BE INSTALLED BY THE ROOFING CONTRACTOR. ENSURE THAT ALL ROOF OPENINGS ARE PROVIDED TO ACCOMMODATE ANY ELECTRICAL CONDUIT PENETRATIONS REQUIRED FOR POWER.
11.	COORDINATE THE INSTALLATION AND FINISH OF ALL SUPPLY AND RETURN AIR DEVICES. AIR DEVICES LOCATED IN GUEST AREAS (INCLUDING DINING AND BAR) SHALL BE PAINTED PER THE ARCHITECTURAL DRAWINGS FINISH SCHEDULE. ALL INTERIOR FACES OF DUCTWORK BEHIND RETURN AIR GRILLES SHALL BE PAINTED FLAT BACK FOR LINE OF SIGHT.
12.	ALL SUPPLY, RETURN, AND RESTROOM EXHAUST DUCTWORK SHALL BE INSTALLED AS HIGH AS POSSIBLE UNDER THE ROOF STRUCTURE.
13.	ALL RECTANGULAR, ROUND, AND FLEXIBLE DUCTWORK SHALL BE SIZED AS SHOWN ON THESE DRAWINGS, AND SHALL BE FABRICATED AND INSTALLED ACCORDING TO THE MOST RECENTLY PUBLISHED SMACNA STANDARDS. ALL JOINTS, SEAMS, AND CONNECTIONS MUST BE SECURELY FASTENED & SEALED BY APPROVED METHODS.
14.	ANY FLEXIBLE DUCTS SHALL BE INSTALLED IN CONCEALED SPACES ONLY. THE MAXIMUM ALLOWABLE LENGTH OF FLEXIBLE DUCT SHALL BE 5'-0". ALL FLEXIBLE DUCTS SHALL BE CONNECTED TO BRANCH RUNS AND FITTINGS WITH A PANDUIT-TYPE BAND, AND SHALL NOT BE ATTACHED DIRECTLY TO THE AIR DEVICE COLLAR.
15.	ALL PENETRATIONS IN FIRE RATED WALL ASSEMBLIES SHALL BE SEALED WITH UL LISTED FIRE STOPPING MATERIAL.
16.	MECHANICAL CONTRACTOR SHALL FURNISH AND INSTALL 4" BLACK OVER WHITE LAMINATE NAMEPLATE WITH 2" LETTERS VISIBLE ADJACENT TO DISCONNECT SWITCH FOR ROOFTOP UNITS AND ROOF MOUNTED FANS WITH THE AREAS THE UNITS SERVE.
17.	HVAC CONTROLS WORK SHALL BE INSTALLED AS FOLLOWS: <ul style="list-style-type: none"> <li>ALL LINE VOLTAGE WIRING, CONDUIT, DISCONNECT SWITCHES AND FINAL CONNECTION TO EQUIPMENT SHALL BE BY THE ELECTRICAL CONTRACTOR.</li> <li>ALL LOW VOLTAGE WIRING AND CONDUIT SHALL BE BY THE MECHANICAL CONTRACTOR.</li> <li>REMOTE ZONE COMBINATION TEMPERATURE/HUMIDITY SENSORS SHALL BE WALL MOUNTED AT 48" AFF, AND CLEARLY LABELED.</li> <li>PROGRAMMABLE THERMOSTATS IN THE MANAGER'S OFFICE SHALL BE WALL MOUNTED AT 48" AFF, VERTICALLY STACKED AND CLEARLY LABELED.</li> <li>TEMPERATURE CONTROL OF THE ROOFTOP UNIT OPERATION SHALL BE MADE BY WIRING FROM THE COMBINATION SENSOR BACK TO THE RESPECTIVE PROGRAMMABLE THERMOSTAT IN THE MANAGER'S OFFICE AND THEN TO THE APPROPRIATE ROOFTOP UNIT CONTROL BOARD. WIRING SHALL BE MADE WITH A SHIELDED 4-20mA SIGNAL GROUNDED TWISTED PAIR INSTALLED WITH CONTINUOUS NON-SPLICED LENGTH BETWEEN EACH DEVICE CONNECTION.</li> <li>HUMIDITY CONTROL OF THE ROOFTOP UNIT OPERATION SHALL BE MADE BY WIRING FROM THE COMBINATION SENSOR DIRECT BACK TO THE APPROPRIATE ROOFTOP UNIT CONTROL BOARD. WIRING SHALL BE MADE WITH A SHIELDED 4-20mA SIGNAL GROUNDED TWISTED PAIR INSTALLED WITH CONTINUOUS NON-SPLICED LENGTH BETWEEN EACH DEVICE CONNECTION.</li> <li>ROOFTOP UNITS SHALL BE SET TO RUN IN "FAN CONTINUOUS" MODE DURING OCCUPIED HOURS, DURING NIGHT SET-BACK HOURS, THE ROOFTOP UNITS SHALL RUN IN "FAN AUTO" MODE.</li></ul>

FAN SCHEDULE											
MARK	SERVICE	CFM	E.S.P. "WG	RPM	MOTOR HP	VOLTS/PH	MANUFACTURER	MODEL	TYPE	WEIGHT	NOTES
KEF-1	HOOD #1	3583	1.875	968	5.00	208/3	CAPTIVEARE	DU240FA	ROOF UPBLAST FAN	300	1,3,5,6,9
KEF-2	HOOD #2	1800	1.20	1064	1.00	208/3	CAPTIVE ARE	DU180FA	ROOF UPBLAST FAN	150	1,3,5,6,9
KEF-3	HOOD #3	1875	1.25	1089	1.50	208/3	CAPTIVEARE	DU180FA	ROOF UPBLAST FAN	176	1,3,5,6,9
DEF-1	DISH MACHINE	600	0.50	1255	0.33	115/1	CAPTIVEARE	DU030FA	ROOF UPBLAST FAN	69	2,4,7,9
TEF-1	RESTROOMS	150	0.20	765	0.09	115/1	CAPTIVE ARE	CFA-0200-CA	CEILING CABINET FAN	13	2,4,7,9
TEF-2	RESTROOMS	150	0.20	765	0.09	115/1	CAPTIVE ARE	CFA-0200-CA	CEILING CABINET FAN	13	2,4,7,9
MAU-1	COOKLINE HOODS	5806	0.55	1531	10.00	208/3	CAPTIVEARE	A3-0500	ROOF MAKEUP FAN	1957	1,3,4,6,8,9

NOTES:

- THE UTILITY CABINET SHALL BE FACTORY EQUIPPED WITH A PREWIRE PACKAGE TO INTERLOCK THE EXHAUST FANS WITH THE MAKEUP AIR UNIT.
- THE FAN SHALL BE FACTORY EQUIPPED WITH AN INDEPENDENT WEATHER PROOF DISCONNECT SWITCH IN SIGHT OF THE EQUIPMENT.
- WEATHER PROOF DISCONNECT SWITCH AND INTERNAL WIRING SHALL BE FACTORY INSTALLED.
- THE FAN SHALL BE FACTORY EQUIPPED WITH A GRAVITY BACKDRAFT DAMPER.
- THE FAN SHALL BE FACTORY EQUIPPED WITH CURB MOUNTED HINGE KITS.
- FURNISHED WITH HOOD PACKAGE, INSTALLED BY THE MECHANICAL CONTRACTOR.
- FURNISHED AND INSTALLED BY THE MECHANICAL CONTRACTOR.
- THE MAKEUP AIR UNIT SHALL BE FACTORY EQUIPPED WITH (2) CIRCUITS OF DX COOLING FOR DUAL STAGE OPERATION, RATED FOR 1124 MBH TOTAL CAPACITY/ 73.0 MBH SENSIBLE CAPACITY, AND A COOLING INTAKE THERMOSTAT. THE MECHANICAL CONTRACTOR SHALL FIELD ADJUST TO 75F.
- ALL EQUIPMENT SHALL BE INSTALLED AND STARTED-UP PER THE MANUFACTURER'S "INSTALLATION, OPERATION, AND MAINTENANCE MANUALS". THE MECHANICAL CONTRACTOR SHALL COMPLETE ALL FACTORY "START-UP AND MAINTENANCE DOCUMENTATION" INCLUDED WITH THE EQUIPMENT PACKAGE, AND PROVIDE A COPY TO THE BARTACO CONSTRUCTION MANAGER.
- THE MAKEUP AIR UNIT IS FACTORY EQUIPPED WITH DIRECT FIRED GAS COMBUSTION HEAT EXCHANGER, RATED FOR 313 MBH INPUT / 288 MBH OUTPUT.

HVAC SEQUENCE OF OPERATION						
MARK	SERVICE	FUNCTION	START TIME	COOLING SETPOINT(°F)	HEATING SETPOINT(°F)	NOTES
AHU-1	DINING	OCCUPIED	9:30 AM	72	72	1 THRU 3
		UNOCCUPIED	12:30 AM	85	55	
AHU-2	DINING	OCCUPIED	9:30 AM	72	72	1 THRU 3
		UNOCCUPIED	12:30 AM	85	55	
AHU-3	KITCHEN	OCCUPIED	9:40 AM	72	72	1 THRU 3
		UNOCCUPIED	12:30 AM	85	55	
AHU-4	KITCHEN	OCCUPIED	8:00 AM	72	72	1 THRU 3
		UNOCCUPIED	1:00 AM	85	55	

NOTES:

- UNIT FAN SHALL RUN CONTINUOUSLY DURING OCCUPIED HOURS, AND CYCLE ON DEMAND DURING UNOCCUPIED HOURS.
- UPON A CALL FOR COOLING:
  - COMPRESSORS TO CYCLE TO MAINTAIN THE SPACE SETTING, WITH THE GAS HEATER LOCKED OUT.
  - THERE SHALL BE A 2F DEAD BAND (ADJUSTABLE) BETWEEN THE 1ST AND 2ND STAGE OF COOLING.
  - THERE SHALL BE A 5 MINUTE (ADJUSTABLE) TIME DELAY BETWEEN THE 1ST AND 2ND STAGE OF COOLING.
- UPON A CALL FOR HEATING:
  - GAS FURNACE TO CYCLE TO MAINTAIN THE SPACE SETTING, WITH THE COMPRESSORS LOCKED OUT.
  - THERE SHALL BE A 2F DEAD BAND (ADJUSTABLE) BETWEEN THE 1ST AND 2ND STAGE OF HEATING.
  - THERE SHALL BE A 5 MINUTE (ADJUSTABLE) TIME DELAY BETWEEN THE 1ST AND 2ND STAGE OF HEATING.

FLY FAN SCHEDULE										
MARK	SERVICE	LENGTH	CFM	VOLTS/ PH	AMPS/HP	MANUFACTURER	MODEL	TYPE	WEIGHT	NOTES
FF-1	SERVICE DOOR	36"	1200	115/1	2.4 / 1/6	MARS	LPV236-1U-0B	WALL MNTD, DOWNBLAST	32	1 THRU 3

NOTES:

- INSTALL COMPLETE WITH MANUFACTURER AVAILABLE DOOR LIMIT MICRO SWITCH.
- UNIT SHALL HAVE A LOUVERED FACE.
- FAN SHALL BE FURNISHED AND INSTALLED BY THE GENERAL CONTRACTOR.

AIR DEVICE SCHEDULE									
MARK	PICTURE	FACE SIZE	TYPE	MOUNTING TYPE	MAXIMUM N.C.	DIRECTION	MANUFACTURER	MODEL	NOTES
CD1		24x24	SUPPLY	LAY-IN	30	4-WAY	TITUS	OMNI	2,3,4,6,7
DL		18x6	SUPPLY	DUCT MOUNTED	30	1-WAY	TITUS	DL	1,2,7
GD1		24x24	SUPPLY	SURFACE (GYP. CLG)	30	4-WAY	TITUS	TMSA-AA	2,3,4,6,7
GD2		12x12	SUPPLY	SURFACE (GYP. CLG)	30	4-WAY	TITUS	TMSA-AA	2,3,4,6,7
KD		24x24	SUPPLY	LAY-IN	30	1-WAY	TITUS	PAS-AA	1,3,7
KR		24x24	RETURN	LAY-IN	30	1-WAY	TITUS	PAR-AA	1,3,7
OD		24x24	SUPPLY	LAY-IN	30	4-WAY	TITUS	TMSA-AA	1,3,4,7
SR1		24x16	RETURN	SURFACE (SDBCMALL)	30	1-WAY	TITUS	350RS	1,3,7
RD		22"	SUPPLY	12"Ø EXPOSED DUCT	30	RADIAL	TITUS	TMR	2,3,7

NOTES:

- AIR DEVICES MOUNTED ON A WHITE SURFACE IN BACK OF HOUSE SHALL BE INSTALLED WITH FACTORY APPLIED OFF WHITE FINISH.
- AIR DEVICES IN THE FRONT OF HOUSE SHALL BE INSTALLED WITH FACTORY MIL FINISH. THE PAINTING CONTRACTOR SHALL APPLY PAINT GRIP PRIMER.
- PROVIDE NECESSARY MOUNTING HARDWARE AND ACCESSORIES AS REQUIRED FOR INTENDED INSTALLATION.
- AIR DEVICE SHALL BE INSTALLED WITH MANUFACTURER AVAILABLE MOLDED INSULATION BACKING. FIELD FABRICATED INSULATION BACKING IS NOT ALLOWED (UNLESS FIRST APPROVED BY THE OWNER'S CONSTRUCTION MANAGER).
- AIR DEVICE NEAR THE EXHAUST HOOD CANOPY SHALL BE INSTALLED COMPLETE WITHOUT SUPPLY AIR FLOW PATTERN CONTROLLERS, TO PREVENT INTERFERENCE WITH EXHAUST CAPTURE AND CONTAINMENT.
- AIR DEVICE SHALL BE INSTALLED WITH ACCESSIBLE OPPOSED BLADE DAMPER FOR MANUAL VOLUME ADJUSTMENT.
- ACCEPTABLE MANUFACTURER FOR INSTALLED AIR DEVICE IS AS LISTED ONLY.

O/A VENTILATION SCHEDULE						
AREA SERVED	VENTILATION (OCCUPANCY)			VENTILATION (AREA)		
	# OF PEOPLE	CFM/PERSON	CFM	SQUARE FEET	CFM/SF	CFM
DINING	127	7.5	953	2109	0.18	380
KITCHEN	24	-	-	2002	-	-
RESTROOMS	-	-	-	494	-	-
SUBTOTALS	-	-	953	-	-	380
TOTAL O/A REQUIRED			1333 CFM	1333 CFM		

NOTES:

CALCULATIONS ARE BASED ON 2018 IMC, TABLE 402.1

- OUTDOOR AIR DEMAND IS: - 1333 CFM
- OUTDOOR AIR PROVIDED IS: + 1440 CFM
- OUTDOOR AIR DIFFERENCE IS: + 107 CFM

TEST AND BALANCE NOTES	
1.	THE GENERAL CONTRACTOR SHALL SUBCONTRACT TO AN INDEPENDENT AIR TEST AND BALANCE CONTRACTOR FOR THE TESTING, ADJUSTING AND BALANCING OF ALL ENVIRONMENTAL SYSTEMS SHOWN OR SPECIFIED ON THE CONTRACT DOCUMENTS. THIS SHALL INCLUDE EQUIPMENT OPERATION IN COOLING, HEATING, AND DEHUMIDIFICATION OPERATIONAL MODES. THE WORK SHALL BE PERFORMED BY A FIRM CERTIFIED BY EITHER ABC OR NEBB, AND FOUR (4) COPIES OF THE FINAL REPORT, SUBMITTED ON CERTIFYING AGENCY FORMS, SHALL BE SUBMITTED TO THE BARTACO CONSTRUCTION MANAGER FOR APPROVAL. THE REPORT SHALL BEAR THE CERTIFICATION SEAL OF THE TAB SUPERVISOR IN CHARGE. FACTORY SHALL CONTAIN ALL AIR SIDE BALANCE SCHEDULE ON THIS SHEET.
2.	THE TEST AND BALANCE REPORT SHALL INCLUDE OPERATIONAL DATA FOR EVERY COMPONENT OF THE COMPLETE MECHANICAL SYSTEM INCLUDING HVAC EQUIPMENT, HVAC AIR DEVICES, KITCHEN FANS, RESTROOM FANS, ETC. THIS DATA SHALL INCLUDE THE BALANCED OPERATING DATA FOR EQUIPMENT AS COMPARED TO THE DESIGN AIR BALANCE SCHEDULE ON THIS SHEET.
3.	FOR CLARIFICATION, THE ENGINEER OF RECORD WILL NOT BE ABLE TO REVIEW THE INSTALLED MECHANICAL SYSTEMS FOR POTENTIAL OPERATIONAL ISSUES OR INSTALLATION DEFICIENCIES WITHOUT THE FULL AND COMPLETE TEST AND BALANCE REPORT.

AIR BALANCE SCHEDULE						
MARK	DINING (CFM)			KITCHEN (CFM)		
	S/A	O/A	E/A	S/A	O/A	E/A
AHU-1	3600	720	-	-	-	-
AHU-2	3600	720	-	-	-	-
AHU-3	-	-	-	3600	720	-
AHU-4	-	-	-	2700	540	-
KEF-1	-	-	-	-	-	3583
KEF-2	-	-	-	-	-	1800
KEF-3	-	-	-	-	-	1975
DEF-1	-	-	-	-	-	600
TEF-1	-	-	-	150	-	-
TEF-2	-	-	-	150	-	-
MAU-1	-	-	-	-	-	5806
TOTAL	7200	1440	500	6300	7066	7858

DINING PRESSURIZATION (O/A) - (E/A) = 1140 CFM      KITCHEN PRESSURIZATION (O/A) - (E/A) = -792 CFM

NET BUILDING PRESSURIZATION (DINING + KITCHEN) = +348 CFM

ELECTRIC HEATER SCHEDULE								
MARK	TYPE	AREA SERVED	HEATING CAPACITY	MAXIMUM CFM	ELECTRICAL VOLT / PH	MANUFACTURER	MODEL	NOTES
PH-1,2,3,4,5	UNIT/CABINET	PATIO	6.0 kW	---	208/ 1	BROMIC	BH0420035	1,5,7,8

NOTES:

- COORDINATE POWER AND DISCONNECT REQUIREMENTS WITH THE ELECTRICAL CONTRACTOR.
- INSTALL COMPLETE WITH MANUFACTURER AVAILABLE SUSPENSION MOUNTING BRACKET.
- INCLUDE MANUFACTURER AVAILABLE INTEGRAL THERMOSTAT TO PREVENT FREEZING.
- INSTALL PER MANUFACTURER'S RECOMMENDATIONS FURNISHED BY OWNER, INSTALLED BY CONTRACTOR. STAINLESS STEEL CONSTRUCTION.
- POST MOUNT/WALL MOUNT.
- MANUAL IGNITION.
- PROVIDE WITH OPTIONAL MOUNTING KIT.
- INSTALL PER MANUFACTURER'S RECOMMENDATIONS FURNISHED AND INSTALLED BY CONTRACTOR.
- STAINLESS STEEL CONSTRUCTION.

SPLIT SYSTEM ELEC. COOLING/HEATING SCHEDULE				
AIR HANDLING UNIT	AHU-1	AHU-2	AHU-3	AHU-4
UNIT TAG	DINING	DINING	KITCHEN/BOH	KITCHEN/BOH
AREA SERVED	CARRIER	CARRIER	CARRIER	CARRIER
MANUFACTURER	40RUA	40RUA	40RUA	40RUA
MODEL NO.	40RUA	40RUA	40RUA	40RUA
INSTALLED (LBS)	425	425	425	404
FAN SECTION				
MOTOR HP	2.40	2.40	2.40	2.40
RATED CFM	3600	3600	3600	2700
DRIVE	STATIC	STATIC	STATIC	STATIC
E.S.P. (W/G)	0.80	0.80	0.80	0.80
MIN. OUTDOOR AIR (CFM)	720	720	720	540
ELECTRIC HEATING				
AMBIENT DB (°F)	18	18	18	18
M.A.T. DB (°F)	61.2	61.2	61.2	61.2
ELEC HEAT (KW@208V)	25.0	25.0	25.0	25.0
TEMPERATURE DIFF. (°F)	16.5	16.5	16.5	22.0
LEAVING AIR TEMP. (°F)	76.5	76.5	76.5	82.0
TOTAL UNIT ELECTRIC DATA				
VOLTS/PH/Hz	208/3/60	208/3/60	208/3/60	208/3/60
MCA (AMPS)	74.0	74.0	74.0	74.0
MOCP (AMPS)	80.0	80.0	80.0	80.0
MIN. COOLING PERFORMANCE				
NUMBER OF CIRCUITS	2	2	2	1
ENTERING DB/WB (°F)	80/67	80/67	80/67	80/67
AMBIENT DB (°F)	95	95	95	95
TOTAL CAP. (MBH)	123.2	123.2	123.2	94.0
SENSIBLE CAP. (MBH)	92.8	92.8	92.8	69.6
AIR COOLED CONDENSER UNIT				
UNIT TAG	CU-1	CU-2	CU-3	CU-4
MANUFACTURER	CARRIER	CARRIER	CARRIER	CARRIER
MODEL NO.	38AUD	38AUD	38AUD	38AUD
NOMINAL CAPACITY (TONS)	10.0	10.0	10.0	7.5
NUMBER OF CIRCUITS	2	2	2	1
INSTALLED (LBS)	516	516	516	391
EER/SEER	10.3/13.0	10.3/13.0	10.3/13.0	11.2/14.0
ELECTRIC DATA				
VOLTS/PH/Hz	208/3/60	208/3/60	208/3/60	208/3/60
MIN. CKT AMPS	39.0	39.0	39.0	37.0
MOCP	50.0	50.0	50.0	60.0

NOTES:

- CONDENSING UNIT SHALL BE FACTORY EQUIPPED WITH THE FOLLOWING OPTIONS/ ACCESSORIES: DX COIL, CONDENSER COIL H/L GUARD, THERMAL EXPANSION VALVE, DRAIN PAN, SIGHT GLASS, LIQUID LINE FILTER, LOW AMBIENT CONTROL KIT, AND ANTI-SHORT CYCLE TIMER.
- PROVIDE FIELD FABRICATED 20 GA. GALVANIZED STEEL AUXILIARY DRIP PAN WITH WATERIGHT SOLDERED CORNERS. PAN SHALL BE 2" DEEP AND EXTEND 2" BEYOND THE AIR HANDLING UNIT IN EACH DIRECTION.
- PROVIDE DUCT MOUNTED SUPPLY AIR SMOKE DETECTOR, CAPABLE OF SHUTTING DOWN THE AIR HANDLING UNIT UPON ACTIVATION. COORDINATE POWER AND DISCONNECT REQUIREMENTS WITH THE ELECTRICAL CONTRACTOR.
- COORDINATE REFRIGERANT SUCTION AND LIQUID LINE SIZING WITH MANUFACTURER REQUIREMENTS, AGAINST THE MAXIMUM DEVELOPED HORIZONTAL AND VERTICAL LINE LENGTHS REQUIRED WITH SITE CONDITIONS.
- COOLING LOADS LISTED ARE AT A.R.I. STANDARD.
- PROVIDE MANUFACTURER SUITABLE 24/7 AUTO CHANGEOVER DIGITAL THERMOSTAT WITH NIGHT SETBACK PROGRAMMING, AND CLEAR ACRYLIC LOCKABLE COVER. COORDINATE INSTALLED LOCATION WITH DECOR.
- FOR AIR HANDLERS INCLUDE TRANE CONDENSATE DRIP PANEL KITS, FIELD INSTALLED BY MECHANICAL CONTRACTOR.
- CONTACT MR. BOB VAN GUILDER (TRANE) AT (214) 957-3692 FOR PRICING AND VERIFY FINAL SELECTIONS FOR EQUIPMENT SELECTION INFORMATION AND ORDERING.

MECHANICAL LEGEND		
SYMBOL	ABBR.	DESCRIPTION
	CD	CEILING DIFFUSER - SUPPLY
	CD	CEILING DIFFUSER BELOW DUCT - SUPPLY
	SAD	RISER - SUPPLY AIR DUCT
	SAD	DROP - SUPPLY AIR DUCT
	CR	CEILING REGISTER - RETURN
	CR	CEILING REGISTER BELOW DUCT - RETURN
	RAD	RISER - RETURN AIR DUCT
	RAD	DROP - RETURN AIR DUCT
	CE	CEILING REGISTER - EXHAUST
	CE	CEILING REGISTER BELOW DUCT - EXHAUST
	EAD	RISER - EXHAUST AIR DUCT
	(L)	LINED DUCTWORK
	VD	MANUAL VOLUME DAMPER
	MD	MOTORIZED VOLUME DAMPER
	FC	FLEXIBLE CONNECTION
		NEW DUCT
	(C/D)	AIR DEVICE DESIGNATION
	TSTAT	PROGRAMMABLE THERMOSTAT
	SENS	REMOTE TEMPERATURE SENSOR
	SD	SMOKE DETECTOR
	POC	POINT OF CONNECTION
	CFM	CUBIC FEET PER MINUTE
	S/A	SUPPLY AIR
	O/A	OUTSIDE AIR
	E/A	EXHAUST AIR
	S.P.	STATIC PRESSURE
	FOH	FRONT OF HOUSE
	BOH	BACK OF HOUSE


MECHANICAL GENERAL NOTES	
1.	NOTE: FOR THE PURPOSE OF CLARITY AND LEGIBILITY, THE DRAWINGS ARE ESSENTIALLY DIAGRAMMATIC AND ALTHOUGH SIZES AND LOCATIONS OF EQUIPMENT ARE DRAWN TO SCALE WHEREVER POSSIBLE, THE CONTRACTOR SHALL MAKE USE OF ALL DATA IN ALL OF THE CONTRACT DOCUMENTS AND VERIFY THIS INFORMATION PRIOR TO ORDERING, FABRICATING OR INSTALLING ANY MATERIALS.
2.	THE MECHANICAL CONTRACTOR SHALL PROVIDE COMPLETE INFORMATION AND COORDINATE WITH THE OTHER CONTRACTORS AND TRADES AS REQUIRED FOR THE COMPLETION AND COORDINATION OF THE COMPLETE PROJECT.
3.	THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ADMINISTERING ALL WARRANTIES ON EQUIPMENT WHICH THEY FURNISH AND INSTALL.
4.	PROVIDE WRITTEN WARRANTY TO REPLACE ALL FAULTY MATERIALS AND/OR LABOR, AT NO COST TO TENANT, FOR A PERIOD OF ONE YEAR FROM DATE OF COMPLETION.
5.	ALL OUTDOOR AIR INTAKE BY MECHANICAL EQUIPMENT SHALL HAVE A MINIMUM 10'-0" HORIZONTAL CLEARANCE FROM THE DISCHARGE OF ANY EXHAUST FAN, RTU GAS EXHAUST OR PLUMBING VENT.
6.	PROVIDE VIBRATION ISOLATION DEVICES AND FLEXIBLE DUCT/ PIPING CONNECTIONS TO ALL MOVING MACHINERY NOT INTERNALLY ISOLATED.
7.	ALL DUCT DIMENSIONS SHOWN ON DRAWINGS ARE CLEAR INSIDE DIMENSIONS.
8.	THE MECHANICAL CONTRACTOR SHALL COORDINATE ALL DUCT AND DIFFUSER LOCATIONS WITH SPRINKLER PIPING, SPRINKLER HEADS AND LIGHT FIXTURES AS REQUIRED FOR A COMPLETE INSTALLATION.
9.	THE MECHANICAL CONTRACTOR SHALL COORDINATE WITH THE GENERAL CONTRACTOR AND OTHER TRADES ALL REQUIRED OPENINGS AND PENETRATIONS. ALL REQUIRED OPENINGS IN FOUNDATIONS, FLOORS, WALLS AND ROOF SHALL BE CONSTRUCTED INTO THE STRUCTURE WITH THE USE OF SLEEVES, CURBS, ETC. CUTTING AND PATCHING SHALL BE HELD TO A MINIMUM.
10.	ALL ITEMS PROJECTING THROUGH THE ROOF SHALL BE FLASHED THROUGH CURBS OR PIPE SEALS A MINIMUM OF 12" ABOVE THE ROOF. THE PIPE CURBS AND SEALS SHALL BE INSTALLED BY THE ROOFING CONTRACTOR. ENSURE THAT ALL ROOF OPENINGS ARE PROVIDED TO ACCOMMODATE ANY ELECTRICAL CONDUIT PENETRATIONS REQUIRED FOR POWER.
11.	COORDINATE THE INSTALLATION AND FINISH OF ALL SUPPLY AND RETURN AIR DEVICES. AIR DEVICES LOCATED IN GUEST AREAS (INCLUDING DINING AND BAR) SHALL BE PAINTED PER THE ARCHITECTURAL DRAWINGS FINISH SCHEDULE. ALL INTERIOR FACES OF DUCTWORK BEHIND RETURN AIR GRILLES SHALL BE PAINTED FLAT BACK FOR LINE OF SIGHT.
12.	ALL SUPPLY, RETURN, AND RESTROOM EXHAUST DUCTWORK SHALL BE INSTALLED AS HIGH AS POSSIBLE UNDER THE ROOF STRUCTURE.
13.	ALL RECTANGULAR, ROUND, AND FLEXIBLE DUCTWORK SHALL BE SIZED AS SHOWN ON THESE DRAWINGS, AND SHALL BE FABRICATED AND INSTALLED ACCORDING TO THE MOST RECENTLY PUBLISHED SMACNA STANDARDS. ALL JOINTS, SEAMS, AND CONNECTIONS MUST BE SECURELY FASTENED & SEALED BY APPROVED METHODS.
14.	ANY FLEXIBLE DUCTS SHALL BE INSTALLED IN CONCEALED SPACES ONLY. THE MAXIMUM ALLOWABLE LENGTH OF FLEXIBLE DUCT SHALL BE 5'-0". ALL FLEXIBLE DUCTS SHALL BE CONNECTED TO BRANCH RUNS AND FITTINGS WITH A PANDUIT-TYPE BAND, AND SHALL NOT BE ATTACHED DIRECTLY TO THE AIR DEVICE COLLAR.
15.	ALL PENETRATIONS IN FIRE RATED WALL ASSEMBLIES SHALL BE SEALED WITH UL LISTED FIRE STOPPING MATERIAL.
16.	MECHANICAL CONTRACTOR SHALL FURNISH AND INSTALL 4" X 6" BLACK OVER WHITE LAMINATE NAMEPLATE WITH 2" LETTERS VISIBLE ADJACENT TO DISCONNECT SWITCH FOR ROOFTOP UNITS AND ROOF MOUNTED FANS WITH THE AREAS THE UNITS SERVE.
17.	HVAC CONTROLS SHALL BE INSTALLED AS FOLLOWS: <ul style="list-style-type: none"> <li>ALL LINE VOLTAGE WIRING, CONDUIT, DISCONNECT SWITCHES AND FINAL CONNECTION TO EQUIPMENT SHALL BE BY THE ELECTRICAL CONTRACTOR.</li> <li>ALL LOW VOLTAGE WIRING AND CONDUIT SHALL BE BY THE MECHANICAL CONTRACTOR.</li> <li>REMOTE ZONE COMBINATION TEMPERATURE/HUMIDITY SENSORS SHALL BE WALL MOUNTED AT 48" AFF. AND CLEARLY LABELED.</li> <li>PROGRAMMABLE THERMOSTATS IN THE MANAGER'S OFFICE SHALL BE WALL MOUNTED AT 48" AFF AND VERTICALLY STACKED AND CLEARLY LABELED.</li> <li>TEMPERATURE CONTROL OF THE ROOFTOP UNIT OPERATION SHALL BE MADE BY WIRING FROM THE COMBINATION SENSOR BACK TO THE RESPECTIVE PROGRAMMABLE THERMOSTAT IN THE MANAGER'S OFFICE AND THEN TO THE APPROPRIATE ROOFTOP UNIT CONTROL BOARD. WIRING SHALL BE MADE WITH A SHIELDED 4-20mA SIGNAL GROUNDED TWISTED PAIR INSTALLED WITH CONTINUOUS NON-SPLICED LENGTH BETWEEN EACH DEVICE CONNECTION.</li> <li>HUMIDITY CONTROL OF THE ROOFTOP UNIT OPERATION SHALL BE MADE BY WIRING FROM THE COMBINATION SENSOR DIRECT BACK TO THE APPROPRIATE ROOFTOP UNIT CONTROL BOARD. WIRING SHALL BE MADE WITH A SHIELDED 4-20mA SIGNAL GROUNDED TWISTED PAIR INSTALLED WITH CONTINUOUS NON-SPLICED LENGTH BETWEEN EACH DEVICE CONNECTION.</li> <li>ROOFTOP UNITS SHALL BE SET TO RUN IN "FAN CONTINUOUS" MODE DURING OCCUPIED HOURS, DURING NIGHT SET-BACK HOURS, THE ROOFTOP UNITS SHALL RUN IN "FAN AUTO" MODE.</li> </ul>
18.	ALL HVAC SUPPLY AND RETURN DUCTWORK SHALL BE INSTALLED AS FOLLOWS: <ul style="list-style-type: none"> <li>CONCEALED HVAC AND MAKEUP AIR DUCTWORK WITHIN THE BUILDING SHALL BE EXTERNALLY WRAPPED AND SECURED WITH MINIMUM R-8.0, 2" INSULATION WITH VAPOR BARRIER PER THE 2018 INTERNATIONAL MECHANICAL CODE WITH LOCAL AMENDMENTS. INSULATION SHALL HAVE MAXIMUM RATINGS OF 25 FLAME SPREAD, 50 SMOKE DEVELOPED.</li> <li>EXPOSED DUCTWORK WITHIN THE BUILDING</li></ul>











**KEYED NOTES**


1. FIELD COORDINATE PLACEMENT OF THE SPLIT SYSTEM AIR HANDLERS. HOLD TIGHT TO BOTTOM OF STRUCTURE BUT STILL ALLOWING FOR ACCESS TO UNIT FOR MAINTENANCE AND CLEANING. REFER TO MECHANICAL DETAILS FOR PROPOSED CONSTRUCTION OF HANGER SUPPORT ASSEMBLY.
2. DUCT MOUNTED SMOKE DETECTOR CAPABLE OF SHUTTING DOWN THE RESPECTIVE MECHANICAL UNIT UPON ACTIVATION.
3. PROGRAMMABLE THERMOSTATS TO BE MOUNTED AT 48" AFF STACKED AND CLEARLY LABELED. VERIFY PLACEMENT WITH ARCHITECTURAL FLOOR PLAN AND INTERIOR ELEVATIONS.
4. WALL MOUNTED REMOTE ZONE TEMPERATURE SENSORS SHALL BE MOUNTED AT 48" AFF AND WIRED BACK TO RESPECTIVE PROGRAMMABLE THERMOSTAT IN MGR'S OFFICE. COORDINATE PLACEMENT WITH WALL DECOR AND EQUIPMENT. FIELD VERIFY WITH THE OWNER'S REPRESENTATIVE FOR THE FINAL LOCATION PRIOR TO INSTALLATION.
5. ROUTE THE COMBUSTION AIR INTAKE AND EXHAUST PIPING FROM THE WATER HEATERS TO TERMINATION LOCATIONS ON THE ROOF. INSTALL WITH THE MINIMUM ELBOWS AND OFFSETS AS NECESSARY FOR A COMPLETE INSTALLATION PER THE WATER HEATER MANUFACTURER'S REQUIREMENTS. PROVIDE WITH DIRECT VENT CONVERSION KIT. PIPING SHALL BE CLASS 3 STAINLESS STEEL.
6. MANUAL PULL STATION FOR KITCHEN HOOD FIRE SUPPRESSION SYSTEM ACTIVATION AND GAS SUPPLY SHUT-OFF TO BE PROVIDED BY THE FIRE SUPPRESSION SUBCONTRACTOR. GENERAL CONTRACTOR SHALL PROVIDE RECESSED JUNCTION BOX AND CONDUIT FOR PULL STATION LINKAGE. FIRE SUPPRESSION SUBCONTRACTOR SHALL VERIFY APPROVED LOCATION WITH THE LOCAL AUTHORITY AND COORDINATE THE COMPLETE INSTALLATION WITH ALL OTHER TRADES.
7. FIRE SUPPRESSION CABINET TO BE FURNISHED WITH THE HOOD PACKAGE, AND INSTALLED BY THE MECHANICAL CONTRACTOR. FINAL PIPING AND LINKAGE CONNECTIONS TO BE MADE BY THE HOOD FIRE SUPPRESSION SUBCONTRACTOR.
8. GANG REFRIGERATION PIPING TOGETHER FOR A SINGLE RISER ON EXTERIOR WALL TO UPPER LEVEL. FOR SINGLE PENETRATION, PROVIDE FIELD FABRICATED WEATHER TIGHT WORK FOR ROUTING OF REFRIGERATION PIPING THROUGH WALL. COORDINATE EXACT WALL PENETRATION LOCATION WITH EXISTING PIPING AND LANDLORD.
9. EXTEND THE GREASE EXHAUST DUCT UP FROM THE HOOD COLLAR AND OFFSET HORIZONTALLY AS NECESSARY BEFORE ROUTING UP THRU ROOF TO THE EXHAUST FAN. HORIZONTAL DUCTWORK SHALL PITCH A MINIMUM 1/4" PER FOOT BACK TOWARDS THE HOOD. GREASE EXHAUST DUCT SHALL BE OF THE SAME SIZE AS THE HOOD COLLAR. FIELD COORDINATE THE REQUIRED TRANSITIONS OF EXHAUST DUCT FROM COMBUSTIBLE MATERIALS TO MAINTAIN THE MINIMUM CLEARANCES REQUIRED PER APPLICABLE CODE(S) AND FIRE WRAP MANUFACTURER'S INSTRUCTIONS.
10. PROVIDE EXHAUST DUCTS SIZED AS SHOWN. ROUTE EXHAUST DUCT FROM THE RESPECTIVE EXHAUST FAN TO RISER UP THROUGH THE ROOF.
11. ROUTE THE 10" CONDENSATE EXHAUST DUCT RISER UP AND OFFSET HORIZONTALLY AS NECESSARY BEFORE ROUTING UP THRU ROOF TO EXHAUST FAN. FIELD VERIFY REQUIRED TRANSITIONS OR OFFSETS OF EXHAUST DUCT FROM STRUCTURE. PITCH HORIZONTAL EXHAUST DUCT A MINIMUM OF 1/4" PER FOOT BACK TOWARDS THE HOOD. CONDENSATE EXHAUST DUCTWORK SHALL BE INSTALLED COMPLETE WITH EXTERNAL DUCT INSULATION SIMILAR TO OTHER HVAC DUCTWORK.
12. EXTEND THE 10" RESTROOM EXHAUST RISER UP TO THE ROOF MOUNTED GRAVITY VENT. FIELD VERIFY ANY REQUIRED TRANSITIONS OR OFFSETS TO AVOID EXISTING STRUCTURE.
13. AIR DEVICE IN HARD LID CEILING SHALL BE INSTALLED COMPLETE WITH EXHAUST DUCT DAMPER FOR MANUAL VOLUME ADJUSTMENT.
14. ROUTE MAKEUP AIR DUCTWORK TO PERFORATED SUPPLY PLENUM COLLAR CONNECTION. MAKEUP AIR DUCT CONNECTION SHALL BE OF THE SAME SIZE AS THE PLENUM COLLAR.
15. ROUTE MAKEUP AIR DUCTWORK FULL SIZE FROM THE UNIT CONNECTION AND DOWN THROUGH THE ROOF AS SHOWN. PROVIDE FLEXIBLE ROOF CONNECTION AND TRANSITION THROUGH THE JOISTS AS REQUIRED.
16. 12" OUTSIDE AIR DUCT UP TO GRAVITY RELIEF VENTILATOR ON ROOF. SIZE DUCT AS SHOWN. VERIFY ROUTING IN FIELD. PROVIDE WITH MOTORIZED DAMPERS AND ACTUATORS NECESSARY FOR COMPLETE OPERATION OF SYSTEM.
17. PROVIDE AIR DEVICES IN CEILING AND DUCTWORK BETWEEN FOR TRANSFER AIR. SIZE DUCT AS SHOWN.
18. REFER TO THE EXPOSED DUCT MOUNTED DIFFUSER DETAIL FOR PROPOSED MOUNTING OF THE DUCT MOUNTED AIR DEVICES. REFER TO ARCHITECTURAL ELEVATIONS FOR PROPOSED MOUNTING HEIGHT.
19. PROVIDE ACCESS PANEL FOR AHU HUNG ABOVE CEILING. RUN ALL BRANCHES IN CEILING SPACE TO MAINTAIN SINGLE PENETRATION THROUGH CEILING.
20. REFER TO ARCHITECTURAL BUILDING INTERIOR ELEVATIONS FOR INSTALLATION HEIGHT OF SIDEWALL AIR DEVICES AND COORDINATE WITH LIGHTING.
21. EXPOSED DUCTWORK TO BE UNFINISHED GALVANIZED DOUBLE WALL SPIRAL DUCTWORK. BOTTOM OF DUCT WORK SHALL BE AT 12'-0" AFF. COORDINATE WITH ARCHITECTURAL DRAWINGS AND ELECTRICAL EQUIPMENT.
22. RETURN GRILLE AIR QUANTITY LISTED IS FOR PARTIAL RETURN DURING STANDARD OPERATING HOURS. RETURN DUCTS ARE SIZED FOR FULL RETURN DURING NIGHT SETBACK CONDITIONS. REFER TO SHEET M2.0 FOR AIR BALANCE REPORT ON DESIGN AIRFLOW RATES.
23. DUCTWORK CONCEALED BY FINISHED WALLS AND CEILINGS SHALL TRANSITION TO INTERNALLY INSULATED RIGID ROUND DUCT PRIOR TO BEING INSTALLED TO LINE OF SIGHT FROM GUESTS.
24. REMOTE GRADE-MOUNTED CONDENSER FOR SPLIT SYSTEM TO BE LOCATED ON EXISTING CONCRETE PAD. IF NOT EXISTING PROVIDE NEW. REFRIGERANT LINES NOT TO EXCEED MAXIMUM LINE LENGTH.
25. CONDENSATE DRAIN FROM AIR HANDLER. REFER TO PLUMBING DRAWINGS FOR CONTINUATION.
26. FIELD COORDINATE COMPLETE INSTALLATION OF REFRIGERATION PIPING TO THE HVAC AIR HANDLING UNITS. ALL PIPING SHALL BE INSTALLED IN STRAIGHT LINES AND SECURELY SUSPENDED FROM THE STRUCTURE TO PREVENT SAGGING. ROUTE REFRIGERANT LINES UP TO THE ROOF AND TO RESPECTIVE CONDENSING UNITS.
27. ELECTRIC PATIO HEATER SHALL BE MOUNTED ON FACTORY AVAILABLE MOUNTING BRACKET. REFER TO ARCHITECTURAL PLANS FOR MOUNTING HEIGHT.

**BRIAN EDWARD CHANDLER, PE**

6201 CAMPUS CIRCLE DRIVE E  
IRVING, TEXAS 75063  
TEL: 972.870.1288  
WWW.IDSTUDIO4.COM  
E-MAIL: bchandler@idstudio4.com


CLIENT:

**bartaco, LLC**  
2920 District Ave.  
Fairfax, VA 22031  
Contact: Becky Holler



**bartaco - JUBILEE COURTYARD**  
**ATLANTA, GEORGIA**  
2950 New Paces Ferry Rd., Suite 200  
Atlanta, Georgia 30339

CLIENT: bartaco, LLC  
Becky Holler



DATE	DESCRIPTION
10.25.21	ISSUE FOR PERMIT
3.28.22	ISSUE FOR CONSTRUCTION

NO.	DATE	DESCRIPTION
1	09.26.2021	ENVIRONMENTAL AND CLARIFICATIONS
2	04.11.2022	OWNER COMMENTS

SHEET TITLE:

**MECHANICAL FLOOR PLAN**

SHEET NUMBER:

**M1.0**