

SHEET NUMBER	SHEET NAME
M001	MECHANICAL ABBREVIATIONS AND SYMBOLS
M101	MECHANICAL FLOOR PLAN
M102	MECHANICAL REFRIGERANT PIPING LAYOUT PLAN
M150	MECHANICAL ROOF PLAN
M501	MECHANICAL DETAILS
M502	MECHANICAL DETAILS
M590	MECHANICAL SPECIFICATIONS
M591	MECHANICAL SPECIFICATIONS
M592	MECHANICAL SPECIFICATIONS
M601	MECHANICAL SCHEDULE
M701	CAPTIVEAIRE DRAWINGS
M702	CAPTIVEAIRE DRAWINGS
M703	CAPTIVEAIRE DRAWINGS
M704	CAPTIVEAIRE DRAWINGS
M705	CAPTIVEAIRE DRAWINGS
M706	CAPTIVEAIRE DRAWINGS
M707	CAPTIVEAIRE DRAWINGS
M708	CAPTIVEAIRE DRAWINGS

## RESPONSIBILITY MATRIX

THIS SCHEDULE IS PROVIDED FOR QUICK REFERENCE ONLY.  
THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ALL WORK DESCRIBED IN THE CONSTRUCTION DOCUMENTS.  
CONFLICTS BETWEEN THIS SCHEDULE AND THE REST OF THE CONTRACT DOCUMENTS SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION PRIOR TO BEGINNING WORK.

DESCRIPTION	FURNISHED			INSTALLED			REMARKS
	GENERAL CONTRACTOR	OWNER	LANDLORD	GENERAL CONTRACTOR	OWNER	LANDLORD	
<b>DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING</b>							
<b>23.1 HVAC DUCTWORK AND PIPING IDENTIFICATION</b>							
23.1.1 HVAC DUCTWORK SYSTEM IDENTIFICATION	X			X			
23.1.2 PIPING SYSTEM IDENTIFICATION	X			X			
23.1.3 UTILITY SHUT OFF IDENTIFICATION IN KITCHEN	X			X			
23.1.4 VALVE TAGS AND CHART	X			X			
23.1.5 HVAC DAMPER IDENTIFICATION	X			X			
<b>23.2 ROOF CURBS</b>							
23.2.1 EXHAUST FAN CURBS			X		X		GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES - TO BE COORDINATED IN THE FIELD
23.2.2 ROOFTOP UNIT CURBS			X		X		GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES - TO BE COORDINATED IN THE FIELD
23.2.3 CONDENSING UNIT CURBS			X		X		GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES - TO BE COORDINATED IN THE FIELD
23.2.4 MAKE UP AIR UNIT CURBS			X		X		GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES - TO BE COORDINATED IN THE FIELD
23.2.5 KITCHEN EXHAUST FAN CURBS			X		X		GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES - TO BE COORDINATED IN THE FIELD
<b>23.3 HVAC DUCTWORK SYSTEM COMPONENTS</b>							
23.3.1 HVAC DUCTWORK	X			X			
23.3.2 INSULATION AND FIRE WRAP	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE TENANT FIT OUT FROM LANDLORD POINT OF CONNECTION
23.3.3 DAMPERS	X			X			
23.3.4 SMOKE DETECTORS			X		X		
23.3.5 SUPPLY, RETURN, AND EXHAUST GRILLS AND REGISTERS	X			X			
<b>23.4 MECHANICAL PIPING SYSTEM COMPONENTS</b>							
23.4.1 WALK-IN COOLER AND FREEZER REFRIGERATION		X			X		WALK-IN COOLER AND FREEZER SUPPLIED BY VENDOR NO. 27 GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE PIPING INSTALLATION AND FINAL CONNECTION
23.4.2 REFRIGERATION FOR OTHER HVAC EQUIPMENT	X			X			
23.4.3 CHILLED WATER	X			X			
23.4.4 CONDENSER WATER	X			X			
23.4.5 HEATING HOT WATER	X			X			
23.4.6 VALVES AND ACCESSORIES (E.G. AIR VENTS)	X			X			
<b>23.5 HVAC EQUIPMENT</b>							
23.5.1 SUPPLY FAN	X			X			
23.5.2 TOILET EXHAUST FAN	X			X			
23.5.3 KITCHEN EXHAUST FAN	X			X			SUPPLIED BY VENDOR NO. 26
23.5.4 DUCTED AND NON-DUCTED HEATING AND COOLING UNITS	X			X			
23.5.5 MAKE UP AIR UNITS	X			X			SUPPLIED BY VENDOR NO. 26
23.5.6 ELECTRIC PATIO HEATERS	X			X			
23.5.7 CONDENSING UNITS	X			X			
23.5.8 RGF PHI SYSTEM	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 12 VENDOR SUBSTITUTION IS NOT PERMITTED
<b>23.6 KITCHEN EXHAUST WITH FIRE SUPPRESSION SYSTEM</b>							
23.6.1 HOOD CONTROL PANEL		X		X			SUPPLIED BY VENDOR NO. 26
23.6.2 KITCHEN EXHAUST HOOD		X		X			SUPPLIED BY VENDOR NO. 26
23.6.3 STRUCTURAL SUPPORT			X		X		
23.6.4 ELECTRICAL AND CONTROL WIRING	X			X			
23.6.5 TANK SYSTEM		X		X			SUPPLIED BY VENDOR NO. 26 GENERAL CONTRACTOR TO COORDINATE AND FACILITATE SYSTEM SIGN-OFF
23.6.6 TANK WIRING AND UTILITIES CONNECTION	X			X			
23.6.7 TANK GAS VALVE		X		X			SUPPLIED BY VENDOR NO. 26
<b>23.7 COMMISSIONING ACTIVITIES</b>							
23.7.1 GREASE EXHAUST WATER LEAKAGE TEST	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 10 VENDOR SUBSTITUTION IS NOT PERMITTED
23.7.2 TESTING AIR BALANCE (TAB) REPORT	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 12 VENDOR SUBSTITUTION IS NOT PERMITTED

## SUBMITTAL MATRIX

GENERAL CONTRACTORS TO ALSO REVIEW ARCHITECTURAL SPECIFICATIONS AS NOTED IN PLANS IN PLAN SECTION 700 OF THE ARCHITECTURAL PACKAGE FOR REQUIRED SUBMITTALS THAT MIGHT NOT BE LISTED BELOW.

SUBMITTAL DESCRIPTION	Required Review Time (Business Days)	Architect Approval	Submittal Required	Physical Sample Required	Submittal for Record	Submittal for Record Only
Anchor Bolts Shops	5	X			X	
ATAS-Detailed Shop DWGS(Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X			X	
Concrete Mix Design	5	X			X	
Construction Prefunctional Checklists	5	X			X	
Decorative Metal Shop Drawings	5	X			X	
Diffusers, Grills & Registers	5	X			X	
Doors, Frames & Hardware	7	X			X	
Ductwork Layout (if there are significant changes in field)	5	X			X	
Electrical Distribution Equipment	5	X			X	
Elevator & Vertical Transportation Shop Drawings	5	X			X	
Epoxy Floor	5	X			X	
Fire Alarm Shop Drawings & Device Cut Sheets	5	X			X	
Fire Sprinkler Shop Drawings, Hydraulic Calculations & Device Cut Sheets	5	X			X	
HVAC Equipment(if Carrier - Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X			X	
Light Fixtures(Submitted by Owner Vendor to Owner/AOR prior to construction)	5	X			X	
M&P Tests, Start-Up, and Programming Reports	5	X			X	
Millwork - Material Submittals (if differs from spec)	5	X	X	X		
Millwork - Shop Drawings (custom items & design features only)	5	X				
Restroom Partitions	5	X			X	
Plumbing Fixtures	5	X			X	
Railing Shop Drawings	5	X			X	
Rebar	5	X			X	
Stair Shop Drawings	5	X			X	
Structural Steel Shop Drawings	7	X			X	
Storefront - product data Submittal (if different from specified)	5	X				
Storefront - Shop Drawings	5	X				
Tile (if differs from spec)	5	X			X	
Window Film	5	X				

## SYMBOLS

HEATING - VENTILATING - AIR CONDITIONING	
SYMBOL	DESCRIPTION
	THERMOSTAT
	REMOTE SENSOR
	SUPPLY DIFFUSER
	RETURN OR EXHAUST GRILLE
	SUPPLY OR FRESH AIR DUCT (SA OR FA)
	RETURN OR EXHAUST AIR DUCT (RA OR EA)
	RECTANGULAR DUCT FIRST FIGURE IS SIDE SHOWN
	ROUND DUCT
	VOLUME DAMPER (ELEV AND PLAN)
	TURNING VANES
	SUPPLY REGISTER OR GRILLE (R OR G)
	RETURN REGISTER OR GRILLE (R OR G)
	FRESH AIR INTAKE (FA)
	SQUARE CEILING DIFFUSER (SUPPLY)
	FAN COIL UNIT AND MARK
	MOTORIZED DAMPER
	REFRIGERANT LIQUID LINE
	REFRIGERANT SUCTION LINE



TN - 1504 - Nashville Tanger Outlets  
4060 CANE RIDGE PKWY, BLDG. 7, SUITE 701  
ANTIOCH, TN 37013

## Gensler

LIC. NO. AA0002837 TEL 415.433.3700  
45 FREMONT ST FAX 415.836.4599  
SUITE 1500  
SAN FRANCISCO, CA 94105  
UNITED STATES

SATELLITE OFFICE: TEL 813.204.9000  
400 N ASHLEY DRIVE  
SUITE 0400 FAX 813.223.6948  
TAMPA, FL 33602  
UNITED STATES



New York ■ Miami ■ Omaha ■ Los Angeles ■ Seattle ■ Honolulu  
800-581-0963 www.schnackel.com

MEPF ENGINEER  
3035 S 72ND ST  
OMAHA NE 68124




Foodservice Equipment, Supplies and Design

FOODSERVICE CONSULTANT  
505 COLLINS ST  
PO BOX 3505  
SOUTH ATTLEBORO  
MA 02703  
TEL 508.399.6000  
FAX 508.761.3620



STRUCTURAL ENGINEER  
13075 HEATHCOTE BLV  
SUITE 170  
GAINESVILLE  
VA 20155  
TEL 571.261.9280

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION



Project Name

TN - 1504 - Nashville Tanger Outlets

Project Number

69.6677.000

Description

MECHANICAL ABBREVIATIONS & SYMBOLS


Scale

AS NOTED

**M001**

- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER. THE CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
  - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
  - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS.
  - CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
  - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
  - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
  - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
  - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGNOMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY. IN THIS REGARD, THE CONTRACTOR SHALL BE RESPONSIBLE FOR AWARD OF THE CONTRACT.
  - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
  - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE SETTING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
  - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
  - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E., BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
  - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1"-1 1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOGA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH ACOUSTICAL DUCT LINER. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
  - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TO THE BOTTOM OF THE STRUCTURE, THRU JOIST SPACE.
  - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNITED ENERGY FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILINGS. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
  - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
  - MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OR DAMAGING, TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
  - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
  - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-RESISTANT FIBERGLASS INSULATION. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
  - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
  - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
  - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AISC OR TABS CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE CONDUCTED BY NATIONAL TAB. CONTACT WILL TURNBERRY AT WILL@NATIONALTAB.COM OR 314-954-6244.


- HVAC NOTES:**
- TOP OPEN RETURN AIR DUCT. PROVIDE OPENING WITH 1/4" MESH GALVANIZED SCREEN.
  - CONTRACTOR SHALL UNDERCUT DOOR 3/4".
  - PROVIDE 8/8 EXHAUST AIR DUCT UP TO E7-3 ON ROOF.
  - NEW CAPTIVE GREASE EXHAUST HOOD TO BE FURNISHED BY OWNER FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. SEE CAPTIVE SHEETS FOR ADDITIONAL INFORMATION. BALANCE HOOD EXHAUST, MAKE-UP, AND SUPPLY AIR AS NOTED ON CAPTIVE SHEETS. PROVIDE TRANSITION FROM DUCTWORK AS INDICATED ON PLANS TO HOOD CONNECTIONS AS REQUIRED TO PROVIDE A COMPLETE, OPERATIONAL SYSTEM. VERIFY ALL MANUFACTURER AND CODE REQUIRED CLEARANCES ARE MAINTAINED. NOTIFY ARCHITECT IF ANY CONFLICTS OCCUR. TRANSITION FROM HOOD EXHAUST COLLAR AS INDICATED ON PLANS AND EXTEND 12" TO KITCHEN HOOD GREASE EXHAUST DUCTWORK UP TO CORRESPONDING GREASE EXHAUST FAN ON ROOF. SEE SHEET M150 FOR CONTINUATION. GREASE DUCT SHALL BE WRAPPED WITH TWO (2) LAYERS OF THERMAL CERAMICS FAST WRAP XL 1 1/2" THICK WITH 3" PERIMETER AND LONGITUDINAL OVERLAPS OR EQUIVALENT U.L.L. LISTED GREASE DUCT WRAP FOR ZERO CLEARANCE TO COMBUSTIBLES. REFER TO SHEET M502, DETAIL 5, FOR ADDITIONAL INFORMATION. TYPICAL PROVIDE CLEANOUTS ON GREASE DUCTWORK AS REQUIRED BY CODE. REFERENCE SHEET M501, DETAIL 1 FOR ADDITIONAL INFORMATION. TYPICAL OF GREASE EXHAUST DUCTWORK. TYPICAL OF GREASE EXHAUST.
  - DUCTWORK TO BE INSTALLED AS HIGH AS CONDITIONS ALLOW. COORDINATE ROUTING AND MOUNTING HEIGHT WITH LIGHTING FIXTURES. NOTIFY THE ARCHITECTS OF ANY CONFLICTS AND COORDINATE WITH THE CONSTRUCTION MANAGER. DUCTWORK TO BE INTERNALLY LINED AS NOTED WITHIN THESE SPECIFICATIONS, AND PAINTED TO MATCH THE CEILING. COORDINATE COLOR/FINISH WITH THE ARCHITECT.
  - ROUTE DUCTWORK BELOW BUILDING OR STRUCTURAL COMPONENTS AS REQUIRED.
  - PROVIDE NEW FC UNIT AS NOTED ON PLANS AND AS SCHEDULED ON SHEET M601.
  - PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
  - HOOD MANUFACTURER TO PROVIDE A "KIT" TO FASTEN THE BOTTOM FLANGE OF THE HOOD TO THE WALL. WITH ONE FASTENER PER STUD WALL. SIL-BOND RTV 4300 ALUMINUM SILICONE SEALANT OR APPROVED SIMILAR, TO BE APPLIED BY GENERAL CONTRACTOR HOOD INSTALLER FOR ANY REMAINING SMALL GAPS. HOOD FASTENING "KIT" DETAIL TO BE INCLUDED IN MANUFACTURER DRAWINGS. REFERENCE SHEET M501, DETAIL 14, FOR ADDITIONAL INFORMATION.
  - PROVIDE AIR CURTAINS AS SHOWN ON PLANS AND AS SCHEDULED ON SHEET M601. CONTRACTOR TO FIELD VERIFY OPENINGS AND SIZES OF AIR CURTAINS INDICATED. COORDINATE WITH ARCHITECT ON FINAL FINISH/COLOR. ALL WIRING TO BE BY THE ELECTRICAL CONTRACTOR.
  - PROVIDE NEW FULLY DIGITAL 7 DAY PROGRAMMABLE TYPE THERMOSTAT WITH REMOTE SENSING CAPABILITIES, AUTO CHANGE OVER AND AUTO SET BACK. MOUNT THERMOSTAT 4" ABOVE FINISHED FLOOR. THERMOSTATS SERVING THE SAME TEMPERATURE ZONE SHALL BE INTERLOCKED TO PREVENT SIMULTANEOUS HEATING AND COOLING. PROVIDE REMOTE TEMPERATURE SENSORS AS INDICATED ON PLAN. COORDINATE LOCATION WITH WALL GRAPHICS LAYOUT.



ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.

**1 MECHANICAL FLOOR PLAN**  
SCALE: 1/4" = 1'-0"

Seal / Signature



Project Name  
**TN - 1504 - Nashville Tanger Outlets**


Project Number  
**69.6677.000**

Description  
**MECHANICAL FLOOR PLAN**

Scale  
AS NOTED

**M101**

- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER. THE CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
  - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
  - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS.
  - CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
  - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
  - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
  - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
  - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
  - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
  - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE SETTING HEIGHTS, HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
  - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
  - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E., BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
  - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RESISTANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOGA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH ACOUSTICAL DUCT LINER.
  - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
  - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE, THRU JOIST SPACE.
  - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNYED ENERGY FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILINGS. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
  - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
  - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
  - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
  - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
  - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
  - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
  - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBERRY AT WILL@NATIONALTAB.COM OR 314-954-6244.
- HVAC NOTES:**
- PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 ABOVE KITCHEN OFFICE AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.
  - PROVIDE REFRIGERANT LINES FROM CONDENSING UNIT ON ROOF TO KITCHEN EQUIPMENT AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.




ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE, IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.

1 MECHANICAL REFRIGERANT PIPING LAYOUT PLAN  
SCALE: 1/4" = 1'-0"

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION

Seal / Signature




Project Name  
TN - 1504 - Nashville Tanger Outlets

Project Number  
69.6677.000

Description  
MECHANICAL REFRIGERANT PIPING LAYOUT PLAN

Scale  
AS NOTED


M102



- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER. THE CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
  - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
  - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS.
  - CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
  - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
  - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
  - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
  - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
  - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
  - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE. AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
  - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
  - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E., BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
  - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOGA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH ACOUSTICAL DUCT LINER. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
  - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE, THRU JOIST SPACE.
  - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR UNYED ENERGY FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILINGS. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
  - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
  - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AISC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE CONDUCTED BY THE VENDOR LISTED BELOW. CONTACT WILL TURNOVER AT WILL@NATIONALTAB.COM OR 314-954-6244.
  - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CONTAINMENT DAMPERS LOCATED ABOVE INACCESSIBLE CEILINGS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
  - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
  - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
  - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AISC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE CONDUCTED BY THE VENDOR LISTED BELOW. CONTACT WILL TURNOVER AT WILL@NATIONALTAB.COM OR 314-954-6244.
- HVAC NOTES:**
- EXISTING DAIKIN, DFC150AL240, 12.5 TON ROOFTOP UNIT TO REMAIN. CONTRACTOR SHALL BALANCE EXISTING UNIT TO PROVIDE 5,000 CFM OF SUPPLY AIR AND THE OUTDOOR AIR INDICATED ON THE PLANS. FIELD VERIFY EXACT LOCATION. THE CONTRACTOR SHALL VERIFY THE UNIT IS EQUIPPED WITH A WATER LEVEL MONITORING DEVICE, AND IF NOT, SHALL PROVIDE. THE CONTRACTOR IS TO PROVIDE A POWER EXHAUST OPTION.
  - EXISTING DAIKIN, DBG120AS, 10 TON ROOFTOP UNIT TO REMAIN. CONTRACTOR SHALL BALANCE EXISTING UNIT TO PROVIDE 4,000 CFM OF SUPPLY AIR AND THE OUTDOOR AIR INDICATED ON THE PLANS. FIELD VERIFY EXACT LOCATION. THE CONTRACTOR SHALL VERIFY THE UNIT IS EQUIPPED WITH A WATER LEVEL MONITORING DEVICE, AND IF NOT, SHALL PROVIDE. THE CONTRACTOR IS TO PROVIDE CONDENSER COIL HAIL GUARDS.
  - NEW CAPTIVEFAIRE GREASE EXHAUST FAN TO BE FURNISHED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE CAPTIVEFAIRE SHEETS FOR ADDITIONAL INFORMATION. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE.
  - RFC ENVIRONMENTAL GROUP, INC. AIR PURIFICATION SYSTEM TO BE PROVIDED BY NTAB. REFER TO RESPONSIBILITY MATRIX ON SHEET M601 FOR ADDITIONAL INFORMATION. SHEET M601 FOR SCHEDULE, AND SHEET M602 FOR SPECIFICATIONS.
  - PROVIDE NEW EXHAUST FAN AS NOTED ON PLANS AND SCHEDULED ON SHEET M601. THE CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE.
  - PROVIDE ASHP AS NOTED ON PLANS AND SCHEDULED ON SHEET M601.
  - PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
  - PROVIDE REFRIGERANT LINES FROM KITCHEN EQUIPMENT CONDENSING UNITS ON ROOF TO UNITS IN THE KITCHEN SPACE AS INDICATED ON THE KITCHEN DRAWINGS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
  - VERIFY EXISTING CONDITIONS. IF NOT PRESENT, DUCT SMOKE DETECTOR ON RETURN, SUPPLY SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
  - PROVIDE GOOSENECK TERMINATION FOR OUTDOOR AIR INTAKE FOR ACU-1. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION IS A MINIMUM OF 10'-0" FROM ANY EXHAUST/FLUE TERMINATION.
  - NEW CAPTIVEFAIRE MAKE-UP AIR UNIT TO BE FURNISHED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE CAPTIVEFAIRE SHEETS FOR ADDITIONAL INFORMATION. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY EXHAUST OR FLUE DISCHARGE.

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION

Seal / Signature




Project Name  
TN - 1504 - Nashville Tanger Outlets

Project Number  
69.6677.000


Description  
MECHANICAL ROOF PLAN

Scale  
AS NOTED


M150



**7** CONDENSER REFRIGERANT LINE PIPING AND POWER THROUGH ROOF DECK  
NOT TO SCALE



**8** TYPICAL ROOF TOP UNIT DETAIL  
NOT TO SCALE



**9** HOOD FASTENING DETAIL  
NOT TO SCALE

MAXIMUM HALF OF DUCT PERIMETER	PAIR AT 10 FT. SPACING		PAIR AT 8 FT. SPACING		PAIR AT 5 FT. SPACING		PAIR AT 4 FT. SPACING	
	STRAP	WIRE/ROD	STRAP	WIRE/ROD	STRAP	WIRE/ROD	STRAP	WIRE/ROD
P/2 = 30"	1" x 22 GA.	10 GA. (.135")	1" x 22 GA.	10 GA. (.135")	1" x 22 GA.	12 GA. (.106")	1" x 22 GA.	12 GA. (.106")
P/2 = 72"	1" x 18 GA.	3/8"	1" x 20 GA.	1/4"	1" x 22 GA.	1/4"	1" x 22 GA.	1/4"
P/2 = 96"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"	1" x 20 GA.	3/8"	1" x 22 GA.	1/4"
P/2 = 120"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"	1" x 20 GA.	1/4"
P/2 = 168"	1 1/2" x 16 GA.	1/2"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 18 GA.	3/8"
P/2 = 192"	---	1/2"	1 1/2" x 16 GA.	1/2"	1" x 16 GA.	3/8"	1" x 16 GA.	3/8"


WHEN STRAPS ARE LAP JOINED USE THESE MINIMUM FASTENERS:

SINGLE HANGER MAXIMUM ALLOWABLE LOAD	SPECIAL ANALYSIS REQUIRED	
	STRAP	WIRE OR ROD (DIA.)
1" x 18, 20, 22 GA. - TWO #10 OR ONE 1/4" BOLT	1" x 22 GA. - 260 LBS.	0.106" - 80 LBS.
1" x 16 GA. - TWO 1/4" DIA.	1" x 20 GA. - 320 LBS.	0.135" - 120 LBS.
1" x 16 GA. - TWO 3/8" DIA.	1" x 18 GA. - 420 LBS.	0.162" - 160 LBS.
PLACE FASTENERS IN SERIES, NOT SIDE BY SIDE.	1" x 16 GA. - 700 LBS.	1/4" - 270 LBS.
	1 1/2" x 16 GA. - 1100 LBS.	3/8" - 680 LBS.
		1/2" - 1280 LBS.
		5/8" - 2000 LBS.
		3/4" - 3000 LBS.

NOTES:  
1. DIMENSIONS OTHER THAN GAUGE ARE IN INCHES.  
2. TABLES ALLOW FOR DUCT WEIGHT, 1 LB./SF INSULATION WEIGHT AND NORMAL REINFORCEMENT AND TRAPEZE WEIGHT, BUT NO EXTERNAL LOADS.  
3. STRAPS ARE GALVANIZED STEEL. OTHER MATERIALS ARE UNCOATED STEEL.  
4. ALLOWABLE LOADS FOR P/2 ASSUME THAT DUCTS ARE 16 GA. MAXIMUM, EXCEPT THAT WHEN MAXIMUM DUCT DIMENSION (W) IS OVER 60" THEN P/2 MAXIMUM IS 1.25 W.  
5. 12, 10 OR 8 GA. WIRE IS STEEL OR BLACK ANNEALED, BRIGHT BASIC OR GALVANIZED TYPE.  
6. DUCTS SHALL BE SUPPORTED AT INTERVALS NOT EXCEEDING 10 FEET.


**4** RECTANGULAR DUCT HANGER TABLE  
NOT TO SCALE

- NOTES:
- THERMAL CERAMICS FIREMASTER FASTWRAP XL IS TESTED TO ASTM E2336 AND UL LISTED PER HNK1.G18 TO PROVIDE ZERO CLEARANCE TO COMBUSTIBLES AND TO PROVIDE A 1 OR 2 HOUR EXPOSURE. THROUGH PENETRATIONS FIRESTOP SYSTEMS ARE TESTED IN ACCORDANCE WITH ASTM E 814 (UL 1479). ICC-ES APPROVAL PER REPORT ESR 2213 OR EST 2832.
  - COMPLIANT TO THE FOLLOWING CODES:  
NFPA 96  
INTERNATIONAL MECHANICAL CODES  
UNIFORM MECHANICAL CODE  
CALIFORNIA MECHANICAL CODE
  - INSULATION APPLIED IN TWO LAYERS WITH TIGHT COMPRESSION JOINT ON BOTH LAYERS AT ALL JOINTS.
  - MINIMUM 16 GAUGE CARBON STEEL (OR 18 GAUGE STAINLESS STEEL) RECTANGULAR OR ROUND GREASE EXHAUST DUCT.
  - INSTALL UL LISTED AND LIQUID TIGHT THERMAL CERAMICS FASTDOOR XL ACCESS DOORS AT ALL CHANGES IN DIRECTION AND AT MINIMUM EVERY 20 FT ON HORIZONTAL RUNS.
  - SUPPORT HANGER SYSTEMS DO NOT NEED TO BE WRAPPED PROVIDED THE HANGER RODS ARE MINIMUM OF 3/8" IN. DIAMETER AND SUPPORTS ARE MINIMUM 2" x 1/8" IN. STEEL ANGLE OR SMACTA EQUIVALENT SUPPORT SYSTEM.
  - THERMAL CERAMICS DUCT WRAP SHALL BE INSTALLED DIRECTLY ONTO THE DUCT AND APPLIED FROM THE HOOD CONNECTION TO THE CONNECTION OF THE FAN.
  - THERMAL CERAMICS DUCT ENCLOSURE SYSTEM SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS AND UL LISTINGS.




\*\* DETAIL COURTESY OF MORGAN THERMAL CERAMICS.


**5** FIREMASTER FASTWRAP XL DETAIL  
NOT TO SCALE




**6** TYPICAL DRYWALL MOUNTING FRAME DETAIL  
NOT TO SCALE



**1** DUCTWORK DETAILS  
NOT TO SCALE



**2** DUCT HANGER DETAIL  
NOT TO SCALE



**3** TYPICAL ROOF TOP UNIT TEE CONNECTION  
NOT TO SCALE

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION

Seal / Signature



Project Name  
TN - 1504 - Nashville Tanger Outlets  
Project Number  
69.6677.000  
Description  
MECHANICAL DETAILS

Scale  
AS NOTED



SPECIFICATIONS TABLE OF CONTENTS

- SECTION 230000 - HVAC GENERAL CONDITIONS
SECTION 230448 - VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT
SECTION 230583 - TESTING, ADJUSTING, AND BALANCING FOR HVAC
SECTION 230713 - DUCT INSULATION
SECTION 230715 - GREASE DUCT FIREPROOFING
SECTION 230719 - HVAC PIPING INSULATION
SECTION 230800 - COMMISSIONING OF HVAC
SECTION 230891 - SEQUENCE OF OPERATIONS FOR HVAC CONTROLS
SECTION 232300 - REFRIGERANT PIPING
SECTION 233100 - HVAC DUCTS AND CASINGS
SECTION 233300 - AIR DUCT ACCESSORIES
SECTION 233423 - AIR PURIFICATION DEVICES
SECTION 233425 - HVAC POWER VENTILATORS
SECTION 233700 - AIR OUTLETS AND INLETS
SECTION 237412 - PACKAGED OUTDOOR ROOF TOP UNITS - GAS FIRED
SECTION 238127 - SMALL SPLIT-SYSTEM HEATING AND COOLING

SECTION 230000 - HVAC GENERAL CONDITIONS

- 1.01 APPLICABILITY
1.02 DEFINITIONS
1.03 CODES AND STANDARDS
1.04 PERMITS AND FEES
1.05 CONTRACT DRAWINGS

- 1.06 EXISTING CONDITIONS
1.07 SUBMITTALS
1.08 QUALITY ASSURANCE
1.09 DELIVERY, STORAGE, AND HANDLING
1.10 WARRANTY AND GUARANTEE
2.01 PRODUCTS

coordination issues arising out of the substitution of materials or equipment, and the coordination of such substitutions with all other contractors and subcontractors.

PART 3 EXECUTION

- 3.01 COORDINATION OF WORK
3.02 EXAMINATION
3.03 INTERFERENCE WITH OTHER PRODUCTS
3.04 FIELD QUALITY CONTROL
3.05 CLEANING AND REPAIR
3.06 PROJECT CLOSURE AND TESTS

END OF SECTION

SECTION 230548 - VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT

- PART 1 GENERAL
1.01 SECTION INCLUDES
1.02 SUBMITTALS

PART 2 PRODUCTS

- 2.01 MANUFACTURERS
2.02 VIBRATION ISOLATORS

PART 3 EXECUTION

- 3.01 INSTALLATION
3.02 SCHEDULES

END OF SECTION

SECTION 230583 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

- PART 1 GENERAL
1.01 SECTION INCLUDES

PART 2 PRODUCTS

- 2.01 MANUFACTURERS
2.02 SUBMITTALS

PART 3 EXECUTION

- 3.01 INSTALLATION
3.02 SCHEDULES

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

- 3.01 GENERAL REQUIREMENTS
3.02 SCHEDULES

PART 1 GENERAL

- 1.01 SECTION INCLUDES
1.02 PRODUCTS

PART 2 MANUFACTURERS

PART 2 MATERIALS

PART 2 PRODUCTS

PART 2 MANUFACTURERS

PART 2 MATERIALS

PART 2 PRODUCTS

PART 3 EXECUTION

PART 3 EXAMINATION

PART 3 PREPARATION

PART 3 INSTALLATION

PART 3 FIELD CONDITIONS

PART 3 FINISHES

PART 3 MAINTENANCE

PART 3 PROTECTION

PART 3 CLEANUP

PART 3 DEMOLITION

PART 3 DISPOSAL

PART 3 STORAGE

PART 3 HANDLING

PART 3 WARRANTY

PART 3 GUARANTEE

PART 3 COMPLIANCE

PART 3 PERMITS

PART 3 FEES

PART 3 DRAWINGS

PART 3 CONDITIONS

PART 3 STANDARDS

PART 3 CODES

PART 3 REGULATIONS

PART 3 ORDINANCES

PART 3 LAWS

PART 3 STATUTES

PART 3 CONSTITUTIONS

PART 3 TREATIES

PART 3 AGREEMENTS

PART 3 CONTRACTS

PART 3 DEEDS

PART 3 WILLARS

PART 3 TESTAMENTS

PART 3 PROBATE

PART 3 ESTATES

PART 3 TRUSTS

PART 3 FIDUCIARIES

PART 3 BENEFICIARIES

PART 3 HEIRSHIP

PART 3 SUCCESSION

PART 3 ESTATE PLANNING

PART 3 TAXATION

PART 3 FINANCIAL

PART 3 ACCOUNTING

PART 3 INVESTMENT

PART 3 RISK MANAGEMENT

PART 3 INSURANCE

PART 3 REINSURANCE

PART 3 UNDERWRITING

PART 3 POLICIES

PART 3 CLAIMS

PART 3 SETTLEMENTS

PART 3 LITIGATION

PART 3 ARBITRATION

PART 3 MEDIATION

PART 3 CONFLICT RESOLUTION

PART 3 DISPUTE RESOLUTION

PART 3 NEGOTIATION

PART 3 MEDIATION

PART 3 ARBITRATION

PART 3 LITIGATION

PART 3 CONFLICT RESOLUTION

PART 3 DISPUTE RESOLUTION

PART 3 NEGOTIATION

PART 3 MEDIATION

PART 3 ARBITRATION

PART 3 LITIGATION

PART 3 CONFLICT RESOLUTION

PART 3 DISPUTE RESOLUTION

PART 3 NEGOTIATION

PART 3 MEDIATION

PART 3 ARBITRATION

PART 3 LITIGATION

Secure insulation with mechanical liner fasteners. Refer to SMACNA HVAC Duct Construction Standards - Metal and Flexible for spacing.

Seal and smooth joints. Seal on coat transverse joints.

Seal linear surface penetrations with adhesive.

Duct dimensions and tolerances shall conform to the requirements for air flow. Increase duct size to allow for insulation thickness.

3.02 SCHEDULES

A. The Contractor may use any of the following insulating materials, at his option, provided the selected material meets with the approval of all State, local and codes and utility company requirements. Verification of compliance of the selected insulating material and thickness with all State and local codes and utility company requirements is the sole responsibility of the installing contractor.

B. Supply and install ducts in ceiling spaces:

1. Flexible Glass Fiber Duct Insulation: 1-1/2 inches thick.

2. Flexible Glass Fiber Duct Liner Insulation: 1 inches thick.

3. Supply, return or exhaust air ducts in crawl spaces, attics or other unconditioned areas.

1. Flexible Glass Fiber Duct Insulation: 3 inches thick.

2. Supply air ducts exposed in finished areas.

1. Flexible Glass Fiber Duct Insulation: 1 inches thick.

E. Return or exhaust air ducts exposed in finished areas: None.

F. Outside air intake ducts (untempered):

1. Flexible Glass Fiber Duct Insulation: 1-1/2 inches thick.

2. Rigid Glass Fiber Duct Insulation: 1-1/2 inches thick.

3. Flexible Glass Fiber Duct Liner Insulation: 1 inches thick.

4. Rigid Glass Fiber Duct Liner Insulation: 1 inches thick.

G. Outside air intake ducts (tempered): None.

END OF SECTION

SECTION 230713.13 - GREASE DUCT FIREPROOFING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Fire resistant duct wrap for kitchen hood exhaust ventilation ducts (grease ducts).

B. Fireproofing of duct penetrations through fire rated walls and floors.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Acceptable Manufacturer: 3M Fire Protection Products, Inc.; Unifrax FireWrap;

2.02 MATERIALS

A. Grease Duct Fireproofing: Material applied directly to metal ducts and achieving two-hour fire rated separation when tested in accordance with UL 2221 or ASTM E2336 by independent testing agency.

1. Surface Burning Characteristics: Flame spread index of 0 and smoke developed index of 0, when tested in accordance with ASTM E 84, both blanket and foil.

2. Combustibility: Non-combustible, when tested in accordance with ASTM E 136.

3. Flexibility: Capable of being formed around corners and shapes by hand.

4. Surface: Full of fire damage resistant surface; fiber not exposed after installation.

5. Maximum Reaction For Duct Access Doors and Panels: Capable of being installed to achieve fire rating without impeding access.

6. Acceptable Product: 3M Fire Barrier Duct Wrap, fire resistant inorganic blanket encapsulated with acryl-reinforced foil facing.

Fasteners: Non-combustible; use one or both of the following to attach

1. Banding: Steel or stainless steel, 1/2 inch wide, minimum, and 0.015 inch

2. Insulation Pins: Copper-coated steel implant pins, minimum 12 gage, for

welded attachment, with galvanized steel self-locking washers, 1-1/2 inch

3. Access Panel Hardware: Galvanized threaded rods, sleeves, washers, and wing nuts

4. Tapes: Aluminum foil tape for sealing exposed fiber edges and repairing tears in

5. Firestopping: Material tested in conjunction with fireproofing, in accordance with

ASTM E 814, to achieve fire rated penetration seal at duct penetrations through

6. Acceptable Products: 3M Fire Barrier 1000, 1003 5/8, 1003 5/8 and 2000+ Silicone

Sealants, as required by tested assembly.

PART 3 EXECUTION

3.01 EXAMINATION

A. Do not begin installation until substrates have been properly prepared.

B. Substrate preparation is the responsibility of another contractor, notify

3.02 PREPARATION

A. Clean surfaces thoroughly prior to installation.

B. Prepare surfaces using the methods recommended by the manufacturer for achieving

the best result for the substrate under the project conditions.

3.03 INSTALLATION

A. Install in strict accordance with manufacturer's instructions and as indicated on

the Drawings.

B. Perform air leakage testing in strict accordance with manufacturer's instructions to

demonstrate the integrity of the duct construction prior to the installation of any

insulation. Insulation must prevent visual inspection of the ductwork on all sides.

C. Install fireproofing on entire surface of ducts indicated, except where Contract

Documents expressly indicate 3-sided or 2-sided installation.

D. At penetrations of ducts through fire rated assemblies (walls, floors, roofs),

install fireproofing and seal annular space between fireproofing and

edge of opening with fireproofing.

E. Fasten fireproofing to ducts using either banding or insulation pins welded

directly to surface of duct; do not use adhesives.

F. Install fireproofing on supports and hangers unless hanger rods are at least 3/8

inch diameter and hanger rods are at least 2 by 2 by 1/4 inch steel angle or equivalent

steel angle.

G. Access Panels: Do not block access; install fireproofing so that panel can be

removed and reinstalled without damaging fireproofing.

H. Seal all cut edges and ends and repair tears in the fireproofing using aluminum foil tape.

END OF SECTION

SECTION 230719 - HVAC PIPING INSULATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Cooling condensate drain piping insulation.

B. Refrigerant piping insulation.

PART 2 PRODUCTS

2.01 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION

A. Surface Burning Characteristics: Flame spread/Smoke developed index of 25/50,

maximum, when tested in accordance with ASTM E 84, NFPA 255, or UL 723.

B. The Contractor shall use the following minimum pipe sizes and lengths of duct,

and horizontal supports are at least 2 by 2 by 1/4 inch steel angle or equivalent

steel angle.

C. Access Panels: Do not block access; install fireproofing so that panel can be

removed and reinstalled without damaging fireproofing.

D. Seal all cut edges and ends and repair tears in the fireproofing using aluminum foil tape.

END OF SECTION

SECTION 230713 - DUCT INSULATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Duct insulation.

B. Duct liner.

C. Insulation jackets.

D. Supply, return or exhaust ducts in ceiling spaces.

E. Supply, return or exhaust ducts in interior unconditioned areas.

F. Supply, return or exhaust ducts in exposed locations.

G. Outside air intake ducts.

1.02 FIELD CONDITIONS

A. Maintain ambient temperatures and conditions required by manufacturers of

adhesives, mastics, and insulation cements.

B. Maintain temperature during and after installation for minimum period of 24 hours.

PART 2 PRODUCTS

2.01 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION

A. Surface Burning Characteristics: Flame spread/Smoke developed index of 25/50,

maximum, when tested in accordance with ASTM E 84, NFPA 255, or UL 723.

B. The Contractor shall use the following minimum pipe sizes and lengths of duct,

and horizontal supports are at least 2 by 2 by 1/4 inch steel angle or equivalent

steel angle.

C. Access Panels: Do not block access; install fireproofing so that panel can be

removed and reinstalled without damaging fireproofing.

D. Seal all cut edges and ends and repair tears in the fireproofing using aluminum foil tape.

END OF SECTION

SECTION 230719 - HVAC PIPING INSULATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Cooling condensate drain piping insulation.

B. Refrigerant piping insulation.

PART 2 PRODUCTS

2.01 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION

A. Surface Burning Characteristics: Flame spread/Smoke developed index of 25/50,

maximum, when tested in accordance with ASTM E 84, NFPA 255, or UL 723.

B. The Contractor shall use the following minimum pipe sizes and lengths of duct,

and horizontal supports are at least 2 by 2 by 1/4 inch steel angle or equivalent

steel angle.

C. Access Panels: Do not block access; install fireproofing so that panel can be

removed and reinstalled without damaging fireproofing.

D. Seal all cut edges and ends and repair tears in the fireproofing using aluminum foil tape.

END OF SECTION

SECTION 230713 - DUCT INSULATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Duct insulation.

B. Duct liner.

C. Insulation jackets.

D. Supply, return or exhaust ducts in ceiling spaces.

E. Supply, return or exhaust ducts in interior unconditioned areas.

F. Supply, return or exhaust ducts in exposed locations.

G. Outside air intake ducts.

1.02 FIELD CONDITIONS

A. Maintain ambient temperatures and conditions required by manufacturers of

adhesives, mastics, and insulation cements.

B. Maintain temperature during and after installation for minimum period of 24 hours.

PART 2 PRODUCTS

## &lt;

Table with 2 columns: Date, Description

Table with 2 columns: Date, Description
06/19/2023 CONSTRUCTION DOCUMENTS
1 07/21/2023 ADDENDUM 1
2 08/21/2023 ISSUE FOR CONSTRUCTION

Seal / Signature



Project Name

TN - 1504 - Nashville Tanger Outlets

Project Number

69.6677.000

Description

MECHANICAL SPECIFICATIONS

Scale

AS NOTED

M591

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. This Section defines the manner and method by which controls function.
B. Perform the functions listed in the Commissioning Authority for each item of equipment or other assembly to be commissioned.
C. Provide two-way radios for use during the testing.
D. Submit start-up plans, Startup Reports, and Pre-functional Checklists for each item of equipment or other assembly to be commissioned.

1.02 RELATED REQUIREMENTS

- A. Section 23 0913 - Instrumentation and Control Devices for HVAC.
B. Equipment performance, controls and accessories shall be as scheduled on the Drawings and specified herein.
C. Functional Testing of the control system as required by the Commissioning Authority.

1.04 SUBMITTALS

- A. Sequence of Operation Documentation: Submit written sequence of operation for entire HVAC system and each piece of equipment.
B. Control System Diagrams: Submit graphic schematic of the control system showing each control component and each component controlled, monitored, or enabled.
C. Points List: Submit list of all control points indicating at least the following information.

1.05 QUALITY ASSURANCE

- A. Design system under direct supervision of a Professional Engineer experienced in design of this work and licensed at the State in which the Project is located.
B. Control system manufacturer shall provide a minimum of two copies of the system manual to the Owner for their reference.
C. Provide three copies of the controls training manuals in a separate manual from the O&M manuals.

PART 2 PRODUCTS

- 1.01 FAN COIL UNITS
A. Time Schedule: Control fan coil units based on the programmed time schedule as determined by the Owner's operating personnel.
B. Supply fan shall run continuously during the occupied period and cycle during the unoccupied period based on a demand for heating or cooling.
C. Dual temperature thermostat or EMS sensor/controller set at 75 degrees F (24 degrees C) maintains constant space temperature during the occupied mode and 10 degrees F (6 degrees C) warmer/cooler during the unoccupied mode by cycling refrigeration compressors and operating reversing valve on a call for heating.

3.02 UNIT HEATERS

- A. Time Schedule: Control unit heaters based on the programmed time schedule as determined by the Owner's operating personnel.
B. Automatic Start Capabilities: Controls shall be capable of automatically adjusting the daily start time of the HVAC system in order to bring each space to the desired occupant temperature immediately prior to scheduled occupancy.

3.21 EXHAUST FANS

- A. General building exhaust fans
B. Specific purpose exhaust fans shall be interlocked with the respective equipment as indicated on the Drawings. Provide necessary sensors and relays to allow control system to accurately sense equipment operation and activate fan systems accordingly.

3.22 MAKE UP AIR UNITS/FANS

- A. Time Schedule: Start and stop make up air fans based on the programmed time schedule as determined by the Owner's operating personnel.

PART 3 EXECUTION

- A. Coordinate with the Commissioning Authority in development of the Pre-functional Checklists and Functional Test Procedures.
B. Furnish additional information requested by the Commissioning Authority.
C. Prepare a preliminary schedule for HVAC pipe and duct system testing, flushing and cleaning, equipment start-up and testing, adjusting, and balancing start and completion for use by the Commissioning Authority; update the schedule as appropriate.
D. Notify the Commissioning Authority when pipe and duct system testing, flushing, cleaning, start-up of each piece of equipment and testing, adjusting, and balancing will occur when commissioning activities not yet performed or not yet scheduled will delay construction notify ahead of time and be proactive in seeing that the Commissioning Authority has the scheduling information needed to efficiently execute the commissioning process.

END OF SECTION

SECTION 230900 - COMMISSIONING OF HVAC

PART 1 GENERAL

1.01 SUMMARY

- A. See Section 01 9113 - General Commissioning Requirements for overall objectives; comply with the requirements of Section 01 9113.
B. This Authority covers the requirements for commissioning; each subcontractor or installer responsible for the installation of a particular system or equipment item to be commissioned is responsible for the commissioning activities relating to that system or equipment item.
C. The Commissioning Authority (CA) directs and coordinates all commissioning activities and provides Pre-functional Checklists and Functional Test Procedures for Contractor's use.

1.02 RELATED REQUIREMENTS

- A. Section 23 0913 - Instrumentation and Control Devices for HVAC Controls.
B. Section 23 0535 - Testing, Adjusting, and Balancing for HVAC.
C. ASHRAE Guideline 1.1 - The HVAC Commissioning Process, 2012.
D. Updated Submittals: Keep the Commissioning Authority informed of all changes to control system documentation made during programming and setup; revise and resubmit when substantial changes are made in control parameters.

1.04 SUBMITTALS

- A. Updated Submittals: Keep the Commissioning Authority informed of all changes to control system documentation made during programming and setup; revise and resubmit when substantial changes are made in control parameters.
B. DRAFT Pre-functional Checklists and Functional Test Procedures for Control System: Detailed written plan indicating the control parameters to be tested, checked, and adjusted; the control system prior to full system Functional Testing; include at least the following for each piece of equipment:
1. System name.
2. List of devices.
3. Step-by-step procedures for testing each controller after installation, including:
a. Process of verifying proper hardware and wiring installation.
b. Process of downloading programs to local controllers and verifying that they are addressed correctly.
c. Process of performing operational checks of each controlled component.
d. Plan and process for calibrating valve and damper actuators and all sensors.
e. Description of the expected field adjustments for transmitters, actuators, and controllers and interlocks with other systems.
f. Copy of proposed log and field check-out sheets to be used to document the process; include space for initial and final read values during calibration of each point and space to specifically indicate when a sensor or controller has "passed" and is operating within the contract parameters.

1.05 OPERATION AND MAINTENANCE MANUALS

- A. Demonstrate operation and maintenance of HVAC system to Owner's personnel; if during any demonstration, the system fails to perform in accordance with the information included in the O&M manual, stop demonstration, repair or adjust, and repeat demonstration. Demonstrations may be combined with training sessions if appropriate.
B. HVAC demonstrations are in addition to, and not a substitute for, Pre-functional Checklists and demonstrations to the Commissioning Authority during Functional Testing.
C. Provide classroom and hands-on training of Owner's designated personnel on operation and maintenance of the HVAC system, control system, and all equipment items indicated to be commissioned. Return for follow up training not less than 30 days after initial training and not more than 6 months after initial training.
D. Review and approve video recording of all training sessions and deliver two copies on DVD's to the Owner for their reference.
E. Review final TAB report, explaining the layout and meanings of each data type.
1. Type.
2. Discuss any outstanding deficient items in control, ducting or design that may affect the proper delivery of air or water.
3. Identify and discuss any terminal units, duct runs, diffusers, coils, fans and pumps that are close to or are not meeting their design capacity.
4. Discuss any temporary settings and steps to finalize them for any areas that are not finalized.
5. Other salient information that may be useful for facility operations, relative to TAB.

1.06 DEMONSTRATION AND TRAINING

- A. Demonstrate operation and maintenance of HVAC system to Owner's personnel; if during any demonstration, the system fails to perform in accordance with the information included in the O&M manual, stop demonstration, repair or adjust, and repeat demonstration. Demonstrations may be combined with training sessions if appropriate.
B. HVAC demonstrations are in addition to, and not a substitute for, Pre-functional Checklists and demonstrations to the Commissioning Authority during Functional Testing.
C. Provide classroom and hands-on training of Owner's designated personnel on operation and maintenance of the HVAC system, control system, and all equipment items indicated to be commissioned. Return for follow up training not less than 30 days after initial training and not more than 6 months after initial training.
D. Review and approve video recording of all training sessions and deliver two copies on DVD's to the Owner for their reference.
E. Review final TAB report, explaining the layout and meanings of each data type.
1. Type.
2. Discuss any outstanding deficient items in control, ducting or design that may affect the proper delivery of air or water.
3. Identify and discuss any terminal units, duct runs, diffusers, coils, fans and pumps that are close to or are not meeting their design capacity.
4. Discuss any temporary settings and steps to finalize them for any areas that are not finalized.
5. Other salient information that may be useful for facility operations, relative to TAB.

1.07 HVAC CONTROL SYSTEM TRAINING

- A. Phase 1 - Basic Control System: Provide minimum of 16 hours of actual training on the control system itself. Upon completion of training, each attendee, using appropriate documentation, should be able to perform elementary operations and describe general hardware architecture and functionality of the system.
a. This training may be held on-site or at the manufacturer's facility, necessary.
b. If held off-site, the training may occur prior to final completion of the system installation. Contractor shall pay expenses of up to two attendees.
2. Phase 2 - Integrating with HVAC Systems: Provide minimum of 16 hours on-site, hands-on training after completion of Functional Testing. Include instruction on:
a. The specific hardware configuration of installed systems in this facility and specific instruction for operating the installed system, including interface with other systems, if any.
b. Security levels, alarms, system start-up, shut-down, power outage and restart routines, change setpoints, and other typical changes.
c. Trend logging and monitoring features (values, change of state, setpoints, etc.).
d. Every display screen, allowing time for questions.
e. Use of keypad or click-in laptop computer at the zone level.
f. Use of remote access to the system via phone lines or networks.
g. Setting up and managing an air terminal unit controller.
h. Graphics generation.
i. Understanding BDC field panel operating programming, when applicable.
3. Phase 3 - Post-Occupancy: Six months after occupancy conduct minimum of 16 hours of training on-site. Provide necessary sensors and relays to allow control system to accurately sense equipment operation and activate fan systems accordingly.
H. Provide the services of the HVAC controls instructor at all training sessions, when requested, to discuss the integration of the controls system as it relates to the equipment being discussed.

END OF SECTION

SECTION 230900 - SEQUENCE OF OPERATIONS FOR HVAC CONTROLS

PART 1 GENERAL

1.01 SUMMARY

- A. See Section 01 9113 - General Commissioning Requirements for overall objectives; comply with the requirements of Section 01 9113.

1.02 RELATED REQUIREMENTS

- A. Section 23 0913 - Instrumentation and Control Devices for HVAC.


1.04 SUBMITTALS

- A. Sequence of Operation Documentation: Submit written sequence of operation for entire HVAC system and each piece of equipment.

Date	Description
------	-------------

06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION

Scale	Description
-------	-------------



Project Name
--------------

TN - 1504 - Nashville Tanger Outlets

Project Number
----------------

69.6677.000

Description
-------------

MECHANICAL SPECIFICATIONS

Scale
-------

AS NOTED

M592

1.01 SECTION INCLUDES	A. Metal ductwork. B. Nonmetal ductwork. C. Round spiral ductwork. D. Double wall insulated round ductwork. E. Kitchen hood ductwork, Type 1 grease hoods. F. Duct cleaning.	3.03 CLEANING A. Clean duct system and force air or high velocity through duct to remove accumulated dust or clean with high power vacuum machines. To obtain sufficient air, clean half the system at a time. Protect equipment which may be harmed by excessive dirt with temporary filters, or bypass during cleaning.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
1.02 PERFORMANCE REQUIREMENTS	A. No variation of duct configuration or sizes permitted except by written permission. Size round ducts installed in place of rectangular ducts in accordance with ASHRAE table of equivalent rectangular and round ducts, only after approval of the Engineer. Sizes shall be secure and rigid. The Contractor may increase duct size without engineer approval, provided all ceiling and shaft clearances can be maintained. Additional charges for increased duct size will not be accepted by the owner. B. Report all conflicts with structure or other obstructions, prior to fabrication of any ductwork. Suitable adjustments in sizes of ducts shall be accommodated without any additional expense to the Owner.	3.04 SCHEDULES A. Ductwork Material: 1. The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the material shall be the responsibility of the installing Contractor as follows: 1. Low Velocity Supply (Heating Systems): Galvanized Steel, Aluminum. 2. Low Velocity Supply (Cooling): Galvanized Steel, Aluminum. 3. Return and Relief: Galvanized Steel, Aluminum. 4. General Exhaust: Galvanized Steel, Aluminum. 5. Outside Air Intake: a. Kitchen Hood Exhaust, Type 1: Carbon Steel, Stainless Steel, Constructed per NFPA 96. b. Kitchen Hood Exhaust, Type 2: Carbon Steel, Stainless Steel, Constructed per NFPA 96. C. Ductwork Pressure Class: 1. Low Velocity Supply (Heating Systems): Scheduled System ESP +0.25", round up to next higher pressure class. 2. Low Velocity Supply (Systems with Cooling): Scheduled System ESP +0.5", round up to next higher pressure class. 3. Return and Relief: 1 inch. 4. General Exhaust: Scheduled System ESP +1.0", round up to next higher pressure class. 5. Outside Air Intake: 1 inch. 6. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
1.03 SUBMITTALS	A. Shop Drawings: Indicate duct fittings, particulars such as gages, sizes, welds, and configuration prior to start of work for all systems. No ductwork shall be fabricated until engineer approved shop drawings have been received by the Contractor. Identify on ductwork shop drawings any deviations in sizes or shapes made necessary by the obstructions of other trades. B. Test Reports: Indicate pressure tests performed. Include date, section tested, test pressure, and leakage rate, following SMACNA (LEAK) - HVAC Air Duct Leakage Test Manual.	3.05 REGULATORY REQUIREMENTS A. Construct ductwork to NFPA 90A, NFPA 90B, and NFPA 96 standards. B. Code or utility company requirements shall supersede any conflicting requirements of this Section.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
1.04 REGULATORY REQUIREMENTS	A. Construct ductwork to NFPA 90A, NFPA 90B, and NFPA 96 standards. B. Code or utility company requirements shall supersede any conflicting requirements of this Section.	3.06 FIELD CONDITIONS A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers. B. Maintain temperatures within acceptable range during and after installation of duct sealants.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
1.05 FIELD CONDITIONS	A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers. B. Maintain temperatures within acceptable range during and after installation of duct sealants.	3.07 MATERIALS A. Galvanized Steel Ducts: Hot-dipped galvanized steel sheet, ASTM A 653/A 653M FS Type B, with G90/Z275 coating. B. Steel Ducts: ASTM A 1008/A 1008M, Designation CS, cold-rolled commercial flat. C. Aluminum Ducts: ASTM B 209 (ASTM B 209M), aluminum sheet, alloy 3003-H14. D. Aluminum Connectors and Accessories: Galvanized Steel, Aluminum. E. Insulated Flexible Ducts: 1. The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected ductwork material is the sole responsibility of the installing Contractor. 2. Two ply vinyl film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 180 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 3. Black polymer film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 0.5 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 175 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 4. Multiple layers of aluminum laminate supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 5. UL 181, Class 1, aluminum laminate and polyester film with latex adhesive supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 6. UL 181, Class 0, interlocking spiral of aluminum foil; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 8 inches WG positive or negative. b. Maximum Velocity: 5000 fpm. c. Temperature Range: -20 degrees F to 250 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. E. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant. 1. Type: Heavy mastic or liquid used alone or with tape, suitable for joint configuration and compatible with substrate, and recommended by manufacturer. 2. VOC Content: Not more than 250 g/L, excluding water. 3. Surface Burning Characteristics: Classified as zero, smoke developed of zero, when tested in accordance with ASTM E 84. 4. For Use With Flexible Insulation: Not applicable. 5. Ductwork Exposed to the Weather: Hard coat VersaGrip 102, (VG-102), UL 181-AM compliant duct joint sealer, as manufactured by Carlisle, with fiberglass scrim tape reinforcement on all seams and on joints, available in longitudinal and circumferential configurations. F. Hanger Rod: ASTM A 36/A 36M; steel; threaded both ends, threaded one end, or continuously threaded.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.01 MATERIALS	A. Galvanized Steel Ducts: Hot-dipped galvanized steel sheet, ASTM A 653/A 653M FS Type B, with G90/Z275 coating. B. Steel Ducts: ASTM A 1008/A 1008M, Designation CS, cold-rolled commercial flat. C. Aluminum Ducts: ASTM B 209 (ASTM B 209M), aluminum sheet, alloy 3003-H14. D. Aluminum Connectors and Accessories: Galvanized Steel, Aluminum. E. Insulated Flexible Ducts: 1. The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected ductwork material is the sole responsibility of the installing Contractor. 2. Two ply vinyl film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 180 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 3. Black polymer film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 0.5 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 175 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 4. Multiple layers of aluminum laminate supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 5. UL 181, Class 1, aluminum laminate and polyester film with latex adhesive supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 6. UL 181, Class 0, interlocking spiral of aluminum foil; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 8 inches WG positive or negative. b. Maximum Velocity: 5000 fpm. c. Temperature Range: -20 degrees F to 250 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. E. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant. 1. Type: Heavy mastic or liquid used alone or with tape, suitable for joint configuration and compatible with substrate, and recommended by manufacturer. 2. VOC Content: Not more than 250 g/L, excluding water. 3. Surface Burning Characteristics: Classified as zero, smoke developed of zero, when tested in accordance with ASTM E 84. 4. For Use With Flexible Insulation: Not applicable. 5. Ductwork Exposed to the Weather: Hard coat VersaGrip 102, (VG-102), UL 181-AM compliant duct joint sealer, as manufactured by Carlisle, with fiberglass scrim tape reinforcement on all seams and on joints, available in longitudinal and circumferential configurations. F. Hanger Rod: ASTM A 36/A 36M; steel; threaded both ends, threaded one end, or continuously threaded.	3.08 DUCTWORK FABRICATION A. Fabricate, support and seal in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible, and as indicated. Provide duct material, gages, reinforcing, and sealing for operating pressures. B. Construct "T"s, bends, and elbows with radius of not less than 1-1/2 times width of duct on centerline, where not otherwise indicated. Provide turning vanes of perforated metal with equal surface area. Where occasional lining is indicated, provide turning vanes of duct material with equal surface area. C. Increase duct sizes gradually, not exceeding 15 degrees divergence wherever possible; maximum 30 degrees divergence upstream of equipment and 45 degrees convergence downstream. D. Fabricate continuously welded round and oval duct fittings two gages heavier than duct gages indicated in SMACNA Standards, rest of ductwork as indicated. Provide standard 45 degree lateral pipe takeoffs unless otherwise indicated where 90 degree conical tee connections may be used. E. Where ducts are connected to exterior wall louvers and duct outlet is smaller than louver frame, provide blank-out panels sealing lower portion of louver. Use same material as duct, painted black on exterior side, seal to louver frame and duct. F. Where ducts are connected to exterior wall louvers and duct outlet is smaller than louver frame, provide blank-out panels sealing lower portion of louver. Use same material as duct, painted black on exterior side, seal to louver frame and duct.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.02 PRODUCTS	A. Air turning devices/extractors. B. Volume control dampers. C. Flexible duct connections. D. Wall registers and grilles.	3.09 ACCESSORIES A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.03 QUALITY ASSURANCE	A. Test and rate air outlet and inlet performance in accordance with ASHRAE Std 70. B. Test and rate lower performance in accordance with ASHRAE Std 70. C. Code requirements shall supersede any conflicting requirements of this Section.	3.10 REGULATORY REQUIREMENTS A. Construct ductwork to NFPA 90A, NFPA 90B, and NFPA 96 standards. B. Code or utility company requirements shall supersede any conflicting requirements of this Section.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.04 QUALIFICATIONS	A. Manufacturer Qualifications: Company specializing in manufacturing the type of product specified in this Section, with minimum five years of documented experience.	3.11 FIELD CONDITIONS A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers. B. Maintain temperatures within acceptable range during and after installation of duct sealants.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.05 ACCESSORIES	A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	3.12 MATERIALS A. Galvanized Steel Ducts: Hot-dipped galvanized steel sheet, ASTM A 653/A 653M FS Type B, with G90/Z275 coating. B. Steel Ducts: ASTM A 1008/A 1008M, Designation CS, cold-rolled commercial flat. C. Aluminum Ducts: ASTM B 209 (ASTM B 209M), aluminum sheet, alloy 3003-H14. D. Aluminum Connectors and Accessories: Galvanized Steel, Aluminum. E. Insulated Flexible Ducts: 1. The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected ductwork material is the sole responsibility of the installing Contractor. 2. Two ply vinyl film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 180 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 3. Black polymer film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 0.5 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 175 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 4. Multiple layers of aluminum laminate supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 5. UL 181, Class 1, aluminum laminate and polyester film with latex adhesive supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 6. UL 181, Class 0, interlocking spiral of aluminum foil; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 8 inches WG positive or negative. b. Maximum Velocity: 5000 fpm. c. Temperature Range: -20 degrees F to 250 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. E. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant. 1. Type: Heavy mastic or liquid used alone or with tape, suitable for joint configuration and compatible with substrate, and recommended by manufacturer. 2. VOC Content: Not more than 250 g/L, excluding water. 3. Surface Burning Characteristics: Classified as zero, smoke developed of zero, when tested in accordance with ASTM E 84. 4. For Use With Flexible Insulation: Not applicable. 5. Ductwork Exposed to the Weather: Hard coat VersaGrip 102, (VG-102), UL 181-AM compliant duct joint sealer, as manufactured by Carlisle, with fiberglass scrim tape reinforcement on all seams and on joints, available in longitudinal and circumferential configurations. F. Hanger Rod: ASTM A 36/A 36M; steel; threaded both ends, threaded one end, or continuously threaded.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.06 ACCESSORIES	A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	3.13 REGULATORY REQUIREMENTS A. Construct ductwork to NFPA 90A, NFPA 90B, and NFPA 96 standards. B. Code or utility company requirements shall supersede any conflicting requirements of this Section.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.07 ACCESSORIES	A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	3.14 FIELD CONDITIONS A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers. B. Maintain temperatures within acceptable range during and after installation of duct sealants.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.08 ACCESSORIES	A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	3.15 MATERIALS A. Galvanized Steel Ducts: Hot-dipped galvanized steel sheet, ASTM A 653/A 653M FS Type B, with G90/Z275 coating. B. Steel Ducts: ASTM A 1008/A 1008M, Designation CS, cold-rolled commercial flat. C. Aluminum Ducts: ASTM B 209 (ASTM B 209M), aluminum sheet, alloy 3003-H14. D. Aluminum Connectors and Accessories: Galvanized Steel, Aluminum. E. Insulated Flexible Ducts: 1. The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected ductwork material is the sole responsibility of the installing Contractor. 2. Two ply vinyl film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 180 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 3. Black polymer film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 0.5 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 175 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 4. Multiple layers of aluminum laminate supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 5. UL 181, Class 1, aluminum laminate and polyester film with latex adhesive supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 6. UL 181, Class 0, interlocking spiral of aluminum foil; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 8 inches WG positive or negative. b. Maximum Velocity: 5000 fpm. c. Temperature Range: -20 degrees F to 250 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. E. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant. 1. Type: Heavy mastic or liquid used alone or with tape, suitable for joint configuration and compatible with substrate, and recommended by manufacturer. 2. VOC Content: Not more than 250 g/L, excluding water. 3. Surface Burning Characteristics: Classified as zero, smoke developed of zero, when tested in accordance with ASTM E 84. 4. For Use With Flexible Insulation: Not applicable. 5. Ductwork Exposed to the Weather: Hard coat VersaGrip 102, (VG-102), UL 181-AM compliant duct joint sealer, as manufactured by Carlisle, with fiberglass scrim tape reinforcement on all seams and on joints, available in longitudinal and circumferential configurations. F. Hanger Rod: ASTM A 36/A 36M; steel; threaded both ends, threaded one end, or continuously threaded.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.09 ACCESSORIES	A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	3.16 FIELD CONDITIONS A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers. B. Maintain temperatures within acceptable range during and after installation of duct sealants.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.10 ACCESSORIES	A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	3.17 MATERIALS A. Galvanized Steel Ducts: Hot-dipped galvanized steel sheet, ASTM A 653/A 653M FS Type B, with G90/Z275 coating. B. Steel Ducts: ASTM A 1008/A 1008M, Designation CS, cold-rolled commercial flat. C. Aluminum Ducts: ASTM B 209 (ASTM B 209M), aluminum sheet, alloy 3003-H14. D. Aluminum Connectors and Accessories: Galvanized Steel, Aluminum. E. Insulated Flexible Ducts: 1. The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected ductwork material is the sole responsibility of the installing Contractor. 2. Two ply vinyl film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 180 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 3. Black polymer film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 0.5 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 175 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 4. Multiple layers of aluminum laminate supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 5. UL 181, Class 1, aluminum laminate and polyester film with latex adhesive supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 6. UL 181, Class 0, interlocking spiral of aluminum foil; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 8 inches WG positive or negative. b. Maximum Velocity: 5000 fpm. c. Temperature Range: -20 degrees F to 250 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. E. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant. 1. Type: Heavy mastic or liquid used alone or with tape, suitable for joint configuration and compatible with substrate, and recommended by manufacturer. 2. VOC Content: Not more than 250 g/L, excluding water. 3. Surface Burning Characteristics: Classified as zero, smoke developed of zero, when tested in accordance with ASTM E 84. 4. For Use With Flexible Insulation: Not applicable. 5. Ductwork Exposed to the Weather: Hard coat VersaGrip 102, (VG-102), UL 181-AM compliant duct joint sealer, as manufactured by Carlisle, with fiberglass scrim tape reinforcement on all seams and on joints, available in longitudinal and circumferential configurations. F. Hanger Rod: ASTM A 36/A 36M; steel; threaded both ends, threaded one end, or continuously threaded.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.11 ACCESSORIES	A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	3.18 FIELD CONDITIONS A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers. B. Maintain temperatures within acceptable range during and after installation of duct sealants.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.12 ACCESSORIES	A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	3.19 MATERIALS A. Galvanized Steel Ducts: Hot-dipped galvanized steel sheet, ASTM A 653/A 653M FS Type B, with G90/Z275 coating. B. Steel Ducts: ASTM A 1008/A 1008M, Designation CS, cold-rolled commercial flat. C. Aluminum Ducts: ASTM B 209 (ASTM B 209M), aluminum sheet, alloy 3003-H14. D. Aluminum Connectors and Accessories: Galvanized Steel, Aluminum. E. Insulated Flexible Ducts: 1. The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected ductwork material is the sole responsibility of the installing Contractor. 2. Two ply vinyl film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 180 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 3. Black polymer film supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 0.5 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 175 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 4. Multiple layers of aluminum laminate supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 5. UL 181, Class 1, aluminum laminate and polyester film with latex adhesive supported by helically wound spring steel wire; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 10 inches WG positive and 1.0 inches WG negative. b. Maximum Velocity: 4000 fpm. c. Temperature Range: -20 degrees F to 210 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. 6. UL 181, Class 0, interlocking spiral of aluminum foil; fiberglass insulation; aluminum vapor barrier film. a. Pressure Rating: 8 inches WG positive or negative. b. Maximum Velocity: 5000 fpm. c. Temperature Range: -20 degrees F to 250 degrees F. d. Minimum R-Value: 4.2 or greater as required by the applicable energy codes. E. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant. 1. Type: Heavy mastic or liquid used alone or with tape, suitable for joint configuration and compatible with substrate, and recommended by manufacturer. 2. VOC Content: Not more than 250 g/L, excluding water. 3. Surface Burning Characteristics: Classified as zero, smoke developed of zero, when tested in accordance with ASTM E 84. 4. For Use With Flexible Insulation: Not applicable. 5. Ductwork Exposed to the Weather: Hard coat VersaGrip 102, (VG-102), UL 181-AM compliant duct joint sealer, as manufactured by Carlisle, with fiberglass scrim tape reinforcement on all seams and on joints, available in longitudinal and circumferential configurations. F. Hanger Rod: ASTM A 36/A 36M; steel; threaded both ends, threaded one end, or continuously threaded.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.
2.13 ACCESSORIES	A. Manufacturers: Krueger; Ruskin Company; Tluc. B. Multi-blade dampers: Provide oil-impregnated nylon or sintered bronze bearings. C. Return and Relief: Galvanized Steel, Aluminum. D. General Exhaust: Galvanized Steel, Aluminum. E. Outside Air Intake: 1 inch. F. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional. END OF SECTION	3.20 FIELD CONDITIONS A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers. B. Maintain temperatures within acceptable range during and after installation of duct sealants.	variable and adjustable pitch motor; hose selected so required rpm is obtained with shaves set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings. K. Kitchen hood exhausters shall be upblast with grease trap, ventilated double wall curb and hinged curb support base for cleaning. Hood exhausters shall comply with requirements of NFPA 9

SYSTEM 2 FRONT OF HOUSE																
ROOM #	NAME	Az AREA (FT <sup>2</sup> )	TABLE 403.3.1.1 OCCUPANCY CATEGORY	TABLE 403.3.1.1 R <sub>D</sub> PEOPLE OA (CFM/PER)	TABLE 403.3.1.1 R <sub>a</sub> AREA OA (CFM/FT <sup>2</sup> )	TABLE 403.3.1.1 OCCUPANT DENSITY (#/1000 FT <sup>2</sup> )	Pz (#)	R <sub>1</sub> Pz	R <sub>2</sub> Pz	R <sub>3</sub> Pz	Vz (CFM)	TABLE 403.3.1.1.2 V <sub>z</sub> (CFM)	V <sub>z</sub> MAX SUPPLY (CFM)	V <sub>z</sub> MIN SUPPLY (CFM)	Z <sub>p</sub>	INTERPOLATED TABLE 403.3.1.1.2.3.2 E <sub>v</sub>
102	DINING ROOM	1,381	CAFETERIA/FAST FOOD DINING	7.5	0.18	100	0	0	11	11	0.80	54	0	0	0.000	1.00
112	CORRIDOR	151	CORRIDORS	0.0	0.08	0	0	0	0	0	0.80	19	350	350	0.054	1.00
		1,532					08	510	252	772		965	5000	5000	0.180	0.98

OUTDOOR AIR CALCULATIONS PER EQUATION 4.1:

SYMBOL	VALUE	DESCRIPTION
P <sub>s</sub>	88	SYSTEM POPULATION
SP <sub>z</sub>	0.8	ZONE POPULATION
D	1.00	OCCUPANT DIVERSITY
V <sub>ou</sub>	772	UNCORRECTED OUTDOOR AIR INTAKE
Z <sub>p</sub> (ft)	0.180	ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)
E <sub>v</sub>	0.98	SYSTEM VENTILATION EFFICIENCY
SV <sub>z</sub>	5000	ZONE PRIMARY AIRFLOW
V <sub>ot</sub>	804	CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM
V <sub>ot</sub>	808	DESIGN OUTDOOR AIRFLOW RATE, CFM

SYSTEM 4 OFFICE																
ROOM #	NAME	Az AREA (FT <sup>2</sup> )	TABLE 403.3.1.1 OCCUPANCY CATEGORY	TABLE 403.3.1.1 R <sub>D</sub> PEOPLE OA (CFM/PER)	TABLE 403.3.1.1 R <sub>a</sub> AREA OA (CFM/FT <sup>2</sup> )	TABLE 403.3.1.1 OCCUPANT DENSITY (#/1000 FT <sup>2</sup> )	Pz (#)	R <sub>1</sub> Pz	R <sub>2</sub> Pz	R <sub>3</sub> Pz	Vz (CFM)	TABLE 403.3.1.1.2 V <sub>z</sub> (CFM)	V <sub>z</sub> MAX SUPPLY (CFM)	V <sub>z</sub> MIN SUPPLY (CFM)	Z <sub>p</sub>	INTERPOLATED TABLE 403.3.1.1.2.3.2 E <sub>v</sub>
107	MANAGERS OFFICE	85	OFFICE SPACES	5.0	0.08	5	2	10	5	15	0.80	19	350	350	0.054	1.00
		85					2	10	5	15		19	350	350	0.054	1.00

OUTDOOR AIR CALCULATIONS PER EQUATION 4.1:

SYMBOL	VALUE	DESCRIPTION
P <sub>s</sub>	2	SYSTEM POPULATION
SP <sub>z</sub>	2	ZONE POPULATION
D	1.00	OCCUPANT DIVERSITY
V <sub>ou</sub>	15	UNCORRECTED OUTDOOR AIR INTAKE
Z <sub>p</sub> (ft)	0.054	ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)
E <sub>v</sub>	1.00	SYSTEM VENTILATION EFFICIENCY
SV <sub>z</sub>	350	ZONE PRIMARY AIRFLOW
V <sub>ot</sub>	15	CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM
V <sub>ot</sub>	15	DESIGN OUTDOOR AIRFLOW RATE, CFM

SYSTEM 5 BOH																
ROOM #	NAME	Az AREA (FT <sup>2</sup> )	TABLE 403.3.1.1 OCCUPANCY CATEGORY	TABLE 403.3.1.1 R <sub>D</sub> PEOPLE OA (CFM/PER)	TABLE 403.3.1.1 R <sub>a</sub> AREA OA (CFM/FT <sup>2</sup> )	TABLE 403.3.1.1 OCCUPANT DENSITY (#/1000 FT <sup>2</sup> )	Pz (#)	R <sub>1</sub> Pz	R <sub>2</sub> Pz	R <sub>3</sub> Pz	Vz (CFM)	TABLE 403.3.1.1.2 V <sub>z</sub> (CFM)	V <sub>z</sub> MAX SUPPLY (CFM)	V <sub>z</sub> MIN SUPPLY (CFM)	Z <sub>p</sub>	INTERPOLATED TABLE 403.3.1.1.2.3.2 E <sub>v</sub>
103	FRONT OF HOUSE	139	SALES	7.5	0.12	15	3	23	17	39	0.80	49	800	800	0.061	1.00
104	COLDLINE	162	KITCHEN (COOKING)	7.5	0.12	20	4	30	19	49	0.80	62	830	830	0.068	1.00
105	COOKLINE	237	KITCHEN (COOKING)	7.5	0.12	20	5	38	28	66	0.80	82	2150	2150	0.059	1.00
106	BOH	360	KITCHEN (COOKING)	7.5	0.12	20	12	90	68	158	0.80	158	3270	3270	0.060	1.00
108	DISHWASH AREA	195	KITCHEN (COOKING)	7.5	0.12	20	4	30	23	53	0.80	67	1680	1680	0.040	1.00
110	MENS RESTROOM	114	NO LISTING	0.0	0.00	0	0	0	0	0	0.80	0	100	100	0.000	1.00
111	WOMENS RESTROOM	130	NO LISTING	0.0	0.00	0	0	0	0	0	0.80	0	100	100	0.000	1.00
		1,541					08	210	158	368		458	9000	9000	0.058	1.00

OUTDOOR AIR CALCULATIONS PER EQUATION 4.1:

SYMBOL	VALUE	DESCRIPTION
P <sub>s</sub>	28	SYSTEM POPULATION
SP <sub>z</sub>	28	ZONE POPULATION
D	1.00	OCCUPANT DIVERSITY
V <sub>ou</sub>	366	UNCORRECTED OUTDOOR AIR INTAKE
Z <sub>p</sub> (ft)	0.066	ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)
E <sub>v</sub>	1.00	SYSTEM VENTILATION EFFICIENCY
SV <sub>z</sub>	9000	ZONE PRIMARY AIRFLOW
V <sub>ot</sub>	366	CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM
V <sub>ot</sub>	370	DESIGN OUTDOOR AIRFLOW RATE, CFM

① OUTSIDE AIR CALCULATIONS

RTU/ACU CONTROL MATRIX			
SETPOINT/CONTROL	EX. RTU-1 DINING	EX. RTU-1, EX. RTU-2 KITCHEN	FC-1 OFFICE
<b>*SETPOINTS*</b>			
COOLING - OCCUPIED SETPOINT	75 F	75 F	75 F
COOLING - UNOCCUPIED SETPOINT	80 F	80 F	80 F
HEATING - OCCUPIED SETPOINT	70 F	70 F	70 F
HEATING - UNOCCUPIED SETPOINT	60 F	60 F	60 F
ECONOMIZER UPPER LIMIT SETPOINT	65 F	65 F	NA
<b>*ACCESSORIES*</b>			
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT	YES	YES	YES
REMOTE TEMPERATURE SENSOR	YES	YES	NO
MOTORIZED OUTDOOR AIR DAMPER	YES	YES	NO
INTEGRATED ECONOMIZER	YES	YES	NO
ECONOMIZER FAULT DETECTION	YES	YES	NO
BAROMETRIC RELIEF	YES	NO	NO
POWERED EXHAUST RELIEF	NO	YES	NO
DEHUMIDIFICATION (HOT GAS REHEAT)	NO	NO	NO
<b>*SUPPLY FAN*</b>			
ON DURING OCCUPIED MODE	YES	YES	YES
VARIABLE VOLUME - MODULATE FAN SPEED	YES	YES	YES
<b>*SAFETIES AND INTERLOCKS*</b>			
RETURN AIR SMOKE DETECTOR	YES	YES	NO
LOW LIMIT FREEZE/STAT	YES	YES	YES
FIRE ALARM CONTROL PANEL INTERLOCK	YES	YES	YES
KITCHEN EXHAUST SYSTEM INTERLOCK	YES	YES	YES

AIR BALANCE SCHEDULE						
EQUIPMENT TAG	SUPPLY AIRFLOW (CFM)	OUTDOOR AIRFLOW (CFM)	RETURN AIRFLOW (CFM)	EXHAUST AIRFLOW (CFM)	OA/SA (%)	REMARKS
EX. RTU-1	5,000	805	4,195		16%	
EX. RTU-2	5,000	205	4,795		4%	
EX. RTU-3	4,000	165	3,835		4%	
MUA-1	2,055	2,055	0		100%	
FC-1	350	15	335		4%	
EF-1				1,285		
EF-2				1,285		
EF-3				300		
TOTAL =		16,405	3,245	13,160	2,870	
RESULTING BUILDING PRESSURIZATION =		375 CFM				
PRESSURIZATION PERCENTAGE =		2.3 %				

CARRIER EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. CONTACT CARRIER CORPORATION FOR PROPOSALS: KEN REVILLA CARRIER RETAIL STRATEGIC ACCOUNTS EMAIL: KEN.REVILLA@CARRIER.COM PHONE: (954) 218-0070

REVIEW ALL RULES AND REGULATIONS PERTAINING TO HVAC INSTALLATION AND MAINTENANCE.

AIR CURTAINS													
MARK	LENGTH (IN)	AIRFLOW (CFM)	HEATER		FANS		ELECTRICAL		MANUFACTURER	MODEL NUMBER	REMARKS		
			IN (KW)	OUT (MBH)	TEMP RISE (F)	QTY	HP	CR/CLUT (QTY)				VOLT	PH
AC-1	43.0	1,243	NA	NA	NA	1	1/5	1	115	1	POWERED AIR	EVE-1-42	[1-3]
AC-2	119.0	3,730	NA	NA	NA	2	1/5	1	115	1	POWERED AIR	EVE-2-120	[1-3]
AC-3	85.0	2,486	NA	NA	NA	2	1/5	1	115	1	POWERED AIR	EVE-2-84	[1-3]
AC-4	97.0	2,948	NA	NA	NA	2	1/5	1	115	1	POWERED AIR	EVE-2-96	[1-3]
AC-5	73.0	1,968	NA	NA	NA	2	1/5	1	115	1	POWERED AIR	EVE-2-72	[1-3]

REMARKS:  
 1. PROVIDE WITH SWITCH ACTIVATION. COORDINATE WITH ARCHITECT AND OWNER FOR SWITCH TYPE AND INSTALLATION LOCATION.  
 2. PROVIDE WITH MOUNTING SYSTEM. FIELD COORDINATE REQUIREMENTS AND COORDINATE WITH ARCHITECT.  
 3. PROVIDE REMOTE CONTROL PANEL. COORDINATE WITH ARCHITECT FOR TYPE AND INSTALLATION LOCATION.

AIR SOURCE HEAT PUMPS													
MARK	LOCATION	SERVES	NOMINAL COOL (TONS)	HEATING AT 47°F (MBH)	ELECTRICAL		SEER /EER	HSPF /COP	MANUFACTURER	MODEL NUMBER	REMARKS		
					VOLT	PH							
ASHP-1	ROOF	FC-1	3/4	10.0	208	1	15.0	15	20.5/-	10.8/-	CARRIER	38MARBQ09	[1]

REMARKS:  
 1. PROVIDE EQUIPMENT WITH SCOR GREATER THAN THE AVAILABLE FAULT CURRENT AT THE EQUIPMENT OR UPSTREAM PANELBOARD. REFER TO THE ELECTRICAL ONE LINE DIAGRAM AND PANEL SCHEDULES FOR AVAILABLE FAULT CURRENT AT UPSTREAM PANELBOARD.

DUCTLESS SPLIT SYSTEMS													
MARK	NOMINAL (TONS)	COOLING		HEATING		SUPPLY AIR (CFM)	FAN (WATT)	ELECTRICAL			SEER /EER	CARRIER MODEL NUMBER	REMARKS
		TOT (MBH)	SEN (MBH)	OUT (MBH)	VOLT			PH	MCA	MCCP			
FC-1	3/4	11.73	8.79	10.00	350	45	208	1	0.2	N/A	20.5/-	40MBCQ09	[1-3]

REMARKS:  
 1. PROVIDE CONDENSATE PUMP.  
 2. INDOOR UNIT POWER PROVIDED FROM OUTDOOR UNIT.  
 3. PROVIDE NEW, WIRED, FULLY DIGITAL, 7 DAY PROGRAMMABLE TYPE THERMOSTAT WITH AUTO CHANGE OVER AND AUTO SET BACK.

DIFFUSERS, GRILLES AND REGISTERS							
MARK	SERVICE	LOCATION	CEILING TYPE	MOUNTING TYPE	MANUFACTURER	MODEL NUMBER	REMARKS
D-1	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	TMS XX 24x24 3 26	[1,2,6]
D-2	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	OMNI XX 12x12 3 26	[1,2,4,6]
D-3	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	PAR XX 24x24 3 26	[1,2,6]
D-4	SUPPLY	DUCT	NA	SURFACE	TITUS	SOORL X X 1 26	[1,5-7]
G-1	RETURN	CEILING	AC TILE	LAY-IN	TITUS	50F X X 3 26	[1,3,5,6]
G-2	EXHAUST	CEILING	GYP. BOARD	SURFACE	TITUS	50F X X 1 26	[1,3,5-7]

REMARKS:  
 1. TITUS IS THE BASE OF DESIGN. KRUEGER, PRICE, NAILOR, CARNES ARE EQUAL. NO EXCEPTIONS.  
 2. SEE PLAN FOR NECK SIZE.  
 3. PROVIDE 1/2" X 1/2" X 1" CORE.  
 4. PROVIDE WITH MODEL TRM FRAME.  
 5. SEE PLAN FOR SIZE.  
 6. DIFFUSERS SHALL BE FINISHED TO MATCH CEILING/WALL/EXPOSED DUCT COLOR. COORDINATE WITH ARCHITECT.  
 7. PROVIDE DIFFUSERS AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.

EXHAUST FANS												
MARK	LOCATION	SERVICE	AIRFLOW (CFM)	EXTERNAL STATIC (IN H2O)	MOTOR DATA			RPM	MANUFACTURER	MODEL NUMBER	REMARKS	
					SONES	FAN (HP)	VOLT					
EF-1	ROOF	HOOD 1	-	-	-	-	-	-	-	-	[4]	
EF-2	ROOF	HOOD 2	-	-	-	-	-	-	-	-	[4]	
EF-3	ROOF	RESTROOMS	300	0.50	7.2	1/8	115	1	1,550	GREENHECK	G-095-D	[1-3]

REMARKS:  
 1. PROVIDE SOLID STATE SPEED CONTROL.  
 2. PROVIDE MOTORIZED BACKDRAFT DAMPER.  
 3. PROVIDE MINIMUM 12 INCH HEIGHT ROOF CURB.  
 4. REFERENCE CAPTIVEAIRE DRAWINGS FOR ADDITIONAL INFORMATION.

UV SYSTEMS												
UNIT NO.	PLACEMENT	PHI CELL MODEL #	UV/CELL SIZE	RANGE	INDOOR PPM TARGET	SIZE	TRANSFORMER	POWER	IN-VOLT	OUT-VOLT	MCA	WEIGHT (LBS.)
RTU-1	BLOWER CABINET	PHI-PKG14-24V	14"	3,000-8000 CFM	< 0.02 PPM	2.25"W x 19.5"L x 1.75"D	SHIP LOOSE	11W	115 VAC	24 VAC	0.50A	2 LBS
RTU-2	BLOWER CABINET	PHI-PKG14-24V	14"	3,000-8000 CFM	< 0.02 PPM	2.25"W x 19.5"L x 1.75"D	SHIP LOOSE	11W	115 VAC	24 VAC	0.50A	2 LBS
RTU-3	BLOWER CABINET	PHI-PKG14-24V	14"	3,000-8000 CFM	< 0.02 PPM	2.25"W x 19.5"L x 1.75"D	SHIP LOOSE	11W	115 VAC	24 VAC	0.50A	2 LBS



TN - 1504 - Nashville Tanger Outlets  
 4060 CANE RIDGE PKWY, BLDG. 7, SUITE 701  
 ANTIOCH, TN 37013



LIC. NO. AA0002837 TEL 415.433.3700  
 45 FREMONT ST SUITE 1500 FAX 415.836.4599  
 SAN FRANCISCO, CA 94105 UNITED STATES  
 SATELLITE OFFICE: TEL 813.204.9000  
 400 N ASHLEY DRIVE SUITE 0400 FAX 813.223.6948  
 TAMPA, FL 33602 UNITED STATES



New York ■ Miami ■ Omaha ■ Los Angeles ■ Seattle ■ Honolulu  
 800-581-0963 www.schnackel.com

MEPF ENGINEER  
 3035 S 72ND ST  
 OMAHA NE 68124



FOODSERVICE EQUIPMENT, SUPPLIES AND DESIGN  
 FOODSERVICE CONSULTANT  
 505 COLLINS ST  
 PO BOX 3505  
 SOUTH ATTLEBORO MA 02703  
 TEL 508.399.6000  
 FAX 508.761.3620



STRUCTURAL ENGINEER  
 13075 HEATHCOTE BLV  
 SUITE 170  
 GAINESVILLE VA 20155  
 TEL 571.261.9280

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION


Seal / Signature



Project Name  
 TN - 1504 - Nashville Tanger Outlets  
 Project Number  
 69.6677.000  
 Description  
 MECHANICAL SCHEDULES

Scale  
 AS NOTED

M601



HOOD STYLE / MODEL	450 DEGREES cfm/ft.	600 DEGREES cfm/ft.	700 DEGREES cfm/ft.
CANOPY ND-2	150	200	250
CANOPY ND-2 W/ END PANELS	105	140	175
SLOPED SND-2	228	294	-
ISLAND ND-2WI	269	300	350
ISLAND ND-2I	346	422	475

ETL HOOD LISTING DETAIL	
EXHAUST CFM = LENGTH OF HOOD X CFM/LIN.FT. (LOAD)	
SUPPLY CFM = EXHAUST CFM X PERCENTAGE REQUIRED	
TOTAL DUCT AREA (sq. in.) = 144 X (CFM) <sup>2</sup>	
DUCT LENGTH =	DUCT WIDTH
*CAPTIVEAIR HOOVER DUCT SIZE ARE CALCULATED USING AN ASSUMED VELOCITY OF 1000-1800 FPM AND A SUPPLY VELOCITY OF 1000 FPM.	

**CAPTIVE-AIRE HOODS BUILT IN COMPLIANCE WITH:**



**BUILDING CODES**

CAPTIVE-AIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:

MATERIAL	CLEARANCE REDUCTION SYSTEM
NON-COMBUSTIBLE	NONE REQUIRED
LIMITED-COMBUSTIBLE	3" UNINSULATED STANDOFF
COMBUSTIBLE	1" INSULATED STANDOFF


**CLEARANCE TO COMBUSTIBLES**

- INSTALLATION**
- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
  - ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
  - HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
  - ALL CONNECTIONS FROM CAPTIVEAIRE HOOD PER MECHANICAL CONTRACTOR'S PLANS.
  - COOKING EQUIPMENT TO SHUT OFF IN EVENT OF FIRE.
  - EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
  - ALL LIGHT FIXTURES SHOWN INSTALLED BY CAPTIVEAIRE ARE FACTORY PREWIRED. INTERCONNECTING BETWEEN HOODS AND TO SWITCHES ARE BY ELECTRICAL CONTRACTOR.
  - LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
  - SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
  - INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTEGRATION, AND ADMINISTRATION OF CODE REQUIREMENTS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.

- BALANCE**
- KITCHEN HOODS MUST BE BALANCED WITH KITCHEN.
  - KITCHEN SHALL BE NEGATIVE WITH RESPECT TO DINING AREA.
  - RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.

- ADDITIONAL**
- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
  - SIGNED AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE RECEIVED BY THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

**GENERAL NOTES**



CaptiveAire Captrate Solo Filter  
ETL Listed Grease Extracting Filters  
Made From 430 Stainless Steel

**FILTER DETAIL**

FOR QUESTIONS, CALL THE  
Eastern PA Mechanical  
REGION 108  
PHONE: (267) 504-4126  
EMAIL: reg108@captiveaire.com

**HOOD INFORMATION - JOB#5970939**

HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST PLENUM				MUA CFM	AC CFM	HOOD CONSTRUCTION	HOOD CONFIG			
										WIDTH	LENG	HEIGHT	DIA				CFM	VEL	SP	END TO END
1	Hood-Left	5430 ND-2-ACPSP-F	CAPTIVEAIRE	7' 4"	600 DEG	I	HEAVY	175	1283	10'	12'	4'	1283	1540	-0.489'	1026	500	430 SS WHERE EXPOSED	LEFT	ALONE
2	Hood-Right	5430 ND-2-ACPSP-F	CAPTIVEAIRE	7' 4"	600 DEG	I	HEAVY	175	1283	10'	12'	4'	1283	1540	-0.489'	1026	500	430 SS WHERE EXPOSED	RIGHT	ALONE

**HOOD INFORMATION**





HOOD NO	TAG	FILTER(S)				LIGHT(S)		UTILITY CABINET(S)				FIRE SYSTEM PIPING	HOOD HANGING WEIGHT		
		TYPE	QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE			TYPE	SIZE
1	Hood-Left	CAPTRATE SOLD FILTER	5	20"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO				YES	505 LBS	
2	Hood-Right	CAPTRATE SOLD FILTER	5	20"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO	RIGHT	12"x54"x30"	TANK FS	4.0/4.0/4.0	YES	991 LBS

**HOOD OPTIONS**

HOOD NO	TAG	OPTION
1	Hood-Left	FIELD WRAPPER 18.00' HIGH FRONT. LEFT END STANDOFF (FINISHED) 1' WIDE 54' LONG INSULATED. RISER SENSOR INSTALL 6IN PLEN. LEFT WALL AS END PANEL.
2	Hood-Right	FIELD WRAPPER 18.00' HIGH FRONT, RIGHT. RISER SENSOR INSTALL 6IN PLEN. RIGHT WIDE VERTICAL END PANEL 42" TOP WIDTH, 36" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS.

**PERFORATED SUPPLY PLENUM(S)**

HOOD NO	TAG	PDS	LENGTH	WIDTH	HEIGHT	TYPE	RISER(S)				
							WIDTH	LENG	DIA	CFM	SP
1	Hood-Left	Front	89'	24'	6'	MUA	12"	20"		513	0.145'
							12"	20"		513	0.145'
							8"		125	0.049'	
							8"		125	0.049'	
							8"		125	0.049'	
2	Hood-Right	Front	100'	24'	6'	MUA	12"	20"		513	0.145'
							12"	20"		513	0.145'
							8"		125	0.049'	
							8"		125	0.049'	
							8"		125	0.049'	



REVISIONS	
DESCRIPTION	DATE

**CAPTIVEAIRE**

Eastern PA Mechanical  
10804 Union Ave, Bala Cynwyd, PA 19004  
PHONE: (267) 504-4126 EMAIL: reg108@captiveaire.com

Shake Shack-1504-Nashville Tanger, TN  
ANTIOCH, TN, 37013

DATE: 4/26/2023  
DWG.#: 5970939  
DRAWN BY: Joe.shilba  
SCALE: 3/4" = 1'-0"  
MASTER DRAWING  
SHEET NO. 1



TN - 1504 - Nashville Tanger Outlets  
4060 CANE RIDGE PKWY, BLDG. 7, SUITE 701  
ANTIOCH, TN 37013

**Gensler**

LIC. NO. AA0002837 TEL 415.433.3700  
45 FREEMONT ST FAX 415.836.4599  
SUITE 1500  
SAN FRANCISCO, CA 94105  
UNITED STATES

SATELLITE OFFICE: TEL 813.204.9000  
400 N ASHLEY DRIVE FAX 813.223.6948  
SUITE 0400  
TAMPA, FL 33602  
UNITED STATES



New York ■ Miami ■ Omaha ■ Los Angeles ■ Seattle ■ Honolulu  
3035 S 72ND ST  
OMAHA NE 68124  
900-581-0963 www.schnackel.com

MEFP ENGINEER  
3035 S 72ND ST  
OMAHA NE 68124




FOODSERVICE CONSULTANT  
505 COLLINS ST  
PO BOX 3505  
SOUTH ATTLEBORO  
MA 02703  
TEL 508.399.6000  
FAX 508.761.3620



STRUCTURAL ENGINEER  
13075 HEATHCOTE BLV  
SUITE 170  
GAINESVILLE  
VA 20155  
TEL 571.261.9280

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION

Seal / Signature



Project Name  
**TN - 1504 - Nashville Tanger Outlets**


Project Number  
**69.6677.000**

Description  
**CAPTIVEAIRE DRAWINGS**

Scale  
AS NOTED

**M701**

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION



Project Name  
**TN - 1504 - Nashville Tanger Outlets**

Project Number  
**69.6677.000**

Description  
**CAPTIVEAIRE DRAWINGS**

Scale  
AS NOTED

**M702**

REVISIONS	
DESCRIPTION	DATE

**CAPTIVEAIRE**

Eastern, PA Mechanical  
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 504-4126 EMAIL: [reg108@captivaire.com](mailto:reg108@captivaire.com)

Shake Shack-1504-Nashville Tanger, TN  
ANTIOCH, TN, 37013

DATE: 4/26/2023


DWG.#:  
5970939

DRAWN BY: Joe Shilba

SCALE:  
3/4" = 1'-0"

MASTER DRAWING

SHEET NO.  
2



1" LAYER OF INSULATION FACTORY INSTALLED IN 1.00" END STANDOFF MEETS 0" REQUIREMENTS CLEARANCE TO COMBUSTIBLE SURFACES.

INSTALLER MUST CONFIRM HOOD IS INSTALLED SUCH THAT THE SPECIFIED WALL, ACTING AS AN END PANEL, IS MATED TIGHT TO THE CORRECT END OF HOOD TO ACHIEVE A REDUCED MINIMUM EXHAUST CFM LISTING. NON-COMPLIANCE WILL NULLIFY THE ETL LISTING, VOID THE MANUFACTURER'S WARRANTY, AND HOLD THE CONTRACTOR LIABLE FOR ANY AND ALL LOSSES, COSTS, AND EXPENSES RELATED TO THE NON-COMFORMANCE OF THE MANUFACTURER'S SPECIFIED INSTRUCTION. THE WALL, ACTING AS AN END PANEL, MUST EXTEND NO LESS THAN 20" FROM THE INTERSECTING WALL ON WHICH HOOD IS MOUNTED AND MUST EXTEND NO LESS THAN 20" UNDER BOTTOM OF HOOD TO BE ELIGIBLE FOR REDUCED MINIMUM EXHAUST CFM LISTING.


LIGHTING FOR ACPSP JOB # 5970939 - HOODS #1, #2 INPUT: 120V AC, 1 PHASE, 50/60HZ, 3.5 WATTS PER LIGHT. TO CONTROL LIGHTS WITH HOOD LIGHT SWITCH, WIRE PER HOOD ELECTRICAL CONTROL PANEL SCHEMATIC. TO CONTROL LIGHTS WITH BUILDING LIGHT SWITCH, WIRE BLACK AND WHITE WIRE TO A 120VAC SERVICE. END TO END ACPSPS REQUIRE 120VAC FIELD WIRING FROM J-BOX TO J-BOX. REPLACE LIGHTS WITH LED LIGHTS ONLY.

PLAN VIEW - HOOD #1 (Hood-Left)  
7'-4.00" LONG 54.30ND-2-ACPSP-F


PLAN VIEW - HOOD #2 (Hood-Right)  
7'-4.00" LONG 54.30ND-2-ACPSP-F

ACPSP SHIPS LOOSE FOR FIELD INSTALLATION

ACPSP SHIPS LOOSE FOR FIELD INSTALLATION



SECTION VIEW - MODEL 5430ND-2-ACPSP-F  
HOOD - #1 (Hood-Left)



SECTION VIEW - MODEL 5430ND-2-ACPSP-F  
HOOD - #2 (Hood-Right)

**FIRE SYSTEM INFORMATION - JOB#5970939**

FIRE SYSTEM NO	TAG	TYPE	SIZE	FLOW POINTS	INSTALLATION	
					SYSTEM	LOCATION ON HOOD
1		TANK FS	4.0/4.0/4.0	46	FIRE CABINET RIGHT	RIGHT, HOOD 2

**GAS VALVE(S)**

FIRE SYSTEM NO	TAG	TYPE	SIZE	SUPPLIED BY
1		SC ELECTRICAL	2.000	CAPTIVEAIRE SYSTEMS

**NOTES**

- FIELD PIPE DROPS AS SHOWN
- PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
- FIELD INSTALLED DROP: FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
- SHIP LOOSE DROP: FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
- RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVING, SALAMANDERS, ETC.
- OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
- IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
- FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.

- APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.
- THIS FIRE SYSTEM COMPLIES WITH U.L. 300 REQUIREMENTS.

- DL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS



JOB #: 5970939  
 JOB NAME: SHAKE SHACK-1504-NASHVILLE TANGER, TN.

SYSTEM SIZE: TANK-SP-3 TOTAL FP REQUIRED: 46.  
 HOOD # 1 7' 4.00" LONG x 54" WIDE x 30" HIGH.  
 RISER # 1 SIZE: 10" x 12".  
 HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.  
 HOOD # 2 7' 4.00" LONG x 54" WIDE x 30" HIGH.  
 RISER # 1 SIZE: 10" x 12".  
 HOOD # 2 METAL BLOW-OFF CAPS INCLUDED.

- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

**LEGEND - FIRE CABINET TANK SYSTEM**

- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.



REVISIONS	
DESCRIPTION	DATE

**CAPTIVEAIRE**  
 Eastern, PA Mechanical  
 PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 504-4126 EMAIL: reg108@captiveaire.com

Shake Shack-1504-Nashville Tanger, TN  
 ANTIUCH, TN, 37013

DATE: 4/26/2023  
 DWG.#: 5970939  
 DRAWN BY: Joe.shilba  
 SCALE: 3/4" = 1'-0"  
 MASTER DRAWING  
  
 SHEET NO. 3



TN - 1504 - Nashville Tanger Outlets  
 4060 CANE RIDGE PKWY, BLDG. 7, SUITE 701  
 ANTIUCH, TN 37013

**Gensler**

LIC. NO. AA0002837 TEL 415.433.3700  
 45 FREMONT ST FAX 415.836.4599  
 SUITE 1500  
 SAN FRANCISCO, CA 94105  
 UNITED STATES  
  
 SATELLITE OFFICE: TEL 813.204.9000  
 400 N ASHLEY DRIVE FAX 813.223.6948  
 SUITE 0400  
 TAMPA, FL 33602  
 UNITED STATES



New York ■ Miami ■ Omaha ■ Los Angeles ■ Seattle ■ Honolulu  
 300-581-0963 www.schnackel.com

MEPP ENGINEER  
 3035 S 72ND ST  
 OMAHA NE 68124




FOODSERVICE CONSULTANT  
 505 COLLINS ST  
 PO BOX 3505  
 SOUTH ATTLEBORO  
 MA 02703  
 TEL 508.399.6000  
 FAX 508.761.3620



STRUCTURAL ENGINEER  
 13075 HEATHCOTE BLV  
 SUITE 170  
 GAINESVILLE  
 VA 20155  
 TEL 571.261.9280

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION

**Seal / Signature**






Project Name  
**TN - 1504 - Nashville Tanger Outlets**  
 Project Number  
**69.6677.000**  
 Description  
**CAPTIVEAIRE DRAWINGS**


Scale  
 AS NOTED

**M703**






TYPICAL DRAIN TRAP INSTALL RECOMMENDED COOLING COIL DRAIN TRAP CONFIGURATION.




- NOTES:
- 1) 1" DIAMETER PVC PIPE ONLY.
  - 2) USE ONLY LOW PROFILE COUPLINGS.
  - 3) ADD CLEAN OUT AS SHOWN.



- FAN #3 AP-D250-200-MPU - HEATER (MAU-1)
1. DIRECT GAS FIRED HEATED MAKE UP AIR UNIT WITH 20" MIXED FLOW DIRECT DRIVE FAN.
  2. INTAKE HOOD WITH EZ FILTERS.
  3. DOWN DISCHARGE - AIR FLOW RIGHT -> LEFT.
  4. PROFILE PLATE CONFIGURATION FOR SIZE 2 DIRECT FIRED UNIT FOR LOW CFM APPLICATIONS.
  5. GAS PRESSURE GAUGE, 0-35", 2.5" DIAMETER, 1/4" THREAD SIZE.
  6. GAS PRESSURE GAUGE, -5 TO +15 INCHES WC, 2.5" DIAMETER, 1/4" THREAD SIZE.
  7. BUTTERFLY MOD VALVE OPTION FOR MOD SIZE 2 (1" MOD VALVE).
  8. SHIP LOOSE GAS STRAINER. TO BE INSTALLED UPSTREAM OF UNIT CONNECTION 1 CONNECTION.
  9. MOTORIZED BACK DRAFT DAMPER 22.75" X 24" FOR SIZE 2 STANDARD & MODULAR HEATER UNITS W/EXTENDED SHAFT, STANDARD GALVANIZED CONSTRUCTION, 3/4" REAR FLANGE, LOW LEAKAGE, LF120S ACTUATOR INCLUDED.
  10. CLOGGED FILTER SWITCH WITH NOTIFICATION ON HMI.
  11. 5 TON, SINGLE CIRCUIT MODULAR PACKAGED AC COOLING OPTION FOR SIZE 2 DF/EH MODULAR PACKAGED UNIT. INCLUDES CONDENSER, DX COIL, FILTER/DRYER KIT, THERMAL EXPANSION VALVE, R410A REFRIGERANT, AND REFRIGERANT PIPING (1,000 TO 2,750 CFM) WHEN ORDERED WITH OPPOSITE AIRFLOW CONDENSERS ACCESS AND COIL PIPING WILL REMAIN IN STANDARD POSITION. DRAIN AND SLEDS WILL MOVE TO THE OPPOSITE SIDE. ANY OTHER CHANGE WILL REQUIRE CLI. CONDENSERS REQUIRE SEPARATE 460V, 3 PHASE POWER SUPPLY UNLESS ORDERED WITH SINGLE POINT CONNECTION. COIL = 3EY1102.
  12. DOWNTURN PLENUM FOR SIZE 2 COOLING COIL MODULE - REQUIRED FOR DOWN DISCHARGE COOLING COIL APPLICATIONS.
  13. FREEZE/STAT FACTORY SET AT 35°F AND 10 MINUTES.
  14. COMMERCIAL SMOKE DETECTOR INTERLOCK (DETECTOR BY OTHERS).
  15. MOUNT LOAD REACTOR IN FAN.
  16. UNIT MOUNTED VFD FOR USE WITH ECPM03.
  17. HINGED DOUBLE WALL INSULATED DOOR ASSEMBLY (BURNER/BLOWER/MPU SECTION).
  18. 2 YEAR PARTS WARRANTY.
- NOTE: SUPPLY DUCT MUST BE INSTALLED TO MEET SMACNA STANDARDS. A MINIMUM STRAIGHT DUCT LENGTH MUST BE MAINTAINED DOWNSTREAM OF UNIT DISCHARGE AS OUTLINED IN AMCA STANDARD 201. WHEN USING RECTANGULAR DUCTWORK, ELBOWS MUST BE RADIUS THROAT, RADIUS BACK WITH TURNING VANES. FLEXIBLE DUCTWORK AND SQUARE THROAT/SQUARE BACK ELBOWS SHOULD NOT BE USED. ANY TRANSITION AND/OR TURNS IN THE DUCTWORK WILL CAUSE SYSTEM EFFECT. SYSTEM EFFECT WILL DRASTICALLY INCREASE STATIC PRESSURE AND REDUCE AIRFLOW. DO NOT RELY ON UNIT TO SUPPORT DUCT IN ANY WAY. FAILURE TO PROPERLY SIZE DUCTWORK MAY CAUSE SYSTEM EFFECTS AND REDUCE PERFORMANCE OF THE EQUIPMENT. SUGGESTED STRAIGHT DUCT SIZE IS 20" X 20".

SUPPLY SIDE HEATER INFORMATION

WINTER TEMPERATURE = 18°F. TEMP. RISE = 60°F.  
 BTUS CALCULATED OFF ACTUAL AIR DENSITY.  
 OUTPUT BTUS AT ALTITUDE OF 0.0 FT. = 130800.  
 INPUT BTUS AT ALTITUDE OF 0.0 FT. = 142174.  
 OUTPUT BTUS AT ALTITUDE OF 380 FT. = 128082.  
 INPUT BTUS AT ALTITUDE OF 380 FT. = 139219.



Installation Wiring		JOB: 5970939 - Shake Shack-1504-Nashville Tn...
DRAWING NUMBER: 895970939-3		SHIP DATE: 4/26/2023
MODEL: AR-D250-200-MPU		

120 V 1 PH	240 V 1 PH	460V 3PH	INSTALLER ACTIONS
			<p>Field Wired Switch</p>

DO NOT CONNECT CONDENSER POWER DROPS TO KITCHEN CONTROL, PACKAGE STARTERS OR VFDs

See above details: Power Connection

FIELD WIRING CONNECTIONS ARE TO BE MADE BY THE INSTALLER WHEN USED WITH PRELIMINARY WIRING TO BE USED.

DAMPERS INTERLOCK TO BURNER AND BLOWER WIRING

NOTES:

WIRE COLOR

BL - BLACK	W - YELLOW
BR - BLUE	OR - GREEN
RD - RED	GY - GRAY
PK - PINK	PU - PURPLE
WH - WHITE	

REVISIONS	
DESCRIPTION	DATE

**CAPTIVE**  
 Eastern, PA Mechanical  
 PO Box 2620, 1 Union Ave, Bala Cynwyd, PA, 19004. PHONE: (267) 504-4126 EMAIL: reg108@captiveaire.com

Shake Shack-1504-Nashville Tanger, TN  
 ANTIUCH, TN, 37013

DATE: 4/26/2023

DWG.#: 5970939

DRAWN BY: Joe.shilba

SCALE: 3/4" = 1'-0"

MASTER DRAWING

SHEET NO. 5



TN - 1504 - Nashville Tanger Outlets  
 4060 CANE RIDGE PKWY, BLDG. 7, SUITE 701  
 ANTIUCH, TN 37013



LIC. NO. AA0002837 TEL 415.433.3700  
 SUITE 1500 FAX 415.836.4599  
 45 FREMONT ST  
 SAN FRANCISCO, CA 94105  
 UNITED STATES

SATELLITE OFFICE: TEL 813.204.9000  
 400 N ASHLEY DRIVE FAX 813.223.6948  
 SUITE 0400  
 TAMPA, FL 33602  
 UNITED STATES



New York Miami Omaha Los Angeles Seattle Honolulu  
 800-581-0963 www.schnackel.com

MEFP ENGINEER  
 3035 S 72ND ST  
 OMAHA NE 68124




FOODSERVICE CONSULTANT  
 505 COLLINS ST  
 PO BOX 3505  
 SOUTH ATTLEBORO  
 MA 02703  
 TEL 508.399.6000  
 FAX 508.761.3620



STRUCTURAL ENGINEER  
 13575 HEATHCOTE BLV  
 SUITE 170  
 GAINESVILLE  
 VA 20155  
 TEL 571.261.9280

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION

Seal / Signature



Project Name  
**TN - 1504 - Nashville Tanger Outlets**

Project Number  
**69.6677.000**


Description  
**CAPTIVEAIRE DRAWINGS**

Scale  
 AS NOTED

**M705**

**ELECTRICAL PACKAGE - JOB#5970939**

NO	TAG	PACKAGE #	LOCATION	SWITCHES		OPTION	FANS CONTROLLED					
				LOCATION	QUANTITY		FAN TAG	TYPE	HP	VOLT	FLA	
1		SC-321110MA	24"x18"x8.62" BDX	SS WALL MOUNT BDX	1 LIGHT 1 FAN	SMART CONTROLS THERMOSTATIC CONTROL W/ RELAY ON/OFF WITH SUPPLY	KEF-1	EXHAUST	3	0.750	460	1.3
							KEF-2	EXHAUST	3	0.750	460	1.3
							MAU-1	SUPPLY	3	2.000	460	3.8







**CASlink Monitor and Control**

- Hood control panel to support communications to cloud-based Building Management System.  
- Hood Control Panel to allow cloud-based Building Management System to monitor real time parameters outlined as MONITORS in the points list.  
- Hood Control Panel to allow cloud-based Building Management System to control parameters outlined as CONTROL in the points list.  
- Hood Control Panel to allow cloud-based Building Management System to implement SYSTEM ECONOMIZER control strategies for fully integrated Building Management.

**MONITORING AND CONTROL POINTS LIST**

DCV Package	Function	SC Package	Function
Room Temperature	MONITOR	Room Temperature(s)	MONITOR
Duct Temperature(s)	MONITOR	Duct Temperature(s)	MONITOR
MHA Discharge Temperature	MONITOR	MHA Discharge Temperature	MONITOR
Kitchen RTU Discharge Temperature	MONITOR	Kitchen RTU Discharge Temperature	MONITOR
Fan Speed	MONITOR	Control Panel	MONITOR
Fan Amperage	MONITOR	Fan Status	MONITOR
Fan Power	MONITOR	PCV Faults	MONITOR
VFD Faults	MONITOR	PCV Filter Clog Percentage	MONITOR
Control Panel	MONITOR	Fan Status	MONITOR
Fan Status	MONITOR	PCV Filter Clog Percentage	MONITOR
PCV Faults	MONITOR	Building Pressure	MONITOR & CONTROL
PCV Filter Clog Percentage	MONITOR	Light Status(s)	MONITOR & CONTROL
Fan Condition	MONITOR	Flush Button	MONITOR & CONTROL
CORE Fire System	MONITOR		
Building Pressure	MONITOR & CONTROL		
Prep Time Button	MONITOR & CONTROL		
Flame Button	MONITOR & CONTROL		
Flame Button	MONITOR & CONTROL		
Flush Button	MONITOR & CONTROL		



REVISIONS

NO	DESCRIPTION	DATE
1		
2		
3		
4		

**CAPTIVE**  
 Eastern, PA Mechanical  
 PO Box 2520, Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 504-4126 EMAIL: esg108@captivemechanical.com

Shake Shack-1504-Nashville Tanger, TN  
 ANTIUCH, TN, 37013

DATE: 4/26/2023  
 DWG #: 5970939  
 DRAWN BY: Joe.shilba  
 SCALE: 3/4" = 1'-0"  
 MASTER DRAWING  
 SHEET NO. 6



TN - 1504 - Nashville Tanger Outlets  
4060 CANE RIDGE PKWY, BLDG. 7, SUITE 701  
ANTIOCH, TN 37013



LIC. NO. AA0002837 TEL 415.433.3700  
45 FREMONT ST FAX 415.836.4599  
SUITE 1500  
SAN FRANCISCO, CA 94105  
UNITED STATES

SATELLITE OFFICE: TEL 813.204.9000  
400 N ASHLEY DRIVE  
SUITE 0400 FAX 813.223.6948  
TAMPA, FL 33602  
UNITED STATES



New York ■ Miami ■ Omaha ■ Los Angeles ■ Seattle ■ Honolulu  
800-581-0963 www.schnackel.com

MEFF ENGINEER  
3035 S 72ND ST  
OMAHA NE 68124




Foodservice Equipment, Supplies and Design

FOODSERVICE CONSULTANT  
505 COLLINS ST  
PO BOX 3505  
SOUTH ATLBORO  
MA 02703  
TEL 508.399.6000  
FAX 508.761.3620



STRUCTURAL ENGINEER  
13575 HEATHCOTE BLV  
SUITE 170  
GAINESVILLE  
VA 20155  
TEL 571.261.9280




Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION



Project Name  
**TN - 1504 - Nashville Tanger Outlets**  
 Project Number  
**69.6677.000**  
 Description  
**CAPTIVEAIRE DRAWINGS**

Scale  
AS NOTED

**M706**



REVISIONS	
DESCRIPTION	DATE

CAPTIVE

Eastern, PA Mechanical  
 PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 504-4126 EMAIL: east108@captiveaire.com

Shake Shack-1504-Nashville, TN  
 ANTIUCH, TN, 37013

DATE: 4/26/2023  
 DWG #: 5970939  
 DRAWN BY: Joe.shilba  
 SCALE: 3/4" = 1'-0"  
 MASTER DRAWING

SHEET NO. 7



TN - 1504 - Nashville Tanger Outlets  
 4060 CANE RIDGE PKWY, BLDG. 7, SUITE 701  
 ANTIUCH, TN 37013



LIC. NO. AA0002837 TEL 415.433.3700  
 45 FREMONT ST FAX 415.836.4599  
 SUITE 1500  
 SAN FRANCISCO, CA 94105  
 UNITED STATES

SATELLITE OFFICE: TEL 813.204.9000  
 400 N ASHLEY DRIVE FAX 813.223.6948  
 SUITE 2400  
 TAMPA, FL 33602  
 UNITED STATES



New York Miami Omaha Los Angeles Seattle Honolulu  
 800-581-0963 www.schnackel.com

MEPF ENGINEER  
 3035 S 72ND ST  
 OMAHA NE 68124




Foodservice Equipment, Supplies and Design

FOODSERVICE CONSULTANT  
 505 COLLINS ST  
 PO BOX 3505  
 SOUTH ATRI LEBORO  
 MA 02703  
 TEL 508.399.6000  
 FAX 508.761.3620



STRUCTURAL ENGINEER  
 13575 HEATHCOTE BLV  
 SUITE 170  
 GAINESVILLE  
 VA 20155  
 TEL 571.261.9280

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION






Project Name  
 TN - 1504 - Nashville Tanger Outlets

Project Number  
 69.6677.000

Description  
 CAPTIVEAIRE DRAWINGS

Scale  
 AS NOTED

M707




One Gallon Grease Cup Installation

Instructions below outline single, or dual, one gallon grease cup installation for ND-2 hood models.

The one gallon grease cup comes as an assembly of stainless steel wall mounting bracket and one gallon cup. The mounting bracket should be installed 2" from the edge of the containment plenum and 3"-4" below the bottom of the hood.

Piping from the hood grease drain should route to the opening of the grease cup, but not into the cup, otherwise the cup will not be able to be removed and emptied.



REVISIONS	
DESCRIPTION	DATE

**CAPTIVE**


Eastern, PA Mechanical  
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: rep108@captivairc.com

Shake Shack-1504-Nashville Tanger, TN  
ANTIOCH, TN, 37013

DATE: 4/26/2023  
DWG.#: 5970939  
DRAWN BY: Joe.shilba  
SCALE: 3/4" = 1'-0"  
MASTER DRAWING

SHEET NO. 8

Date	Description
06/19/2023	CONSTRUCTION DOCUMENTS
07/21/2023	ADDENDUM 1
08/21/2023	ISSUE FOR CONSTRUCTION



Project Name  
TN - 1504 - Nashville Tanger Outlets  
Project Number  
69.6677.000  
Description  
CAPTIVEAIRE DRAWINGS

Scale  
AS NOTED

**M708**