

SEE PLUMBING PLANS 4 M-3.0 FOR ANSI GAS VALVE NOTES.

OPENING 4 INSTALLATION BY MECHANICAL CONTRACTOR. COORDINATE RECEIVING WITH G.C. SEE KITCHEN PLANS FOR HOOD INFO.

PROVIDE MINIMUM WORK CLEARANCE AS REQ'D BY THE FORT WORTH AMENDMENTS TO THE MECHANICAL CODE TO ALL SYSTEM PARTS THAT MAY REQUIRE MAINTENANCE OR DUCTMARK INSPECTIONS.
ALL VOLUME DAMPERS TO BE FLAGGED WITH A BRIGHT COLORED RIBBON OR TAPE. VERIFY WITH INSPECTOR IN FIELD.

CAPTIVE AIRE GREASE DUCT UP THRU ROOF EE-2. SEE CAPTIVE AIRE PLANS FOR SIZES (TYP EF 1-5).

DINING ROOM SUPPLY DUCTWORK FOR RTU-4 & 5 IS PROVIDED BY CAPTIVE AIRE PURCHASED DIRECT BY OWNER AND INSTALLED BY MECHANICAL CONTRACTOR. SEE CAPTIVE AIRE DRAWINGS FOR DUCT SIZES. RETURN DUCT IS FURNISHED & INSTALLED BY MECHANICAL CONTRACTOR.

DINING ROOM SUE-C DUCTWORK FOR RTU-4 & 5 IS PROVIDED BY CAPTIVE AIRE PURCHASED DIRECT BY OWNER AND INSTALLED BY MECHANICAL CONTRACTOR. SIZES SHOWN FOR COORDINATION. SEE CAPTIVE AIRE DRAWINGS FOR DUCT SIZES. RETURN DUCT IS FURNISHED & INSTALLED BY MECHANICAL CONTRACTOR.

TRANSITION TO BUILT-UP FAN COIL UNIT THRU ROOF.

COORDINATE HEIGHT OF AC UNIT WITH I.T. SHELVING.

5 KN 8'-0" A.F.F. WALL BRACKET UNIT MOUNTED STAT & DISCONNECT

NORTH
HVAC PLAN
SCALE: 1/4" = 1'-0"

