

SPECIFICATION SECTION 230593 TESTING, ADJUSTING, AND BALANCE REQUIRES AN INDEPENDENT TAB CONTRACTOR (NEBB OR AABC) TO TEST ALL EQUIPMENT TO ENSURE COMPLIANCE WITH DRAWINGS. OWNER'S REPRESENTATIVE SHALL RECEIVE REPORT / VERIFICATION.

**GENERAL NOTES:**

- DUCT SYSTEMS SERVING REMOVAL OF GREASE LADEN AIR (TYPE 1 HOOD) SHALL BE CONSTRUCTED AND INSTALLED SO THAT GREASE WILL NOT ACCUMULATE IN DUCTWORK. DUCTWORK SHALL SLOPE AT 2% TOWARD HOOD OR GREASE RESERVOIR. PROVIDE DUCT CLEAN OUTS AT ALL CHANGES OF DIRECTION WITH GREASE TIGHT ACCESS DOORS.
- DUCTWORK SERVING KITCHEN AND WORK ROOM AREAS SHALL NOT BE LINED. DUCTWORK SERVING THESE AREAS SHALL UTILIZE EXTERNAL DUCT WRAP INSULATION.
- MAINTAIN MINIMUM 10'-0" CLEARANCE BETWEEN OUTDOOR AIR INTAKES AND EXHAUST FANVENT TERMINATIONS.
- KITCHEN HOODS ARE PROVIDED BY KITCHEN EQUIPMENT SUPPLIER AND INSTALLED BY MECHANICAL CONTRACTOR.
- REFER TO HOOD MANUFACTURER SHOP DRAWINGS FOR HOOD SUPPORT INFORMATION.
- CEILING SPACE IS LIMITED. COORDINATE WORK WITH OTHER TRADES.
- EXPOSED DUCTWORK SHALL BE CLEAN AND FREE OF DEFECTS.
- EXPOSED DUCTWORK SHALL BE CONSTRUCTED OF PAINT LOCK SHEETMETAL AND PAINTED AS DIRECTED BY ARCHITECT.

**PLAN NOTES:**

- MOUNTING LOCATION FOR DUCT MOUNTED SMOKE DETECTOR.
- LOCATION OF MANUAL PULL STATION. INSTALL PER MANUFACTURER INSTRUCTIONS.
- LOCATION OF RTU THERMOSTATS. LABEL THERMOSTATS WITH RTU NUMBER. LABELS BY M.C.
- LOCATION OF RTU TEMPERATURE SENSORS MOUNTED 7'-0" AFF.
- COORDINATE DUCT BETWEEN STRUCTURAL TRUSSES WITH SIZES SHOWN.
- EXHAUST HOOD PROVIDED BY OTHERS. INSTALLED BY MECHANICAL CONTRACTOR. INSTALL PER MANUFACTURER'S INSTRUCTIONS.
- TRANSITION AND CONNECT 10" GREASE DUCT TO EXHAUST FAN AS SHOWN. ROUTE DUCT UP AND CONNECT TO EXHAUST FAN. OFFSET AS REQUIRED TO AVOID ROOF STRUCTURE AND TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTSIDE AIR INTAKES AND 5'-0" FROM PARAPET WALLS. REFER TO DETAIL ON SHEET M-2. ALL GREASE DUCT SHALL BE INSTALLED WITH DUCT WRAP AND ACCESS DOORS AS DETAILED AND PER MANUFACTURER INSTRUCTIONS. SEE CAPTIVE AIR DRAWING.
- TRANSITION AND CONNECT 14" GREASE DUCT TO EXHAUST FAN AS SHOWN. ROUTE DUCT UP AND CONNECT TO EXHAUST FAN. OFFSET AS REQUIRED TO AVOID ROOF STRUCTURE AND TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTSIDE AIR INTAKES AND 5'-0" FROM PARAPET WALLS. REFER TO DETAIL ON SHEET M-2. ALL GREASE DUCT SHALL BE INSTALLED WITH DUCT WRAP AND ACCESS DOORS AS DETAILED AND PER MANUFACTURER INSTRUCTIONS. SEE CAPTIVE AIR DRAWING.
- COMBUSTION AIR AND VENT PIPING THROUGH ROOF. HOLD AS HIGH AS POSSIBLE AND PROVIDE TERMINATION PER MANUFACTURER'S RECOMMENDATIONS. EXTEND TO WATER HEATER. COORDINATE REQUIREMENTS WITH WATER HEATER. MAINTAIN 10'-0" CLEARANCE FROM ALL OUTSIDE AIR INTAKES.
- COORDINATE DUCT ROUTING WITH ELECTRICAL GEAR. DO NOT ROUTE DUCTWORK ABOVE ELECTRICAL GEAR.
- RETURN AIR DUCT LOCATED BETWEEN ROOF TRUSSES. OPEN DUCTWORK UP TOWARD STRUCTURE. COVER OPENING WITH 3/4" EXPANDED WITH MESH.
- SUPPORT EXHAUST FAN FROM STRUCTURE AS REQUIRED BY THE MANUFACTURER.
- ROUTE DUCT AS HIGH AS POSSIBLE OVER OFFICE AREA TO ALLOW FOR ROUTING OF CABLES.
- MOUNT CONDENSING UNIT ON ROOF AS DETAILED AND AS REQUIRED BY THE MANUFACTURER. CONNECT REFRIGERANT PIPING PER MANUFACTURER RECOMMENDATIONS. SEE SHEET M2 FOR MOUNTING DETAIL.
- ROUTE RETURN AIR DUCT THROUGH OR BETWEEN ROOF TRUSSES.
- ROUTE 10" EXHAUST DUCT UP THROUGH ROOF TO ROOF CAP. VERIFY 10' CLEARANCE FROM ALL OUTSIDE AIR INTAKES.
- HOOD SHALL BE PROVIDED WITH FACTORY PRE-WIRE PACKAGE AND A PRE-ENGINEERED UL-300 FIRE SUPPRESSION SYSTEM. SYSTEM SHALL BE PROPERLY SIZED FOR THE HOOD, DUCT PLENUM AND ALL EQUIPMENT BELOW (VERIFY EXACT REQUIREMENTS WITH KITCHEN EQUIPMENT SUPPLIER). HOOD EXHAUST, MAKE-UP AND LIGHTS SHALL BE SWITCHED FROM CONTROL PANEL THAT IS INTEGRAL TO FRONT OF UTILITY CABINET. UTILITY CABINET SHALL SERVE ALL HOODS.
- PROVIDE LOCKING QUADRANT DAMPER AND SQUARE TO ROUND TRANSITION FOR DUCT CONNECTION TO RETURN GRILLE.
- COORDINATE DUCT DROP BETWEEN STRUCTURAL TRUSSES WITH SIZES SHOWN. TRANSITION RETURN AIR DUCT TO FIT BETWEEN STRUCTURE.
- PROVIDE CAPTIVE AIRE VBE WINDBAND EXTENSION FOR KEF-1 AND KEF-2.
- EXPOSED DUCTWORK SHALL BE DUAL WALL, PAINTLOCK CONSTRUCTION AND PAINTED AS PER DIRECTION OF ARCHITECT (TYP.).
- COORDINATE EXPOSED DUCTWORK WITH LIGHTS (TYP.).



**A MECHANICAL PLAN**  
SCALE: 1/4" = 1'-0"  
**NORTH**

**MECHANICAL LEGEND**

HVAC:		HVAC:		HVAC:		MISC. SYMBOLS:	
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	SUPPLY AIR DIFFUSER		ELBOW ROUND DUCT		ECCENTRIC TRANSITION		EQUIPMENT IDENTIFICATION
	RETURN AIR GRILLE WITH SOUND BOOT		ROUND DUCT DROP / DOWN		DUCT OFFSET - RISE OR DROP		PLAN NOTE
	RETURN AIR GRILLE		ROUND DUCT RISE / UP		FLEX DUCT (5'-0" MAX. LENGTH)		ABOVE FINISHED FLOOR
	SIDE WALL REGISTER / GRILLE		FLEXIBLE CONNECTION		OPPOSED BLADE DAMPER	SA	SUPPLY AIR
	SUPPLY AIR DUCT RISE / UP		DUCT SIZE / DIMENSIONS FIRST SIZE TOP DIMENSION		PARALLEL BLADE DAMPER	RA	RETURN AIR
	SUPPLY DUCT DROP / DOWN		45° HIGH EFFICIENCY TAKE-OFF		THERMOSTAT / SENSOR	EA	EXHAUST AIR
	RETURN OR EXHAUST DUCT RISE / UP		45° HIGH EFFICIENCY TAKE-OFF WITH LOCKING QUAD. DAMPER		HUMIDISTAT / SENSOR	OSA	OUTSIDE AIR
	RETURN OR EXHAUST DUCT DROP / DOWN		CONCENTRIC TRANSITION		FIRE SMOKE DAMPER	RAG	RETURN AIR GRILLE
	ELBOW WITH TURNING VANES		RECT. TO ROUND TRANSITION		FIRE DAMPER		


**OUTDOOR AIR CALCULATION**

UNIT	AREA (SQFT)	OCCUPANCY CLASSIFICATION	OCCUPANT DENSITY # PEOPLE	PEOPLE OUTDOOR AIRFLOW RATE IN BREATHING ZONE, (RP) CFM/PERSON	AREA OUTDOOR AIRFLOW RATE IN BREATHING ZONE, (RA) CFM/SQFT	EXHAUST AIRFLOW RATE CFM/SQFT	BREATHING ZONE OUTDOOR AIRFLOW (VBZ)	ZONE AIR DISTRIBUTION EFFECTIVENESS (EZ)	ZONE OUTDOOR AIRFLOW (CFM)
RTU-1	1595	DINING RM	80	7.5	0.18		...	0.8	888
	120	RESTROOM	0	0	0.06		...	0.8	8
									896
RTU-2	975	KITCHEN	20	7.5	0.12	0.7	...	0.8	267
	45	OFFICE	1	5	0.06		...	0.8	8
									1171



NOTE: PROVIDE SHORT RADIUS ELBOWS (1 TIMES CENTERLINE 90° ELL) FOR ELBOW DOWN TO DIFFUSER ON EXPOSED DUAL WALL DUCTWORK IN DINING ROOM. DIFFUSER SHALL BE MINIMUM OF 9'-0" A.F.F. SEE DETAIL.

NOTE: REMOTE SENSORS WIRE TO THERMOSTAT. HUMIDITY SENSORS WIRE UP TO THE PRODIGY CONTROL PANEL. REFER TO HUMIDITY SENSOR INSTALLATION INSTRUCTIONS. HUMIDITY LEVEL IS CONTROL ON THE PRODIGY PANEL. SET HUMIDITY LEVEL AT 50-55%. CONTACT NA TECH SUPPORT GROUP AT 1-800-367-6285 FOR QUESTIONS.



THE DESIGN AND DETAILS DISCLOSED HEREIN ARE THE EXCLUSIVE PROPERTY OF RODGER W. BAKER, AIA AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT HIS PRIOR WRITTEN CONSENT.  
RODGER W. BAKER, AIA

**MECHANICAL PLAN**


DATE  
**7/8/2022**

DRAWN BY:


CHECKED BY:

SHEET NO.


**M1**



**1** ROUND DUCT TAKE-OFF  
NO SCALE



**2** RECTANGULAR DUCT TAKE-OFF  
NO SCALE



**3** DOWNFLOW ROOF TOP UNIT DETAIL  
NO SCALE

ROOFTOP UNIT SCHEDULE																				
MARK	MFR	MODEL NO.	NOM. TONS	EVAP. CFM	EXT. STATIC P. IN. WG. (NOTE 2)	COOLING			HEATING (GAS)			ELECTRICAL			MINIMUM OUTDOOR AIR (CFM)	TOTAL WEIGHT (LBS)	EER	REFRIG.	NOTES	
						TOTAL MBH	SENS. MBH	AMB.	EVAP. EAT DB/WB	MBH INPUT	MBH OUTPUT	VOLTI/0HZ	BLOWER MOTOR	MIN. MCA (AMPS)						MIN. MOCF (AMPS)
RTU-1	CARRIER	48FCEN14	12.5	4,850	1.0	140.9	103.8	100	80/67	224	181	208/3/60	5 HP	68	80	1000	1400	10.2	R-410a	1,2,3,4,5,6
RTU-2	CARRIER	48FCEN08	7.5	3,000	1.0	86.6	63.9	100	80/67	180	146	208/3/60	3 HP	39	50	300	1150	11.2	R-410a	1,2,3,4,5,6

- NOTES:**
- PROVIDE LOW LEAK OUTDOOR AIR ECONOMIZER WITH DRY BULB CONTROL, FAULT DETECTION AND DIAGNOSTIC MODULE. PROVIDE UNIT WITH HOT GAS REHEAT WITH 75° L.A.T., TIME DELAY ON COMPRESSOR RE-START, CRANKCASE HEATER, BAROMETRIC RELIEF DAMPER, CONDENSATE DRAIN PAN-FLOAT SWITCH, AND COMPRESSOR LOCK-OUT WITH AMBIENT BELOW 55° F FOR EACH UNIT. OUTDOOR AIR DAMPER TO FULLY CLOSE W/ FAN SHUTDOWN FOR ALL UNITS. PROVIDE UNIT WITH 2-SPEED FAN CONTROL.
  - EXTERNAL STATIC PRESSURE LISTED REPRESENTS STATIC PRESSURE REQUIRED FOR DUCTWORK AND DIFFUSERS OUTSIDE THE HVAC UNIT COMPLETELY INDEPENDENT OF ANY PRESSURE DROP THROUGH THE HVAC EQUIPMENT INCLUDING BUT NOT LIMITED TO FILTERS, COILS AND ECONOMIZERS. THE FAN AND MOTOR SHALL BE SIZED APPROPRIATELY TO MEET THIS DEFINITION OF EXTERNAL STATIC PRESSURE.
  - PROVIDE COMMERCIAL 7-DAY PROGRAMMABLE HEAT/COOL/AUTO CHANGE-OVER THERMOSTAT WITH REMOTE TEMPERATURE AND HUMIDITY SENSORS AND ECONOMIZER OUTPUT FOR EACH UNIT. ECONOMIZER/OUTDOOR AIR DAMPER IS TO CLOSE DURING UNOCCUPIED HOURS. THERMOSTAT SHALL BE HONEYWELL VISIONPRO (OR EQUAL) WITH HUMIDITY CONTROL.
  - PROVIDE 18" HIGH (AT LOWEST POINT) PRE-FABRICATED INSULATED ROOF CURB WITH SLOPE TO MATCH SLOPE OF ROOF FOR EACH UNIT.
  - PROVIDE HAIL GUARDS FOR EACH UNIT.
  - DISCONNECT AND RETURN AIR SMOKE DETECTOR TO BE FACTORY INSTALLED. MECHANICAL CONTRACTOR TO COORDINATE UNIT MOCF WITH ELECTRICAL CONTRACTOR.

**NOTE:**  
RTUs, MAU, KITCHEN EXHAUST HOODS & FANS, AND COOLER / FREEZER SPLIT SYSTEMS HAVE BEEN PRE-PURCHASED BY THE OWNER. EQUIPMENT SHALL BE DELIVERED TO THE SITE ON-TIME FOR MECHANICAL CONTRACTOR INSTALLATION OR STORED ON SITE BY THE CONTRACTOR.

ALL WARRANTIES SHALL BE TRANSFERRED TO THE CONSTRUCTION TEAM AT TIME OF AWARDSING CONTRACTORS. EQUIPMENT WARRANTY ISSUES SHALL BE THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR.

DIFFUSER SCHEDULE						
MARK	MFR	MODEL	NECK SIZE	FACE SIZE	FINISH	REMARKS
SD-1	TITUS	TMR	12"Ø	22"Ø	WHITE	WITH OPPOSED BLADE DAMPER, FIELD PREP FOR PAINTING
SD-2	TITUS	TMS3	10"Ø	24"x24"	WHITE	
SD-3	TITUS	PAS3	10"Ø	24"x24"	WHITE	
SD-4	TITUS	T3SD4	8"Ø	24"x24"	WHITE	THERMAL VAV DIFFUSER
SD-5	TITUS	TMS3	6"Ø	12"x12"	WHITE	WITH OPPOSED BLADE DAMPER AND TRM KIT
SD-6	TITUS	TMS3	8"Ø	24"x24"	WHITE	WITH OPPOSED BLADE DAMPER AND TRM KIT
SD-7	TITUS	TMS3	8"Ø	12"x12"	WHITE	WITH OPPOSED BLADE DAMPER AND TRM KIT
RG-1	AMER. LOUVER CO.	STRATUS	20"x20"	24"x24"	WHITE	SEE NOTE 1.
RG-2	TITUS	350RL	8"x8"	-	WHITE	
RG-3	TITUS	50F	10x22	24X12	WHITE	

- NOTES:**
- RETURN GRILL TO BE PLASTIC FILTER RETURN. FILTER TO BE AMERICAN AIR FILTER (AAF) FRONTLINE GREEN 1", WITH AAF AMERIFRAME SIZE 20x20x1.

EXHAUST FAN SCHEDULE									
MARK	MFR	MODEL	CFM	EXTERNAL STATIC P. IN. WG.	RPM	ELECTRICAL		FAN TYPE	REMARKS
						VOLTI/0HZ	PWR		
EF-1	COOK	GC-146	75	0.25	900	120/160	30.3W	CEILING EXH.	
EF-2	COOK	GC-168	150	0.25	1099	120/160	50.4W	CEILING EXH.	


- NOTES:**
- PROVIDE CEILING GRILLE, INTEGRAL BACK DRAFT DAMPER, DISCONNECT SWITCH, AND VARIABLE SPEED CONTROLLER.
  - FANS SHALL NOT EXCEED SCHEDULED RPM.

PUMP SCHEDULE											
MARK	SERVICE	GPM	HEAD	EFFICIENCY	MOTOR			PIPE INCHES	FLOW	STARTER BY	REMARKS
					HP	RPM	ELECTRICAL				
RCP-1	DOMESTIC HW	10	6	-	3/4	3250	115/601	-	CONST	-	1


- REMARKS:**
- SELECTION BASED ON BELL & GOSSETT INLINE PUMP MODEL PL-30. ALL BRONZE CONSTRUCTION.

BUILDING AIR BALANCE SCHEDULE						
MARK	SPACE OR AREA	EXHAUST AIR CFM	OUTSIDE AIR CFM	RETURN AIR CFM	SUPPLY AIR CFM	REMARKS
RTU-1	DINING	--	1000	3850	4850	--
RTU-2	DINING	--	300	2700	3000	--
MAU-1	KITCHEN	--	1980	0	1980	--
KEF-1	RANGE - KITCHEN HOOD	1600	--	--	--	--
KEF-2	FRYERS - KITCHEN HOOD	775	--	--	--	--
KEF-4	DISHWASHER - KITCHEN HOOD	525	--	--	--	--
EF-1	WOMEN'S RESTROOM	75	--	--	--	--
EF-2	MEN'S RESTROOM	150	--	--	--	--
TOTALS	BUILDING TOTALS	3,125	3,280	6,550	9,830	NOTE: AREA IS 155 CFM POSITIVE


- NOTES:**
- THERMAL CERAMICS FIREMASTER FASTWRAP XL OR PYROSCAT XL HAS BEEN TESTED IN ACCORDANCE WITH ASTM E2306 TO PROVIDE ZERO CLEARANCE TO COMBUSTIBLES AND MEETS THE REQUIREMENTS FOR ONE OR TWO HOUR ENCLOSURES. THROUGH PENETRATIONS FIRESTOP SYSTEMS ARE TESTED IN ACCORDANCE WITH EITHER ASTM E 814 OR UL 1479. ICC-ES APPROVAL PER REPORT ESR 2213 OR ESR 2832. UNDERWRITERS LABORATORIES (UL) LISTINGS SHOW COMPLIANCE TO UL 1479 FOR THROUGH PENETRATION FIRESTOP SYSTEMS.
  - COMPLIANT TO THE FOLLOWING CODES: NFPA 96 2003 AND 2006 INTERNATIONAL MECHANICAL CODES 2006 UNIFORM MECHANICAL CODE.
  - INSULATION APPLIED IN TWO LAYERS WITH TIGHT COMPRESSION JOINT ON INSIDE LAYER AND 3 INCH MINIMUM OVERLAPS ON BOTH PERIMETER AND LONGITUDINAL OVERLAPS ON OUTSIDE LAYER.
  - GREASE EXHAUST DUCT RUNS FROM THE HOOD EXHAUST CONNECTION UP TO THE EXHAUST FAN ON THE ROOF WITH MINIMAL TURNS OR BENDS AND MAINTAINING MINIMUM 1/4 UNIT VERTICAL RISE PER 12 UNITS HORIZONTAL RUN. NFPA 96 COMPLIANT ACCESS DOORS LOCATED AS REQUIRED BY CODE.
  - THERMAL CERAMICS FIREMASTER ACCESS DOORS AS SPECIFIED IN ICC-ES BUILDING CODE REPORTS ESR 2213 OR ESR 2832.
  - ROOF MOUNTED EXHAUST FAN IS MOUNTED ON A HINGED BASE WHICH ALLOWS ACCESS TO THE DUCT FROM THE ROOF.
  - SUPPORT HANGER SYSTEMS DO NOT NEED TO BE WRAPPED PROVIDED THE HANGER RODS ARE AT LEAST A MINIMUM OF 3/8 IN. DIAMETER. USE MINIMUM 2 X 2 X 1/8 IN. STEEL ANGLE OR SMACNA EQUIVALENT SUPPORT SYSTEM.
  - THERMAL CERAMICS DUCT ENCLOSURE SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS.
  - THERMAL CERAMICS DUCT WRAP SHALL BE INSTALLED ON THE DUCT FROM THE HOOD CONNECTION TO THE CONNECTION TO THE FAN.



**6** COMMERCIAL KITCHEN GREASE DUCT SYSTEM  
NO SCALE



**7** GREASE HOOD DETAIL  
NO SCALE



THE DESIGN AND DETAILS DISCLOSED HEREIN ARE THE EXCLUSIVE PROPERTY OF RODGER W. BAKER, AIA AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT HIS PRIOR WRITTEN CONSENT.

RODGER W. BAKER, AIA

**MECHANICAL DETAILS**


DATE  
**7/8/2022**

DRAWN BY:

CHECKED BY:

SHEET NO.  
**M2**

**ND-2 HANGING ANGLE DETAIL**



ROD AND NUTS TO BE SUPPLIED BY INSTALLING CONTRACTOR. HANGING ANGLE IS PRE-FINISHED AT FACTORY.

**HANGING ANGLE LOCATIONS**


HOOD STYLE	DIM FROM REAR	DIM FROM FRONT (24\"/>	
CANOPY ND2	4.166"	2.246"	2.246"
ND2-PSP-F	4.166"	2.246"	2.246"
BACKSHELF BD-2	4.166"	2.246"	-
VHB/VHB-G	36"x36"	42"x42"	48"x48"
FRONT/BACK DIMS BY SIZE	2.246"	2.246"	2.246"

**CALCULATIONS UTILIZED**

EXHAUST CFM=LENGTH OF HOOD X CFM/LIN.FT. (LOAD)  
 SUPPLY CFM=EXHAUST CFM X PERCENTAGE REQUIRED  
 TOTAL DUCT AREA=144 X  
 DUCT LENGTH= DUCT DEPTH  
 CAPTIVE-AIRE DUCT CONNECTION SIZES ARE CALCULATED USING AN EXHAUST VELOCITY OF 1500-1800 FPM AND A SUPPLY VELOCITY OF 300-400 FPM.

**BUILDING CODES**

CAPTIVE-AIRE HOODS ARE BUILT IN COMPLIANCE WITH:



Listed under ETL File number 3054804-001/002

**CLEARANCE TO COMBUSTIBLES**

CAPTIVE-AIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:

MATERIAL	CLEARANCE REDUCTION SYSTEM
NON-COMBUSTIBLE	NONE REQUIRED
LIMITED-COMBUSTIBLE	3" UNSHIELDED STANDOFF
COMBUSTIBLE	1" INSULATED STANDOFF

**GENERAL NOTES**

**INSTALLATION**

- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
- ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
- HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
- ALL CONNECTIONS FROM CAPTIVE-AIRE DUCT PER MECHANICAL CONTRACTOR'S PLANS.
- COOKING EQUIPMENT TO SHUT-OFF IN EVENT OF FIRE.
- EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
- ALL LIGHTS/FIXTURES SHOWN INSTALLED BY CAPTIVE-AIRE ARE FACTORY PREWIRED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES BY ELECTRICAL CONTRACTORS.
- LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
- SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
- INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTEGRATION AND ADMINISTRATION OF CODE REQUIREMENTS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.


**BALANCE**

- KITCHEN HOODS MUST BE BALANCED WITH KITCHEN.
- KITCHEN SHALL BE NEGATIVE WITH RESPECT TO DRIVING AREA.
- RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.

**ADDITIONAL**

- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
- SIGNED AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE RECEIVED BY THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

**FILTER DETAIL**



CaptiveAire Captrate Solo Filter  
 ETL Listed Grease Extracting Filters  
 Made From 430 Stainless Steel

**HOOD INFORMATION - JOB#5516907**

HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST RISE (RISERS)	MUA CFM	AC CFM	HOOD CONSTRUCTION	HOOD COOKING END	HOOD COOKING ROW
1	GRIDDLE HD	5424 ND-2-ACSPSP-F	CAPTIVEAIRE	8' 0"	450 DEG	I	MEDIUM	200	1605	4" 14" 1600 1487 -0.734"	1280	505	430 SS WHERE EXPOSED	ALONE	FRONT
2	FRY HD	5424 ND-2-ACSPSP-F	CAPTIVEAIRE	5' 0"	450 DEG	I	MEDIUM	175	875	4" 10" 875 1604 -0.590"	700	276	430 SS WHERE EXPOSED	ALONE	ALONE
3	DISH HD	4224 VHB-G	CAPTIVEAIRE	3' 0"	700 DEG	II	N/A	150	525	4" 10" 525 963 -0.060"	0	0	304 SS 100%	ALONE	ALONE

**HOOD INFORMATION**

HOOD NO	TAG	TYPE	QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	LIGHT(S)			UTILITY CABINET(S)			FIRE DUTY SYSTEM	HOOD WEIGHT	
								TYPE	GUARD	LOCATION	SIZE	TYPE	SIZE			MODEL #
1	GRIDDLE HD	CAPTIVATE SOLO FILTER	5	16"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO	LEFT	12"x54"x24"	1 LIGHT	DCV-2111	1 FAN	NO	660 LBS
2	FRY HD	CAPTIVATE SOLO FILTER	3	16"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	NO						NO	421 LBS
3	DISH HD						0								NO	161 LBS

**HOOD OPTIONS**

HOOD NO	TAG	OPTION
1	GRIDDLE HD	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT LEFT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS RIGHT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS
2	FRY HD	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT RIGHT END PANEL 24" TOP WIDTH, 54" BOTTOM WIDTH, 45" HIGH 430 SS LEFT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS RISER SENSOR INSTALL 6IN PLEN.
3	DISH HD	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT.


**PERFORATED SUPPLY PLENUM(S)**

HOOD NO	TAG	POS	LENGTH	WIDTH	HEIGHT	TYPE	RISERS		
							WIDTH	LENG	DIA
1	GRIDDLE HD	Front	108"	24"	6"	MUA	12"	256	0.084"
						MUA	12"	256	0.084"
						MUA	12"	256	0.084"
						MUA	12"	256	0.084"
						AC	8"	101	0.033"
						AC	8"	101	0.033"
2	FRY HD	Front	60"	24"	6"	MUA	12"	233	0.070"
						MUA	12"	233	0.070"
						AC	8"	92	0.028"
						AC	8"	92	0.028"
						AC	8"	92	0.028"
						AC	8"	92	0.028"


**SPECIFICATION: CAPTRATE GREASE-STOP SOLO FILTER**

THE CAPTRATE GREASE-STOP SOLO FILTER IS A SINGLE-STAGE FILTER FEATURING A UNIQUE 5-BATTLE DESIGN IN CONJUNCTION WITH A SLOTTED REAR Baffle DESIGN TO DELIVER EXCEPTIONAL FILTRATION EFFICIENCY. FILTER IS STAINLESS STEEL CONSTRUCTION, AND SIZED TO FIT INTO STANDARD 2-INCH DEEP HOOD CHANNEL(S). UNITS SHALL INCLUDE STAINLESS STEEL HANDLES AND A FASTENING DEVICE TO SECURE THE TWO COMPONENTS WHEN ASSEMBLED.

GREASE EXTRACTION EFFICIENCY PERFORMANCE SHALL REMOVE AT LEAST 75% OF GREASE PARTICLES FIVE MICRONS IN SIZE, AND 85% GREASE PARTICLES SEVEN MICRONS IN SIZE AND LARGER, WITH A CORRESPONDING PRESSURE DROP NOT TO EXCEED 1.0 INCHES OF WATER GAUGE. THE CAPTRATE GREASE-STOP SOLO WAS TESTED TO ASTM STANDARD ASTM F2191-05. MANUFACTURER APPROVED FOR USE IN SOLID FUEL APPLICATIONS AS A SPARK ARRESTER. EFFICIENCY VS. PARTICLE DIAMETER. PRESSURE DROP VS. FLOW RATE.




CAPTIVATE FILTERS ARE BUILT IN COMPLIANCE WITH: NSF, UL, and ETL certifications.




PLAN VIEW - HOOD #1 (GRIDDLE HD)  
 8' 0.00" LONG 54.24ND-2-ACSPSP-F

ACPS SP SHIPS LOOSE FOR FIELD INSTALLATION




PLAN VIEW - HOOD #2 (FRY HD)  
 5' 0.00" LONG 54.24ND-2-ACSPSP-F


ACPS SP SHIPS LOOSE FOR FIELD INSTALLATION




PLAN VIEW - HOOD #3 (DISH HD)  
 3' 6.00" LONG 42.24VHB-G



SECTION VIEW - MODEL 5424ND-2-ACSPSP-F HOOD - #1 (GRIDDLE HD)




SECTION VIEW - MODEL 5424ND-2-ACSPSP-F HOOD - #2 (FRY HD)




SECTION VIEW - MODEL 4224VHB-G HOOD - #3 (DISH HD)

**PATENT NUMBERS**


AC-PSP (UNITED STATES) - US PATENT 7063030 B2  
 AC-PSP (WALL (CANADA) - CA PATENT 2602609  
 AC-PSP (ISLAND (CANADA) - CA PATENT 2602630



HOOD CORNER HANGING ANGLE (HARDWARE BY INSTALLER)



FULL LENGTH HANGING ANGLE (HARDWARE BY INSTALLER)



SUPPLY PLENUM HANGING ANGLE (HARDWARE BY INSTALLER)

**ASSEMBLY INSTRUCTIONS**

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TPI GRADE 5 (MINIMUM) ALL-THREAD, SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TPI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION BENEATH HOOD HANGING ANGLES AND ABOVE CEILING ANCHORS. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.

**ASSEMBLY INSTRUCTIONS**

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TPI GRADE 5 (MINIMUM) ALL-THREAD, SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TPI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION ABOVE CEILING ANCHORS. SINGLE HEX NUT BENEATH HANGING ANGLE IS ACCEPTABLE FOR FULL LENGTH HANGING ANGLES. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.

**ASSEMBLY INSTRUCTIONS**

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TPI GRADE 5 (MINIMUM) ALL-THREAD, SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TPI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION ABOVE CEILING ANCHORS. SINGLE HEX NUT BENEATH HANGING ANGLE IS ACCEPTABLE FOR PSP HANGING ANGLES. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.

**REVISIONS**

DESCRIPTION	DATE



www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com

HBT Foodservice

www.captiveaire.com

104 W 9th St Suite 204, Kansas City, MO, 64105 PHONE: (816) 221-8575 FAX: (816) 221-8311 EMAIL: rsg@captivate.com







- FAN #1 0.280-104RPU - HEATER ITEM 74.3
- DIRECT GAB FRED HEATED MAKE UP AIR UNIT WITH 15" MIXED FLOW DIRECT DRIVE FAN
- HEAT EXCHANGER WITH 12 FILTERS
- DOWN DISCHARGE - AIR FLOW RIGHT - LEFT
- GAS PRESSURE GAUGE - 5 TO 11 INCHES WC - 1/2" DIAMETER, 1/4" THREAD SIZE
- GAS PRESSURE GAUGE - 0 TO 2.5" DIAMETER, 1/4" THREAD SIZE
- LOW FIRE START - ALLOWS THE BURNER TO BE ENERGIZED WHEN THE MODULATION CONTROL IS IN A LOW FIRE POSITION
- COOLING INTERLOCK RELAY - JAVAC COIL - 200V CONTACTS - LOCK OUT BURNER CIRCUIT WHEN AC IS ENERGIZED
- MOTORIZED BACK DRAFT DAMPER - 18" X 18" FOR SIZE 1" STANDARD MODULAR HEATER LATEL W/ TRENCH 3/4" 1" STANDARD GALVANIZED CONSTRUCTION - 30" HEAT EXCHANGER - 12" COILS - 12" COILS - 12" COILS
- EX COOLING INTAKE AIR THERMOSTAT AND RELAYS MOUNTED IN UNIT - SET POINT FOR THERMOSTAT SHOULD BE 60°F
- 15 TON COIL CIRCULATES 1500 GPM OF WATER FOR SIZE 1500 GPM MODULAR PACKAGED UNIT INCLUDES CONDENSER, DX COIL, FILTER DRYER KIT, THERMAL EXPANSION VALVE, R450A REFRIGERANT, AND REFRIGERANT PIPING (1.800 TO 3.000 CFM) WHEN ORDERED WITH OPPOSITE AIRFLOW CONDENSERS ACCESS COIL PIPING WILL REMAIN IN STANDARD POSITION (DRAIN AND BLEED WILL WORK TO THE OPPOSITE SIDE. ANY OTHER CHANGE WILL REQUIRE CL) CONDENSERS REQUIRE SEPARATE 200V, 3 PHASE POWER SUPPLY UNLESS ORDERED WITH SINGLE POINT CONNECTION. COIL = 200V/3PH
- SEPARATE 120VAC WIRING PACKAGE FOR MAKE UP AIR UNITS. OPTION MUST BE SELECTED WHEN MOUNTING INTO PREWIRE PANEL OR WITH DOW PACKAGE. PROVIDES SEPARATE 120VAC INPUT TO SUPPLY FAN. THIS 120V SIGNAL MUST BE RUN BY ELECTRICIAN FROM ECU TO MAIN SWITCH.
- DOWN CURB FLEXIBLE DR. SIZE - COOLING COIL MODULE. REQUIRED FOR DOWN DISCHARGE COOLING COIL APPLICATIONS
- MINI DOUBLE WALL INSULATED DOOR ASSEMBLY (BURNER/LOWER/UPPER SECTION)
- 2 YEAR PARTS WARRANTY

NOTE: SUPPLY DUCT MUST BE INSTALLED TO MEET SMACNA STANDARDS. A MINIMUM STRAIGHT DUCT LENGTH MUST BE MAINTAINED DOWNSTREAM OF UNIT DECREASE AS OUTLINED IN SMACNA PUBLICATION 201. WHEN USING RECTANGULAR DUCTWORK, ELBOWS MUST BE RADIUS THROAT (RADUS BACK WITH TURNING VANES). FLEXIBLE DUCTWORK AND SQUARE THROAT SQUARE SHOCK ELBOWS SHOULD NOT BE USED. ANY TRANSITION AND/OR TURN IN THE DUCTWORK WILL CAUSE SYSTEM EFFECT. SYSTEM EFFECT WILL INCREASE STATIC PRESSURE AND REDUCE AIRFLOW. DO NOT RELY ON UNIT TO SUPPORT DUCT IN ANY WAY. FAILURE TO PROPERLY SIZE DUCTWORK MAY CAUSE SYSTEM EFFECTS AND REDUCE PERFORMANCE OF THE EQUIPMENT. SUGGESTED STRAIGHT DUCT SIZE IS 14" X 14".



SUPPLY SIDE HEATER INFORMATION:

WINTER TEMPERATURE = 20°F. TEMP. RISE = 50°F. RTU IS CALCULATED OFF ACTUAL AIR DENSITY. OUTPUT RTU AT ALTITUDE OF 500 FT. = 119842. INPUT RTU AT ALTITUDE OF 0.0 FT. = 128490. OUTPUT RTU AT ALTITUDE OF 1000 FT. = 113893. INPUT RTU AT ALTITUDE OF 1070 FT. = 112419.



**GENERAL NOTES:**

- 1) 1" DIAMETER PVC PIPE ONLY
- 2) USE ONLY LOW PROFILE COUPLINGS
- 3) ADD CLEAN OUT AS SHOWN.



REVISIONS	
DESCRIPTION	DATE




Freddy's - Fort Oglethorpe, GA  
RINGGOLD, GA, 30738

DATE: 6/15/2022  
DWG.#: 5516907  
DRAWN BY: michael.co  
SCALE: 1/2" = 1'-0"  
MASTER DRAWING

SHEET NO. 3

**BSG**  
BAKER DESIGN GROUP PA  
1024 E. 1st Street N. Wichita, KS 67214 316.267.7142  
rodger@bakergdesigngroup.com

**FREDDY'S FROZEN CUSTARD**  
BATTLEFIELD PARKWAY  
FORT OGLETHORPE, GA.



THE DESIGN AND DETAILS DISCLOSED HEREIN ARE THE EXCLUSIVE PROPERTY OF RODGER W. BAKER, AIA AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT HIS PRIOR WRITTEN CONSENT.




RODGER W. BAKER, AIA

DATE  
7/8/2022

DRAWN BY:  
CHECKED BY:


SHEET NO.  
**M5**

ELECTRICAL PACKAGE - JOB#5516907				SWITCHES		OPTION		FANS CONTROLLED					
NO	TAG	PACKAGE#	LOCATION	QUANTITY	DESCRIPTION	DESCRIPTION	DESCRIPTION	FAN TAG	TYPE	HP	VOL.1	VOL.2	
1	ECM-1	DCV211	UTILITY CABINET LEFT	1 LIGHT	1 FAN	SMART CONTROLS DCV		ITEM 74.1	EXHAUST	3	1.000	208	1.8
				1 FAN				ITEM 74.2	EXHAUST	1	0.500	115	8.3
								ITEM 74.3	SUPPLY	3	3.000	208	8.8



**Demand Control Ventilation Hood Control Panel Specifications:**


- Controls shall be listed by ETL (UL 308A) and shall comply with demand ventilation system shutdown requirements outlined in IECC 403.2.8 (2015).
- The control enclosure shall be NEMA 1 rated and listed for installation inside of the exhaust hood utility cabinet. The control enclosure may be constructed of stainless steel or painted steel.
- Temperature probe(s) located in the exhaust duct riser(s) shall be constructed of stainless steel.
- A digital controller shall be provided to activate the hood exhaust fans dynamically based on a fixed differential between the ambient and duct temperatures. This function shall meet the requirements of IMC 507.1.1.
- A digital controller shall provide adjustable hysteresis settings to prevent cycling of the fans after the cooling appliances have been turned off and/or the heat in the exhaust system is reduced.
- A digital controller shall provide an adjustable minimum fan run-time setting to prevent fan cycling.
- Variable Frequency Drives (VFDs) shall be provided for fans as required. The digital controller shall modulate the VFDs between a minimum setpoint and a maximum setpoint on demand. The duct temperature sensor input(s) to the digital controller shall be used to calculate the speed reference signal.
- The VFD speed range of operation shall be from 0% to 100% for the system, with the actual minimum speed set as required to meet minimum ventilation requirements.
- An internal algorithm to the digital controller shall modulate supply fan VFD speed proportional to all exhaust fans that are located in the same fan group as the supply fan.
- The system shall operate in PREP MODE during light cooking heat or COOL DOWN MODE when sufficient heat remains underneath the hood system after cooking operations have completed. Operation during either of these periods will disable the supply fans and provide an exhaust fan speed that is equal to the minimum ventilation requirement.
- A digital controller shall disable the supply fan(s), activate the exhaust fan(s), activate the appliance shunt trip, and disable an electric gas valve automatically when fire condition is detected on a covered hood.
- A digital controller shall allow for external BMS fan control via Dry Contact (external control shall not override fan operation logic as required by code).
- An LCD interface shall be provided with the following features:
  - On/Off push button fan & light switch activation
  - Integrated gas valve reset for electronic gas valves (no reset relay required)
  - VFD Fault display with audible & visual alarm notification
  - Duct temperature sensor failure detection with audible & visual alarm notification
  - Mis-wired duct temperature sensor detection with audible & visual alarm notification
  - A single low voltage CAN BUS wiring connection
  - An energy savings indicator that utilizes measured kWh from the VFDs



**TYPICAL HOOD CONTROL PANEL INSTALLATION**

**Sequence of Operations:**

- The hood control panel is capable of operating in one or more of the following states at any given time:
  - **Automatic:** The system operates based on the differential between room temperature and the temperature at the hood canopy or exhaust duct collar. Fans activate at a configurable temperature differential threshold. Depending on the job configuration each fan zone can be configured as static or dynamic. These terms refer to whether a variable motor (such as EC Motors or VFD driven motors) modulate with temperature. If the panel is equipped with variable speed fans and the zone is defined as "dynamic", these will modulate within a user-defined range based on the temperature differential. Panels equipped with variable speed fans and a fan zone defined as "static", fans will run at a set speed calculated for the drive. Demand control ventilation systems are capable of modulating exhaust and make up air fan speeds per the requirements outlined in IECC 403.2.8.
  - **Manual:** The system operates based on human input from an HMI.
  - **Schedule:** A weekly schedule can be set to run fans for a specified period throughout the day. There are three scheduled times per day to allow for the user to set up a time that is suitable to their needs. Any time that is within the defined occupied time, the system will run at modulation mode and follow the fan procedure algorithm based on temperature during this time. During unoccupied time, the system will have an extra effort to prevent unintended activation of the system during a time where the system is not being occupied.
  - **Other:** The system operates based on the input from an external source (IOC, BMS or hardwired interlock)



**TYPICAL ANSUL R-102 SYSTEM LAYOUT**

**SPECIFICATIONS**

THE RESTAURANT FIRE SUPPRESSION SYSTEM SHALL BE THE PRE-ENGINEERED TYPE WITH A FIXED NOZZLE AGENT DISTRIBUTION NETWORK. IT SHALL BE LISTED WITH UNDERWRITERS LABORATORIES, INC. (UL)

THE SYSTEM SHALL BE CAPABLE OF AUTOMATIC DETECTION AND ACTUATION WITH LOCAL OR REMOTE MANUAL ACTUATION. ACCESSORIES SHALL BE AVAILABLE FOR MECHANICAL OR ELECTRICAL GAS LINE SHUT-OFF APPLICATIONS.

THE EXTINGUISHING AGENT SHALL BE A POTASSIUM CARBONATE, POTASSIUM ACETATE-BASED FORMULATION DESIGNED FOR FLAME KNOCKDOWN AND SECUREMENT OF GREASE RELATED FIRES. IT SHALL BE AVAILABLE IN PLASTIC CONTAINERS WITH INSTRUCTIONS FOR LIQUID AGENT HANDLING AND USAGE.

THE REGULATED RELEASE MECHANISM SHALL BE COMPATIBLE WITH A FUSIBLE LINK DETECTION SYSTEM. THE FUSIBLE LINK SHALL BE SELECTED AND INSTALLED ACCORDING TO THE OPERATING TEMPERATURE IN THE VENTILATING SYSTEM. THE FUSIBLE LINK SHALL BE SUPPORTED BY A DETECTOR BRACKET/ LINKAGE ASSEMBLY.

REVISIONS	
DESCRIPTION	DATE

**CAPTIVE**  
 HBT Foodservice  
 www.captivehbt.com  
 104 W 8th St Suite 204 - Kansas City, MO. 64105 PHONE: (816) 221-8575 FAX: (816) 221-8511 EMAIL: reg@captivae.com


Freddy's - Fort Oglethorpe, GA  
 RINGGOLD, GA, 30736

**DATE:** 6/15/2022  
**DWG.#:** 5516907  
**DRAWN BY:** michael.co  
**SCALE:** 1/2" = 1'-0"  
**MASTER DRAWING**

**SHEET NO.**  
 4

**BDG**  
 BAKER DESIGN GROUP PA  
 1024 E. 1st Street N. Wichita, KS 67214 316.267.7142  
 roddger@bakerdesigngroup.com

**FREDDY'S FROZEN CUSTARD**  
 BATTLEFIELD PARKWAY  
 FORT OGLETHORPE, GA.



THE DESIGN AND DETAILS DISCLOSED HEREIN ARE THE EXCLUSIVE PROPERTY OF RODGER W. BAKER, AIA AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT HIS PRIOR WRITTEN CONSENT.

RODGER W. BAKER, AIA

DRAWN BY:  
 CHECKED BY:  
 SHEET NO.  
**M6**

**Mechanical Specifications**  
**Table of Contents**  
 Division 2 - Mechanical  
 23000 - Heating & Ventilating and Air Conditioning  
 23001 - Operation & Maintenance Manuals  
 23002 - Heating & Ventilating and Air Conditioning  
 23003 - Insulation, Low Pressure Duct  
 23004 - HVAC Insulation, General  
 23005 - Controls, Electric  
 23006 - Ductwork, Low Pressure, Galvanized Steel  
 23007 - Ductwork, Low Pressure, Flexible  
 23008 - Diffusers, Registers, & Grilles  
 23009 - Air Distribution Equipment (Furnaces, Condensing Units & Exhaust Fans)  
 23010 - Packaging, Outdoor, Central-Station Air-Handling Units  
 23011 - Heating & Ventilating, and Air Conditioning, General  
 PART 1 - GENERAL  
 1.1 DESCRIPTION  
 A. Section 23000 pertains to heating, ventilating, and air conditioning (HVAC) work. This section applies to and governs all HVAC sections.  
 B. Refer to other divisions for continuation of exterior work.  
 1.2 PERMITS, FEES, CODES, ORDINANCES, AND REGULATIONS  
 A. Obtain and pay for all permits, inspections and connection fees required by governing bodies in connection with the work. Deliver certificates of inspection to the owner.  
 B. All work shall comply with governing codes, ordinances, and regulations of the city, county, and state having jurisdiction, and the national electrical code, mechanical code, and requirements of the Board of Health.  
 1.3 QUALITY ASSURANCE  
 A. Obtain and pay for all permits, inspections and connection fees required by governing bodies in connection with the work. Deliver certificates of inspection to the owner.  
 B. All work shall comply with governing codes, ordinances, and regulations of the city, county, and state having jurisdiction, and the national electrical code, mechanical code, and requirements of the Board of Health.  
 1.4 SUBMITTALS  
 A. Product data: Submit on all materials, products, and equipment unless otherwise specified or acknowledged in writing.  
 B. Samples: Submit when specified or requested.  
 C. Operation and maintenance manuals: Submit copies of O and M manuals to Architect.  
 1.5 JOB CONDITIONS  
 A. Protect materials, apparatus, and equipment from damage, moisture, dirt, debris, and work of other trades.  
 B. Use of paper, cardboard, or other flimsy material will not be permitted. Replace damaged protective materials immediately. Do not install damaged materials and equipment; remove from the site.  
 1.6 RECORDED DOCUMENTS  
 A. Furnish owner with one set of accurately marked blue-line copies of the drawings, indicating all changes from the contract drawings and all work and controls as installed.  
 1.7 GUARANTEE AND SERVICE  
 A. Where standard guarantees are called for herein, furnish three (3) copies to be inserted in operation and maintenance manuals.  
 B. All preventative maintenance and normal service will be performed by the owner's maintenance personnel after final acceptance of the work. This shall not alter the contractor's guarantee of the work in any way.  
 C. All labels shall be securely affixed.  
 PART 2 - PRODUCTS  
 2.1 GENERAL  
 A. All materials and equipment shall be new. Systems shall be provided complete, and each system as a whole, and in all its parts, shall function correctly up to the specified capacity. Should a system, or any part thereof fail to meet performance requirements by the owner, necessary replacements, alterations, or repairs, as required by the owner, shall be made to bring performance up to specified requirements of building construction and finished damaged or marred by such replacements, alterations, or repairs shall be restored to prior conditions, at no additional cost to the owner.  
 B. Where multiple items of equipment of materials are required, they shall be the product of a single manufacturer.  
 C. Before ordering any equipment, the size of all equipment shall be checked to easily fit spaces allotted on the drawings.  
 D. Items, pipe sleeves, supports, and anchorage of air conditioning equipment shall be provided as specified herein. Where such items are to set or embedded in concrete, masonry, or similar work, the items shall be furnished and layout made at the proper time for the setting or embedment thereof so as to cause no delay in the work.  
 E. Piping assemblies of equipment shown on the drawings are diagrammatic. All piping and appurtenances required for the proper operation of all equipment shall be provided.  
 2.2 MANUFACTURER'S NAMES AND CATALOG NUMBERS  
 A. Specific references have been made to one or more manufacturer's names and name or catalog numbers. This does not indicate that the material and equipment specified is necessarily an "off the shelf" item. Requirements for specific finishes, materials, or other modifications may introduce variances from manufacturer's standards. Contractor shall ascertain that such modifications are fully considered.  
 2.3 DIAGRAMS, NAMEPLATES, AND LABELS  
 A. Each major component of equipment shall have the manufacturer's name, address, and catalog number on a plate securely affixed in a conspicuous place. The nameplate of a distributing agent will not be accepted.  
 B. All pieces of equipment, valves, starters, disconnects, and all pneumatic and electrical control instruments and apparatus shall be identified with 1/16" thick black laminated plastic nameplates, with 3/16" high white laminated letters. Similar and line equipment shall be designated with numerical suffix (Example: Thermostat, T-1). The nameplate identifications shall coincide with items appearing on diagrams.  
 C. Provide a label for the mechanical system stating:  
 "Installation by (Name, Address, and Phone Number of Contractor)"  
 D. Letters shall be 1/4" high and located on a conspicuous place in the mechanical room.  
 PART 3 - EXECUTION  
 3.1 INSTALLATION AND WORKMANSHIP  
 A. The work shall be performed by qualified mechanics and all materials, apparatus, and equipment shall be installed in neat, workmanlike manner. Any material, apparatus, or equipment which, in the opinion of the owner, is improperly installed shall be removed and the reinstalled in an approved manner at no additional cost to the owner.  
 B. The work shall be coordinated with the work of other trades. Where the work is dependent upon work of other trades or work already in place, such other work and work in place shall be examined and shall be in proper condition and state of completion before continuing the installation.  
 C. The installation of the system shall, in general, be in accordance with the drawings and regards to location of equipment, ducts, pipes, and the like. Piping ductwork indicated shall be followed as accurately as actual construction will permit and any deviations whatsoever shall be called to the attention of the architect-engineer. Where necessary, as determined by the architect-engineer, contractor shall furnish drawings showing proposed changes.  
 3.2 EARTHWORK AND Dewatering  
 A. Perform in accordance with Division 2.  
 3.3 CUTTING AND PATCHING  
 A. Layout openings for cutting by other trades as required.  
 B. Cutting of steel, concrete, or any other structural part must be approved in writing by owner prior to cutting.  
 3.4 WATERPROOFING  
 A. Do not cut or penetrate waterproofed surfaces, or waterproofing membranes, without first making arrangements for repair by a method approved by architect-engineer.  
 B. Copies of certificates of inspection.  
 C. Guarantees, including extended guarantees.  
 3.5 ELECTRICAL WORK  
 A. Power wiring from panels to motor controllers and from controllers to motors is specified in Division 16.  
 B. Motor starters not specified to be provided with the motors at the factory area specified in Division 16.  
 C. Submit wiring diagrams for approval and provide working diagrams so that the electrical work may be properly accomplished.  
 D. Electrical control wiring for connection of temperature controllers, push buttons, interlocks in motor controllers, and like items is specified in the control section (a) in this division. Furnish all equipment with complete internal control wiring.  
 E. Electrical work specified in this division shall conform to applicable provisions of Division 16. All control wiring shall be in conduit.  
 F. Provide motors conforming to characteristics shown on electrical drawings.  
 3.6 SUPPORTS FOR PIPING AND EQUIPMENT  
 A. Support for piping shall be supported from structural members and not from metal deck and slab assemblies.  
 3.7 ACCESS DOORS (ACCESS PANELS)  
 A. Provide access doors for maintenance, adjustment, removal, and repair of valves, controls, dampers, equipment, and like items furnished hereunder.  
 B. Provide access doors where required. Panels shall be located to make all items easily accessible.  
 3.8 CLEAN UP  
 A. Refer to general conditions for cleaning up.  
 B. Clean all materials and equipment off of dust, paint, spots and stains, soil marks, and other foreign matter.  
 3.9 FINAL INSPECTION  
 A. Notice to the architect-engineer that the work is ready for final inspection. The contractor shall:  
 1. Submit test and balance report and complete requirements as noted.  
 2. Submit letter from control manufacturer certifying that controls have been checked for operation and calibration, and that system is operating as intended.  
 B. Contractor shall furnish necessary mechanics to operate system, make necessary adjustments and assist with final inspection.  
 3.10 INSTRUCTION OF OWNERS OPERATING PERSONNEL  
 A. The contractor shall include the cost of the services of qualified instructor(s) to instruct the owner's operating personnel in the operation, adjustment, care, and maintenance of all HVAC equipment and systems.  
 B. Instruction shall be performed at a time approved by the owner and after all HVAC equipment and systems are installed, complete, adjusted, and operating to specified requirements, contractor shall notify the architect-engineer when instructions will be given.  
 C. Qualifications of instructors shall be subject to approval of the owner and equipment manufacturer.  
 D. Additional requirements concerning operation and maintenance of mechanical equipment and systems may be specified in other sections.  
 E. Two (2) copies of acknowledgment of all required instructions to owner's operating personnel, signed by the owner or his authorized representative, shall be submitted prior to submitting application for final payment. An additional copy of this acknowledgment is required in each copy of operation and maintenance manuals required in the section "Operation & Maintenance Manuals".  
 END OF SECTION  
 23001 - Operation & Maintenance Manuals  
 PART 1 - GENERAL

1.1 DESCRIPTION  
 A. Furnish three (3) copies of complete operation and maintenance manuals to the owner, for approval and for the owner, on all equipment and systems. The manuals shall be bound in hard-back, three ring loose-leaf binders.  
 PART 2 - PRODUCTS  
 2.1 MANUAL CONTENTS  
 A. Title sheet with job name, and the names, addresses, and phone numbers of the contractor, subcontractor, control subcontractor, related contractors and material and equipment suppliers.  
 B. Table of contents.  
 C. A copy of acknowledgment of instruction to the owner's operating personnel in the operation of all mechanical equipment and systems, signed by the owner or his authorized representative.  
 D. Typeset operating instructions for the owner's personnel describing how to stop and start each piece of equipment, how to set the temperature control system for normal operation and normal restarting procedures, caution and warning notices. Record drawings of all systems including electrical and control diagrams.  
 PART 3 - EXECUTION  
 3.1 DELIVERY  
 A. Deliver the manuals to the Architect at substantial completion.  
 END OF SECTION  
 23059 - Testing, Adjusting, & Balance  
 PART 1 - GENERAL  
 1.1 SPECIAL NOTICE  
 A. Each contractor shall read all relevant documents, become familiar with the job, scope of work, type of general construction, and the architectural, structural, mechanical, and electrical drawings and specification. Each contractor shall also familiarize himself with the purpose for which these documents have been prepared and shall become cognizant of all the details involved. Each contractor shall coordinate his work with that of others.  
 B. An independent test and balance contractor shall provide test and balance services. TAB contractor shall be NEHS or AABC certified. TAB contractor shall be National TAB and contracted through the building owner.  
 1.2 STARTUP TEST AND ADJUSTMENT  
 A. Startup, testing, and adjusting this equipment is to be put into final operating condition by the owner's work and benefit. All tests of equipment and systems required to prove compliance with the drawings and specification shall be performed in the presence of the owner's representative.  
 1.3 GENERAL  
 A. Inquire about any problems or complaints.  
 B. Compare mechanical plans to installed system.  
 C. Document design specifications for report.  
 D. Ensure all fans are running for balance.  
 E. Measure initial building pressure.  
 1.4 INSPECT ROOFTOP EQUIPMENT  
 A. Inspect units and note any deficiencies.  
 B. Record unit nameplate data.  
 C. Check thermostats for proper settings.  
 D. Check for correct fan rotation (including condenser fans).  
 E. Check conditions of filters and coils.  
 F. Check position of outside air dampers.  
 G. Check gas lines and condensate lines.  
 H. Check belt tension and pulley alignment.  
 I. Check disconnect switches and circuit breakers.  
 J. Check any fan noise and vibration.  
 K. Check heat-cool modes of RTUs.  
 1.5 TEST AND BALANCE KITCHEN HOOD SYSTEM (WHERE APPLICABLE)  
 A. Measure supply and exhaust FPM hoods.  
 B. Clean hood smoke capture and equipment on site.  
 C. Adjust supply and exhaust RPM and supply air damper, as required.  
 D. Note adjustments made on pulleys.  
 E. Measure final RPM's.  
 F. Evaluate duct system design and installation.  
 G. Ensure hood smoke capture and equipment on site.  
 1.6 TEST AND BALANCE HEATING/COOLING SYSTEM  
 A. Measure RTU supply and return airflow values.  
 B. Check for drafts, hot/cold spots in occupied spaces.  
 C. Adjust RPM as necessary to achieve design.  
 D. Check actual motor amps versus motor rated f.a.  
 E. Note adjustments made on pulleys.  
 F. Measure and record motor RPM.  
 G. Evaluate duct system design and installation.  
 H. Ensure slightly positive building pressure.  
 I. Set and record damper positions.  
 J. Measure final building pressure.  
 1.7 FINAL REVIEW  
 A. Review report and data for completeness.  
 B. Discuss results and findings with superintendent.  
 C. Air qualities shall be balance to within +/-10% of design as a general rule. However, its come cases, the air quantities may need to be adjusted differently in order to ensure acceptable control levels; hood capture pressure, positive building pressure, etc. Notify the superintendent of any deficiencies needing immediate attention. The G.C. shall have the mechanical and electrical contractors call to promptly correct any such problems (i.e. replace burned out motors, failed thermostats, incorrect wiring, bad coil breakers and starters, dirty filters).  
 PART 2 - PRODUCTS  
 PART 3 - EXECUTION  
 END OF SECTION  
 23013 - Insulation, Low Pressure Duct  
 PART 1 - GENERAL  
 1.1 DESCRIPTION  
 A. All low pressure duct systems, two (2) inches water gage or less, shall be insulated.  
 B. All applicable requirements of this section, "HVAC-Insulation, General," shall apply to this section.  
 1.2 EQUIVALENT MATERIALS  
 A. Materials other than those specified will be considered for approved equal.  
 PART 2 - PRODUCTS  
 2.1 INSULATION  
 A. Manufacturer's: Schuller (Johns Manville) Microtex - Textre-Fire - Certain-Teed-Saint - Cocain - Owens Corning - Knauf Fiberglas  
 B. Insulate internally low velocity rectangular supply ducts, and return air ducts with fiberglass duct liner with a minimum density of 2.0 pounds per cubic foot and a maximum "K" factor of 0.27 at 75 degrees F mean temperature comply with ASTM 1071 (Type 1). The liner insulation surface coating shall contain an EPA registered, anti-microbial agent so it will not support microbial growth as tested in accordance with ASTM G21 and G22. The liner shall have an NRC not less than the minimum standard listed in ASTM 1071. Liner for supply ductwork shall be 1"-thick and liner for return ductwork shall be 1"-thick.  
 C. Insulate internally high velocity rectangular supply ducts with 1 1/2"-thick liner of 2.0 pounds per cubic foot density, as follows: Note: Do not insulate ducts in kitchens.  
 1. Apply insulation from the fan back down the duct for a distance of 15 feet in all directions. Apply in all branches if multiple branches occur near the fan.  
 2. Round exhaust ducts shall be insulated.  
 D. Coat all exposed edges with Foster's gray no. 30-70 lagtime adhesive.  
 E. Adhere liner to interior sides of duct with minimum 50% coverage of fire retardant adhesive such as Foster 85-11, Children, or Minnesota Mining. Equivalent to comply with ASC-A-7001.  
 F. Use mechanical fastening of Gaskets Hinged Pits, or Sika-Blocks on maximum 18" centers at all sections when width exceeds 12" and/or sides when height exceeds 24". Pins shall comply with SMCMAA MF-1.  
 G. Apply a brush width of Foster's fire retardant coating gray no. 30-70 lagtime over all joints, visible cut edges, and leading edges of insulation to prevent fire erosion.  
 H. Duct joints on drawings are for dimensions made of lining and sheet metal size shall be increased accordingly. If adhesive is applied in shop use Foster Spray - FAS 85-11 if applied in field use Foster Spray - FAS adhesive 85-20. Adhesives shall be approved and listed by underwriters laboratory and shall bear the U.L. label.  
 I. Thickness and classifications of duct liner shall be printed on the face of the liner by the manufacturer.  
 J. Duct liner shall have and underwriters laboratories fire hazard rating with a flame spread not to exceed 25 and fuel contributed and smoke developed ratings not to exceed 50.  
 2.2 DUCT INSULATION (EXTERNAL)  
 A. Manufacturer's: Schuller (Johns Manville) - Textre-Fire - Certain-Teed-Saint - E.O. Wood - Owens Corning - Knauf Fiberglas  
 B. Insulate externally all round and oval ducts, all conical rectangular supply air ducts which are noted or specified to have no duct lining; 1 1/2"-thick and of 0.5 - 0.75 pound density fiberglass ductwrap with a foil-form kraft vapor barrier applied with outward-clinging straps. Insulation to have a minimum R-value of 5.7.  
 C. Insulation shall be continuous through partitions, coils, etc. Insulate fire damper sleeves to partitions.  
 D. Exposed round ductwork in dining and lounge area shall be uninsulated.  
 2.3 GREASE DUCT INSULATION  
 A. 1 and 2 Hour; zero insulation Applied Fire Protection for Commercial Kitchen Grease Ducts when tested in accordance with ASTM E 2335. Passes all Acceptance Criteria in Sections 16.1 to 16.5 - Reference ICC-ES Building Code Report ESR 2213 or ESR 2832, also reference UL Listing HNK1 G-18.  
 B. 1 and 2 Hour Applied Fire Protection when tested in accordance with UL 1978, Compliant per Interlock Listing TCB1 120-1.  
 C. 1 and 2 Hour - F and T-Rated Through Penetration Firestop when tested in accordance with ASTM E 814 UL 1479; UL Through Penetration Listings, CAJ-1562; CAJ-7004; CAJ-7012; CAJ-7014; CAJ-7019; CAJ-7021; CAJ-7047; CAJ-7055; CAJ-7058; CAJ-7119; F-A-1093; F-A-1094; F-A-3048; F-C-7038; FC-7037; WL-7041; WL-7099; WL-7121; WL-7145; WL-7088.  
 D. 1 and 2 Hour Applied Fire Protection for Ventilation Air Duct when tested in accordance with ISO 8944-1985 - Reference UL Listings HNLJ V19; HNLJ V26.  
 E. Manufacturers: Subject to compliance with requirements, provide one of the following:  
 1. 

- a. CertainTeed Corp., FlameChok
- b. Nelson Fire Stop Products, Nelson FSB FlamenShield Blanket
- c. Thermal Ceramics, FireMaster XL
- d. 3M Fire Barrier Wrap Products
- e. Unifrax Corporation, FireWrap

 F. Access Doors (Fire-Rated): Thermal Ceramics FastDoor XL (or equal) for duct access to Type I commercial kitchen hood exhaust ductwork. Install access openings at each change in direction and at intervals as required by code. Insulation cover system shall be tested and listed by UL (PNKT G18) to provide zero clearance to combustible construction and [1] [2] hour fire rating per ASTM E 2335. Duct access cover panel shall be tested and listed by UL (VYSI HNK76) with integral response gasket to provide liquid tight seal and shall have a top temperature gasket and signage "Access Door - Do not Obstruct" compliant to code and NFPA 96. Installation shall be performed by an experienced contractor per manufacturer instructions and applicable UL Listings. Sheet metal and insulation contractors shall coordinate installation of the FastDoor XL and the duct enclosure system.  
 PART 3 - EXECUTION  
 3.1 INSTALLATION  
 A. All supply and return air ductwork.  
 B. Air supply diffuser backs and necks:  
 1. All supply diffuser backs and necks, shall be insulated with one (1) inch-thick, 3/4 pound density, Manville P-series Smallcell, or approved equal fiberglass blanket insulation, having a conductance (K) no greater than 0.31. Adhesive insulation to the duct as specified below.  
 END OF SECTION  
 230716 - HVAC Insulation, General  
 PART 1 - GENERAL  
 1.1 DESCRIPTION  
 A. The section governs all HVAC insulation.  
 1.2 SUBMITTALS  
 A. Submit product data covering thermal, permeability, and fire performance characteristics of all insulation material, adhesives, and finishes. Data shall be clearly marked to show intended use, thickness, finishes, adhesives, and application techniques.  
 PART 2 - PRODUCTS  
 PART 3 - EXECUTION  
 3.1 INSTALLATION  
 A. Insulation shall not be installed until testing procedures have been complied with all surfaces and have been cleaned free of dirt and grease and are completely dried.  
 B. Protect adjacent surfaces, equipment and premises from dropping of coatings adhesives and finishes. Remove all excess materials and debris from both exposed and concealed areas so that these areas are completely clean.  
 C. Remove all excess materials and debris from both exposed and concealed areas so that these areas are completely clean.  
 D. Insulation shall not be applied until the general construction has progressed sufficiently to ensure against physical or moisture damage to the insulation. Replace any insulation which has become wet.  
 E. Ductwork hanger rods must be installed and perpendicular before insulation is installed.  
 F. All joints between insulation blankets, sleeves, etc. shall be sealed and taped with 7-wide pressure sensitive tape with adhesive applied to overlapping vapor barriers before tape is applied. Tape to be full faced, reinforced tape as recommended by insulation manufacturer to maintain all ratings of insulation. Cloth back generic "duct tape" is not acceptable.  
 G. Insulation to be secured externally to all ductwork as well as permanently joined to other portions of insulation on the same duct per manufacturer's recommendations.  
 H. All duct insulation is to U.L. Classified.  
 END OF SECTION  
 23090 - Controls, Electric  
 PART 1 - GENERAL  
 1.1 DESCRIPTION  
 A. The work consists of installing controls for the HVAC system as on the drawings.  
 1.2 SUBMITTALS  
 A. Provide substantial consideration of complete control diagrams for the system with construction details and engineering data sheet on all system components.  
 1.3 ELECTRICAL  
 A. Electrical work and materials associated with the control system shall be installed as work of this section but in accordance with Division 16.  
 B. Power wiring is specified under Division 16 and show on electrical drawings.  
 C. Electrical control wiring conduit and fittings associated with the space temperature and humidity control including interlocking with motor controllers, control accessories, and appurtenances are to be provided under this section. Control wiring shall be in conduit.  
 PART 2 - PRODUCTS  
 2.1 ELECTRONIC ROOM THERMOSTATS AND REMOTE SENSORS  
 A. Thermostat shall be as specified in the drawings.  
 B. Thermostat shall have automatic heating-cooling changeover to control operation of the heating and cooling on rooftop air conditioning units.  
 2.2 SMOKE DETECTION/FAN SHUT-DOWN  
 A. Smoke detector shall be by integrally installed by the mechanical contractor as specified in the drawings.  
 B. Remote alarm indicator for duct mounted smoke detectors shall be specified in the drawings.  
 C. Smoke detector shall be powered as specified in drawings.  
 PART 3 - EXECUTION  
 3.1 ELECTRIC ROOM THERMOSTATS  
 A. Smoke detectors shall be wired as slow voltage circuit. (24v)  
 B. B. Thermostats and sensors shall be wired as low voltage circuit.  
 C. Line voltage wiring shall be by the electrical contractor.  
 D. Mechanical contractor shall provide and install all wiring and necessary appurtenances to perform all of the temperature control sequences.  
 END OF SECTION  
 23013 - Ductwork, Low Pressure, Galvanized Steel  
 PART 1 - GENERAL  
 1.1 QUALITY ASSURANCE  
 A. Ducts shall be constructed and installed in accordance with "HVAC Duct Construction Standards" published by the Steel Metal and Air Conditioning Contractors National Association, Inc. (SMACNA)  
 B. Ductwork shape, size, and location shall be in accordance with plans as closely as possible. Note that duct sizes called out on plans are clear inside dimensions of ductwork. Increase ductwork to accommodate duct liner.  
 1.2 JOB CONDITIONS  
 A. Inspect the drawings and verify existing conditions in the field. Report conflicts before starting fabrication.  
 PART 2 - PRODUCTS  
 2.1 DUCT MATERIAL  
 A. Outdoor-Air Refrigerant Coil: Refrigerant coil in the outdoor-air stream to reject heat during cooling operations and to absorb heat during heating operations. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated throughout the building.  
 B. Outdoor-Air Refrigerant-Coil Fan: The outdoor-air refrigerant-coil fan in RTUs. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated through the system.  
 C. RTU: Rooftop unit. As used in this Section, this abbreviation means packaged, outdoor, central-station air-handling units. This abbreviation is used regardless of whether the unit is mounted on the roof or on a concrete base on ground.  
 D. Supply-Air Fan: The fan providing supply air to conditioned space. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.  
 E. Supply-Air Refrigerant Coil: Refrigerant coil in the supply-air stream to absorb heat (provide cooling) during cooling operations and to reject heat (provide heating) during heating operations. "Supply coil" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.  
 1.3 ACTION SUBMITTALS  
 A. Product Data: Include manufacturer's technical data for each RTU, including rated capacities, dimensions, required clearances, characteristics, furnished specialties, and accessories.  
 B. Shop Drawings: Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.  
 1. Wiring Diagrams: Power, signal, and control wiring.  
 1.4 INFORMATIONAL SUBMITTALS  
 A. Field quality-control test reports.  
 B. Warranty.  
 1.5 CLOSEOUT SUBMITTALS  
 A. Operation and maintenance data.  
 1.6 QUALITY ASSURANCE  
 A. ARI Compliance:  
 1. Comply with ARI 210240 and ARI 340360 for testing and rating energy efficiencies for RTUs.  
 2. Comply with ARI 270 for testing and rating sound performance for RTUs.  
 B. ASHRAE Compliance:  
 1. Comply with ASHRAE 15 for refrigerant system safety.  
 2. Comply with ASHRAE 33 for methods of testing cooling and heating coils.  
 3. Comply with applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Start-up."  
 C. ASHRAE/IESNA 91.1 Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."  
 D. NFPA Compliance: Comply with NFPA 90A and NFPA 90B.  
 E. UL Compliance: Comply with UL 1995.  
 END OF SECTION  
 23016 - Ductwork, Low Pressure, Flexible  
 PART 1 - GENERAL  
 1.1 DESCRIPTION  
 A. Provides where indicated on the drawings and specified herein, factory fabricated and pre-insulated flexible ducts.  
 1.2 QUALITY ASSURANCE  
 A. Flexible ducts, including insulation and sealants, shall conform to the requirements of NFPA 90A and UL Standard 181 for class 1 ducts.  
 B. Performance data shall be based on test performed in accordance with Air Diffusion Council flexible air duct test code FD72.  
 PART 2 - PRODUCTS  
 2.1 LOW PRESSURE FLEXIBLE DUCTWORK  
 A. Low pressure flexible ductwork shall consist of corrosion resistant spring steel helix bonded to a glass reinforced neoprene sleeve insulated with a minimum of 1 inch-thick, 1 pound density fiberglass insulation which is in turn covered with an outer vapor barrier of fiber reinforced foil-core kraft laminate.  
 B. Insulation shall have a thermal conductivity (K) no greater than 0.25 at 75 degrees F.  
 C. Duct for low velocity system connectors shall have a working pressure of not less than 1-1/2 inches of water gage and a maximum operating temperature of not less than 250 degrees F.  
 2.2 DUCT CONNECTIONS  
 A. Where flexible ducts connect to low pressure ducts to form run-outs to individual outlets, plenums, or low pressure terminals, provide factory fabricated fittings complete with manuals and balancing dampers having locking quadrants. Where low pressure ducts are internally insulated the connector shall be furnished with air extension to project through and protect the insulation for connection to equipment. auxiliary sleeves shall be provided to allow at least 2 inches of surface for clamping of flexible ductwork. Sleeves shall be screwed or bolted to equipment lip frame.  
 2.3 CLAMPS  
 A. Provide galvanized spring steel clamps or Panduit straps at connections to duct fittings or devices.  
 2.4 MANUFACTURER  
 A. Flexible ductwork and components shall be as manufactured by general environmental corporation or approved by code.  
 PART 3 - EXECUTION  
 3.1 INSTALLATION  
 A. Install duct connectors to low pressure ducts using manufacturer's template for all holes and secure the connector with sheet metal screws having first applied Foster's 30-02 duct sealant to the adjoining surfaces. Do not pressurize the system for 48 hours.  
 B. Stretch new duct when removing it from cartons where it may have been shipped in a compressed state.  
 C. Use the minimum length of flexible duct required to make the specific connection unless specifically noted otherwise on the drawings. The maximum develop length of flex duct is 4'-0".  
 D. Avoid sharp bends. Use a minimum inside bend radius equal to one (1) times the inside diameter of the duct.  
 E. Support horizontal duct runs as detailed in the construction documents.  
 F. Allow the flexible duct to extend straight away from connectors for a few inches prior to inflating all bends.  
 G. Adhesive and sealants to connection of flexible duct to the rigid duct or terminate as follows:  
 1. Apply Foster's 30-02 sealant to the inside of the flexible duct to a depth of three (3) inches.  
 2. Repair all damage to vapor barrier with Foster's 35-50 reinforced with 4-inch-wide glass fabric and a second coat of Foster's 35-50.  
 END OF SECTION  
 23013 - DIFFUSERS, REGISTERS, AND GRILLES  
 PART 1 - GENERAL  
 1.1 DESCRIPTION  
 A. Air distribution devices shall be provided to deliver the indicated volume of supply air without exceeding the available flow and with NC rating as follows:  
 1. Kitchen & Work Areas: NC-35  
 2. Dining and Customer Lobby Area: NC-30.  
 1.2 SUBMITTALS  
 A. Shop drawings: Indicate locations, spacing air volume, and type of each device.  
 B. Product data: Manufacturers catalog cuts and product description including air quantity, pattern, throw, pressure drop, NC ratings, finish, dimensions, and complete construction details and materials.  
 PART 2 - PRODUCTS  
 2.1 DIFFUSERS, GRILLES, AND REGISTERS  
 A. Diffusers, grilles, and registers shall be from one of the following manufacturers:  
 1. Klueger.  
 2. Kueger.  
 3. Pace.  
 4. Nalor.  
 B. For model numbers and type see air distribution schedule on drawing.  
 C. Diffusers, grilles, and registers shall be of the surface, flush, or in-ry-in type, color corresponding to the ceiling which they are located.  
 D. The finish of the diffusers, grille, or register face panel shall be as noted on plans.  
 PART 3 - EXECUTION  
 3.1 INSTALLATION  
 A. Install where shown on drawings.  
 B. Registers, diffusers, and fittings shall be securely attached to finish surfaces, or structural member behind finish surfaces.  
 C. Lay-in diffusers mounted in acoustical tile ceilings shall be rigidly mounted, above the face panel, to the ceiling suspension system.  
 END OF SECTION  
 23400 - Air Distribution Equipment (Exhaust Fans)  
 PART 1 - GENERAL  
 1.1 CEILING-MOUNTED VENTILATORS  
 A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:  
 1. Greenheck Fan Corporation  
 2. Loren Cook Company  
 3. PennBarry  
 4. Twin City Fan  
 B. Housing: Steel, lined with acoustical insulation.  
 C. Fan Wheel: Centrifugal wheels directly mounted on motor shaft. Fan shrouds, motor, and fan wheel shall be removable for service.  
 D. Grille: Plastic, louvered grille with flange on intake and thumbcrew attachment to fan housing.  
 E. Electrical Requirements: Junction box and electrical connection with ground and reconnected for motor plug-in.  
 F. Accessories (not included for additional information):  
 1. Variable-Speed Controller: Solid-state controller to reduce speed from 100 to less than 50 percent.  
 2. Manual Start Switch: Single-pole rocker switch assembly with cover and pilot light.  
 3. Time-Delay Switch: Assembly with single-pole rocker switch, timer, and cover plate.  
 4. Motion Sensor: Motion detector with adjustable shutoff timer.  
 5. Ceiling Radiation Damper: Fire-rated assembly with ceramic blanket, stainless-steel springs, and fusible link.  
 6. Filter: Washable aluminum to fit between fan and grille.  
 7. Isolation: Rubber-in-shear vibration isolators.  
 8. Manufacturer's standard roof jack or wall cap, and transition fittings.  
 END OF SECTION  
 237413 - PACKAGED, OUTDOOR, CENTRAL-STATION AIR-HANDLING UNITS  
 PART 1 - GENERAL  
 1.1 SUMMARY  
 A. This Section includes packaged, outdoor, central-station air-handling units (rooftop units) with the following components and accessories:  
 1. Direct-expansion cooling.  
 2. Gas furnace.  
 3. Economizer outdoor-air return-air damper section.  
 4. Integral space-temperature controls.  
 5. Roof curb.  
 1.2 DEFINITIONS  
 A. Outdoor-Air Refrigerant Coil: Refrigerant coil in the outdoor-air stream to reject heat during cooling operations and to absorb heat during heating operations. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated throughout the building.  
 B. Outdoor-Air Refrigerant-Coil Fan: The outdoor-air refrigerant-coil fan in RTUs. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated through the system.  
 C. RTU: Rooftop unit. As used in this Section, this abbreviation means packaged, outdoor, central-station air-handling units. This abbreviation is used regardless of whether the unit is mounted on the roof or on a concrete base on ground.  
 D. Supply-Air Fan: The fan providing supply air to conditioned space. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.  
 E. Supply-Air Refrigerant Coil: Refrigerant coil in the supply-air stream to absorb heat (provide cooling) during cooling operations and to reject heat (provide heating) during heating operations. "Supply coil" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.  
 1.3 ACTION SUBMITTALS  
 A. Product Data: Include manufacturer's technical data for each RTU, including rated capacities, dimensions, required clearances, characteristics, furnished specialties, and accessories.  
 B. Shop Drawings: Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.  
 1. Wiring Diagrams: Power, signal, and control wiring.  
 1.4 INFORMATIONAL SUBMITTALS  
 A. Field quality-control test reports.  
 B. Warranty.  
 1.5 CLOSEOUT SUBMITTALS  
 A. Operation and maintenance data.  
 1.6 QUALITY ASSURANCE  
 A. ARI Compliance:  
 1. Comply with ARI 210240 and ARI 340360 for testing and rating energy efficiencies for RTUs.  
 2. Comply with ARI 270 for testing and rating sound performance for RTUs.  
 B. ASHRAE Compliance:  
 1. Comply with ASHRAE 15 for refrigerant system safety.  
 2. Comply with ASHRAE 33 for methods of testing cooling and heating coils.  
 3. Comply with applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Start-up."  
 C. ASHRAE/IESNA 91.1 Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."  
 D. NFPA Compliance: Comply with NFPA 90A and NFPA 90B.  
 E. UL Compliance: Comply with UL 1995.  
 END OF SECTION  
 23016 - Ductwork, Low Pressure, Flexible  
 PART 1 - GENERAL  
 1.1 DESCRIPTION  
 A. Provides where indicated on the drawings and specified herein, factory fabricated and pre-insulated flexible ducts.  
 1.2 QUALITY ASSURANCE  
 A. Flexible ducts, including insulation and sealants, shall conform to the requirements of NFPA 90A and UL Standard 181 for class 1 ducts.  
 B. Performance data shall be based on test performed in accordance with Air Diffusion Council flexible air duct test code FD72.  
 PART 2 - PRODUCTS  
 2.1 LOW PRESSURE FLEXIBLE DUCTWORK  
 A. Low pressure flexible ductwork shall consist of corrosion resistant spring steel helix bonded to a glass reinforced neoprene sleeve insulated with a minimum of 1 inch-thick, 1 pound density fiberglass insulation which is in turn covered with an outer vapor barrier of fiber reinforced foil-core kraft laminate.  
 B. Insulation shall have a thermal conductivity (K) no greater than 0.25 at 75 degrees F.  
 C. Duct for low velocity system connectors shall have a working pressure of not less than 1-1/2 inches of water gage and a maximum operating temperature of not less than 250 degrees F.  
 2.2 DUCT CONNECTIONS  
 A. Where flexible ducts connect to low pressure ducts to form run-outs to individual outlets, plenums, or low pressure terminals, provide factory fabricated fittings complete with manuals and balancing dampers having locking quadrants. Where low pressure ducts are internally insulated the connector shall be furnished with air extension to project through and protect the insulation for connection to equipment. auxiliary sleeves shall be provided to allow at least 2 inches of surface for clamping of flexible ductwork. Sleeves shall be screwed or bolted to equipment lip frame.  
 2.3 CLAMPS  
 A. Provide galvanized spring steel clamps or Panduit straps at connections to duct fittings or devices.  
 2.4 MANUFACTURER  
 A. Flexible ductwork and components shall be as manufactured by general environmental corporation or approved by code.  
 PART 3 - EXECUTION  
 3.1 INSTALLATION  
 A. Install duct connectors to low pressure ducts using manufacturer's template for all holes and secure the connector with sheet metal screws having first applied Foster's 30-02 duct sealant to the adjoining surfaces. Do not pressurize the system for 48 hours.  
 B. Stretch new duct when removing it from cartons where it may have been shipped in a compressed state.  
 C. Use the minimum length of flexible duct required to make the specific connection unless specifically noted otherwise on the drawings. The maximum develop length of flex duct is 4'-0".  
 D. Avoid sharp bends. Use a minimum inside bend radius equal to one (1) times the inside diameter of the duct.  
 E. Support horizontal duct runs as detailed in the construction documents.  
 F. Allow the flexible duct to extend straight away from connectors for a few inches prior to inflating all bends.  
 G. Adhesive and sealants to connection of flexible duct to the rigid duct or terminate as follows:  
 1. Apply Foster's 30-02 sealant to the inside of the flexible duct to a depth of three (3) inches.  
 2. Repair all damage to vapor barrier with Foster's 35-50 reinforced with 4-inch-wide glass fabric and a second coat of Foster's 35-50.  
 END OF SECTION  
 23013 - DIFFUSERS, REGISTERS, AND GRILLES  
 PART 1 - GENERAL  
 1.1 DESCRIPTION  
 A. Air distribution devices shall be provided to deliver the indicated volume of supply air without exceeding the available flow and with NC rating as follows:  
 1. Kitchen & Work Areas: NC-35  
 2. Dining and Customer Lobby Area: NC-30.  
 1.2 SUBMITTALS  
 A. Shop drawings: Indicate locations, spacing air volume, and type of each device.  
 B. Product data: Manufacturers catalog cuts and product description including air quantity, pattern, throw, pressure drop, NC ratings, finish, dimensions, and complete construction details and materials.  
 PART 2 - PRODUCTS  
 2.1 DIFFUSERS, GRILLES, AND REGISTERS  
 A. Diffusers, grilles, and registers shall be from one of the following manufacturers:  
 1. Klueger.  
 2. Kueger.  
 3. Pace.  
 4. Nalor.  
 B. For model numbers and type see air distribution schedule on drawing.  
 C. Diffusers, grilles, and registers shall be of the surface, flush, or in-ry-in type, color corresponding to the ceiling which they are located.  
 D. The finish of the diffusers, grille, or register face panel shall be as noted on plans.  
 PART 3 - EXECUTION  
 3.1 INSTALLATION  
 A. Install where shown on drawings.  
 B. Registers, diffusers, and fittings shall be securely attached to finish surfaces, or structural member behind finish surfaces.  
 C. Lay-in diffusers mounted in acoustical tile ceilings shall be rigidly mounted, above the face panel, to the ceiling suspension system.  
 END OF SECTION  
 23400 - Air Distribution Equipment (Exhaust Fans)  
 PART 1 - GENERAL  
 1.1 CEILING-MOUNTED VENTILATORS  
 A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:  
 1. Greenheck Fan Corporation  
 2. Loren Cook Company  
 3. PennBarry  
 4. Twin City Fan  
 B. Housing: Steel, lined with acoustical insulation.  
 C. Fan Wheel: Centrifugal wheels directly mounted on motor shaft. Fan shrouds, motor, and fan wheel shall be removable for service.  
 D. Grille: Plastic, louvered grille with flange on intake and thumbcrew attachment to fan housing.  
 E. Electrical Requirements: Junction box and electrical connection with ground and reconnected for motor plug-in.  
 F. Accessories (not included for additional information):  
 1. Variable-Speed Controller: Solid-state controller to reduce speed from 100 to less than 50 percent.  
 2. Manual Start Switch: Single-pole rocker switch assembly with cover and pilot light.  
 3. Time-Delay Switch: Assembly with single-pole rocker switch, timer, and cover plate.  
 4. Motion Sensor: Motion detector with adjustable shutoff timer.  
 5. Ceiling Radiation Damper: Fire-rated assembly with ceramic blanket, stainless-steel springs, and fusible link.  
 6. Filter: Washable aluminum to fit between fan and grille.  
 7. Isolation: Rubber-in-shear vibration isolators.  
 8. Manufacturer's standard roof jack or wall cap, and transition fittings.  
 END OF SECTION  
 237413 - PACKAGED, OUTDOOR, CENTRAL-STATION AIR-HANDLING UNITS  
 PART 1 - GENERAL  
 1.1 SUMMARY  
 A. This Section includes packaged, outdoor, central-station air-handling units (rooftop units) with the following components and accessories:  
 1. Direct-expansion cooling.  
 2. Gas furnace.  
 3. Economizer outdoor-air return-air damper section.  
 4. Integral space-temperature controls.  
 5. Roof curb.  
 1.2 DEFINITIONS  
 A. Outdoor-Air Refrigerant Coil: Refrigerant coil in the outdoor-air stream to reject heat during cooling operations and to absorb heat during heating operations. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated throughout the building.  
 B. Outdoor-Air Refrigerant-Coil Fan: The outdoor-air refrigerant-coil fan in RTUs. "Outdoor air" is defined as the air outside the building or taken from outdoors and not previously circulated through the system.  
 C. RTU: Rooftop unit. As used in this Section, this abbreviation means packaged, outdoor, central-station air-handling units. This abbreviation is used regardless of whether the unit is mounted on the roof or on a concrete base on ground.  
 D. Supply-Air Fan: The fan providing supply air to conditioned space. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.  
 E. Supply-Air Refrigerant Coil: Refrigerant coil in the supply-air stream to absorb heat (provide cooling) during cooling operations and to reject heat (provide heating) during heating operations. "Supply coil" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.  
 1.3 ACTION SUBMITTALS  
 A. Product Data: Include manufacturer's technical data for each RTU, including rated capacities, dimensions, required clearances, characteristics, furnished specialties, and accessories.  
 B. Shop Drawings: Indicate dimensions, weights, loads, required clearances, method of field assembly