

WALK-IN COOLER/FREEZER UNITS			
EQUIPMENT	MANUFACTURER	MODEL	NOTES
COOLER EVAPORATOR	THERMALRITE	RL6A SERIES	A
COOLER CONDENSER	THERMALRITE	RFO SERIES	A
FREEZER EVAPORATOR	THERMALRITE	RL6E SERIES	A
FREEZER CONDENSER	THERMALRITE	RFO SERIES	A

NOTES:
A. EQUIPMENT BY OWNER'S VENDOR. INFORMATION PROVIDED FOR REFERENCE ONLY.

- MECHANICAL PLAN NOTES:**
- PROVIDE CONCENTRIC VENT MODEL NUMBER PVC-3CT.
 - MAINTAIN ALL OUTSIDE AIR INTAKES A MINIMUM OF 10'-0" RADIUS FROM EXHAUST, TYPICAL.
 - CONTRACTOR SHALL VERIFY WITH EQUIPMENT SUPPLIER EXACT ROUTING AND SIZE OF INSULATED REFRIGERANT PIPING. SINGLE LINESHET SHOWN FOR CLARITY. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
 - TURN DOWN 6"Ø INTAKE AND END OPEN OVER ROOF (MIN. 24") WITH INSECT SCREEN.
 - CONTRACTOR SHALL COORDINATE WITH NATIONAL TAB TO PROVIDE UV-PHI INDOOR AIR PURIFICATION SYSTEM, MODEL PHI-PKG-24V. INSTALL IN UNIT BLOWER COMPARTMENT PER MANUFACTURER'S INSTRUCTIONS.
 - AREA RESERVED FOR REFRIGERATION CONDENSER(S) PROVIDED BY KITCHEN EQUIPMENT CONTRACTOR. COORDINATE EQUIPMENT LOCATION AND CONDENSER INSTALLATION WITH KITCHEN EQUIPMENT CONTRACTOR.
 - REFERENCE PLUMBING DRAWINGS FOR CONDENSATE DRAIN ROUTING AND TERMINATION REQUIREMENTS.
 - FAN DISCHARGE TO BE LOCATED A MINIMUM OF 3'-0" ABOVE ROOF SURFACE.

Bergmeyer

BOSS
611 Shilpiper St.
Boston, MA 02210
617.542.1025

LA
800 South Figueroa St.
Los Angeles, CA 90017
213.337.1090

CO
875 N. High St.
Columbus, OH 43215
980.900.8887

www.bergmeyer.com


CONSULTANTS:

HENDERSON ENGINEERS
8345 LENEKA DRIVE, SUITE 300
LENEKA, KS 66214
TEL 913.742.5000 FAX 913.742.5001
WWW.HENDERSONENGINEERS.COM

2350004653
AZ. CORPORATE NO: 10470-0
EXPIRES 6/30/2025

SEAL SIGNATURE:

EXPIRES ON: 09/30/2026



02/03/2025

NO.	BY	DATE	DESCRIPTION
D	HEI	2025-01-29	ADDENDUM D
B	HEI	2024-09-12	ADDENDUM B
A	HEI	2024-06-28	ADDENDUM A
HEI		2024-04-29	PERMIT/BID SET

SHAKE SHACK

SHAKE SHACK AVONDALE


9778 W MCDOWELL RD
PHOENIX, AZ 85037
SHACK #1421

ADDENDUM C

MECHANICAL ROOF PLAN

DRAWN BY: Author
CHECKED BY: Checker
JOB NO: 2350004653

M150




MECHANICAL ROOF PLAN
1/4" = 1'-0"

NATHAN T. LOVE
20250221.11:01 PM
Autodesk Docu/20250210.00 - Shake Shack Avondale M150/SHACK 1421/Avondale MZ/MEPR/02.rvt

NO.	BY	DATE	DESCRIPTION
B	HEI	2024-09-12	ADDENDUM B
A	HEI	2024-06-28	ADDENDUM A
HEI		2024-04-29	PERMIT/IBID SET

SHAKE SHACK	
SHAKE SHACK AVONDALE	
9778 W MCDOWELL RD PHOENIX, AZ 85037 SHACK #1421	
ADDENDUM C	
MECHANICAL DETAILS	

DRAWN BY:	Author
CHECKED BY:	Checker
JOB NO:	235004653
M501	



Division 23: TABLE OF CONTENTS
GENERAL MECHANICAL REQUIREMENTS
1. GENERAL INSTRUCTIONS
A. GENERAL REQUIREMENTS
B. DEFINITIONS
C. PRE-BID SITE VISIT
D. MATERIAL AND WORKMANSHIP
E. MANUFACTURERS
F. COORDINATION
G. ORDINANCES AND CODES
H. PROTECTION OF EQUIPMENT AND MATERIALS
I. SUBSTITUTIONS
J. SUBMITTALS
K. ELECTRONIC DRAWINGS FILES
L. RECORD DRAWINGS (AS-BUILT DRAWINGS)
M. OPERATION AND MAINTENANCE INSTRUCTIONS
N. SPARE PARTS
O. TRAINING
P. WARRANTIES

Division 23: HEATING, VENTILATING, AND AIR CONDITIONING
1. GENERAL INSTRUCTIONS
A. GENERAL REQUIREMENTS
All requirements under Division 01 and the general and supplementary conditions of these specifications apply to this section and division.
The specifications and drawings for the project are complementary, and any portion of work described in one shall be provided as if described in both.
Drawings are graphic representations of the work upon which the contract is based. They show the materials and their relationship to one another, including sizes, shapes, locations, and connections.
Furnish: "to supply and deliver to the project site, ready for unloading, unpacking, assembly, installation and similar operations."

Unless stated otherwise in writing to the Engineer by the Contractor, Contractor warrants to the Engineer, Architect, and Owner the following:
1. Proposed substitution has been fully investigated and determined to meet or exceed the specified Work in all respects unless stated otherwise in the substitution request.
2. Proposed substitution is consistent with the Contract Documents and will produce indicated results, including functional clearances, maintenance service, and sourcing of replacement parts.
3. Proposed substitution has received necessary approvals of authorities having jurisdiction.
4. Same warranty will be furnished for proposed substitution as for specified Work.
5. If accepted substitution fails to perform as required, Contractor shall replace substitute material or system with that originally specified and bear cost of replacement.
6. Coordination, installation and changes in the Work as necessary for accepted substitution will be complete in all respects.

E. CUTTING AND PATCHING
Conform to the requirements in Division 01. Cut walls, floors, ceilings, and other portions of the facility as required to install work under this division.
F. ROUGH-IN
Coordinate without delay all roughing-in with other divisions. Conceal piping, conduit, and rough-in except in unfinished areas and where otherwise shown.
G. STRUCTURAL SUPPORT SYSTEMS
Structural steel used for support of equipment, ductwork and piping shall be new, clean, and conform to ASTM Designation A-36.
H. PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS AND CURBS
Provide prefabricated equipment support rails and roof curbs manufactured by AES Industries, Custom Curb, Inc., Pate Company, Thybar or approved equal.
I. ACCESS PANELS AND DOORS
Refer to Architectural documents for specification of access panels and doors.
J. PENETRATIONS
Provide sleeves for pipes passing through above grade concrete or masonry walls, concrete floor or roof slabs.
K. ELECTRONIC DRAWING FILES
In preparation of shop drawings or record drawings, Contractor may, at his option, obtain electronic drawing files in AutoCAD or DXF format on CD-ROM disk, DVD or flash drive or direct download, as desired, from the Engineer for a shipping and handling fee of \$200 for a drawing set up to 12 sheets and \$15 per sheet for each additional sheet.
L. RECORD DRAWINGS (AS-BUILT DRAWINGS)
During progress of the work in this division, Contractor shall maintain an accurate record of all changes made during the installation of the system.
M. OPERATION AND MAINTENANCE INSTRUCTIONS
During the course of construction, collect and compile a complete brochure of equipment furnished and installed on this project.
N. SPARE PARTS
Furnish to Owner, with receipt, the following spare parts for the equipment furnished for this project:
1. One set of spare filters of each type required for each unit.
2. Furnish one complete set of belts for each fan.
3. Furnish three operating keys for each type of air outlet and inlet that require them.
O. TRAINING
At a time mutually agreed upon between the Owner and Contractor, provide the services of a factory trained and authorized representative to train Owner's designated personnel on the operation and maintenance of the equipment provided for this project.
P. WARRANTIES
Warrant each system and each element thereof against all defects due to faulty workmanship, design, or material for a period of 12 months from date of Substantial Completion, unless specific items are noted to carry a longer warranty in the construction documents or manufacturer's standard warranty exceeds 12 months.

Bergmeyer CONSULTANTS
HENDERSON ENGINEERS
SEAL SIGNATURE:
EXPIRES ON: 09/30/2026
SHAKE SHACK AVONDALE
9778 W MCDOWELL RD PHOENIX, AZ 85037
MECHANICAL SPECIFICATIONS
DRAWN BY: Nathan T. Love
CHECKED BY: Nathan T. Love
JOB NO: 235004653
M590

Install wiring parallel to building lines wherever possible. Conceal all control wiring in finished rooms. Do not install Class 2 wiring in raceways containing Class 1 wiring. Boxes and panels containing high voltage wiring and equipment may not be used for low-voltage wiring except for the purpose of interlacing the two wires (e.g., relays and transformers). All wire-to-device and wire-to-wire connections shall be made at a terminal block or terminal strip. All runs of communication wiring shall be unsheathed length when that length is concealed in raceways. Verify the integrity of the entire network following the cable installation. Use appropriate test measures for each particular cable. Label all wiring and cabling at each end within 2 inches of termination with the controller termination number. Label control devices used in the system with permanent labels using the identifiers that match the record documents.

O. EQUIPMENT FURNISHED BY OTHERS

Provide necessary equipment and accessories that are not provided by the equipment supplier or Owner to complete installation of equipment furnished by others in locations as indicated on the drawings, specified herein, or both. Equipment and accessories not provided by the equipment supplier may include, but not be limited to, flues, vents, intakes, associated roof jacks and caps to outdoors, dampers, in-line fans, roof fans, and control interlocks, etc. as required for proper operation of the complete system in accordance with the manufacturer's instructions.

Contractor shall be responsible for correct rough-in dimensions and shall verify them with Architect and/or equipment supplier prior to gasket installations.

P. SYSTEM TESTING, ADJUSTING, AND BALANCING

Upon completion of each phase of the installation, test each system in conformance with local code requirements and as noted below. Furnish labor and equipment required to test each system installed under this contract. Assume all costs involved in making the tests and repairing and/or replacing any damages resulting therefrom.

The final test and balance of the building HVAC systems shall be completed by National TAB (no exceptions) and contracted by the General Contractor. The representative from National TAB shall be certified by the National Environmental Balancing Bureau (NEBB), Associated Air Balance Council (AABC), or Testing, Adjusting and Balancing Bureau (TAB). TAB shall be performed in accordance with the most current edition of the certified agencies procedural standard for testing, adjusting and balancing and shall comply with the strictest interpretation of that standard for execution and reporting of all TAB work.

Work shall include but not be limited to: Perform test readings on fans, units, coils, pumps, etc. and adjust equipment to deliver specified amounts of air. Prepare testing and balancing report log showing air supply quantities, air entering and leaving temperatures and pressures at design flow, fan and unit test readings, motor voltage and amp draws, etc., and submit six copies of the final completion of data to the Architect for evaluation and approval before final inspection of the project. Balance air systems to within plus or minus 10 percent for terminal devices and branch lines and plus or minus 5 percent for main ducts and air handling equipment of the amount of air shown on the drawings. TAB Contractor shall record space temperatures and make adjustments in airflow to each diffuser to obtain uniform temperatures (no greater than +/- 3 F) in spaces. Document temperatures and adjustments in tab report. Adjust equipment to operate as intended by the specification. TAB report shall include a report summary/remarks section in accordance with the procedural standard that provides both system set-up and a summary of deficiencies as defined by the procedural standard.

TAB Contractor shall be responsible to calibrate, set, and adjust automatic temperature control sensors, actuators and control devices. Check proper sequencing of interlock systems and operation of safety controls, adjust thermostats, and control setpoints, limits and time based adjustment to operate in accordance with the performance requirements of the Construction Documents. Adjust pumps, fans, etc. for proper and efficient operation. Certify to Architect that adjustments have been made and that system is operating satisfactorily. Calibrate, set, and adjust automatic temperature controls. Check proper sequencing of interlock systems, and operation of safety controls.

Division 23 contractor shall align bearings and replace bearings that have dirt or foreign material in them with new bearings without additional cost to the Owner.

Q. VIBRATION ISOLATION

Provide vibration isolation equipment and materials by a single manufacturer. If type and deflection for specific equipment is not specified within the contract documents, reference ASHRAE Handbook "HVAC Applications" or provide per manufacturer's recommendations. Approved manufacturers include Caldyn, Kinetics Noise Control, Mason Industries, Inc., Vibration Eliminator Co., Inc., Vibration Mounting and Controls, or Vibro-Acoustics, provided their systems are in compliance with the specified design and performance requirements.

General Requirements: Select vibration isolators by the weight distribution to produce uniform deflection. Vibration isolators shall have either linear deflection or calibration markings so that, after adjustment, the static deflection can be verified, thus determining that the load is within the proper range of the isolator. Isolators shall operate in the linear portion of their load versus deflection curves. Spring isolators shall have 50 percent excess capacity without becoming coil bound. Coil vibration isolators with factory-applied coatings are exposed to weather and other corrosive environments and shall be protected with factory-applied corrosion resistance protection. Install and adjust vibration isolators in accordance with manufacturers written instructions.

Pipe connections: Provide flexible connectors for piping system connections on equipment side of shutoff valves for all pumps, mechanical equipment supported or suspended by spring isolators, and where indicated on drawings. Flexible fabric piping connectors from stainless steel or rubber materials are suitable for system fluid. Flexible piping connectors shall be bellows, spherical or braided hose type as recommended by the manufacturer for the application.

Isolator Types:

- 1. Type WP (Waffle Pads): Provide 5/16 inch thick neoprene pads ribbed or waffled on both sides. Manufacture pads with bridge bearing quality neoprene and select for a minimum diameter of 50 and designed for 15 percent strain, with a static deflection of 0.05 inches. Provide steel plates where required between the equipment and the neoprene pad to provide selected deflection. If the isolator is bolted to the structure, install a neoprene mounting sleeve under the bolt head between the steel washer and the base plate to prevent metal to metal contact. Provide Mason Industries Type W or equal.
2. Type SPNH (Spring and Neoprene Hangers): Provide a steel hanger box containing a laterally stable, double-deflecting neoprene isolator in series with a steel spring. Design springs so the ratio of the horizontal to vertical spring constant is between one and two. The spring diameter shall be not less than 80 percent of the compressed height of the spring at rated load. Load rated springs shall operate within the linear portion of their load versus deflection curve over a deflection range of not less than 50 percent above static deflection. Spring diameter and hanger box hole size shall be large enough to permit the hanger rod to swing through a 30 degree arc. Include the following details in the project jurisdiction: Where not already determined within the project, specify the isolating function. The neoprene element shall have a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of not less than 0.4 inches. Unless otherwise specified, the static deflection of SPNH hangers shall be 2 inches. Provide SPNH hangers with 1 inch diameter cast brass or bronze water source heat pumps and fan-powered VAV terminal units. When installed, do not cock the spring element and do not allow the hanger box to rotate through a full 360 degree arc without encountering obstructions. Provide Mason Industries Type 30N or equal.
3. Type NR (Neoprene Bushing): Provide neoprene, rubber-in-shear bushings for lightweight (less than 100 pounds), suspended equipment supported from structure with all thread rod and angle iron or Unistrut. Select for a minimum diameter of 50 and designed for 15 percent strain, with a static deflection of 0.15 inches. Provide Mason Industries Type HMB or equal.

R. SEISMIC CONTROLS FOR MEFF SYSTEMS

Seismic Protection Criteria: Risk/Occupancy Category: II, III or IIIIV; Site Seismicity Category: Seismic Engineer to Determine; Seismic Design Category: Contractor's Seismic Engineer to Determine; Component Importance Factor: Determined from ASCE 7, most recent version.

The Contractor shall be responsible for determining the requirements for seismic bracing of mechanical, electrical, and plumbing systems. Seismic protection criteria used to determine seismic bracing requirements of all mechanical, electrical, and plumbing systems shall be determined by the applicable code adopted in the project jurisdiction. Where not already determined within the project jurisdiction, the Contractor shall be responsible for contracting a licensed professional engineer to establish building site class, seismic design category, seismic zone, or any other criteria necessary to determine the requirements for seismic bracing on mechanical, electrical, and/or plumbing systems.

Seismic bracing of fire protection systems shall be installed in strict accordance with the provisions of NFPA 13 (2010 or later edition).

The Contractor shall determine the type and location of seismic bracing required for the mechanical, electrical, and plumbing elements shown on the drawings based on the established seismic criteria, the size and weight of the supported element, and the distance from structure to supported element.

The Contractor shall submit the following shop drawing information to the AHJ and the Engineer for review and approval:

- 1. Seismic analysis listing all applicable seismic design criteria.
2. Descriptive catalog data of seismic bracing materials.
3. Shop drawings showing bracing type and location.
4. Installation details of all bracing used.
5. Calculations showing that the seismic restraints meet the seismic requirements.
Shop drawings and calculations shall be signed and sealed by a registered professional engineer, licensed in the state of the project and employed by the manufacturer of the seismic bracing products. Calculations shall include dead loads, static seismic loads, and capacity of materials utilized for connections.

Seismic bracing, restraints, isolators, and isolation materials shall be of the same manufacturer and shall be certified by the manufacturer. Approved manufacturers are: Amber/Booth Company, Inc., B-Line/Tolco, ISAT, Kinetics Noise Control, Inc., Loos & Company, Inc., Mason Industries, Inc., Uni-strut, or Vibro-Acoustics. Each device shall have a pre-approval number from California CSFHD or other recognized government agency showing maximum restraint ratings.

Seismic bracing measures to be applied to mechanical, electrical, and plumbing equipment/systems shall be installed in strict accordance with all applicable local, state, and/or federal codes as well as manufacturer's requirements. The most stringent criteria shall apply. All anchor connections to structure for support of mechanical and electrical equipment, regardless of the size for seismic restraints, shall be shown on shop drawings.

S. AIR FILTERS

Provide AAF/Flanders Perfect Pleat HC M8, Camfil Farr 3000, pleated, throwaway type filters, minimum MERV 8, or similar as manufactured by Air Filter, Inc., Bioclimatic, Columbus, Koch, or approved equal, unless otherwise indicated.

Temporary filters used to protect openings in ductwork and inside equipment when permanent HVAC equipment is used during the construction period shall be pleated, throwaway type filters, minimum MERV 8.

T. REFRIGERANT AND OIL

Provide full refrigerant and oil charge in new air conditioning refrigeration systems, and maintain it for full term of the guarantee.

U. IDENTIFICATION

Provide manufacturer's standard pre-printed, semi-rigid snap-on or permanent adhesive, pressure-sensitive vinyl pipe markers. Color code pipe markers to comply with ANSI A13.1.

Install pipe markers on each HVAC piping system and include arrows to show normal direction of flow.

Locate pipe markers and color bands wherever piping is exposed to view in occupied spaces, machine rooms, accessible maintenance spaces (shafts, tunnels, plenums), and exterior non-concealed locations. Provide plastic laminate or brass valve tag on every valve, lock and control device in each HVAC piping system; exclude check valves, valves within factory-fabricated equipment units, and shut-off valves at HVAC terminal devices and similar rough-in connections of end-use fixtures and units.

Provide manufacturer's standard laminated plastic, color coded equipment markers. Conform to the following color code: Green for Cooling; Yellow for Heating; Yellow/Green for combined Cooling and Heating; Brown for Energy Recirculation; Blue for other equipment types. Conform to ANSI A13.1 for Hazardous Equipment.

Provide stenciled signs for equipment identification at Contractor's option or where distance of required identification requires lettering larger than 1 inch height. Stencil paint shall be exterior type, oil-based, alkylid enamel, minimum 1-1/4 inch height or greater as required for long distance identification, white or black color for best contrast.

Provide duct markers or provide stenciled signs and arrows indicating ductwork service and flow direction in black or white lettering for best contrast with duct or insulation color. Locate markers maximum 50 feet along each duct side and within 5 feet of all control and balancing dampers or branch ducts more than 25 feet length and within 5 feet on each side of wall, floor, and ceiling penetrations. Provide additional markers in congested areas or at multiple duct runs as required for clarity.

3. DUCT INSULATION, DUCTWORK, ACCESSORIES, FLUES AND FANS

A. DUCT INSULATION

Provide fiberglass duct liner with fibers firmly bonded together with a thermosetting resin. Liner surface shall serve as a barrier against infiltration of dust and dirt, shall meet ASTM C1338 for fungi resistance, and shall be cleanable using duct cleaning methods and procedures. Provide UL 1738 listed plastic flue gas vents, with positive or negative flue pressures complying with NFPA 211 and suitable for condensing gas appliances. Provide PVC system by IPEX "System 1738", or Polypropylene system by Centromtherm "Innoflu" or equal by Nova Flex Group "Z-DENS."

Vents and combustion air ducts for condensing type appliances shall be Schedule 40 PVC pipe and socket fittings meeting ASTM D2855 and UL 1738, manufactured by IPEX. Use solvent cement meeting ASTM D2564 and make joints in accordance with ASTM D2855.

Where plastic gas vents are installed in a return air plenum, wrap the vent with fire rated plenum insulation. Reference Article "Plenum Insulation" for plenum-rated fire wrap. Coordinate vent material compatibility with the appliance manufacturer's installation instructions prior to purchasing and installation.

E. AIR DEVICES

Provide air devices as scheduled on drawings, manufactured by Carnes, Krueger, Metallaire, Nalor Industries, Price, Tilus, or Tuttle & Bailey. Select air devices to limit room noise level to no higher than NC-30 unless otherwise shown. Provide with a plastic gasket to make an airtight seal against the mounting surface. Coordinate final location, frame, and mounting type of air devices with Architectural reflected ceiling plans.

Submit complete shop drawings including information on noise level, pressure drop, throw, CFM for each air device, styles, borders, etc. Clearly mark with specified equipment number. Submit samples of each air device as required by the Engineer.

Provide wall return air grilles and exhaust air registers with horizontal 35 or 45 degree angle vision-proof bars. Provide concealed fasteners for wall mounted registers and grilles. Provide floor supply air registers of aluminum heavy duty type with 0 degree deflection. Provide remote dampers for supply air registers and exhaust air registers unless indicated otherwise.

Provide ceiling mounted air devices of lay-in or surface mounted type as required to be compatible with ceiling construction. Provide ceiling diffusers and grilles with finished finish unless noted otherwise.

Provide linear slot diffusers of standard one-piece lengths up to 6-foot and furnish in multiple sections greater than 6-foot. Join multiple sections together end-to-end with alignment pins to form a continuous slot appearance. For installations in a hard ceiling, install diffuser per manufacturers installation instructions prior to installation of drywall. Contractor shall use manufacturer's hard ceiling clips for mounting to ceiling framing. Screws through face of linear slot diffuser are not acceptable. Provide alignment components by the manufacturer. Provide plenums by the slot diffuser manufacturer. Plenums shall be internally insulated by the manufacturer with minimum 1/4 inch thick fiberglass insulation.

Provide linear slot diffusers of standard one-piece lengths up to 6-foot and furnish in multiple sections greater than 6-foot. Join multiple sections together end-to-end with alignment pins to form a continuous slot appearance. For installations in a hard ceiling, install diffuser per manufacturers installation instructions prior to installation of drywall. Contractor shall use manufacturer's hard ceiling clips for mounting to ceiling framing. Screws through face of linear slot diffuser are not acceptable. Provide alignment components by the manufacturer. Provide plenums by the slot diffuser manufacturer. Plenums shall be internally insulated by the manufacturer with minimum 1/4 inch thick fiberglass insulation.

F. CONTROL DAMPERS

Provide factory fabricated, parallel blade control dampers sized as shown on the drawings and as specified. Individual damper sections shall not be larger than 48 inches x 60 inches with maximum blade width of 6 inches. Frame construction shall be minimum 16 gauge galvanized steel for rectangular dampers, 20 gauge for round, 1/8 inch thick for aluminum, with flanges for duct mounting. Provide weather resistant seals, mechanically attached and field replaceable. Provide a minimum of one damper actuator per section. Test damper performance in accordance with AMCA 500-D.

Provide modulating dampers with linear flow characteristics. Size modulating dampers based on the smaller of 1,500 FPM through the damper or full open air pressure drop of 0.1 inches W.C. Size two-position dampers full duct size and select to minimize pressure drop.

Motorized dampers used for ventilation air intake, exhaust air, or relief air shall have leakage rates not to exceed 4.0 CFM/square foot in full closed position at 1 inch W.G. pressure differential across the damper.

Provide dampers as manufactured by Greenheck, CESCO, Pottoff, Nalor, or Ruskin. Reference manufacturer with model number for outside air dampers is Ruskin CD-50 constructed of aluminum, and all other applications is Ruskin CD-35 constructed of galvanized steel.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee tight close-off of dampers against system pressure encountered. Each operator shall be provided with spring-return for normally closed or normally open position for the damper. Provide a power source for the damper operator. Damper operators shall be provided by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

G. LOUVERS, PLENUMS, SCREENS

Provide intake and exhaust air louvers by Ruskin model ELF37X or equal, American Warning & Ventilation, Cesco, Greenheck, Industrial Louvers or Louvers & Dampers as scheduled on the drawings. Coordinate exact size and location with architectural drawings. Louvers shall be stationary, with mill finish. Louvers shall have extruded aluminum blades, 0.800 inch wall thickness, 45 degree blade angle. Blades on 5 inch centers; frame shall be extruded aluminum, 0.080 inch wall thickness; with expanded flattened aluminum birdscreen. Provide louvers with a minimum free area of 45 percent, with a maximum air pressure drop of 0.1 inch at scheduled airflow.

Construct plenums with galvanized steel framing members and galvanized sheet metal, braced with galvanized angles. Gauges and bracing shall conform to SMACNA recommendations for ductwork of like size. Where access doors are shown, provide hinged doors with #202 Ventlok latch. Make watertight connections to louvers, sloping bottom of plenum to drain water to weepholes in bottom of louver.

Provide screens on louvers, ducts, hoods, fans, and openings to the outdoors as scheduled and/or noted on the drawings. Insect screens shall be 0.012-inch thickness, 14 inch mesh, aluminum wire. Bird screens shall be 0.041-inch, 102 inch mesh galvanized steel wire. Provide motorized control dampers or backdraft dampers where shown on the drawings.

Wind Driven Rain Performance: Louvers shall comply with ANSIA/AMA 500L for wind driven rain performance. Louvers shall have not less than 99 percent effectiveness when subjected to wind velocities of 29 and 50 mph with rainfall rates of 3 in/hr and 8 in/hr respectively and a core intake velocity not less than what is scheduled on the plans.

Windborne-Debris Impact Resistance: Louvers located within 30 feet of grade shall comply with AMCA 540.

H. EXHAUST AIR SYSTEMS

Provide roof mounted exhaust fans as scheduled on the drawings, or equal ACME, Carnes, Cook, Greenheck, Pembroy, or Twin City Fans complete with aluminum housing, aluminum centrifugal wheel, motor with integral thermal overload protection, disconnect switch mounted inside the housing, birdscreen, backdraft damper, and pre-fabricated roof curb. Three phase fans shall be furnished with magnetic starters with push button station.

I. KITCHEN EXHAUST AIR SYSTEMS

Install kitchen grease exhaust package furnished by the owner. System includes kitchen hood, grease exhaust fan/plenum/control unit, filtered makeup air unit and a mechanical or electrical gas shutoff valve provided with the kitchen exhaust system to shutoff fuel or power source to cooking equipment upon detection of fire. Valve shall have a clearly marked open/closed indicator.

Provide ducts connecting Type 1 exhaust hoods to exhaust fans made of #16 gauge black iron with continuously welded joints and clean-out doors. Provide transition at connection to fan with opening size equal to or greater than the venturi opening of the fan inlet. Provide gasket at flanged connection to fan rated for 1500 degrees Fahrenheit and grease applications. Enclose duct in fireproof enclosure per locally adopted mechanical code or, if approved by local code official, in fire rated wrap insulation. Insulation shall be minimum two-hour rated duct wrap insulation for Type 1 hood grease exhaust duct applications and shall conform to ASTM E2336 where required to comply with IMC. Insulation shall be flexible wrap enclosure rated for minimum 2000 degrees Fahrenheit and for zero clearance to combustibles. Insulation shall be non-mineral wool, passive, low bio-persistent fiber totally encapsulated on all sides with aluminum foil. Insulation shall be as manufactured by Certainteed, Thermal Ceramics, Unifrax or 3M. Exhaust duct back towards hood at minimum of 1/4 inch per linear foot. At Contractor's option, a UL listed concrete ductwork package that complies with UL 1878 standard for grease ducts may be used in lieu of the welded black iron duct for connecting hood to exhaust fan. Ductwork package shall be as manufactured by Meta-Fab, Schebler, Sekirk, or approved equal. Provide manufacturers UL listing number and verification certificate as a part of the shop drawing submittal. Install duct package in strict conformance with manufacturer's instructions and recommendations.

All portions of grease duct systems shall be tested for leakage in accordance with the "Grease Duct Test" paragraph of the IMC. Leakage tests shall be by water leakage type or equivalent test methods as approved by the local code official to determine that all joints are airtight tight. Water leakage test shall be performed by Environmental Corporation of America or owner approved testing contractor. Tests shall be performed in the presence of the local code official. Any joints found defective shall be repaired and retested until satisfactory results are obtained. The contractor shall submit a copy of the grease duct leakage test report to the architect/engineer complete with the approval signature of the local code official.

4. HVAC EQUIPMENT

A. ROOFTOP UNITS (GAS FIRED HEAT) 3-25 TONS

Install electrical cooling, gas heating rooftop units as scheduled on the drawings furnished by owner, manufactured by Captive Aire with features as noted in the RTU schedule and in the RTU Control Matrix, and complete with factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater, and low pressure switches; direct expansion cooling and condensing coils with 1 inch factory installed flexible elastomeric insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight; minimum SEER or EER rating (cooling) as required by the applicable energy code or greater if scheduled on the drawings, centrifugal evaporator blower; air filter rack, propeller type condenser fan; aluminumized steel heat exchanger, minimum AFUE rating (heating) as required by the applicable energy code or greater if scheduled on the drawings; forced combustion air blower; complete factory installed motor-processor controls including anti-short cycle timers, time delay relays and minimum "on" time controls, 100 percent safety gas shutoff, direct spark ignition system; built-in thermal overload protection on motors and compressors; outdoor air damper; relief; weatheright housing constructed of zinc coated, heavy gauge, galvanized steel with weather-resistant baked enamel finish; pre-engineered roof curb with minimum height as scheduled on the drawings if unit is equipped with internal vibration isolators; Type CMB if unit is not equipped with internal vibration isolators; single point electrical power connection. Provide guards or louvered panels to protect the condenser coil from hail or other damage. Provide a 125 VAC, 20 amp duplex convenience receptacle mounted to unit ready for field wiring with a cover UL listed for wet and damp locations when in use. Provide electronic programmable type thermostat. Provide unit complete with manufacturer's one year guarantee on components plus an additional four year guarantee on the compressors and heat exchangers. For units equipped with an economizer damper assembly, the assembly shall be covered with minimum 5 year manufacturer warranty, certified to operate through 60,000 damper opening and closing cycles, and certified to meet leakage requirements specified under the section, "Control Dampers."

2. FLEXIBLE DUCT

Low pressure (duct pressure class up to and including 2 inches w.g.) and medium pressure (duct pressure class 2.1 inch to 6 inches w.g.) flexible duct shall be Flexmaster type 8B, Thermalex type G-KM, M-KE, JPL type Silver Jacket, or equal (fire retardant polyethylene) protective vapor barrier, UL 181 Class 1, acoustical insulated duct, R-6.0 fiberglass insulation. Provide CPE liner with steel wire helix mechanically locked or permanently bonded to the liner.

Flexible duct runs shall not exceed 5 feet in length, and shall be installed fully extended and straight as possible avoiding tight turns. Install flexible duct in accordance with manufacturer's instructions. Support flexible duct at maximum 5 feet on center and within 6 inches of bends. Bends shall not exceed a centerline radius of one duct diameter. Duct sag shall not exceed 1/2 inch. Supporting in direct contact with the duct shall not be less than 1-1/2 inches in width.

Connect flexible duct to rigid metal duct or air devices as recommended by the manufacturer. At a minimum, install two wraps of duct tape around the inner corner of the duct and a metallic or non-metallic duct clamp over the tape and two wraps of duct tape or a clamp over the outer jacket. Duct clamps shall be labeled in accordance with UL-181B and marked 181B-C. Duct tape shall be labeled in accordance with UL 181B and marked 181B-FX.

D. PLASTIC FLUE GAS VENTS

Provide UL 1738 listed plastic flue gas vents, with positive or negative flue pressures complying with NFPA 211 and suitable for condensing gas appliances. Provide PVC system by IPEX "System 1738", or Polypropylene system by Centromtherm "Innoflu" or equal by Nova Flex Group "Z-DENS."

Vents and combustion air ducts for condensing type appliances shall be Schedule 40 PVC pipe and socket fittings meeting ASTM D2855 and UL 1738, manufactured by IPEX. Use solvent cement meeting ASTM D2564 and make joints in accordance with ASTM D2855.

Where plastic gas vents are installed in a return air plenum, wrap the vent with fire rated plenum insulation. Reference Article "Plenum Insulation" for plenum-rated fire wrap. Coordinate vent material compatibility with the appliance manufacturer's installation instructions prior to purchasing and installation.

E. AIR DEVICES

Provide air devices as scheduled on drawings, manufactured by Carnes, Krueger, Metallaire, Nalor Industries, Price, Tilus, or Tuttle & Bailey. Select air devices to limit room noise level to no higher than NC-30 unless otherwise shown. Provide with a plastic gasket to make an airtight seal against the mounting surface. Coordinate final location, frame, and mounting type of air devices with Architectural reflected ceiling plans.

Submit complete shop drawings including information on noise level, pressure drop, throw, CFM for each air device, styles, borders, etc. Clearly mark with specified equipment number. Submit samples of each air device as required by the Engineer.

Provide wall return air grilles and exhaust air registers with horizontal 35 or 45 degree angle vision-proof bars. Provide concealed fasteners for wall mounted registers and grilles. Provide floor supply air registers of aluminum heavy duty type with 0 degree deflection. Provide remote dampers for supply air registers and exhaust air registers unless indicated otherwise.

Provide ceiling mounted air devices of lay-in or surface mounted type as required to be compatible with ceiling construction. Provide ceiling diffusers and grilles with finished finish unless noted otherwise.

Provide linear slot diffusers of standard one-piece lengths up to 6-foot and furnish in multiple sections greater than 6-foot. Join multiple sections together end-to-end with alignment pins to form a continuous slot appearance. For installations in a hard ceiling, install diffuser per manufacturers installation instructions prior to installation of drywall. Contractor shall use manufacturer's hard ceiling clips for mounting to ceiling framing. Screws through face of linear slot diffuser are not acceptable. Provide alignment components by the manufacturer. Provide plenums by the slot diffuser manufacturer. Plenums shall be internally insulated by the manufacturer with minimum 1/4 inch thick fiberglass insulation.

Provide linear slot diffusers of standard one-piece lengths up to 6-foot and furnish in multiple sections greater than 6-foot. Join multiple sections together end-to-end with alignment pins to form a continuous slot appearance. For installations in a hard ceiling, install diffuser per manufacturers installation instructions prior to installation of drywall. Contractor shall use manufacturer's hard ceiling clips for mounting to ceiling framing. Screws through face of linear slot diffuser are not acceptable. Provide alignment components by the manufacturer. Provide plenums by the slot diffuser manufacturer. Plenums shall be internally insulated by the manufacturer with minimum 1/4 inch thick fiberglass insulation.

F. CONTROL DAMPERS

Provide factory fabricated, parallel blade control dampers sized as shown on the drawings and as specified. Individual damper sections shall not be larger than 48 inches x 60 inches with maximum blade width of 6 inches. Frame construction shall be minimum 16 gauge galvanized steel for rectangular dampers, 20 gauge for round, 1/8 inch thick for aluminum, with flanges for duct mounting. Provide weather resistant seals, mechanically attached and field replaceable. Provide a minimum of one damper actuator per section. Test damper performance in accordance with AMCA 500-D.

Provide modulating dampers with linear flow characteristics. Size modulating dampers based on the smaller of 1,500 FPM through the damper or full open air pressure drop of 0.1 inches W.C. Size two-position dampers full duct size and select to minimize pressure drop.

Motorized dampers used for ventilation air intake, exhaust air, or relief air shall have leakage rates not to exceed 4.0 CFM/square foot in full closed position at 1 inch W.G. pressure differential across the damper.

Provide dampers as manufactured by Greenheck, CESCO, Pottoff, Nalor, or Ruskin. Reference manufacturer with model number for outside air dampers is Ruskin CD-50 constructed of aluminum, and all other applications is Ruskin CD-35 constructed of galvanized steel.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee tight close-off of dampers against system pressure encountered. Each operator shall be provided with spring-return for normally closed or normally open position for the damper. Provide a power source for the damper operator. Damper operators shall be provided by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

G. LOUVERS, PLENUMS, SCREENS

Provide intake and exhaust air louvers by Ruskin model ELF37X or equal, American Warning & Ventilation, Cesco, Greenheck, Industrial Louvers or Louvers & Dampers as scheduled on the drawings. Coordinate exact size and location with architectural drawings. Louvers shall be stationary, with mill finish. Louvers shall have extruded aluminum blades, 0.800 inch wall thickness, 45 degree blade angle. Blades on 5 inch centers; frame shall be extruded aluminum, 0.080 inch wall thickness; with expanded flattened aluminum birdscreen. Provide louvers with a minimum free area of 45 percent, with a maximum air pressure drop of 0.1 inch at scheduled airflow.

Construct plenums with galvanized steel framing members and galvanized sheet metal, braced with galvanized angles. Gauges and bracing shall conform to SMACNA recommendations for ductwork of like size. Where access doors are shown, provide hinged doors with #202 Ventlok latch. Make watertight connections to louvers, sloping bottom of plenum to drain water to weepholes in bottom of louver.

Provide screens on louvers, ducts, hoods, fans, and openings to the outdoors as scheduled and/or noted on the drawings. Insect screens shall be 0.012-inch thickness, 14 inch mesh, aluminum wire. Bird screens shall be 0.041-inch, 102 inch mesh galvanized steel wire. Provide motorized control dampers or backdraft dampers where shown on the drawings.

Wind Driven Rain Performance: Louvers shall comply with ANSIA/AMA 500L for wind driven rain performance. Louvers shall have not less than 99 percent effectiveness when subjected to wind velocities of 29 and 50 mph with rainfall rates of 3 in/hr and 8 in/hr respectively and a core intake velocity not less than what is scheduled on the plans.

Windborne-Debris Impact Resistance: Louvers located within 30 feet of grade shall comply with AMCA 540.

H. EXHAUST AIR SYSTEMS

Provide roof mounted exhaust fans as scheduled on the drawings, or equal ACME, Carnes, Cook, Greenheck, Pembroy, or Twin City Fans complete with aluminum housing, aluminum centrifugal wheel, motor with integral thermal overload protection, disconnect switch mounted inside the housing, birdscreen, backdraft damper, and pre-fabricated roof curb. Three phase fans shall be furnished with magnetic starters with push button station.

I. KITCHEN EXHAUST AIR SYSTEMS

Install kitchen grease exhaust package furnished by the owner. System includes kitchen hood, grease exhaust fan/plenum/control unit, filtered makeup air unit and a mechanical or electrical gas shutoff valve provided with the kitchen exhaust system to shutoff fuel or power source to cooking equipment upon detection of fire. Valve shall have a clearly marked open/closed indicator.

Provide ducts connecting Type 1 exhaust hoods to exhaust fans made of #16 gauge black iron with continuously welded joints and clean-out doors. Provide transition at connection to fan with opening size equal to or greater than the venturi opening of the fan inlet. Provide gasket at flanged connection to fan rated for 1500 degrees Fahrenheit and grease applications. Enclose duct in fireproof enclosure per locally adopted mechanical code or, if approved by local code official, in fire rated wrap insulation. Insulation shall be minimum two-hour rated duct wrap insulation for Type 1 hood grease exhaust duct applications and shall conform to ASTM E2336 where required to comply with IMC. Insulation shall be flexible wrap enclosure rated for minimum 2000 degrees Fahrenheit and for zero clearance to combustibles. Insulation shall be non-mineral wool, passive, low bio-persistent fiber totally encapsulated on all sides with aluminum foil. Insulation shall be as manufactured by Certainteed, Thermal Ceramics, Unifrax or 3M. Exhaust duct back towards hood at minimum of 1/4 inch per linear foot. At Contractor's option, a UL listed concrete ductwork package that complies with UL 1878 standard for grease ducts may be used in lieu of the welded black iron duct for connecting hood to exhaust fan. Ductwork package shall be as manufactured by Meta-Fab, Schebler, Sekirk, or approved equal. Provide manufacturers UL listing number and verification certificate as a part of the shop drawing submittal. Install duct package in strict conformance with manufacturer's instructions and recommendations.

All portions of grease duct systems shall be tested for leakage in accordance with the "Grease Duct Test" paragraph of the IMC. Leakage tests shall be by water leakage type or equivalent test methods as approved by the local code official to determine that all joints are airtight tight. Water leakage test shall be performed by Environmental Corporation of America or owner approved testing contractor. Tests shall be performed in the presence of the local code official. Any joints found defective shall be repaired and retested until satisfactory results are obtained. The contractor shall submit a copy of the grease duct leakage test report to the architect/engineer complete with the approval signature of the local code official.

4. HVAC EQUIPMENT

A. ROOFTOP UNITS (GAS FIRED HEAT) 3-25 TONS

Install electrical cooling, gas heating rooftop units as scheduled on the drawings furnished by owner, manufactured by Captive Aire with features as noted in the RTU schedule and in the RTU Control Matrix, and complete with factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater, and low pressure switches; direct expansion cooling and condensing coils with 1 inch factory installed flexible elastomeric insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight; minimum SEER or EER rating (cooling) as required by the applicable energy code or greater if scheduled on the drawings, centrifugal evaporator blower; air filter rack, propeller type condenser fan; aluminumized steel heat exchanger, minimum AFUE rating (heating) as required by the applicable energy code or greater if scheduled on the drawings; forced combustion air blower; complete factory installed motor-processor controls including anti-short cycle timers, time delay relays and minimum "on" time controls, 100 percent safety gas shutoff, direct spark ignition system; built-in thermal overload protection on motors and compressors; outdoor air damper; relief; weatheright housing constructed of zinc coated, heavy gauge, galvanized steel with weather-resistant baked enamel finish; pre-engineered roof curb with minimum height as scheduled on the drawings if unit is equipped with internal vibration isolators; Type CMB if unit is not equipped with internal vibration isolators; single point electrical power connection. Provide guards or louvered panels to protect the condenser coil from hail or other damage. Provide a 125 VAC, 20 amp duplex convenience receptacle mounted to unit ready for field wiring with a cover UL listed for wet and damp locations when in use. Provide electronic programmable type thermostat. Provide unit complete with manufacturer's one year guarantee on components plus an additional four year guarantee on the compressors and heat exchangers. For units equipped with an economizer damper assembly, the assembly shall be covered with minimum 5 year manufacturer warranty, certified to operate through 60,000 damper opening and closing cycles, and certified to meet leakage requirements specified under the section, "Control Dampers."

B. SPLIT DUCTLESS AIR-CONDITIONING SYSTEMS

Provide split ductless system consisting of evaporator section with wall or ceiling mounting as indicated and remote condensing section similar to Carrier, Comfort Star, Daikin, Friedrich, Fujitsu, Lennox, LG, Mitsubishi, Samsung, Sanyo, Trane, or York. Evaporator cabinet shall be factory assembled pre-wired consisting of furniture-grade steel with baked-enamel finish, front accents with discreet driver centrifugal fans, 2-speed motor, and cleanable foam filter. Evaporator coil shall be direct-expansion cooling coil of seamless copper tubes expanded into aluminum fins

Provide remote sensors where indicated on the drawings and integrate them with the thermostat control equipment. Remote sensors shall have the following features:
1. Wired connection.
2. Temperature sensor.
3. Humidity sensor.
4. Blank faceplate.
5. Where multiple remote sensors are shown for a single unit, the sensors shall be provided in a single device.

Dry-bulb temperature sensors at a minimum shall be accurate to +/- 2 degrees Fahrenheit over the range of 40 to 80 degrees Fahrenheit. Wet-bulb temperature shall be calculated using dry-bulb temperature and humidity and shall be accurate to +/- 2 degrees Fahrenheit. Enthalpy shall be calculated using dry-bulb temperature and humidity and shall be accurate to +/- 3 BTU/lb over the range of 20 to 36 BTU/lb. Humidity sensors at a minimum shall be accurate within +/- 3 percent full range between 20 and 95 percent, with drift less than 1 percent full scale per year. Pressure transmitters at a minimum shall be accurate to +/- 1 percent full scale with drift less than 1 percent full scale per year.

Smoke detectors furnished and installed as indicated in this section or as scheduled on the plans (or heat detectors, if permitted by code) shall shut down each associated unit supply fan upon activation where required by code. Provide remote visual and audible alarm device in an approved location if smoke detectors are not connected to a fire alarm panel and label device as "Air Duct Detector Trouble".

Provide 24 Volt or 120 Volt timeswitches Intermatic Series FM1D20 or equal programmable type with 7-day programming with up to two "ons" and "offs" per day. Battery backup shall provide 48 hours of memory retention. Override timer switches shall be spring wound, 5-hour, normally open type. Coordinate 120 V wiring of timeswitch with electrical contractor if 120 V model is provided.

Provide relays with contact rating, configuration, and coil voltage that is suitable for the application. Relay shall be general purpose, enclosed plug-in type and protected by a heat and shock resistant duct cover. Number of contacts and operational function shall be as required. Transient suppression shall be provided as an integral part of the relay. Contactors shall be single coil, electrically operated, mechanically held, double-break, silver-to-silver type protected by arcing contacts. Positive locking shall be obtained without the use of hooks, latches, or semi-permanent magnets. Operating and release times shall be 100 milliseconds or less.

7. SEQUENCE OF OPERATION
A. FAN COIL UNIT CONTROL
During occupied hours, operate fan coil unit supply fan continuously and open outdoor air damper to maintain minimum ventilation. Cycle stage(s) of DX cooling and electric heating to maintain room thermostat set point (75 degrees Fahrenheit cooling, 70 degrees Fahrenheit heating). Duct mounted smoke detectors shall shutdown unit upon alarm.

During unoccupied hours, cycle the fan coil unit supply fan and cooling or heating system to maintain unoccupied setback temperature set points. Outdoor air motorized damper shall be closed during unoccupied hours.
Connect the Outdoor air motorized damper to the same time clock as the restroom exhaust.

B. KITCHEN EXHAUST FAN CONTROL
Kitchen exhaust fan shall be energized through on-off switches at the associated exhaust hoods or cooking equipment or through a master kitchen ventilation control panel as indicated on the drawings. Kitchen fans shall be interlocked to operate with cooking appliances, make-up air and other air-handling equipment providing fresh air to the kitchen area as noted or scheduled on the drawings.

C. ROOFTOP UNIT CONTROL
Refer to RTU CONTROL MATRIX on Sheet M601 for required rooftop unit control options.

D. RESTROOM EXHAUST FAN (EF-1) CONTROL
Operate exhaust fans continuously during occupied hours and shut down during unoccupied hours. Provide a 7-day timeclock to switch each system between occupied and unoccupied operation.

E. CO2 EXHAUST FAN (EF-2) CONTROL
Interlock fan operation with CO2 sensor located in mechanical room. Fan to energize during high level alarm as specified on plans.

F. AIR CURTAIN CONTROL
Interlock air curtain with door limit switch to energize when the door opens. Units scheduled with heating coils shall cycle the stages of heat to maintain room temperature setpoint of 70 F (adj).

8. ALTERNATES
A. DESCRIPTION
Refer to the architectural portion of the specification for list of alternates. Applicable sections of the base specifications shall apply to all work required by the alternate unless otherwise specified. Determine whether or not and how each alternate affects work. Include labor, materials, equipment, and transportation services necessary for and incidental to the completion of work under each alternate. Furnish separate bid for each alternate applicable to work, stating the amount to be added or deducted from the base bid.

9. COMMISSIONING OF MECHANICAL SYSTEMS
Commissioning of HVAC System

A. PART 1 GENERAL

1.1 SUMMARY
a. Section includes Cx process requirements for the following HVAC systems, assemblies, and equipment:
1. Air handling units (Supply fans, return fan, packaged units, roof top units, specialized fans)
2. Exhaust fans
3. Fan coil units and terminal units
4. Condensing units
5. Make-Up air units
6. Ductwork and piping
b. Related Requirements:
1. Section 019113 "General Commissioning Requirements" for general Cx process requirement and CxA responsibilities.

1.2 INFORMATIONAL SUBMITTALS
a. Construction Checklists: Draft construction checklists will be created by CxA for Contractor review.
b. Construction Checklists: Installation and Performance test checklists for systems, assemblies, subsystems, equipment, and components to be part of the Cx process and according to requirement in Section 019113 "General Commissioning Requirement."

1. Refrigigerant piping, including the following:
a. Refrigerant piping, fittings, and specialties.
b. Refrigerant charge.
c. General duty and specialty valves.
d. Meters and gauges.
2. Air distribution systems, including the following:
a. Supply, return, and exhaust systems.
b. Metal ducts, liners, and fittings.
c. Nonmetal ducts and fittings.
d. Air-duct accessories, including volume dampers, fire and smoke dampers, turning vanes, sound attenuators, and flexible connectors.
e. Duct-mounted access doors and panels.
3. Kitchen exhaust system, including the following:
a. Exhaust and makeup air system.
b. Metal ducts, liners, and fittings.
d. Air-duct accessories, including volume dampers, fire and smoke dampers, turning vanes, sound attenuators, and flexible connectors.
e. Duct-mounted access doors and panels.
f. Exhaust fans.
g. Make-Up air unit
4. Air-handling equipment, including the following:
a. Fans and motors.
b. Indoor air-handling units with and without coils, dampers, and filters.
c. Outdoor air-handling units with and without coils, dampers, and filters.

B. PART 3 EXECUTION
3.1 CONSTRUCTION CHECKLISTS
a. Complete detailed construction checklists (prefunctional checklists) prepared by the CxA for HVAC systems, assemblies, subsystems, equipment, and components.
1. Air and hydronic distribution systems, including the following:
a. Supply, return, outdoor-air, and exhaust-air distribution systems.
b. Automatic dampers.
c. Control valves.
2. Heating and cooling terminal and unitary equipment, including the following:
a. Unit heaters.
b. Fan coil units.
c. Electric heating.
3. TAB verification.

3.2 CONSTRUCTION CHECKLIST REVIEW
a. Review and provide written comments on draft construction checklists. CxA will create required draft construction checklists and provide item to Contractor.
b. Return draft construction checklist review comments within 5 days of receipt.
c. When review comments have been resolved, the CxA will provide final construction checklists marked "Approved for Use, (date)."
d. Use only construction checklists marked "Approved for Use, (date)."

3.3 Cx TESTING PREPARATION
a. Certify that HVAC systems, subsystems, and equipment have been installed, calibrated, and started and that they are operating according to the Contract Documents and approved submittals.
b. Set systems, subsystems, and equipment into operating mode to be tested according to approved test procedures (for example, normal shutdown, normal auto position, normal manual position, unoccupied cycle, and alarm conditions).

3.4 Cx TESTS COMMON TO HVAC SYSTEMS
a. Comply with construction checklist requirements, including installation checks, startup, and performance tests requirements for HVAC systems and equipment.
b. Measure capacities and effectiveness of systems, assemblies, subsystems, equipment and components, including operational and control functions, to verify compliance with acceptance criteria.
c. Coordinate schedule with, and perform Cx activities at the direction of CxA.
d. Provide technicians, instrumentation, tools, and equipment to perform and document the following:
1. Construction checklist verification tests.
2. Construction checklist verification tests demonstrations
3. Cx test demonstrations.

3.5 START-UP DOCUMENTATION COMMON TO ALL SYSTEMS
a. The following Start-Up Documentation (Checklists and Tests) shall be considered common to all systems:
1. Checkout shall proceed from lower level devices to larger components to the entire system operation.
2. Verify labeling is affixed per specification and visible.
3. Verify prerequisite procedures are done.
4. Inspect for damage and ensure none is present.
5. Verify system is installed per the manufacturer's recommendations.
6. Verify system has undergone Start-Up per the manufacturer's recommendations.
7. Verify that access is provided for inspection, operation and repair.
8. Verify that access is provided for eventual replacement of the equipment.
9. Verify that record drawings, submittal data and O&M documentation accurately reflect the installed systems.
10. Verify all gauges and test ports are provided as required by contract documents and manufacturer's recommendations.
11. Verify all recorded nameplate data is accurate.
12. Verify that the installation ensures safe operation and maintenance.
13. Verify all rotating and moving parts are properly lubricated.
14. Verify specified replacement material/stock has been provided as required by the Contract Documents.
15. Verify all monitoring and ensure all alarms are active and set per requirements.

3.6 MECHANICAL IDENTIFICATION
a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following checks:
1. Verify all valve tags, piping, duct, and equipment labeling corresponds with drawings and indexes and meets requirements specified. Correct any deficiencies for all piping and duct system.
2. Adjusting: Relocate any mechanical identification device which has become visually blocked by work of this division or other divisions.
3. Cleaning: Clean face of identification devices, and glass frames of valve charts.

3.7 MECHANICAL INSULATION
a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Examine all piping, systems and equipment specified to be insulated.
1. Ensure quality of insulation. Patch and repair all insulation damaged after installation.
2. Ensure the integrity of vapor barrier around all cold surfaces.

3.8 PIPING GENERAL
a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: These procedures apply to all installed piping systems, including underground site utilities.
1. Inspect all piping for proper installation, adequate support (with appropriate vibration isolation where applicable) and adequate isolation valves for required service.
2. Provide notifications of pipe cleaning and flushing activities.
3. Flush and clean all piping and clean all strainers. Provide documentation of all related procedures.
4. Ensure adequate drainage is provided at low points and venting is provided at high points.
5. Ensure facilities to effectively drain and fill the system are in place.
6. Ensure air is thoroughly removed from the system as applicable.
7. Provide notification of pressure testing.
8. Pressure and/or leak test all applicable systems in accordance with the requirements in the applicable Division 23 specification.
9. Sterilize applicable piping systems as specified in the individual sections and as required by regulatory authorities.
10. Submit pressure test reports that document the pressure testing results with certification of the results. Include drawings/diagrams indicating sections of pipe that are tested with the corresponding report.
11. Set and adjust fill, pressure, or level controls to the required setting.

3.9 AC MOTORS
a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following checks during start-up and as specified in manufacturer's instructions:
1. Verify proper alignment, installation, and rotation.
2. Verify properly sized overloads are in place.
c. Start-Up Tests: Perform the following tests, measurements, or procedures during start-up and as specified in the manufacturer's instruction
1. Measure voltage available to all phases. Measure amps and RPM after motor has been placed in operation and is under load.
2. Record all motor nameplate data.

3.10 PACKAGED HEATING AND COOLING UNITS
a. Include all applicable "Start-Up Checks Common to All Systems".
b. Refer to AC Motors in this section.
c. General: Provide the services of a factory-authorized service representative to test and inspect unit installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
b. Start-Up Checks: Perform the following inspections/checks during start-up:
1. Test controls and demonstrate compliance with requirements. Replace damaged or malfunctioning controls and equipment.
2. Install new filters after start-up.

3.11 TERMINAL UNITS
a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following inspections/checks during start-up:
1. After construction is completed, including painting if applicable, clean unit exposed surfaces.
2. Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
3. Verify adequate access for maintenance.
4. Check power and control voltages.
5. Check rotation of fan where applicable.
6. Check operation of water leak sensors.
7. Check calibration and operation of the controlling elements.
8. Check control valves for required close-off and fail position.
9. Install new filter units for terminals requiring same.

3.12 FANS
a. Include all applicable "Start-Up Checks Common to All Systems".
b. General: Provide the services of a factory-authorized service representative to test and inspect exhaust fan installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
c. Start-Up Checks: Perform the following inspections/checks during start-up:
1. Inspect the field assembly of components and installation of the units, piping, ductwork, and electrical connections.
2. Clean unit cabinet interiors to remove foreign material and construction dirt and dust. Vacuum clean fan wheel, fan cabinet, coils entering air face. Ensure volatile irritants are contained and kept out of occupied spaces.
3. Adjust and lubricate dampers and linkages for proper damper operation.
4. Verify the unit is secure on mountings and supporting devices and connections for ductwork, and electrical are complete. Verify proper thermal overload protection is installed in motors, starters, and disconnects.
5. Ensure vibration isolation integrity is maintained with the fan installation and associated connections.
6. Lubricate bearings, pulleys, belts, and other moving parts with factory-recommended lubricants.
7. Stroke all dampers to ensure free and full travel.

3.13 DUCTWORK ACCESSORIES
a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following checks during start-up and as specified:
1. Cleaning: Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
c. Start-Up Tests: In addition to specifications, perform the following as a minimum:
1. Operate installed ductwork accessories to demonstrate compliance with requirements. Test for air leakage while system is operating. Repair or replace faulty accessories, as required to obtain proper operation and leak proof performance.
2. Label access doors in accordance with Division 21 Section "Mechanical Identification"
3. Adjusting: Adjust ductwork accessories for proper settings, install fusible links in-fire dampers and adjust for proper action.

END OF SECTION 23

Bergmeyer logo and contact information. Henderson Engineers logo and contact information. Seal signature area with a circular stamp for Nathaniel T. Love. Table with revision history. Shake Shack logo and address. Addendum C title. Mechanical Specifications title. Drawn by and checked by fields. Job number M592.

ROOFTOP UNIT CONTROL MATRIX

Table with columns: CONTROL FEATURE, UNITS, RTU-1 SETPOINT OR Y/N, RTU-2 SETPOINT OR Y/N, NOTES. Includes sections for CONTROL STRATEGY, HEATING AND COOLING SET POINTS, PROGRAMMED CONTROL FEATURES, EQUIPMENT COMPONENTS, SAFETY FEATURES, and SUPPLY FAN CONTROL METHODS.

NOTES: DIV. 23 CONTRACTOR SHALL PROVIDE CONTROL PANEL(S), WIRING, THERMOSTAT(S), TEMPERATURE SENSOR(S), HUMIDISTAT(S), AND/OR CO2 SENSOR(S) WHERE SHOWN ON THE DRAWINGS AND AS REQUIRED TO FACILITATE THE SCHEDULED EQUIPMENT MODULES AND SEQUENCES OF OPERATION...

ROOFTOP UNIT SCHEDULE (DX COOLING, NATURAL GAS HEAT)

Table with columns: MARK, MANUFACTURER, MODEL, NOMINAL TONS, UNIT TYPE, SUPPLY FAN (CFM, ESP, HP, VFD), COOLING COIL (TH, SH, EAT, LAT), HEAT EXCHANGER (REFR, MIN EFF, MIN NO, MIN OUT, NOM INPUT, MIN EFF, EAT, MIN NO, MIN NO), ELECTRICAL (VPH, MCA, MOCP, DISC), WEIGHT (LBS), NOTES. Includes RTU-1 and RTU-2 units.

EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS. EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T.12 / VENDOR LIST FOR MORE INFORMATION. MODEL NUMBERS AND NOMINAL TONS LISTED SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER, MODEL NUMBERS, OR NOMINAL TONS ONLY...

FAN COIL UNIT SCHEDULE (HEAT PUMP)

Table with columns: MARK, MFR, MODEL, SUPPLY FAN (CFM, ESP, NOM, TH, SH), COOLING COIL (EAT, LAT), HEAT PUMP HEATING COIL (REFR, MIN EFF, MIN NO, MIN OUT, NOM INPUT, MIN EFF, EAT, MIN NO, MIN NO), ELECTRICAL (VPH, MCA, MOCP, DISC), WEIGHT (LBS), NOTES. Includes FCU-1 unit.

EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS. B. ASSOCIATED CONDENSING UNIT SHALL BE BY THE SAME MANUFACTURER. C. FOR COOLING, EQUIPMENT SIZED FOR 95°F AMBIENT TEMPERATURE. HEAT PUMP HEATING CAPACITY BASED ON AMBIENT TEMPERATURE LISTED.

BUILDING AIR BALANCE SUMMARY NORMAL OPERATION

Table with columns: UNIT NO., SUPPLY (CFM), OUTDOOR (CFM), EXHAUST (CFM), PERCENT O/A/S/A. Includes RTU-1, RTU-2, FCU-1, KEF-1, KEF-2, KEF-3, EF-1, and TOTALS.

BUILDING AIR BALANCE SUMMARY ECONOMIZER MODE

Table with columns: UNIT NO., SUPPLY (CFM), OUTDOOR (CFM), EXHAUST (CFM), PERCENT O/A/S/A. Includes RTU-1, RTU-2, FCU-1, KEF-1, KEF-2, KEF-3, EF-1, and TOTALS.

HEAT PUMP CONDENSING UNIT SCHEDULE

Table with columns: MARK, SERVICE, MANUFACTURER, MODEL, REFR TYPE, COOLING CAPACITY (TH, AMB, MIN EFF, CAP), HEATING CAPACITY (AMB, MIN EFF, COP), ELECTRICAL (VPH, MCA, MOCP), WEIGHT (LBS), NOTES. Includes CU-1 unit.

EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS. B. EQUIPMENT CAPACITY SCHEDULED IS MINIMUM CAPACITY THAT MUST BE PROVIDED AT AMBIENT TEMPERATURE INDICATED.

GRILLE, REGISTER, AND DIFFUSER SCHEDULE

Table with columns: MARK, MANUFACTURER, SERVICE, MODEL, CONSTRUCTION MATERIAL, FACE TYPE, MOUNTING LOCATION, FACE SIZE (IN), MAX NC, NOTES. Includes CEG, CRG, CSD1, CSD2, CSD3, WRG, and WSR.

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED.

LOUVER SCHEDULE

Table with columns: MARK, SERVICE, MANUFACTURER, MODEL, SIZE (W x H), CFM, MIN FREE AREA (SF), MAX VEL (PPM), MAX APD (IN W.C.), NOTES. Includes LV-1 unit.

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED.

AIR CURTAIN SCHEDULE

Table with columns: MARK, SERVICE AREA, MANUFACTURER, MODEL, LENGTH (IN), MAX AIRFLOW, HEATING CAPACITY (KW), MOTOR, VPH/MZ, NOTES. Includes AC-1 and AC-2 units.

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED.

FAN SCHEDULE

Table with columns: MARK, SERVICE, MANUFACTURER, MOUNTING, MODEL, CFM, ESP (IN), DRIVE, HP, RPM, VFD, ELECTRICAL (VPH, DISC, STARTER), NOTES. Includes EF-1 and EF-2 units.

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED.

PROJECT DESIGN CONDITIONS


Table with columns: CLIMATE CONDITIONS (WEATHER STATION, CLIMATE ZONE, HEATING DB, COOLING DB), BUILDING OPERATING HOURS (MONDAY-FRIDAY, SATURDAY, SUNDAY, HOLIDAY), SET POINTS (COOLING / DE-HUMIDIFICATION, HEATING, HUMIDIFICATION, ZONE VENTILATION RESET), SPACE OPERATING HOURS (OCCUPIED / UNOCCUPIED), NOTES.

NOTES: A. ZONE LEVEL SET POINT CONDITIONS SHALL BE AS SCHEDULED UNLESS OTHERWISE SCHEDULED OR NOTED ON THE DRAWINGS FOR ROOM SPECIFIC SPACE CONDITIONS. B. ZONE LEVEL OCCUPANCY HOUR SCHEDULE SHALL BE PER BUILDING OPERATING HOURS UNLESS OTHERWISE SCHEDULED.


OUTSIDE AIR REQUIREMENTS, IMC-2018 (IP)

Table with columns: SYSTEM DESIGNATION, SYSTEM TAB NAME OR LIST 'SINGLE', SINGLE-ZONE SYSTEM ASSOCIATED VENTILATION ZONE, SINGLE ZONE WORST CASE ZONE AIR DISTRIBUTION EFFECTIVENESS [Ez], SYSTEM VENTILATION EFFICIENCY [Ev], FLOOR AREA SERVED BY SYSTEM [A_s] (SF), SYSTEM AVERAGED AREA-BASED OUTDOOR AIR RATE (CFM/SF), SYSTEM POPULATION (PEOPLE), SYSTEM AVERAGED PEOPLE-BASED OUTDOOR AIR RATE (CFM/PPM), REQUIRED OA INTAKE FLOW [V_o] (CFM), REQUIRED DCV OA INTAKE FLOW [V_d] (CFM), DESIGN OA INTAKE FLOW [V_o] (CFM), NOTES.

GENERAL NOTES: 1. VENTILATION CALCULATIONS BASED ON IMC-2018. 2. SYSTEM POPULATIONS BASED ON MAX SEATING AND/OR CODE MAXIMUM VALUES. 3. SINGLE ZONE SYSTEMS (Vot + Voz): SYSTEM VENTILATION EFFICIENCY CALCULATION IS NOT REQUIRED FOR SINGLE ZONE SYSTEMS. WORST CASE AIR DISTRIBUTION EFFECTIVENESS BETWEEN HEATING AND COOLING MODES OF OPERATION IS SHOWN IN TABLE.



CONSULTANTS: HENDERSON ENGINEERS 8345 LENEAX DRIVE, SUITE 300 LENEAX, AZ 85214 TEL 913.742.5000 FAX 913.742.5001 WWW.HENDERSONENGINEERS.COM



EXPIRES ON: 09/30/2026

12/13/2024

Table with columns: NO., BY, DATE, DESCRIPTION. Includes entries for Addendum A and B.



SHAKE SHACK AVONDALE

9778 W MCDOWELL RD PHOENIX, AZ 85037 SHACK #1421

ADDENDUM C

MECHANICAL SCHEDULES

DRAWN BY: Author

CHECKED BY: Checker

JOB NO: 235004653

M601

COMcheck Software Version COMcheckWeb Mechanical Compliance Certificate

Project Information: Energy Code: 2018 IECC, Project Title: Shake Shack - Avondale, Location: Goodyear, Arizona, Climate Zone: 2b, Project Type: New Construction

Additional Efficiency Package(s): Credits: 1.0 Required, 0.0 Proposed

Mechanical Systems List: Quantity System Type & Description. 1 RTU-1 (Single Zone): Heating: 1 each - Central Furnace, Gas, Capacity = 87 kBtu/h. Cooling: 1 each - Single Package DX Unit, Capacity = 116 kBtu/h. 1 RTU-2 (Single Zone): Heating: 1 each - Central Furnace, Gas, Capacity = 157 kBtu/h. Cooling: 1 each - Single Package DX Unit, Capacity = 213 kBtu/h. 1 FCU-1 (Single Zone): Split System Heat Pump, Heating Mode, Capacity = 18 kBtu/h. Cooling Mode, Capacity = 16 kBtu/h. 3 Water Heater: Gas Instantaneous Water Heater, Capacity: 0 gallons, Input Rating: 199 kBtu/h w/ Circulation Pump

Project Title: Shake Shack - Avondale, Report date: 03/15/24, Data filename: Page 1 of 11

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2018 IECC requirements in COMcheck Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist. DALTON JUENEMANN - DESIGNER, Signature, Date: 03/15/2024

Project Title: Shake Shack - Avondale, Report date: 03/15/24, Data filename: Page 2 of 11

COMcheck Software Version COMcheckWeb Inspection Checklist

Energy Code: 2018 IECC. Requirements: 98.0% were addressed directly in the COMcheck software. Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed.

Table with 4 columns: Section # & Req ID, Plan Review, Complies?, Comments/Assumptions. Rows include C103.2 [PR2], C103.2 [PR3], and C406 [PR9].

Additional Comments/Assumptions:

Project Title: Shake Shack - Avondale, Report date: 03/15/24, Data filename: Page 3 of 11

Table with 4 columns: Section # & Req ID, Footing / Foundation Inspection, Complies?, Comments/Assumptions. Row: C403.12.3 [FD9].

Additional Comments/Assumptions:

Project Title: Shake Shack - Avondale, Report date: 03/15/24, Data filename: Page 4 of 11

Table with 4 columns: Section # & Req ID, Plumbing Rough-In Inspection, Complies?, Comments/Assumptions. Rows include C404.5, C404.5.1, C404.5.2 [PL6], C404.6.1, C404.6.2 [PL3], C404.6.3 [PL7], C404.7 [PL8].

Additional Comments/Assumptions:

Project Title: Shake Shack - Avondale, Report date: 03/15/24, Data filename: Page 5 of 11

Table with 4 columns: Section # & Req ID, Mechanical Rough-In Inspection, Complies?, Comments/Assumptions. Rows include C402.2.6 [ME41], C403.11.3 [ME6], C403.8.4 [ME142], C403.8.5 [ME143], C403.12.1 [ME71], C403.5.5 [ME113], C403.2.2 [ME59], C403.7.1 [ME59], C403.7.2 [ME115], C403.7.6 [ME141], C403.7.4 [ME57].

Project Title: Shake Shack - Avondale, Report date: 03/15/24, Data filename: Page 6 of 11

Table with 4 columns: Section # & Req ID, Mechanical Rough-In Inspection, Complies?, Comments/Assumptions. Rows include C403.7.5 [ME116], C403.11.1, C403.11.2 [ME60], C403.5, C403.5.1, C403.5.2 [ME62], C403.5.3, C403.5.3 [ME124], C403.5.3, C403.5.3 [ME125], C403.5.3, C403.4.1, C403.3.3 [ME35], C408.2.2 [ME33], C403.5, C403.5.1, C403.5.2 [ME123].

Project Title: Shake Shack - Avondale, Report date: 03/15/24, Data filename: Page 7 of 11

Additional Comments/Assumptions:

Project Title: Shake Shack - Avondale, Report date: 03/15/24, Data filename: Page 8 of 11

Bergmeyer logo and contact information: 875 N High St, Columbus, OH 43215, 980.900.8887

CONSULTANTS: HENDERSON ENGINEERS, 8345 LENEZA DRIVE, SUITE 300, LENEZA, KS 66214, TEL 913.742.5000, FAX 913.742.5001, WWW.HENDERSONENGINEERS.COM

SEAL SIGNATURE: EXPIRES ON: 09/30/2026, NATHAN T. LOVE, 12/13/2024

Table with columns: NO, BY, DATE, DESCRIPTION. Rows include B HEI 2024-09-12 ADDENDUM B, A HEI 2024-06-28 ADDENDUM A, HEI 2024-04-29 PERMIT/BD SET

SHAKE SHACK AVONDALE, 9778 W MCDOWELL RD, PHOENIX, AZ 85037, SHACK #1421, ADDENDUM C

MECHANICAL ENERGY CODE COMPLIANCE, DRAWN BY: Author, CHECKED BY: Checker, JOB NO: 235004653, M630

Section # & Req. ID	Rough-In Electrical Inspection	Complies?	Comments/Assumptions
C405.6 [EL26]	Low-voltage dry-type distribution electric transformers meet the minimum efficiency requirements of Table C405.6.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C405.7 [EL27]	Electric motors meet the minimum efficiency requirements of Tables C405.7(1) through C405.7(4). Efficiency verified through certification program or the equipment efficiency ratings shall be provided by motor manufacturer (where certification programs do not exist).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C405.8.2, C405.8.2.1 [EL28]	Escalators and moving walks comply with ASME A17.1/CSA B44 and have automatic controls configured to reduce speed to the minimum permitted speed in accordance with ASME A17.1/CSA B44 or applicable local code when not conveying passengers.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C405.9 [EL29]	Total voltage drop across the combination of feeders and branch circuits <= 5%.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Shake Shack - Avondale Report date: 03/15/24
Data filename: Shake Shack - Avondale Page 9 of 11

Section # & Req. ID	Final Inspection	Complies?	Comments/Assumptions
C303.3, C408.2.5, [F18]	Furnished OEM manuals for HVAC systems within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.2 [F127]	HVAC systems and equipment capacity does not exceed calculated loads.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1 [F147]	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1.1 [F142]	Heat pump controls prevent supplemental electric resistance heat from coming on when not needed.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.4.1.1 [F138]	Thermostatic controls have a 5 °F deadband.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.4.1.2 [F120]	Temperature controls have setpoint overlap restrictions.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.4.1.3 [F139]	Each zone equipped with setback controls using automatic time clock or programmable control system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.2.1, C403.2.4.2.2 [F140]	Automatic Controls: Setback to 55°F (heat) and 85°F (cool); 7-day clock, 2-hour occupant override, 15-hour backup.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.2.3 [F141]	Systems include optimum start controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.3 [F111]	Heat traps installed on supply and discharge piping of non-circulating systems.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.4 [F125]	All piping insulated in accordance with section details and Table C403.11.3.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.6.1 [F132]	Controls are installed that limit the operation of a recirculation pump installed to maintain temperature of a storage tank. System return pipe is a dedicated return pipe or a cold water supply pipe.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Shake Shack - Avondale Report date: 03/15/24
Data filename: Shake Shack - Avondale Page 10 of 11

Section # & Req. ID	Final Inspection	Complies?	Comments/Assumptions
C408.1.1 [F157]	Building operations and maintenance documents will be provided to the owner. Documents will cover manufacturer's information, specifications, programming procedures and means of illustrating to owner how building, equipment and systems are intended to be installed, maintained, and operated.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.1 [F128]	Commissioning plan developed by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3 [F131]	HVAC equipment has been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3.2 [F110]	HVAC control systems have been tested to ensure proper operation, calibration and adjustment of controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3.3 [F132]	Economizers have been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.4 [F129]	Preliminary commissioning report completed and certified by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5.1 [F17]	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5.3 [F143]	An air and/or hydronic system balancing report is provided for HVAC systems.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5.4 [F130]	Final commissioning report due to building owner within 90 days of receipt of certificate of occupancy.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Shake Shack - Avondale Report date: 03/15/24
Data filename: Shake Shack - Avondale Page 11 of 11




CONSULTANTS:
HENDERSON ENGINEERS
8345 LENEZA DRIVE, SUITE 300
LENEZA, KS 66214
TEL 913.742.5000 FAX 913.742.5001
WWW.HENDERSONENGINEERS.COM
235004653
AZ CORPORATE NO: 184700
EXPIRES 6/30/2025

SEAL SIGNATURE:
EXPIRES ON: 09/30/2026

12/13/2024

NO.	BY	DATE	DESCRIPTION
B	HEI	2024-09-12	ADDENDUM B
A	HEI	2024-06-28	ADDENDUM A
HEI		2024-04-29	PERMIT/BID SET



SHAKE SHACK AVONDALE

9778 W MCDOWELL RD
PHOENIX, AZ 85037
SHACK #1421

ADDENDUM C

MECHANICAL ENERGY
CODE COMPLIANCE

DRAWN BY: Author
CHECKED BY: Checker
JOB NO: 235004653

M631

NATHAN T. LOVE

12/12/2024 12:51:16 PM Autodesk Docs/20250210.00 - Shake Shack Avondale AZ/SHack 142 /Avondale AZ/NEPR/02.rvt

KITCHEN EXHAUST HOOD SCHEDULE

SCHEDULE FOR REFERENCE ONLY. EQUIPMENT FURNISHED BY OWNER.

MARK	EQUIPMENT SERVED	MANUFACTURER	TYPE	MODEL	HOOD DIMENSIONS (IN.) (L x W x H)	EXHAUST AIR (CFM)	DESIGN CFM/FT	WEIGHT (LBS)	NOTES
HOOD 1	FRYER	CAPTIVEAIRE	TYPE I	5430 ND-2	59" x 54" x 30"	860	175	747	A-H
HOOD 2	GRILL (SOUTH)	CAPTIVEAIRE	TYPE I	5430 ND-2	59" x 54" x 30"	738	150	356	A-H
HOOD 3	GRILL (NORTH)	CAPTIVEAIRE	TYPE I	5430 ND-2	59" x 54" x 30"	738	150	356	A-H

NOTES:

- HOOD SUPPLIER SHALL PROVIDE HOOD PRE-PIPED FOR WET-TYPE FIRE EXTINGUISHING SYSTEM MEETING REQUIREMENTS OF NFPA-96 AND LOCAL CODES.
- HOOD SUPPLIER SHALL FURNISH HOOD WITH UL LISTED BAFFLE-TYPE GREASE FILTERS, GREASE DRAIN WITH REMOVABLE CUP, AND UL LISTED VAPORPROOF LIGHT FIXTURES.
- HOOD SUPPLIER SHALL FURNISH STAINLESS STEEL ENCLOSURE PANELS FROM TOP OF HOOD TO FINISH CEILING AND 3 INCH STANDOFF FROM WALL AS REQUIRED.
- HOOD SUPPLIER SHALL FACTORY INSTALL THE HOOD CONTROL PACKAGE IN THE HOOD UTILITY CABINET.
- PROVIDED WITH HOOD FIRE SUPPRESSION SYSTEM MEETING NFPA-96 AND LOCAL CODES.
- PROVIDED WITH INTERLOCK KIT WITH ONE TEMPERATURE SENSOR PER GREASE EXHAUST COLLAR TO MEET IMC REQUIREMENTS.
- HOOD FIRE SUPPRESSION SYSTEM SUPPLIER SHALL FURNISH AUTOMATIC SOLENOID GAS SHUT-OFF VALVE TO BE INSTALLED BY PLUMBING CONTRACTOR.
- REFER TO REFERENCE DRAWINGS OF KITCHEN HOOD MANUFACTURER FOR KITCHEN EXHAUST HOOD DETAILS.

KITCHEN EXHAUST FAN SCHEDULE

SCHEDULE FOR REFERENCE ONLY. EQUIPMENT FURNISHED BY OWNER.

MARK	SERVICE DESCRIPTION	MANUFACTURER	MOUNTING	MODEL	CFM	ESP (IN)	BHP	NOM HP	FAN RPM	DRIVE (BELT/DIRECT)	VFD (Y/N)	ELECTRICAL			WEIGHT (LBS)	NOTES
												V/PH	DISC TYPE	STARTER TYPE		
KEF 1	HOOD 1	CAPTIVEAIRE	ROOF	DUS9HFA	860	1.0	0.32	0.5	1460	DIRECT	N	208/1	NF	N/A	79	A-G
KEF 2	HOOD 2	CAPTIVEAIRE	ROOF	DUS9HFA	738	1.0	0.29	0.5	1419	DIRECT	N	208/1	NF	N/A	79	A-G
KEF 3	HOOD 3	CAPTIVEAIRE	ROOF	DUS9HFA	738	1.0	0.29	0.5	1419	DIRECT	N	208/1	NF	N/A	79	A-G

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:

- PROVIDED WITH GREASE EXHAUST FAN WITH ROOF CURB EXTENSION FOR 40 INCH MINIMUM DISCHARGE HEIGHT ABOVE ROOF SURFACE OR AT ELEVATION HIGHER THAN ADJACENT BUILDING STRUCTURE WITHIN 10 FEET WHICHEVER IS GREATER. GREASE TRAP WITH ABSORBANT MATERIAL AND DRAIN CONNECTION, HINGE KIT, ACCESS PORT FOR CLEANING FAN BLADES AND INTEGRAL MOTOR OVERLOAD PROTECTION.
- PROVIDED WITH FACTORY MOUNTED DISCONNECT SWITCH.
- FAN SHALL BE SELECTED FOR STABLE OPERATION AT ELEVATED TEMPERATURE OF 300 F.
- PROVIDED WITH MANUFACTURER'S FAN SPEED CONTROLLER FOR BALANCING PURPOSES.
- PROVIDED WITH MANUFACTURER'S ELECTRONICALLY COMMUTATED (EC) MOTOR.
- NOMINAL MOTOR HP SHALL BE NO LARGER THAN THE FIRST AVAILABLE NOMINAL MOTOR SIZE GREATER THAN THE BHP.
- PROVIDE WITH AUXILIARY CONTACTS FOR SHUTDOWN UPON NOTIFICATION FROM FIRE ALARM SYSTEM.

Bergmeyer

BOS
 811
 875 N High St
 Columbus, OH 43215
 614.462.1025
 614.462.1025

LA
 800 South Figueroa St
 Los Angeles, CA 90017
 213.337.1090

CO
 875 N High St
 Columbus, OH 43215
 614.462.1025

www.bergmeyer.com

CONSULTANTS:

HENDERSON ENGINEERS
 8345 LENEXA DRIVE, SUITE 300
 LENEXA, KS 66214
 TEL 913.742.5001 FAX 913.742.5001
 WWW.HENDERSONENGINEERS.COM

235004653
 AZ CORPORATE NO: 18470-0
 EXPIRES 6/30/2025

SEAL SIGNATURE:

EXPIRES ON: 09/30/2026

12/13/2024

C	HEI	2024-12-16	ADDENDUM C
B	HEI	2024-09-12	ADDENDUM B
HEI	2024-04-29	PERMIT/BID SET	
NO.	BY	DATE	DESCRIPTION

SHAKE SHACK

SHAKE SHACK AVONDALE

9778 W MCDOWELL RD
 PHOENIX, AZ 85037
 SHACK #1421

ADDENDUM C

CAPTIVEAIRE DRAWINGS

DRAWN BY: Author
 CHECKED BY: Checker
 JOB NO: 235004653


M701

MECHANICAL GENERAL NOTES:

- DO NOT ROUTE ANY DUCTWORK OR PIPING ABOVE ELECTRICAL PANELS. REFER TO SHEET M001 FOR ADDITIONAL GENERAL NOTES AND REQUIREMENTS.
- REFER TO DETAILS AND SCHEDULES SHEETS FOR FURTHER INFORMATION.
- MOUNT ALL THERMOSTATS AND SENSORS CONTROLLING HVAC EQUIPMENT AT 48" AFF UNLESS OTHERWISE NOTED.

MECHANICAL PLAN NOTES:

- TYPE I GREASE HOOD EXHAUST DUCTWORK SHALL BE MINIMUM 16 GAUGE STEEL OR MINIMUM 19 GAUGE STAINLESS STEEL WITH LIQUID TIGHT WELDS.
- INSTALL ACCESS PANELS FOR CLEANING AS REQUIRED BY NFPA 96 AND LOCAL CODES. TRANSITION GREASE DUCTWORK AS REQUIRED TO HOOD AND FAN CONNECTIONS. PROVIDE 45° MAX OFFSETS AS REQUIRED TO COORDINATE WITH STRUCTURE. PROVIDE RADIUS ELBOWS WITHOUT TURNING VANES. SLOPE HORIZONTAL GREASE DUCT BACK TOWARDS HOOD AT MINIMUM OF 1/4" PER LINEAL FOOT. GREASE DUCTS SHALL BE CONTAINED IN A UL APPROVED GREASE DUCT WRAP SYSTEM.
- INSTALL "DUCTMATE ULTIMATE DOOR" ON DUCTS 12" OR LARGER AND INSTALL "DUCTMATE F2 SANDWICH ACCESS DOOR" FOR DUCTS LESS THAN 12" ON GREASE DUCT FOR CLEANING IN LOCATION SHOWN AT A MINIMUM AND AS REQUIRED BY NFPA 96 AND LOCAL CODES.
- TYPE I HOODS SHALL BE FURNISHED COMPLETE WITH INTERNALLY PIPED FIRE SUPPRESSION SYSTEM AND EXTERNAL FOAM SUPPLY BOTTLES WITH REMOTE PULL CONTROLS AND IN COMPLIANCE WITH NFPA 96 DIVISION 23 SHALL COORDINATE COMPLETE INSTALLATION WITH FIRE PROTECTION CONTRACTOR TO MEET APPROVAL OF LOCAL INSPECTOR AND CODE COMPLIANCE INCLUDING TESTING.
- HOOD SHALL OVERHANG THE COOKING SURFACE BY AT LEAST 6" ON BOTH SIDES.
- MOUNT THERMOSTATS, HUMIDITY SENSORS, AND TEMPERATURE SENSORS ON WALL. THERMOSTATS AND SENSOR(S) SHALL BE LABELED TO MATCH THE UNIT TAG AND CORRESPOND TO THE ELECTRICAL LEGEND IN THE ELECTRICAL PANELBOARD SERVING THE EQUIPMENT. COORDINATE COLOR WITH ARCHITECT.
- COMBINATION TEMPERATURE SENSOR AND HUMIDITY SENSOR.
- MOUNT TEMPERATURE SENSOR PROVIDED WITH KITCHEN EXHAUST HOODS ON WALL.
- INSTALL HOOD FIRE SUPPRESSION MANUAL PULL STATION. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH FIRE SUPPRESSION SYSTEM INSTALLER AND THE AUTHORITY HAVING JURISDICTION.
- CARBON DIOXIDE SENSOR WITH REMOTE ALARM REPEATER FURNISHED BY OWNER'S CO2 VENDOR AND LOCATED AT 12" AFF. THE SENSOR SHALL BE EQUIPPED WITH A LOCAL AUDIBLE AND VISUAL ALARM. THE LOW LEVEL ALARM SHALL ACTIVATE THE LOCAL AUDIBLE AND VISUAL ALARM. THE HIGH LEVEL ALARM SHALL ACTIVATE EF-2. IF THE BUILDING HAS A FIRE ALARM, PROVIDE THE APPROPRIATE FIRE ALARM INTERFACE MODULE TO INTERLOCK WITH THE BUILDING FIRE ALARM SYSTEM. THE HIGH-LEVEL CO2 ALARM SHALL SIGNAL BUILDING FIRE ALARM WHEN EQUIPPED. LOW LEVEL ALARM - 0.5% = 5,000 PPM. HIGH LEVEL ALARM - 3.0% = 30,000 PPM.
- INSTALL DUCT SMOKE DETECTOR IN RETURN AIR PLENUM.
- INSTALL EMERGENCY ALARM IN MANAGER'S OFFICE TO INDICATE CARBON MONOXIDE AND CARBON DIOXIDE DETECTION IN MECHANICAL ROOM. PROVIDE LIGHT IN OFFICE WITH TAG FOR EACH ALARM.
- PROVIDE COMBUSTION AIR AND EXHAUST PIPE AND ROUTE TO CONCENTRIC VENT THROUGH ROOF.
- REFRIGERANT PIPING UP TO CU-1 ON ROOF, REF 1M150.
- CONTRACTOR TO COORDINATE 1" UNDERCUT ON DOOR FOR EXHAUST AIR PATH.
- AIR CURTAIN MOUNTED ABOVE DOOR. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
- PROVIDE 1/4" GALVANIZED CONSTRUCTION HARDWARE CLOTH SCREEN OVER OPEN END OF RETURN DUCT. PROVIDE DUCT LINER IN BOOT. RETURN AIR DUCT SHALL BE MINIMUM 36" HORIZONTAL EXTENSION FOR SOUND ATTENUATION.
- PROVIDE SA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.
- PROVIDE RA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.
- PROVIDE EA DUCT THROUGH ROOF. TRANSITION TO EXHAUST FAN INLET SIZE WITHIN CURB.
- 9"X9" GREASE EXHAUST DUCT UP TO KEF-1 ON ROOF.
- 8"X8" GREASE EXHAUST DUCT UP TO KEF-2 ON ROOF.
- 8"X8" GREASE EXHAUST DUCT UP TO KEF-3 ON ROOF.
- ROUTE DUCTWORK LEVEL, TIGHT TO STRUCTURE, AND ABOVE LIGHTS. COORDINATE WITH STORM DRAINAGE, STRUCTURAL, AND ELECTRICAL.
- INSTALL LOUVER CENTERED IN DOOR WITH BOTTOM OF LOUVER AT 0'-6" AFF.
- TRANSITION 6" OUTDOOR AIR DUCT TO 4" FLEXIBLE DUCTWORK AND CONNECT TO UNIT.
- MOUNT WITH CENTER OF RETURN GRILLES AT 13'-0" AFF.
- TERMINATE 4"X10" EXHAUST DUCT AT 1'-0" A.F.F. PROVIDE 1/4" GALVANIZED CONSTRUCTION HARDWARE CLOTH SCREEN OVER OPEN END OF EXHAUST DUCT.
- BALANCE RETURN AIR DAMPER TO 800 CFM.
- BALANCE RETURN AIR DAMPER TO 4100 CFM.



1 MECHANICAL FLOOR PLAN
1/4" = 1'-0"



ALL GREASE DUCT TO BE WATER TESTED BY ENVIROMATIC AT MECHANICAL CONTRACTOR'S EXPENSE. CONTACT OWNER'S NATIONAL ACCOUNT VENDOR:

ENVIROMATIC
DON PFLEIDERER
1.800.325.8476
inspections@enviromatic.com

THE BUILDINGS HVAC SYSTEMS SHALL BE BALANCED BY NATIONAL TAB (NO EXCEPTIONS) AND CONTRACTED BY THE GENERAL CONTRACTOR.

CONTACT:
WILL TURNBOUGH
will@natontab.com
855-682-8822 ext704

1	HEI	2025-02-17	IFC SET
B	HEI	2024-09-12	ADDENDUM B
A	HEI	2024-08-28	ADDENDUM A
HEI		2024-04-29	PERMIT/IBID SET
NO.	BY	DATE	DESCRIPTION



SHAKE SHACK AVONDALE

9778 W MCDOWELL RD
PHOENIX, AZ 85037
SHACK #1421

IFC SET

MECHANICAL FLOOR PLAN

DRAWN BY: Author

CHECKED BY: Checker

JOB NO: 235004653

M101