



KEYNOTES (# & Letters marked on drawing):

1) 14" dia duct off AHU14 ducted to Chase L & then routed up to 6th floor to a non-functioning VAV that serves (3) air devices @ Max 800 CFM.

A) AHU-15 Traverse Supply Duct 12" x 54"

B) AHU-14 Traverse Supply 44" x 28" Oval OD

C) AHU-14 Traverse Supply 38" x 14" Oval ID

D) AHU-14 Traverse Supply 14" Dia

E) AHU-14 Traverse Return 42" Dia

Mechanical Room located in Basement (D Wing).