


NO.	DATE	REVISIONS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	05/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR LL REVIEW



NO.	DATE	REMARKS

MECHANICAL SYMBOLS		V2.06	
THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS OR ABBREVIATIONS ARE USED.			
STANDARD MOUNTING HEIGHT		HVAC DUCTWORK AND ACCESSORIES	
<p>THERMOSTATS (USER ADJUSTABLE/TOP OF DEVICE) 48"</p> <p>CONTROLS (TOP OF DEVICE) 48"</p> <p>INSTALL DEVICES AT THE MOUNTING HEIGHTS SHOWN ABOVE UNO IN THE CONSTRUCTION DOCUMENTS. MOUNTING HEIGHTS LISTED ABOVE OR ELSEWHERE IN THE CONSTRUCTION DOCUMENTS ARE FOR AIR TO BOTTOM OF DEVICE UNO. ALL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH CURRENT ADA AND LOCAL REQUIREMENTS.</p>	LINEAR SLOT DIFFUSER INSULATED FLEXIBLE DUCT (MAX. 5'-0" LONG) BRANCH DUCT WITH 45° RECTANGULAR ROUND BRANCH FITTING AND MANUAL VOLUME DAMPER ELBOW WITH TURNING VANES BRANCH DUCT WITH BELL-MOUTH FITTING & MANUAL VOLUME CONTROL DAMPER RETURN, EXHAUST, OR OUTSIDE AIR DUCT UP RETURN, EXHAUST, OR OUTSIDE AIR DUCT DOWN SUPPLY AIR DUCT UP SUPPLY AIR DUCT DOWN EQUIPMENT WITH FLEXIBLE DUCT CONNECTION 10" (NECK SIZE) CSD-1 (TYPE) 300 CFM (CFM OF SUPPLY DIFFUSER OR REGISTER) 24x24 (NECK SIZE) CEG-1 (TYPE) 800 CFM (CFM OF EXHAUST GRILLE) MANUAL VOLUME DAMPER SQUARE TO ROUND TRANSITION DUCT MOUNTED SMOKE DETECTOR (SD=SUPPLY/RD=RETURN) ROUND DUCT TAG INDICATING DIAMETER RECTANGULAR DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS. FLAT OVAL DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS. RISER DESIGNATION FIRE DAMPER FIRE SMOKE DAMPER SMOKE DAMPER VOLUME DAMPER MOTORIZED DAMPER BACKDRAFT DAMPER	<p>DIRECTION OF FLOW</p> <p>CONTROL VALVE</p> <p>THREE-WAY CONTROL VALVE</p> <p>SHUTOFF VALVE</p> <p>CHECK VALVE</p> <p>BALANCING VALVE WITH PRESSURE PORTS</p> <p>TRIPLE DUTY VALVE WITH PRESSURE PORTS</p> <p>STRAINER</p> <p>STRAINER WITH BLOWDOWN VALVE</p> <p>RELIEF / SAFETY VALVE</p> <p>SOLENOID VALVE</p> <p>PRESSURE REDUCING VALVE</p> <p>GAS PRESSURE REGULATOR</p> <p>THERMOSTATIC MIXING VALVE</p> <p>PIPE ANCHOR</p> <p>EXPANSION JOINT</p> <p>PIPE GUIDE</p> <p>PIPE SUPPORT</p> <p>F & T TRAP</p> <p>BUCKET TRAP</p> <p>THERMOSTATIC TRAP</p> <p>BACKFLOW PREVENTER</p> <p>PRESSURE GAUGE</p> <p>THERMOMETER</p> <p>PRESSURE AND TEMPERATURE TEST PLUG</p> <p>UNION</p> <p>FLANGE CONNECTION</p> <p>VACUUM RELIEF VALVE</p> <p>AUTOMATIC AIR VENT</p> <p>MANUAL AIR VENT</p> <p>PRESSURE / VACUUM SWITCH</p> <p>CLEANOUT</p> <p>CAP</p> <p>ELBOW UP</p> <p>ELBOW DOWN</p> <p>TEE UP</p> <p>TEE DOWN</p> <p>ELBOW UP WITH SHUT-OFF VALVE (SOV)</p> <p>ELBOW DOWN WITH SHUT-OFF VALVE (SOV)</p> <p>TEE UP WITH SHUT-OFF VALVE (SOV)</p> <p>TEE DOWN WITH SHUT-OFF VALVE (SOV)</p> <p>REDUCER</p> <p>RECIRCULATION PUMP</p> <p>P-TRAP</p> <p>GAS COCK</p> <p>TOP BEAM CLAMP</p> <p>TRAPEZE HANGER</p> <p>FLEXIBLE CONNECTION</p>	
ANNOTATION			
<p>MECHANICAL PLAN NOTE CALLOUT</p> <p>MECHANICAL EQUIPMENT DESIGNATION (CONTRACTOR FURNISHED AND INSTALLED UNLESS NOTED OTHERWISE)</p> <p>CONNECTION POINT OF NEW WORK TO EXISTING</p> <p>DETAIL REFERENCE. UPPER NUMBER INDICATES DETAIL NUMBER LOWER NUMBER INDICATES SHEET NUMBER</p> <p>SECTION CUT DESIGNATION</p>			
ABBREVIATIONS			
<p>A/C AIR CONDITIONING</p> <p>ACC AIR COOLED CHILLER</p> <p>ACCU AIR COOLED CONDENSING UNIT</p> <p>AFC ABOVE FINISHED CEILING</p> <p>AFF ABOVE FINISHED FLOOR</p> <p>AFG ABOVE FINISHED GRADE</p> <p>AHF AUTHORITY HAVING JURISDICTION</p> <p>AHU AIR HANDLING UNIT</p> <p>AI ANALOG INPUT</p> <p>AO ANALOG OUTPUT</p> <p>AP ACCESS PANEL</p> <p>AD AIR PRESSURE DROP</p> <p>AWG AMERICAN WIRE GAUGE</p> <p>B BOILER</p> <p>B BUILDING AUTOMATION SYSTEM</p> <p>BB BACKBONE</p> <p>BD BACKDRAFT DAMPER</p> <p>BD BLOWDOWN</p> <p>BFC BELOW FINISHED CEILING</p> <p>BFF BELOW FINISHED FLOOR</p> <p>BFG BELOW FINISHED GRADE</p> <p>BFP BOILER FEED PUMP</p> <p>BHP BRAKE HORSEPOWER</p> <p>BI BINARY INPUT</p> <p>BO BINARY OUTPUT</p> <p>BOD BOTTOM OF DUCT</p> <p>BOS BOTTOM OF STRUCTURE</p> <p>BTU BRITISH THERMAL UNIT</p> <p>CFM CUBIC FEET PER MINUTE</p> <p>CH CHILLER</p> <p>CLG COOLING</p> <p>CO CLEANOUT</p> <p>CP CONDENSATE PUMP</p> <p>CP CONTROL POWER TRANSFORMER</p> <p>CRAC COMPUTER ROOM AIR CONDITIONING UNIT</p> <p>CRU COMPUTER ROOM UNIT</p> <p>CT COOLING TOWER</p> <p>CWP CONTROL VALVE</p> <p>CWP WATER PUMP</p> <p>CU CONDENSING UNIT</p> <p>CHUP CHILLED WATER PUMP</p> <p>DB DECIBELS</p> <p>DBA DECIBEL AVERAGE</p> <p>DD DIRECT DIGITAL CONTROL</p> <p>DI DIGITAL INPUT</p> <p>DISC DISCONNECT</p> <p>DN DOWN</p> <p>DS DUCT SILENCER</p> <p>EAT EXHAUST AIR ENTERING</p> <p>EA AIR TEMPERATURE</p> <p>ED EXHAUST DUCT</p> <p>EDB ENTERING DRY BULB</p> <p>EF EXHAUST FAN</p> <p>EFF EFFICIENCY</p> <p>EMS ENERGY MANAGEMENT SYSTEM</p> <p>ESP EXTERNAL STATIC PRESSURE</p> <p>EWB ENTERING WET BULB</p> <p>EWJ ENTERING WATER TEMPERATURE</p> <p>FCU FAN COIL UNIT</p> <p>FFA FROM FLOOR ABOVE</p> <p>FFB FROM FLOOR BELOW</p> <p>FF FINISHED FLOOR</p> <p>FPI FINS PER INCH</p> <p>FPM FEET PER MINUTE</p> <p>GC GENERAL CONTRACTOR</p> <p>GPM GALLONS PER MINUTE</p> <p>HOA HAND-OFF-AUTOMATIC</p> <p>HP HORSEPOWER</p> <p>HTG HEATING</p> <p>HWP HEATING WATER PUMP</p> <p>IN WC INCHES OF WATER COLUMN</p> <p>L LAT</p> <p>LA LEAVING AIR TEMPERATURE</p> <p>LDB LEAVING DRY BULB</p> <p>LP LOW PRESSURE</p> <p>LWB LEAVING WET BULB</p> <p>LWT LEAVING WATER TEMPERATURE</p> <p>MAU MAKE-UP AIR UNIT</p> <p>MAX MAXIMUM</p> <p>MBH 1000 BTU PER HOUR</p> <p>MD MOTORIZED DAMPER</p> <p>MFR MANUFACTURER</p> <p>MIN MINIMUM</p> <p>N/A NOT APPLICABLE</p> <p>N/C NORMALLY CLOSED</p> <p>N/O NORMALLY OPEN</p> <p>NOM NOMINAL</p> <p>NC NOISE CRITERIA</p> <p>NF NON-FUSED</p> <p>NIC NOT IN CONTRACT</p> <p>PIC PRESSURE INDEP. CONTROL VALVE</p> <p>PROVIDE FURNISH AND INSTALL</p> <p>QTY QUANTITY</p> <p>RA RETURN AIR</p> <p>RC ROOM CRITERIA</p> <p>RD RETURN DUCT</p> <p>REA RELIEF AIR</p> <p>REF REFRIGERANT</p> <p>RH RELATIVE HUMIDITY</p> <p>RPM REVOLUTIONS PER MINUTE</p> <p>RTU ROOFTOP UNIT</p> <p>SA SUPPLY AIR</p> <p>SCP STEAM CONDENSATE PUMP</p> <p>SD SMOKE DETECTOR</p> <p>SD SUPPLY DUCT</p> <p>SF SUPPLY FAN</p> <p>SH SENSIBLE HEAT CAPACITY</p> <p>SOV SCOPE OF WORK</p> <p>SP STATIC PRESSURE</p> <p>ST STEAM TRAP</p> <p>STM STEAM</p> <p>TBD TO BE DETERMINED</p> <p>TCOC TEMPERATURE CONTROL CONTRACTOR</p> <p>TEMPERATURE CONTROL PANEL</p> <p>TF TRANSFER FAN</p> <p>TEA TO FLOOR ABOVE</p> <p>TFB TO FLOOR BELOW</p> <p>TH TOTAL HEAT CAPACITY</p> <p>TSP TOTAL STATIC PRESSURE</p> <p>TT TEMPERATURE TRANSMITTAL</p> <p>TYP TYPICAL</p> <p>UF UNDERFLOOR</p> <p>UG UNDERGROUND</p> <p>UIS UNDERSLAB</p> <p>UNO UNLESS NOTED OTHERWISE</p> <p>VAV VARIABLE AIR VOLUME</p> <p>VEL VELOCITY</p> <p>VFD VARIABLE FREQUENCY DRIVE</p> <p>VRV VARIABLE REFRIGERANT FLOW</p> <p>VRF VARIABLE REFRIGERANT VOLUME</p> <p>W/ WITH</p> <p>W/O WITHOUT</p> <p>WB WET BULB</p> <p>WC WATER COLUMN</p> <p>WPD WATER PRESSURE DROP</p> <p>XP EXPLOSION PROOF</p>			
HVAC CONTROL DEVICES			
<p>HUMIDISTAT</p> <p>THERMOSTAT</p> <p>CARBON MONOXIDE SENSOR</p> <p>CARBON DIOXIDE SENSOR</p> <p>DIFFERENTIAL PRESSURE SENSOR</p> <p>FLOW SWITCH</p> <p>HUMIDITY SENSOR</p> <p>PULL STATION</p> <p>REMOTE TESTING STATION WITH INDICATING LIGHT</p> <p>STATIC PRESSURE</p> <p>TEMPERATURE SENSOR</p>			
ALL DUCT DIMENSIONS SHOWN ON DRAWINGS ARE INSIDE DIMENSIONS. REFER TO DUCTWORK SPECIFICATIONS FOR DUCTWORK INSULATION AND LINER INFORMATION.			

- GENERAL NEW NOTES:**
- PRIOR TO SUBMITTING BID, VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH THE EXISTING CONDITIONS OF THE PROJECT. REVIEW THE GENERAL NOTES, SPECIFICATIONS AND OTHER DRAWINGS FOR ADDITIONAL REQUIREMENTS WHICH MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY ARCHITECT, ENGINEER AND/OR OWNER OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
 - EXISTING CONDITIONS WERE TAKEN FROM ORIGINAL DRAWINGS AND SITE VISITS AND MAY NOT REFLECT EXACT "AS-BUILT" CONDITIONS. FIELD VERIFY EXISTING CONDITIONS PRIOR TO SUBMITTING FINAL BIDS. COORDINATE NEW WORK AND DEMOLITION WITH OTHER DISCIPLINES AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION.
 - COORDINATE THE INSTALLATION OF THE MECHANICAL SYSTEMS WITH OTHER TRADES TO ENSURE A NEAT AND ORDERLY INSTALLATION. INSTALL DUCTWORK AND PIPING AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS. COORDINATE INSTALLATION OF DUCTWORK AND PIPING TO AVOID CONFLICTS WITH ELECTRICAL PANELS, LIGHTING FIXTURES, ETC. ANY MODIFICATIONS REQUIRED DUE TO LACK OF COORDINATION WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AT NO EXTRA COST TO THE OWNER.
 - WHERE SHUTDOWN OF EXISTING SYSTEMS IS REQUIRED DURING NEW WORK, COORDINATE SHUTDOWN TIME AND DURATION WITH THE OWNER TO MINIMIZE DOWNTIME. NOTIFY OWNER SEVEN (7) DAYS PRIOR TO INTERRUPTION OF SERVICE.
 - DURING INSTALLATION OF NEW WORK, AVOID DAMAGING EXISTING SURFACES AND EQUIPMENT TO REMAIN. REPAIR DAMAGE CAUSED DURING CONSTRUCTION AT NO EXTRA COST TO THE OWNER.
 - PROVIDE TEMPORARY BARRIERS TO CONTAIN DUST AND DEBRIS RESULTING FROM THE PERFORMANCE OF THE WORK TO THE AREA WHERE WORK IS BEING PERFORMED.
 - ALL MECHANICAL EQUIPMENT SHOWN ON THE MECHANICAL PLANS SHALL BE PROVIDED BY DIVISION 23 UNLESS OTHERWISE NOTED.
 - NEW MECHANICAL EQUIPMENT, DUCTWORK AND PIPING ARE SHOWN AT APPROXIMATE LOCATIONS. FIELD MEASURE FINAL DUCTWORK AND PIPING LOCATIONS PRIOR TO FABRICATING AND MAKE ADJUSTMENTS AS REQUIRED TO FIT THE DUCTWORK AND PIPING WITHIN THE AVAILABLE SPACE. VERIFY THAT FINAL EQUIPMENT LOCATIONS MEET MANUFACTURER'S RECOMMENDATIONS REGARDING SERVICE CLEARANCE AND PROPER AIRFLOW CLEARANCE AROUND EQUIPMENT.
 - REFER TO ARCHITECTURAL DRAWINGS FOR RELATED CONSTRUCTION DETAILS AS APPLICABLE TO THE HVAC SYSTEM. UTILITY CHASES AND PENETRATIONS SHOWN ON ARCHITECTURAL DRAWINGS THAT ARE INTENDED FOR DUCTWORK AND PIPING MEET REQUIREMENTS.
 - COORDINATE LOCATION OF ROOF MOUNTED HVAC EQUIPMENT AND ROOF PENETRATIONS WITH THE ARCHITECTURAL AND STRUCTURAL DRAWINGS.
 - INDOOR AIR QUALITY MEASURES: PROTECT INSIDE OF (INSTALLED AND DELIVERED) DUCTWORK AND HVAC UNITS FROM EXPOSURE TO DUST, DIRTY PAINT AND MOISTURE. REPLACE INSULATION THAT HAS BECOME WET AT ANY TIME DURING CONSTRUCTION, DRYING THE INSULATION IS NOT ACCEPTABLE. SEAL ANY TEARS OR JOINTS OF INTERNAL FIBERGLASS INSULATION. REMOVE DEBRIS FROM CEILING/RETURN AIR PLENUM INCLUDING DUST. AN INDEPENDENT, PROFESSIONAL DUCT CLEANING COMPANY SHALL VACUUM CLEAN ANY DUCTWORK CONNECTED TO HVAC UNITS THAT WERE OPERATED DURING THE CONSTRUCTION PERIOD AFTER NEW FILTERS ARE INSTALLED AND PRIOR TO TURNING SYSTEM OVER TO THE OWNER. THE INTERNAL SURFACES AND ASSOCIATED COILS OF ANY HVAC UNITS THAT WERE OPERATED SHALL ALSO BE CLEANED.
 - INSTALL DUCTWORK AND PIPING PARALLEL TO BUILDING COLUMN LINES UNLESS OTHERWISE SHOWN OR NOTED.
 - OVERHEAD HANGERS AND SUPPORTS FOR EQUIPMENT, DUCTWORK AND PIPING SHALL BE FASTENED TO BUILDING JOISTS OR BEAMS. DO NOT ATTACH HANGERS AND SUPPORTS TO THE ABOVE FLOOR SLAB OR ROOF EXCEPT WHERE CONCRETE INSERTS IN CONCRETE SLABS ARE ALLOWED BY THE SPECIFICATIONS.
 - COORDINATE LOCATION OF EQUIPMENT SUPPORTS WITH LOCATION OF EQUIPMENT ACCESS PANELS/DOORS TO ENABLE SERVICE OF EQUIPMENT AND/OR FILTER REPLACEMENT.
 - SEAL PENETRATIONS THROUGH THE BUILDING COMPONENTS IN ACCORDANCE WITH THE CONTRACT SPECIFICATIONS. FIREPROOF PENETRATIONS THROUGH FIRE RATED COMPONENTS IN ACCORDANCE WITH U.L. REQUIREMENTS.
 - COORDINATE THE EXACT MOUNTING SIZE AND FRAME TYPE OF DIFFUSERS, REGISTERS AND GRILLES WITH THE SUPPLIER TO MEET THE CEILING, WALL AND DUCT INSTALLATION REQUIREMENTS.
 - ADJUST LOCATION OF CEILING DIFFUSERS, REGISTERS AND GRILLES AS REQUIRED TO ACCOMMODATE FINAL CEILING GRID AND LIGHTING LOCATIONS.
 - PAINT PORTIONS OF DUCTWORK AND INSULATION THAT ARE EXPOSED TO VIEW BY THE INSTALLATION OF DIFFUSERS, REGISTERS, AND GRILLES IN CEILINGS OR WALLS FLAT BLACK. PORTIONS INCLUDE BOTH THE INTERIOR OF UNLINED DUCTWORK AND THE EXTERIOR OF DUCTWORK AND INSULATION.
 - LOCATE AND SET THERMOSTATS AND HUMIDISTATS AT LOCATIONS SHOWN ON PLANS. VERIFY EXACT LOCATION WITH ARCHITECT PRIOR TO INSTALLATION. INSTALL DEVICES WITH TOP OF DEVICE AT MAXIMUM 48" AFF TO MEET ADA REQUIREMENTS UNLESS NOTED OTHERWISE ON PLANS. PROVIDE INSULATED BACKING FOR THERMOSTATS MOUNTED ON EXTERIOR BUILDING WALLS. INSTALL WIRING IN CONDUIT PROVIDED BY DIVISION 26. AT A MINIMUM, PROVIDE CONDUIT IN THE WALL FROM THE JUNCTION BOX TO 6" ABOVE THE CEILING.
 - COORDINATE THE LOCATION AND ELEVATION OF WALL-MOUNTED DEVICES WITH PRESENTATION BOARDS, DISPLAY CABINETS, SHELVES OR OTHER COMPONENTS SHOWN ON THE ARCHITECTURAL DRAWINGS THAT ARE TO BE INSTALLED UNDER OTHER DIVISIONS. CONTRACTOR WILL NOT BE REIMBURSED FOR RELOCATION OF WALL-MOUNTED DEVICES CAUSED BY A LACK OF COORDINATION.
 - PROVIDE A MANUAL BALANCING DAMPER IN EACH DUCT TAKEOFF FROM SUPPLY, RETURN, OUTDOOR AND EXHAUST AIR DUCTS.
 - PROVIDE A PREFABRICATED 45 DEGREE, HIGH EFFICIENCY, RECTANGULAR/ROUND BRANCH DUCT TAKEOFF FITTING FOR BRANCH DUCT CONNECTIONS AND TAKE-OFFS TO INDIVIDUAL DIFFUSERS, REGISTERS AND GRILLES. PROVIDE WATER TIGHT, MANUAL BALANCING DAMPER AND LOCKING QUADRANT WHERE INDICATED ON PLANS.
 - BRANCH DUCTWORK TO AIR OUTLETS SHALL BE SAME SIZE AS OUTLET NECK SIZE UNLESS OTHERWISE NOTED.
 - REFER TO SPECIFICATIONS FOR DUCTWORK AND PIPING INSULATION REQUIREMENTS. DUCT SIZES ON MECHANICAL PLANS INDICATE CLEAR INSIDE AIRFLOW DIMENSIONS. INCREASE SHEET METAL SIZES ACCORDINGLY TO ACCOUNT FOR THICKNESS OF DUCT LINER.
 - FLEXIBLE DUCTWORK SHALL NOT EXCEED 5'-0" IN LENGTH AND SHALL BE INSTALLED AND SUPPORTED TO AVOID SHARP BENDS AND SAGGING. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
 - PROVIDE EQUIPMENT VENTS AND FLUES PER EQUIPMENT MANUFACTURERS RECOMMENDATIONS AND EQUIPMENT SPECIFICATIONS. KEEP PENETRATIONS THROUGH ROOF A MINIMUM OF 10'-0" FROM HVAC EQUIPMENT FRESH AIR INLETS AND 2'-0" FROM ROOF PARAPETS.
 - PROVIDE TYPE I GREASE HOOD EXHAUST DUCTWORK OF MINIMUM 16 GAUGE BLACK IRON WITH LIQUID TIGHT WELDS, WITH ACCESS PANELS FOR GREASE CLEANING AS REQUIRED BY NFPA 96 AND LOCAL CODES. SLOPE DUCT BACK TOWARDS HOOD AT MINIMUM OF 1/4" PER LINEAL FOOT MAINTAINING 18" CLEARANCE TO COMBUSTIBLE MATERIALS. INSTALL GREASE DUCTS IN AN APPROVED FIRE-RATED ENCLOSURE SEPARATED FROM THE EXHAUST DUCT BY A MINIMUM OF 6" AND MAXIMUM OF 12". VENTILATE ENCLOSURE TO THE OUTSIDE AIR IF REQUIRED BY CODE. AS AN OPTION, IF APPROVED BY LOCAL CODES, PROVIDE AN APPROVED WRAP SYSTEM IN LIEU OF THE RATED DUCT ENCLOSURE SYSTEM. DUCT WRAP SYSTEM SHALL MEET UL REQUIREMENTS FOR GREASE DUCT ENCLOSURES.
 - PROVIDE A NEW SET OF AIR FILTERS IN UNITS PRIOR TO TESTING, ADJUSTING AND BALANCING AND BEFORE TURNING SYSTEM(S) OVER TO OWNER.
 - FIELD VERIFY THAT THE EXISTING EQUIPMENT INCLUDING ACCESSORIES BEING REUSED FOR THIS PROJECT IS NOT DAMAGED AND IS IN GOOD WORKING ORDER. REPORT ANY DEFICIENCIES TO THE OWNER OR ARCHITECT. SUBMIT TO THE OWNER AND ARCHITECT A WRITTEN REPORT DESCRIBING TESTS PERFORMED TO VERIFY OPERATION AND RESULTS OF THE TESTS.
 - CLEAN EXISTING EQUIPMENT AND EQUIPMENT COMPONENTS BEING REUSED FOR THIS PROJECT. PROVIDE NEW FILTERS FOR EXISTING AIR HANDLING EQUIPMENT PRIOR TO STARTUP OF EQUIPMENT. NEW FILTERS SHALL BE COMPATIBLE WITH THE EXISTING EQUIPMENT AND EQUAL IN PERFORMANCE TO THE EXISTING FILTERS AT NEW CONDITION UNLESS OTHERWISE NOTED. CLEAN STRAINERS IN PIPING SYSTEMS PRIOR TO STARTING PUMPS.
 - TEMPORARY INSTALLATIONS OF INFECTION CONTROL MEASURES DURING CONSTRUCTION SHALL BE COORDINATED WITH THE FACILITY'S INFECTION CONTROL STAFF. PRIOR TO CONSTRUCTION PROVIDE ALL REQUIRED TEMPORARY INSTALLATIONS, INCLUDING DETAILS OF THE INFECTION CONTROL MEASURES SUCH AS TEMPORARY BARRIERS AND MEMBRANES, PORTABLE EXHAUST FANS AND TEMPORARY DUCTWORK. TEMPORARY INSTALLATIONS MUST NOT HAVE A NEGATIVE IMPACT ON EXISTING SYSTEMS NOR CAUSE UNSAFE CONDITIONS. TEMPORARY INSTALLATIONS SHALL MAINTAIN ADEQUATE EGRESS AND SHALL NOT OBSTRUCT EXISTING EXITS, CREATE A FIRE HAZARD OR REDUCE REQUIRED FIRE RESISTANCE. TEMPORARY VENTILATION SYSTEMS SHALL NOT CAUSE THE AIR BALANCE OF ADJACENT ROOMS OR SPACES TO BE IMPACTED OR ALTER THE PERFORMANCE OF PERMANENT BUILDING VENTILATION SYSTEMS. AIRFLOW MEASUREMENTS SHALL BE TAKEN TO VERIFY ADJACENT ROOMS OR SPACES ARE NOT IMPACTED.

MECHANICAL SHEET INDEX

M001	MECHANICAL GENERAL INFORMATION
M101	MECHANICAL FLOOR PLAN
M150	MECHANICAL FLOOR PLAN
M501	MECHANICAL DETAILS
M502	MECHANICAL DETAILS
M503	GAS RISER DIAGRAM
M590	MECHANICAL SPECIFICATIONS
M591	MECHANICAL SPECIFICATIONS
M592	MECHANICAL SPECIFICATIONS
M601	MECHANICAL SCHEDULES
M602	MECHANICAL SCHEDULES
M630	MECHANICAL ENERGY CODE COMPLIANCE
M631	MECHANICAL ENERGY CODE COMPLIANCE
M701	CAPTIVE AIRE DRAWINGS
M702	CAPTIVE AIRE DRAWINGS
M703	CAPTIVE AIRE DRAWINGS
M704	CAPTIVE AIRE DRAWINGS
M705	CAPTIVE AIRE DRAWINGS
M706	CAPTIVE AIRE DRAWINGS

RESPONSIBILITY MATRIX


DESCRIPTION	FURNISHED			INSTALLED			REMARKS
	GC	OWNER	LL	GC	OWNER	LL	
DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING							
23.1 HVAC DUCTWORK AND PIPING IDENTIFICATION							
HVAC DUCTWORK SYSTEM IDENTIFICATION							
PIPING SYSTEM IDENTIFICATION							
UTILITY SHUT OFF IDENTIFICATION IN KITCHEN							
VALVE TAGS AND CHART							
HVAC DAMPER IDENTIFICATION							
23.2 ROOF CURBS							
23.3 HVAC DUCTWORK SYSTEM COMPONENTS							
HVAC DUCTWORK							
GREASE EXHAUST INSIDE TENANT SPACE							
GREASE EXHAUST LOUVER							
MAKEUP AIR DUCTWORK INSIDE TENANT SPACE							
MAKEUP AIR LOUVER							
OUTSIDE AIR DUCTWORK INSIDE TENANT SPACE							
OUTSIDE AIR LOUVER							
GENERAL EXHAUST AIR DUCTWORK INSIDE TENANT SPACE							
GENERAL EXHAUST AIR LOUVER							
INSULATION AND FIRE WRAP							
DAMPERS							
SMOKE DETECTORS							
SUPPLY, RETURN, AND EXHAUST GRILLES AND REGISTERS							
23.4 MECHANICAL PIPING SYSTEM COMPONENTS							
WALK-IN COOLER AND FREEZER WATER COOLED CONDENSERS							1
VALVES AND ACCESSORIES (E.G. AIR VENTS)							
CONDENSER WATER PIPING WITHIN TENANT SPACE							
CONDENSER WATER LOOP BTU METER							
CONDENSER WATER PIPING TO DEMISED SPACE							
HEAT PUMP WATER PUMPS (HPWP)							
23.5 HVAC EQUIPMENT							
GENERAL EXHAUST FAN							
KITCHEN EXHAUST PRECIPITATOR							
DUCTED AND NON-DUCTED HEATING AND COOLING UNITS							
MAKEUP AIR UNIT							
23.6 KITCHEN EXHAUST WITH FIRE SUPPRESSION SYSTEM							
HOOD CONTROL PANEL							
KITCHEN EXHAUST HOOD							
STRUCTURAL SUPPORT							
ELECTRICAL AND CONTROL WIRING							
ANSUL SYSTEM							2
ANSUL WIRING AND UTILITIES CONNECTION							
ANSUL GAS VALVE							
23.7 COMMISSIONING ACTIVITIES							
GREASE EXHAUST WATER LEAKAGE TEST							
TEST AND BALANCE (TAB) REPORT							
GENERAL NOTES: 1. INFORMATION CONTAINED WITHIN IS BASED ON THE EXECUTED WORK LETTER DATE... 2. REFER TO FINAL WORK LETTER FOR ALL LANDLORD / TENANT SCOPE OF WORK...							
REMARKS: 1. WALK-IN COOLER AND FREEZER SUPPLIED BY VENDOR NO. 27. GENERAL... INSTALLATION AND FINAL CONNECTION. 2. GENERAL CONTRACTOR TO COORDINATE AND FACILITATE SYSTEM SIGN-OFF.							

SUBMITTAL MATRIX

SUBMITTAL DESCRIPTION	Required Review Time (Business Days)	Architect of Record	Shake Shack	Physical Sample Required	Submit for Record	Submit for Record Only
GENERAL CONTRACTORS TO ALSO REVIEW ARCHITECTURAL SPECIFICATIONS AS NOTED IN PLANS IN PLAN SECTION 700 OF THE ARCHITECTURAL PACKAGE FOR REQUIRED SUBMITTALS THAT MIGHT NOT BE LISTED BELOW.						
Diffusers, Grills & Registers	5	X			X	
Ductwork Layout (if there are significant changes in field)	5	X			X	
HVAC Equipment (if Carrier - Submitted by Owner Vendor directly to Owner/AOR prior to construction)	5	X			X	
MEP Tests, Start-Up, and Programming Reports	5	X			X	

FIELD VERIFICATION
Contractor shall verify all figured dimensions and conditions at the job site and notify Aria Group Architects, Inc. of any dimensional errors, omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.
COPYRIGHT
Aria Group Architects, Inc. shall retain all common law, statutory and other reserved rights. These drawings and related documents shall not be duplicated, disclosed or otherwise used without the consent of Aria Group Architects, Inc.

NO.	DATE	REVISIONS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	05/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR ILL REVIEW



Drawing Title	
MECHANICAL FLOOR PLAN	
Job No.	Drawn
214815	Author
Scale	Date
1/4" = 1'-0"	05/16/22
Sheet No.	
M101	

ALL GREASE DUCT TO BE WATER TESTED BY ENVIROMATIC AT MECHANICAL CONTRACTOR'S EXPENSE. CONTACT OWNER'S NATIONAL ACCOUNT VENDOR.

ENVIROMATIC
DON PFLEDERER
1.800.325.8476
inspections@enviromatic.com

THE BUILDINGS HVAC SYSTEMS SHALL BE BALANCED BY NATIONAL TAB (NO EXCEPTIONS) AND CONTRACTED BY THE GENERAL CONTRACTOR.


CONTACT:
WILL TURNBOUGH
will@natonattab.com
855-682-6822 ext704

MECHANICAL GENERAL NOTES:

- DO NOT ROUTE ANY DUCTWORK OR PIPING ABOVE ELECTRICAL PANELS. REFER TO SHEET M001 FOR ADDITIONAL GENERAL NOTES AND REQUIREMENTS.
- REFER TO DETAILS AND SCHEDULES SHEETS FOR FURTHER INFORMATION.
- MOUNT ALL THERMOSTATS AND SENSORS CONTROLLING HVAC EQUIPMENT AT 48" AFF UNLESS OTHERWISE NOTED.

MECHANICAL PLAN NOTES:

- TYPE I HOODS SHALL BE FURNISHED COMPLETE WITH INTERNALLY PIPED FIRE SUPPRESSION SYSTEM AND EXTERNAL FOAM SUPPLY BOTTLES WITH REMOTE PULL CONTROLS AND IN COMPLIANCE WITH NFPA 96. DIVISION 23 SHALL COORDINATE COMPLETE INSTALLATION WITH FIRE PROTECTION CONTRACTOR TO MEET APPROVAL OF LOCAL INSPECTOR AND CODE COMPLIANCE INCLUDING TESTING.
- TYPE I GREASE HOOD EXHAUST DUCTWORK SHALL BE MINIMUM 16 GAUGE STEEL OR MINIMUM 18 GAUGE STAINLESS STEEL WITH LIQUID TIGHT WELDS. INSTALL ACCESS PANELS FOR CLEANING AS REQUIRED BY NFPA 96 AND LOCAL CODES. TRANSITION GREASE DUCTWORK AS REQUIRED TO HOOD AND FAN CONNECTIONS. PROVIDE 45" MAX OFFSETS AS REQUIRED TO COORDINATE WITH STRUCTURE. PROVIDE RADIUS ELBOWS WITHOUT TURNING VANES. SLOPE HORIZONTAL GREASE DUCT TOWARDS HOOD AT MINIMUM OF 1/4" PER LINEAL FOOT. GREASE DUCTS SHALL BE CONTAINED IN A UL APPROVED GREASE DUCT WRAP SYSTEM.
- REFER TO CAPTIVE AIRE DRAWINGS FOR INFORMATION REGARDING HOOD(S) AND HVAC DIFFUSERS LOCATED NEAR THE HOOD(S).
- 8"X8" GREASE DUCT UP THRU ROOF TO KITCHEN EXHAUST FAN. REF M150 FOR CONTINUATION. PROVIDE TRANSITION AS REQUIRED TO MAKE FULL SIZE CONNECTION TO KITCHEN EXHAUST FAN. TYPICAL FOR KEF-1, KEF-2, KEF-3 AND KEF-4.
- PROVIDE SA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR.
- PROVIDE RA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR.
- MOUNT THERMOSTATS AND TEMPERATURE SENSOR(S) ON WALL. LOCATE THERMOSTAT IN OFFICE AND TEMPERATURE/HUMIDITY SENSORS IN ZONE. THERMOSTATS AND SENSORS SHALL BE LABELED TO MATCH THE UNIT TAG AND CORRESPOND TO THE ELECTRICAL LEGEND IN THE ELECTRICAL PANELBOARD SERVING THE EQUIPMENT. COORDINATE COLOR WITH ARCHITECT.
- MOUNT TEMPERATURE SENSOR PROVIDED WITH KITCHEN EXHAUST HOODS ON WALL.
- INSTALL "F2" GREASE DUCT SANDWICH ACCESS DOOR* GREASE DUCT ACCESS PANELS FOR CLEANING IN LOCATION SHOWN AT A MINIMUM AND AS REQUIRED BY NFPA 96 AND LOCAL CODES.
- INSTALL HOOD FIRE SUPPRESSION MANUAL PULL STATION COORDINATE EXACT LOCATION AND REQUIREMENTS WITH FIRE SUPPRESSION SYSTEM INSTALLER AND THE AUTHORITY HAVING JURISDICTION.
- 10"X10" EXHAUST DUCT UP TO EF-1 ON ROOF.
- INSTALL DUCT SMOKE DETECTOR IN RETURN AIR DUCT.
- CARBON MONOXIDE DETECTOR FURNISHED BY OWNER. INSTALL AT 5'-0" AFF. SENSOR SHALL BE PROVIDED WITH AND INTERCONNECTED WITH AUDIBLE AND VISUAL ALARM. COORDINATE FINAL LOCATION WITH OWNER REPRESENTATIVE.
- PROVIDE ANAUX AX80 OR APPROVED EQUAL CARBON DIOXIDE SENSOR WITH REMOTE ALARM REPEATER TO BE MOUNTED AT 18" AFF. PROVIDE CARBON DIOXIDE SENSOR WITH RELAY. RELAY SHALL BE INTERLOCKED WITH THE BUILDING FIRE ALARM SYSTEM. THE SENSOR SHALL BE EQUIPPED WITH A LOCAL AUDIBLE AND VISUAL ALARM. THE LOW LEVEL ALARM SHALL ACTIVATE THE LOCAL AUDIBLE AND VISUAL ALARM. THE HIGH LEVEL ALARM SHALL ACTIVATE RELAY. INSTALL SENSOR PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
LOW LEVEL ALARM - 0.5% = 5,000 PPM
HIGH LEVEL ALARM - 3.0% = 30,000 PPM
- INSTALL KITCHEN HOODS CENTERED OVER THE COOKLINE SO THAT THE HOOD OVERHANGS THE COOKING SURFACES BY AT LEAST 6" ON BOTH SIDES.
- REFRIGERANT PIPING UP TO CU-1 ON ROOF. REF I1M150.
- AIR CURTAIN MOUNTED ABOVE DOOR. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
- PROVIDE COMBUSTION AIR AND EXHAUST PIPE AND ROUTE TO CONCENTRIC VENT THROUGH ROOF.
- PROVIDE WITH CONCENTRIC VENT IPEX UL 1738 ITEM NUMBER 397006.
- MOUNT BOTTOM OF RETURN AIR DUCTWORK AT 11'-4" A.F.F. PROVIDE 1/4" GALVANIZED CONSTRUCTION HARDWARE CLOTH SCREEN OVER OPEN END OF RETURN DUCT. PROVIDE DUCT LINER IN BOOT. RETURN AIR DUCT SHALL BE MINIMUM 36" HORIZONTAL EXTENSION FOR SOUND ATTENUATION.
- INSTALL HOOD CONTROL PANEL PER MANUFACTURER'S INSTRUCTIONS. REFER TO CAPTIVE AIRE DRAWINGS FOR MORE INFORMATION.
- INSTALL DUCTWORK TIGHT TO BOTTOM OF STRUCTURE. APPROXIMATE ELEVATION B.O.D. 11'-0" A.F.F.
- INSTALL GAS SOLENOID FURNISHED WITH HOOD FIRE SUPPRESSION SYSTEMS. INSTALL GAS SOLENOID AND SHUTOFF VALVE BELOW CEILING VISIBLE FOR MAINTENANCE.
- SUPPLY 1-1/4" G DN TO EACH WATER HEATER, 1-1/2" COLD WATER DN TO AND 1-1/2" HW DN TO EACH HOT WATER
- 3/4" TEST PORT WITH ISOLATION VALVE
- 3/4" TEST PORT WITH ISOLATION VALVE. ENSURE THAT A MINIMUM OF 36" BETWEEN GAS METER AND ELECTRICAL
- NOTE: NOT USED
- INSTALL REMOTE ANSUL CABINET ON WALL PANEL PER MANUFACTURER'S INSTRUCTIONS. REFER TO CAPTIVE AIRE DRAWINGS FOR MORE INFORMATION.
- MOUNT STANDARD SIZE 24"X24" ACCESS PANEL FOR DAMPERS OVER HARD HALLWAY CEILING.
- SEE P101 FOR DRAIN LOCATION.
- LEAK DETECTION SYSTEM IS REQUIRED FOR WALK-IN FREEZER PER COLORADO MECHANICAL CODE.




1 MECHANICAL FLOOR PLAN
1/4" = 1'-0"

Gas Piping General Notes

VERIFY GAS LOADS AND GAS ROUGH-IN OF KITCHEN EQUIPMENT WITH THE KITCHEN EQUIPMENT SHOP DRAWINGS PRIOR TO INSTALLING GAS PIPING. PROVIDE GAS COCKS, UNIONS, ETC. AS SPECIFIED AND REQUIRED. INSTALL GAS QUICK DISCONNECTS WHERE FURNISHED WITH THE KITCHEN EQUIPMENT.

PAINT EXTERIOR GAS PIPING WITH A RUST INHIBITOR PAINT PER THE ARCHITECT'S SPECIFICATIONS.

INSTALL ENTIRE GAS PIPING SYSTEM ON BUILDING ROOF AS INDICATED ON DRAWINGS. MINIMIZE GAS PIPING INSTALLED INSIDE THE BUILDING SHELL SERVING INTERIOR EQUIPMENT. PROVIDE GAS PRESSURE REGULATORS, GAS COCKS AND SUPPORTS FOR A COMPLETE WORKING GAS SYSTEM.




① GAS RISER
NTS

SHAKE SHACK
9723 FEDERAL DR., COLORADO SPRINGS, CO 80921

FIELD VERIFICATION
Contractor shall verify all figured dimensions and conditions at the job site and notify Aria Group Architects, Inc. of any dimensional errors, omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.
COPYRIGHT
Aria Group Architects, Inc. shall retain all common law, statutory and other reserved rights. These drawings and related documents shall not be duplicated, disclosed or otherwise used without the consent of Aria Group Architects, Inc.

NO.	DATE	REVISIONS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	05/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR LL REVIEW



Drawing Title
GAS RISER DIAGRAM

Job No. 214815
Drawn Author

Scale 1/4" = 1'-0"
Date 05/16/22

Sheet No.
M503

GENERAL MECHANICAL REQUIREMENTS

1. GENERAL INSTRUCTIONS

- A. GENERAL REQUIREMENTS
B. DEFINITIONS
C. PRE-BID SITE VISIT
D. MATERIAL AND WORKMANSHIP
E. MANUFACTURERS
F. COORDINATION
G. ORDINANCES AND CODES
H. PROTECTION OF EQUIPMENT AND MATERIALS
I. SUBMITTALS
J. ELECTRONIC DRAWINGS FILES
K. RECORD DRAWINGS (AS-BUILT DRAWINGS)
L. OPERATION AND MAINTENANCE INSTRUCTIONS
M. SPARE PARTS
N. TRAINING
O. WARRANTIES

2. GENERAL MATERIALS AND INSTALLATION

- A. BUILDING OPERATION
B. ACCIDENTAL DAMAGE
C. CUTTING AND PATCHING
D. ROUGH-IN
E. STRUCTURAL SUPPORT SYSTEMS
F. PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS AND CURBS
G. ACCESS PANELS AND DOORS
H. PENETRATIONS
I. FIRESTOPPING
J. MOTORS AND STARTERS
K. VARIABLE FREQUENCY DRIVES
L. ELECTRICAL WIRING
M. EQUIPMENT FURNISHED BY OTHERS
N. SYSTEM TESTING, ADJUSTING, AND BALANCING
O. VIBRATION ISOLATION
P. AIR FILTERS
Q. PENETRATIONS AND OIL
R. IDENTIFICATION

3. DUCT INSULATION, DUCTWORK, ACCESSORIES, FLUES AND FANS

- A. DUCT INSULATION
B. DUCTWORK
C. FLEXIBLE DUCT
D. PLASTIC FLUE GAS VENTS
E. AIR DEVICES
F. CONTROL DAMPERS
G. EXHAUST AIR SYSTEMS
H. KITCHEN EXHAUST AIR SYSTEMS

4. HVAC EQUIPMENT

- A. ROOFTOP UNITS (GAS FIRED HEAT) 3-25 TONS (RTU-1)
B. ROOFTOP UNITS (DOAS) (GAS FIRED HEAT) 12.5 TONS (RTU-2)
C. ELECTRIC UNIT HEATERS
D. SPLIT DUCTLESS AIR-CONDITIONING SYSTEMS
E. AIR CURTAINS

5. PIPING AND PIPING SPECIALTIES

- A. REFRIGERANT PIPING AND INSULATION
B. SYSTEM EVACUATION AND CHARGING

6. TEMPERATURE CONTROLS

- A. GENERAL REQUIREMENTS
B. WIRING
C. THERMOSTAT CONTROL EQUIPMENT
D. SENSORS AND RELAYS

7. SEQUENCE OF OPERATION

- A. FAN COIL UNIT CONTROL
B. KITCHEN EXHAUST FAN CONTROL
C. ROOFTOP UNIT CONTROL
D. ROOFTOP UNIT CONTROL (RTU-2 ONLY)
E. RESTROOM EXHAUST FAN (EF-1) CONTROL
F. AIR CURTAIN CONTROL
G. ELECTRIC UNIT HEATER CONTROL

8. ALTERNATIVES

- A. DESCRIPTION
B. EXECUTION

9. COMMISSIONING OF MECHANICAL SYSTEM

- A. GENERAL
B. EXECUTION

DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING

1. GENERAL INSTRUCTIONS

A. GENERAL REQUIREMENTS

All requirements under Division 01 and the general and supplementary conditions of these specifications apply to this section and division. Where the requirements of this section and division exceed those of Division 01, this section and division take precedence.

The specifications and drawings for the project are complementary, and any portion of work described in one shall be provided as if described in both.

Drawings are graphic representations of the work upon which the contract is based. They show the materials and their relationship to one another, including sizes, shapes, locations, and dimensions. They also show the intended general arrangement of the systems without showing all of the exact details as to elevations, offsets, control lines, and other installation requirements.

B. DEFINITIONS

- Division - References contained in this specification follow the numbering system defined in the Construction Specifications Institute (CSI) MasterFormat 2004 Edition.
2004 Edition
Division 1 - Fire Suppression
Division 2 - Plumbing
Division 3 - HVAC
Division 4 - Electrical
Division 5 - Communications
Division 6 - Division 28 - Electronic Safety and Security

Furnish: "to supply and deliver to the project site, ready for unloading, unpacking, assembly, installation and similar operations."
Install: "to perform all operations at the project site including, but not limited to, the actual unloading, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, testing, commissioning, starting up and similar operations, complete, and ready for the intended use."

Furnished by Owner (or Owner-Furnished) or Furnished by Others: "an item furnished by the Owner or under other divisions or contracts, and installed under the requirements of this division, complete and ready for intended use, including all items and services incidental to the work necessary for proper installation and operation.

Engineer: Where referenced in this division, "Engineer" is the Engineer of Record and the Design Professional for the work under this division, and is a duly licensed professional engineer, architect, or other design professional, as defined in the General and Supplementary Conditions.

AHJ: The local code and/or inspection agency (Authority) Having Jurisdiction over the work.

NRTL: Nationally recognized testing laboratory, as defined and listed by OSHA in 29 CFR 1910.7 (e.g., UL, ETL, CSA), and acceptable to the AHJ over this project.

Substitution: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor. Substitutions include Value Engineering proposals.

The terms "approved equal," "equivalent," or "equal" are used synonymously and shall mean "accepted by or acceptable to the Engineer as equivalent to the item or manufacturer specified."

C. PREBID SITE VISIT

Prior to submitting bid, visit the site of the proposed work and become fully informed as to the conditions under which the work is to be done. Failure to comply with this requirement shall not be considered sufficient justification to request or obtain extra compensation over and above the contract price.

D. MATERIAL AND WORKMANSHIP

Provide new material, equipment, and apparatus under this contract unless otherwise stated herein, of best quality normally used for the purpose in good commercial practice, and free from defects.

Pipe, pipe fittings, pipe specialties and valves shall be manufactured in plants located in the United States or certified to meet the specified ASTM and ANSI standards.

Work performed under this contract shall provide a neat and "workmanlike" appearance when completed, to the satisfaction of the Architect and Engineer.

The complete installation shall function as designed and intended with respect to efficiency, capacity, noise level, etc. Abnormal noise caused by rattling equipment, piping, ducts, air devices, and squeaks in rotating components shall not be acceptable.

Remove from the premises waste material present as a result of work, including cartons, crating, paper, stickers, and/or excavation material, not used in backfilling, etc. Clean equipment installed under this contract to present a neat and clean installation at the termination of the work.

Repair or replace public and private property damaged as a result of work performed under this contract to the satisfaction of authorities and regulations having jurisdiction. Provide all safety lights, guards, and warning signs required for the performance of the work and for the safety of the public.

Where a list is provided, manufacturers are listed alphabetically and not in accordance with any ranking or preference.

Where manufacturers are not listed, provide products subject to compliance with requirements from manufacturers that have been actively engaged in manufacturing the specified product for no less than 5 years.

Unless otherwise indicated, the General Contractor shall provide chases and openings in building construction required for installation of the systems specified herein. Contractors shall make all arrangements with the General Contractor with information where chases and openings are required.

Figured dimensions shall be taken in preference to scale dimensions. Contractor shall take his own measurements at the building, as variations may occur. Contractor shall be held responsible for errors that could have been avoided by proper checking and inspection.

Provide materials with trim that will properly fit the types of ceiling, wall, or floor finishes actually installed. Model numbers listed in the specifications or shown on the drawings are not intended to designate the required trim.

Work performed under this contract shall, at a minimum, be in conformance with applicable national, state and local codes having Jurisdiction. Equipment furnished and associated installation work performed under this contract shall be in strict compliance with current applicable codes adopted by the local AHJ, including any amendments and standards as set forth by the following:

- 1. National Electrical Code (NEC)
2. National Fire Protection Association (NFPA)
3. Underwriters Laboratories (UL)
4. Occupational Safety and Health Administration (OSHA)
5. American Society of Mechanical Engineers (ASME)
6. American Society of Heating, Refrigerating, and Air Conditioning Engineers (ASHRAE)
7. American National Standards Institute (ANSI)
8. American Society of Testing and Materials (ASTM)
9. Other national standards and codes where applicable.

Where the contract documents exceed the requirements of the referenced codes, standards, etc., the contract documents shall take precedence. Where conflicts between various codes, ordinances, rules, and regulations exist, comply with the most stringent.

Promptly bring all conflicts observed between codes, ordinances, rules, regulations, referenced standards, and these documents to the attention of the Architect and Engineer for final resolution. Contractor will be held responsible for any violation of the law.

Procure and pay for permits and licenses required for the accomplishment of the work herein described. Where required, obtain, pay for, and furnish certificates of inspection to Owner.

Store and protect from damage equipment and materials delivered to job site. For materials and equipment susceptible to changing weather conditions, dampness, or temperature variations, store inside in conditioned spaces. For materials and equipment not susceptible to these conditions, cover with waterproof, tear-resistant, heavy tarp or polyethylene plastic as required to protect from dewater, dust, dirt, paint, water, or physical damage.

Plug, seal, or cap open ends of ductwork and piping systems while stored and installed during construction when in use to prevent the entrance of debris into the systems. Remove temporary protection prior to starting equipment and turning the system over to the owner.

Materials, products, equipment, and systems described in the Bidding Documents establish a standard of required function, dimension, appearance and quality to be met by the proposed substitution. The base bid shall include only the products from manufacturers specifically named in the drawings and specifications. To request a substitution, request the Substitution Request Form from the Architect or Engineer. Complete and send the Substitution Request Form for each material, product, equipment, or system that is proposed to be substituted.

Unless stated otherwise in writing to the Engineer by the Contractor, Contractor warrants to the Engineer, Architect, and Owner the following:

- 1. Proposed substitution has been fully investigated and determined to meet or exceed the specified Work in all respects unless stated otherwise in the substitution request.
2. Proposed substitution complies with the Contract Documents and will produce indicated results, including functional clearances, maintenance service, and sourcing of replacement parts.
3. Proposed substitution has received necessary approvals of authorities having jurisdiction.
4. Same warranty will be furnished for proposed substitution as for specified Work.
5. If accepted substitution fails to perform as required, Contractor shall replace substitute material or system that with originally specified and bear costs incurred thereby.

Coordination, installation and changes in the Work as necessary for accepted substitution will be complete in all respects.

No substitutions will be considered unless the Substitution Request Form is completed and attached with the appropriate substitution documentation. No substitution will be considered prior to receipt of bids unless written request for approval to bid has not been relayed by the Engineer at least ten (10) calendar days prior to the date for receipt of bids.

If the proposed substitution is approved prior to receipt of bids, such approval will be stated in an addendum. Bidders shall not rely upon approvals made in any other way. Verbal approval will not be given. No substitutions will be considered after the contract is awarded unless specifically provided in the contract documents.

Assemble and submit for review shop drawings, material lists, manufacturer product literature for equipment to be furnished, and items requiring coordination between contractors under this contract. Provide submittals in sufficient detail so as to demonstrate compliance with these contract documents and the design concept. Prior to transmitting submittals, verify that the equipment submitted is mutually compatible and suitable for the intended use, will fit the available space, and maintain manufacturer recommended service clearances.

Transmit submittals as early as required to support the project schedule. Allow for two weeks Engineer review time, plus to/from mailing time via the Architect, plus a duplication of this time for resubmittal, if required. Only resubmit those sections requested for resubmittal.

Submittals shall contain the project name, applicable specification section, submittal date, equipment identification acronym as used on the drawings, and the Contractor's signature certifying that the submittal has been checked by the Contractor, complies with the drawings and specifications, and is coordinated with other trades. Manufacturer product literature shall include shop drawings, product data, performance sheets, samples and other submittals required by this division. Highlight, mark, list, or indicate the materials, performance criteria, and accessories that are being proposed. General product catalog data not specifically noted to be part of the specified product will be rejected and returned without review.

Submittals and shop drawings shall not contain the firm name, logo, seal, or signature of the Engineer. They shall not be copies of the work product of the Engineer. If the Contractor desires to use elements of such product, refer to paragraph "Electronic Drawing Files" for procedures to be used.

Separate submittals according to individual specification sections. Illegible submittals will be rejected and returned without review. Catalog data shall be properly bound, identified, indexed and tabbed in a 3-ring binder. Each item or model number shall be clearly marked and accessories indicated. Label the equipment identification acronym or number as used on the drawings and include performance curves, capacities, sizes, weights, materials, finishes, wiring diagrams, electrical requirements and deviations from specified equipment or materials.

Provide the quantity of submittals required by Division 01. If not indicated and hard-copy sets are provided, submit a minimum of six (6) copies. Refer to Division 01 for acceptance of electronic submittals for this project. For electronic submittals, Contractor shall submit the documents in accordance with the procedures specified in Division 01. Contractor shall notify the Architect and Engineer that the submittals have been posted. If electronic submittal procedures are not defined in Division 01, Contractor shall include the website, user name, and password information for the equipment identification acronym or number as used on the drawings.

The checking and subsequent acceptance of submittals by the Engineer and/or Architect shall not relieve the Contractor from responsibility for deviations from the drawings and specifications, errors in dimensions, details, size of members, or quantities, omissions of components or fittings, coordination of electrical requirements, and not coordinating items with actual building conditions and adjacent work.

In preparation of shop drawings or record drawings, Contractor may, at his option, obtain electronic drawing files in AutoCAD or DXF format on CD-ROM disk, DVD disk, flash drive or direct download, as desired, from the Engineer for a shipping and handling fee of \$200 for a drawing set up to 12 sheets and \$15 per sheet for each additional sheet. Contact the Architect for written authorization and Engineer for the necessary release agreement form and to specify shipping method and drawing format. In addition to payment, the written authorization from the Architect and release agreement form from the Engineer must be received before electronic drawing files will be sent.

During progress of the work in this division, Contractor shall maintain an accurate record of all changes made during the installation of the system. Upon completion of the work, accurately transfer all record information to three identical sets of the approved shop drawings. Insert one set into each copy of the manual described below.

See Division 01 and General Conditions for additional information.

During the course of construction, collect and compile a complete brochure of equipment furnished and installed on this project. Include operational and maintenance instructions, manufacturer's catalog sheets, wiring diagrams, parts lists, approved submittals and shop drawings, warranties, and descriptive literature as furnished by the equipment manufacturer. Include an inside cover sheet that lists the project name, date, Owner, Architect, Engineer, General Contractor, Sub-Contractor, and an index of contents.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Refer to Division 01 for acceptance of electronic manuals for this project. For electronic manuals, refer to paragraph "Submittals" for requirements.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Papers, loose-leaf binders, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Submit signed and sealed drawings that indicate the design and installation requirements of pre-engineered roof supports can withstand the design criteria listed. Include installation requirements for anchoring to the roof structure. The Engineer is not responsible and will not provide the seal and signature. Deliver submittal to the local AHJ for approval prior to installation of the contractor provided, pre-engineered roof supports.

Refer to Architectural documents for specification of access panels and doors.

Provide access doors for all concealed equipment and duct piping assemblies that require service where indicated or as required, except where above lay-in ceilings. Access doors shall be adequately sized for the devices served with a minimum size of 18 inches x 18 inches. Access doors must be of the proper construction for type of construction in which it is installed. Obtain Architect's approval of type, size, location and color before ordered. Provide factory-fabricated and assembled units, complete with attachment devices and fasteners ready for installation, concealed hinges, flush screwdriver-operated cam lock, and anchor straps. Provide access doors manufactured by Greenheck, Milcor, Thus, Zum, or equal.

Provide sleeves for pipes passing through above grade concrete or masonry walls, concrete floor or roof slabs. Sleeves are not required for core drilled holes in existing masonry walls, concrete floors or roofs. Provide 10 gauge galvanized steel sleeves for sleeves 6 inches and smaller. Provide galvanized steel metal sleeves for larger than 6 inches. Schedule 40 PVC sleeves are acceptable for installation in areas without return air plenums.

Seal elevated floor, exterior wall and roof penetrations watertight and weathertight with non-shrink, non-hardening commercial sealant. Pack with mineral wool and seal both ends with minimum of 1/2 inch of sealant.

Seal around penetrations of fire rated assemblies. Coordinate fire ratings and locations with the architectural drawings. Refer to architectural specifications for fire stoppings. Provide a product schedule for UL listing, location, wall or floor rating and installation drawing for each penetration fire stop system.

Extend pipe insulation for insulated pipe through floor, wall and roof penetrations, including fire rated walls and floors. The vapor barrier shall be maintained. Size sleeve for a minimum of 1 inch annular clear space between inside of sleeve and outside of insulation.

Provide prefabricated roof curbs where pipes and/or ductwork penetrate elevated slabs or the roof of the exterior. Provide cover curb of weather-resistant material and seal duct or pipe penetrations through the cover. Provide pipe collar of weather-resistant material with stainless steel pipe clamps for piping penetrations.

Provide box frames for rectangular openings welded 12 gauge galvanized steel attached to forms and of a maximum dimension established by the Architect. Notify the General Contractor or Architect before installing any box openings not shown on the Architectural or Structural drawings.

Seal concrete or masonry exterior wall penetrations below grade with "wall pipes" and mechanical sleeve seals. Provide cast iron "wall pipes" with integral watertight ring manufactured by Jay R. Smith, Josam, Wade, Watts or Zum. Provide modular mechanical sleeve seals, manufactured by Calpico, Metraflex, or Thunderrite / Link Seal.

Seal elevated concrete slab with water proof membrane penetrations with "wall pipes" and water proof sealant. Secure waterproof membrane flashing between "wall pipe" clamping flange and clamping ring. Provide cast iron "wall pipes" with integral watertight ring manufactured by Jay R. Smith, Josam, Wade, Watts or Zum.

Provide sleeves for horizontal pipe passing through or under foundation. Sleeves shall be cast iron soil pipe two nominal pipe sizes larger than the pipe served.

Provide Schedule 40 PVC pipe sleeves for vertical pressure pipe passing through concrete slab on grade. Sleeves shall be one nominal pipe size larger than the pipe served and two pipe sizes larger than pipe served for ductile iron pipes with restraining rods. Seal water-tight with silicone caulk.

Provide 1/2 inch thick cellular foam insulation around perimeter of non-pressure pipe passing thru concrete slab on grade. Insulation shall extend to 2 inches above and below the concrete slab.

Sealants and accessories shall have fire-resistance ratings indicated, as established by testing identical assemblies in accordance with UL 2079 or ASTM E 814, or other NRTL acceptable to AHJ.

Manufacturers: Hill, RectorSeal, Specified Technologies Inc., United States Gypsum Company, or 3M corp.

Through and Membrane Penetration Firestopping Systems Product Schedule. Provide UL listing, location, wall or floor rating, and installation drawing for each penetration fire stop system.

Where project conditions require modification to qualified testing and inspecting agency's illustrations for a particular firestopping condition, submit illustration, with modifications marked, approved by penetration firestopping manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly, include qualifications data for testing agency.

Provide motors and starter equipment where not furnished with the equipment package. Motors shall have copper windings, Class B insulation, and standard squirrel cage with starting torque characteristics suitable for the equipment served. Motors controlled by variable frequency drives shall have a minimum rise times in accordance with NEMA MG-1, Part 31. Motors 5 horsepower and larger controlled by variable frequency drives shall be provided with a shaft grounding system equal to Aegis SGR Bearing Protection Ring, Inpro/Seal Current Overvoltage Ring (CDR) or approved equal. Motors for air handling equipment shall be selected for quiet operation. Each motor shall be checked for proper rotation after electrical connection has been completed. Provide drip-proof enclosure for locations protected from weather and not in air stream of fan, and totally enclosed fan cooled enclosures for outdoor exposure to weather. Motors shall be manufactured by Century, General Electric, Louis Allis, Westinghouse, or approved equal.

Provide every motor, except fractional horsepower single phase motors with an approved type of "built-in" thermal overload protection, with a motor starter. Each starter shall be provided with overload heaters sized to the motor rating, and every three phase motor starter shall have overload heaters in each phase. Ambient compensated heaters shall be installed whenever necessary. Unless noted otherwise, motor starters shall be furnished by the Division 23 Contractor for installation and connection by the Division 26 Contractor. Starters shall be Allen-Bradley, Clark, Furnas, Square D, or approved equal.

Provide PWM variable frequency drives (VFD) to control fan or pump motors as indicated on the drawings. Provide VFD as manufactured by AC Technology, Asea Brown Boveri, Danfoss, Reliance Electric, or Yaskawa. Include an integral, door-interlocked input circuit breaker or fused disconnect which may be padlocked in the "OFF" position.

A magnetic control manual bypass integral to each drive. Provide two magnetic controllers, mechanically and electrically interlocked, to isolate the inverter output from line voltage. The inverter input shall be isolated by either a third magnetic controller or a second disconnect switch to isolate the inverter from the power source while still operating the motor. The bypass shall include a 120/160 control transformer, fused on both the primary and secondary, and bi-metallic thermal motor overload relays with adjustable trip settings.

Provide input AC line reactors without exception. Reactors shall be minimum 3 percent inductance, and "K" rated per IEEE C57-110 for harmonic current content. Reactors shall be integral to the drive enclosure without need for field wiring.

The VFD shall have an RS-485 port as standard. The standard protocols shall be Johnson Controls N2 bus, Modbus, and Siemens Building Technologies FLN. Optional protocols for BACnet, DeviceNet, Ethernet, LonWorks, and Profibus shall be available. Each individual drive shall have the protocol in the base VFD. The use of third party gateways and multiplexers is not acceptable. All protocols shall be "certified" by the governing authority. Use of non-certified protocols is not allowed. The VFD shall allow the DDC system to control the digital and analog outputs of the drive via the serial interface. This control shall be independent of any VFD function. In addition, all the digital and analog inputs of the drive shall be capable of being monitored by the DDC system.

Drive supplier shall provide jobsite start-up, Owner training, and a one-year parts and on-site labor warranty. Multiple visits shall be included to allow for tuning and troubleshooting of the controls system as required.

High voltage wiring is defined as 50 Volts or higher. Low voltage wiring is defined as less than 50 Volts. Line voltage wiring shall be provided by Division 26. Line voltage control and interlock wiring for mechanical systems shall also be provided by Division 26. Low voltage control wiring shall be provided by Division 23. Furnish wiring diagrams to Division 26 as required for proper equipment hookup. Coordinate with Division 26 the actual wire sizing amps for mechanical equipment (from the equipment nameplate) to ensure proper installation.

Provide power and communication wiring with transient protection in accordance with IEEE C62.41.2. All control and interlock wiring shall comply with the NEC. Control wiring shall be sized to accommodate the voltage drop associated with the distance between the control device and the controller. Control wiring shall be UL rated for plenum installation in accord NEC Class 1 (line voltage) wiring shall be UL listed in approved raceway according to the NEC and Division 26 requirements. Maximum allowable voltage for control wiring shall be 120 V. All low-voltage wiring shall meet NEC Class 2 requirements. Low-voltage power circuits shall be sub-fused when required to meet Class 2 current limit.

Conduit for Control Wiring: EMT with compression fittings, cold rolled steel, zinc coated or zinc-coated rigid steel with threaded connections.

Pull and Junction Boxes: Size according to number, size, and position of entering raceway as required by National Electrical Codes. Enclosure type shall be suited to location.

Install wiring parallel to building lines wherever possible. Conceal all control wiring in finished rooms. Do not install Class 2 wiring in raceway containing Class 1 wiring. Boxes and panels containing high class 1 wiring and equipment may not be used for low voltage wiring except for the purpose of interlocking the two wires (e.g., relays and transformers). All wire-to-device and wire-to-wire connections shall be made at a terminal block or terminal strip. All runs of communication wiring shall be insulated length when that length is commercially available. Verify the integrity of the entire network following the cable installation. Use appropriate test measures for each particular cable. Label all wiring and cabling at each end within 2 inches of termination with the controller termination number. Label control devices used in the system with permanent labels using the identifiers that match the record documents.

Provide necessary equipment and accessories that are not provided by the equipment supplier or Owner to complete installation of equipment furnished by others in locations as indicated on the drawings, specified herein, or both. Equipment and accessories not provided by the equipment supplier may include, but not be limited to fuses, vents, intakes, associated roof jacks and caps to outdoors, dampers, in-line fans, roof fans, control interlocks, etc. as required for proper operation of the complete system in accordance with the manufacturer's instructions.

O. VIBRATION ISOLATION

Provide vibration isolation equipment and materials by a single manufacturer. If type and deflection for specific equipment is not specified within the contract documents, reference ASHRAE Handbook "HVAC Applications" or provide per manufacturer's recommendations. Approved manufacturers include Caldyn, Kinetics Noise Control, Mason Industries, Inc., Vibration Eliminator Co., Inc., Vibro-Mixing and Controls, or Vibro-Acoustics, provided their systems are in compliance with the specified design and performance requirements.

General Requirements: Select vibration isolators by the weight distribution to produce uniform deflection. Vibration isolators shall have other known un-deflected heights or calibration markings so that, after adjustment, the static deflection can be verified, thus determining that the load is within the proper range of the isolator. Isolators shall operate in the linear portion of their load versus deflection curves. Slightly under excess capacity without exceeding coil bound. Coat vibration isolators with factory-applied paint. Coat vibration isolators exposed to weather and other corrosive environments with factory-applied corrosion resistance protection. Install and adjust vibration isolators in accordance with manufacturers written instructions.

Pipe connections: Provide flexible connectors for piping system connections on equipment side of shutoff valves for all pumps, mechanical equipment supported or suspended by spring isolators, and where indicated on drawings. Flexible flexible piping connectors from stainless steel or other materials as suitable for system fluid. Flexible piping connectors shall be bellows, spherical or braided hose type as recommended by the manufacturer for the application.

Isolator Types:

1. Type WP (Waffle Pads): Provide 5/16 inch thick neoprene pads ribbed or waffled on both sides. Manufacture pads with bridge grooves and select for a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of 0.05 inches. Incorporate steel load spreading plates where required between the equipment and the neoprene pad to provide selected deflection. If the isolator is bolted to the structure, install a neoprene mounting sleeve under the bolt head between the steel washer and the base plate to prevent metal to metal contact. Provide Mason Industries Type W or equal.
2. Type SPNH (Spring and Neoprene Hangers): Provide a steel hanger box containing a laterally stable, double-deflecting neoprene isolator in series with a steel spring. Design springs so ratio of the horizontal to vertical spring constant is between one and two. The spring diameter shall be not less than 80 percent of the compressed height of the spring at rest load. Loaded springs shall operate within the linear portion of their load versus deflection curve over a deflection range of not less than 50 percent above design deflection. Size hanger and hanger box hole size shall be large enough to permit the hanger rod to swing through a 90 degree arc. Include a neoprene bushing to prevent contact between the lower hanger rod and hanger box and short-circuiting the isolating function. The neoprene element shall have a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of not less than 0.4 inches. Unless otherwise specified, the static deflection of SPNH hangers shall be 2 inches. Provide SPNH hangers with 1 inch static deflection for water source heat pumps and fan-powered VAV terminal units. When installed, do not cock the spring element and do not allow the hanger box to rotate through a full 360 degree arc without encountering obstructions. Provide Mason Industries Type SPNH or equal.
3. Type NR (Neoprene Bushing): Provide neoprene, rubber-in-shear bushings for lightweight (less than 100 pounds), suspended equipment supported from structure with all thread rod and angle iron or Unistrut. Select for a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of 0.15 inches. Provide Mason Industries Type HMIB or equal.

P. AIR FILTERS

Provide AAF/Flanders Perfect Pleat HC-M8, Camfil FX 3030, pleated, throwaway type filters, minimum MERV 8, or similar as manufactured by Air Filter, Inc., Bioclimatic, Columbus, Koch, or approved equal, unless otherwise indicated.

Temporary filters used to protect openings in ductwork and inside equipment when permanent HVAC equipment is used during the construction period shall be pleated, throwaway type filters, minimum MERV 6.

Q. REFRIGERANT AND OIL

Provide full refrigerant and oil charge in new air conditioning refrigeration systems, and maintain it for full term of the guarantee.

R. IDENTIFICATION

Provide manufacturer's standard pre-printed, semi-rigid snap-on or permanent adhesive, pressure-sensitive vinyl pipe markers. Color code pipe markers to comply with ANSI A13.1.

Install pipe markers on each HVAC piping system and include arrows to show normal direction of flow.

Locate pipe markers and color bands wherever piping is exposed to view in occupied spaces, machine rooms, accessible maintenance spaces (shafts, tunnels, plenums), and exterior non-enclosed locations.

Provide plastic laminate or brass valve tag on every valve, cock and control device in each HVAC piping system; exclude check valves within factory-fabricated equipment units, and shut-off valves at HVAC terminal devices and similar rough-in connections of end-use features and units.

Provide manufacturer's standard laminated plastic, color coded equipment markers. Conform to the following color code: Green for Cooling; Yellow for Heating; Yellow/Green for combination Cooling and Heating; Brown for Energy Reclamation; Blue for other equipment types. Conform to ANSI A13.1 for Hazardous Equipment.

Provide stenciled signs for equipment identification at Contractor's option or where distance of required identification requires lettering larger than 1 inch height. Stencil paint shall be exterior type, oil-based, alkyl enamel, minimum 1/4-inch height or greater as required for long distance identification, white or black color for best contrast.

Provide duct markers or provide stenciled signs and arrows indicating ductwork service and flow direction in black or white lettering for best contrast with duct or insulation color. Locate markers maximum 50 feet from each duct side and within 5 feet of control and balancing dampers or branch ducts more than 25 feet length and within 5 feet on each side of wall, floor, and ceiling penetrations. Provide additional markers in congested areas or at multiple duct runs as required for clarity.

A. DUCT INSULATION, DUCTWORK, ACCESSORIES, FLUES AND FANS

1. DUCT INSULATION

Provide fiberglass duct liner with fibers firmly bonded together with a thermosetting resin. Liner surface shall serve as a barrier against infiltration of duct and air flow resistance, and shall be cleanable using duct cleaning methods and procedures. Provide fiberglass equipment outlined by North American Insulation Manufacturers Association (NAIMA) duct cleaning guide. Install with liner adhesive and mechanical fasteners in accordance with manufacturer's instructions and recommendations. Ductwork signs shown on drawings are inside clear dimensions. Increase sheet metal by liner thickness in both directions where liner is installed.

Provide rectangular liner conforming to ASTM C1071, Type I or II that is 1-1/2 inch thick, 1-1/2 pound density, minimum R-6.0 Certainteed Corp. "Toughguard" or equivalent, Johns Manville, Owens-Corning, or Krauf.

Provide round liner that is 1-1/2 inch thick, 4 pounds density, minimum R-6.0 Johns Manville "Spiracoustic Plus" or equivalent, Certainteed or Owens-Corning.

Provide liner on the following interior air ducts and where specified on the drawings:

1. Exposed round and rectangular supply ductwork.
2. Exposed round and rectangular return ductwork.

At interface of lined and wrapped ductwork, overlap lined ductwork at least 2 feet beyond wrapped insulation.

Cover concealed, rigid ductwork with ASTM C555, Type II flexible fiberglass insulation. Installed insulation shall be 2 inch thick, 3/4 pound density, minimum R-6.0 duct wrap, Certainteed or equivalent Johns Manville, Owens-Corning, or Krauf with heavy-duty foil-scrim-kraft facing, and with joints taped with 3 inch wide foil tape as follows:

1. Round and rectangular supply and return air ductwork.
2. Unlined Round and rectangular outside air ductwork.
3. Round and rectangular exhaust and relief air ductwork within 10 feet of exterior discharge.

Cover Outdoor air, Exhaust air and Relief air plenums connected to exterior louvers with 1-1/2 inch thick, 1.5 pound density, rigid fiberglass insulation conforming to ASTM C812, Class 2.

Insulating materials, adhesives, coatings, etc., shall not exceed flame spread rating of 25 and smoke developed rating of 50 per ASTM E834. Containers for mastics and adhesives shall have UL Label.

Provide supply and return ductwork located exterior to the building, insulation shall be minimum R-8.0. Provide insulation and jacket in accordance with one of the following three options:

1. Exterior insulation and jacket consisting of 2 inch thickness of Armauff flexible elastomeric insulation or equivalent meeting ASTM C534 with integral UV resistant cladding laminated at factory. Cover all seams with Armauff seal tape.
2. Exterior insulation consisting of 2 inch thickness of flexible elastomeric insulation meeting ASTM C534 or 3 lb density rigid fiberglass meeting ASTM C612, and jacket consisting of 2/8 ounce corrugated aluminum jacket with aluminum fitting covers and minimum three aluminum attachment bands per section.
3. Exterior insulation consisting of 2 inch thickness of flexible elastomeric insulation meeting ASTM C534 or 3 lb density rigid fiberglass meeting ASTM C612, and jacket consisting of 15.5 mils thick Venturaclad Plus UV resistant cladding.

Install exterior ductwork with sufficient slope to ensure that water cannot pond anywhere on the duct. Drainage must be achieved by sloping ductwork -- not by varying the insulation thickness. Locate longitudinal seams of outer shell (aluminum, flexible elastomeric, or cladding as applicable) at bottom of duct. Install cladding in strict conformance with cladding manufacturer's instructions.

B. DUCTWORK

Provide galvanized steel ductwork and housings as shown on drawings. Construct ductwork including fittings and transitions in conformance with current SMACNA standards relative to gauge, bracing, joints, etc. Minimum thickness of duct shall be 26-gauge sheet metal. Reinforce housings and ductwork over 30 inches with 1/4 inch angles not less than 5'-0" on centers, and closer if required for sufficient rigidity to prevent vibration. Support horizontal runs of duct from strap iron hangers on centers not to exceed 8'-0". Do not support ceiling grids, conduits, pipes, equipment, etc. from ductwork. Coordinate routing of ductwork with other contractors such that piping, electrical conduit, and associated supports are not routed through the ductwork.

Provide pre-engineered roof duct supports supports by Cooper B-Line, Elite Components, ERICO, FNV, Mira, PHD Manufacturing, PHP Systems, Roof Top Box, Unistrut (Akrotes), Zet Fostler, or approved equal. Support ductwork on the roof with pre-engineered roof duct supports that rest on top of the roofing membrane, not requiring any attachment to the roof structure and not penetrating the roofing assembly, with embedded support fixtures as required to support the duct. Provide steel pedestal type supports with minimum 18x18 inch thermoplastic or rubber base or 4 inch wide closed-cell polyethylene block with length as required. Maintain minimum 6 inches clearance under duct to finished roof surface.

Coordinate with the pre-engineered roof duct support manufacturer to anchor the duct supports directly to the roof structure in accordance with the manufacturer's installation instructions or provide intermediate duct supports engineered to meet the wind resistance and seismic design criteria. Reference Section, "PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS".

Construct non-VAV supply ducts to meet SMACNA positive pressure of 2 inches w.g. Construct Return, Outdoor and Exhaust ductwork upstream of fans to meet SMACNA negative pressure of 1 inch w.g. Construct exhaust ductwork downstream of fans to meet SMACNA positive pressure of 1 inch w.g.

Provide mill phosphatized or galvanized finish for exposed ductwork to be field painted. Shop treated sheet metal shall have galvanized metal primer applied in the shop after fabrication and prior to shipping.

Seal ductwork with heavy liquid sealant, Hardcoat Tongrolp 601, Design Polymer DP 1010, United Mopli duct sealer or approved equal, applied according to manufacturer's instructions. Seal all longitudinal and transverse ductwork joints airtight to meet SMACNA Seal Class A. Tapes and mastics shall be listed and labeled in accordance with UL 181A.

Provide elbow turns, turns, and offsets with a minimum centerline radius of 1-1/2 times the duct width. Where space does not permit full radius elbows, provide short radius elbows with a minimum of two continuous splitter vanes. Vanes shall be the entire length of the bend. Provide mirrored elbows where space does not permit radius elbows, where shown on the drawings, or at the option of the contractor with the engineer's approval. Mirrored elbows less than 45 degrees shall not require turning vanes. Mirrored elbows 45 degrees and greater shall have single thickness turning vanes of same gauge as ductwork, rigidly fastened with guide strips in ductwork. Vanes for mirrored elbows shall be provided in all supply and exhaust ductwork and in return and outside air ductwork that has an air velocity exceeding 1000 fpm. Do not install vanes in grease ductwork. The use of square throat radius bend elbows is prohibited. Remove and replace all installed elbows of this type with an approved elbow or an additional cost to the owner.

Connect ducts to vibrating equipment and when transitioning between two different metallic duct materials (e.g., aluminum to galvanized steel) by means of flexible connectors. Flexible connectors shall be neoprene coated glass cloth canvas connections, Duro-Dyn, Elgen, Ventilatoric or equal. Flexible connectors shall have a flame spread of 25 or less and smoke developed rating not higher than 50. Make airtight joints and install with minimum 1-1/2 inches slack.

Provide balancing dampers, manufactured by Gesco, Greenheck, Louvers & Dampers, Nalor Industries, Pottoff, Ruskin, Tamco, or approved equal, where shown on drawings and wherever necessary for complete control of air flow. Splitter dampers shall be controlled by locking quadrants; provide Young Regulator or Venlok end bearings for the damper rod. Rectangular volume dampers shall be opposed blade interlocking type. Round volume dampers shall be single-blade type consisting of circular blade mounted to a shaft. Provide Firemaster model ST-0 or equal 45 degree rectangular/round side takeoff fitting with model BCO damper with locking quadrants and insulation build out for round ductwork branch takeoffs to individual air devices. Omit damper at takeoff fitting when damper is located downstream of takeoff.

Where access to dampers through a hard ceiling is required, provide a concealed, remote cable-operated, butterfly-type volume damper assembly with external remote operator. Damper shall include rolled lead stiffeners, reinforced blades, reinforced blade, self-lubricating bearing, and remote operator mounting plate. External operator shall attach to damper as a single piece with no linkage adjustment required. Damper shall be adjustable through the diffuser frame with standard 1/4 inch nutdriver or flat screwdriver. Provide positive, direct, two-way damper control with no sleeves, springs or screw adjustments to come loose after installation. Provide cable length to span the distance from the damper to the remote operator location. Install damper in branch duct. Do not install in diffuser neck. Install remote operator on the back of the diffuser frame or side of a small diameter plenum. Support cable assembly to diffuser neck and limit travel intervals. Where applicable, provide a ceiling cap with cover plate made of aluminum. The ceiling cap may be used for access to cable operator. Provide round dampers by Metropolitan Air Technology model RT-250, Young's Regulator model 5020-1200, or approved equal. Provide rectangular dampers by Metropolitan Air Technology model RT-200, Young's Regulator model 5020-1200, or approved equal. Provide remote cable control by Metropolitan Air Technology model RT-WGA, Young's Regulator model 270-275, or approved equal.

Round or oval ductwork shall be FlatKGroup Semco, United, Hercules Industries of equal, sheetmetal, with smooth interior surface, with low pressure (duct pressure class up to and including 2 inches w.g.) Round ductwork gauges per the following table (reference SMACNA HVAC duct construction standards for gauges when pressures exceed 2 inches w.g.):

Size	Duct Gauge	Fitting Gauge
14" & under	26	24
14" thru 26"	24	22
28" thru 36"	22	20
38" thru 50"	20	20
52" thru 60"	18	18

Levis & Lambert, Linx Industries Lindal Safe, or approved equal factory-manufactured round ductwork and fittings may be substituted for specified round branch ductwork, at Contractors option. Heavy liquid joint sealant may be omitted on factory-manufactured round ductwork.

Low pressure (duct pressure class up to and including 2 inches w.g.) Fittings 24 inches in diameter and less shall be prefabricated, spot-welded and internally sealed. Continuously welded fittings larger than 24 inches in diameter. Fitting gauge shall be 22 gauge for 36 inch fittings and under; 20 gauge for larger sizes. 90 degree tees shall be conical type. Seal longitudinal and transverse ductwork joints airtight with heavy liquid sealant applied according to manufacturer's instructions. Provide gauge thickness in medium pressure (duct pressure class 3 inches to 8 inches w.g.) ductwork as recommended by SMACNA.

C. FLEXIBLE DUCT

Low pressure (duct pressure class up to and including 2 inches w.g.) and medium pressure (duct pressure class 2.1 inch to 6 inches w.g.) flexible duct type BS, Thermalex type G-M, M-ME, JPL, type Silver Jacket, or equal (fire retardant polyethylene) protective vapor barrier, UL 181 Class 1, acoustical insulated duct, R-6.0 fiberglass insulation. Provide CPE liner with steel wire helix mechanically locked or permanently bonded to the liner.

Flexible duct runs shall not exceed 5 feet in length, and shall be installed fully extended and straight as possible avoiding tight turns. Install flexible duct in accordance with manufacturer's instructions. Support flexible duct at maximum 5 feet on center and within 6 inches of bends. Bends shall not exceed a centerline radius of one duct diameter. Duct sag shall not exceed 1/2 inch. Supporting material in direct contact with the duct shall not be less than 1-1/2 inches in width.

Connect flexible duct to rigid metal duct or air devices as recommended by the manufacturer. At a minimum, install two wraps of duct tape around the inner core connection and a metallic or non-metallic clamp over the tape and two wraps of duct tape or a clamp over the outer jacket. Duct clamps shall be labeled in accordance with UL-181B and marked 181B-C. Duct tape shall be labeled in accordance with UL 181B and marked 181B-FX.

D. PLASTIC FLUE GAS VENTS

Provide UL 1738 listed plastic flue gas vents, with positive or negative flue pressures complying with NFPA 211 and suitable for condensing gas applications. Provide PVC system by IFPEX "System 1738", or Polypropylene system by Centrotherm "Innoflow" or equal by Nova Flex Group "Z-DENS".

Vents and combustion air ducts for condensing type appliances shall be Schedule 40 PVC pipe and socket fittings meeting ASTM D2855 and UL 1738, manufactured by IFPEX. Use solvent cement meeting ASTM D2854 and make joints in accordance with ASTM D2855.

E. AIR DEVICES

Provide air devices as scheduled on drawings, manufactured by Carnes, Krueger, Metalarie, Nalor Industries, Price, TTUs, or Tuttle & Bailey. Select air device with outlet velocity higher than NC-30 unless otherwise shown. Provide devices with a soft plastic gasket to make an airtight seal against the mounting surface. Coordinate final location, frame, and mounting type of air devices with Architectural reflected ceiling plans.

Submit complete shop drawings including information on noise level, pressure drop, return, CFM for each air device, styles, borders, etc. Clearly marked with specified equipment number. Submit samples of each air device as requested by the Engineer.

Provide wall return air grilles and exhaust air registers with horizontal 35 or 45 degree angle vision-proof bars. Provide concealed fasteners for wall mounted registers and grilles. Provide floor supply air registers of aluminum alloy vane type with 0 degree deflection. Provide opposed blade dampers for supply air registers and exhaust air registers unless indicated otherwise.

Provide ceiling mounted air devices of lay-in or surface mounted type as required to be compatible with ceiling construction. Provide ceiling diffusers and grilles with white enamel finish unless noted otherwise.

Provide linear slot diffusers of standard one-piece lengths up to 6-feet and furnish in multiple sections greater than 6-feet. Join multiple sections with a 1/8 inch wide gasket to form a continuous slot appearance. For installations in a hard ceiling, install diffuser per manufacturers installation instructions prior to installation of drywall. Contractor shall use manufacturer's hard ceiling clips for mounting to ceiling framing. Screws through face of linear slot diffuser are not acceptable. Provide alignment components by the manufacturer. Provide plenums by the linear diffuser manufacturer. Plenums shall be internally insulated with the manufacturer with minimum 1/4 inch thick, fiberglass insulation.

F. CONTROL DAMPERS

Provide factory fabricated, parallel blade control dampers sized as shown on the drawings and as specified. Individual damper sections shall be made of aluminum with maximum blade width of 6 inches. Frame construction shall be minimum 16 gauge galvanized steel for rectangular dampers, 20 gauge for round, 1/8 inch thick for aluminum, with flanges for duct mounting. Provide elastomeric or neoprene seals, mechanically attached and field replaceable. Provide a minimum of one damper actuator per section. Test damper performance in accordance with AMCA 500-2.

Provide modulating dampers with linear flow characteristics. Size modulating dampers based on the smaller of 1,500 FPM through the damper or full open air pressure drop of 1.1 inches W.G. Size low-position dampers full duct size and select to maintain pressure drop. Motorized dampers used for ventilation air intake, exhaust air, or relief air shall have leakage rates not to exceed 4.0 CFM/square foot at closed position at 1 inch W.G. pressure differential.

Provide dampers as manufactured by Greenheck, CESCO, Pottoff, Nalor, or Ruskin. Reference manufacturer with model number for outside air dampers is Ruskin CD-50 constructed of aluminum, and all other applications is Ruskin CD-35 constructed of galvanized steel.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee tight close-off of dampers against system pressure encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruption as required by the control systems specified on the drawings. Damper operators shall be manufactured by Bellini, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

G. EXHAUST AIR SYSTEMS

Provide roof mounted exhaust fans as scheduled on the drawings, or equal ACME, Carnes, Cook, Greenheck, Pennbray, or Twin City Fans complete with aluminum housing, aluminum centrifugal wheel, motor with integral thermal overload protection, disconnect switch mounted inside the housing, bitrocked drain and pate prefabricated roof curb with minimum height of 12 inches for roofs with no insulation, 14 inches for roofs with insulation or as scheduled on the drawings. Exhaust fans serving Type I kitchen exhaust hoods shall discharge a minimum of 40 inches above the roof surface, shall have hinged access including access for fire inspection and cleaning per NFPA 96, grease drain through floor filled with replaceable, absorbent material or replaceable cup and pad with absorbent material which absorbs grease and rejects water, and insulated curb, and shall be installed in accordance with NFPA 96 and local codes.

H. KITCHEN EXHAUST AIR SYSTEMS

Install kitchen grease exhaust package furnished by the owner. System includes kitchen hood, grease exhaust fan, packaged DOAS unit and a mechanical or electrical gas shutoff valve provided with the kitchen exhaust system to shutoff fuel or power source to cooking equipment upon detection of fire. Valve shall have a clearly marked open/closed indicator.

Provide ducts connecting Type I exhaust hoods to exhaust fans made of #16 gauge black iron with continuously welded joints and clean-out doors. Provide transition of connection to fan with opening size equal to or greater than the venturi opening of the fan inlet. Provide gasket at flanged connection to fan rated for 1500 degrees Fahrenheit and grease applications. Enclose duct in fireproof enclosure per locally adopted mechanical code or, if approved by local code official, in fire rated wrap insulation. Insulation shall be minimum two-hour rated duct wrap insulation for Type Hood grease exhaust duct applications and shall conform to ASTM E2336 as required by code with IBC. Insulation shall be flexible wrap enclosure rated for minimum 2000 degrees Fahrenheit and for zero clearance to combustibles. Insulation shall be non-mineral wool, passive, low bio-persistent fiber totally encapsulated on all sides with aluminum foil. Insulation shall be as manufactured by Certainteed, Thermo Ceramics, Unifrax or JM. Slope duct back towards hood at minimum of 1/4 inch per linear foot. At Contractor's option, a UL listed concrete ductwork package that complies with UL 1978 standard for grease ducts may be used in lieu of the welded black iron duct for connecting hood to exhaust fan. Ductwork package shall be as manufactured by Meta-Fab, Schebler, Selkirk, or approved equal. Provide manufacturers UL listing number and verification certificate as a part of the shop drawing submittal. Install duct package in strict conformance with manufacturer's instructions and recommendations.

All portions of grease duct systems shall be tested for leakage in accordance with the "Grease Duct Test" paragraph of the IMC. Leakage tests shall be by water leakage type or equivalent test methods as approved by the local code official to determine that all joints are liquid tight. Water leakage test shall be performed by Environmental Corporation of America or owner approved testing agency and shall be in accordance with the IMC. Tests include leak detection, and if necessary, the defective shall be repaired and retested until satisfactory results are obtained. The contractor shall submit a copy of the grease duct leakage test report to the architect/engineer complete with the approval signature of the local code official.

A. HVAC EQUIPMENT

1. ROOFTOP UNITS (GAS FIRED HEAT) 3-25 TONS

Provide electric cooling, gas heating rooftop units as scheduled on the drawings, manufactured by Aeon, Carrier, Dakin, Lennox, Johnson Controls, Trane, or Yaw, with features as noted in the RTU schedule and in the RTU Control Matrix, complete with factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater and low pressure switches, direct expansion cooling and condensing coils with factory installed flexible elastomeric insulation and aluminum and liquid lines not directly localized above a condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating (as required by the applicable energy code or greater if applicable), fan filter rack, air filter rack, proper type condenser fan, aluminum steel heat exchanger, minimum AFUE rated (as required by applicable energy code or greater if scheduled on the drawings, forced combustion air blower, complete factory installed motor-processor controls including anti-short cycle timers, time delay relays and minimum "on" time of 100 minutes, 100% modulating gas control system, built-in thermal overload protection on motors and compressors, outdoor air damper, relief, weatherproof housing constructed of zinc coated, heavy gauge, galvanized steel with weather-resistant baked enamel finish; pre-engineered roof curb with minimum height as scheduled on the drawings if unit is equipped with integral vibration isolators; Type CMR unit is not equipped with integral vibration isolators; safety point electrical power connection. Provide guards or louvered panels to protect the condenser fan from hail or other damage. Provide a 125 VAC, 20 amp duplex convenience receptacle mounted to unit ready for field wiring with a cover UL listed for wet and damp locations in use. Provide equipment and components with manufacturer's one year guarantee on components plus an additional four year guarantee on the compressors and heat exchangers. For units equipped with an economizer assembly, the assembly shall be certified with minimum 5 year manufacturer warranty, certified to operate through 60,000 damper opening and closing cycles, and certified to meet leakage requirements specified under the section, "Control Dampers".

2. ROOFTOP UNITS (DOAS) (GAS FIRED HEAT) 12.5 TONS (RTU-2)

Provide RTU unit as scheduled on the drawings manufactured by Captive Air with features as noted on the RTU schedule.

3. ELECTRIC UNIT HEATERS

Provide electric unit heaters as scheduled on the drawings, manufactured by Berko, Brasco, Inceco, Markal, OMAR, or Raywall, equipped, compatible with standard mounting brackets and hardware for horizontal airflow. Furnish heater fan motors complete with a manual motor starter with automatic thermal cutoff sized to the motor load, disconnect switch, and other code required safety devices. Provide unit mounted thermostat and manual summer/winter changeover switch.

D. SPLIT DUCTLESS AIR-CONDITIONING SYSTEMS

Provide split ductless system consisting of evaporator section for wall or ceiling mounting as indicated and remote condensing section similar to Carrier, Comfort Star, Dakin, Friedrich, Fujitsu, Lennox, LG, Mitsubishi, Samsung, Sanyo, Trane, or York. Evaporator cabinet shall be factory assembled pre-wired consisting of furnace-grade steel with baked-enamel finish, front access, with direct-drive centrifugal fans, 2-stage motor, and optional foam filter. Evaporator coil shall be direct-expansion cooling coil of seamless copper tubes expanded into aluminum fins, with thermal-expansion valve with external evaporator. Air-cooled condenser shall be of corrosion-resistant cabinet containing compressor, copper-tube aluminum-fin coils, direct-drive propeller fans with motors with internal overload protection; capacity control to 0 degrees Fahrenheit.

Provide concrete bases for units located on roof. Provide pre-engineered roof equipment support rails for units located on roof. Securely attach units to rail.

Provide refrigerant piping sized as recommended by equipment manufacturer with foamed plastic insulation on the suction line as specified in this section.

Control System: Unit-mounted panel with ON/OFFS, control transformer with circuit breaker, solid-state temperature- and humidity-control modules. Provide solid-state unit-mounted control panel with start-stop switch, adjustable humidity set point, and adjustable temperature set point. Refer to sequence of operation.

E. AIR CURTAINS

Provide air curtains manufactured by Berner, Marley, Mars, or Powered Air, of sizes and capacities shown on drawings. Units shall comply with AMCA 220A, AHRI 110 and NSF 37. Unit housing shall be constructed of aluminum, aluminumized steel, or galvanized steel with powder coated/alodine/zincdipnish, with metal mounting brackets. Unit shall have air adjustment by way of multi-speed motors or adjustable intake louvers. Unit shall have an adjustable integral discharge nozzle. Units shall have statically and dynamically balanced fans with direct drive fan drives. Motors shall be single speed/thermostatically mounted, continuous duty, with permanently sealed pre-lubricated ball bearings, and internal disconnect.

Furnish unit with washable panel filters with welded galvanized steel mounting frames, gasketed, with fasteners for bolting together bulk-up filter bars. Furnish unit with built-in line voltage thermostat wired to air curtain junction box. Furnish with plug-in-type automatic door switch, start-stop pushbutton switch, factory-installed time-delay relay, and mounting brackets and accessories. Furnish unit with motor control panel complete with motor starter, 115V transformer with primary and secondary fuses, terminal strip, and NEMA 250 enclosure.

5. PIPING AND PIPING SPECIALTIES

A. REFRIGERANT PIPING AND INSULATION

Copper Tubing: ASTM B820, Type ACR, hand-drawn straight lengths, and soft-annealed coils, seamless copper tubing. Tubing shall be factory cleaned, ready for installation, and have ends capped to protect cleanliness of pipe interiors prior to shipping.

Refrigerant Liner Kits: Soft-annealed copper tubing of pipe diameters as recommended by the manufacturer and of length as required for the installation. Tubing shall be factory or field insulated with flexible mineral wool insulation with thickness as specified below.

Fittings: wrought-copper fittings: ANSI B16.22, streamlined pattern.

Solder filler metals: ASTM B32, 95.5 Tin-Antimony.

Brazing filler metals:

1. AWS A5.8, Classification BAg-5: Silver (Ag) 44.0-46.0 percent, Zinc (Zn) 23.0-27.0 percent, and Copper (Cu) 29.0-31.0 percent.
2. AWS A5.8, Classification BCuP-5: Phosphorus (P) 4.8-5.2 percent, Silver (Ag) 14.5-15.5 percent, and Copper (Cu) remainder.

Braze mechanical joints. Solder joints connecting to refrigerant valves and specialties. Continuously purge the pipe and fittings during brazing with an inert gas per manufacturer's recommendations (e.g., dry nitrogen) to prevent oxidation of scale. Manual purge until the joint is cool to the touch. Provide temporary cap or cover on completed joints with open ends to prevent entry of contaminating materials.

Insulate refrigerant lines with flexible elastomeric insulation, Armetex or equal. Insulate suction and liquid lines between the expansion valve, evaporator, and compressor with 1/2 inch thick insulation on pipes less than 1 inch in size and 1 inch thick for pipes 1 inch and larger. Insulate hot gas and liquid lines between the compressor condenser, and expansion valve with 1 inch thick insulation on pipes less than 1-1/2 inch and 1-1/2 inch thick for pipes 1-1/2 inch and larger. Piping insulation shall have a flame spread of 25 or less, and a smoke developed rating of 50 or less when tested in accordance with ASTM E84. Coat insulation that is exposed to the elements with a protective clear sealer. Install and support piping to a minimum. Support and secure piping to Unistrut type supports so that no vibration passes to the building structure. Pipe attachments shall be copper-plate or have nonmetallic coating for electrolytic protection where attachments are in direct contact with copper tubing. Install a support within one foot of each change of direction. Mount pipe hangers and supports on the insulation with saddles to prevent hangers from rupturing the insulation. Replace insulation that is cut or broken by the hangers.

Run refrigerant lines parallel and perpendicular to wall and floor lines and to appear straight and in good order. Pitch suction lines down slightly (1 inch in 20 feet) towards the compressor. Provide oil traps at the base of vertical suction risers over 8 feet high. Install liquid sight glasses in liquid lines nearest the expansion valve. Factory mount expansion valves with the sensing bulb shipped loose. Field mount expansion valve bulb after refrigerant piping is complete (damage may occur if bulbs come in contact with heat).

For systems of 5 ton capacity and smaller, the contractor shall have the option to provide copper refrigerant tubing line set sized as recommended by equipment manufacturer and of length as required for the installation. Provide quick-connect flare tubing compression fittings, solder connections, or brazed connections as recommended by the manufacturer to match the connections of the condensing unit and evaporator coil.

B. SYSTEM EVACUATION AND CHARGING

Blow out refrigeration lines with dry nitrogen at a suitable pressure before making final connection at the condensing unit or coil to ensure against dirt, scale, or other foreign material being in the lines. Draw a vacuum to 29 inches of mercury. Break this vacuum by charging dry refrigerant gas into the system, raising the pressure to 0 PSIG. Repeat the latter two steps for a triple evacuation before the final evacuation is started. Make final evacuation by reducing the system absolute pressure to a maximum of 0.5 millimeters (500 microns) and allow the pump to run at this pressure for a minimum of two hours.

Repeat the proper amount of refrigerant charge per the manufacturer's recommendations. Record the amount of refrigerant by weight charged into the system for each circuit recorded to the nearest 1/4 pound on tags and attach tags to the liquid line near the condensing unit. Refrigerant shall be supplied by the HVAC Contractor.

C. PIPING MATERIALS

Natural Gas Above Slab: Gas piping above ground shall be Schedule 40 black steel with malleable iron screwed fittings, or standard welded fittings.

D. SYSTEM TESTING AND ADJUSTING

For low pressure natural gas systems, subject the pipe to 10 psig air pressure for a period of one hour. The resultant pressure differential for this period shall be 0 psig. Test per gas company requirements where required.

For welded natural gas systems and systems with an operating pressure in excess of 14" water column, subject the pipe to 60 psig air pressure for a period of one hour. The resultant pressure differential for this period shall be 0 psig. Test per gas company requirements where required.

E. VALVES

Gas Cocks 2 inch and Smaller: Lubricated type with semi-steel body an

Gate Valves 2 inch and Smaller: Class 125, rising stem, soldered lead cast bronze body and parts, sweat ends, with wedge disc. By Apollo # 1025-LF, Hammond # UP-688, Milwaukee # UP668 or Nibco # F-113-LF.

Gas Cocks 2 inch and Smaller: Lubricated type with semi-steel body and full area rectangular port with screwed ends by Homestead # 601, Miliken #200M or RM Energy Systems # D125.

F. WATER HEATER

Provide heater with redundant gas valves. Provide with gas train and / or low water cutoff as required by local boiler code.

G. PIPING INSULATION

#1038

FIELD VERIFICATION
Contractor shall verify all signed dimensions and conditions at the job site and notify Aria Group Architects, Inc. of any dimensional errors, omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.
COPYRIGHT
Aria Group Architects, Inc. shall retain all common law, statutory and other reserved rights. These drawings and related documents shall not be duplicated, disclosed or otherwise used without the consent of Aria Group Architects, Inc.

NO.	DATE	REVISIONS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	05/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR LL REVIEW



Drawing Title
MECHANICAL SPECIFICATIONS

Job No. 214815 Drawn MJW

Scale Date 05/16/22

Sheet No.
M592

3.5 START-UP DOCUMENTATION COMMON TO ALL SYSTEMS

- a. The following Start-Up Documentation (Checklists and Tests) shall be considered common to all systems:
 1. Checkout shall proceed from lower level devices to larger components to the entire system operation.
 2. Verify labeling is affixed per specification and visible.
 3. Verify prerequisite procedures are done.
 4. Inspect for damage and ensure none is present.
 5. Verify system is installed per the manufacturer's recommendations.
 6. Verify system has undergone Start-Up per the manufacturer's recommendations.
 7. Verify that access is provided for eventual replacement of the equipment.
 8. Verify that access is provided for eventual replacement of the equipment.
 9. Verify that record drawings, submittal data and O&M documentation accurately reflect the installed systems.
 10. Verify all gauges and test ports are provided as required by contract documents and manufacturer's recommendations.
 11. Verify all recorded nameplate data is accurate.
 12. Verify that the installation ensures safe operation and maintenance.
 13. Verify all rotating and moving parts are properly lubricated.
 14. Verify specified replacement material/stock has been provided as required by the Contract Documents.
 15. Verify all monitoring and ensure all alarms are active and set per requirements.

3.6 MECHANICAL IDENTIFICATION

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Perform the following checks:
 1. Verify all valve tags, piping, duct, and equipment labeling corresponds with drawings and indexes and meets requirements specified. Correct any deficiencies for all piping and duct system.
 2. Adjusting: Relocate any mechanical identification device which has become visually blocked by work of this division or other divisions.
 3. Cleaning: Clean face of identification devices, and glass frames of valve charts.

3.7 MECHANICAL INSULATION

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Examine all piping, systems and equipment specified to be insulated.
 1. Ensure quality of insulation. Patch and repair all insulation damaged after installation.
 2. Ensure the integrity of vapor barrier around all cold surfaces.

3.8 PIPING GENERAL

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: These procedures apply to all installed piping systems, including underground site utilities.
 1. Inspect all piping for proper installation, adequate support (with appropriate vibration isolation where applicable) and adequate isolation valves for required service.
 2. Provide notifications of pipe cleaning and flushing activities.
 3. Flush and clean all piping and clean all strainers. Provide documentation of all related procedures.
 4. Ensure adequate drainage is provided at low points and venting is provided at high points.
 5. Ensure facilities to effectively drain and fill the system are in place.
 6. Ensure air is thoroughly removed from the system as applicable.
 7. Provide notification of pressure testing.
 8. Pressure and/or leak test all applicable systems in accordance with the requirements in the applicable Division 23 specification.
 9. Sterilize applicable piping systems as specified in the individual sections and as required by regulatory authorities.
 10. Submit pressure test reports that document the pressure testing results with certification of the results. Include drawings/diagrams indicating sections of pipe that are tested with the corresponding report.
 11. Set and adjust fill, pressure, or level controls to the required setting.

3.9 AC MOTORS

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Perform the following checks during start-up and as specified in manufacturer's instructions:
 1. Verify proper alignment, installation, and rotation.
 2. Verify properly sized overloads are in place.
- c. Start-Up Tests: Perform the following tests, measurements, or procedures during start-up and as specified in the manufacturer's instruction:
 1. Measure voltage available to all phases. Measure amps and RPM after motor has been placed in operation and is under load.
 2. Record all motor nameplate data.

3.10 PACKAGED HEATING AND COOLING UNITS

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Refer to AC Motors in this section.
- c. General: Provide the services of a factory-authorized service representative to test and inspect unit installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
- b. Start-Up Checks: Perform the following inspections/checks during start-up:
 1. Test controls and demonstrate compliance with requirements. Replace damaged or malfunctioning controls and equipment.
 2. Install new filters after start-up.

3.11 TERMINAL UNITS

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Perform the following inspections/checks during start-up:
 1. After construction is completed, including painting if applicable, clean unit exposed surfaces.
 2. Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
 3. Verify adequate access for maintenance.
 4. Check power and control voltages.
 5. Check rotation of fan where applicable.
 6. Check operation of water leak sensors.
 7. Check calibration and operation of the controlling elements.
 8. Check control valves for required close-off and fail position.
 9. Install new filter units for terminals requiring same.

3.12 FANS


- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. General: Provide the services of a factory-authorized service representative to test and inspect exhaust fan installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
- c. Start-Up Checks: Perform the following inspections/checks during start-up:
 1. Inspect the field assembly of components and installation of the units, piping, ductwork, and electrical connections.
 2. Clean unit cabinet interiors to remove foreign material and construction dirt and dust. Vacuum clean fan wheel, fan cabinet, coils entering air face. Ensure volatile irritants are contained and kept out of occupied spaces.
 3. Adjust and lubricate dampers and linkages for proper damper operation.
 4. Verify the unit is secure on mountings and supporting devices and connections for ductwork, and electrical are complete. Verify proper thermal overload protection is installed in motors, starters, and disconnects.
 5. Ensure vibration isolation integrity is maintained with the fan installation and associated connections.
 6. Lubricate bearings, pulleys, belts, and other moving parts with factory-recommended lubricants.
 7. Stroke all dampers to ensure free and full travel.

3.13 DUCTWORK ACCESSORIES

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Perform the following checks during start-up and as specified:
 1. Cleaning: Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
- c. Start-Up Tests: In addition to specifications, perform the following as a minimum:
 1. Operate installed ductwork accessories to demonstrate compliance with requirements. Test for air leakage while system is operating. Repair or replace faulty accessories, as required to obtain proper operation and leak proof performance.
 2. Label access doors in accordance with Division 21 Section "Mechanical Identification"
 3. Adjusting: Adjust ductwork accessories for proper settings, install fusible links in-fire dampers and adjust for proper action.

END OF SECTION 23

NO.	DATE	REVISIONS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	05/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR LL REVIEW
NO.	DATE	REMARKS
REVISIONS		



01/18/2023

Drawing Title
MECHANICAL SCHEDULES

Job No. 214815 Drawn MJW
Scale Date 05/16/22

Sheet No.
M601

ROOFTOP UNIT SCHEDULE (DX COOLING, NATURAL GAS HEAT)

MARK	MANUFACTURER	MODEL	NOMINAL TONS	UNIT TYPE	COOLING COIL										GAS FIRED HEAT EXCHANGER				ELECTRICAL				WEIGHT (LBS)	NOTES								
					CFM	ESP (IN)	BHP (HP)	NOM HP (Y/N)	VFD (N)	TH (MBH)	SH (MBH)	EAT (°F DB)	LAT (°F WB)	REFR (°F WB)	MIN EFF (EER)	MIN STAGES	MIN OUT (MBH)	NOM INPUT (MBH)	MIN EFF (%)	EAT (°F DB)	LAT (°F DB)	MIN STAGES			MIN O/A (CFM)	VPH	MCA	MOCP	DISC TYPE			
RTU-1	CARRIER	48HCFE09	8.5	SINGLE ZONE	3,300	0.5	1.4	--	N	81.8	81.6	79.6	54.2	50.7	42.9	R410A	12.0	13.0	2	132.5	161.3	82	44.3	92.4	2	1070	208/3	41	50	NF	1369	A - S

*** EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION.**
MODEL NUMBERS AND NOMINAL TONS LISTED SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER, MODEL NUMBERS, OR NOMINAL TONS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
A. REFER TO ROOFTOP UNIT CONTROL MATRIX FOR ADDITIONAL UNIT FEATURES, COMPONENTS, MODULES, ACCESSORIES, AND CONTROLS THAT SHALL BE PROVIDED WITH THE EQUIPMENT.
B. EQUIPMENT SIZED FOR 90°F AMBIENT TEMPERATURE.
C. PROVIDE 2" MERV 8, EFFICIENT PLEATED THROWAWAY AIR FILTERS.
D. INTEGRATED ECONOMIZER - DIFFERENTIAL ENTHALPY ENABLE (OA ENTHALPY + RA ENTHALPY)
E. STARTERS FOR ALL MOTORS SHALL BE FURNISHED INTEGRAL WITH UNIT.
F. PROVIDE 3-SPEED MOTOR TO FACILITATE STAGED FAN SPEED CONTROL.
G. PROVIDE SINGLE POINT POWER CONNECTION.
H. COORDINATE SIZE OF CONDUCTOR TERMINATION LUGS WITH CONDUCTOR SIZES SHOWN ON ELECTRICAL DRAWINGS.
I. PROVIDE 125 VAC, 20 AMP DUPLEX CONVENIENCE RECEPTACLE MOUNTED TO UNIT READY FOR FIELD WIRING WITH A COVER UL LISTED FOR WET AND DAMPER LOCATIONS WHEN IN USE.
J. SPECIFIED FAN ESP ACCOUNTS FOR DUCT LOSSES EXTERNAL TO UNIT.
K. PROVIDE MOTOR HORSEPOWER TO OVERCOME INTERNAL UNIT STATIC PRESSURE DROP PLUS SPECIFIED EXTERNAL, STATIC PRESSURE DROP. NOMINAL MOTOR HP SHALL BE NO LARGER THAN THE FIRST AVAILABLE NOMINAL MOTOR SIZE GREATER THAN THE REQUIRED BHP.
L. PROVIDE INSULATED ROOF CURB WITH MINIMUM HEIGHT REQUIRED TO MAINTAIN BOTTOM OF EQUIPMENT A MINIMUM OF 24 INCHES ABOVE FINISHED ROOF SURFACE. PROVIDE SLOPED CURB IF NEEDED TO MATCH ROOF SLOPE.
M. SCHEDULED WEIGHT IS THE MAXIMUM ALLOWABLE OPERATING WEIGHT OF THE EQUIPMENT AND CURB.
N. COOLING COIL LAT IS LEAVING AIR TEMPERATURE OF COIL.
O. PROVIDE GUARDS TO PROTECT CONDENSER COIL FROM HALL OR OTHER DAMAGE.
P. PROVIDE HEATER TO MEET OR EXCEED SCHEDULED MINIMUM MBH OUTPUT. NOMINAL INPUT IS BASED ON LISTED MANUFACTURER'S STANDARD PRODUCT. COORDINATE EQUIPMENT GAS LOAD WITH PLUMBING CONTRACTOR IF DIFFERENT FROM THAT SCHEDULED. MEET MINIMUM EFFICIENCY SCHEDULED.
Q. SELECT EQUIPMENT FOR ELEVATION OF 6572 FEET ABOVE SEA LEVEL.
R. PROVIDE HOT GAS REHEAT COIL.
S. CONTRACTOR TO COORDINATE WITH NATIONAL TAB TO PROVIDE UV-PHI INDOOR AIR PURIFICATION SYSTEM, PHI CELL MODEL NO. PHI-PKG14-24V IN BLOWER CABINET.

UNIT HEATER SCHEDULE (ELECTRIC)

MARK	MANUFACTURER	MODEL	OUTPUT (KW)	MIN NO OF STAGES	CFM	VPH	NOTES
EUH-1	QMARK	MUH93-31	3	1	350	208/1	A-F

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
A. MOUNT 8 FEET ABOVE FINISHED FLOOR WITHOUT OBSTRUCTING AIRFLOW.
B. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE IN ARCHITECTURAL SET.
C. PROVIDE NECESSARY MOUNTING BRACKET AND ACCESSORIES FOR WALL MOUNTING.
D. PROVIDE FACTORY MOUNTED DISCONNECT SWITCH.
E. SUPPORT UNIT AS RECOMMENDED BY UNIT MANUFACTURER.
F. PROVIDE WITH WALL MOUNTED LINE VOLTAGE THERMOSTAT.

ROOFTOP UNIT SCHEDULE (DX COOLING, NATURAL GAS HEAT)

****PART OF CAPTIVE AIRE KITCHEN PACKAGE****

MARK	MANUFACTURER	MODEL	UNIT TYPE	DX COOLING COIL										GAS HEAT EXCHANGER				ELECTRICAL				WEIGHT (LBS)	NOTES							
				CFM	ESP (IN)	BHP (HP)	NOM HP (Y/N)	TH (MBH)	SH (MBH)	EAT (°F DB)	LAT (°F WB)	REFR (°F WB)	MIN EFF (EER)	MIN STAGES	MIN OUT (MBH)	NOM INPUT (MBH)	MIN EFF (%)	EAT (°F DB)	LAT (°F DB)	MIN STAGES	MIN O/A (CFM)			VPH	MCA	MOCP	DISC TYPE	STARTER TYPE		
RTU-2	CARRIER	CASRTU3-1400-20-20T-DOAS	DOAS	4,600	1.0	--	5.0	123.8	123.7	82.5	55.3	51.1	43.2	R410A	12.2	13.0	2	132.5	161.3	82	44.3	92.4	2	1070	208/3	41	50	NF	1369	A - V

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE, REF ARCHITECTURAL DRAWINGS.
B. PROVIDE INLET WITH 2" MERV 8, EFFICIENT PLEATED THROWAWAY AIR FILTERS.
C. PROVIDE FACTORY MOUNTED DISCONNECT INSTALLED ON SERVICE SIDE OF UNIT.
D. STARTERS FOR ALL MOTORS SHALL BE FURNISHED INTEGRAL WITH UNIT.
E. PROVIDE UNIT WITH SINGLE POINT ELECTRICAL CONNECTION.
F. SPECIFIED FAN ESP ACCOUNTS FOR DUCT LOSSES EXTERNAL TO UNIT. FILTER LOSS IS AT A MAXIMUM OF 400 FPM FACE VELOCITY.
G. PROVIDE MOTOR HORSEPOWER TO OVERCOME INTERNAL UNIT STATIC PRESSURE DROP PLUS SPECIFIED EXTERNAL, STATIC PRESSURE DROP. NOMINAL MOTOR HP SHALL BE NO LARGER THAN THE FIRST AVAILABLE NOMINAL MOTOR SIZE GREATER THAN THE REQUIRED BHP.
H. MECHANICAL CONTRACTOR SHALL PROVIDE SMOKE DETECTORS IN RETURN AIR DUCT.
I. PROVIDE INSULATED ROOF CURB WITH MINIMUM HEIGHT OF 18" INCHES. PROVIDE SLOPED CURB IF NEEDED TO MATCH ROOF SLOPE.
J. SCHEDULED WEIGHT IS THE MAXIMUM ALLOWABLE OPERATING WEIGHT OF THE EQUIPMENT AND CURB.
K. PROVIDE WITH STAINLESS STEEL HEAT EXCHANGER.
L. UNIT DESIGNED FOR NATURAL GAS AT A REQUIRED GAS SUPPLY PRESSURE OF 7.14" W.C.
M. PROVIDE HEATER TO MEET OR EXCEED SCHEDULED MINIMUM MBH OUTPUT. NOMINAL INPUT IS BASED ON LISTED MANUFACTURER'S STANDARD PRODUCT. COORDINATE EQUIPMENT GAS LOAD WITH PLUMBING CONTRACTOR IF DIFFERENT FROM THAT SCHEDULED. MEET MINIMUM EFFICIENCY SCHEDULED.
N. PROVIDE UNIT WITH VERTICAL SUPPLY AIR DUCT DISCHARGE THROUGH UNIT CURB.
O. PROVIDE UNIT WITH MOTORIZED INTAKE DAMPERS.
P. PROVIDE FREEZESTAT IN THE SUPPLY AIR DUCT TO SHUT DOWN THE SUPPLY FAN AND CLOSE THE OUTDOOR AIR DAMPER IF TEMPERATURE IN THE SUPPLY DUCT DROPS BELOW 40 DEGREES FAHRENHEIT.
Q. DIVISION 26 SHALL INTERLOCK DEDICATED OUTDOOR AIR UNIT WITH HOOD CONTROL PANEL TO OPERATE AT THE SAME TIME AS THE KITCHEN EXHAUST FAN(S).
R. DIVISION 26 SHALL INTERLOCK DEDICATED OUTDOOR AIR UNIT TO SHUT DOWN FROM A SIGNAL FROM THE HOOD FIRE SUPPRESSION ANSUL SYSTEM.
S. PROVIDE WITH DISCHARGE DUCT SENSOR WITH MODULATING OR STAGED COOLING AND HEATING CAPABILITY AS REQUIRED FOR OPERATION OF CONTROLS.
T. PROVIDE UNIT WITH HOT GAS REHEAT COIL.
U. SELECT EQUIPMENT FOR ELEVATION OF 6572 FEET ABOVE SEA LEVEL.
V. CONTRACTOR TO COORDINATE WITH NATIONAL TAB TO PROVIDE UV-PHI INDOOR AIR PURIFICATION SYSTEM, PHI CELL MODEL NO. PHI-PKG14-24V IN BLOWER CABINET.

ROOFTOP UNIT CONTROL MATRIX

CONTROL FEATURE	UNITS	RTU-1 SETPOINT OR Y/N	NOTES
SETPPOINTS			
COOLING - OCCUPIED SETPOINT	°F	75	
COOLING - UNOCCUPIED SETPOINT	°F	80	
HEATING - OCCUPIED SETPOINT	°F	70	
HEATING - UNOCCUPIED SETPOINT	°F	60	
DEHUMIDIFICATION SETPOINT - HUMIDITY SENSOR FEEDBACK	% RH	50%	B
PROGRAMMED CONTROL FEATURES			
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT		Y	B
REMOTE TEMPERATURE SENSOR		Y	B
EQUIPMENT ACCESSORIES AND CONTROL MODULES			
OUTSIDE AIR DAMPER - MOTOR OPERATED (MODULATING)		Y	L
INTEGRATED ECONOMIZER - DIFFERENTIAL ENTHALPY ENABLE (OA ENTHALPY + RA ENTHALPY)	BTULB	Y	E
ECONOMIZER FAULT DETECTION AND DIAGNOSTICS (FDD) SYSTEM		Y	F, G
RELIEF - BAROMETRIC DAMPER		Y	M
COOLING COIL (DX - STAGED)		Y	M
DEHUMIDIFICATION - HOT GAS REHEAT		Y	O
HEATING COIL (NATURAL GAS)		Y	M
SUPPLY FAN CONTROL METHODS			
ON DURING OCCUPIED HOURS		Y	
CYCLE WITH LOADS DURING UNOCCUPIED HOURS		Y	
VARIABLE VOLUME - MODULATE FAN SPEED IN RESPONSE TO ZONE TEMPERATURE		Y	M, R
SAFETIES, INTERLOCKS, AND ALARMS			
GAS VALVE SAFETY		Y	F
RETURN AIR SMOKE DETECTOR - SAFETY SHUTDOWN		Y	B
FIRE ALARM CONTROL PANEL - SAFETY SHUTDOWN INTERLOCK		Y	B
KITCHEN EXHAUST SYSTEM INTERLOCK		Y	S

DIV. 23 CONTRACTOR SHALL PROVIDE CONTROL PANEL(S), WIRING, THERMOSTAT(S), TEMPERATURE SENSOR(S), HUMIDISTAT(S), AND/OR CO2 SENSOR(S) WHERE SHOWN ON THE DRAWINGS AND AS REQUIRED TO FACILITATE THE SCHEDULED CONTROL MODULES AND SEQUENCES OF OPERATION. EACH UNIT SHALL CONTROL BASED ON ITS OWN INTERNAL SAFETIES, TIME DELAYS, AND SEQUENCES UNLESS NOTED OTHERWISE. COORDINATE WITH OWNER FINAL BUILDING AND EQUIPMENT SCHEDULES DURING STARTUP. REFERENCE DIVISION SPECIFICATIONS FOR INDIVIDUAL DEVICE REQUIREMENTS.

NOTES:
B. DIVISION 23 CONTRACTOR SHALL PROVIDE DEVICE.
E. IF SETPOINT VALUE IS LISTED, IT INDICATES ECONOMIZER HIGH-LIMIT SHUTOFF. UNIT SHALL BE IN ECONOMIZER IF CONDITIONS ARE LESS THAN SETPOINT. THE FOLLOWING SENSORS SHALL DETERMINE ECONOMIZER ON POINT. OUTSIDE AIR TEMPERATURE, DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE. RETURN AIR TEMPERATURE, DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE. OUTSIDE AIR HUMIDITY, DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE. RETURN AIR HUMIDITY, DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
F. DEVICE SHALL BE FACTORY MOUNTED AND PRE-WIRED FOR OPERATION SUBJECT TO THE ONBOARD CONTROLLER.
G. PROVIDE UNIT WITH AN INDOOR SYSTEM CONSISTING OF PERMANENTLY INSTALLED OUTSIDE AIR, SUPPLY AIR, AND RETURN AIR TEMPERATURE SENSORS. THE UNIT CONTROLLER SHALL AT A MINIMUM BE CAPABLE OF PROVIDING SYSTEM STATUS OF ECONOMIZER, COMPRESSOR, HEATING, MIXED AIR LOW LIMIT ALARM, AND SENSOR VALUES. EACH OPERATING MODE SHALL BE CAPABLE OF INDEPENDENTLY OPERATING FOR TESTING. THE SYSTEM SHALL REPORT FAULTS TO AN APPLICATION ACCESSIBLE BY SERVICE PERSONNEL. THE FOLLOWING FAULTS SHALL BE DETECTED: AIR TEMPERATURE FAILURE, ECONOMIZER ENABLE/DISABLED WHEN ECONOMIZER SHOULD BE OFF/ON, RESPECTIVELY, DAMPER NOT MODULATING, AND EXCESS OUTSIDE AIR.
L. EQUIPMENT MANUFACTURER SHALL PROVIDE MODULATING DAMPER AND CONTROLS CAPABLE OF ADJUSTING THE DAMPER POSITION TO MAINTAIN THE SCHEDULED OUTSIDE AIR ON THE DRAWINGS ACROSS ALL FAN SPEEDS. DIV. 23 CONTRACTOR SHALL PROGRAM MULTIPLE DAMPER POSITION SETPOINTS IN THE FIELD DURING TESTING AND BALANCING TO MAINTAIN MINIMUM VENTILATION WHEN NOT IN ECONOMIZER. DAMPER SHALL BE CLOSED DURING UNOCCUPIED HOURS.
M. UNITARY CONTROLLER SHALL MODULATE AND/OR CYCLE SUPPLY FAN SPEED SETTING AND COIL CAPACITY STAGES SUBJECT TO THE INTERNAL SAFETIES AND SEQUENCES TO MAINTAIN SCHEDULED SETPOINTS.
O. PROGRAM DEHUMIDIFICATION SEQUENCE BASED ON ZONE AIR HUMIDITY.
R. PROVIDE MODULATING FAN CONTROL WITH MINIMUM SPEED LESS THAN 50% OF FULL SPEED. AT MINIMUM SPEED THE FAN SHALL DRAW NO MORE THAN 30% OF FULL SPEED POWER.
S. INTERLOCK RTU WITH KITCHEN EXHAUST HOOD SYSTEM(S) TO SHUT DOWN UPON SIGNAL FROM HOOD FIRE EXTINGUISHING SYSTEM. INTERLOCK RTU WITH KITCHEN EXHAUST FAN TO ENERGIZE WHEN HOOD SYSTEM IS ENERGIZED FOR PRESSURIZATION.

PACKAGED DOAS UNIT CONTROL MATRIX

CONTROL FEATURE	UNITS	RTU-2 SETPOINT OR Y/N	NOTES
CONTROL STRATEGY			
DOAS SUPPLY AIR TEMPERATURE CONTROL		Y	
HEATING AND COOLING SET POINTS			
COOLING - OCCUPIED SETPOINT	°F	75	
COOLING - UNOCCUPIED SETPOINT	°F	80	
HEATING - OCCUPIED SETPOINT	°F	70	
HEATING - UNOCCUPIED SETPOINT	°F	60	
DEHUMIDIFICATION MODE ENABLE - OUTSIDE AIR DEW POINT	°F DP	55	F
DEHUMIDIFICATION - COOLING CONTROL - COIL LEAVING AIR TEMPERATURE SETPOINT	°F DB	55	F
PROGRAMMED CONTROL FEATURES			
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT		Y	B
EQUIPMENT COMPONENTS, ACCESSORIES AND CONTROL FEATURES			
COOLING COIL (DX - MODULATING CAPACITY)		Y	K
DEHUMIDIFICATION - MODULATING HOT GAS REHEAT		Y	K
HEATING - HEAT PUMP - MODULATING HEATING		Y	K
HEATING - NATURAL GAS - MODULATING		Y	K
OUTSIDE AIR DAMPER - MOTOR OPERATED		Y	J
SUPPLY FAN CONTROL METHODS			
ON DURING OCCUPIED MODE		Y	
CONSTANT SPEED SUPPLY FAN OPERATION		Y	K
SAFETIES, INTERLOCKS, AND ALARMS			
GAS VALVE SAFETY		Y	F
RETURN AIR SMOKE DETECTOR - SAFETY SHUTDOWN		Y	B
LOW LIMIT FREEZESTAT - FREEZE PROTECTION SAFETY SHUTDOWN		Y	F
DIFFERENTIAL PRESSURE SWITCH - FILTER CHANGE ALARM		Y	F
FIRE ALARM CONTROL PANEL - SAFETY SHUTDOWN INTERLOCK		Y	F
KITCHEN EXHAUST SYSTEM INTERLOCK		Y	L

DIV. 23 CONTRACTOR SHALL PROVIDE CONTROL PANEL(S), WIRING, THERMOSTAT(S), TEMPERATURE SENSOR(S), HUMIDISTAT(S), AND/OR CO2 SENSOR(S) WHERE SHOWN ON THE DRAWINGS AND AS REQUIRED TO FACILITATE THE SCHEDULED CONTROL MODULES AND SEQUENCES OF OPERATION. EACH UNIT SHALL CONTROL BASED ON ITS OWN INTERNAL SAFETIES, TIME DELAYS, AND SEQUENCES UNLESS NOTED OTHERWISE. COORDINATE WITH OWNER FINAL BUILDING AND EQUIPMENT SCHEDULES DURING STARTUP. REFERENCE DIVISION SPECIFICATIONS FOR INDIVIDUAL DEVICE REQUIREMENTS.

NOTES:
B. DIVISION 23 CONTRACTOR SHALL PROVIDE DEVICE.
F. DEVICE SHALL BE FACTORY MOUNTED AND PRE-WIRED FOR OPERATION SUBJECT TO THE ONBOARD CONTROLLER.
J. DAMPER SHALL BE CLOSED DURING UNOCCUPIED MODE.
K. UNITARY CONTROLLER SHALL MODULATE AND/OR CYCLE SUPPLY FAN SPEED AND COIL CAPACITY SUBJECT TO THE INTERNAL SAFETIES AND SEQUENCES TO MAINTAIN SCHEDULED SETPOINTS.
L. INTERLOCK RTU WITH KITCHEN EXHAUST HOOD SYSTEM(S) TO SHUT DOWN UPON SIGNAL FROM HOOD FIRE EXTINGUISHING SYSTEM. INTERLOCK RTU WITH KITCHEN EXHAUST FAN TO ENERGIZE WHEN HOOD SYSTEM IS ENERGIZED FOR PRESSURIZATION.
Q. VENTILATION ONLY MODE PROVIDES OUTSIDE AIR DIRECTLY TO SPACE WITHOUT HEATING OR COOLING WHEN OUTDOOR AIR IS FAVORABLE. VENTILATION ONLY MODE CAN BE INTERRUPTED ON A CALL FOR DEHUMIDIFICATION.

BUILDING AIR BALANCE SUMMARY NORMAL OPERATION

UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/SA
RTU-1	3,300	1,070	--	32%
RTU-2	4,600	2,425	--	53%
FCU-1	420	40	--	10%
KEF-1	--	--	700	--
KEF-2	--	--	700	--
KEF-3	--	--	700	--
KEF-4	--	--	700	--
EF-1	--	--	300	--
TOTALS	8,320	3,535	3,100	--
TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)				435
PERCENT POSITIVE PRESSURIZATION				12.3%

BUILDING AIR BALANCE SUMMARY ECONOMIZER MODE

UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/SA
RTU-1	2,211	2,211	--	100%
RTU-2	3,082	3,082	--	100%
FCU-1	420	40	--	10%
KEF-1	--	--	700	--
KEF-2	--	--	700	--
KEF-3	--	--	700	--
KEF-4	--	--	700	--
EF-1	--	--	300	--
BAROMETRIC RELIEF RTU-1	--	--	1,141	--
POWER EXHAUST RTU-2	--	--	657	--
TOTALS	5,713	5,333	4,898	--
TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)				435
PERCENT POSITIVE PRESSURIZATION				8.2%

FAN COIL UNIT SCHEDULE (HEAT PUMP)

MARK	MANUFACTURER	MODEL	SUPPLY FAN					COOLING COIL				HEAT PUMP HEATING COIL				ELECTRICAL				WEIGHT (LBS)	NOTES			
			CFM	ESP (IN)	NOM HP	TH (MBH)	SH (MBH)	EAT (°F DB)	LAT (°F WB)	REFR (°F WB)	MIN OUT (MBH)	AMBIENT (DB)	EAT (°F DB)	LAT (°F DB)	MIN O/A (CFM)	VPH	MCA	MOCP	DISC TYPE					
FCU-1	CARRIER	40MCCQ1--3	420	0.025	0.06	9.9	9.9	76.4	56.5	46.8	46.3	R410A	12.2	-1.5	63.2	90	40	208/1	N/A	N/A	N/A	NF	45	A - 1

*** EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION.**
MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE, REF ARCHITECTURAL DRAWINGS.
B. ASSOCIATED CONDENSING UNIT SHALL BE BY THE SAME MANUFACTURER.
C. FOR COOLING, EQUIPMENT SIZED FOR 100°F AMBIENT TEMPERATURE. HEAT PUMP HEATING CAPACITY BASED ON AMBIENT TEMPERATURE LISTED.
D. PROVIDE UNIT WITH CLEANABLE AIR FILTERS.
E. PROVIDE WITH 7-DAY PROGRAMMABLE THERMOSTAT WITH STAGED HEATING AND COOLING CAPABILITY AS REQUIRED FOR OPERATION OF HEATING AND COOLING CONTROLS.
F. PROVIDE FACTORY MOUNTED STARTER AND DISCONNECT SWITCH INSTALLED ON SERVICE SIDE OF UNIT.
G. PROVIDE SINGLE POINT POWER CONNECTION.
H. PROVIDE WITH SPRING VIBRATION ISOLATION AND ALL-THREAD HANGING RODS.
I. REFERENCE PLUMBING PLANS FOR CONDENSATE DRAIN PIPING FROM UNIT.

HEAT PUMP CONDENSING UNIT SCHEDULE

MARK	SERVICE	MANUFACTURER	MODEL	REFR	COOLING CAPACITY			HEATING CAPACITY			ELECTRICAL				WEIGHT (LBS)	NOTES
					TH (MBH)	AMBIENT (DB)	MIN EFF (EER)	CAP (MBH)	AMBIENT (DB)	MIN EFF COP 4°F	MIN O/A (CFM)	VPH	MCA	MOCP		
CU-1	FCU-1	CARRIER	38MARBO18AA3	R410A	9.9	89.3	19.0	12.2	-1.5	3.3	18	25	208/1	102.5	A - H	

*** EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION.**
MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE, REF ARCHITECTURAL DRAWINGS.
B. EQUIPMENT CAPACITY SCHEDULED IS MINIMUM CAPACITY THAT MUST BE PROVIDED AT AMBIENT TEMPERATURE INDICATED.
C. CONTRACTOR SHALL VERIFY WITH EQUIPMENT SUPPLIER EXACT QUANTITY AND SIZE OF REFRIGERANT PIPING.
D. PROVIDE LIQUID LINE FILTER DRYER AND SIGHT GLASS.
E. PROVIDE PREFABRICATED EQUIPMENT SUPPORT FALLS.
F. PROVIDE FACTORY MOUNTED DISCONNECT INSTALLED ON SERVICE SIDE OF UNIT.
G. STARTERS FOR ALL MOTORS SHALL BE FURNISHED INTEGRAL WITH UNIT.
H. COORDINATE SIZE OF CONDUCTOR TERMINATION LUGS WITH CONDUCTOR SIZES SHOWN ON ELECTRICAL DRAWINGS.

FAN SCHEDULE

MARK	SERVICE DESCRIPTION	MANUFACTURER	MOUNTING	MODEL	CFM	ESP (IN)	BHP (HP)	NOM HP (Y/N)	FAN RPM	DRIVE (BELT/DIRECT)	VFD (N)	ELECTRICAL	NOTES		
EF-1	TOILETS	GREENHECK	ROOF	G-09S-D	300	0.5	0.1	1/8	1550	DIRECT	N	120/1	NON-FUSED	N/A	A - E

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE, REF ARCHITECTURAL DRAWINGS.
B. PROVIDE WITH MINIMUM 24" HIGH ROOF CURB, BIRDSCREEN AND BACKRRAFT DAMPER.
C. PROVIDE FACTORY MOUNTED DISCONNECT SWITCH.
D. INTERLOCK FAN OPERATION WITH TIME CLOCK.
E. PROVIDE WITH MANUFACTURER'S FAN SPEED CONTROLLER FOR BALANCING PURPOSES.

PROJECT DESIGN CONDITIONS

CLIMATE CONDITIONS	WEATHER STATION: USAF ACADEMY AF, CO, USA										BUILDING OPERATING HOURS:						
	CLIMATE ZONE	HEATING (DB)	COOLING (DB/COOLING)	WIND	RELATIVE HUMIDITY	WIND DIRECTION											

GRILLE, REGISTER, AND DIFFUSER SCHEDULE

MARK	MANUFACTURER	SERVICE	MODEL	CONSTRUCTION MATERIAL	FACE TYPE	MOUNTING LOCATION	FACE SIZE (IN)	MAX. NC	NOTES
CEG1	E.H. PRICE	EXHAUST GRILLE W/ DAMPER	80D	STEEL	EGGGRATE	SURFACE	12x12	30	A B C F G H
CRG1	E.H. PRICE	RETURN GRILLE	80	STEEL	EGGGRATE	LAY-IN	24x24	30	A B C F G H
CSD1	E.H. PRICE	SUPPLY DIFFUSER	PDDR	STEEL	PERFORATED	LAY-IN	24x24	30	A B C F H
CSB2	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	LAY-IN	24x24	30	A B C F H K
CSB3	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	SURFACE	12x12	30	A B C F H J K L
WSR1	E.H. PRICE	SUPPLY REGISTER W/ DAMPER	520D	STEEL	LOUVERED FACE	WALL OR DUCT	(SEE PLANS)	30	A B C D E F G H

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

- NOTES:
- A. EQUIPMENT FURNISHED AND INSTALLED PER THE EQUIPMENT RESPONSIBILITY SCHEDULE.
 - B. NECK SIZE SHOWN ON DRAWINGS. PROVIDE BRANCH DUCT TO MATCH NECK SIZE UNLESS OTHERWISE SHOWN ON DRAWINGS.
 - C. DIFFUSERS SHALL BE PREFINISHED TO MATCH CEILING/WALL/EXPOSED DUCT COLOR (COORDINATE WITH ARCHITECT).
 - D. FRONT BLADES PARALLEL TO LONG DIMENSION.
 - E. DOUBLE DEFLECTION BARS SHALL BE ADJUSTABLE.
 - F. FRAME TYPE TO MATCH CEILING/WALL CONSTRUCTION. COORDINATE WITH ARCHITECTURAL REFLECTED CEILING/WALL PLAN.
 - G. PROVIDE OPPOSED BLADE DAMPER ADJUSTABLE FROM FACE OF DEVICE.
 - H. PROVIDE DIFFUSERS, LINEAR SLOTS, AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.
 - J. CONTRACTOR SHALL PROVIDE REMOTE CABLE-OPERATED VOLUME DAMPER BY METROPOLITAN AIR TECHNOLOGIES MODEL RT-250 WITH EXTERNAL WORM GEAR OPERATOR OR EQUIVALENT YOUNG REGULATOR BUTTERFLY DAMPER WITH 270/275 CONTROLLER. OPERATOR SHALL HAVE A SQUARE DRIVE FOR 1/4" NUT DRIVER. DAMPER ASSEMBLY SHALL INCLUDE GALVANIZED STEEL DUCT WITH ROLLED BEAD STIFFENERS, REINFORCED BLADE, SELF LUBRICATING BEARING AND WORM GEAR MOUNTING PLATE. DAMPER SHALL BE INSTALLED IN BRANCH DUCT NOT INLET OF PLENUM DIFFUSER.
 - K. 4-WAY THROW PATTERN UNLESS OTHERWISE INDICATED BY FLOW ARROWS ON DRAWINGS.
 - L. PROVIDE RAPID MOUNT FRAME FOR INSTALLATION IN HARD CEILING.

AIR CURTAIN SCHEDULE

MARK	SERVICE AREA	MANUFACTURER	MODEL	UNIT SPECS				V/PHHZ	NOTES
				LENGTH (IN)	MAX. AIRFLOW (CFM)	HEATING CAPACITY (KW)	MOTOR (HP)		
AC-1	MAIN ENTRY	MARS	STD2	72	2758	24	(2) 1/2	208/3	A, C - F
AC-2	PATIO ENTRY	MARS	STD2	36	1379	12	1/2	208/3	A, C - F
AC-3	ENTRY	MARS	STD2	36	1379	12	1/2	208/3	A, C - F
AC-4	SERVICE ENTRY	MARS	STD2	36	1379	N/A	1/2	115/1	A - E

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

- NOTES:
- A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS.
 - B. MOUNT UNIT PER MANUFACTURERS RECOMMENDATIONS TO FACE OF WALL AND SUPPORT VERTICALLY.
 - C. PROVIDE INTEGRAL STARTER AND DISCONNECT SWITCH.
 - D. PROVIDE AIR CURTAIN WITH NORMALLY CLOSED DOOR LIMIT SWITCH FOR INSTALLATION ON DOOR. THE AIR CURTAIN SHALL ENERGIZE WHEN DOOR OPENS.
 - E. PROVIDE WITH DELAY MICROSWITCH WITH ADJUSTABLE DELAY TIMERS PRE MOUNTED IN THE AIR CURTAIN CONTROL PANEL.
 - F. MOUNT UNIT PER MANUFACTURERS RECOMMENDATIONS FROM STRUCTURE AND SUPPORT VERTICALLY.

TOTAL CONNECTED NATURAL GAS LOAD

EQUIPMENT DESIGNATION	DESCRIPTION	CFH (EACH)
101	GRIDDLE	81
101	GRIDDLE	81
103	FRYER	160
104	FRYER	160
TOTAL =		482
MECHANICAL EQUIPMENT		
EQUIPMENT DESIGNATION	DESCRIPTION	CFH (EACH)
RTU-1	ROOFTOP UNIT	162
RTU-2	DEDICATED OUTDOOR AIR SYSTEM	344
WH	WATER HEATER	199
WH	WATER HEATER	199
TOTAL =		904
TOTAL CONNECTED LOAD =		1386

NATURAL GAS SYSTEM OPERATING PRESSURE: 7" WC
 NATURAL GAS SYSTEM SIZED WITH TOTAL DEVELOPED LENGTH FROM GAS METER TO MOST REMOTE PIECE OF EQUIPMENT: 160 FEET
 SYSTEM DESIGN PRESSURE DROP: 0.5" WC

LOW PRESSURE GAS PIPE SIZING CHART

PIPE SIZE	LOAD (CFH)
1/2"	40
3/4"	84
1"	158
1-1/4"	325
1-1/2"	486
2"	937
2-1/2"	1,493
3"	2,340
4"	5,384
6"	15,772

OPERATING PRESSURE OF 7"WC WITH A PRESSURE DROP OF 0.5"WC
 TOTAL DEVELOPED LENGTH = 160 FEET
 TOTAL CONNECTED LOAD = 1386 CFH
 BASED ON NFPA 54 EQUATION 4.1


COLORADO MECHANICAL CODE REFRIGERANT AMOUNT COMPLIANCE CALCULATOR

WORST CASE ROOM NAME	OUTDOOR UNIT MARK	OCCUPANCY CLASSIFICATION	REFRIGERATING SYSTEM CLASSIFICATION	REFRIGERATING SYSTEM LEAK PROBABILITY	REFRIGERANT TYPE	REFRIGERANT GROUP	RCL: REFRIGERANT CONCENTRATION LIMIT (LB/1,000 CU FT)	RCL ADJUSTED FOR ALTITUDE (LB/1,000 CU FT)	ROOM AREA (SQ FT)	ROOM HEIGHT (FT)	ADDITIONAL VOLUME FROM COMMUNICABLE SPACE (CU FT)	TOTAL DISPERSION VOLUME (CU FT)	ALLOWABLE REF. CHARGE IN NETWORK (LBS)	ACTUAL SYSTEM REFRIGERANT CHARGE (LBS)	ACTUAL REF. CHARGE COMPLIES?
FREEZER	-	COMMERCIAL	DIRECT	HIGH	404A	A1	31	31.0	33.0	8.00	0	704	6.2	14.0	NO
COOLER	-	COMMERCIAL	DIRECT	HIGH	404A	A1	31	31.0	88.0	8.00	0	264	21.8	14.0	YES
CUSTARD MACHINE	-	COMMERCIAL	DIRECT	HIGH	404A	A1	31	31.0	996.0	10.00	2,329	12,289	361.0	20.0	YES

NOTES:
 A. PLENUMS: SPACE ABOVE SUSPENDED CEILING SHALL NOT BE INCLUDED IN CALCULATING THE REFRIGERANT QUANTITY LIMIT IN THE SYSTEM UNLESS SUCH SPACE IS PART OF THE AIR SUPPLY OR RETURN SYSTEM. (SECTION 7.3.2.2)

NO.	DATE	REMARKS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	08/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR LL REVIEW

REVISIONS



Drawing Title
MECHANICAL SCHEDULES

Job No. 214815
 Drawn MJW

Scale
 Date 05/16/22

Sheet No.
M602

COMcheck Software Version 4.1.5.3
Mechanical Compliance Certificate

Project Information
 Energy Code: 2015 IECC
 Project Title: Shake Shack (Interquest)
 Location: Colorado Springs, Colorado
 Climate Zone: 5b
 Project Type: New Construction

Construction Site: Colorado Springs, CO
 Owner/Agent: Shake Shack
 Designer/Contractor: Henderson Engineers Lenexa, KS

Additional Efficiency Package(s)
 Credits: 1.0 Required, 1.0 Proposed
 Reduced Lighting Power: 1.0 credit

Mechanical Systems List

Quantity	System Type & Description
1	RTU-1 (Single Zone): Heating: 1 each - Central Furnace, Gas, Capacity = 133 kBtu/h Proposed Efficiency = 82.00% EER, Required Efficiency: 80.00 % EER or 78% AFUE Cooling: 1 each - Single Package DX Unit, Capacity = 82 kBtu/h, Air-Cooled Condenser, Air Economizer Proposed Efficiency = 12.00 EER, Required Efficiency: 11.00 EER + 12.6 IEER Fan System: RTU-1 Dring/Dwring - Compliance (Motor nameplate HP method): Passes Fans: RTU-1 Supply, Constant Volume, 3300 CFM, 2.0 motor nameplate hp, 1.4 design brake hp (1.4 max. BHP), 0.0 fan efficiency grade
1	RTU-2 (Single Zone): Heating: 1 each - Central Furnace, Gas, Capacity = 275 kBtu/h Proposed Efficiency = 80.00% EER, Required Efficiency: 80.00 % EER Cooling: 1 each - Single Package DX Unit, Capacity = 124 kBtu/h, Air-Cooled Condenser, Air Economizer Proposed Efficiency = 11.00 EER, Required Efficiency: 11.00 EER + 12.6 IEER Fan System: RTU-2 Klotzen/BCH - Compliance (Motor nameplate HP method): Passes Fans: RTU-2 Supply, Constant Volume, 4800 CFM, 5.0 motor nameplate hp, 0.0 fan efficiency grade
1	CU-1/FCU-1 (Single Zone): Split System Heat Pump Heating Mode: Capacity = 12 kBtu/h Proposed Efficiency = 8.20 HSPF, Required Efficiency = 8.20 HSPF Cooling Mode: Capacity = 10 kBtu/h Proposed Efficiency = 10.00 SEER, Required Efficiency: 14.00 SEER Fan System: FCU-1/FCU-1 Office - Compliance (Motor nameplate HP method): Passes Fans: FCU-1 Supply, Constant Volume, 420 CFM, 0.1 motor nameplate hp, 0.0 fan efficiency grade
2	Water Heater 1: Gas Storage Water Heater, Capacity: 90 gallons, Input Rating: 199 kBtu/h w/ Circulation Pump Proposed Efficiency: 98.00 % EER, Required Efficiency: 80.00 % EER

Project Title: Shake Shack (Interquest) Report date: 05/12/22
 Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest, Page 1 of 13
 CO001\Energy\ComCheck.cck

Mechanical Compliance Statement
 Compliance Statement: The proposed mechanical design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2015 IECC requirements in COMcheck Version 4.1.5.3 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.
 Malvin Warrick - Mechanical Designer
 Name: Title: Signature Date: 5/12/2021

COMcheck Software Version 4.1.5.3
Inspection Checklist
 Energy Code: 2015 IECC

Requirements: 100.0% were addressed directly in the COMcheck software
 Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Plan Review	Complies?	Comments/Assumptions
C103.2 [PR2]	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical systems and equipment and document where exceptions to the standard are claimed. Load calculations per acceptable engineering standards and handbooks.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C103.2 [PR3]	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the service water heating systems and equipment and document where exceptions to the standard are claimed. Hot water system sized per manufacturer's sizing guide.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C406 [PR9]	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the additional energy efficiency package options.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack (Interquest) Report date: 05/12/22
 Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest, Page 3 of 13
 CO001\Energy\ComCheck.cck

Section # & Req.ID	Footing / Foundation Inspection	Complies?	Comments/Assumptions
C403.2.4 [FO9]	Snow/ice melting system sensors for future connection to controls. Freeze protection systems have automatic controls installed.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack (Interquest) Report date: 05/12/22
 Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest, Page 4 of 13
 CO001\Energy\ComCheck.cck

Section # & Req.ID	Plumbing Rough-In Inspection	Complies?	Comments/Assumptions
C404.5.1 [PL6]	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.5.2 [PL6]	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.5.3 [PL6]	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.6.1 [PL3]	Automatic time switches installed to automatically switch off the recirculating hot-water system or heat traps.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.6.2 [PL7]	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.6.3 [PL7]	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.6.4 [PL7]	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.7 [PL8]	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack (Interquest) Report date: 05/12/22
 Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest, Page 5 of 13
 CO001\Energy\ComCheck.cck

Section # & Req.ID	Plumbing Rough-In Inspection	Complies?	Comments/Assumptions
C404.7 [PL8]	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.7 [PL8]	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack (Interquest) Report date: 05/12/22
 Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest, Page 6 of 13
 CO001\Energy\ComCheck.cck

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C402.2.6 [ME11]	Thermally ineffective panel surfaces of sensible heating panels have insulation >= R-5.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.13 [ME11]	Unenclosed spaces that are heated use only radiant heat.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.2.3 [ME53]	HVAC equipment efficiency verified.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	See the Mechanical Systems list for values.
C403.2.4 [ME11]	Fault detection and diagnostics installed with air-cooled unitary DX units having economizers.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4 [ME11]	Fault detection and diagnostics installed with air-cooled unitary DX units having economizers.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.6 [ME59]	Demand control ventilation provided for spaces >500 ft ² and >25 people/1,000 ft ² occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow >3,000 cfm.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.2.6 [ME115]	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.2.7 [ME37]	Exhaust air energy recovery on systems meeting Table C403.2.7(1) and C403.2.7(2).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.2.8 [ME116]	Kitchen exhaust systems comply with replacement air and conditioned supply air limitations, and satisfy hood rating requirements and maximum exhaust rate criteria.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.9 [ME60]	HVAC ducts and plenums installed in or under a slab, verification may need to occur during Foundation Inspection.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.9 [ME10]	Ducts and plenums sealed based on static pressure and location.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.9.1.3 [ME11]	Ductwork operating > 3 in. water column requires air leakage testing.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack (Interquest) Report date: 05/12/22
 Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest, Page 7 of 13
 CO001\Energy\ComCheck.cck

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C403.2.9.1.3 [ME11]	Ductwork operating > 3 in. water column requires air leakage testing.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.9.1.3 [ME11]	Ductwork operating > 3 in. water column requires air leakage testing.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.3 [ME62]	Air economizers provided where required, meet the requirements for design capacity, control signal, ventilation controls, high-limit shut-off, integrated economizer control, and provide a means to relieve excess outside air during operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.3 [ME62]	Air economizers provided where required, meet the requirements for design capacity, control signal, ventilation controls, high-limit shut-off, integrated economizer control, and provide a means to relieve excess outside air during operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.4.2 [ME122]	Open- or closed-circuit cooling towers have a separate heat exchanger to isolate the cooling tower from the heat pump loop, and heat loss is controlled by shutting down the circulation pump on the cooling tower loop.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.4.4 [ME110]	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply. See the Mechanical Systems list for values.
C403.4.4 [ME110]	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply. See the Mechanical Systems list for values.
C403.4.4 [ME110]	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply. See the Mechanical Systems list for values.
C404.2.1 [ME111]	Gas-fired water-heating equipment installed in new buildings: where a singular piece of water-heating equipment >= 1,000 kBtu/h serves the entire building, thermal efficiency >= 90 EER. Where multiple pieces of water-heating equipment serve the building with combined rating >= 1,000 kBtu/h, the combined input-capacity-weighted-average thermal efficiency >= 90 EER. Exclude input rating of equipment in individual dwelling units and equipment <= 100 kBtu/h.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.2.1 [ME53]	Air outlets and zone terminal devices have means for air balancing.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack (Interquest) Report date: 05/12/22
 Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest, Page 8 of 13
 CO001\Energy\ComCheck.cck

SHAKE SHACK
 9723 FEDERAL DR., COLORADO SPRINGS, CO 80921

FIELD VERIFICATION
 Contractor shall verify all figured dimensions and conditions at the job site and notify Aria Group Architects, Inc. of any dimensional errors, omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.
 COPYRIGHT
 Aria Group Architects, Inc. shall retain all common law, statutory and other reserved rights. These drawings and related documents shall not be duplicated, disclosed or otherwise used without the consent of Aria Group Architects, Inc.

NO.	DATE	REVISIONS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	05/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR LL REVIEW

NO. DATE REMARKS
 REVISIONS

 01/18/2023

Drawing Title
MECHANICAL ENERGY CODE COMPLIANCE
 Job No. 214815 Drawn MJW
 Scale Date 05/16/22
 Sheet No. **M630**

Section # & Req. ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C403.5.1, C403.5.2, [K12.123]	Refrigerated display cases, walk-in coolers or walk-in freezers served by remote compressors and remote condensers not located in a condensing unit, have fan-powered condensers that comply with Sections C403.5.1 and refrigeration compressor systems that comply with C403.5.2.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

Section # & Req. ID	Final Inspection	Complies?	Comments/Assumptions
C403.3, C408.2.5.3 [F18]	Furnished O&M manuals for HVAC systems within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.2 [F127]	HVAC systems and equipment capacity does not exceed calculated loads.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1 [F147]	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1 [F147]	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1 [F147]	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1.1 [F142]	Heat pump controls prevent supplemental electric resistance heat from coming on when not needed.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1.2 [F138]	Thermostatic controls have a 5 °F deadband.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1.3 [F120]	Temperature controls have setpoint overlap restrictions.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.2 [F139]	Each zone equipped with setback controls using automatic time clock or programmable control system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.2.1, C403.2.4.2.2 [F140]	Automatic Controls: Setback to 55°F (heat) and 85°F (cool); 7-day clock, 2-hour occupant override, 10-hour backup.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.2.3 [F141]	Systems include optimum start controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.2.4.2.3 [F141]	Systems include optimum start controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Shake Shack (Interquest) Report date: 05/12/22
Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest. Page 9 of 13
CO\001\Energy\ComCheck.cck

Project Title: Shake Shack (Interquest) Report date: 05/12/22
Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest. Page 10 of 13
CO\001\Energy\ComCheck.cck


Section # & Req. ID	Final Inspection	Complies?	Comments/Assumptions
C403.2.4.2, 3 [F41]	Systems include optimum start controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.3 [F111]	Heat traps installed on supply and discharge piping of non-circulating systems.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.4 [F125]	All piping insulated in accordance with section details and Table C403.2.10.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.6.1 [F12]	Controls are installed that limit the operation of a recirculation pump installed to maintain temperature of a storage tank. System return pipe is a dedicated return pipe or a cold water supply pipe.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.1 [F128]	Commissioning plan developed by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3 [F131]	HVAC equipment has been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3 [F10]	HVAC control systems have been tested to ensure proper operation, calibration and adjustment of controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3 [F132]	Economizers have been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.4 [F129]	Preliminary commissioning report completed and certified by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5 [F17]	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5.3 [F43]	An air and/or hydronic system balancing report is provided for HVAC systems.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5.4 [F30]	Final commissioning report due to building owner within 90 days of receipt of certificate of occupancy.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Shake Shack (Interquest) Report date: 05/12/22
Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest. Page 11 of 13
CO\001\Energy\ComCheck.cck

Project Title: Shake Shack (Interquest) Report date: 05/12/22
Data filename: J:\Lenexa\Programs\P-T\Shake Shack\2150004946 Shake Shack 1438 - Interquest. Page 12 of 13
CO\001\Energy\ComCheck.cck



FIELD VERIFICATION
Contractor shall verify all figured dimensions and conditions at the job site and notify Aria Group Architects, Inc. of any dimensional errors, omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.
COPYRIGHT
Aria Group Architects, Inc. shall retain all common law, statutory and other reserved rights. These drawings and related documents shall not be duplicated, disclosed or otherwise used without written consent of Aria Group Architects, Inc.

NO.	DATE	REVISIONS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	08/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR LL REVIEW



Drawing Title
MECHANICAL ENERGY CODE COMPLIANCE

Job No. 214815 Drawn MJW

Scale Date 05/16/22

Sheet No.
M631

FIRE SYSTEM INFORMATION - JOB#5782747

FIRE SYSTEM NO	TAG	TYPE	SIZE	FLOW POINTS	INSTALLATION	
					SYSTEM	LOCATION ON HOOD
1		TANK FS	4.0/4.0	36	WALL UTILITY CABINET LEFT	N/A
2		TANK FS	4.0/4.0	36	WALL UTILITY CABINET LEFT	N/A

GAS VALVE(S)

FIRE SYSTEM NO	TAG	TYPE	SIZE	SUPPLIED BY
1		SC ELECTRICAL	2.000	CAPTIVEAIRE SYSTEMS
2		SC ELECTRICAL	2.000	CAPTIVEAIRE SYSTEMS

NOTES

- FIELD PIPE DROPS AS SHOWN
- PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
- FIELD INSTALLED DROP; FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
- SHIP LOOSE DROP; FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
- RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVEING, SALAMANDERS, ETC.
- OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
- IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
- FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.

- APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.
- THIS FIRE SYSTEM COMPLIES WITH UL 300 REQUIREMENTS.
- DL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS

SYSTEM SIZE: TANK-SP-2-WC TOTAL FP REQUIRED: 36.
 HOOD # 2 4' 0.00" LONG x 36" WIDE x 50" HIGH.
 RISER # 1 SIZE: 8" x 8".
 HOOD # 2 METAL BLOW-OFF CAPS INCLUDED.
 HOOD # 3 4' 0.00" LONG x 36" WIDE x 50" HIGH.
 RISER # 1 SIZE: 8" x 8".
 HOOD # 3 METAL BLOW-OFF CAPS INCLUDED.

- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

LEGEND - FIRE CABINET TANK SYSTEM

- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.

NOTES

- FIELD PIPE DROPS AS SHOWN
- PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
- FIELD INSTALLED DROP; FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
- SHIP LOOSE DROP; FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
- RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVEING, SALAMANDERS, ETC.
- OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
- IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
- FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.





- APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.
- THIS FIRE SYSTEM COMPLIES WITH UL 300 REQUIREMENTS.
- DL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS

SYSTEM SIZE: TANK-SP-2-WC TOTAL FP REQUIRED: 36.
 HOOD # 1 4' 0.00" LONG x 36" WIDE x 50" HIGH.
 RISER # 1 SIZE: 8" x 8".
 HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.
 HOOD # 4 4' 0.00" LONG x 36" WIDE x 50" HIGH.
 RISER # 1 SIZE: 8" x 8".
 HOOD # 4 METAL BLOW-OFF CAPS INCLUDED.

- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

LEGEND - FIRE CABINET TANK SYSTEM

- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.



REVISIONS

NO.	DATE	DESCRIPTION

CAPTIVEAIRE
 Eastern PA Mechanical
 PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 904-4728 EMAIL: mg1008@captiveaire.com
 www.captiveaire.com

Snake Shack-1438-Interquest-CO-R3(Kitchen)
 COLORADO SPRINGS, CO, 80921

DATE: 12/22/2022

DWG.#: 5782747

DRAWN BY: Joe.shiiba

SCALE: 3/4" = 1'-0"

MASTER DRAWING

SHEET NO. 2

NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

FIELD VERIFICATION
 Contractor shall verify all figured dimensions and conditions at job site and notify Aria Group Architects, Inc. of any dimensional errors, omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.
 COPYRIGHT
 Aria Group Architects, Inc. shall retain all common law, statutory and other reserved rights. These drawings and related documents shall not be duplicated, disclosed or otherwise used without written consent of Aria Group Architects, Inc.

NO.	DATE	REMARKS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	05/19/22	ADDENDUM #1
	04/25/22	PERMIT / BID ISSUE FOR LL REVIEW

FOR REFERENCE ONLY

Drawing Title
CAPTIVEAIRE DRAWINGS

Job No. 214815 Drawn _____

Scale Date 05/16/22

Sheet No.
M702

EXHAUST FAN INFORMATION

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	MANUFACTURER	CFM	ESP	RPM	MOTOR ENCL.	HP	BHP	PHASE	VOLT	FLA	DISCHARGE VELOCITY	WEIGHT (LBS)	SDNES
1	KEF-1	1	DU50HFA	CAPTIVEAIRE	700	1.250	1549	TEAD-ECM	0.500	0.3840	1	208	3.8	266 FPM	82	16.7067343199543
2	KEF-2	1	DU50HFA	CAPTIVEAIRE	700	1.250	1549	TEAD-ECM	0.500	0.3840	1	208	3.8	266 FPM	82	16.7067343199543
3	KEF-3	1	DU50HFA	CAPTIVEAIRE	700	1.250	1549	TEAD-ECM	0.500	0.3840	1	208	3.8	266 FPM	82	16.7067343199543
4	KEF-4	1	DU50HFA	CAPTIVEAIRE	700	1.250	1549	TEAD-ECM	0.500	0.3840	1	208	3.8	266 FPM	82	16.7067343199543


FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	KEF-1	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FDR GREASE DUCTS
		1	ECM WIRING PACKAGE - PWM SIGNAL FROM ECPM03 PREWIRE (TELCO MOTOR), CCW ROTATION
		1	2 YEAR PARTS WARRANTY
2	KEF-2	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FDR GREASE DUCTS
		1	ECM WIRING PACKAGE - PWM SIGNAL FROM ECPM03 PREWIRE (TELCO MOTOR), CCW ROTATION
		1	2 YEAR PARTS WARRANTY
3	KEF-3	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FDR GREASE DUCTS
		1	ECM WIRING PACKAGE - PWM SIGNAL FROM ECPM03 PREWIRE (TELCO MOTOR), CCW ROTATION
		1	2 YEAR PARTS WARRANTY
4	KEF-4	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FDR GREASE DUCTS
		1	ECM WIRING PACKAGE - PWM SIGNAL FROM ECPM03 PREWIRE (TELCO MOTOR), CCW ROTATION
		1	2 YEAR PARTS WARRANTY

CURB ASSEMBLIES

NO	DN FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	KEF-1	34 LBS	CURB	19.500"W X 19.500"L X 24.000"H ALONG LENGTH, RIGHT VENTED HINGED.
2	# 2	KEF-2	34 LBS	CURB	19.500"W X 19.500"L X 24.000"H ALONG LENGTH, RIGHT VENTED HINGED.
3	# 3	KEF-3	34 LBS	CURB	19.500"W X 19.500"L X 24.000"H ALONG LENGTH, RIGHT VENTED HINGED.
4	# 4	KEF-4	34 LBS	CURB	19.500"W X 19.500"L X 24.000"H ALONG LENGTH, RIGHT VENTED HINGED.


FANS #1 (KEF-1), #2 (KEF-2), #3 (KEF-3), #4 (KEF-4) - DU50HFA EXHAUST FAN




- FEATURES:**
- DIRECT DRIVE CONSTRUCTION (NO BELTS/PULLEYS).
 - ROOF MOUNTED FANS.
 - RESTAURANT MODEL.
 - UL705 AND UL762 AND ULC-S645
 - VARIABLE SPEED CONTROL.
 - INTERNAL WIRING.
 - THERMAL OVERLOAD PROTECTION (SINGLE PHASE).
 - HIGH HEAT OPERATION 300°F (149°C).
 - GREASE CLASSIFICATION TESTING.
 - NEMA 3R SAFETY DISCONNECT SWITCH.

NORMAL TEMPERATURE TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING AIR AT 300°F (149°C) UNTIL ALL FAN PARTS HAVE REACHED THERMAL EQUILIBRIUM, AND WITHOUT ANY DETERIORATING EFFECTS TO THE FAN WHICH WOULD CAUSE UNSAFE OPERATION.

ABNORMAL FLARE-UP TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING BURNING GREASE VAPORS AT 600°F (316°C) FOR A PERIOD OF 15 MINUTES WITHOUT THE FAN BECOMING DAMAGED TO ANY EXTENT THAT COULD CAUSE AN UNSAFE CONDITION.



PITCHED CURBS ARE AVAILABLE FOR PITCHED ROOFS.
SPECIFY PITCH
EXAMPLE: 7/12 PITCH = 30° SLOPE.



REVISIONS

NO.	DESCRIPTION	DATE

CAPTIVEAIRE
Eastern PA Mechanical
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 804-4128 EMAIL: reg1008@captiveaire.com

Shake Shack-Interquest-CO-R3(Kitchen)
COLORADO SPRINGS, CO, 80921

DATE: 12/22/2022
DWG.#: 5782747
DRAWN BY: Joe.shiiba
SCALE: 3/4" = 1'-0"
MASTER DRAWING

SHEET NO.
3

NOTE:
THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

FIELD VERIFICATION
Contractor shall verify all figured dimensions and conditions at the job site and notify Aria Group Architects, Inc. of any dimensional errors, omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.

COPYRIGHT
Aria Group Architects, Inc. shall retain all common law, statutory and other reserved rights. These drawings and related documents shall not be duplicated, disclosed or otherwise used without the consent of Aria Group Architects, Inc.

NO.	DATE	REVISIONS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	05/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR LL REVIEW


FOR REFERENCE ONLY

Drawing Title
CAPTIVE AIRE DRAWINGS

Job No. 214815	Drawn ---
Scale	Date 05/16/22
Sheet No. M703	

CRIMSON+ CONTROL DETAILS

LOW VOLTAGE & INTERLOCKS (SEE SCHEMATICS FOR LINE VOLTAGE)



SC- Specification:

The Electrical Package, typically FP, is designed to thermostatically activate the exhaust fans for an exhaust hood whenever elevated temperatures are sensed in the exhaust system. This option will meet the requirements of IMC 507.2.1.1 by providing a thermostat(s) mounted in the duct or hood riser to sense increased exhaust temperatures. Controls shall be listed by ETL (UL 508A). The control enclosure shall be NEMA 1 rated and listed for installation inside of the exhaust hood utility cabinet. The control enclosure may be constructed of stainless steel or painted steel.

Temperature probes(s) located in the duct riser shall be constructed of Stainless Steel. A room temperature sensor is also provided for field installation in the kitchen space in order to start the fan(s) based on the temperature differential between the room and the exhaust air in the duct, rather than fixed set-points. The system is factory pre-set to activate the fans at 10 deg F° above the room temperature.

Once the duct temperature reaches the activation point, the exhaust fans will be activated. The controls also provide hysteresis to prevent cycling of the fans after the cooking appliances have been turned off and the heat in the exhaust system is reduced. The hysteresis is factory set 2 degrees and will keep the exhaust running until the temperature falls 2 degrees below the activation set point. A hysteresis timer also exists to keep the fans running for at least 30 min after being activated by the temperature rise.

The activation and hysteresis settings may be field adjusted on the board LCD interface located inside the control enclosure to meet application needs. The panel is factory configured to shut down supply fans, turn on the exhaust fans and turn off the hood lights in a fire condition.

REVISIONS	
DESCRIPTION	DATE

CAPTIVEAIRE
www.captiveaire.com

Eastern PA Mechanical
PO Box 2520, 1 Union Ave, Blain, Pa 15004 PHONE: (877) 504-4238 EMAIL: reg100@captiveaire.com

Shake Shack-Interquest, CO-R3(Kitchen)
COLORADO SPRINGS, CO, 80921

DATE: 12/22/2022
DWG.#: 5782747
DRAWN BY: Joe.shiiba
SCALE: 3/4" = 1'-0"
MASTER DRAWING
SHEET NO. 6

CUSTOMER APPROVAL TO MANUFACTURE:

Approved as Noted

Approved with NO Exception Taken

Revise and Resubmit

SIGNATURE _____

Your Title _____ Date _____

NOTE:
THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

SHAKE SHACK
9723 FEDERAL DR., COLORADO SPRINGS, CO 80921

FIELD VERIFICATION
Contractor shall verify all figured dimensions and conditions at the job site and notify Aria Group Architects, Inc. of any dimensional errors, omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.

COPYRIGHT
Aria Group Architects, Inc. shall retain all common law, statutory and other reserved rights. These drawings and related documents shall not be duplicated, disclosed or otherwise used without written consent of Aria Group Architects, Inc.

NO.	DATE	REVISIONS
3	01/17/23	ISSUE FOR CONSTRUCTION
2	11/04/22	ADDENDUM #2
1	05/19/22	ADDENDUM #1
	05/16/22	ISSUE FOR PERMIT / BID
	04/25/22	ISSUE FOR LL REVIEW

FOR REFERENCE ONLY

Drawing Title
CAPTIVE AIRE DRAWINGS

Job No. 214815
Drawn _____

Scale _____
Date 05/16/22

Sheet No.
M706