

1	HEI	2023-08-21	IFC SET
C	HEI	2023-05-09	ADDENDUM C
B	HEI	2023-04-26	ADDENDUM B
A	HEI	2023-02-08	ADDENDUM A
NO.	BY	DATE	DESCRIPTION



SHAKE SHACK
BLOOMINGDALE, IL

355 ARMY TRAIL ROAD,
BLOOMINGDALE, IL 60108
SHACK #1474

IFC SET

MECHANICAL FLOOR
PLAN

DRAWN BY: *Author*
CHECKED BY: *Checker*
JOB NO: 20188.00


M101

MECHANICAL GENERAL NOTES:

- DO NOT ROUTE ANY DUCTWORK OR PIPING ABOVE ELECTRICAL PANELS.
- REFER TO SHEET M001 FOR ADDITIONAL GENERAL NOTES AND REQUIREMENTS.
- REFER TO DETAILS AND SCHEDULES SHEETS FOR FURTHER INFORMATION.
- MOUNT ALL THERMOSTATS AND SENSORS CONTROLLING HVAC EQUIPMENT AT 48" AFF UNLESS OTHERWISE NOTED.

MECHANICAL PLAN NOTES:


- TYPE I HOODS SHALL BE FURNISHED COMPLETE WITH INTERNALLY PIPED FIRE SUPPRESSION SYSTEM AND EXTERNAL FOAM SUPPLY BOTTLES WITH REMOTE PULL CONTROLS AND IN COMPLIANCE WITH NFPA 96, DIVISION 23 SHALL COORDINATE COMPLETE INSTALLATION WITH FIRE PROTECTION CONTRACTOR TO MEET APPROVAL OF LOCAL INSPECTOR AND CODE COMPLIANCE INCLUDING TESTING.
- TYPE I GREASE HOOD EXHAUST DUCTWORK SHALL BE MINIMUM 18 GAUGE STEEL OR MINIMUM 18 GAUGE STAINLESS STEEL WITH LIQUID TIGHT WELDS. DUCTWORK MUST HAVE FLANGE OR LAP WELDS. BUTT WELDS ARE NOT PERMITTED. INSTALL ACCESS PANELS FOR CLEANING AS REQUIRED BY NFPA 96 AND LOCAL CODES. TRANSITION GREASE DUCTWORK AS REQUIRED TO HOOD AND FAN CONNECTIONS. PROVIDE 45° MAX OFFSETS AS REQUIRED TO COORDINATE WITH STRUCTURE. PROVIDE RADIUS ELBOWS WITHOUT TURNING VANES. SLOPE HORIZONTAL GREASE DUCT BACK TOWARDS HOOD AT MINIMUM OF 1/4" PER LINEAL FOOT. GREASE DUCTS SHALL BE CONTAINED IN A UL APPROVED GREASE DUCT WRAP SYSTEM.
- MOUNT THERMOSTATS AND TEMPERATURE SENSOR(S) ON WALL. THERMOSTATS AND SENSOR(S) SHALL BE LABELED TO MATCH THE UNIT TAG AND CORRESPOND TO THE ELECTRICAL LEGEND IN THE ELECTRICAL PANELBOARD SERVING THE EQUIPMENT. COORDINATE COLOR WITH ARCHITECT.
- 8"X8" GREASE EXHAUST DUCT UP TO KEF-1 ON ROOF.
- 8"X8" GREASE EXHAUST DUCT UP TO KEF-2 ON ROOF.
- 8"X8" GREASE EXHAUST DUCT UP TO KEF-3 ON ROOF.
- 8"X8" GREASE EXHAUST DUCT UP TO KEF-4 ON ROOF.
- COMBINATION TEMPERATURE SENSOR AND HUMIDITY SENSOR.
- PROVIDE SA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.
- PROVIDE RA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.
- INSTALL HOOD FIRE SUPPRESSION MANUAL PULL STATION. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH FIRE SUPPRESSION SYSTEM INSTALLER AND THE BUILDING FIRE ALARM SYSTEM.
- CARBON DIOXIDE SENSOR WITH REMOTE ALARM REPEATER FURNISHED BY OWNERS VENDOR. RELAY SHALL BE INTERLOCKED WITH THE BUILDING FIRE ALARM SYSTEM. THE SENSOR SHALL BE EQUIPPED WITH A LOCAL AUDIBLE AND VISUAL ALARM. THE LOW LEVEL ALARM SHALL ACTIVATE THE LOCAL AUDIBLE AND VISUAL ALARM. THE HIGH LEVEL ALARM SHALL ACTIVATE RELAY. INSTALL SENSOR PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- INSTALL "ULTIMATE DOOR" ON DUCTS 12" OR LARGER AND INSTALL "ULTIMATE F1 SANDWICH ACCESS DOOR" FOR DUCTS LESS THAN 12" ON GREASE DUCT ACCESS PANELS FOR CLEANING IN LOCATIONS SHOWN AT A MINIMUM AND AS REQUIRED BY NFPA 96 AND LOCAL CODES. OPENING SHALL BE NO LESS THAN 12" IN THE ALLOWABLE DIMENSION FOR CLEANING AND MAINTENANCE.
- INSTALL DUCT SMOKE DETECTOR IN RETURN AIR PLENUM.
- REFRIGERANT PIPING UP TO CU-1 ON ROOF. REF 1M150.
- ROUTE DUCTWORK LEVEL, TIGHT TO STRUCTURE, AND ABOVE LIGHTS. COORDINATE WITH STORM DRAINAGE, STRUCTURAL, AND ELECTRICAL.
- INSTALL CAPTIVE AIRE REMOTE HOOD TANK SYSTEM CABINET TIGHT TO CEILING PER MANUFACTURER'S INSTRUCTIONS.
- HOOD SHALL OVERHANG THE COOKING SURFACE BY AT LEAST 6" ON BOTH SIDES.
- INSTALL REMOTE MOUNTED HOOD MONITORING PANEL ON WALL BELOW TANK SYSTEM CABINET PER MANUFACTURER'S INSTRUCTIONS.
- PROVIDE EA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.
- CONTRACTOR TO COORDINATE 1" UNDERCUT ON DOOR FOR EXHAUST AIR PATH.
- WALL MOUNT REMOTE HOOD CONTROLLER 48" A.P.F. CONTROLLER PROVIDED WITH HOOD PACKAGE BY OWNER.



ALL GREASE DUCT TO BE WATER TESTED BY ENVIRONMENTAL MECHANICAL CONTRACTOR'S EXPENSE. CONTACT OWNER'S NATIONAL ACCOUNT VENDOR:
ENVIRONMENTAL
DON PFLEDERER
1.800.325.8476
inspections@enviromatic.com

THE BUILDINGS HVAC SYSTEMS SHALL BE BALANCED BY NATIONAL TAB (NO EXCEPTIONS) AND CONTRACTED BY THE GENERAL CONTRACTOR.
CONTACT:
WILL TURNBOUGH
will@nationaltab.com
655-682-6822 ext1704

MECHANICAL FLOOR PLAN
1/4" = 1'-0"




MECHANICAL GENERAL NOTES:

1. ALL VENT STACKS SHALL BE NO LESS THAN 12" FROM PARAPET, AT LEAST 10 FEET FROM OUTSIDE AIR INTAKES, AND ABOVE ROOF SURFACE 6" MINIMUM TO FULL HEIGHT OF PARAPET, WHICHEVER IS GREATER. CONTRACTOR SHALL PROVIDE BRACING AS SPECIFIED.
2. COORDINATE EXACT EQUIPMENT LOCATIONS WITH OTHER TRADES PRIOR TO INSTALLATION.
3. REFER TO SHEET M001 FOR ADDITIONAL GENERAL NOTES.
4. REFER TO DETAILS AND SCHEDULES SHEETS FOR FURTHER INFORMATION.

MECHANICAL PLAN NOTES:

1. AREA RESERVED FOR REFRIGERATION CONDENSER(S) PROVIDED BY KITCHEN EQUIPMENT CONTRACTOR. COORDINATE EQUIPMENT LOCATION AND CONDENSER INSTALLATION WITH KITCHEN EQUIPMENT CONTRACTOR.
2. MAINTAIN ALL OUTSIDE AIR INTAKES A MINIMUM OF 10'-0" RADIUS FROM EXHAUST, TYPICAL.
3. TURN DOWN 6"0" INTAKE AND END OPEN OVER ROOF (MIN. 24") WITH INSECT SCREEN.
4. REFERENCE PLUMBING DRAWINGS FOR CONDENSATE DRAIN ROUTING AND TERMINATION REQUIREMENTS.
5. CONTRACTOR SHALL COORDINATE WITH NATIONAL TAB TO PROVIDE UV-PIH INDOOR AIR PURIFICATION SYSTEM, MODEL PHI-PKG-24V. INSTALL IN UNIT BLOWER COMPARTMENT PER MANUFACTURER'S INSTRUCTIONS.
6. CONTRACTOR SHALL VERIFY WITH EQUIPMENT SUPPLIER EXACT ROUTING AND SIZE OF INSULATED REFRIGERANT PIPING. SINGLE LINESHET SHOWN FOR CLARITY. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.



1 MECHANICAL ROOF PLAN
1/4" = 1'-0"

Bergmeyer

LA
800 South Figueroa St.
Los Angeles, CA 90017
212.337.1090

BOB
91 Shepley St.
Boston, MA 02210
617.542.1025

www.bergmeyer.com


CONSULTANTS:

HENDERSON
ENGINEERS
8345 LENEXA DRIVE, SUITE 300
LENEXA, KS 66214
TEL 913.742.2000 FAX 913.742.5001
WWW.HENDERSONENGINEERS.COM

2250003452
IL CORPORATE NO. 184-002965
EXPIRES 4/30/2025

SEAL SIGNATURE:

EXPIRES ON: 11/30/2023



08/21/2023

NO.	BY	DATE	DESCRIPTION
1	HEI	2023-08-21	IFC SET
C	HEI	2023-05-09	ADDENDUM C
B	HEI	2023-04-26	ADDENDUM B
A	HEI	2023-02-08	ADDENDUM A
	HEI	2023-01-09	PERMIT/IBID SET



SHAKE SHACK
BLOOMINGDALE IL


355 ARMY TRAIL ROAD,
BLOOMINGDALE, IL 60108
SHACK #1474

IFC SET


MECHANICAL ROOF PLAN

DRAWN BY: _____ Author
CHECKED BY: _____ Checker
JOB NO: _____ 20188.00

M150




- NOTES:**
- ALL ATTACHMENTS SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS AND SHALL BE APPROVED FOR THE SPECIFIC APPLICATION.
 - COORDINATE ALL ATTACHMENTS WITH ARCHITECT AND STRUCTURAL ENGINEER.
 - REFER TO SPECIFICATIONS FOR MORE INFORMATION ON APPROVED ATTACHMENT METHODS.
 - REFER TO SPECIFICATIONS FOR REQUIREMENTS RELATING TO SEISMIC INSTALLATIONS.
 - FOR OPEN WEB JOIST STRUCTURE, CONTRACTOR MAY HANG FROM TOP CHORD AND RUN DUCT AND PIPING THROUGH WEB JOIST WHEN APPROPRIATE. ANY CONCENTRATED LOADS NOT OCCURRING AT JOIST PANEL POINTS MUST BE REVIEWED BY A STRUCTURAL ENGINEER FOR FIELD INSTALLED PANEL BRACE REQUIREMENTS.




- NOTES:**
- CUT METAL DECKING TO ALLOW CURB INSTALLATION ON STEEL FRAMING. AFTER CURB IS SET IN PLACE, TRIM REMAINING METAL DECKING AND INSTALL WITHIN CURB. TACK WELD DECKING TO SUPPORT STEEL. DO NOT WELD INTERIOR DECKING TO ROOF CURB. PROVIDE ADDITIONAL CROSS FRAMING TO SUPPORT INTERIOR DECKING AND FILL MATERIAL AS REQUIRED.
 - REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR ROOF CURBS, ANCHORING AND SEISMIC/WIND RESISTANCE.

13 ROOF CURB DETAIL
NTS


14 HANGER UPPER ATTACHMENT DETAILS
NTS




10 ROUND AIR DUCT OR PIPE PENETRATION THROUGH ROOF DETAIL
NTS



9 ROOF EQUIPMENT SUPPORT RAIL DETAIL
NTS




6 DUCT HANGER LOWER ATTACHMENT DETAILS
NTS




5 KITCHEN EXHAUST HOOD ELEVATION DETAIL
NTS

6 DUCT HANGER LOWER ATTACHMENT DETAILS
NTS


5 KITCHEN EXHAUST HOOD ELEVATION DETAIL
NTS




2 HARD CEILING DIFFUSER DETAIL
NTS




1 LAY-IN CEILING DIFFUSER DETAIL
NTS




12 UPBLAST GREASE EXHAUST FAN DETAIL
NTS




11 DOWNBLAST EXHAUST FAN DETAIL
NTS




8 GREASE DUCT CLEANOUT ACCESS DOOR DETAIL
NTS



7 GREASE DUCT FIRE WRAP INSULATION INSTALLATION DETAIL
NTS



4 CEILING CASSETTE DETAIL
NTS



3 DUCT MOUNTED REGISTER DETAIL
NTS

- NOTES:**
- SUBMIT SHOP DRAWINGS OF ALL HOOD SYSTEMS TO CITY FOR APPROVAL PRIOR TO INSTALLATION.
 - TOTAL HOOD SYSTEM TO BE IN COMPLETE CONFORMANCE WITH NFPA, AND ALL LOCAL CODES AND REGULATIONS.
 - COORDINATE ALL FIRE PROTECTION SYSTEMS WITH FIRE PROTECTION CONTRACTOR WHO SHALL ALSO BE RESPONSIBLE FOR ALL PERMITS AND TESTING REQUIRED.
 - PROVIDE WRAP SYSTEM WHERE APPROVED BY LOCAL CODES IN LIEU OF RATED ENCLOSURE.
 - PROVIDE ACCESS PANELS AS REQUIRED BY LOCAL CODE AND PER PLAN.
 - HOODS SHALL EXTEND MINIMUM 6" BEYOND ALL OPEN SIDES AND FRONT EDGE OF FOOD COOKING EQUIPMENT BEING SERVED.

NO.	BY	DATE	DESCRIPTION
1	HEI	2023-08-21	IFC SET
C	HEI	2023-05-09	ADDENDUM C
B	HEI	2023-04-26	ADDENDUM B
A	HEI	2023-02-08	ADDENDUM A
HEI	2023-01-09	PERMIT/IBID SET	



SHAKE SHACK
BLOOMINGDALE, IL

355 ARMY TRAIL ROAD,
BLOOMINGDALE, IL 61018
SHACK #1474

IFC SET

MECHANICAL DETAILS

DRAWN BY: Author
CHECKED BY: Checker
JOB NO: 20188.00

M501

Division 23: TABLE OF CONTENTS

GENERAL MECHANICAL REQUIREMENTS

1. GENERAL INSTRUCTIONS

- A. GENERAL REQUIREMENTS
B. DEFINITIONS
C. PRE-BID SITE VISIT
D. MATERIAL AND WORKMANSHIP
E. MANUFACTURERS
F. COORDINATION
G. ORDINANCES AND CODES
H. PROTECTION OF EQUIPMENT AND MATERIALS
I. SUBSTITUTIONS
J. SUBMITTALS
K. ELECTRONIC DRAWINGS FILES
L. RECORD DRAWINGS (AS-BUILT DRAWINGS)
M. OPERATION AND MAINTENANCE INSTRUCTIONS
N. SPARE PARTS
O. TRAINING
P. WARRANTIES

2. GENERAL MATERIALS AND INSTALLATION

- A. BUILDING OPERATION
B. EXISTING EQUIPMENT REUSE AND REMOVAL
C. EXCAVATION AND BACKFILLING
D. INCIDENTAL DAMAGE
E. CUTTING AND PATCHING
F. ROUGH-IN
G. STRUCTURAL SUPPORT SYSTEMS
H. PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS AND CURBS
I. ACCESS PANELS AND DOORS
J. PENETRATIONS
K. FIRESTOPPING
L. MOTORS AND STARTERS
M. VARIABLE FREQUENCY DRIVES
N. ELECTRICAL WIRING
O. EQUIPMENT FURNISHED BY OTHERS
P. SYSTEM TESTING, ADJUSTING AND BALANCING
Q. VIBRATION ISOLATION
R. SEISMIC CONTROLS FOR MEFP SYSTEMS
S. AIR FILTERS
T. REFRIGERANT AND OIL
U. IDENTIFICATION

3. DUCT INSULATION, DUCTWORK, ACCESSORIES, FLUES AND FANS

- A. DUCT INSULATION
B. DUCTWORK
C. FLEXIBLE FLUE GAS VENTS
D. AIR DEVICES
E. CONTROL DAMPERS
G. EXHAUST AIR SYSTEMS
H. KITCHEN EXHAUST AIR SYSTEMS

4. HVAC EQUIPMENT

- A. ROOFTOP UNITS (GAS FIRED HEAT) 3-25 TONS
B. ELECTRIC UNIT HEATERS
C. NATURAL GAS RADIANT HEATERS
D. SPLIT DUCTLESS AIR-CONDITIONING SYSTEMS
E. AIR CURTAINS

5. PIPING AND PIPING SPECIETIES

- A. REFRIGERANT PIPING AND INSULATION
B. SYSTEM EVACUATION AND CHARGING

6. TEMPERATURE CONTROLS

- A. GENERAL REQUIREMENTS
B. WIRING
C. THERMOSTAT CONTROL EQUIPMENT
D. SENSORS AND RELAYS

7. SEQUENCE OF OPERATION

- A. FAN COIL UNIT CONTROL
B. KITCHEN EXHAUST FAN CONTROL
C. MAKEUP AIR UNIT CONTROL
D. ROOFTOP UNIT CONTROL
E. RESTROOM EXHAUST FAN (EF-1) CONTROL
F. AIR CURTAIN CONTROL
G. ELECTRIC UNIT HEATER CONTROL

8. ALTERNATIVES

- A. DESCRIPTION

9. COMMISSIONING OF MECHANICAL SYSTEM

- A. GENERAL
B. EXECUTION

DESIGNER NOTE: EDIT THIS TABLE OF CONTENTS AS REQUIRED FOR YOUR PROJECT

Division 23: HEATING, VENTILATING, AND AIR CONDITIONING

1. GENERAL INSTRUCTIONS

A. GENERAL REQUIREMENTS

All requirements under Division 01 and the general and supplementary conditions of these specifications apply to this section and division. Where the requirements of this section and division exceed those of Division 01, this section and division take precedence.

The specifications and drawings for the project are complementary, and any portion of work described in one shall be provided as if described in both. In the event of discrepancies, notify the Engineer and request clarification prior to proceeding with the work involved.

B. DEFINITIONS

Division: References contained in this specification follow the numbering system defined in the Construction Specifications Institute (CSI) MasterFormat 2004 Edition.

- 1. Division 21 - Fire Suppression
2. Division 22 - Plumbing
3. Division 23 - HVAC
4. Division 26 - Electrical
5. Division 27 - Communications
6. Division 28 - Electronic Safety and Security

Furnish: "to supply and deliver to the project site, ready for unloading, unpacking, assembling, installation and similar operations."

Install: "to perform all operations at the project site including, but not limited to, the actual unloading, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, testing, commissioning, starting up and similar operations, complete and ready for the intended use."

Engineer: Where referenced in this division, "Engineer" is the Engineer of Record and the Design Professional for the work under this division, and is a consultant to, and an authorized representative of the Architect, as defined in the General and/or Supplementary Conditions. When used in this division, Engineer means increased involvement by and obligations to the Engineer, in addition to involvement by and obligations to the Architect.

NRTL: National recognized testing laboratory, as defined and listed by OSHA in 29 CFR 1910.7 (e.g., UL, ETL, CSA), and acceptable to the AHJ for this project. Nationally recognized testing laboratories and standards listed are used only to represent the characteristics required and are not intended to restrict the use of other NRTLs that are acceptable to the AHJ and standards that meet the specified criteria.

Substitution: Changes in products, materials, equipment, and methods of construction those required by the Contract Documents and proposed by Contractor. Substitutions include Value Engineering proposals.

The terms "approved equal", "equivalent", or "equal" are used synonymously and shall mean "accepted by or acceptable to the Engineer as equivalent to the item or manufacturer specified".

C. PREBID SITE VISIT

Prior to submitting bid, visit the site of the proposed work and become fully informed as to the conditions under which the work is to be performed and the requirements shall not be considered sufficient justification to request or obtain extra compensation over and above the contract price.

D. MATERIAL AND WORKMANSHIP

Provide new material, equipment, and apparatus under this contract unless otherwise stated herein, of best quality normally used for the purpose in good commercial practice, and free from defects. Install material and equipment in accordance with the manufacturer's installation instructions.

Pipe, pipe fittings, pipe specialties and valves shall be manufactured in plants located in the United States or certified to meet the specified ASTM and ANSI standards.

Work performed under this contract shall provide a neat and "workmanlike" appearance when completed, to the satisfaction of the Architect and Engineer. Workmanship shall be the finest possible by experienced mechanics.

The complete installation shall function as designed and intended with respect to efficiency, capacity, noise level, etc. Abnormal noise caused by rattling equipment, piping, or vibrating components shall not be acceptable.

Remove from the premises waste material present as a result of work performed under this contract and clean installation of the Architect or termination of the work.

Repair or replace public and private property damaged as a result of work performed under this contract to the satisfaction of authorities and regulators having jurisdiction. Provide all safety lights, guards, and warning signs required for the performance of the work and for the safety of the public.

E. MANUFACTURERS

In other articles where lists of manufacturers are introduced, subject to compliance with requirements, provide products by one of the manufacturers specified.

Where a list is provided, manufacturers are listed alphabetically and not in accordance with any ranking or preference.

Where manufacturers are not listed, provide products subject to compliance with requirements from manufacturers that have been actively involved in manufacturing the specified product for no less than 5 years.

F. COORDINATION

Coordinate work with that of other trades so that the various components of the systems are installed at the proper time, will fit the available space, and will allow proper service access to those items requiring maintenance.

Unless otherwise indicated, the General Contractor shall provide chases and openings in building construction required for installation of the systems specified herein.

Figured dimensions shall be taken in preference to scale dimensions. Contractor shall take his own measurements at the building as variations may occur.

G. ORDINANCES AND CODES

Work performed under this contract shall, at a minimum, be in conformance with applicable national, state and local codes having jurisdiction. Equipment furnished and associated installation work performed under this contract shall be in strict compliance with current applicable codes adopted by the local AHJ, including any amendments and standards as set forth by the following:

- 1. National Electrical Code (NEC)
2. National Fire Protection Association (NFPA)
3. Underwriters Laboratories (UL)
4. Occupational Safety and Health Administration (OSHA)
5. American Society of Mechanical Engineers (ASME)
6. American Society of Heating, Refrigerating, and Air Conditioning Engineers (ASHRAE)
7. American National Standards Institute (ANSI)
8. American Society of Testing and Materials (ASTM)
9. Other national standards and codes where applicable.

Where the contract documents exceed the requirements of the referenced codes, standards, etc., the contract documents take precedence. Where conflicts between various codes, ordinances, rules, and regulations exist, comply with the most stringent.

Promptly bring all conflicts observed between codes, ordinances, rules, regulations, referenced standards, and these documents to the attention of the Architect and Engineer for final resolution. Contractor will be held responsible for any violation of the law.

Procure and pay for permits and licenses required for the accomplishment of the work herein described. Where required, obtain, pay for, and furnish certificates of inspection to Owner.

H. PROTECTION OF EQUIPMENT AND MATERIALS

Store and protect from damage equipment and materials delivered to job site. For materials and equipment susceptible to changing weather conditions, dampness, or temperature variations, store inside in conditioned spaces.

Plug, seal, or cap open ends of ductwork and piping systems while stored and installed during construction when not in use to prevent the entrance of debris into the systems.

I. SUBSTITUTIONS

Materials, products, equipment, and systems described in the Bidding Documents establish a standard of required function, dimension, appearance and quality to be met by the proposed substitution.

Unless stated otherwise in writing to the Engineer by the Contractor, Contractor warrants to the Engineer, Architect, and Owner the following:

- 1. Proposed substitution has been fully investigated and determined to meet or exceed the specified Work in all respects unless stated otherwise in the substitution request.
2. Proposed substitution is consistent with the Contract Documents and will produce indicated results, including functional clearances, maintenance service, and access.
3. Proposed substitution has received necessary approvals of authorities having jurisdiction.
4. Same warranty will be furnished for proposed substitution as for specified Work.
5. If accepted substitution fails to perform as required, Contractor shall replace substitute material or system with that originally specified and bear costs incurred thereby.
6. Coordination, installation and changes in the Work as necessary for accepted substitution will be complete in all respects.

No substitutions will be considered unless the Substitution Request Form is completed and attached with the appropriate substitution documentation. No substitution will be considered prior to receipt of bids unless written request for approval to bid has been received by the Engineer at least ten (10) calendar days prior to the date for receipt of bids.

J. SUBMITTALS

Assemble and submit for review shop drawings, material lists, manufacturer product literature for equipment to be furnished, and items requiring coordination between contractors under this contract.

Transmit submittals as early as required to support the project schedule. Allow for two weeks Engineer review time, plus to/from mailing time via the Architect, plus a duplication of this time for resubmittal, if required.

Submittals shall contain the project name, applicable specification section, submittal date, equipment identification acronym as used on the drawings, and the Contractor's stamp.

Separate submittals according to individual specification sections. Illegible submittals will be rejected and returned without review. Catalog data shall be properly bound, identified, indexed and tabbed in a 3-ring binder.

Provide the quantity of submittals required by Division 01. If not indicated and hard-copy sets are provided, submit a minimum of six (6) copies. Refer to Division 01 for acceptance of electronic submittals for this project.

Provide the quantity of submittals required by Division 01. If not indicated and hard-copy sets are provided, submit a minimum of six (6) copies. Refer to Division 01 for acceptance of electronic submittals for this project.

The checking and subsequent acceptance of submittals by the Engineer and/or Architect shall not relieve the Contractor of responsibility for deviations from the drawings and specifications, errors in dimensions, details, size of members, or quantities, omissions of components or fittings, and not coordinating items with actual building conditions and adjacent work.

K. ELECTRONIC DRAWING FILES

In preparation of shop drawings or record drawings, Contractor may, at his option, obtain electronic drawing files in AutoCAD or DXF format on CD-ROM disk, DVD disk, flash drive or direct download, as desired, from the Engineer for a shipping and handling fee of \$200 for a drawing set up to 12 sheets and \$15 per sheet for each additional sheet.

During progress of the work in this division, Contractor shall maintain an accurate record of all changes made during the installation of the system. Upon completion of the work, accurately transfer all record information to three identical sets of the approved shop drawings. Insert one set into each copy of the manual described below.

M. OPERATION AND MAINTENANCE INSTRUCTIONS

During the course of construction, collect and compile a complete brochure of equipment furnished and installed on this project. Include operational and maintenance instructions, manufacturer's catalog sheets, wiring diagrams, parts lists, approved submittals and shop drawings, warranties, and descriptive literature as furnished by the manufacturer.

N. SPARE PARTS

Furnish to Owner, with receipt, the following spare parts for the equipment furnished for this project: One set of spare filters of each type required for each unit. In addition to the spare set of filters, install new filters prior to testing, adjusting, and balancing work and before turning system over to Owner.

O. TRAINING

At a time mutually agreed upon between the Owner and Contractor, provide the services of a factory trained and authorized representative to train Owner's designated personnel on the operation and maintenance of the equipment provided for this project.

Provide training to include, but not be limited to, an overview of the system and/or equipment as it relates to the facility as a whole; operation and maintenance procedures and schedules related to startup and shutdown, troubleshooting, servicing, preventive maintenance and appropriate operator intervention; and review of data included in the operation and maintenance manual.

Submit a certification letter to the Architect stating that the Owner's designated representative has been trained as specified herein. Letter shall include date, time, attendees and subject of training. The Contractor and the Owner's representative shall sign the certification letter indicating agreement that the training has been provided.

P. WARRANTIES

Warrant each system and each element thereof against all defects due to faulty workmanship, design, or material for a period of 12 months from date of Substantial Completion, unless specific items are noted to carry a longer warranty in the construction documents or manufacturer's standard warranty exceeds 12 months.

Q. COORDINATION

Coordinate work with that of other trades so that the various components of the systems are installed at the proper time, will fit the available space, and will allow proper service access to those items requiring maintenance.

Unless otherwise indicated, the General Contractor shall provide chases and openings in building construction required for installation of the systems specified herein.

Figured dimensions shall be taken in preference to scale dimensions. Contractor shall take his own measurements at the building as variations may occur.

Procure and pay for permits and licenses required for the accomplishment of the work herein described. Where required, obtain, pay for, and furnish certificates of inspection to Owner.

H. PROTECTION OF EQUIPMENT AND MATERIALS

Store and protect from damage equipment and materials delivered to job site. For materials and equipment susceptible to changing weather conditions, dampness, or temperature variations, store inside in conditioned spaces.

Plug, seal, or cap open ends of ductwork and piping systems while stored and installed during construction when not in use to prevent the entrance of debris into the systems.

Remove all unused equipment, ductwork, piping, and associated supports. Cap ductwork and piping at mains and seal air and water tight.

Provide items of HVAC systems modification required because of building remodeling, as noted on the drawings or necessary for proper operation. Match existing materials and construction techniques when modifying existing systems unless specified otherwise.

Seal airtight existing ductwork required to be abandoned in place or not in use at the termination of the work.

Clean and rebalance existing ductwork, diffusers, registers, and grilles intended for reuse as required or as indicated on drawings.

Clean and refurbish existing HVAC equipment intended for reuse as required for proper operation including replacement of filters, belts, motors, remote controls, and safety interlocks.

C. EXCAVATION AND BACKFILLING

Perform excavation and backfill required for installation of underground work under this contract. Trenches shall be of sufficient width. Crisp or brace trenches to prevent cave-in or settlement. Do not excavate trenches close to columns and walls of new building without prior consultation with the Architect.

Excavation as specified herein shall be classified as common excavation. Common excavation shall comprise the satisfactory removal and disposition of material of whatever substances and of every description encountered, including rock, if any, within the limits of the work as specified and shown on the drawings.

D. INCIDENTAL DAMAGE

Repair streets, sidewalks, drives, paving, walls, finishes, and other facilities damaged in the course of the work. Repair materials shall match existing construction. Repair work shall meet all requirements of the Owner, local authorities having jurisdiction, and meet the satisfaction of the Architect.

E. CUTTING AND PATCHING

Conform to the requirements in Division 01. Cut walls, floors, ceilings, and other portions of the facility as required to install work under this division. Obtain permission from the Architect prior to cutting. Do not cut or disturb structural members without prior approval from the Architect and Structural Engineer.

F. ROUGH-IN

Coordinate without delay all rough-in with other divisions. Conceal piping, conduit, and rough-in except in unfinished areas and where otherwise shown.

G. STRUCTURAL SUPPORT SYSTEMS

Structural steel used for support of equipment, ductwork and piping shall be new, clean, and conform to ASTM Designation A-36. Support mechanical components from the building structure. Do not support mechanical components from ceilings, other mechanical or electrical components, and other non-structural elements.

H. PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS AND CURBS

Provide prefabricated equipment support rails and roof curbs manufactured by AES Industries, Custom Curb, Inc., Pate Company, Thybor or approved equal. Provide roof and step to match roof insulation thickness.

Attach equipment directly to pre-engineered roof equipment support using one of the following methods: 1. Rail Equipment Supports: Secure each equipment support to the rail with a minimum of 4 points of connection per leg.

1. Rail Equipment Supports: Secure each equipment support to the rail with a minimum of 4 points of connection per leg. 2. Roof Curbs: Secure each curb of the equipment to the curb nailer using a minimum of 4 lag screws, located along the length of the equipment.

1. Rail Equipment Supports: Secure each equipment support to the rail with a minimum of 4 points of connection per leg. 2. Roof Curbs: Secure each curb of the equipment to the curb nailer using a minimum of 4 lag screws, located along the length of the equipment.

1. Rail Equipment Supports: Secure each equipment support to the rail with a minimum of 4 points of connection per leg. 2. Roof Curbs: Secure each curb of the equipment to the curb nailer using a minimum of 4 lag screws, located along the length of the equipment.

1. Rail Equipment Supports: Secure each equipment support to the rail with a minimum of 4 points of connection per leg. 2. Roof Curbs: Secure each curb of the equipment to the curb nailer using a minimum of 4 lag screws, located along the length of the equipment.

I. ACCESS PANELS AND DOORS

Refer to Architectural documents for specification of access panels and doors. Provide access doors for all concealed equipment and duct and piping accessories that require service where indicated or as required, except where above lay-in ceilings.

Provide access doors for all concealed equipment and duct and piping accessories that require service where indicated or as required, except where above lay-in ceilings. Access doors shall be adequately sized for the devices served with a minimum size of 18 inches x 18 inches.

J. PENETRATIONS

Provide sleeves for pipes passing through above grade concrete or masonry walls, concrete floor or roof slabs. Sleeves are not required for core drilled holes in existing masonry walls, concrete floors or roofs.

Seal concrete or masonry exterior wall penetrations below grade with "wall pipes" and mechanical sleeve seals. Provide cast iron "wall pipes" with integral waterstop ring manufactured by Jay R. Smith, Josam, Wade, Watts or Zum.

Seal elevated concrete slab with water proof membrane penetrations with "wall pipes" and water proof sealant. Secure waterproof membrane flashing between "wall pipe" clamping flange and clamping ring.

Provide sleeves for horizontal pipe passing through or under foundation. Sleeves shall be cast iron soil pipe two nominal pipe sizes larger than the pipe served.

Provide Schedule 40 PVC pipe sleeves for vertical pressure pipe passing through concrete slab on grade. Sleeves shall be one nominal pipe size larger than the pipe served and two pipe sizes larger than pipe served for ductile iron pipes with restraining rods.

Provide 1/2 inch thick cellular foam insulation around perimeter of non-pressure pipe passing thru concrete slab on grade. Insulation shall extend to 2 inches above and below the concrete slab.

K. FIRESTOPPING

Sealants and accessories shall have fire-resistance ratings indicated, as established by testing identical assemblies in accordance with UL 2079 or ASTM E 814, or other NRTL acceptable to AHJ.

Through and Membrane Penetration Specified Systems Product Schedule: Provide UL listing, location, wall or floor rating, and installation drawing for each penetration fire stop system.

Where project conditions require modification to qualified testing and inspecting agency's illustrations for a particular firestopping condition, submit illustration, with modifications marked, approved by penetration firestopping manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly.

L. MOTORS AND STARTERS

Provide motors and starting equipment where not furnished with the equipment package. Motors shall have copper windings, Class B insulation, and standard squirrel cage with starting torque characteristics suitable for the equipment served.

Provide every motor, except fractional horsepower single phase with an approved type of "built-in" thermal overload protection, with a motor starter. Each starter shall be provided with overload heaters sized to the motor rating, and every three phase motor starter shall have overload heaters in each phase.

Provide every motor, except fractional horsepower single phase with an approved type of "built-in" thermal overload protection, with a motor starter. Each starter shall be provided with overload heaters sized to the motor rating, and every three phase motor starter shall have overload heaters in each phase.

Provide every motor, except fractional horsepower single phase with an approved type of "built-in" thermal overload protection, with a motor starter. Each starter shall be provided with overload heaters sized to the motor rating, and every three phase motor starter shall have overload heaters in each phase.

M. VARIABLE FREQUENCY DRIVES

Provide VFD variable frequency drives (VFD) to control fan or pump motors as indicated on the drawings. Provide VFD as manufactured by AC Technology, Asea Brown Boveri, Danfos, Reliance Electric, or Yaskawa.

Provide a magnetic contactor manual bypass integral to each drive. Provide two magnetic contactors, mechanically and electrically interlocked, to isolate the inverter output from line voltage.

The VFD shall have an RS-485 port as standard. The standard protocols shall be Johnson Controls N2 bus, Modbus, and Siemens Building Technologies FLN. Optional protocols for BACnet, DeviceNet, Ethernet, LonWorks, and Profibus shall be available.

Drive supplier shall provide jobsite start-up, Owner training, and a one-year parts and on-site labor warranty. Multiple visits shall be included to allow for tuning and troubleshooting of the controls system as required.


Bergmeyer logo and contact information: 800 South Figueroa St., Los Angeles, CA 90017. Tel: 913.742.2000, Fax: 913.742.1090.

HENDERSON ENGINEERS logo and contact information: 8345 LENEXA DRIVE, SUITE 300, LENEXA, KS 66214. Tel: 913.742.2000, Fax: 913.742.5001.

COY M. MACY logo and contact information: 250030452, IL CORPORATE NO. 184-020266, EXPRES 4-302025.

08/21/2023

Table with columns: I, HEI, DATE, IFC SET, ACCENDUM C, ACCENDUM B, ACCENDUM A, PERMIT/BD SET.



SHAKE SHACK BLOOMINGDALE IL

355 ARMY TRAIL ROAD, BLOOMINGDALE, IL 60108 SHACK #1474

IFC SET

MECHANICAL SPECIFICATIONS

Table with columns: DRAWN BY, CHECKED BY, JOB NO., Author, Checker, 20188.00

M590

N. ELECTRICAL WIRING

High voltage wiring is defined as 50 Volts or higher. Low voltage wiring is defined as less than 50 Volts. Line voltage wiring shall be provided by Division 26. Line voltage control and interlock wiring for mechanical systems shall also be provided by Division 26. Low voltage control wiring shall be provided by Division 23. Furnish wiring diagrams to Division 26 as required for proper equipment hookup. Coordinate with Division 26 the actual wire sizing amps for mechanical equipment (from the equipment nameplate) to ensure proper installation.

Provide power and communication wiring with transient protection in accordance with IEEE C62.41.2. All control and interlock wiring shall comply with the NEC. Control wiring shall be sized to accommodate the voltage drop associated with the distance between the control device and the controller. Control wiring not installed in conduit shall be UL rated for plenum installation. All NEC Class 1 (line voltage) wiring shall be UL listed in approved raceway according to the NEC and Division 26 requirements. Maximum allowable voltage for control wiring shall be 120 V. All low-voltage wiring shall meet NEC Class 2 requirements. Low-voltage power circuits shall be sub-fused when required to meet Class 2 current limit.

Conduit for Control Wiring: EMT with compression fittings, cold rolled steel, zinc coated or zinc-coated rigid steel with threaded connections.

Pull and Junction Boxes: Size according to number, size, and position of entering raceway as required by National Electrical Codes. Enclosure type shall be suited to location.

Install wiring parallel to building lines wherever possible. Conceal all control wiring in finished rooms. Do not install Class 2 wiring in raceway containing Class 1 wiring. Boxes and panels containing high voltage wiring and equipment may not be used for low-voltage wiring except for the purpose of interfacing the two wires (e.g., relays and transformers). All wire-to-device and wire-to-wire connections shall be made at a terminal block or terminal strip. All runs of communication wiring shall be unspliced length when that length is commercially available. Verify the integrity of the entire run following the cable installation. Use appropriate test measures for each portion/cable. Label all wiring and cabling at each end within 2 inches of termination with the controller/termination number. Label control devices used in the system with permanent labels using the identifiers that match the record documents.

O. EQUIPMENT FURNISHED BY OTHERS

Provide necessary equipment and accessories that are not provided by the equipment supplier or Owner to complete installation of equipment furnished by others in locations as indicated on the drawings, specified herein, or both. Equipment and accessories not provided by the equipment supplier may include, but not be limited to, fuses, vents, intakes, associated rod jacks and caps to outdoors, dampers, in-line fans, roof fans, and control interlocks, etc. as required for proper operation of the complete system in accordance with the manufacturer's instructions.

Contractor shall be responsible for correct rough-in dimensions and shall verify them with Architect and/or equipment supplier prior to service installations.

P. SYSTEM TESTING, ADJUSTING, AND BALANCING

Upon completion of each phase of the installation, test each system in conformance with local code requirements and as noted below. Furnish labor and equipment required to test each system installed under this contract. Assume all costs involved in making the tests and repairing and/or replacing any damages resulting therefrom.

The final test and balance of the building HVAC systems shall be completed by National TAB (no exceptions) and contracted by the General Contractor. The representative from National TAB shall be certified by the National Environmental Balancing Bureau (NEBB), Associated Air Balance Council (AABC), or Testing, Adjusting and Balancing Bureau (TABB). TAB shall be performed in accordance with the most current edition of the certified agencies procedure standard for testing, adjusting and balancing and shall comply with the strictest interpretation of that standard for execution and reporting of all TAB work.

Work shall include but not be limited to: Perform test readings on fans, units, coils, pumps, etc. and adjust equipment to deliver specified amounts of air. Prepare testing and balancing report log showing air supply quantities, air entering and leaving temperatures and pressures at design flow, fan and unit test readings, motor voltage and amp draws, etc., and submit copies of the final compilation of data to the Architect for evaluation and approval before final balance air systems to within plus or minus 10 percent for terminal devices and branch lines and plus or minus 5 percent for main ducts and air handling equipment of the amount of air shown on the drawings. TAB Contractor shall record space temperatures and make adjustments in airflow each diffuser to obtain uniform temperature (no greater than +/- 3°F) in spaces. Document temperatures and adjustments in tab report. Adjust equipment to operate as intended by the specification. TAB report shall include a report summary/remarks' section in accordance with the procedural standard that provides both system set up and a summary of deficiencies as defined by the procedural standard.

TAB Contractor shall be responsible to calibrate, set, and adjust automatic temperature control sensors, actuators and control devices. Check proper sequencing, interlock systems, and operation of safety controls, adjust thermostats, and control stoppages, limits and time based adjustment to operate in accordance with the performance requirements of the Construction Documents. Adjust pumps, fans, etc. for proper and efficient operation. Certify to Architect that adjustments have been made and that system is operating satisfactorily. Calibrate, set, and adjust automatic temperature controls. Check proper sequencing of interlock systems, and operation of safety controls.

Division 23 contractor shall align bearings and replace bearings that have dirt or foreign material in them with new bearings without additional cost to the Owner.

Q. VIBRATION ISOLATION

Provide vibration isolation equipment and materials by a single manufacturer. If type and deflection for specific equipment is not specified within the contract documents, reference ASHRAE Handbook "HVAC Applications" or provide per manufacturer's recommendations. Approved manufacturers include Caldyn, Kinetics Noise Control, Mason Industries, Inc., Vibration Eliminator Co., Inc., Vibration Mounting and Controls, or Vibro-Acoustics, provided their systems are in compliance with the specified design and performance requirements.

General Requirements: Select vibration isolators by the weight distribution to produce uniform deflection. Vibration isolators shall have equal known un-deflected heights so that, after adjustment, the static deflection can be verified, thus ensuring that the load is within the proper range of the isolator. Isolators shall operate in the linear portion of their load versus deflection curve. Spring isolators shall have 50 percent excess capacity without becoming coil bound. Coil vibration isolators with factory-applied paint. Coat vibration isolators exposed to weather and other corrosive environments with factory-applied corrosion resistance protection. Install and adjust vibration isolators in accordance with manufacturers written instructions.

Pipe connections. Provide flexible connectors for piping system connections on equipment side of shutoff valves for all pumps, mechanical equipment supported or suspended by spring isolators, and where indicated on drawings. Flexible fabric piping connectors from stainless steel or rubber materials as suitable for the system fluid. Flexible piping connectors shall be bellows, spherical or braided hose type as recommended by the manufacturer for the application.

1. Types

- Type WP (Waffle Pads): Provide 5/16 inch thick neoprene pads ribbed or waffled on both sides. Manufacture pads with bridge bearing quality neoprene and seal to a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of 0.05 inches. Incorporate steel load spreading plates where required between the equipment and the neoprene pad to provide selected deflection. If the isolator is bolted to the structure, install a neoprene mounting sleeve under the bolt head between the steel washer and the base plate to prevent metal to metal contact. Provide Mason Industries Type V or equal.
- Type SPNH (Spring and Neoprene Hangers): Provide a steel hanger box containing a laterally stable, double-deflecting neoprene isolator in series with a steel spring. Design springs so the ratio of the horizontal to vertical spring constant is between one and two. The spring diameter shall be not less than 80 percent of the compressed height of the spring at rated load. Loaded springs shall operate within the linear portion of their load versus deflection curve over a deflection range of not less than 50 percent above design deflection. Spring diameter and hanger box hole size shall be large enough to permit the hanger rod to swing through a 30 degree arc. Include a neoprene bushing to prevent contact between the lower hanger rod and hanger box and short-circuiting the isolating function. The neoprene element shall have a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of not less than 0.4 inches. Unless otherwise specified, the static deflection of SPNH hangers shall be 2 inches. Provide SPNH hangers with 1 inch static deflection for water source heat pumps and fan-powered VAV terminal units. When installed, do not cock the spring element and do not allow the hanger box to rotate through a full 360 degree arc without encountering obstructions. Provide Mason Industries Type 30M or equal.
- Type NR (Neoprene Bushing): Provide neoprene, rubber-in-shear bushings for lightweight (less than 100 pounds), suspended equipment. Select bushing based on all thread rod and angle iron or Unistrut. Select for a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of 0.15 inches. Provide Mason Industries Type HMB or equal.

R. SEISMIC CONTROLS FOR MEFP SYSTEMS

Seismic Protection Criteria:
Risk/Occupancy Category: I, II or III/IV
Site Soil Category: Contractor's Seismic Engineer to Determine
Seismic Design Category: Contractor's Seismic Engineer to Determine
Component Importance Factor: Determined from ASCE 7, most recent version.

The Contractor shall be responsible for determining the requirements for seismic bracing of mechanical, electrical, and plumbing systems. Seismic protection criteria used to determine seismic bracing requirements of all mechanical, electrical, and plumbing systems shall be determined by the applicable code adopted in the project jurisdiction. Where not already determined within the contract documents, the Contractor shall be responsible for contracting a licensed professional engineer to establish building site class, seismic design category, seismic zone, or any other criteria necessary to determine the requirements for seismic bracing of mechanical, electrical, and/or plumbing systems.

Seismic bracing of fire protection systems shall be installed in strict accordance with the provisions of NFPA 13 (2010 or later edition).
The Contractor shall determine the type and location of seismic bracing required for the mechanical, electrical, and plumbing elements shown on the drawings based on the established seismic criteria, the size and weight of the supported element, and the distance from structure of the supported element.
The Contractor shall submit the following shop drawing information to the AHJ and the Engineer for review and approval:
1. Seismic analysis listing all applicable seismic design criteria.
2. Descriptive bracing materials.
3. Shop drawings showing bracing type and location.
4. Installation details of all bracing used.
Calculations showing bracing restraints meet the seismic requirements.
Shop drawings and calculations shall be signed and sealed by a registered professional engineer, licensed in the state of the project and employed by the manufacturer of the seismic bracing products. Calculations shall include dead loads, static seismic loads, and capacity of materials utilized for connections.

Seismic bracing, restraints, isolators, and isolation materials shall be of the same manufacturer and shall be certified by the manufacturer. Approved manufacturers are: Ambr/Booth Company, Inc., B-Line/Toledo, ISAT, Kinetics Noise Control, Inc., Loox & Company, Inc., Mason Industries, Inc., Unistrut, or Vibro-Acoustics. Each device shall have a pre-approval number from California OSHPD or other recognized government agency showing maximum restraint ratings.

Seismic bracing measures to be applied to mechanical, electrical, and plumbing equipment/systems shall be installed in strict accordance with all applicable local, state, and/or federal codes as well as manufacturer's requirements. The most stringent criteria shall apply. All structure for connections to be provided for support of mechanical and electrical equipment, regardless of the need for seismic restraints, shall be shown on shop drawings.

S. AIR FILTERS

Provide AAF/Filters Perfect Pleat HC M8, Camfil Fair 30/30, pleated, throwaway type filters, minimum MERV 8, or similar as manufactured by Air Filter, Inc., Bioclimatic, Cambiux, Koch, or approved equal, unless otherwise indicated.

Temporary filters used to protect openings in ductwork and inside equipment when permanent HVAC equipment is used during the construction period shall be pleated, throwaway type filters, minimum MERV 8.

T. REFRIGERANT AND OIL

Provide full refrigerant and oil charge in new air conditioning refrigeration systems, and maintain it for full term of the guarantee.

U. IDENTIFICATION

Provide manufacturer's standard pre-printed, semi-rigid snap-on or permanent adhesive, pressure-sensitive vinyl pipe markers. Color code pipe markers to comply with ANSI A13.1.

Install pipe markers on each HVAC piping system and include arrows to show normal direction of flow.

Locate pipe markers and color bands wherever piping is exposed to view in occupied spaces, machine rooms, accessible maintenance spaces (shafts, tunnels, plenums) and other non-concealed locations.

Provide plastic laminate or brass valve tag on every valve, coil and control device in each HVAC piping system; exclude check valves, plastic within factory-fabricated equipment units, and shut-off valves at HVAC terminal devices and similar rough-in connections of end-use fixtures and units.

Provide manufacturer's standard laminated plastic, color coded equipment markers. Conform to the following color code: Green for Cooling, Yellow for Heating, Yellow/Green for combination Cooling and Heating; Brown for Energy Reclamation; Blue for other equipment types. Conform to ANSI A13.1 for Hazardous Equipment.

Provide stenciled signs for equipment identification at Contractor's option or where distance of required identification requires lettering larger than 1 inch height. Stencil paint shall be exterior type, oil-based, alkyl enamel, minimum 1-1/4 inch height or greater as required for long distance identification, white or black color for best contrast.

Provide duct markers or provide stenciled signs and arrows indicating ductwork service and flow direction in black or white lettering for best contrast with duct or insulation color. Locate markers maximum 50 feet along each duct side and within 5 feet of all control and balancing dampers or branch ducts more than 25 feet length and within 5 feet on each side of wall, floor, and ceiling penetrations. Provide additional markers in congested areas or at multiple duct runs as required for clarity.

3. DUCT INSULATION, DUCTWORK, ACCESSORIES, FLUES AND FANS

A. DUCT INSULATION

Provide fiberglass duct liner with fibers firmly bonded together with a thermosetting resin. Liner surface shall serve as a barrier against infiltration of dust and dirt, shall meet ASTM C1336 for fungi resistance, and shall be cleanable using duct cleaning methods and equipment outlined by North American Insulation Manufacturers Association (NAIMA) duct cleaning guide. Install with liner adhesive and mechanical fasteners in accordance with manufacturer's instructions and recommendations. Ductwork signs shown on drawings are inside clear dimensions. Increase sheet metal by liner thickness in both directions where liner is installed.

Provide rectangular liner conforming to ASTM C1071, Type I or I with 1-1/2 inch thick, 1-1/2 pound density, minimum R-6.0 Certainteed Corp. "Toughguard" or equivalent, Johns Manville, Owens-Corning, or Knaflex.

Provide round liner that is 1-1/2 inch thick, 4 pound density, minimum R-6.0 Johns Manville "Spiroacoustic Plus" or equivalent, Certainteed or Owens-Corning.

Provide liner on the following interior air ducts and where specified on the drawings:

- Exposed round and rectangular supply ductwork.
- Exposed round and rectangular return ductwork.

At interface of lined and wrapped ductwork, overlap lined ductwork at least 2 feet beyond wrapped insulation.

Cover concealed, rigid ductwork with ASTM C553, Type I flexible fiberglass insulation. Installed insulation shall be 2 inch thick, 3/4 pound density, minimum R-6.0 duct wrap, Certainteed Corp. "Toughguard" or equivalent, Johns Manville, Owens-Corning, or Knaflex heavy-duty foil scrim-kraft facing, and with joints taped with 3 inch wide foil tape as follows:

- Round and rectangular supply and return air ductwork.
- Unlined Round and rectangular outside air ductwork.
- Round and rectangular exhaust and relief air ductwork within 10 feet of exterior discharge.

Cover Outdoor air, Exhaust air and Relief air Plenums connected to exterior louvers with 1-1/2 inch thick, 1.5 pound density, rigid fiberglass insulation conforming to ASTM C612, Class 2.

Insulating materials, adhesives, coatings, etc., shall not exceed flame spread rating of 25 and smoke developed rating of 50 per ASTM E84. Containers for mastics and adhesives shall have UN 1 Label.

For supply and return ductwork located exterior to the building, insulation shall be minimum R-8.0. Provide insulation and jacket in accordance with one of the following three options:

- Exterior insulation and jacket consisting of 2 inch thickness of Armaflex flexible elastomeric insulation or equivalent meeting ASTM C534 with integral 1/2 mils thick UL resistant cladding laminated at factory. Cover all seams with Armaflex seal tape.
- Exterior insulation consisting of 2 inch thickness of flexible elastomeric insulation meeting ASTM C534 or 3 lb density rigid fiberglass meeting ASTM C612, and jacket consisting of 20 gauge corrugated aluminum jacket with aluminum fitting covers and minimum three aluminum attachment bands per section.
- Exterior insulation consisting of 2 inch thickness of flexible elastomeric insulation meeting ASTM C534 or 3 lb density rigid fiberglass meeting ASTM C612, and jacket consisting of 15.5 mils thick Venturoleux Plus UV resistant cladding.

Install exterior ductwork with sufficient slope to ensure that water cannot pond anywhere on the duct. Drainage must be achieved by sloping ductwork - not by varying the insulation thickness. Locate longitudinal seams of outer shell (aluminum, flexible elastomeric, or cladding as applicable) at bottom of duct. Install cladding in strict conformance with cladding manufacturer's instructions.

B. DUCTWORK

Provide galvanized steel ductwork and housings as shown on drawings. Construct ductwork including fittings and transitions in conformance with current SMACNA standards relative to gauge, bracing, joints, etc. Minimum thickness ductwork shall be 26-gauge sheet metal. Reinforce housings and ductwork over 1-1/4 inch angles not less than 5'-0" on centers, and closer if required for sufficient rigidity to prevent vibration. Support horizontal runs of duct from strap iron hangers on centers not to exceed 6'-0". Do not support ceiling grid, conduits, pipes, equipment, etc., from ductwork. Coordinate routing of ductwork with other contractors such that piping, electrical conduit, and associated supports are not routed through the ductwork.

Provide pre-engineered roof duct supports supports by Cooper B-Line, Elite Components, ERICO, FNN, Mio, PHD Manufacturing, or equivalent, approved equal, or approved equal. Support ductwork on the roof with pre-engineered roof duct supports that rest on top of the roofing membrane, not requiring any attachment to the roof structure and not penetrating the roofing assembly, with embedded support fixtures as required to support the duct. Provide steel pedestal type supports with minimum 18 inch thermoplastic or rubber base or 4 inch wide aluminum base as manufactured by Certainteed, Thermal Ceramics, Unifrax or 3M. Slope duct back towards hood at minimum of 1/4 inch per linear foot. All Contractor's option, a UL listed concrete ductwork package that complies with UL 1978 standard for grease ducts may be used in lieu of the welded black iron rod for connecting hood to exhaust fan. Ductwork packages shall be as manufactured by Metal-Fab, Schebler, Sektek, or approved equal. Provide manufacturers UL listing number and verification certificate as a part of the shop drawing submittal. Install duct package in strict conformance with manufacturer's instructions and recommendations.

Coordinate with the pre-engineered roof duct support manufacturer to anchor the duct supports directly to the roof structure in accordance with the manufacturer's installation instructions or provide intermediate duct supports engineered to meet the wind resistance and seismic design criteria. Reference Section, "PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS."

Construct non-VAV supply ducts to meet SMACNA positive pressure of 2 inches w.g. Construct Return, Outdoor and Exhaust ductwork upstream of fans to meet SMACNA negative pressure of 1 inch w.g. Construct exhaust ductwork downstream of fans to meet SMACNA positive pressure of 1 inch w.g.

Provide mill phosphatized or galvanized finish for exposed ductwork to be field painted. Shop treated sheet metal shall have galvanized metal primer applied in the shop after fabrication and prior to shipping.

Seal ductwork with heavy liquid sealant. Harcourt Ironport 601N, Design Polymer DP 1010, United McGill duct sealer or approved equal, applied according to sealant manufacturer's instructions. Seal all longitudinal and transverse ductwork joints airtight to meet SMACNA Seal Class A. Tapes and mastics shall be listed and labeled in accordance with UL 181A.

Provide radius elbows, turns, and offsets with a minimum centerline radius of 1-1/2 times the duct width. Where space does not permit full radius elbows, provide short radius elbows with a minimum of two continuous spliced vanes. Vanes shall be the entire length of the bend. Provide mirrored elbows where space does not permit radius elbows, where shown on the drawings, or at the option of the contractor with the engineer's approval. Elbows shall have 45 degree bends and 90 degree elbows shall have 45 degree bends. Direct expansion coils and condensing coils with 1 inch factory installed flexible elastomeric insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating by the applicable code. Provide direct expansion coil heat exchanger, minimum AFUE rating (Heating) as required by the applicable energy code or greater if scheduled on the drawings, forced combustion air blower; complete factory installed micro-process control including anti-short cycle times, time delay relays and minimum "on" time controls, 100 percent safety gas shutoff, direct spark ignition system, built-in thermal overload protection on motors and compressors; outdoor air damper; relief, weatheright housing constructed of zinc coated, heavy gauge, galvanized steel with weather-resistant baked enamel finish; pre-engineered roof curb with minimum height as scheduled on the drawings if unit is equipped with internal vibration isolators, Type CM8 if unit is not equipped with internal vibration isolators; single point electrical power connection. Install guards or louvered panels to protect the condenser coil from hail or other damage and a 125 VAC, 20 amp duplex electronic receptacle mounted to unit ready for field wiring with a cover UL listed for wet and damp locations when in use. Install in-vacuum programmable type thermostat provided with unit. Install RTU package furnished by the owner.

Provide balancing dampers, manufactured by Cesco, Greenheck, Louvers & Dampers, Nalor Industries, Potluff, Ruskin, Tamco, or approved equal, where indicated on drawings. Provide manual control of air flow. Splitter dampers shall be controlled by locking quadrants; provide Young Regulator or Ventlok end bearings for the damper rod. Rectangular volume dampers shall be opposed blade interlocking type. Round volume dampers shall be single-blade type consisting of circular blade mounted to a shaft. Provide Flexmaster model 570 or equal 45 degree rectangular louvered fitting with model 603 damper with locking quadrant and insulation built out for round ductwork branch takeoffs in individual air devices. Omist damper of takeoff fitting when damper is located downstream of takeoff.

Where access to dampers through a hard ceiling is required, provide a concealed, remote cable-operated, butterfly-type volume damper assembly with external worm gear operator. Damper assembly shall include duct casing with rolled beam stiffeners, reinforced blade, self-lubricating bearing, and remote operator mounting plate. External operator shall attach to damper as a single piece with no linkage adjustment required. Damper shall be adjustable through the diffuser frame with standard 1/4 inch nutdriver or flat screwdriver. Provide positive, direct, two-way damper control with no sleeves, springs or screw adjustments to come loose after installation. Provide cable length to span the distance from the damper to the remote operator in branch duct. Do not install in diffuser neck. Install remote operator on the back of the diffuser frame or side of a slot diffuser plenum. Support cable assembly to avoid bends and kinks in cable at manufacturer recommended intervals. Where approved by architect, a ceiling cup with cover plate may be used for access to cable operator. Provide round dampers by Metropolitan Air Technology model RT-50, Young's Regulator model 5020-1200, or approved equal. Provide rectangular dampers by Metropolitan Air Technology model RT-WGA, Young's Regulator model 820-975, or approved equal.

Round or oval ductwork shall be FlakTGroup Simco, United, Hercules Industries or equal, sheetmetal, with smooth interior surface, with low pressure (duct pressure class up to and including 2 inches w.g.) Round ductwork gauges per the following table (reference SMACNA HVAC duct construction standards for gauges, where pressures exceed 2 inches w.g.)

Size	Duct Gauge	Fitting Gauge
14" x under	26	24
15" thru 26"	24	22
28" thru 36"	22	20
38" thru 50"	20	20
52" thru 60"	18	18

Low pressure (duct pressure class up to and including 2 inches w.g.) and medium pressure (duct pressure class 2 1/4 inch to 6 inches w.g.) flexible duct shall be Flexmaster type BB, Thermaflex type G-KM, M-KE, JPL, type SBR, Jacket, or equal (if replacement polyethylene) protective vapor barrier, UL-181 Class 1, acoustical insulated duct, R-6.0 fiberglass insulation. Provide CRE liner with steel wire helix mechanically locked or permanently bonded to the liner.

Flexible duct runs shall not exceed 5 feet in length, and shall be installed fully extended and straight as possible avoiding tight turns. Install flexible duct in accordance with manufacturer's instructions. Support flexible duct at maximum 5 feet on center and within 6 inches of bends. Bends shall not exceed a centerline radius of one duct diameter. Duct sag shall not exceed 1/2 inch. Supporting material in direct contact with the duct shall not be less than 1-1/2 inches in width.

C. FLEXIBLE DUCT

Low pressure (duct pressure class up to and including 2 inches w.g.) and medium pressure (duct pressure class 2 1/4 inch to 6 inches w.g.) flexible duct shall be Flexmaster type BB, Thermaflex type G-KM, M-KE, JPL, type SBR, Jacket, or equal (if replacement polyethylene) protective vapor barrier, UL-181 Class 1, acoustical insulated duct, R-6.0 fiberglass insulation. Provide CRE liner with steel wire helix mechanically locked or permanently bonded to the liner.

Flexible duct runs shall not exceed 5 feet in length, and shall be installed fully extended and straight as possible avoiding tight turns. Install flexible duct in accordance with manufacturer's instructions. Support flexible duct at maximum 5 feet on center and within 6 inches of bends. Bends shall not exceed a centerline radius of one duct diameter. Duct sag shall not exceed 1/2 inch. Supporting material in direct contact with the duct shall not be less than 1-1/2 inches in width.

Connect flexible duct to rigid metal duct or air devices as recommended by the manufacturer. At a minimum, install two wraps of duct tape around the inner core connection and a metallic or non-metallic duct tape around the tape and two wraps of duct tape or a clamp over the outer jacket. Duct clamps shall be labeled in accordance with UL-181B and labeled 181B-C. Duct wraps shall be labeled in accordance with UL 181B and labeled 181B-FX.

D. PLASTIC FLUE GAS VENTS

UL listed 1738 listed plastic flue gas vents, with positive or negative fire pressures complying with NFPA 211 and suitable for condensing gas appliances. Provide PVC system by IPEX "System 1738" or Polypropylene system by Centrium "Innofloor" or equal by Nova Flex Group "Z-DENTS".

Vents and combustion air ducts for condensing type appliances shall be Schedule 40 PVC pipe and socket fittings meeting ASTM D2665 and UL 1738, manufactured by IPEX. Use solvent cement meeting ASTM D2654 and make joints in accordance with ASTM D2655.

Where plastic gas vents are installed in a return air plenum, wrap the vent with fire rated plenum insulation. Reference Article "Plenum Insulation" for plenum-rated fire wrap. Coordinate vent material compatibility with the appliance manufacturer's installation instructions prior to purchasing and installation.

E. AIR DEVICES

Provide air devices as scheduled on drawings, manufactured by Carnes, Krueger, Metaltare, Nalor Industries, Price, Titus, or Tuttle & Bailey. Select air devices to limit room noise level to no higher than NC-30 unless otherwise shown. Provide devices with a soft plastic gasket to make an airtight seal against the mounting surface. Coordinate final location, frame, and mounting type of air devices with Architectural reflected ceiling plans.

Submit complete shop drawings including information on noise level, pressure drop, throw, CFM for each air device, styles, borders, etc. Clearly marked with specified equipment number. Submit samples of each air device as requested by the Engineer.

Provide wall return air registers and exhaust air registers with horizontal 35 or 45 degree angle vane-proof bars. Provide concealed equipment registers with wall mounted registers and grilles with heavy duty type with 0 degree deflection.

Provide ceiling mounted air devices of lay-in or surface mounted type as required to be compatible with ceiling construction. Provide ceiling diffusers and grilles with white enamel finish unless noted otherwise.

Provide linear slot diffusers of standard one-piece lengths up to 6-feet and furnish in multiple sections greater than 6-feet. Join multiple sections together end-to-end with alignment pins to form a continuous slot appearance. For installations in a hard ceiling, install diffuser per manufacturer's installation instructions prior to installation of drywall. Contractor shall use manufacturer's hand ceiling clips for mounting to ceiling framing. Screws through face of linear slot diffuser are not acceptable. Provide alignment components by the manufacturer. Provide plenums by the slot diffuser manufacturer. Plenums shall be internally insulated by the manufacturer with minimum 1/4 inch thick, fiberglass insulation.

F. CONTROL DAMPERS

Provide factory fabricated, parallel blade control dampers sized as shown on the drawings and as specified. Individual damper sections shall not be larger than 48 inches x 60 inches with maximum blade width of 6 inches. Frame construction shall be minimum 16 gauge galvanized steel for rectangular dampers, 20 gauge for round, 1/8 inch thick aluminum, with flanges for duct mounting. Provide elastomeric or neoprene seals, mechanically attached and field replaceable. Provide a minimum of one damper actuator per section. Test damper performance in accordance with AMCA 500-D.

Provide modulating dampers with linear flow characteristics. Size modulating dampers based on the smaller of 1,500 FPM through the damper or full open air pressure drop of 0.1 inches W.C. Size two-position dampers full load size and select to minimize pressure drop.

Motorized dampers used for ventilation air intake, exhaust air, or relief air shall have leakage rates not to exceed 4 CFM/square foot in full closed position at 1 inch W.G. pressure differential across the damper.

Provide dampers as manufactured by Greenheck, Cesco, Potluff, Nalor, or Ruskin. Reference manufacturer with model number for outside air dampers is Ruskin CD-50 constructed of aluminum, and all other applications is Ruskin CD-35 constructed of galvanized steel.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee tight closure of dampers against system pressure encountered. Each operator shall be provided with spring-return for normally closed or normally open position or account for low temperatures, or power interruption as required by the control systems specified on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

G. EXHAUST AIR SYSTEMS

Provide roof mounted exhaust fans as scheduled on the drawings, or equal ACFM, Carnes, Cook, Greenheck, Pennbarr, or Twin City Fans complete with aluminum housing, aluminum centrifugal wheel, motor with integral thermal overload protection, disconnect switch mounted inside the housing, bistatene, backdraft damper, and pale prefabricated roof curb. Three phase fans shall be furnished with magnetic starters with push button station.

H. KITCHEN EXHAUST AIR SYSTEMS

Install kitchen grease exhaust package furnished by the owner. System includes kitchen hood, grease exhaust fan/pollution control unit, filtered makeup air unit and a mechanical or electrical gas shutoff valve provided with the kitchen exhaust system to shutoff fuel or power source to cooking equipment upon detection of fire. Valve shall have a clearly marked open/closed indicator.

Provide ducts connecting Type 1 exhaust hoods to exhaust fans made of #16 gauge black iron with continuously welded joints and fire-rated doors. Provide at least one opening that is minimum size of 20 inches by 20 inches for personnel entry. Where an opening of this size is not possible, provide access openings at each change in direction and at 10 foot intervals. Locate openings on sides of duct 1-1/2 inches minimum from bottom and fit with grease-tight covers of same material as duct. Cleanouts shall be provided with tight fitting doors constructed of steel having the same thickness as the ductwork. All door assemblies including any frames and gaskets shall be approved for the application and shall not have fasteners that penetrate the duct. The gasket material shall be listed for continuous duty and rated for not less than 1,500°F. Support systems for ducts 24 inch and larger in any dimension shall be designed for the weight of the duct plus 800 pounds at any point in the system. Provide transition connection to fan with opening size equal to or greater than the venturi opening of the fan inlet. Provide gasket at flanged connection to fan rated for 1500 degrees Fahrenheit and grease applications. Enclose duct in reroof enclosure per locally adopted mechanical code or, if approved by local code official, in fire rated wrap insulation. Insulation shall be minimum two-hour rated duct wrap insulation for Type 1 hood and grease exhaust duct applications shall conform to ASTM E2336 where required to comply with IMC. Insulation shall be flexible wrap enclosure rated for minimum 2000 degrees Fahrenheit and for zero clearance to combustibles. Insulation shall be non-mineral wool, passive, low bio-persistent fiber totally encapsulated on all sides with aluminum foil. Insulation shall be as manufactured by Certainteed, Thermal Ceramics, Unifrax or 3M. Slope duct back towards hood at minimum of 1/4 inch per linear foot. All Contractor's option, a UL listed concrete ductwork package that complies with UL 1978 standard for grease ducts may be used in lieu of the welded black iron rod for connecting hood to exhaust fan. Ductwork packages shall be as manufactured by Metal-Fab, Schebler, Sektek, or approved equal. Provide manufacturers UL listing number and verification certificate as a part of the shop drawing submittal. Install duct package in strict conformance with manufacturer's instructions and recommendations.

All portions of grease duct systems shall be tested for leakage in accordance with the "Grease Duct Test" paragraph of the IMC. Leakage tests shall be by water leakage type or equivalent test methods as approved by the local code official to determine that all joints are liquid tight. Water leakage test shall be performed by Environmental Corporation of America or owner approved testing contractor. Tests shall be performed in the presence of the local code official. Any joints found defective shall be repaired and retested until satisfactory results are obtained. The contractor shall submit a copy of the grease duct leakage test report to the architect/engineer complete with the approval signature of the local code official.

4. HVAC EQUIPMENT

A. ROOFTOP UNITS (GAS FIRED HEAT) 3-25 TONS

Install electric cooling, gas heating rooftop units provided by owner as scheduled on the drawings, manufactured by Captive Aire, with features as noted in the RTU schedule and in the RTU Control Matrix, and complete with factory installed direct-drive hermetic compressors with internal built-in vibration and sound reduction, crankcase heaters, minimum SEER and EER ratings by the applicable code, pressure switches, direct expansion coils and condensing coils with 1 inch factory installed flexible elastomeric insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating by the applicable code. Provide direct expansion coil heat exchanger, minimum AFUE rating (Heating) as required by the applicable energy code or greater if scheduled on the drawings, forced combustion air blower; complete factory installed micro-process control including anti-short cycle times, time delay relays and minimum "on" time controls, 100 percent safety gas shutoff, direct spark ignition system, built-in thermal overload protection on motors and compressors; outdoor air damper; relief, weatheright housing constructed of zinc coated, heavy gauge, galvanized steel with weather-resistant baked enamel finish; pre-engineered roof curb with minimum height as scheduled on the drawings if unit is equipped with internal vibration isolators, Type CM8 if unit is not equipped with internal vibration isolators; single point electrical power connection. Install guards or louvered panels to protect the condenser coil from hail or other damage and a 125 VAC, 20 amp duplex electronic receptacle mounted to unit ready for field wiring with a cover UL listed for wet and damp locations when in use. Install in-vacuum programmable type thermostat provided with unit. Install RTU package furnished by the owner.

B. ELECTRIC UNIT HEATERS

Provide electric unit heaters as scheduled on the drawings, manufactured by Berko, Brasch, Indecon, Markel, QMark, or Raywell, standard type propeller unit heaters with sidewall mounting brackets and hardware for horizontal airflow. Furnish heater fan motors complete with a manual motor start with automatic thermal cutoff sized to the motor load, disconnect switch, and other code required safety devices. Provide unit mounted thermostat and manual summer/winter changeover switch.

C. SPLIT DUCTLESS AIR-CONDITIONING SYSTEMS

Provide split ductless system consisting of evaporator section for wall or ceiling mounting as indicated and remote condensing section similar to Carrier, Comfort Star, Dakin, Friedrich, Fujitsu, Lennox, LG, Mitsubishi, Samsung, Sanyo, Trans, or York. Evaporator cabinet shall be factory assembled pre-wired consisting of furniture-grade steel with baked-enamel finish, front access, with direct-drive fans with direct drive fan drives. Motors shall be direct-expansion cooling coil of seamless copper tubes expanded into aluminum fins, with thermal-expansion valve with external equalizer. Air-cooled condenser shall be of corrosion-resistant cabinet comprising compressor, copper-tube aluminum-fin coils, direct-drive propeller fans with motors with internal overload protection; capacity control to 2 degrees Fahrenheit.

Provide concrete bases for units located on grade. Provide pre-engineered roof equipment support rails for units located on roof. Securely attach units to rails.

Provide refrigerant piping sized as recommended by equipment manufacturer with foamed plastic insulation on the suction line as specified in this section.

Control System: Unit-mounted panel with controls, control transformer with circuit breaker, solid-state temperature- and humidity-control modules. Provide isolate/heat control panel with start-stop switch, adjustable humidity set point, and adjustable temperature set point. Relay for sequence of operation.

7. SEQUENCE OF OPERATION

A. FAN COIL UNIT CONTROL

During occupied hours, operate fan coil unit supply fan continuously and open outdoor air damper to maintain minimum ventilation. Cycle stage(s) of DX cooling and electric heating to maintain room thermostat set point (75 degrees Fahrenheit cooling, 70 degrees Fahrenheit heating). Duct mounted smoke detectors shall shutdown unit upon alarm.

During unoccupied hours, cycle the fan coil unit supply fan and cooling or heating system to maintain unoccupied setback temperature set points. Outdoor air damper shall be closed during unoccupied hours.

Connect the Outdoor air damper to the same time clock as the restroom exhaust.

B. KITCHEN EXHAUST FAN CONTROL

Kitchen exhaust fan shall be energized through on-off switches at the associated exhaust hoods or cooking equipment or through a master kitchen ventilation control panel as indicated on the drawings. Kitchen fans shall be interlocked to operate with cooking appliances, make-up air and other air-handling equipment providing fresh air to the kitchen area as noted or scheduled on the drawings.

C. MAKE-UP AIR UNIT CONTROL

Make-up air unit supply air fan shall be energized and the outside air damper shall open 100% when exhaust fans are energized. Exhaust fans and make-up air units shall modulate thru the hood control panel. Refer to installation, operation, and maintenance manual.

D. ROOFTOP UNIT CONTROL

Refer to RTU CONTROL MATRIX on Sheet M601 for required rooftop unit control options.

E. RESTROOM EXHAUST FAN (EF-1) CONTROL

Operate exhaust fans continuously during occupied hours and shut down during unoccupied hours. Provide a 7-day timeclock to switch each system between occupied and unoccupied operation.

F. AIR CURTAIN CONTROL

Interlock air curtain with door limit switch to energize when the door opens. Units scheduled with heating coils shall cycle the stages of heat to maintain room temperature setpoint of 70 F (adj).

G. ELECTRIC UNIT HEATER CONTROL

Unit heater shall be activated by unit mounted thermostat to maintain room temperature setpoint (60 deg F).

8. ALTERNATES

A. DESCRIPTION

Refer to the architectural portion of the specification for list of alternates. Applicable sections of the base specifications shall apply to all work required by the alternate unless otherwise specified. Determine whether or not and how each alternate affects work. Include labor, materials, equipment, and transportation services necessary for and incidental to the completion of work under each particular alternate. Furnish separate bid for each alternate applicable to work, stating the amount to be added or deducted from the base bid.

9. COMMISSIONING OF MECHANICAL SYSTEMS

Commissioning of HVAC System

A. PART 1 GENERAL

1.1 SUMMARY

- a. Section includes Cx process requirements for the following HVAC systems, assemblies, and equipment:
1. Air handling units (Supply fans, return fan, packaged units, roof top units, specialized fans)
2. Exhaust fans
3. Fan coil units and terminal units
4. Condensing units
5. Make-Up air units
6. Ductwork and piping
b. Related Requirements:
1. Section 019113 "General Commissioning Requirements" for general Cx process requirement and CxA responsibilities.

1.2 INFORMATIONAL SUBMITTALS

- a. Construction Checklists: Draft construction checklists will be created by CxA for Contractor review.
b. Construction Checklists: Installation and Performance test checklists for systems, assemblies, subsystems, equipment, and components to be part of the Cx process and according to requirement in Section 019113 "General Commissioning Requirement."
1. Refrigerant piping, including the following:
a. Refrigerant piping, fittings, and specialties.
b. Refrigerant charge.
c. General duty and specialty valves.
d. Meters and gauges.
2. Air distribution systems, including the following:
a. Supply, return, and exhaust systems.
b. Metal ducts, liners, and fittings.
c. Nonmetal ducts and fittings.
d. Air-duct accessories, including volume dampers, fire and smoke dampers, turning vanes, sound attenuators, and flexible connectors.
e. Duct-mounted access doors and panels.
3. Kitchen exhaust system, including the following:
a. Exhaust and makeup air system.
b. Metal ducts, liners, and fittings.
d. Air-duct accessories, including volume dampers, fire and smoke dampers, turning vanes, sound attenuators, and flexible connectors.
e. Duct-mounted access doors and panels.
f. Exhaust fans.
g. Make-Up air unit

- 4. Air-handling equipment, including the following:
a. Fans and motors.
b. Indoor air-handling units with and without coils, dampers, and filters.
c. Outdoor air-handling units with and without coils, dampers, and filters.

B. PART 3 EXECUTION

3.1 CONSTRUCTION CHECKLISTS

- a. Complete detailed construction checklists (prefunctional checklists) prepared by the CxA for HVAC systems, assemblies, subsystems, equipment, and components.
1. Air and hydronic distribution systems, including the following:
a. Supply, return, outdoor-air, and exhaust-air distribution systems.
b. Automatic dampers.
c. Control valves.
2. Heating and cooling terminal and unitary equipment, including the following:
a. Unit heaters.
b. Fan coil units.
c. Electric heating.
3. TAB verification.

3.2 CONSTRUCTION CHECKLIST REVIEW

- a. Review and provide written comments on draft construction checklists. CxA will create required draft construction checklists and provide item to Contractor.
b. Return draft construction checklist review comments within 5 days of receipt.
c. When review comments have been resolved, the CxA will provide final construction checklists marked "Approved for Use, (date)."
d. Use only construction checklists marked "Approved for Use, (date)."

3.3 Cx TESTING PREPARATION

- a. Certify that HVAC systems, subsystems, and equipment have been installed, calibrated, and started and that they are operating according to the Contract Documents and approved submittals.
b. Set systems, subsystems, and equipment into operating mode to be tested according to approved test procedures (for example, normal shutdown, normal auto position, normal manual position, unoccupied cycle, and alarm conditions).

3.4 Cx TESTS COMMON TO HVAC SYSTEMS

- a. Comply with construction checklist requirements, including installation checks, startup, and performance tests requirements for HVAC systems and equipment.
b. Measure capacities and effectiveness of systems, assemblies, subsystems, equipment and components, including operational and control functions, to verify compliance with acceptance criteria.
c. Coordinate schedule with, and perform Cx activities at the direction of CxA.
d. Provide technicians, instrumentation, tools, and equipment to perform and document the following:
1. Construction checklist verification tests.
2. Construction checklist verification tests demonstrations
3. Cx test demonstrations.

3.5 START-UP DOCUMENTATION COMMON TO ALL SYSTEMS

- a. The following Start-Up Documentation (Checklists and Tests) shall be considered common to all systems:
1. Checkout shall proceed from lower level devices to larger components to the entire system operation.
2. Verify labeling is affixed per specification and visible.
3. Verify prerequisite procedures are done.
4. Inspect for damage and ensure none is present.
5. Verify system is installed per the manufacturer's recommendations.
6. Verify system has undergone Start-Up per the manufacturer's recommendations.
7. Verify that access is provided for inspection, operation and repair.
8. Verify that access is provided for eventual replacement of the equipment.
9. Verify that record drawings, submittal data and O&M documentation accurately reflect the installed systems.
10. Verify all gauges and test ports are provided as required by contract documents and manufacturer's recommendations.
11. Verify all recorded nameplate data is accurate.
12. Verify that the installation ensures safe operation and maintenance.
13. Verify all rotating and moving parts are properly lubricated.
14. Verify specified replacement material/stock has been provided as required by the Contract Documents.
15. Verify all monitoring and ensure all alarms are active and set per requirements.

3.6 MECHANICAL IDENTIFICATION

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following checks:
1. Verify all valve tags, piping, duct, and equipment labeling corresponds with drawings and indexes and meets requirements specified. Correct any deficiencies for all piping and duct system.
2. Adjusting: Relocate any mechanical identification device which has become visually blocked by work of this division or other divisions.
3. Cleaning: Clean face of identification devices, and glass frames of valve charts.

3.7 MECHANICAL INSULATION

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Examine all piping, systems and equipment specified to be insulated.
1. Ensure quality of insulation. Patch and repair all insulation damaged after installation.
2. Ensure the integrity of vapor barrier around all cold surfaces.

3.8 PIPING GENERAL

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: These procedures apply to all installed piping systems, including underground site utilities.
1. Inspect all piping for proper installation, adequate support (with appropriate vibration isolation where applicable) and adequate isolation valves for required services.
2. Provide notifications of pipe cleaning and flushing activities.
3. Flush and clean all piping and clean all strainers. Provide documentation of all related procedures.
4. Ensure adequate drainage is provided at low points and venting is provided at high points.
5. Ensure facilities to effectively drain and fill the system are in place.
6. Ensure air is thoroughly removed from the system as applicable.
7. Provide notification of pressure testing.
8. Pressure and/or leak test all applicable systems in accordance with the requirements in the applicable Division 23 specification.
9. Sterilize applicable piping systems as specified in the individual sections and as required by regulatory authorities.
10. Submit pressure test reports that document the pressure testing results with certification of the results. Include drawings/diagrams indicating sections of pipe that are tested with the corresponding report.
11. Set and adjust fill, pressure, or level controls to the required setting.

3.9 AC MOTORS

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following checks during start-up and as specified in manufacturer's instructions:
1. Verify proper alignment, installation, and rotation.
2. Verify properly sized overloads are in place.
c. Start-Up Tests: Perform the following tests, measurements, or procedures during start-up and as specified in the manufacturer's instruction:
1. Measure voltage available to all phases. Measure amps and RPM after motor has been placed in operation and is under load.
2. Record all motor nameplate data.

3.10 PACKAGED HEATING AND COOLING UNITS

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Refer to AC Motors in this section.
c. General: Provide the services of a factory-authorized service representative to test and inspect unit installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
b. Start-Up Checks: Perform the following inspections/checks during start-up:
1. Test controls and demonstrate compliance with requirements. Replace damaged or malfunctioning controls and equipment.
2. Install new filter units after start-up.

3.11 TERMINAL UNITS

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following inspections/checks during start-up:
1. After construction is completed, including painting if applicable, clean unit exposed surfaces.
2. Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
3. Verify adequate access for maintenance.
4. Check power and control voltages.
5. Check rotation of fan where applicable.
6. Check operation of water leak sensors.
7. Check calibration and operation of the controlling elements.
8. Check control valves for required close-off and fail position.
9. Install new filter units for terminals requiring same.

3.12 FANS

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. General: Provide the services of a factory-authorized service representative to test and inspect exhaust fan installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
c. Start-Up Checks: Perform the following inspections/checks during start-up:
1. Inspect the field assembly of components and installation of the units, piping, ductwork, and electrical connections.
2. Clean unit cabinet interiors to remove foreign material and construction dirt and dust. Vacuum clean fan wheel, fan cabinet, coils entering air face. Ensure volatile irritants are contained and kept out of occupied spaces.
3. Adjust and lubricate dampers and linkages for proper damper operation.
4. Verify the unit is secure on mountings and supporting devices and connections for ductwork, and electrical are complete. Verify proper thermal overload protection is installed in motors, starters, and disconnects.
5. Ensure vibration isolation integrity is maintained with the fan installation and associated connections.
6. Lubricate bearings, pulleys, belts, and other moving parts with factory-recommended lubricants.
7. Stroke all dampers to ensure free and full travel.

3.13 DUCTWORK ACCESSORIES

- a. Include all applicable "Start-Up Checks Common to All Systems".
b. Start-Up Checks: Perform the following checks during start-up and as specified:
1. Cleaning: Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
c. Start-Up Tests: In addition to specifications, perform the following as a minimum:
1. Operate installed ductwork accessories to demonstrate compliance with requirements. Test for air leakage while system is operating. Repair or replace faulty accessories, as required to obtain proper operation and leak proof performance.
2. Label access doors in accordance with Division 21 Section "Mechanical Identification"
3. Adjusting: Adjust ductwork accessories for proper settings, install fusible links in fire dampers and adjust for proper action.

END OF SECTION 23

Bergmeyer logo and address: 800 South Figueroa St., Los Angeles, CA 90017. Also includes Boston office address: 51 Shepley St., Boston, MA 02210.

HENDERSON ENGINEERS logo and address: 8345 LENEXA DRIVE, SUITE 300, LENEXA, KS 66214. Website: WWW.HENDERSONENGINEERS.COM

SEAU SIGNATURE: COY M. MACY, LICENSED PROFESSIONAL ENGINEER, EXP. 08/21/2023. Includes a circular professional seal for Coy M. Macy, No. 082,068,038, State of Illinois.

Table with 3 columns: I, HEI, and Description. Rows include IFC SET, ADDENDUM C, ADDENDUM B, ADDENDUM A, and PERMIT/BIID SET.

Table with 3 columns: NO., BY, DATE, DESCRIPTION. Rows include HEI 2023-08-21 IFC SET, HEI 2023-06-09 ADDENDUM C, HEI 2023-04-26 ADDENDUM B, HEI 2023-02-08 ADDENDUM A, HEI 2023-01-09 PERMIT/BIID SET.



SHAKE SHACK BLOOMINGDALE IL
355 ARMY TRAIL ROAD, BLOOMINGDALE, IL 60108
SHACK #1474
IFC SET

MECHANICAL SPECIFICATIONS

DRAWN BY: Author
CHECKED BY: Checker
JOB NO: 20188.00

M592

ROOFTOP UNIT CONTROL MATRIX						
CONTROL FEATURE	UNITS	RTU-1 DINING SETPOINT OR Y/N	RTU-2 KITCHEN SETPOINT OR Y/N	NOTES		
SETPOINTS						
COOLING - OCCUPIED SETPOINT	'F	75	75			
COOLING - UNOCCUPIED SETPOINT	'F	80	80			
HEATING - OCCUPIED SETPOINT	'F	70	70			
HEATING - UNOCCUPIED SETPOINT	'F	60	60			
DEHUMIDIFICATION SETPOINT - HUMIDITY SENSOR FEEDBACK	% RH	50%	NA		B	
PROGRAMMED CONTROL FEATURES						
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT		Y	Y	B		
REMOTE TEMPERATURE AND HUMIDITY SENSOR		Y	Y	B		
EQUIPMENT ACCESSORIES AND CONTROL MODULES						
OUTSIDE AIR DAMPER - MOTOR OPERATED (MODULATING)		Y	Y	L		
INTEGRATED ECONOMIZER - DIFFERENTIAL ENTHALPY ENABLE (EA (ENTHALPY < RA (ENTHALPY))	BTULB	Y	Y	E		
RELIEF - BAROMETRIC DAMPER		Y	N			
RELIEF - CONSTANT VOLUME POWERED EXHAUST FAN		N	Y	H		
COOLING COIL (DX - STAGED)		Y	Y	M		
DEHUMIDIFICATION - HOT GAS REHEAT		Y	N	O		
HEATING COIL (NATURAL GAS)		Y	Y	M		
SUPPLY FAN CONTROL METHODS						
ON DURING OCCUPIED HOURS		Y	Y			
CYCLE WITH LOADS DURING UNOCCUPIED HOURS		Y	Y			
VARIABLE VOLUME - STAGED FAN CONTROL IN RESPONSE TO ACTIVE COOLING COIL STAGES		Y	Y	M, Q		
SAFETIES, INTERLOCKS, AND ALARMS						
GAS VALVE SAFETY		Y	Y	F		
RETURN AIR SMOKE DETECTOR - SAFETY SHUTDOWN		Y	Y	U		
FIRE ALARM CONTROL PANEL - SAFETY SHUTDOWN INTERLOCK		Y	Y			
KITCHEN EXHAUST SYSTEM INTERLOCK		Y	Y	S		

DIV. 23 CONTRACTOR SHALL PROVIDE CONTROL PANEL(S), WIRING, THERMOSTAT(S), TEMPERATURE SENSOR(S), HUMIDISTAT(S), AND/OR CO2 SENSOR(S) WHERE SHOWN ON THE DRAWINGS AND AS REQUIRED TO FACILITATE THE SCHEDULED CONTROL MODULES AND SEQUENCES OF OPERATION. EACH UNIT SHALL CONTROL BASED ON ITS OWN INTERNAL SAFETIES, TIME DELAYS, AND SEQUENCES UNLESS NOTED OTHERWISE. COORDINATE WITH OWNER FINAL BUILDING AND EQUIPMENT SCHEDULES DURING STARTUP. REFERENCE DIVISION SPECIFICATIONS FOR INDIVIDUAL DEVICE REQUIREMENTS.

NOTES:
 B. DIVISION 23 CONTRACTOR SHALL PROVIDE DEVICE.
 E. IF SETPOINT VALUE IS LISTED, IT INDICATES ECONOMIZER HIGH-LIMIT SHUT-OFF. UNIT SHALL BE IN ECONOMIZER IF CONDITIONS ARE LESS THAN SETPOINT. THE FOLLOWING SENSORS SHALL DETERMINE ECONOMIZER ON/OFF POINT:
 OUTSIDE AIR TEMPERATURE; DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
 RETURN AIR TEMPERATURE; DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
 OUTSIDE AIR HUMIDITY; DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
 RETURN AIR HUMIDITY; DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
 F. DEVICE SHALL BE FACTORY MOUNTED AND PRE-WIRED FOR OPERATION SUBJECT TO THE ONBOARD CONTROLLER.
 H. POWERED EXHAUST FAN SHALL STAGE ON AND OFF ACCORDING TO DAMPER POSITION.
 L. EQUIPMENT MANUFACTURER SHALL PROVIDE MODULATING DAMPER AND CONTROLS CAPABLE OF ADJUSTING THE DAMPER POSITION TO MAINTAIN THE SCHEDULED OUTSIDE AIR ON THE DRAWINGS ACROSS ALL FAN SPEEDS. DIV. 23 CONTRACTOR SHALL PROGRAM MULTIPLE DAMPER POSITION SETPOINTS IN THE FIELD DURING TESTING AND BALANCING TO MAINTAIN MINIMUM VENTILATION WHEN NOT IN ECONOMIZER. DAMPER SHALL BE CLOSED DURING UNOCCUPIED HOURS.
 M. UNITARY CONTROLLER SHALL MODULATE AND/OR CYCLE SUPPLY FAN SPEED SETTING AND COIL CAPACITY STAGES SUBJECT TO THE INTERNAL SAFETIES AND SEQUENCES TO MAINTAIN SCHEDULED SETPOINTS.
 Q. PROGRAM DEHUMIDIFICATION SEQUENCE BASED ON ZONE AIR HUMIDITY.
 O. PROVIDE STAGED FAN CONTROL WITH MINIMUM 2 FAN SPEEDS. LOW SPEED SHALL NOT EXCEED 60% OF FULL SPEED AND SHALL DRAW NO MORE THAN 40% OF FAN POWER AT FULL SPEED.
 S. INTERLOCK RTU WITH KITCHEN EXHAUST HOOD SYSTEM(S) TO SHUT DOWN UPON SIGNAL FROM HOOD FIRE EXTINGUISHING SYSTEM. INTERLOCK RTU WITH KITCHEN EXHAUST FAN TO ENERGIZE WHEN HOOD SYSTEM IS ENERGIZED FOR PRESSURIZATION.
 U. DIVISION 28 CONTRACTOR SHALL PROVIDE DEVICE.

GRILLE, REGISTER, AND DIFFUSER SCHEDULE									
MARK	MANUFACTURER	SERVICE	MODEL	CONSTRUCTION MATERIAL	FACE TYPE	MOUNTING LOCATION	FACE SIZE (IN)	MAX. NC	NOTES
CEG	E.H. PRICE	EXHAUST GRILLE W/ DAMPER	80D	STEEL	EGGGRATE	SURFACE	12x12	30	A B C F G H
CRG	E.H. PRICE	RETURN GRILLE	80	STEEL	EGGGRATE	LAY-IN	24x24	30	A B C F H
CS1D	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	SURFACE	12x12	30	A B C F H J K L
CS2D	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	LAY-IN	24x24	30	A B C F H K
CS3D	E.H. PRICE	SUPPLY DIFFUSER	PDOR	STEEL	PERFORATED	LAY-IN	24x24	30	A B C F H
WRG	E.H. PRICE	RETURN GRILLE W/ DAMPER	530D	STEEL	LOUVERED FACE	WALL OR DUCT	30	A B C D F H	
WSR	E.H. PRICE	SUPPLY REGISTER W/ DAMPER	520D	STEEL	LOUVERED FACE	WALL OR DUCT (SEE PLANS)	30	A B C D E F G H	

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
 A. EQUIPMENT FURNISHED AND INSTALLED PER THE EQUIPMENT RESPONSIBILITY SCHEDULE.
 B. NECK SIZE SHOWN ON DRAWINGS. PROVIDE BRANCH DUCT TO MATCH NECK SIZE UNLESS OTHERWISE SHOWN ON DRAWINGS.
 C. DIFFUSERS SHALL BE PREFINISHED TO MATCH CEILING/WALL/EXPOSED DUCT COLOR (COORDINATE WITH ARCHITECT).
 D. FRONT BLADES PARALLEL TO LONG DIMENSION.
 E. DOUBLE DEFLECTION BARS SHALL BE ADJUSTABLE.
 F. FRAME TYPE TO MATCH CEILING/WALL CONSTRUCTION. COORDINATE WITH ARCHITECTURAL REFLECTED CEILING/WALL PLAN.
 G. PROVIDE OPPOSED BLADE DAMPER ADJUSTABLE FROM FACE OF DEVICE.
 H. PROVIDE DIFFUSERS, LINEAR SLOTS, AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.
 J. CONTRACTOR SHALL PROVIDE REMOTE CABLE-OPERATED VOLUME DAMPER BY METROPOLITAN AIR TECHNOLOGIES MODEL RT-250 WITH EXTERNAL WORM GEAR OPERATOR OR EQUIVALENT YOUNG REGULATOR BUTTERFLY DAMPER WITH 270-275 CONTROLLER. OPERATOR SHALL HAVE A SQUARE DRIVE FOR 1/4" NUT DRIVER. DAMPER ASSEMBLY SHALL INCLUDE GALVANIZED STEEL DUCT WITH ROLLED BEAD STIFFENERS, REINFORCED BLADE, SELF LUBRICATING BEARING AND WORM GEAR MOUNTING PLATE. DAMPER SHALL BE INSTALLED IN BRANCH DUCT NOT INLET OF PLENUM DIFFUSER. (REF. 2M601)
 K. 4-WAY THROW PATTERN UNLESS OTHERWISE INDICATED BY FLOW ARROWS ON DRAWINGS.
 L. PROVIDE RAPID MOUNT FRAME FOR INSTALLATION IN HARD CEILING.

PROJECT DESIGN CONDITIONS																									
CLIMATE CONDITIONS						BUILDING OPERATING HOURS:																			
WEATHER STATION: CHICAGO DUPAGE, IL, USA						MONDAY - FRIDAY																			
CLIMATE ZONE: 5A						SATURDAY																			
HEATING (DB): 99.6%						SUNDAY																			
COOLING (DB/MCWB): 0.4%						HOLIDAY																			
SPACE / UNIT DESCRIPTION	SET POINTS										SPACE OPERATING HOURS OCCUPIED / UNOCCUPIED	NOTES													
	COOLING / DEHUMIDIFICATION					HEATING							HUMIDIFICATION					ZONE VENTILATION / RESET							
	UNOCC	UNOCC	MAX RH %	MIN RH %	MIN	UNOCC	UNOCC	MAX RH %	MIN RH %	MIN			UNOCC	UNOCC	MAX RH %	MIN RH %	MIN	UNOCC	UNOCC	MAX RH %	MIN RH %	MIN	UNOCC	UNOCC	MAX RH %
DINING AREAS	75	80	50%	NA	70	60	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	A,B,C
OFFICES	75	80	50%	NA	70	60	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	A,B,C
MECHANICAL ROOM	NA	NA	NA	NA	70	60	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	A,B,C
KITCHEN/BOH	75	80	50%	NA	70	60	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	A,B,C

NOTES:
 A. ZONE LEVEL SET POINT CONDITIONS SHALL BE AS SCHEDULED UNLESS OTHERWISE SCHEDULED OR NOTED ON THE DRAWINGS FOR ROOM SPECIFIC SPACE CONDITIONS.
 B. ZONE LEVEL OCCUPANCY HOUR SCHEDULE SHALL BE PER BUILDING OPERATING HOURS UNLESS OTHERWISE SCHEDULED.
 C. ZONE LEVEL CONTROLS SHALL BE CAPABLE OF OPERATING WITH INDEPENDENT OCCUPANCY SCHEDULES.

ROOFTOP UNIT SCHEDULE (DX COOLING, NATURAL GAS HEAT)																														
EQUIPMENT IN SCHEDULE FOR REFERENCE ONLY. FURNISHED BY OWNER.																														
MARK	MANUFACTURER	MODEL	NOMINAL TONS	UNIT TYPE	SUPPLY FAN				COOLING COIL				EAT				HEAT EXCHANGER				ELECTRICAL				WEIGHT (LBS)	NOTES				
					CFM	ESP (IN)	HP	VFD (Y/N)	TH (MBH)	SH (MBH)	EAT (°F DB)	(°F WB)	(°F DB)	(°F WB)	REFR (R410A)	MIN EFF (MBH)	MIN NO STAGES	MIN OUT (MBH)	NOM INPUT (MBH)	MIN EFF (%)	EAT (°F DB)	(°F DB)	MIN NO STAGES	MIN O/A CFM			VPH	MCA	MOCP	DISC TYPE
RTU-1	CAPTIVE AIRE	12.5 Ton	12.5	SINGLE ZONE	2,400	0.8	3	Y	140.5	83.3	82.1	88.5	50.6	49.1	R410A	21.3	3	126.6	159.3	81	36.2	85	2	1100	2083	60.9	70	FUSED	2338	A-O
RTU-2	CAPTIVE AIRE	20 Ton	20	SINGLE ZONE	4,700	0.8	5	Y	230.3	142.8	83.2	89.4	55.6	54.0	R410A	18.2	3	275.4	344.3	81	30.7	85	2	2500	2083	89.1	100	FUSED	2871	A-O

*** EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS. EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T12 / VENDOR LIST FOR MORE INFORMATION.**
 MODEL NUMBERS AND NOMINAL TONS LISTED SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER, MODEL NUMBERS, OR NOMINAL TONS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
 A. REFER TO ROOFTOP UNIT CONTROL MATRIX FOR CONTROL FEATURES, MODULES, AND ACCESSORIES THAT SHALL BE PROVIDED WITH THE EQUIPMENT.
 B. EQUIPMENT SIZED FOR 100% AMBIENT TEMPERATURE.
 C. PROVIDE 2" MERV 8 EFFICIENT PLEATED THROWAWAY AIR FILTERS.
 D. PROVIDE FACTORY MOUNTED DISCONNECT INSTALLED ON SERVICE SIDE OF UNIT.
 E. STARTERS FOR ALL MOTORS SHALL BE FURNISHED INTEGRAL WITH UNIT.
 F. PROVIDE SINGLE POINT POWER CONNECTION.
 G. COORDINATE SIZE OF CONDUCTOR TERMINATION LUGS WITH CONDUCTOR SIZES SHOWN ON ELECTRICAL DRAWINGS.
 H. PROVIDE 125 VAC, 20 AMP DUPLEX CONVENIENCE RECEPTACLE MOUNTED TO UNIT READY FOR FIELD WIRING WITH A COVER UL LISTED FOR WET AND DAMPER LOCATIONS WHEN IN USE.
 I. SPECIFIED FAN ESP ACCOUNTS FOR DUCT LOSSES EXTERNAL TO UNIT.
 J. PROVIDE MOTOR HORSEPOWER TO OVERCOME INTERNAL UNIT STATIC PRESSURE DROP PLUS SPECIFIED EXTERNAL STATIC PRESSURE DROP. NOMINAL MOTOR HP SHALL BE NO LARGER THAN THE FIRST AVAILABLE NOMINAL MOTOR SIZE GREATER THAN THE REQUIRED BHP.
 K. PROVIDE INSULATED ROOF CURB WITH MINIMUM HEIGHT REQUIRED TO MAINTAIN BOTTOM OF EQUIPMENT A MINIMUM OF 24 INCHES ABOVE FINISHED ROOF SURFACE. PROVIDE SLOPED CURB IF NEEDED TO MATCH ROOF SLOPE.
 L. COORDINATE WITH ROOF INSULATION THICKNESS AND ROOF TAPER AT INSTALLED LOCATION. COORDINATE CURB TYPE WITH DRAWINGS.
 M. SCHEDULED WEIGHT IS THE MAXIMUM ALLOWABLE OPERATING WEIGHT OF THE EQUIPMENT ONLY.
 N. COOLING COIL LAT IS LEAVING AIR TEMPERATURE OF COIL.
 O. PROVIDE GUARDS TO PROTECT CONDENSER COIL FROM HAIL OR OTHER DAMAGE.
 D. PROVIDE HEATER TO MEET OR EXCEED SCHEDULED MINIMUM MBH OUTPUT. NOMINAL INPUT IS BASED ON LISTED MANUFACTURER'S STANDARD PRODUCT. COORDINATE EQUIPMENT GAS LOAD WITH PLUMBING CONTRACTOR IF DIFFERENT FROM THAT SCHEDULED. MEET MINIMUM EFFICIENCY SCHEDULED.

UNIT HEATER SCHEDULE (ELECTRIC)									
MARK	MANUFACTURER	MODEL	OUTPUT (KW)	MIN. NO. OF STAGES	CFM	VPH	NOTES		
EUH-1	QMARK	CDF-558	5	1	300	208/1	B	C	E F G
EUH-2	QMARK	MUH05-81	5	1	350	208/1	A	C	D E F H

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
 A. MOUNT 8 FEET ABOVE FINISHED FLOOR WITHOUT OBSTRUCTING AIRFLOW.
 B. PROVIDE WITH FACTORY INSTALLED THERMOSTAT.
 C. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE IN ARCHITECTURAL SET.
 D. PROVIDE NECESSARY MOUNTING BRACKET AND ACCESSORIES FOR WALL MOUNTING.
 E. PROVIDE FACTORY INSTALLED DISCONNECT SWITCH.
 F. SUPPORT UNIT AS RECOMMENDED BY UNIT MANUFACTURER.
 G. FURNISH WITH RECESSED MOUNTING ENCLOSURE.
 H. PROVIDE WITH WALL MOUNTED LINE VOLTAGE THERMOSTAT.

FAN COIL UNIT SCHEDULE (HEAT PUMP)																								
MARK	MFR	MODEL	SUPPLY FAN				COOLING COIL				HEAT PUMP HEATING COIL				ELECTRICAL				WEIGHT (LBS)	NOTES				
			CFM	ESP (IN)	NOM HP	VFD (Y/N)	TH (MBH)	SH (MBH)	EAT (°F DB)	(°F WB)	(°F DB)	(°F WB)	REFR (R410A)	MIN EFF (MBH)	MIN NO STAGES	MIN OUT (MBH)	NOM INPUT (MBH)	MIN EFF (%)			EAT (°F DB)	(°F DB)	MIN NO STAGES	MIN O/A CFM
FCU-1	CARRIER	40MBCQ18	420	0.025	0.061	10.0	9.0	76.5	63.9	57.0	55.5	R410A	8.51	-3.8	63	85	40	208/1	N/A	N/A	N/A	NF	45	A-J

*** EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION.**
 MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
 A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS.
 B. ASSOCIATED CONDENSING UNIT SHALL BE BY THE SAME MANUFACTURER.
 C. FOR COOLING, EQUIPMENT SIZED FOR 95% AMBIENT TEMPERATURE. HEAT PUMP HEATING CAPACITY BASED ON AMBIENT TEMPERATURE LISTED.
 D. PROVIDE UNIT WITH CLEANABLE AIR FILTERS.
 E. PROVIDE WITH 7-DAY PROGRAMMABLE THERMOSTAT WITH STAGED HEATING AND COOLING CAPABILITY AS REQUIRED FOR OPERATION OF HEATING AND COOLING CONTROLS.
 F. PROVIDE FACTORY MOUNTED STARTER AND DISCONNECT SWITCH INSTALLED ON SERVICE SIDE OF UNIT.
 G. PROVIDE SINGLE POINT POWER CONNECTION.
 H. PROVIDE WITH SPRING VIBRATION ISOLATION AND ALL-THREAD HANGING RODS.
 J. REFERENCE PLUMBING PLANS FOR CONDENSATE DRAIN PIPING FROM UNIT.

BUILDING AIR BALANCE SUMMARY NORMAL OPERATION				
UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/S/A
RTU-1	2,400	1,100	--	46%
RTU-2	4,700	2,500	--	53%
FCU-1	420	40	--	10%
KEF-1	--	--	700	--
KEF-2	--	--	700	--
KEF-3	--	--	700	--
KEF-4	--	--	700	--
EF-1	--	--	300	--
TOTALS	7,520	3,640	3,100	--
TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)			540	
PERCENT POSITIVE PRESSURIZATION			14.8%	

HEAT PUMP CONDENSING UNIT SCHEDULE															
MARK	SERVICE	MANUFACTURER	MODEL	REFR TYPE	COOLING CAPACITY			HEATING CAPACITY			ELECTRICAL			WEIGHT (LBS)	NOTES
					TH (MBH)	AMBIENT (DB)	MIN EFF (SEER)	CAP (MBH)	AMBIENT (DB)	MIN EFF COP 47°F	MIN O/A CFM	VPH	MCA		
CU-1	FCU-1	CARRIER	38MAQ18	R410A	10.6	95.0	20.0	8.5	-3.8	3.43	18	25	208 / 1	119	A-H

*** EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION.**
 MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
 A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS.
 B. EQUIPMENT CAPACITY SCHEDULED IS MINIMUM CAPACITY THAT MUST BE PROVIDED AT AMBIENT TEMPERATURE INDICATED.
 C. CONTRACTOR SHALL VERIFY WITH EQUIPMENT SUPPLIER EXACT QUANTITY AND SIZE OF REFRIGERANT PIPING.
 D. PROVIDE LIQUID LINE FILTER DRYER AND SIGHT GLASS.
 E. PROVIDE PREFABRICATED EQUIPMENT SUPPORT RAILS.
 F. PROVIDE FACTORY MOUNTED DISCONNECT INSTALLED ON SERVICE SIDE OF UNIT.
 G. STARTERS FOR ALL MOTORS SHALL BE FURNISHED INTEGRAL WITH UNIT.
 H. COORDINATE SIZE OF CONDUCTOR TERMINATION LUGS WITH CONDUCTOR SIZES SHOWN ON ELECTRICAL DRAWINGS.

BUILDING AIR BALANCE SUMMARY ECONOMIZER MODE				
UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/S/A
RTU-1	2,400	2,400	--	100%
RTU-2	4,700	4,700	--	100%
FCU-1	420	40	--	10%
KEF-1	--	--	700	--
KEF-2	--	--	700	--
KEF-3	--	--	700	--
KEF-4	--	--	700	--
EF-1	--	--	300	--
RELIEF RTU-1	--	--	1,300	--
RELIEF RTU-2	--	--	2,200	--
TOTALS	7,520	7,140	6,600	--
TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)			540	
PERCENT POSITIVE PRESSURIZATION			7.6%	

AIR CURTAIN SCHEDULE									
MARK	SERVICE AREA	MANUFACTURER	MODEL	UNIT SPECS				NOTES	
				LENGTH (IN)	MAX AIRFLOW	HEATING CAPACITY (KW)	MOTOR		
AC-1	MAIN ENTRY	MARS	STD2	36	1040	12	1/2	208/3	A-F
AC-2	SERVICE ENTRY	MARS	STD2	36	1379	N/A	1/2	115/1	A-E

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
 A. EQUIPMENT FURNISHED AND INSTALLED BY MECHANICAL CONTRACTOR. REF ARCHITECTURAL DRAWINGS.
 B. MOUNT UNIT PER MANUFACTURER'S RECOMMENDATIONS TO FACE OF WALL AND SUPPORT VERTICALLY.
 C. PROVIDE INTEGRAL STARTER AND DISCONNECT SWITCH.
 D. PROVIDE AIR CURTAIN WITH NORMALLY CLOSED DOOR LIMIT SWITCH FOR INSTALLATION ON DOOR. THE IR CURTAIN SHALL ENERGIZE WHEN DOOR OPENS.
 E. PROVIDE WITH DELAY MICROSWITCH WITH ADJUSTABLE DELAY TIMERS PRE MOUNTED IN THE AIR CURTAIN CONTROL PANEL.
 F. PROVIDE WITH WALL MOUNTED THERMOSTAT.

FAN SCHEDULE														
MARK	SERVICE	MANUFACTURER	MOUNTING	MODEL	CFM	ESP (IN)	DRIVE (BELT/DIRECT)	MIN HP	FAN RPM	VFD (Y/N)	ELECTRICAL			NOTES
											VPH	DISC. TYPE	STARTER TYPE	
EF-1	TOILETS	GREENHECK	ROOF	G-080-VG	300	0.5	DIRECT	1/10	1663	N	120/1	NF	COMBINATION	A-E

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:
 A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS.
 B. PROVIDE WITH MINIMUM 12" HIGH ROOF CURB, BIRDSCREEN AND BACKDRAFT DAMPER.
 C. PROVIDE FACTORY MOUNTED DISCONNECT SWITCH.
 D. INTERLOCK FAN OPERATION WITH TIME CLOCK.
 E. PROVIDE WITH MANUFACTURER'S FAN SPEED CONTROLLER FOR BALANCING PURPOSES.

||
||
||

COMcheck Software Version COMcheckWeb
Mechanical Compliance Certificate

Project Information
 Energy Code: 2018 IECC
 Project Title: Shake Shack - Bloomingdale IL
 Location: Bloomingdale, Illinois
 Climate Zone: 5a
 Project Type: New Construction

Construction Site: Owner/Agent: Designer/Contractor:

Additional Efficiency Package(s)
 Credits: 1.0 Required 0.0 Proposed

Mechanical Systems List

Quantity System Type & Description

- 1 RTU 1 (Single Zone):
 Heating: 1 each - Central Furnace, Gas, Capacity = 113 kBtu/h
 Proposed Efficiency = 83.00% EER, Required Efficiency: 80.00% EER or 80% AFUE
 Cooling: 1 each - Single Package DX Unit, Capacity = 153 kBtu/h, Air-Cooled Condenser, Air Economizer
 Proposed Efficiency = 11.80 EER, Required Efficiency = 10.80 EER
 Proposed Part Load Efficiency = 21.30 IEER, Required Part Load Efficiency = 12.20 IEER
 Fan System: RTU 1 - Compliance (Motor nameplate HP and fan efficiency method) : Passes
 Fans:
 RTU 1 Supply, Single-Zone VAV, 2400 CFM, 3.0 motor nameplate hp, 0.0 fan efficiency grade, 0.0 total fan efficiency, 0.0 design fan efficiency, fan exception: Single fan <= 5HP
- 1 RTU 2 (Single Zone):
 Heating: 1 each - Central Furnace, Gas, Capacity = 234 kBtu/h
 Proposed Efficiency = 83.00% EER, Required Efficiency: 80.00% EER or 80% AFUE
 Cooling: 1 each - Single Package DX Unit, Capacity = 263 kBtu/h, Air-Cooled Condenser, Air Economizer
 Proposed Efficiency = 11.10 EER, Required Efficiency = 9.80 EER
 Proposed Part Load Efficiency = 18.20 IEER, Required Part Load Efficiency = 11.40 IEER
 Fan System: RTU 2 - Compliance (Motor nameplate HP and fan efficiency method) : Passes
 Fans:
 RTU 2 Supply, Single-Zone VAV, 4700 CFM, 5.0 motor nameplate hp, 0.0 fan efficiency grade, 0.0 total fan efficiency, 0.0 design fan efficiency, fan exception: Single fan <= 5HP

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2018 IECC requirements in COMcheck Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

DALTON JUENEMANN - DESIGNER *Dalton Juennemann* **11/28/2022**
 Name - Title Signature Date

Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 1 of 10

Section # & Req. ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C402.2.6 (ME41)	Thermally ineffective panel surfaces of sensible heating panels have insulation >= R-3.5.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.8.4 (ME142)	Motors for fans that are not less than 1/12 hp and less than 1 hp are electronically commutated motors or have a minimum motor efficiency of 70 percent. These motors have the means to adjust motor speed.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.8.4 (ME142)	Motors for fans that are not less than 1/12 hp and less than 1 hp are electronically commutated motors or have a minimum motor efficiency of 70 percent. These motors have the means to adjust motor speed.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.8.5 (ME143)	Each DX cooling system > 65 kbtu and chiller water/evaporative cooling system with fans > 1/4 hp are designed to vary the indoor fan airflow as a function of load and comply with detailed requirements of this section.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.8.5 (ME143)	Each DX cooling system > 65 kbtu and chiller water/evaporative cooling system with fans > 1/4 hp are designed to vary the indoor fan airflow as a function of load and comply with detailed requirements of this section.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.12.1 (ME71)	Systems that heat outside the building envelope are radiant heat systems controlled by an occupancy sensing device or timer switch.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.5 (ME113)	Fault detection and diagnostics installed with air-cooled unitary DX units having economizers.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.5 (ME113)	Fault detection and diagnostics installed with air-cooled unitary DX units having economizers.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.2 (ME59)	Natural or mechanical ventilation is provided in accordance with International Mechanical Code Chapter 4. Mechanical ventilation has capability to reduce outdoor air supply to minimum per IMC Chapter 4.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.7.1 (ME131)	Demand control ventilation provided for spaces >50 ft ² and >25 people/1000 ft ² occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow >3,000 cfm.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.7.2 (ME131)	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 5 of 10

COMcheck Software Version COMcheckWeb
Inspection Checklist
 Energy Code: 2018 IECC

Requirements: 100.0% were addressed directly in the COMcheck software
 Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req. ID	Plan Review	Complies?	Comments/Assumptions
C103.2 (PR2)	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical systems and equipment and document where exceptions to the standard are claimed. Load calculations per acceptable engineering standards and handbooks.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C406 (PR9)	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the additional energy efficiency package options.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 2 of 10

Section # & Req. ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C403.7.6 (ME141)	HVAC systems serving guestrooms in Group R-1 buildings with > 50 guestrooms: Each guestroom is provided with controls that automatically manage temperature setpoint and ventilation (see sections C403.7.6.1 and C403.7.6.2).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.7.4 (ME57)	Exhaust air energy recovery on systems meeting Table C403.7.4(1) and C403.7.4(2).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Where prohibited by the International Mechanical Code.
C403.7.5 (ME116)	Kitchen exhaust systems comply with replacement air and conditioned supply air limitations, and satisfy hood rating requirements and maximum exhaust rate criteria.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.11.1 (ME60)	HVAC ducts and plenums insulated in accordance with C403.11.1 and constructed in accordance with C403.11.2, verification may need to occur during Foundation Inspection.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.1 (ME62)	Air economizers provided where required, meet the requirements for design capacity, control signal, ventilation controls, high-limit shut-off, integrated economizer control, and provide a means to relieve excess outside air during operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.1 (ME62)	Air economizers provided where required, meet the requirements for design capacity, control signal, ventilation controls, high-limit shut-off, integrated economizer control, and provide a means to relieve excess outside air during operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.3 (ME124)	Air economizers automatically reduce outdoor air intake to the design minimum outdoor air quantity when outdoor air intake will not reduce cooling energy usage. See Table C403.5.3.3 for applicable device types and climate zones.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.3 (ME124)	Air economizers automatically reduce outdoor air intake to the design minimum outdoor air quantity when outdoor air intake will not reduce cooling energy usage. See Table C403.5.3.3 for applicable device types and climate zones.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.3 (ME125)	System capable of relieving excess outdoor air during air economizer operation to prevent overpressurizing the building. The relief air outlet located to avoid recirculation into the building.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.3 (ME125)	System capable of relieving excess outdoor air during air economizer operation to prevent overpressurizing the building. The relief air outlet located to avoid recirculation into the building.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 6 of 10

Section # & Req. ID	Footing / Foundation Inspection	Complies?	Comments/Assumptions
C403.12.3 (FO7)	Snow/ice melting system and freeze protection systems have sensors and controls configured to limit service for pavement temperature and outdoor temperature, future connection to controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 3 of 10

Section # & Req. ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C405.3.3 (ME126)	Return, exhaust/relief and outdoor air dampers used in economizers have motorized dampers that automatically shut when not in use and meet maximum leakage rates. Reference section C403.7.7 for details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C405.3.3 (ME126)	Return, exhaust/relief and outdoor air dampers used in economizers have motorized dampers that automatically shut when not in use and meet maximum leakage rates. Reference section C403.7.7 for details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.4.1 (ME63)	Heating for vestibules and air curtains with integral heating include automatic controls that shut off the heating system when outdoor air temperatures > 45F. Vestibule heating and cooling systems controlled by a thermostat in the vestibule with heating setpoint = 60F and cooling setpoint = 80F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.3.9 (ME35)	Hot gas bypass limited to: <=240 kBTu/h - 50% >240 kBTu/h - 25%	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.3.3 (ME35)	Hot gas bypass limited to: <=240 kBTu/h - 50% >240 kBTu/h - 25%	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.2.1 (ME53)	Air outlets and zone terminal devices have means for air balancing.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.3 (ME123)	Refrigerated display cases, walk-in coolers or walk-in freezers served by remote compressors and remote condensers not located in a condensing unit, have fan-powered condensers that comply with Section C403.5.3 and refrigeration compressor systems that comply with C403.5.2.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 7 of 10

Section # & Req. ID	Plumbing Rough-In Inspection	Complies?	Comments/Assumptions
C404.5.1 (PL6)	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.5.1 (PL6)	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.6.3 (PL7)	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.6.3 (PL7)	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.7 (PL8)	Demand recirculation water systems have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.7 (PL8)	Demand recirculation water systems have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 4 of 10


Section # & Req. ID	Rough-In Electrical Inspection	Complies?	Comments/Assumptions
C405.6 (EL26)	Low-voltage dry-type distribution electric transformers meet the minimum efficiency requirements of Table C405.6.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C405.7 (EL27)	Electric motors meet the minimum efficiency requirements of Tables C405.7(1) through C405.7(4). Efficiency verified through certification under an approved certification program or the equipment efficiency ratings shall be provided by motor manufacturer (where certification programs do not exist).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C405.8.2 (EL28)	Escalators and moving walks comply with ASME A17.1/CSA B44 and have automatic controls configured to reduce speed to the minimum permitted speed in accordance with ASME A17.1/CSA B44 or applicable local code when not conveying passengers.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C405.9 (EL29)	Total voltage drop across the combination of feeders and branch circuits <= 5%.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)
 Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 8 of 10



CONSULTANTS:
HENDERSON ENGINEERS
 8345 LENEAX DRIVE, SUITE 300
 LENEAX, KS 66214
 TEL 913.742.2000 FAX 913.742.5001
 WWW.HENDERSONENGINEERS.COM
 250003452
 IL CORPORATE NO. 184-002965
 EXPRES 4-20-2025



SEAU SIGNATURE: COY M. MACY 08/21/2023

NO.	BY	DATE	DESCRIPTION
1	HEI	2023-08-21	IFC SET
2	HEI	2023-06-09	ADDENDUM C
3	HEI	2023-04-26	ADDENDUM B
4	HEI	2023-02-08	ADDENDUM A
5	HEI	2023-01-09	PERMIT/IBD SET



SHAKE SHACK
 BLOOMINGDALE, IL

355 ARMY TRAIL ROAD,
 BLOOMINGDALE, IL 60108
 SHACK #1474

IFC SET

MECHANICAL ENERGY
 CODE COMPLIANCE

DRAWN BY: Author
 CHECKED BY: Checker
 JOB NO: 20188.00

M630

CONSULTANTS:

HENDERSON ENGINEERS
 8345 LENEKA DRIVE, SUITE 300
 LENEKA, KS 66214
 TEL 913.742.2000 FAX 913.742.5001
 WWW.HENDERSONENGINEERS.COM

2250003452
 IL CORPORATE NO. 184-002965
 EXPIRES 4/30/2025


SEAL SIGNATURE:



08/21/2023

1	HEI	2023-08-21	IFC SET
C	HEI	2023-06-09	ADDENDUM C
B	HEI	2023-04-26	ADDENDUM B
A	HEI	2023-02-08	ADDENDUM A
HEI		2023-01-09	PERMIT/BID SET

NO.	BY	DATE	DESCRIPTION
-----	----	------	-------------



SHAKE SHACK
 BLOOMINGDALE IL

355 ARMY TRAIL ROAD,
 BLOOMINGDALE, IL 60108
 SHACK #1474

IFC SET

MECHANICAL ENERGY
 CODE COMPLIANCE

DRAWN BY: _____ Author
 CHECKED BY: _____ Checker
 JOB NO: _____ 20188.00

M631

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C403.3 C408.2.5 3 [F18]¹	Furnished O&M manuals for HVAC systems within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.2 1 [F12]¹	HVAC systems and equipment capacity does not exceed calculated loads.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4 1 [F14]¹	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4 1 [F14]¹	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.4.1 2 [F138]¹	Thermostatic controls have a 5 °F deadband.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4 1.3 [F120]¹	Temperature controls have setpoint overlap restrictions.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4 2 [F139]¹	Each zone equipped with setback controls using automatic time clock programmable control system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4 2.1 [F140]¹	Automatic Controls: Setback to 55°F (heat) and 55°F (cool); 7-day clock, 2-hour occupant override, 10-hour backup	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4 2.3 [F141]¹	Systems include optimum start controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4 2.3 [F141]¹	Systems include optimum start controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.1.1 1 [F15]¹	Building operations and maintenance documents will be provided to the owner. Documents will cover manufacturers' information, specifications, programming procedures and means of illustrating to owner how building, equipment and systems are intended to be installed, maintained, and operated.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 9 of 10

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C408.2.1 1 [F128]¹	Commissioning plan developed by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3 1 [F131]¹	HVAC equipment has been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3 2 [F110]¹	HVAC control systems have been tested to ensure proper operation, calibration and adjustment of controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3 3 [F132]¹	Economizers have been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.4 1 [F129]¹	Preliminary commissioning report completed and certified by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5 1 [F17]¹	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5 3 [F143]¹	An air and/or hydronic system balancing report is provided for HVAC systems.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5 4 [F130]¹	Final commissioning report due to building owner within 90 days of receipt of certificate of occupancy.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Shake Shack - Bloomingdale IL Report date: 11/28/22
 Data filename: Page 10 of 10

HOOD INFORMATION

HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST PLENUM RISER(S)				HOOD CONSTRUCTION	HOOD CONFIG			
										WIDTH	LENG	HEIGHT	DIA		CFM	VEL	SP	END TO END
1	GRILL	3650 BD-2	CAPTIVEAIRE	4' 0"	600 DEG	1	HEAVY	175	700	8"	8"	4"	700	1575	-0.574'	430 SS WHERE EXPOSED	ALDNE	ALDNE
2	GRILL	3650 BD-2	CAPTIVEAIRE	4' 0"	600 DEG	1	HEAVY	175	700	8"	8"	4"	700	1575	-0.574'	430 SS WHERE EXPOSED	ALDNE	ALDNE
3	FRYER	3650 BD-2	CAPTIVEAIRE	4' 0"	600 DEG	1	HEAVY	175	700	8"	8"	4"	700	1575	-0.574'	430 SS WHERE EXPOSED	ALDNE	ALDNE
4	FRYER	3650 BD-2	CAPTIVEAIRE	4' 0"	600 DEG	1	HEAVY	175	700	8"	8"	4"	700	1575	-0.574'	430 SS WHERE EXPOSED	ALDNE	ALDNE



FOR QUESTIONS, CALL THE
 Eastern PA Mechanical
 REGION 109
 PHONE: (267) 504-4126
 EMAIL: reg108@captiveaire.com

HOOD INFORMATION



HOOD NO	TAG	TYPE	FILTER(S)			LIGHT(S)			UTILITY CABINET(S)			FIRE SYSTEM PIPING	HOOD HANGING WEIGHT			
			QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE			FIRE SYSTEM	SIZE	ELECTRICAL MODEL #
1	GRILL	CAPRATE SOLD FILTER	2	16"	20"	85% SEE FILTER SPEC	1	RECESSED ROUND	NO	WALL MNT	12"x60"x24"	TANK FS	4.0/4.0/4.0/4.0		YES	215 LBS
2	GRILL	CAPRATE SOLD FILTER	2	16"	20"	85% SEE FILTER SPEC	1	RECESSED ROUND	NO						YES	215 LBS
3	FRYER	CAPRATE SOLD FILTER	2	16"	20"	85% SEE FILTER SPEC	1	RECESSED ROUND	NO					YES	215 LBS	
4	FRYER	CAPRATE SOLD FILTER	2	16"	20"	85% SEE FILTER SPEC	1	RECESSED ROUND	NO					YES	215 LBS	

HOOD OPTIONS

HOOD NO	TAG	OPTION
1	GRILL	FIELD WRAPPER 37.00" HIGH FRONT, LEFT, RIGHT.
		RIGHT QUARTER END PANEL 26" TOP WIDTH, 0" BOTTOM WIDTH, 26" HIGH 430 SS.
		LEFT QUARTER END PANEL 26" TOP WIDTH, 0" BOTTOM WIDTH, 26" HIGH 430 SS.
		1-PINT GREASE CUP.
2	GRILL	RISER SENSOR INSTALL 6IN PLEN.
		FIELD WRAPPER 37.00" HIGH FRONT, LEFT, RIGHT.
		RIGHT QUARTER END PANEL 26" TOP WIDTH, 0" BOTTOM WIDTH, 26" HIGH 430 SS.
		LEFT QUARTER END PANEL 26" TOP WIDTH, 0" BOTTOM WIDTH, 26" HIGH 430 SS.
3	FRYER	1-PINT GREASE CUP.
		RISER SENSOR INSTALL 6IN PLEN.
		FIELD WRAPPER 37.00" HIGH FRONT, LEFT, RIGHT.
		RIGHT QUARTER END PANEL 26" TOP WIDTH, 0" BOTTOM WIDTH, 26" HIGH 430 SS.
4	FRYER	LEFT QUARTER END PANEL 26" TOP WIDTH, 0" BOTTOM WIDTH, 26" HIGH 430 SS.
		1-PINT GREASE CUP.
		RISER SENSOR INSTALL 6IN PLEN.
		FIELD WRAPPER 37.00" HIGH FRONT, LEFT, RIGHT.



PLAN VIEW - HOOD #1 (GRILL), #2 (GRILL), #3 (FRYER), #4 (FRYER)
 4' 0.00" LONG 3650BD-2



SECTION VIEW - MODEL 3650BD-2

LISTINGS & CERTIFICATIONS

CAPTIVEAIRE HOODS BUILT IN COMPLIANCE WITH:

3054804-001 & 3054804-002
 STANDARD 710
 Listed under ETL File number 3054804-001/002

CLEARANCE TO COMBUSTIBLES

CAPTIVEAIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:


MATERIAL	CLEARANCE	REDUCTION SYSTEM
NON-COMBUSTIBLE	NONE REQUIRED	
LIMITED-COMBUSTIBLE	3" UNINSULATED STANDOFF	
COMBUSTIBLE	1" UNINSULATED STANDOFF	

GENERAL NOTES

- INSTALLATION**
- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
 - ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
 - HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
 - ALL CONNECTIONS FROM CAPTIVEAIRE HOOD PER MECHANICAL PLANS.
 - COOKING EQUIPMENT TO SHUT OFF IN EVENT OF FIRE.
 - EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
 - ALL LIGHT FIXTURES SHOWN INSTALLED BY CAPTIVEAIRE ARE FACTORY PROVIDED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES ARE BY ELECTRICAL CONTRACTOR.
 - LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
 - SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
 - INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTEGRATION, AND ADMINISTRATION OF CODE REQUIREMENTS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.
- BALANCE**
- KITCHEN HOODS MUST BE BALANCED WITH KITCHEN.
 - KITCHEN SHALL BE NEGATIVE WITH RESPECT TO DINING AREA.
 - RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.
- ADDITIONAL**
- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
 - SIGNED AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE RETURNED TO THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

HVAC DISTRIBUTION NOTE

IT IS RECOMMENDED NOT TO INSTALL HIGH VELOCITY DIFFUSERS OR HVAC RETURNS WITHIN TEN (10) FEET OF THE EXHAUST HOOD. PERFORATED, LOW-VELOCITY, NON-DIRECTIONAL DIFFUSERS ARE RECOMMENDED.



VERIFY CEILING HEIGHT

HEIGHT REQUIRED TO VERIFY THAT HOOD FITS SPACE AND TO SIZE THE ENCLOSURE PANELS

REVISIONS

NO.	DESCRIPTION	DATE
1		
2		
3		

CAPTIVEAIRE
 Eastern PA Mechanical
 PO Box 2520, 1 Union Ave, Bala Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg108@captiveaire.com

Shake Shack-1474-Bloomington, IL
 BLOOMINGTON, IL, 60108

DATE: 10/24/2022
 DWG #: 5698811
 DRAWN BY: Joe Shilka
 SCALE: 3/4" = 1'-0"
 MASTER DRAWING
 SHEET NO. 1

NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

Bergmeyer
 CONSULTANTS:
 SEAL SIGNATURE: _____ FOR REFERENCE ONLY
 DRAWN BY: Author
 CHECKED BY: Checker
 JOB NO: 20188.00
 M701
 800 South Figueroa St.
 Los Angeles, CA 90017
 212.337.1090
 www.bergmeyer.com

FIRE SYSTEM INFORMATION

FIRE SYSTEM NO	TAG	TYPE	SIZE	FLOW POINTS	INSTALLATION	
					SYSTEM	LOCATION ON HOOD
1		TANK FS	4.0/4.0/4.0/4.0	64	WALL UTILITY CABINET LEFT	N/A

GAS VALVE(S)

FIRE SYSTEM NO	TAG	TYPE	SIZE	SUPPLIED BY
1		SC ELECTRICAL	VFY	CAPTIVEAIRE SYSTEMS

WALL-MOUNT UTILITY CABINET

HOOD NO	LOCATION	SIZE	UTILITY CABINET(S)				WEIGHT
			FIRE SYSTEM	TYPE	SIZE	ELECTRICAL SWITCHES QUANTITY	
1	WALL MNT	12"x60"x24"	TANK FS		4.0/4.0/4.0/4.0		500.00 LBS

INCLUDES: FIELD INSTALLATION AND HOOKUP DURING NORMAL BUSINESS HOURS BY CERTIFIED INSTALLERS ONLY IN THE LOCATION NOTED ABOVE. TWO SITE VISITS ONLY (ONE VISIT TO SET PULL STATION & SYSTEM HOOKUP AND ONE VISIT FOR ONE TEST; ADDITIONAL VISITS WILL RESULT IN ADDITIONAL CHARGES). ONE MECHANICAL OR ELECTRICAL GAS VALVE PER SYSTEM AT A MAXIMUM SIZE OF 2". PERMIT, AND SYSTEM TEST.
EXCLUDES: UNION LABOR & PREVAILING WAGE (LABOR & WAGES WILL BE ADDED IF APPLICABLE), GAS VALVE INSTALLATION, ELECTRICAL HOOKUP AND CONNECTIONS, HANGING OF FIRE CABINET, SHUNT TRIP, HANDHELD EXTINGUISHER(S), ON-SITE RE-PIPING DUE TO EQUIPMENT LAYOUT CHANGES.

LEGEND - FIRE CABINET TANK SYSTEM

- 1 4 GALLON TANK.
- 2 PRIMARY ACTUATOR RELEASE.
- 3 SECONDARY ACTUATOR RELEASE.
- 4 PRESSURE SUPERVISION SWITCH.
- 5 PRIMARY HOSE ASSEMBLY.
- 6 SECONDARY HOSE ASSEMBLY.
- 7 REMOTE MANUAL ACTUATION DEVICE.

NOTES

- FIELD PIPE DROPS AS SHOWN
- PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
- FIELD INSTALLED DROP: FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
- SHIP LOOSE DROP: FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
- RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVEING, SALAMANDERS, ETC.
- OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
- IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
- FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.

- APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.
- THIS FIRE SYSTEM COMPLIES WITH U.L. 300 REQUIREMENTS.



- DL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS
JOB #: 5600403.
JOB NAME: SHAKESHACK-1462-BAYBROOKHOUSTON(KITCHEN).

SYSTEM SIZE: TANK-SP-4-WC TOTAL FP REQUIRED: 64.
HOOD # 1 4' 0.00' LONG x 36" WIDE x 50" HIGH.
RISER # 1 SIZE: 8" x 8".
HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.
HOOD # 2 4' 0.00' LONG x 36" WIDE x 50" HIGH.
RISER # 1 SIZE: 8" x 8".
HOOD # 2 METAL BLOW-OFF CAPS INCLUDED.
HOOD # 3 4' 0.00' LONG x 36" WIDE x 50" HIGH.
RISER # 1 SIZE: 8" x 8".
HOOD # 3 METAL BLOW-OFF CAPS INCLUDED.
HOOD # 4 4' 0.00' LONG x 36" WIDE x 50" HIGH.
RISER # 1 SIZE: 8" x 8".
HOOD # 4 METAL BLOW-OFF CAPS INCLUDED.

- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.


WALL-MOUNT UTILITY CABINET ASSEMBLY INSTRUCTIONS

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TPI GRADE 5 (MINIMUM) ALL-THREAD. SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TPI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION BENEATH UTILITY CABINET HANGING ANGLES AND ABOVE CEILING ANCHORS. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.



REVISIONS

DESCRIPTION	DATE




CAPTIVE
Eastern PA Mechanical
www.captiveaire.com
www.easternpa.com
PO Box 2620, 1 Union Ave, Bala Cynwyd, PA, 19004 PHONE: (267) 304-4128 EMAIL: reg108@captiveaire.com

Shake Shack-1474-Bloomington, IL
BLOOMINGTON, IL, 60108

DATE: 10/24/2022
DWG.#: 5698811
DRAWN BY: Joe.shilka
SCALE: 3/4" = 1'-0"
MASTER DRAWING

SHEET NO. 2



NOTE:
THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

Bergmeyer
LA
900 South Figueroa St.
Los Angeles, CA 90017
212.337.1090
www.bergmeyer.com

CONSULTANTS:
SEAL SIGNATURE:
FOR REFERENCE ONLY

NO.	BY	DATE	DESCRIPTION
1	HEI	2023-08-21	IFC SET
C	HEI	2023-06-09	ADDENDUM C
B	HEI	2023-04-26	ADDENDUM B
A	HEI	2023-02-08	ADDENDUM A
HEI		2023-01-09	PERMIT/ID SET



SHAKE SHACK
BLOOMINGDALE IL

355 ARMY TRAIL ROAD,
BLOOMINGDALE, IL 60108
SHACK #1474

IFC SET

CAPTIVE AIRE DRAWINGS

DRAWN BY: Author
CHECKED BY: Checker
JOB NO: 20188.00

M702

EXHAUST FAN INFORMATION

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	MANUFACTURER	CFM	ESP	RPM	MOTOR ENCL	HP	BHP	PHASE	VOLT	FLA	DISCHARGE VELOCITY	WEIGHT (LBS)	SDNES
1	KEF-1	1	DU50HFA	CAPTIVEAIRE	700	1.250	1549	TEAD-ECM	0.500	0.3840	1	208	3.8	266 FPM	82	16.7067343199543
2	KEF-2	1	DU50HFA	CAPTIVEAIRE	700	1.250	1549	TEAD-ECM	0.500	0.3840	1	208	3.8	266 FPM	82	16.7067343199543
3	KEF-3	1	DU50HFA	CAPTIVEAIRE	700	1.250	1549	TEAD-ECM	0.500	0.3840	1	208	3.8	266 FPM	82	16.7067343199543
4	KEF-4	1	DU50HFA	CAPTIVEAIRE	700	1.250	1549	TEAD-ECM	0.500	0.3840	1	208	3.8	266 FPM	82	16.7067343199543



FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	KEF-1	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FOR GREASE DUCTS
		1	ECM WIRING PACKAGE - PWM SIGNAL FROM ECPM03 PREWIRE (TELCD MOTOR), CCW ROTATION
		1	2 YEAR PARTS WARRANTY
2	KEF-2	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FOR GREASE DUCTS
		1	ECM WIRING PACKAGE - PWM SIGNAL FROM ECPM03 PREWIRE (TELCD MOTOR), CCW ROTATION
		1	2 YEAR PARTS WARRANTY
3	KEF-3	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FOR GREASE DUCTS
		1	ECM WIRING PACKAGE - PWM SIGNAL FROM ECPM03 PREWIRE (TELCD MOTOR), CCW ROTATION
		1	2 YEAR PARTS WARRANTY
4	KEF-4	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FOR GREASE DUCTS
		1	ECM WIRING PACKAGE - PWM SIGNAL FROM ECPM03 PREWIRE (TELCD MOTOR), CCW ROTATION
		1	2 YEAR PARTS WARRANTY

CURB ASSEMBLIES

NO	DN FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	KEF-1	34 LBS	CURB	19.500"W X 19.500"L X 24.000"H ALDNG LENGTH, RIGHT VENTED HINGED.
2	# 2	KEF-2	34 LBS	CURB	19.500"W X 19.500"L X 24.000"H ALDNG LENGTH, RIGHT VENTED HINGED.
3	# 3	KEF-3	34 LBS	CURB	19.500"W X 19.500"L X 24.000"H ALDNG LENGTH, RIGHT VENTED HINGED.
4	# 4	KEF-4	34 LBS	CURB	19.500"W X 19.500"L X 24.000"H ALDNG LENGTH, RIGHT VENTED HINGED.

FANS #1 (KEF-1), #2 (KEF-2), #3 (KEF-3), #4 (KEF-4) - DU50HFA EXHAUST FAN



TOP VIEW

FEATURES:


- DIRECT DRIVE CONSTRUCTION (NO BELTS/PULLEYS).
- ROOF MOUNTED FANS.
- RESTAURANT MODEL.
- UL705 AND UL762 AND ULC-3645
- VARIABLE SPEED CONTROL.
- INTERNAL WIRING.
- THERMAL OVERLOAD PROTECTION (SINGLE PHASE).
- HIGH HEAT OPERATION 300°F (149°C).
- GREASE CLASSIFICATION TESTING.
- NEMA 3R SAFETY DISCONNECT SWITCH.

NORMAL TEMPERATURE TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING AIR AT 300°F (149°C) UNTIL ALL FAN PARTS HAVE REACHED THERMAL EQUILIBRIUM, AND WITHOUT ANY DEGRADATING EFFECTS TO THE FAN WHICH WOULD CAUSE UNSAFE OPERATION.

ABNORMAL FLARE-UP TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING BURNING GREASE VAPORS AT 600°F (316°C) FOR A PERIOD OF 15 MINUTES WITHOUT THE FAN BECOMING DAMAGED TO ANY EXTENT THAT COULD CAUSE AN UNSAFE CONDITION.


OPTIONS

- GREASE BOX.
- FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FOR GREASE DUCTS.
- ECM WIRING PACKAGE - PWM SIGNAL FROM ECPM03 PREWIRE (TELCD MOTOR), CCW ROTATION.
- 2 YEAR PARTS WARRANTY.



PITCHED CURBS ARE AVAILABLE FOR PITCHED ROOFS.

SPECIFY PITCH:
EXAMPLE: 7/12 PITCH = 30° SLOPE.



REVISIONS	
DESCRIPTION	DATE



PO Box 2520, 1 Union Ave, Bala Cynwyd, PA, 19004 PHONE: (267) 504-4175 EMAIL: egi108@captiveaire.com

Shake Shack-1474-Bloomington, IL
BLOOMINGDALE, IL, 60108

DATE: 10/24/2022


DWG.#: 5698811

DRAWN BY: Joe.shilba

SCALE: 3/4" = 1'-0"

MASTER DRAWING

SHEET NO. 3



NOTE:
THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

Bergmeyer

LA
800 South Figueroa St.
Los Angeles, CA 90017
212.337.1090

CONSULTANTS:

SEAL SIGNATURE: _____
FOR REFERENCE ONLY

1 HEI 2023-08-21 IFC SET
C HEI 2023-05-09 ADDENDUM C
B HEI 2023-04-26 ADDENDUM B
A HEI 2023-02-08 ADDENDUM A
HEI 2023-01-09 PERMIT/IBD SET

NO. BY DATE DESCRIPTION

SHAKE SHACK

SHAKE SHACK
BLOOMINGDALE IL

355 ARMY TRAIL ROAD,
BLOOMINGDALE, IL 60108
SHACK #1474

IFC SET

CAPTIVE AIRE DRAWINGS

DRAWN BY: _____ Author
CHECKED BY: _____ Checker
JOB NO: 20188.00




M703

ELECTRICAL PACKAGE

NO	TAG	PACKAGE #	LOCATION	SWITCHES		OPTION	FANS CONTROLLED					
				LOCATION	QUANTITY		FAN TAG	TYPE	HP	VOLT	FLA	
1		SC-240110MA	WALL MOUNT IN SS BOX 14" x 18" x 6"	05 - SS WALL MOUNT BOX	1 LIGHT 1 FAN	SMART CONTROLS THERMOSTATIC CONTROL W/ RELAY ON/OFF WITH SUPPLY	KEF-1	EXHAUST	1	0.500	208	3.8
							KEF-2	EXHAUST	1	0.500	208	3.8
							KEF-3	EXHAUST	1	0.500	208	3.8
							KEF-4	EXHAUST	1	0.500	208	3.8

ELECTRICAL PACKAGE - JOB#5698811

NO	TAG	PACKAGE #	LOCATION	SWITCHES		OPTION	FANS CONTROLLED					
				LOCATION	QUANTITY		FAN TAG	TYPE	HP	VOLT	FLA	
1		SC-240110MA	WALL MOUNT IN SS BOX	05 - SS WALL MOUNT BOX	1 LIGHT 1 FAN	SMART CONTROLS THERMOSTATIC CONTROL W/ RELAY ON/OFF WITH SUPPLY	KEF-3	EXHAUST	1	0.500	208	3.8
							KEF-4	EXHAUST	1	0.500	208	3.8
							KEF-1	EXHAUST	1	0.500	208	3.8
							KEF-2	EXHAUST	1	0.500	208	3.8



REVISIONS	
DESCRIPTION	DATE



CAPTIVE
Eastern PA Mechanical
www.captiveaire.com
www.captiveaire.com
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (678) 504-4126 EMAIL: res108@captivate.com


Shake Shack-1474-Bloomington, IL
BLOOMINGTON, IL, 60108

DATE: 10/24/2022
DWG #: 5698811
DRAWN BY: Joe Shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING
SHEET NO. 4

Bergmeyer
LA
900 South Figueroa St.
Los Angeles, CA 90017
212.337.1090
www.bergmeyer.com

CONSULTANTS:
SEAL SIGNATURE:
FOR REFERENCE ONLY

NO.	BY	DATE	DESCRIPTION
1	HEI	2023-08-21	IFC SET
C	HEI	2023-06-09	ADDENDUM C
B	HEI	2023-04-26	ADDENDUM B
A	HEI	2023-02-08	ADDENDUM A
HEI		2023-01-09	PERMIT/IFC SET



SHAKE SHACK
BLOOMINGDALE, IL

355 ARMY TRAIL ROAD,
BLOOMINGDALE, IL 60108
SHACK #1474

IFC SET

CAPTIVE AIRE DRAWINGS


DRAWN BY: Author
CHECKED BY: Checker
JOB NO: 20188.00

M704

NOTE:
THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.


CRIMSON+ CONTROL DETAILS

LOW VOLTAGE & INTERLOCKS (SEE SCHEMATICS FOR LINE VOLTAGE)



TYPICAL HOOD WITH THERMOSTATIC CONTROL
SENSOR FIELD WIRING DETAILS
REFER TO ELECTRICAL SCHEMATICS
FOR FINAL DETAILS

--- FIELD WIRING



SC- Specification:

The Electrical Package, typically FP, is designed to thermostatically activate the exhaust fans for an exhaust hood whenever elevated temperatures are sensed in the exhaust system. This option will meet the requirements of IMC 507.2.1.1 by providing a thermostat(s) mounted in the duct or hood riser to sense increased exhaust temperatures. Controls shall be listed by ETL (UL 508A). The control enclosure shall be NEMA 1 rated and listed for installation inside of the exhaust hood utility cabinet. The control enclosure may be constructed of stainless steel or painted steel.

Temperature probes(s) located in the duct riser shall be constructed of Stainless Steel. A room temperature sensor is also provided for field installation in the kitchen space in order to start the fan(s) based on the temperature differential between the room and the exhaust air in the duct, rather than fixed set-points. The system is factory pre-set to activate the fans at 10 deg F° above the room temperature.

Once the duct temperature reaches the activation point, the exhaust fans will be activated. The controls also provide hysteresis to prevent cycling of the fans after the cooking appliances have been turned off and the heat in the exhaust system is reduced. The hysteresis is factory set 2 degrees and will keep the exhaust running until the temperature falls 2 degrees below the activation set point. A hysteresis timer also exists to keep the fans running for at least 30 min after being activated by the temperature rise.

The activation and hysteresis settings may be field adjusted on the board LCD interface located inside the control enclosure to meet application needs. The panel is factory configured to shut down supply fans, turn on the exhaust fans and turn off the hood lights in a fire condition.

REVISIONS	
DESCRIPTION	DATE

Eastern PA Mechanical
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 904-4729 EMAIL: rep1008@captiveaire.com

Shake Shack-1474-Bloomington, IL
BLOOMINGDALE, IL, 60108

DATE: 10/24/2022
DWG.#: 5698811
DRAWN BY: Joe Shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING

SHEET NO. 6

CUSTOMER APPROVAL TO MANUFACTURE:

Approved as Noted

Approved with ND Exception Taken

Revise and Resubmit

SIGNATURE _____

Your Title _____ Date _____

NOTE:
THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

Bergmeyer

CONSULTANTS:

SEAL SIGNATURE: _____
FOR REFERENCE ONLY

1	HEI	2023-08-21	IFC SET
C	HEI	2023-05-09	ADDENDUM C
B	HEI	2023-04-26	ADDENDUM B
A	HEI	2023-02-08	ADDENDUM A
HEI		2023-01-09	PERMIT/BD SET

NO. BY DATE DESCRIPTION

SHAKE SHACK

SHAKE SHACK
BLOOMINGDALE, IL

355 ARMY TRAIL ROAD,
BLOOMINGDALE, IL 60108
SHACK #1474

IFC SET

CAPTIVE AIRE DRAWINGS

DRAWN BY: _____ Author

CHECKED BY: _____ Checker

JOB NO: _____ 20188.00

M706

DOAS/RTU FAN SCHEDULE - JOB#5723950

FAN UNIT NO	TAG	QTY	DOAS/RTU MODEL #	FAN INFORMATION				ELECTRICAL INFORMATION				COOLING INFORMATION				REHEAT INFORMATION				GAS HEAT INFORMATION				NOTES													
				MANUFACTURER	BLOWER	RETURN AIR CFM	MAX OUTSIDE AIR CFM	TOTAL CFM	WEIGHT (LBS)	ESP	HP	PHASE	VOLT	MCA	MDCP	DB	WB	DB	WB	DB	WB	DP	TOTAL		SENS.	IEER	ISMRE	DISCHARGE DB	DISCHARGE WB	CAPACITY DESIRED	CAPACITY MAX	MOISTURE REMOVAL RATE	GAS TYPE	INPUT BTUS	OUTPUT BTUS	TEMP RISE	REQUIRED INPUT GAS PRESSURE
1	RTU-1	1	CASRTU3-1200-1B-12.5T	CAPTIVEAIRE	18P-3	1300	1100	2400	2361	1.000	3.00	3	208	61.9A	70A	90.3°F	74.7°F	82.1°F	68.5°F	48.3°F	48.0°F	47.8°F	153.6 MBH	88.1 MBH	21.3	4.1	75.0°F	62.5°F	70.7 MBH	101 MBH	57.0 LBS/HR	NATURAL	156296	126600	43°F	7 IN. W.C. - 14 IN. W.C.	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18
2	RTU-2	1	CASRTU3-1400-24-20T	CAPTIVEAIRE	24MF-3-RTU	2200	2500	4700	2771	1.000	5.00	3	208	93.4A	100A	90.3°F	74.7°F	83.2°F	69.4°F	51.7°F	51.7°F	51.8°F	246.0 MBH	154.1 MBH	18.2	6.0	75.0°F	62.5°F	120.2 MBH	129.6 MBH	84.3 LBS/HR	NATURAL	340000	275400	48°F	7 IN. W.C. - 14 IN. W.C.	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18

- NOTES:
1. INVERTER SCROLL COMPRESSOR WITH INTEGRATED OIL SENSOR. DIGITAL OR STAGED SCROLL NOT AN APPROVED EQUAL
 2. DIRECT DRIVE PLENUM BLOWER. BELT DRIVEN BLOWERS ARE NOT ACCEPTABLE
 3. INTEGRATED MONITORING VIA CELLULAR CONNECTION BY MANUFACTURER
 4. REFRIGERATION PRESSURE MONITORING ON HIGH AND LOW PRESSURE SIDE OF SYSTEM INCLUDED THROUGH DIGITAL INTERFACE
 5. EC MOTOR CONDENSING FANS
 6. ELECTRONIC EXPANSION VALVE. TXV NOT ACCEPTABLE
 7. SUCTION LINE ACCUMULATOR
 8. FACTORY COMMISSIONING WITH 5 YEAR PARTS WARRANTY, 25 YEAR WARRANTY ON STAINLESS STEEL HEAT EXCHANGER
 9. AVERAGING INTAKE, EVAP AND DISCHARGE TEMPERATURE SENSORS (DISCHARGE SENSOR TO BE FACTORY MOUNTED WITHIN UNIT)
 10. 2" EXTERIOR DUAL-WALL CONSTRUCTION W/ R-13 INSULATION-MINIMUM EGOR EXTERIOR W/ TGA BASE
 11. 81% EFFICIENT FURNACE, WITH MODULATING INDUCER TO MAINTAIN CONSTANT COMBUSTION EFFICIENCY ACROSS FIRING RANGE. 6:1 TURNDOWN WITH NG AND 5:1 TURNDOWN WITH LP
 12. SUPPLY CFM MONITORING INTEGRAL TO UNIT WITH CFM MEASUREMENT INCLUDED THROUGH DIGITAL INTERFACE
 13. FULLY MODULATING HOT GAS REHEAT
 14. 15 DEGREE LOW AMBIENT OPERATION
 15. HAIL GUARD FOR CONDENSING COIL
 16. RTU ECONOMIZER WITH DIFFERENTIAL ENTHALPY CONTROL
 17. BAROMETRIC RELIEF DAMPER
 18. DOWN DISCHARGE/DOWN RETURN


FOR QUESTIONS, CALL THE
 Eastern PA Mechanical
 REGION 108
 PHONE (607) 504 - 4126
 EMAIL: reg108@captiveaire.com

FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	RTU-1	1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE
		1	RTU TOTAL CFM MONITORING
		1	SHIP LOOSE GAS STRAINER 3/4"
		1	SINGLE POINT ELECTRICAL CONNECTION FOR RTU. 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #08, #47, "MA" OR "E2" PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE.
		1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
		1	LDW AMBIENT COOLING OPERATION - DOWN TO OF AMBIENT
		1	RTU3 DOWN DISCHARGE
		1	2" MERV 13 FILTERS FOR RTU3 (QTY. 4)
		1	2" MERV 8 FILTERS FOR RTU3 (QTY. 4)
		1	OVERHEAT STAT
		1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
		1	12.5 TON MODULATING COOLING OPTION, 208/230V. R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS
		1	12.5 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL
		1	REMOTE TEMPERATURE AND HUMIDITY SPACE SENSOR
		1	RTU3 CURB DUCT HANGER
		1	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS
		1	OCCUPIED SCHEDULING
		1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI
		1	RTU3 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX
		1	RTU ECONOMIZER - DIFFERENTIAL ENTHALPY CONTROL
		1	RTU3 ECONOMIZER BAROMETRIC RELIEF
		1	RTU3 HAIL GUARD
		1	RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI
		1	RTU3 DOWN RETURN
2	RTU-2	1	VAV PACKAGE W/ MANUAL/DDC CONTROL (S71 VFD INCLUDED)
		1	CONTROL PANEL ENCLOSURE HEATER 100W - RECOMMENDED FOR WINTER DESIGN TEMPERATURES LESS THAN 0°F
		1	RTU HEATED FURNACE CONDENSATE DRAIN KIT. REQUIRED FOR WINTER DESIGN TEMP OF 0 DEGREES F AND LOWER
		1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS)
		1	RTU HEATED FURNACE CONDENSATE DRAIN KIT. REQUIRED FOR WINTER DESIGN TEMP OF 0 DEGREES F AND LOWER
		1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE
		1	RTU TOTAL CFM MONITORING
		1	SINGLE POINT ELECTRICAL CONNECTION FOR RTU. 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #08, #47, "MA" OR "E2" PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE.
		1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
		1	LDW AMBIENT COOLING OPERATION - DOWN TO OF AMBIENT
		1	2" MERV 13 FILTERS FOR RTU3 (QTY. 4)
		1	2" MERV 8 FILTERS FOR RTU3 (QTY. 4)
		1	OVERHEAT STAT
		1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
		1	20 TON MODULATING COOLING OPTION, 208/230V. R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS
		1	20 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL
		1	REMOTE TEMPERATURE AND HUMIDITY SPACE SENSOR
		1	RTU3 CURB DUCT HANGER
		1	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS
		1	CONTROL PANEL ENCLOSURE HEATER 100W - RECOMMENDED FOR WINTER DESIGN TEMPERATURES LESS THAN 0°F
		1	OCCUPIED SCHEDULING
		1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI
		1	RTU3 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX
		1	RTU ECONOMIZER - DIFFERENTIAL ENTHALPY CONTROL
1	RTU3 ECONOMIZER BAROMETRIC RELIEF		
1	RTU3 HAIL GUARD		
1	RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI		
1	RTU3 DOWN RETURN		
1	VAV PACKAGE W/ MANUAL/DDC CONTROL (S71 VFD INCLUDED)		
1	LOAD REACTOR MOUNTED IN FAN		
1	RTU3 DOWN DISCHARGE, 400, 500 MBH		
1	ZIEHL POWERED EXHAUST FOR RTU3 - MANUAL CONTROL. 3000 CFM MAX AT 0"		
1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS)		

CURB ASSEMBLIES

NO	ON	FAN TAG	WEIGHT	ITEM	SIZE
1	# 1	RTU-1	154 LBS	CURB	59.500"W X 91.000"L X 26.000"H INSULATED.
2	# 2	RTU-2	154 LBS	CURB	59.500"W X 91.000"L X 26.000"H INSULATED.



REVISIONS

NO.	DESCRIPTION	DATE



Shake Shack-1474-Bloomingtondale, IL (HVAC)R3
 BLOOMINGDALE, IL, 60108

DATE: 8/17/2023
 DWG.#: 5723950
 DRAWN BY: Joe.shilka
 SCALE: 1/2" = 1'-0"
 MASTER DRAWING

SHEET NO. 1

NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

Bergmeyer
 LA
 BOS
 800 South Figueroa St.
 Los Angeles, CA 90017
 212.337.1090

CONSULTANTS:

SEAL SIGNATURE:
 FOR REFERENCE ONLY

1 HEI 2023-08-21 IFC SET
 C HEI 2023-06-09 ADDENDUM C
 B HEI 2023-04-26 ADDENDUM B
 A HEI 2023-02-08 ADDENDUM A
 HEI 2023-01-09 PERMIT/BD SET









SHAKE SHACK
 BLOOMINGDALE IL
 355 ARMY TRAIL ROAD,
 BLOOMINGDALE, IL 60108
 SHACK #1474

IFC SET


CAPTIVE AIRE DRAWINGS

DRAWN BY: Author
 CHECKED BY: Checker
 JOB NO: 20188.00

M707



REVISIONS	
NO.	DESCRIPTION



Shake Shack-1474-Bloomington, IL (HVAC)R3
BLOOMINGDALE, IL, 60108

FAN #1 CASRTU3-1,200-18-12.5T - HEATER (RTU-1)

- NOTES:
- DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
 - DENOTES CORNER WEIGHT.
 - ROOF OPENING MUST BE 2" SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.

NOTE:
THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

Bergmeyer
LA
800 South Figueroa St.
Los Angeles, CA 90017
617-542-1025
www.bergmeyer.com

CONSULTANTS:
SEAL SIGNATURE:
FOR REFERENCE ONLY

NO.	BY	DATE	DESCRIPTION
1	HEI	2023-08-21	IFC SET
C	HEI	2023-05-09	ADDENDUM C
B	HEI	2023-04-26	ADDENDUM B
A	HEI	2023-02-08	ADDENDUM A
HEI	2023-01-09	PERMIT/IBD SET	



SHAKE SHACK
BLOOMINGDALE IL









355 ARMY TRAIL ROAD,
BLOOMINGDALE, IL 60108
SHACK #1474

IFC SET

CAPTIVE AIRE DRAWINGS

DRAWN BY: Author
CHECKED BY: Checker
JOB NO: 20188.00

M708



REVISIONS	
NO.	DESCRIPTION

CAPTIVE
 Eastern PA Mechanical
 PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 504-4126 EMAIL: mg108@captivemechanical.com

Shake Shack-1474-Bloomington, IL (HVAC)R3
 BLOOMINGDALE, IL, 60108
 DATE: 8/17/2023
 DWG.#: 5723950
 DRAWN BY: Joe Shilka
 SCALE: 1/2" = 1'-0"
 MASTER DRAWING
 SHEET NO. 3


FAN #2 CASRTU3-I.400-24MF-20T - HEATER (RTU-2)
 NOTES:
 1. DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
 2. DENOTES CORNER WEIGHT.
 3. ROOF OPENING MUST BE 2' SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.

NOTE:
 THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

Bergmeyer
 LOS ANGELES
 800 South Figueroa St.
 Los Angeles, CA 90017
 213.337.1090
 www.bergmeyer.com

CONSULTANTS:
 SEAL SIGNATURE:
 FOR REFERENCE ONLY

NO.	BY	DATE	DESCRIPTION
1	HEI	2023-08-21	IFC SET
C	HEI	2023-05-09	ADDENDUM C
B	HEI	2023-04-26	ADDENDUM B
A	HEI	2023-02-08	ADDENDUM A
HEI		2023-01-09	PERMIT/IBD SET



SHAKE SHACK
 BLOOMINGDALE, IL

355 ARMY TRAIL ROAD,
 BLOOMINGDALE, IL 60108
 SHACK #1474

IFC SET

CAPTIVE AIRE DRAWINGS

DRAWN BY: Author
 CHECKED BY: Checker
 JOB NO: 20188.00

M709