

Summary

The purpose of this evaluation at Chili's in Orlando, FL was to address general issues within the HVAC system. When speaking with the manager upon arrival, they said they have had no complaints of discomfort or humidity within the building since the newer RTU's have been installed.

Upon initial inspection of the inside of the building, building pressure was slightly negative at $-0.0114''$ which is within tolerance of the IMC building pressure. Overall, building maintained temperature and humidity within tolerance to make building comfortable. On the roof, older units have some wear on them as well as several issues as shown on the remarks section of this report.

It is recommended to resolve all issues listed in the remarks section. After these issues are resolved a general balance should be done on the building to ensure positive pressure of the building and correct airflow on all units to make the building as comfortable as possible.