



20" x 28" SLEEVY DROP (300 CFM) FROM HVAC UNIT No. 1. PROVIDE SWEEP 90° AT BOTTOM OF AIR DUCT. TYPICAL OF BOTH UNITS.

PROVIDE REMOTE SIGNAL PANEL w/ AUDIOVISUAL ALARMS FOR HVAC UNITS. MOUNT @ 6'-6" AFF.

12" x 12" RETURN AIR DUCT. 750 CFM EA.

24" x 27" RETURN RISER (2250 CFM) FROM HVAC UNIT No. 2. PROVIDE DUCT SMOKE DETECTOR IN RETURN AIR DUCT. TYPICAL OF BOTH UNITS.

PROVIDE DIRECTIONAL VANES FOR AIRFLOW TO 22" MAIN DUCT.

12" x 12" RETURN AIR DUCT. 750 CFM EA.