



- ### CONSTRUCTION NOTES:
- M.E. CONTRACTOR (M.C.) SHALL INSTALL MANUAL FIRE PULL AT LOCATION SHOWN. ENSURE BETWEEN 10 AND 20 FEET FROM COOKING EQUIPMENT WHICH IT SERVES. SEE GENERAL NOTE #4/5 (FOR EASY IDENTIFICATION) THE FIRE PULL FOR CORRESPONDING HOODS #1, #2, #3, AND #7.
 - E.C. SHALL INSTALL THERMOSTATS WITH AUTOMATIC SUB-BASES FOR AUTOMATIC SWITCH-OVER BETWEEN COOLING MODES. MOUNT SENSORS @ 48" A.F.F. PROVIDE I-BOX AS REQUIRED. MASTER THERMOSTATS OFFICE WALL @48" A.F.F. AS SHOWN. E.C. SHALL LABEL EACH FOR EASY IDENTIFICATION. M.C. SHALL PROVIDE CONTROL WIRING AND TERMINATIONS. ALL THERMOSTAT FUNCTIONS SHALL BE SET TO AUTO.
 - M.C. SHALL INSTALL AIR CURTAIN, (3) TOTAL, ABOVE DOORS AS LOW AS POSSIBLE AT LOCATION SHOWN WITH ELECTRICAL CONTRACTOR AS REQUIRED.
 - ALL RTU'S SHALL BE PROVIDED WITH SMOKE DETECTORS IN THE SUPPLY AND/OR RETURN SIDE OF THE UNIT AS REQUIRED WITH LOCAL AUTHORITIES. ACCESS SHALL BE PROVIDED FOR INSPECTION AND MAINTENANCE.

LEGEND

- DIFFUSER SYMBOL
SEE SHEET M2 FOR SCHED.
- AIRFLOW (CFM)
- CEILING SUPPLY DIFFUSER
(DIFFUSER SHOWN IS A)
- WALL MOUNTED SUPPLY AIR REGISTER
- RIGID ROUND DUCT
- ROUND FLEX DUCT