



MOUNT AIR DOOR IN CEILING, CENTERED ON DOOR OPENING. AT 12" OFFWALL. PROVIDE WITH FACTORY MOUNTED DOOR SWITCH. MICROSWITCH IN DOOR FRAME ON STRIKE SIDE. SEE ARCHITECTURAL.

ELECTRIC HEATER, INC. TO MOUNT ON WALL PER MANUFACTURERS RECOMMENDATIONS.

MOUNT AIR DOOR IN CEILING, CENTERED ON DRIVE THRU DOOR OPENING AND 4" OFF THE WALL FOR INSTALLATION AND OPERATION. PROVIDE WITH FACTORY MOUNTED DOOR SWITCH AND AIR CURTAIN PROVIDED BY TOMBARROW COMPANY. REFER TO SHEET M-501 FOR AIR CURTAIN WIRING.

MOUNT AC#1 MAIN TRUNK LINE AS TIGHT AS POSSIBLE TO STRUCTURE.

SEAL DUCT PENETRATIONS IN DRAFT STOPPING CURTAIN AIR DRAFT STOPPING CURTAIN FOR DRAFT STOPPING CURTAIN.

CEILING MOUNTED CLEAN DUCT AND DISCHARGE TO TYPE A/DIFFUSER IN TEAM ROOM AS SHOWN.