

# MECHANICAL SHEET INDEX

M-001	MECHANICAL GENERAL INFORMATION
M-101	MECHANICAL FLOOR PLAN
M-150	MECHANICAL ROOF PLAN
M-501	MECHANICAL DETAILS
M-590	MECHANICAL SPECIFICATIONS
M-591	MECHANICAL SPECIFICATIONS
M-592	MECHANICAL SPECIFICATIONS
M-601	MECHANICAL SCHEDULES
M-630	MECHANICAL ENERGY CODE COMPLIANCE
M-701	CAPTIVEAIRE DRAWINGS
M-702	CAPTIVEAIRE DRAWINGS
M-703	CAPTIVEAIRE DRAWINGS
M-704	CAPTIVEAIRE DRAWINGS
M-705	CAPTIVEAIRE DRAWINGS
M-706	CAPTIVEAIRE DRAWINGS

## RESPONSIBILITY MATRIX

DESCRIPTION	FURNISHED		INSTALLED		REMARKS
	GC	OWNER	GC	OWNER	
<b>DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING</b>					
23.1 HVAC DUCTWORK AND PIPING IDENTIFICATION					
HVAC DUCTWORK SYSTEM IDENTIFICATION					
PIPING SYSTEM IDENTIFICATION					
UTILITY SHUT OFF IDENTIFICATION IN KITCHEN					
VALVE TAGS AND CHART					
HVAC DAMPER IDENTIFICATION					
23.2 ROOF CURBS					
EXHAUST FAN CURBS					
ROOFTOP UNIT CURBS					
CONDENSING UNIT CURBS					
KITCHEN EXHAUST FAN CURBS					
<b>23.3 HVAC DUCTWORK SYSTEM COMPONENTS</b>					
HVAC DUCTWORK					
GREASE DUCTWORK					
OUTSIDE AIR DUCTWORK					
SUPPLY AND RETURN AIR DUCTWORK					
RESTROOM EXHAUST AIR DUCTWORK					
INSULATION AND FIRE WRAP					
DAMPERS					
SMOKE DETECTORS					
SUPPLY, RETURN, AND EXHAUST GRILLS AND REGISTERS					
<b>23.4 MECHANICAL PIPING SYSTEM COMPONENTS</b>					
WALK-IN COOLER AND FREEZER CONDENSER REFRIGERANT LINE SETS					A
REFRIGERANT PIPING FOR HVAC EQUIPMENT					
VALVES AND ACCESSORIES (E.G. AIR VENTS)					
<b>23.5 HVAC EQUIPMENT</b>					
RESTROOM EXHAUST FAN					
KITCHEN EXHAUST FAN WITH CURB EXTENSION					
DUCTED AND NON-DUCTED HEATINGS AND COOLING UNITS					C
WALK-IN COOLER AND FREEZER CONDENSING UNITS					
<b>23.6 KITCHEN EXHAUST WITH FIRE SUPPRESSION SYSTEM</b>					
HOOD CONTROL PANEL					
REMOTE HOOD SWITCHES IN OFFICE					
KITCHEN EXHAUST HOOD					
STRUCTURAL SUPPORT					
ELECTRICAL AND CONTROL WIRING					
TANK SYSTEM					
TANK SYSTEM WIRING AND UTILITIES CONNECTION					B
TANK SYSTEM GAS VALVE					
PULL STATION					
<b>23.7 MECHANICAL SAFETY SENSORS</b>					
CO2 MONITOR					
<b>23.8 COMMISSIONING ACTIVITIES</b>					
GREASE EXHAUST WATER LEAKAGE TEST					
TEST AND BALANCE (TAB) REPORT					

GENERAL NOTES:  
 1. INFORMATION CONTAINED WITHIN IS BASED ON OUR INTERPRETATION OF THE FINAL EXECUTED WORK LETTER.  
 2. CONTRACTOR TO CONFIRM ALL SCOPE WITH FINAL WORK LETTER PRIOR TO PROCUREMENT OF EQUIPMENT.

REMARKS:  
 A. WALK-IN COOLER AND FREEZER CONDENSING UNITS FURNISHED AND INSTALLED BY OWNER VENDOR.  
 B. GENERAL CONTRACTOR TO COORDINATE TANK INSTALLATION TIME WITH OWNER VENDOR AND FACILITATE SYSTEM SIGN-OFF.  
 C. ROOFTOP UNITS ARE EXISTING TO REMAIN AND PROVIDED UNDER THE SHELL BUILDING PERMIT.

## SUBMITTAL MATRIX

Required Review Time (Business Days)	Architect of Record	Shake Shack	Physical Sample Required	Submit for Record	Submit for Record Only
5	X			X	
5	X			X	
5	X			X	
5	X			X	

GENERAL CONTRACTORS TO ALSO REVIEW ARCHITECTURAL SPECIFICATIONS AS NOTED IN PLANS IN PLAN SECTION 700 OF THE ARCHITECTURAL PACKAGE FOR REQUIRED SUBMITTALS THAT MIGHT NOT BE LISTED BELOW.

**SUBMITTAL DESCRIPTION**  
 Diffusers, Grills & Registers  
 Ductwork Layout (if there are significant changes in field)  
 HVAC Equipment (if Captive Aire - Submitted by Owner Vendor directly to Owner/AOR prior to construction)  
 MEP Tests, Start-Up, and Programming Reports

## GENERAL NOTES:


- PRIOR TO SUBMITTING BID, VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH THE EXISTING CONDITIONS OF THE PROJECT. REVIEW THE GENERAL NOTES, SPECIFICATIONS AND OTHER DRAWINGS FOR ADDITIONAL REQUIREMENTS WHICH MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY ARCHITECT, ENGINEER AND/OR OWNER OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
- PROVIDE SEISMIC RESTRAINTS AS NEEDED FOR THE MECHANICAL SYSTEMS IN THE PROJECT BASED ON THE SEISMIC ANALYSIS REQUIRED BY THE SPECIFICATIONS.
- EXISTING CONDITIONS WERE TAKEN FROM ORIGINAL DRAWINGS AND SITE VISITS AND MAY NOT REFLECT EXACT "AS-BUILT" CONDITIONS. FIELD VERIFY EXISTING CONDITIONS PRIOR TO SUBMITTING FINAL BIDS. COORDINATE NEW WORK AND DEMOLITION WITH OTHER DISCIPLINES AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION.
- COORDINATE THE INSTALLATION OF THE MECHANICAL SYSTEMS WITH OTHER TRADES TO ENSURE A NEAT AND ORDERLY INSTALLATION. INSTALL DUCTWORK AND PIPING AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS. COORDINATE INSTALLATION OF DUCTWORK AND PIPING TO AVOID CONFLICTS WITH ELECTRICAL PANELS, LIGHTING FIXTURES, ETC. ANY MODIFICATIONS REQUIRED DUE TO LACK OF COORDINATION WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AT NO EXTRA COST TO THE OWNER.
- WHERE SHUTDOWN OF EXISTING SYSTEMS IS REQUIRED DURING NEW WORK, COORDINATE SHUTDOWN TIME AND DURATION WITH THE OWNER TO MINIMIZE DOWNTIME. NOTIFY OWNER SEVEN (7) DAYS PRIOR TO INTERRUPTION OF SERVICE.
- DURING INSTALLATION OF NEW WORK, AVOID DAMAGING EXISTING SURFACES AND EQUIPMENT TO REMAIN. REPAIR DAMAGE CAUSED DURING CONSTRUCTION AT NO EXTRA COST TO THE OWNER.
- PROVIDE TEMPORARY BARRIERS TO CONTAIN DUST AND DEBRIS RESULTING FROM THE PERFORMANCE OF THE WORK TO THE AREA WHERE WORK IS BEING PERFORMED.
- ALL MECHANICAL EQUIPMENT SHOWN ON THE MECHANICAL PLANS SHALL BE PROVIDED BY DIVISION 23 UNLESS OTHERWISE NOTED.
- NEW MECHANICAL EQUIPMENT, DUCTWORK AND PIPING ARE SHOWN AT APPROXIMATE LOCATIONS. FIELD MEASURE FINAL DUCTWORK AND PIPING LOCATIONS PRIOR TO FABRICATION AND MAKE ADJUSTMENTS AS REQUIRED TO FIT THE DUCTWORK AND PIPING WITHIN THE AVAILABLE SPACE. VERIFY THAT FINAL EQUIPMENT LOCATIONS MEET MANUFACTURER'S RECOMMENDATIONS REGARDING SERVICE CLEARANCE AND PROPER AIRFLOW CLEARANCE AROUND EQUIPMENT.
- REFER TO ARCHITECTURAL DRAWINGS FOR RELATED CONSTRUCTION DETAILS AS APPLICABLE TO THE HVAC SYSTEM. VERIFY CHASES AND PENETRATIONS SHOWN ON ARCHITECTURAL DRAWINGS THAT ARE INTENDED FOR DUCTWORK AND PIPING MEET REQUIREMENTS.
- COORDINATE LOCATION OF ROOF MOUNTED HVAC EQUIPMENT AND ROOF PENETRATIONS WITH THE ARCHITECTURAL AND STRUCTURAL DRAWINGS.
- INDOOR AIR QUALITY MEASURES: PROTECT INSIDE OF (INSTALLED AND DELIVERED) DUCTWORK AND HVAC UNITS FROM EXPOSURE TO DUST, DIRT, PAINT AND MOISTURE. REPLACE INSULATION THAT HAS BECOME WET AT ANY TIME DURING CONSTRUCTION. DRYING THE INSULATION IS NOT ACCEPTABLE. SEAL ANY TEARS OR JOINTS OF INTERNAL FIBERGLASS INSULATION. REMOVE DEBRIS FROM CEILING/RETURN AIR PLENUM INCLUDING DUST. AN INDEPENDENT, PROFESSIONAL DUCT CLEANING COMPANY SHALL VACUUM CLEAN ANY DUCTWORK CONNECTED TO HVAC UNITS THAT WERE OPERATED DURING THE CONSTRUCTION PERIOD AFTER ALL FILTERS ARE INSTALLED AND PRIOR TO TURNING SYSTEM OVER TO THE OWNER. THE INTERNAL SURFACES AND ASSOCIATED COILS OF ANY HVAC UNITS THAT WERE OPERATED SHALL ALSO BE CLEANED.
- INSTALL DUCTWORK AND PIPING PARALLEL TO BUILDING COLUMN LINES UNLESS OTHERWISE SHOWN OR NOTED.
- OVERHEAD HANGERS AND SUPPORTS FOR EQUIPMENT, DUCTWORK AND PIPING SHALL BE FASTENED TO BUILDING JOISTS OR BEAMS. DO NOT ATTACH HANGERS AND SUPPORTS TO THE ABOVE FLOOR SLAB OR ROOF EXCEPT WHERE CONCRETE INSERTS IN CONCRETE SLABS ARE ALLOWED BY THE SPECIFICATIONS.
- COORDINATE LOCATION OF EQUIPMENT SUPPORTS WITH LOCATION OF EQUIPMENT ACCESS PANELS/DOORS TO ENABLE SERVICE OF EQUIPMENT AND/OR FILTER REPLACEMENT.
- SEAL PENETRATIONS THROUGH THE BUILDING COMPONENTS IN ACCORDANCE WITH THE CONTRACT SPECIFICATIONS. FIREPROOF PENETRATIONS THROUGH FIRE RATED COMPONENTS IN ACCORDANCE WITH U.L. REQUIREMENTS.
- COORDINATE THE EXACT MOUNTING SIZE AND FRAME TYPE OF DIFFUSERS, REGISTERS AND GRILLES WITH THE SUPPLIER TO MEET THE CEILING, WALL AND DUCT INSTALLATION REQUIREMENTS.
- ADJUST LOCATION OF CEILING DIFFUSERS, REGISTERS AND GRILLES AS REQUIRED TO ACCOMMODATE FINAL CEILING GRID AND LIGHTING LOCATIONS.
- PAINT PORTIONS OF DUCTWORK AND INSULATION THAT ARE EXPOSED TO VIEW BY THE INSTALLATION OF DIFFUSERS, REGISTERS, AND GRILLES IN CEILINGS OR WALLS FLAT BLACK. PORTIONS INCLUDE BOTH THE INTERIOR OF UNLINED DUCTWORK AND THE EXTERIOR OF DUCTWORK AND INSULATION.
- DUCTWORK CROSSING FIRE RATED WALLS OR OTHER FIRE RATED ASSEMBLIES SHALL BE MINIMUM 26 GAUGE SHEET METAL.
- PROVIDE FIRE OR FIRE/SMOKE DAMPERS, AS APPLICABLE, IN DUCTWORK AT CEILINGS AND WALLS AT LOCATIONS SHOWN ON THE PLANS. FIRE AND FIRE/SMOKE DAMPERS SHALL CONFORM TO NFPA AS APPLICABLE. COORDINATE SLEEVE LENGTH WITH REQUIREMENTS OF INSTALLED LOCATION.
- PROVIDE WALL OR DUCT ACCESS PANELS OR DOORS FOR ACCESS TO FIRE AND FIRE/SMOKE DAMPERS. ACCESS PANEL OR DOOR SHALL BE MINIMUM SIZE OF 10" BY 10" AND SHALL BE INSTALLED WITHIN 12" OF DAMPER. PROVIDE A REMOVABLE DUCT SECTION WHERE DUCT SIZE IS TOO SMALL FOR A 10" BY 10" ACCESS DOOR.
- LOCATE AND SET THERMOSTATS AND HUMIDISTATS AT LOCATIONS SHOWN ON PLANS. VERIFY EXACT LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION. DEVICE MOUNTING HEIGHT SHALL MEET ADA REQUIREMENTS UNLESS OTHERWISE NOTED ON PLANS. PROVIDE INSULATED BACKING FOR THERMOSTATS MOUNTED ON EXTERIOR BUILDING WALLS. INSTALL THERMOSTAT CONDUIT PROVIDED BY DIVISION 26. AT A MINIMUM, PROVIDE CONDUIT IN THE WALL FROM THE JUNCTION BOX TO 6" ABOVE THE CEILING.
- COORDINATE THE LOCATION AND ELEVATION OF WALL-MOUNTED DEVICES WITH PRESENTATION BOARDS, DISPLAY CABINETS, SHELVES OR OTHER COMPONENTS SHOWN ON THE ARCHITECTURAL DRAWINGS THAT ARE TO BE INSTALLED UNDER OTHER DIVISIONS. CONTRACTOR WILL NOT BE REIMBURSED FOR RELOCATION OF WALL-MOUNTED DEVICES CAUSED BY A LACK OF COORDINATION.
- PROVIDE A MANUAL BALANCING DAMPER IN EACH DUCT TAKEOFF FROM SUPPLY, RETURN, OUTDOOR AND EXHAUST AIR DUCTS.
- PROVIDE A PREFABRICATED 45 DEGREE, HIGH EFFICIENCY, RECTANGULAR/ROUND BRANCH DUCT TAKEOFF FITTING FOR BRANCH DUCT CONNECTIONS AND TAKE-OFFS TO INDIVIDUAL DIFFUSERS, REGISTERS AND GRILLES. PROVIDE WITH INTEGRAL MANUAL BALANCING DAMPER AND LOCKING QUADRANT WHERE INDICATED ON PLANS.
- BRANCH DUCTWORK TO AIR OUTLETS SHALL BE SAME SIZE AS OUTLET NECK SIZE UNLESS OTHERWISE NOTED.
- REFER TO SPECIFICATIONS FOR DUCTWORK AND PIPING INSULATION REQUIREMENTS. DUCT SIZES ON MECHANICAL PLANS INDICATE CLEAR INSIDE AIRFLOW DIMENSIONS. INCREASE SHEET METAL SIZES ACCORDINGLY TO ACCOUNT FOR THICKNESS OF DUCT LINER.
- FLEXIBLE DUCTWORK SHALL NOT EXCEED 5'-0" IN LENGTH AND SHALL BE INSTALLED AND SUPPORTED TO AVOID SHARP BENDS AND SAGGING. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- PROVIDE EQUIPMENT VENTS AND FLUES PER EQUIPMENT MANUFACTURERS RECOMMENDATIONS AND EQUIPMENT SPECIFICATIONS. KEEP PENETRATIONS THROUGH ROOF A MINIMUM OF 10'-0" FROM HVAC EQUIPMENT FRESH AIR INLETS AND 2'-0" FROM ROOF PARAPETS.
- PROVIDE A NEW SET OF AIR FILTERS IN UNITS PRIOR TO TESTING, ADJUSTING AND BALANCING AND BEFORE TURNING SYSTEM(S) OVER TO OWNER.
- FULLY CHARGE EXISTING REFRIGERANT SYSTEMS BEING REUSED FOR THIS PROJECT IN ACCORDANCE WITH MANUFACTURER'S WRITTEN INSTRUCTIONS. CHARGE SYSTEMS WITH NEW REFRIGERANT MATCHING EXISTING.
- TEMPORARY INSTALLATIONS OF INFECTION CONTROL MEASURES DURING CONSTRUCTION SHALL BE COORDINATED WITH THE FACILITY'S INFECTION CONTROL STAFF. PRIOR TO CONSTRUCTION PROVIDE ALL REQUIRED TEMPORARY INSTALLATIONS, INCLUDING DETAILS OF THE INFECTION CONTROL MEASURES SUCH AS TEMPORARY BARRIERS AND MEMBRANES, PORTABLE EXHAUST FANS AND TEMPORARY DUCTWORK. TEMPORARY INSTALLATIONS MUST NOT HAVE A NEGATIVE IMPACT ON EXISTING SYSTEMS NOR CAUSE UNSAFE CONDITIONS. TEMPORARY INSTALLATIONS SHALL MAINTAIN ADEQUATE EGRESS AND SHALL NOT OBSTRUCT EXISTING EXITS. CREATE A FIRE HAZARD OR REDUCE REQUIRED FIRE RESISTANCE. TEMPORARY VENTILATION SYSTEMS SHALL NOT CAUSE THE AIR BALANCE OF ADJACENT ROOMS OR SPACES TO BE IMPACTED OR ALTER THE PERFORMANCE OF PERMANENT BUILDING VENTILATION SYSTEMS. AIRFLOW MEASUREMENTS SHALL BE TAKEN TO VERIFY ADJACENT ROOMS OR SPACES ARE NOT IMPACTED.

# MECHANICAL SYMBOLS

STANDARD MOUNTING HEIGHT		HVAC DUCTWORK AND ACCESSORIES		PIPING SYMBOLS		
<p>THERMOSTATS (USER ADJUSTABLE) (TOP OF DEVICE)</p> <p>46" 46"</p>		<p>DUCTWORK/EQUIPMENT TO BE REMOVED OR RELOCATED</p>		<p>DIRECTION OF FLOW</p>		
<p>INSTALL DEVICES AT THE MOUNTING HEIGHTS SHOWN ABOVE UNLESS IN THE CONSTRUCTION DOCUMENTS. MOUNTING HEIGHTS LISTED ABOVE OR ELSEWHERE IN THE CONSTRUCTION DOCUMENTS ARE AFF OR AG TO TOP OF THE DEVICE UNLESS NOTED OTHERWISE. ALL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH CURRENT ADA AND LOCAL REQUIREMENTS.</p>	<p>EXISTING DUCTWORK/EQUIPMENT TO REMAIN</p>	<p>LINEAR SLOTT DIFFUSER</p>		<p>CONTROL VALVE</p>		
<p>ANNOTATION</p>	<p>MECHANICAL PLAN NOTE CALLOUT</p>	<p>INSULATED FLEXIBLE DUCT (MAX. 5'-0" LONG)</p>		<p>THREE-WAY CONTROL VALVE</p>		
<p>MECHANICAL EQUIPMENT DESIGNATION (CONTRACTOR FURNISHED AND INSTALLED UNLESS NOTED OTHERWISE)</p>	<p>CONNECTION POINT OF NEW WORK TO EXISTING</p>	<p>BRANCH DUCT WITH 45° RECTANGLE-ROUND BRANCH FITTING AND MANUAL VOLUME DAMPER</p>		<p>SHUTOFF VALVE</p>		
<p>DETAIL REFERENCE. UPPER NUMBER INDICATES DETAIL NUMBER LOWER NUMBER INDICATES SHEET NUMBER</p>	<p>SECTION CUT DESIGNATION</p>	<p>ELBOW WITH TURNING VANES</p>		<p>CHECK VALVE</p>		
<p>DEDICATED FLOOR ACCESS TILE</p>	<p>ACCESS PANEL</p>	<p>BRANCH DUCT WITH BELL-MOUTH FITTING &amp; MANUAL VOLUME CONTROL DAMPER</p>		<p>BALANCING VALVE WITH PRESSURE PORTS</p>		
<p>ABBREVIATIONS</p>	<p>A/C AIR CONDITIONING</p> <p>ACC AIR COOLED CHILLER</p> <p>ACCU AIR COOLED CONDENSING UNIT</p> <p>AFC ABOVE FINISHED CEILING</p> <p>AFB ABOVE FINISHED FLOOR</p> <p>AFG ABOVE FINISHED GRADE</p> <p>AHJ AUTHORITY HAVING JURISDICTION</p> <p>AHU AIR HANDLING UNIT</p> <p>AI ANALOG INPUT</p> <p>AO ANALOG OUTPUT</p> <p>AP ACCESS PANEL</p> <p>APD AIR PRESSURE DROP</p> <p>AWG AMERICAN WIRE GAUGE</p> <p>B BOLLER</p> <p>BAS BUILDING AUTOMATION SYSTEM</p> <p>BB BACKBONE</p> <p>BD BACKDRAFT DAMPER</p> <p>BD BLOWDOWN</p> <p>BFC BELOW FINISHED CEILING</p> <p>BFF BELOW FINISHED FLOOR</p> <p>BFG BELOW FINISHED GRADE</p> <p>BFP BOLLER FEED PUMP</p> <p>BHP BRAKE HORSEPOWER</p> <p>BI BINARY INPUT</p> <p>BO BINARY OUTPUT</p> <p>BOD BOTTOM OF DUCT</p> <p>BOS BOTTOM OF STRUCTURE</p> <p>BTU BRITISH THERMAL UNIT</p> <p>CFM CUBIC FEET PER MINUTE</p> <p>CH CHILLER</p> <p>CLG COOLING</p> <p>CP CONDENSATE PUMP</p> <p>CRAC CONTROL POWER TRANSFORMER</p> <p>CRU COMPUTER ROOM AIR CONDITIONING UNIT</p> <p>CT COOLING TOWER</p> <p>CV CONTROL VALVE</p> <p>CWP CONDENSER</p> <p>DB WATER PUMP</p> <p>DBA DECIBEL AVERAGE</p> <p>DDC DIRECT DIGITAL CONTROL</p> <p>DI DIGITAL INPUT</p> <p>DISC DISCONNECT</p> <p>DN DOWN</p> <p>DS DUCT SILENCER</p> <p>DX DIRECT EXPANSION</p> <p>(E) EXISTING</p> <p>EA EXHAUST AIR</p> <p>EAT ENTERING</p> <p>EA AIR TEMPERATURE</p> <p>EDB EXHAUST DUCT</p> <p>EDD ENTERING DRY BULB</p> <p>EF EXHAUST FAN</p> <p>EFF EFFICIENCY</p> <p>EMS ENERGY MANAGEMENT SYSTEM</p> <p>ESP EXTERNAL STATIC PRESSURE</p> <p>ETR EXISTING TO REMAIN</p> <p>EWB ENTERING WET BULB</p> <p>EWV ENTERING WATER TEMPERATURE</p> <p>FCU FAN COIL UNIT</p> <p>FCA FROM FLOOR ABOVE</p> <p>FFB FROM FLOOR BELOW</p> <p>FF FINISHED FLOOR</p> <p>FFI FINS PER INCH</p> <p>FFM FEET PER MINUTE</p> <p>GC GENERAL CONTRACTOR</p> <p>GEA GREASE EXHAUST AIR</p> <p>GPM GALLONS PER MINUTE</p> <p>HDA HAND-OFF-AUTOMATIC</p> <p>HP HORSEPOWER</p> <p>HTG HEATING</p> <p>HWP HEATING WATER PUMP</p> <p>IN WC INCHES OF WATER COLUMN</p> <p>L LOUVER</p> <p>LAT LEAVING AIR TEMPERATURE</p> <p>LDB LEAVING DRY BULB</p> <p>LFP LOW PRESSURE</p> <p>LWB LEAVING WET BULB</p> <p>LWT LEAVING WATER TEMPERATURE</p> <p>MAU MAKE-UP AIR UNIT</p> <p>MAX MAXIMUM</p> <p>MIN MINIMUM</p> <p>MFR MOTORIZED DAMPER</p> <p>MN MANUFACTURER</p> <p>N/A NOT APPLICABLE</p> <p>NIC NORMALLY CLOSED</p> <p>NO NORMALLY OPEN</p> <p>NOM NOMINAL</p> <p>NC NOISE CRITERIA</p> <p>NF NOT IN CONTRACT</p> <p>OA OUTSIDE AIR</p> <p>OD OUTSIDE AIR PRESSURE INDEP. CONTROL VALVE</p> <p>OD QTY PROVIDE FURNISH AND INSTALL</p> <p>RA RETURN AIR</p> <p>RC ROOM CRITERIA</p> <p>RD REFRIGERANT DUCT</p> <p>REA RELIEF AIR</p> <p>RF RETURN FAN</p> <p>RFR REFRIGERANT</p> <p>RH RELATIVE HUMIDITY</p> <p>RH ROOF HOOD</p> <p>RPM REVOLUTIONS PER MINUTE</p> <p>RTU ROOFTOP UNIT</p> <p>SA SUPPLY AIR</p> <p>SCP STEAM CONDENSATE PUMP</p> <p>SD SMOKE DUCT DETECTOR</p> <p>SD SUPPLY DUCT</p> <p>SF SUPPLY FAN</p> <p>SF SENSIBLE HEAT CAPACITY</p> <p>SOW SCOPE OF WORK</p> <p>SP STATIC PRESSURE</p> <p>ST STEAM TRAP</p> <p>STM STEAM</p> <p>TBD TO BE DETERMINED</p> <p>TCIC TEMPERATURE CONTROLS CONTRACTOR</p> <p>TCP TEMPERATURE CONTROL PANEL</p> <p>TF TRANSFER FAN</p> <p>TFA TO FLOOR ABOVE</p> <p>TFB TO FLOOR BELOW</p> <p>TH TOTAL HEAT CAPACITY</p> <p>TSP TOTAL STATIC PRESSURE</p> <p>TT TEMPERATURE TRANSMITTAL</p> <p>U/F UNDERFLOOR</p> <p>UG UNDERGROUND</p> <p>US UNDERSLAB</p> <p>UH UNIT HEATER</p> <p>UNO UNLESS NOTED OTHERWISE</p> <p>VAV VARIABLE AIR FLOW</p> <p>VEL VELOCITY</p> <p>VFD VARIABLE FREQUENCY DRIVE</p> <p>VRF VARIABLE REFRIGERANT FLOW</p> <p>VRV VARIABLE REFRIGERANT VOLUME</p> <p>W WITH</p> <p>WO WITHOUT</p> <p>WB WET BULB</p> <p>WC WATER COLUMN</p> <p>WPD WATER PRESSURE DROP</p> <p>XP EXPLOSION PROOF</p>	<p>24x24 (NECK SIZE) CG-1 (TYPE) 800 CFM (CFM OF EXHAUST GRILLE)</p>	<p>EQUIPMENT ACCESS TILE (IN ACT CEILINGS)</p>	<p>ACCESS PANEL (IN GYPSUM)</p>	<p>MANUAL VOLUME DAMPER</p>	<p>SQUARE TO ROUND TRANSITION</p>
<p>24x24 (NECK SIZE) CG-1 (TYPE) 800 CFM (CFM OF EXHAUST GRILLE)</p>	<p>EQUIPMENT ACCESS TILE (IN ACT CEILINGS)</p>	<p>ACCESS PANEL (IN GYPSUM)</p>	<p>MANUAL VOLUME DAMPER</p>	<p>SQUARE TO ROUND TRANSITION</p>	<p>DUCT MOUNTED SMOKE DETECTOR (SD=SUPPLY/RD=RETURN)</p>	
<p>XX" Ø</p>	<p>ROUND DUCT TAG INDICATING DIAMETER</p>	<p>XX" x XX"</p>	<p>RECTANGULAR DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS</p>	<p>XX" x XX" Ø</p>	<p>FLAT OVAL DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS</p>	
<p>FD</p>	<p>FIRE DAMPER</p>	<p>FSN</p>	<p>FIRE SMOKE DAMPER</p>	<p>SD</p>	<p>SMOKE DAMPER</p>	
<p>VD</p>	<p>VOLUME DAMPER</p>	<p>MD</p>	<p>MOTORIZED DAMPER</p>	<p>BD</p>	<p>BACKDRAFT DAMPER</p>	
<p>ALL DUCT DIMENSIONS SHOWN ON DRAWINGS ARE INSIDE DIMENSIONS. REFER TO DUCTWORK SPECIFICATIONS FOR DUCTWORK INSULATION AND LINER INFORMATION.</p>	<p>HVAC CONTROL DEVICES</p>	<p>Humidistat</p> <p>Thermostat</p> <p>Carbon Monoxide Sensor</p> <p>Carbon Dioxide Sensor</p> <p>Differential Pressure Sensor</p> <p>Flow Switch</p> <p>Humidity Sensor</p> <p>Pull Station</p> <p>Remote Testing Station with Indicating Light</p> <p>Static Pressure</p> <p>Temperature Sensor</p>	<p>EXISTING PIPING TO BE REMOVED OR RELOCATED</p> <p>EXISTING PIPING TO REMAIN</p> <p>CONDENSATE DRAIN (CD)</p> <p>HEATING HOT WATER SUPPLY (HWS)</p> <p>HEATING HOT WATER RETURN (HWR)</p> <p>CHILLED WATER SUPPLY (CHWS)</p> <p>CHILLED WATER RETURN (CHWR)</p> <p>HOT / CHILLED WATER SUPPLY (HCS)</p> <p>HOT / CHILLED WATER RETURN (HCR)</p> <p>CONDENSER WATER SUPPLY (CWS)</p> <p>CONDENSER WATER RETURN (CWR)</p> <p>REFRIGERANT LIQUID (RL)</p> <p>REFRIGERANT DISCHARGE (HOT GAS) (RD)</p> <p>REFRIGERANT SUCTION (RS)</p> <p>REFRIGERANT DISCHARGE BYPASS (RDB)</p> <p>REFRIGERANT VENT (RV)</p>			




CONSULTANTS:  
**HNY**  
 CONSULTING ENGINEERS  
 240 WEST 37TH STREET, 3RD FLOOR  
 NEW YORK, NY 10018  
 Tel: 212 413 8400  
 www.hny.com  
 245002084  
 NC CORPORATE NO. P-2461  
 EXPRES 6/30/2026



10/13/2025

SEALED SIGNATURE:  
 JOSHUA N. HOVER

NO.	BY	DATE	DESCRIPTION
1	HNY	2025-10-13	IFC SET
A	HNY	2025-04-15	ADDENDUM A
HNY	2025-02-03	PERMIT SET	
HNY	2025-01-13	75% SET	



SHAKE SHACK CONCORD MILLS

8031 CONCORD MILLS BLVD  
 CONCORD, NC 28027, SUITE 103  
 SHACK #1630

IFC SET

MECHANICAL GENERAL INFORMATION

DRAWN BY: Author  
 CHECKED BY: Checker  
 JOB NO: 2024032.00

M-001


- MECHANICAL GENERAL NOTES:**
- DO NOT ROUTE ANY DUCTWORK OR PIPING ABOVE ELECTRICAL PANELS.
  - REFER TO SHEET M-101 FOR ADDITIONAL GENERAL NOTES AND REQUIREMENTS.
  - REFER TO DETAILS AND SCHEDULES SHEETS FOR FURTHER INFORMATION.
  - MOUNT ALL THERMOSTATS AND SENSORS CONTROLLING HVAC EQUIPMENT AT 48" AFF UNLESS OTHERWISE NOTED.

**MECHANICAL PLAN NOTES:**

- MD01 MOUNT THERMOSTATS, HUMIDITY SENSORS, AND TEMPERATURE SENSOR(S) ON WALL. THERMOSTATS AND SENSOR(S) SHALL BE LABELED TO MATCH THE UNIT TAG AND CORRESPOND TO THE ELECTRICAL LEGEND IN THE ELECTRICAL PANELBOARD SERVING THE EQUIPMENT. COORDINATE COLOR WITH ARCHITECT.
- MD02 COMBINATION TEMPERATURE SENSOR AND HUMIDITY SENSOR.
- MD03 MOUNT TEMPERATURE SENSOR PROVIDED WITH KITCHEN EXHAUST HOODS ON WALL.
- MD04 INSTALL HOOD FIRE SUPPRESSION MANUAL PULL STATION. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH FIRE SUPPRESSION SYSTEM INSTALLER AND THE AUTHORITY HAVING JURISDICTION.
- MD05 CARBON DIOXIDE SENSOR WITH REMOTE ALARM REPEATER FURNISHED BY OWNER'S CO2 VENDOR AND LOCATED AT 12" AFF. THE SENSOR SHALL BE EQUIPPED WITH A LOCAL AUDIBLE AND VISUAL ALARM. THE LOW-LEVEL ALARM SHALL ACTIVATE THE LOCAL AUDIBLE AND VISUAL ALARM. IF THE BUILDING HAS A FIRE ALARM, PROVIDE THE APPROPRIATE FIRE ALARM INTERFACE MODULE TO INTERLOCK WITH THE BUILDING FIRE ALARM SYSTEM. THE HIGH-LEVEL CO2 ALARM SHALL SIGNAL BUILDING FIRE ALARM WHEN EQUIPPED. LOW LEVEL ALARM - 0.5% = 5,000 PPM. HIGH LEVEL ALARM - 3.0% = 30,000 PPM.
- MD07 INSTALL DUCT SMOKE DETECTOR IN RETURN AIR PLENUM.
- MD08 INSTALL EMERGENCY ALARM IN MANAGER'S OFFICE TO INDICATE CARBON MONOXIDE AND CARBON DIOXIDE DETECTION IN MECHANICAL ROOM. PROVIDE LIGHT IN OFFICE WITH TAG FOR EACH ALARM.
- ME01 PROVIDE COMBUSTION AIR AND EXHAUST PIPE AND ROUTE TO CONCENTRIC VENT THROUGH ROOF.
- MH01 TYPE I GREASE HOOD EXHAUST DUCTWORK SHALL BE MINIMUM 18 GAUGE STEEL OR MINIMUM 18 GAUGE STAINLESS STEEL WITH LIQUID TIGHT WELDS.
- MH03 INSTALL ACCESS PANELS FOR CLEANING AS REQUIRED BY NFPA 96 AND LOCAL CODES. TRANSITION GREASE DUCTWORK AS REQUIRED TO HOOD AND FAN CONNECTIONS. PROVIDE 45° MAX OFFSETS AS REQUIRED TO COORDINATE WITH STRUCTURE. PROVIDE RADIUS ELBOWS WITHOUT TURNING VANES. SLOPE HORIZONTAL GREASE DUCT BACK TOWARDS HOOD AT MINIMUM OF 1/4" PER LINEAL FOOT. GREASE DUCTS SHALL BE CONTAINED IN A UL APPROVED GREASE DUCT WRAP SYSTEM.

**MECHANICAL PLAN NOTES:**

- MH04 INSTALL "DUCTMATE ULTIMATE DOORS" ON GREASE DUCT FOR CLEANING IN LOCATION(S) SHOWN AT A MINIMUM AND AS REQUIRED BY NFPA 96.
- MH05 TYPE I HOODS SHALL BE FURNISHED COMPLETE WITH INTERNALLY PIPED FIRE SUPPRESSION SYSTEM AND EXTERNAL FOAM SUPPLY BOTTLES WITH REMOTE PULL CONTROLS AND IN COMPLIANCE WITH NFPA 96. DIVISION 23 SHALL COORDINATE COMPLETE INSTALLATION WITH FIRE PROTECTION CONTRACTOR TO MEET APPROVAL OF LOCAL INSPECTOR AND CODE COMPLIANCE INCLUDING TESTING. HOOD SHALL OVERHANG THE COOKING SURFACE BY AT LEAST 6" ON BOTH SIDES.
- MH01 PROVIDE SA DUCT THROUGH ROOF, FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.
- MH02 PROVIDE RA DUCT THROUGH ROOF, FULL SIZE OF UNIT OPENING, AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.
- MH03 PROVIDE EA DUCT THROUGH ROOF, TRANSITION TO EXHAUST FAN INLET SIZE WITHIN CURB.
- MH08 ROUTE DUCTWORK LEVEL, TIGHT TO STRUCTURE, AND ABOVE LIGHTS. COORDINATE WITH STORM DRAINAGE, STRUCTURAL, AND ELECTRICAL.
- MH16 TRANSITION 6" OUTDOOR AIR DUCT TO 4" FLEXIBLE DUCTWORK AND CONNECT TO UNIT.
- MO01 CONTRACTOR TO COORDINATE 1" UNDERCUT ON DOOR FOR EXHAUST AIR PATH.
- MO02 AIR CURTAIN MOUNTED ABOVE DOOR. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
- MO03 PROVIDE 1/4" GALVANIZED CONSTRUCTION HARDWARE CLOTH SCREEN OVER OPEN END OF RETURN DUCT. PROVIDE DUCT LINER IN BOOT. RETURN AIR DUCT SHALL BE MINIMUM 36" HORIZONTAL EXTENSION FOR SOUND ATTENUATION.
- MO06 ROUTE DUCTWORK BELOW SHED ROOF TO MECHANICAL EQUIPMENT OR AIR DEVICE.



1 MECHANICAL FLOOR PLAN  
1/4" = 1'-0"

THE BUILDINGS HVAC SYSTEMS SHALL BE BALANCED BY NATIONAL TAB (NO EXCEPTIONS) AND CONTRACTED BY THE GENERAL CONTRACTOR.

CONTACT:  
WILL TURNBOUGH  
will@natortab.com  
855-682-6822 ext704

ALL GREASE DUCT TO BE WATER TESTED BY ENVIROMATIC AT MECHANICAL CONTRACTOR'S EXPENSE. CONTACT OWNER'S NATIONAL ACCOUNT VENDOR:

ENVIROMATIC  
DON PFLEDERER  
1.800.325.8476  
inspections@enviromatic.com

**Bergmeyer**

800 South Figueroa St.  
Los Angeles, CA 90017  
213.337.1090

875 N High St.  
Columbus, OH 43215  
380.900.8887

Shepley St.  
Boston, MA 02210  
617.542.1025

CONSULTANTS:

**HNY**  
CONSULTING  
ENGINEERS

240 WEST 37TH STREET, 3RD FLOOR  
NEW YORK, NY 10018  
TEL: 212.413.8400  
www.hny.com

245002084  
NC CORPORATE NO. P-2451  
EXPIRES 6/30/2026

SEAL SIGNATURE:

**KORIN CAROLINE**  
PROFESSIONAL  
ENGINEER  
SEAL  
046826  
KORIN CAROLINE  
N. H. C.E.

10/13/2025

NO.	BY	DATE	DESCRIPTION
1	HNY	2025-10-13	IFC SET
A	HNY	2025-04-15	ADDENDUM A
HNY	2025-02-03	PERMIT SET	
HNY	2025-01-13	75% SET	

**SHAKE SHACK**

SHAKE SHACK CONCORD MILLS

8031 CONCORD MILLS BLVD  
CONCORD, NC 28027, SUITE 103  
SHACK #1630

IFC SET

MECHANICAL FLOOR PLAN

DRAWN BY: Author  
CHECKED BY: Checker  
JOB NO: 20240321.00


M-101

10/13/2025 11:52:03 AM Autodesk Docs/20240321.00\_Shake\_Shack\_Concord Mills\_NCS34565020204\_MEPF\_20.rvt

JOSHUA N. HOVER

**MECHANICAL PLAN NOTES:**

- ME02 PROVIDE CONCENTRIC VENT MODEL NUMBER PVC-3CT.
- ME04 MAINTAIN ALL OUTSIDE AIR INTAKES A MINIMUM OF 10'-0" RADIUS FROM EXHAUST, TYPICAL.
- ME06 TURN DOWN 6"Ø INTAKE AND END OPEN OVER ROOF (MIN. 24") WITH INSECT SCREEN.
- ME07 CONTRACTOR SHALL COORDINATE WITH NATIONAL TAB TO PROVIDE UV-PHI INDOOR AIR PURIFICATION SYSTEM, MODEL PHI-PKG-24V, INSTALL IN UNIT BLOWER COMPARTMENT PER MANUFACTURER'S INSTRUCTIONS.
- MO04 AREA RESERVED FOR REFRIGERATION CONDENSER(S) PROVIDED BY KITCHEN EQUIPMENT CONTRACTOR. COORDINATE EQUIPMENT LOCATION AND CONDENSER INSTALLATION WITH KITCHEN EQUIPMENT CONTRACTOR.
- MO05 REFERENCE PLUMBING DRAWINGS FOR CONDENSATE DRAIN ROUTING AND TERMINATION REQUIREMENTS.
- MO07 REFERENCE THE MECHANICAL RESPONSIBILITY MATRIX ON SHEET M001 FOR CURB AND EQUIPMENT FURNISHING AND INSTALLATION.



**1 MECHANICAL ROOF PLAN**  
1/4" = 1'-0"

ROOFTOP UNITS ARE EXISTING TO REMAIN AND PROVIDED UNDER THE SHELL BUILDING PERMIT.

# Bergmeyer

LA  
800 South Figueroa St.  
Los Angeles, CA 90017  
213.337.1090

CO  
875 N High St.  
Columbus, OH 43215  
380.900.8887

BCS  
Shepley St.  
Boston, MA 02210  
617.542.1025


www.bergmeyer.com

CONSULTANTS:



**HNY**  
CONSULTING  
ENGINEERS  
240 WEST 37TH STREET, 3RD FLOOR  
NEW YORK, NY 10018  
TEL: 212 413 8400  
www.hny-eng.com  
245002084  
NC CORPORATE NO. P-2451  
EXPIRES 6/30/2026

SEAL SIGNATURE:



10/13/2025

1	HNY	2025-10-13	IFC SET
A	HNY	2025-04-15	ADDENDUM A
HNY		2025-02-03	PERMIT SET
HNY		2025-01-13	75% SET

NO.	BY	DATE	DESCRIPTION
-----	----	------	-------------



**SHAKE SHACK CONCORD MILLS**

8031 CONCORD MILLS BLVD  
CONCORD, NC 28027, SUITE 103  
SHACK #1630

IFC SET

MECHANICAL ROOF PLAN

DRAWN BY: Author


CHECKED BY: Checker

JOB NO: 20240321.00


## M-150

10/13/2025 11:42:05 AM Autodesk Docs://20240321.00\_Shake\_Shack\_Concord Mills\_NC535265002/041/MEP\_204.rvt


JOSHUA N. HOYER




8 ROUND DUCT PENETRATION THROUGH ROOF DETAIL NTS




4 DUCT HANGER LOWER ATTACHMENT DETAILS NTS




7 GREASE DUCT CLEANOUT ACCESS DOOR DETAIL NTS




3 REGISTER MOUNTING TO RECTANGULAR DUCT DETAIL NTS




10 UPBLAST GREASE EXHAUST FAN DETAIL NTS




6 GREASE DUCT FIRE WRAP INSULATION INSTALLATION DETAIL NTS




2 CEILING DIFFUSER DETAIL NTS



9 ROOF MOUNTED DOWNBLAST FAN DETAIL NTS



5 KITCHEN EXHAUST HOOD ELEVATION DETAIL NTS



1 CEILING DIFFUSER DETAIL NTS

**Bergmeyer**

LA 800 South Figueroa St. Los Angeles, CA 90017  
 CO 275 N High St. Columbus, OH 43215  
 BOS 100 State St. Boston, MA 02210

212.337.1090  
 617.542.1025  
 380.900.8887  
 www.bergmeyer.com

CONSULTANTS:

**HNY**  
 CONSULTING ENGINEERS

240 WEST 37TH STREET, 3RD FLOOR  
 NEW YORK, NY 10018  
 TEL: 212.413.8400  
 www.hny.com

245002084  
 NC CORPORATE NO. P-2451  
 EXPIRES 6/30/2026

SEAL SIGNATURE:

**JOSHUA N. HOYER**  
 PROFESSIONAL ENGINEER  
 SEAL 046266  
 10/13/2025

NO.	BY	DATE	DESCRIPTION
1	HNY	2025-10-13	IFC SET
A	HNY	2025-04-15	ADDENDUM A
HNY	2025-02-03	PERMIT SET	
HNY	2025-01-13	75% SET	

**SHAKE SHACK**

SHAKE SHACK CONCORD MILLS

8031 CONCORD MILLS BLVD  
 CONCORD, NC 28027, SUITE 103  
 SHACK #1630

IFC SET

MECHANICAL DETAILS

DRAWN BY: Author  
 CHECKED BY: Checker  
 JOB NO: 20240321.00

M-501

**Division 23: HEATING, VENTILATING, AND AIR CONDITIONING**

**1. GENERAL INSTRUCTIONS**

**A. GENERAL REQUIREMENTS**

All requirements under Division 01 and the general and supplementary conditions of these specifications apply to this section and division. Where the sections of this section and division exceed those of Division 01, this section and division take precedence. Become thoroughly familiar with all contents as to requirements that affect this division, section, or both. Work required under this division includes all material, equipment, appliances, transportation, services, and labor required to complete the entire system as required by the drawings and specifications, or reasonably inferred to be necessary to facilitate the function of each system as implied by the design and the equipment specified.

The specifications and drawings for the project are complementary, and any portion of work described in one shall be provided as if described in both. In the event of discrepancies, notify the Engineer and request clarification prior to proceeding with the work involved.

Drawings are graphic representations of the work upon which the contract is based. They show the materials and their relationship to one another, including sizes, shapes, locations, and connections. They convey the scope of work, indicating the intended general arrangement of the systems without showing all of the exact details as to elevations, offsets, control lines, and other installation requirements. Use the drawings as a guide when laying out the work and to verify that materials and equipment will fit into the designated spaces, and which when installed per manufacturers' requirements, will ensure a complete, coordinated, satisfactory, and properly operating system.

**B. DEFINITIONS**

Division References contained in this specification follow the numbering system defined in the Construction Specifications Institute (CSI) MasterFormat 2004 Edition. Specification Divisions 01 through 13 provided with this project may reference the CSI MasterFormat 1995 Edition. The corresponding division references between the 2004 Edition and 1995 Edition are as follows:

- |   |             |
|---|-------------|
| 1. Division 21 – Fire Suppression                           | Division 15 |
| 2. Division 22 – Plumbing                                   | Division 15 |
| 3. Division 23 – Heating, Ventilating, and Air Conditioning | Division 15 |
| 4. Division 26 – Electrical                                 | Division 16 |
| 5. Division 27 – Communications                             | Division 16 |
| 6. Division 28 – Electronic Safety and Security             | Division 16 |

Furnish: "to supply and deliver to the project site, ready for unloading, unpacking, assembly, installation and similar operations."

Install: "to perform all operations at the project site including, but not limited to, the actual unloading, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, testing, commissioning, starting up and similar operations, complete, and ready for the intended use."

Provide: "to furnish and install."

Furnished by Owner (or Owner-Furnished) or Furnished by Others: "an item furnished by the Owner or under other divisions or contracts, and installed under the requirements of this division, complete and ready for intended use, including all items and services incidental to the work necessary for proper installation and operation. Include the installation under the warranty required by this division."

Engineer: Where referenced in this division, "Engineer" is the Engineer of Record and the Design Professional for the work under this division, and is a consultant to, and an authorized representative of the Architect, as defined in the General and/or Supplementary Conditions. When used in this division, Engineer means increased involvement by and obligations to the Engineer, in addition to involvement by and obligations to the Architect.

AHJ: The local code and/or inspection agency (Authority) Having Jurisdiction over the work.

NRTL: Nationally recognized testing laboratory, as defined and listed by OSHA in 29 CFR 1910.7 (e.g., UL, ETL, CSA), and acceptable to the AHJ over this project. Nationally recognized testing laboratories and standards listed are used only to represent the characteristics required, and are not intended to restrict the use of other NRTLs that are acceptable to the AHJ and standards that meet the specified criteria.

Substitution: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor. Substitutions include Value Engineering proposals.

- Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of required materials or equipment.
- Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required in order to meet other Project requirements but may offer advantage to Contractor or Owner.

The terms "approved equal," "equivalent," or "equal" are used synonymously and shall mean "accepted by or acceptable to the Engineer as equivalent to the item or manufacturer specified." The term "approved" shall mean labeled, listed, or both, by an NRTL, and acceptable to the AHJ over this project.

**C. PREBID SITE VISIT**

Prior to submitting bid, visit the site of the proposed work and become fully informed as to the conditions under which the work is to be done. Failure to comply with this requirement shall not be considered sufficient justification to request or obtain extra compensation over and above the contract price.

**D. MATERIAL AND WORKMANSHIP**

Provide new material, equipment, and apparatus under this contract unless otherwise stated herein, of best quality normally used for the purpose in good commercial practice, and free from defects. Install material and equipment in accordance with the manufacturer's and industry instructions and the specifications or shown on the drawings are not necessarily intended to designate the required trim, view descriptions of the firm government model numbers.

Pipe, pipe fittings, pipe specialties and valves shall be manufactured in plants located in the United States or certified to meet the specified ASTM and ANSI standards.

Work performed under this contract shall provide a neat and "workmanlike" appearance when completed, to the satisfaction of the Architect and Engineer. Workmanship shall be the finest possible by experienced mechanics. Installations shall comply with applicable codes and laws.

The complete installation shall function as designed and intended with respect to efficiency, capacity, noise level, etc. Abnormal noise caused by rattling equipment, piping, ducts, air devices, and squeaks in rotating components shall not be acceptable. Materials and equipment shall be of commercial specification grade in quality. Light duty and residential grade equipment shall not be accepted unless otherwise indicated.

Remove from the premises waste material present as a result of work, including cartons, crating, paper, stickers, and/or excavation material not used in backfilling, etc. Clean equipment installed under this contract to present a neat and clean installation at the termination of the work.

Repair or replace public and private property damaged as a result of work performed under this contract to the satisfaction of authorities and regulations having jurisdiction. Provide all safety lights, guards, and warning signs required for the performance of the work and for the safety of the public.

**E. MANUFACTURERS**

In other articles where lists of manufacturers are introduced, subject to compliance with requirements, provide products by one of the manufacturers specified.

Where a list is provided, manufacturers are listed alphabetically and not in accordance with any ranking or preference.

When manufacturers are not listed, provide products subject to compliance with requirements from manufacturers that have been actively involved in manufacturing the specified product for no less than 5 years.

**F. COORDINATION**

Coordinate work with that of other trades so that the various components of the systems are installed at the proper time, will fit the available space, and will allow proper service access to those items requiring maintenance. Components which are installed without regard to the above shall be relocated at no additional cost to the Owner.

Unless otherwise indicated, the General Contractor shall provide chases and openings in building construction required for installation of the systems specified herein. Contractor shall furnish the General Contractor with information where chases and openings are required. Contractor shall keep informed as to the work of other trades engaged in the construction of the project and shall execute work in a manner as to not interfere with or delay the work of other trades.

Figured dimensions shall be taken in preference to scale dimensions. Contractor shall take his own measurements at the building, as variations may occur. Contractor shall be held responsible for errors that could have been avoided by proper checking and inspection.

Provide materials with trim that will properly fit the types of ceiling, wall, or floor finishes actually installed. Model numbers listed in the specifications or shown on the drawings are not intended to designate the required trim.

**G. ORDINANCES AND CODES**

Work performed under this contract shall, at a minimum, be in conformance with applicable national, state and local codes having jurisdiction. Equipment furnished and associated installation work performed under this contract shall be in strict compliance with current applicable codes adopted by the local AHJ, including any amendments and standards as set forth by the following:

- National Electrical Code (NEC)
- National Fire Protection Association (NFPA)
- Underwriters Laboratories (UL)
- Occupational Safety and Health Administration (OSHA)
- American Society of Mechanical Engineers (ASME)
- American Society of Heating, Refrigerating, and Air Conditioning Engineers (ASHRAE)
- American National Standards Institute (ANSI)
- American Society of Testing and Materials (ASTM)
- Other national standards and codes where applicable.

Where the contract documents exceed the requirements of the referenced codes, standards, etc., the contract documents shall take precedence. Where conflicts between various codes, ordinances, rules, and regulations exist, comply with the most stringent.

Promptly bring all conflicts observed between codes, ordinances, rules, regulations, referenced standards, and these documents to the attention of the Architect and Engineer for the final resolution. Contractor will be held responsible for any violation of the law.

Procure and pay for permits and licenses required for the accomplishment of the work herein described. Where required, obtain, pay for, and furnish certificates of inspection to Owner.

**H. PROTECTION OF EQUIPMENT AND MATERIALS**

Store and protect from damage equipment and materials delivered to job site. For materials and equipment susceptible to changing weather conditions, dampness, or temperature variations, store inside in conditioned spaces. For materials and equipment not susceptible to these conditions, cover with waterproof, tear-resistant, heavy tarp or polyethylene plastic as required to protect from plaster, dust, dirt, paint, water, or physical damage. Replace insulation that has become wet at any time during construction. Drying the insulation is not acceptable. Seal any leaks in joints of thermal fiberglass insulation. Equipment and material damaged by construction activities shall be rejected and Contractor shall furnish new equipment and material of a like kind at his own expense.

Keep premises broom clean of foreign material created during work performed under this contract. Piping, equipment, etc. shall have a neat and clean appearance at the termination of the work. Remove debris from ceiling/return air plenum, including dust.

Plug, seal, or cap open ends of ductwork and piping systems while stored and installed during construction when not in use to prevent the entrance of debris into the systems. Remove temporary protection prior to starting equipment and turning the system over to the owner.

**I. SUBSTITUTIONS**

Materials, products, equipment, and systems described in the Bidding Documents establish a standard of required function, dimension, appearance and quality to be met by the proposed substitution. The base bid shall include only the products from manufacturers specially named in the Bidding Documents and specifications. To request a substitution, request the Substitution Request Form from the Architect or Engineer. Complete and send the Substitution Request Form for each material, product, equipment, or system that is proposed to be substituted. The burden of proof of the merit of the proposed substitution is upon the proposer.

Unless stated otherwise in writing by the Engineer by the Contractor, Contractor warrants to the Engineer, Architect, and Owner the following:

- Proposed substitution has been fully investigated and determined to meet or exceed the specified Work in all respects unless stated otherwise in the substitution request.
- Proposed substitution is consistent with the Contract Documents and will produce indicated results, including functional clearances, maintenance and operation, and securing of replacement parts.
- Proposed substitution has received necessary approvals of authorities having jurisdiction.
- Same warranty will be furnished for proposed substitution as for specified Work.
- If accepted substitution fails to perform as required, Contractor shall replace substitute material or system with that originally specified and bear costs incurred thereby.
- Coordination, installation and changes in the Work as necessary for accepted substitution will be complete in all respects.

No substitutions will be considered unless the Substitution Request Form is completed and attached with the appropriate substitution documentation. No substitution will be considered prior to receipt of bids unless written request for approval to bid has been received by the Engineer at least ten (10) calendar days prior to the date for receipt of bids.

If the proposed substitution is approved prior to receipt of bids, such approval will be stated in an addendum. Bidders shall not rely upon approvals made in any other way. Verbal approval will not be given. No substitutions will be considered after the contract is awarded unless specifically provided in the contract documents.

**J. SUBMITTALS**

Assemble and submit for review shop drawings, material lists, manufacturer product literature for equipment to be furnished, and items requiring coordination with other trades under this contract. Provide submittals in sufficient detail so as to demonstrate compliance with these contract documents and the design concept. Prior to transmitting submittals, verify that the equipment submitted is mutually compatible and suitable for the intended use, will fit the available space, and maintain manufacturer recommended service clearances. If the size of equipment furnished makes necessary any change in location or configuration, submit a shop drawing showing the proposed layout.

Transmit submittals as early as required to support the project schedule. Allow for two weeks Engineer review time, plus to/from mailing time via the Architect, plus a duplication of this time for resubmittal, if required. Only resubmit those sections requested for resubmittal.

Submittals shall contain the project name, applicable specification section, submittal date, equipment identification acronym as used on the drawings, and the Contractor's stamp. The stamp shall certify that the submittal has been checked by the Contractor, complies with the drawings and specifications, and is coordinated with other trades. Manufacturer product literature shall include shop drawings, finishes, wiring diagrams, electrical requirements. Contractor shall allow for the Engineer's review time as specified above in the construction schedule. Contractor shall submit only the documents required to purchase the materials and/or equipment in the electronic submittal.

Submittals and shop drawings shall not contain the firm name, logo, seal, or signature of the Engineer. They shall not be copies of the work product of the Engineer. If the Contractor desires to use elements of such product, refer to paragraph "Electronic Drawing Files" for procedures to be used.

Separate submittals according to individual specification sections. Illegible submittals will be rejected and returned without review. Catalogs and product literature shall be clearly marked and indexed and labeled. A hard copy format or a single PDF file for each specification section is acceptable. Each item or model number shall be clearly marked and accessories indicated. Label the catalog data with the equipment identification acronym or number as used on the drawings and include performance curves, capacities, sizes, weights, materials, finishes, wiring diagrams, electrical requirements and dimensions from specified equipment or materials. For equipment with motor starters or VFDs, include short circuit current ratings. Mark out inapplicable items. Shop drawings will be returned without review if the above mentioned requirements are not met.

Provide the quantity of submittals required by Division 01. If not indicated and hard-copy sets are provided, submit a minimum of six (6) copies. Refer to Division 01 for acceptance of electronic submittals for this project. For electronic submittals, Contractor shall submit the data in a format that is readable by the Architect and Engineer. Contractor shall allow for the Engineer's review time as specified above in the construction schedule. Contractor shall submit only the documents required to purchase the materials and/or equipment in the electronic submittal. Item name, date, Owner, Architect, Engineer, General Contractor, Sub-Contractor, and an index of contents.

The checking and subsequent acceptance of submittals by the Engineer and/or Architect shall not relieve the Contractor from responsibility for deviations from the drawings and specifications, errors in dimensions, details, size of members, or quantities, omissions of components or fittings; coordination of electrical requirements; and not coordinating items with actual building conditions and adjacent work. Proceed with the procurement and installation of equipment only after receiving approved shop drawings relative to each item.

**K. ELECTRONIC DRAWING FILES**

In preparation of shop drawings or record drawings, Contractor may, at his option, obtain electronic drawing files in AutoCAD or DXF format on CD-ROM disk, DVD disk, flash drive or direct download, as desired, from the Engineer for a shipping and handling fee of \$200 for a drawing set up to 12 sheets and \$15 per sheet for each additional sheet. Contact the Architect for written authorization and the Engineer for the necessary release agreement form and to specify shipping method and drawing format. In addition to payment, the written authorization from the Architect and release agreement form from the Engineer must be received before electronic drawing files will be sent.

**L. RECORD DRAWINGS (AS-BUILT DRAWINGS)**

During progress of the work in this division, Contractor shall maintain an accurate record of all changes made during the installation of the system. Upon completion of the work, accurately transfer all record information to three identical sets of the approved shop drawings. Insert one set into each copy of the manual described below.

See Division 01 and General Conditions for additional information.

**M. OPERATION AND MAINTENANCE INSTRUCTIONS**

During the course of construction, collect and compile a complete brochure of equipment furnished and installed on this project. Include operational and maintenance instructions, manufacturer's catalog sheets, wiring diagrams, parts lists, approved submittals and shop drawings, warranties, and descriptive literature as furnished by the equipment manufacturer. Include an inside cover sheet that lists the project name, state, Owner, Architect, Engineer, General Contractor, Sub-Contractor, and an index of contents.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for review and approval. The literature shall include the following: Page 1: operation, startup, rubber bands, loose-leaf binding, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Include Record Drawings as described above.

Refer to Division 01 for acceptance of electronic manuals for this project. For electronic manuals, refer to paragraph "Submittals" for requirements.

**N. FLAMMABLE REFRIGERANTS**

Equipment with refrigeration systems using Group A2L refrigerants shall meet all requirements of ASHRAE Std 15 and this section.

- Listing and Installation Requirements:
- Listed in accordance with 484 or UL 60335-2-240/CSA C22.2 No. 60335-2-40.
  - The nameplate shall include a symbol indicating that a flammable refrigerant is used, as specified by the product listing.
  - A label indicating a flammable refrigerant is used shall be placed adjacent to service ports and other locations where service involving components containing refrigerant is performed, as specified by the product listing.

Refrigeration systems shall have an integral refrigerant detection system that meets the following requirements as documented in ASHRAE Std 15:

- Utilize a set point, nonadjustable in the field, to generate an output signal to initiate mitigation actions.
- Field recalibration of refrigerant detection system shall not be permitted.
- Be capable of detecting the presence of a specified refrigerant corresponding to the refrigerant designation of the refrigerant contained in the refrigeration system.
- Have access for replacement of refrigerant detection system components.
- Have self-diagnostics to determine operational status of the sensing element.
- Generate air circulation fans of the equipment upon failure of a self-diagnostic check.
- Generate an output signal in not more than 30 seconds when exposed to a refrigerant concentration of 25% LFL (+0%, -1%).

Manufacturer's refrigeration mitigation action shall be completed in not more than 15 seconds after the initiation of the output signal of the equipment's integral refrigerant detection system and shall be maintained for at least 5 minutes after the output signal has reset.

**O. SPARE PARTS**

Furnish to Owner, with receipt, the following spare parts for the equipment furnished for this project:

- One set of spare filters of each type required for each unit. In addition to the spare set of filters, install new filters prior to testing, adjusting, and balancing work and before turning system over to Owner.
- Furnish one complete set of belts for each.
- Furnish three operating keys for each type of air outlet and inlet that require them.

**P. TRAINING**

At a time mutually agreed upon between the Owner and Contractor, provide the services of a factory trained and authorized representative to train Owner's designated personnel on the operation and maintenance of the equipment provided for this project.

Provide training to include, but not be limited to: an overview of the system and/or equipment as it relates to the facility as a whole; operation and maintenance procedures and schedules related to startup and shutdown, troubleshooting, servicing, preventive maintenance and appropriate operator intervention; and review of data included in the operation and maintenance manuals.

Submit a certification letter to the Architect stating that the Owner's designated representative has been trained as specified herein. Letter shall include date, time, attendees and subject of training. The Contractor and the Owner's representative shall sign the certification letter indicating agreement that the training has been provided.

Schedule training with Owner with at least 7 days advance notice.

**Q. WARRANTIES**

Warrant each system and each element thereof against all defects due to faulty workmanship, design, or material for a period of 12 months from date of Substantial Completion, unless specific items are noted to carry a longer warranty in the construction documents or manufacturer's standard warranty exceeds 12 months. Remedy all defects, occurring within the warranty period(s), as stated in the General Conditions and Division 01.

Warranties shall include labor and material, including travel expenses. Make repairs or replacements without any additional costs to the Owner, and to the satisfaction of the Owner, Architect, and Engineer.

Perform the remedial work promptly, upon written notice from the Engineer or Owner.

At the time of Substantial Completion, deliver to the Owner all warranties, in writing and properly executed, including term limits for warranties extending beyond the one year period and any actions the Owner must take in order to maintain warranty status. Each warranty instrument shall be addressed to the Owner and state the commencement date and term.

**2. GENERAL MATERIALS AND INSTALLATION**

**A. BUILDING OPERATION**

Comply with the schedule of operations as outlined in the architectural portions of this specification. Accomplish work requiring interruption of building operation at a time when the building is not in operation and only with written approval of building Owner and/or tenant. Coordinate interruption of building operation with the Owner and/or tenant a minimum of seven (7) days in advance of work.

**B. EXISTING EQUIPMENT REUSE AND REMOVAL**

Remove all unused equipment, ductwork, piping, and associated supports. Cap ductwork and piping at mains and seal air and water tight.

Provide items of HVAC systems modification required because of building remodeling, as noted on the drawings or necessary for proper operation. Match existing materials and construction techniques when modifying existing systems unless specified otherwise. Coordinate additional requirements with General Contractor and Architect.

Seal airtight existing ductwork required to be abandoned in place or not in use at the termination of the work.

Cap and seal weathertight existing roof curbs and roof openings to be abandoned in place as a result of equipment removal.

Clean and refurbish existing ductwork, diffusers, registers, and grilles intended for reuse as required or as indicated on drawings.

Clean and replace existing HVAC equipment intended for reuse as required for proper operation including replacement of filters, belts, motors, remote controls, and safety interlocks.

**C. COINCIDENTAL DAMAGE**

Repair streets, sidewalks, drives, paving, walls, finishes, and other facilities damaged in the course of the work. Repair materials shall match existing construction. Repair work shall meet all requirements of the Owner, local authorities having jurisdiction, and meet the satisfaction of the Architect.

**D. CUTTING AND PATCHING**

Conform to the requirements in Division 01. Cut walls, floors, ceilings, and other portions of the facility as required to install work under this division. Obtain permission from the Architect prior to cutting. Do not cut or disturb structural members without prior approval from the Architect and Structural Engineer. For post-tensioned slabs, x-ray slab and closely coordinate all core drill locations with Architect and Structural Engineer prior to performing any work. Obtain approval from Architect and Structural Engineer for all core drills and penetrations at least four days prior to performing work. Penetrations shall be made as small as possible while maintaining required clearances between the building element penetrated and the system component. Patch around openings to match the adjacent construction including fire ratings, if applicable. Repair and refinish areas disturbed by work to the condition of adjoining surfaces in a manner satisfactory to the Architect.

**E. ROUGH-IN**

Coordinate without delay all roughing-in with other divisions. Conceal piping, conduit, and rough-in except in unfinished areas and where otherwise shown.

**F. STRUCTURAL SUPPORT SYSTEMS**

Structural steel used for support of equipment, ductwork and piping shall be new, clean, and conform to ASTM Designation A-36. Support mechanical components from the building structure. Do not support mechanical components from ceilings, other mechanical or electrical components, and other non-structural elements.

**G. PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS AND CURBS**

Provide prefabricated equipment support rails and roof curbs manufactured by AES Industries, Custom Curb, Inc., Pate Company, Thybar or approved equal. Provide with fully milled raised cant and step to match roof insulation thickness, welded, minimum 18 gauge galvanized steel shell, internally reinforced to load bearing factors of equipment being supported, minimum 1-1/2 inch thick, 3 pound rigid insulation internal to shell to maintain continuous roof insulation where required, factory installed wood nailer, and minimum 18 gauge jacket with counterflashing where equipment does not fully cover the equipment support. Provide sloped roof equipment supports to enable level installation. Provide rigid backing material behind cant to maintain cant slope. Provide multiple support rails to uniformly support the equipment. Attach to roof structure according to manufacturer's installation instructions.

Attach equipment directly to pre-engineered roof equipment support using one of the following methods:

- Rail Equipment Supports: Secure each equipment support leg to the rail with a minimum of 4 points of connection per leg.
- Roof Curbs: Secure each corner of the equipment to the curb nailer using a minimum of 4 lag screws, located along the length of the equipment. Alternatively, secure equipment to the curb using hold-down brackets. Provide minimum 6 inch long, 1/4" galvanized steel brackets sized to wrap around top of curb and under equipment base rail with sufficient horizontal offset to cover overlap gap between the equipment rail and curb. Secure bracket to equipment and curb nailer using a minimum of 8 points of connection per bracket. Provide one bracket at each corner along the length of the unit.
- Hold-Down Brackets: Coordinate with the curb manufacturer to determine the quantity and size of hold-down brackets and fasteners, with installation instructions for each unit to meet a Building Design Risk Category of II and a Design Wind Speed of 115 mph.
- Submit signed and sealed drawings that indicate the design and installation requirements of pre-engineered roof supports can withstand the design criteria listed, include installation requirements for anchoring to the roof structure. The Engineer is not responsible and will not provide the seal and signature. Deliver submittals to the local AHJ for approval prior to installation of the contractor provided, pre-engineered roof supports.
- Provide seismic restraints in accordance with Article "Seismic Controls for MEFP Systems."

**H. ACCESS PANELS AND DOORS**

Refer to Architectural documents for specification of access panels and doors.

**I. PENETRATIONS**

Provide sleeves for pipes passing through above grade concrete or masonry walls, concrete floor or roof slabs. Sleeves are not required for core drilled holes in existing masonry walls, concrete floors or roofs. Provide 10 gauge galvanized steel sleeves for sleeves 6 inches and smaller. Provide galvanized steel metal sleeves for larger than 6 inches. Schedule 40 PVC sleeves are acceptable for installation in areas without return air plenums.

Seal elevated floor, exterior wall and roof penetrations weathertight and weathertight with non-shrink, non-hardening commercial sealant. Pack with mineral wool and seal both ends with minimum of 1/2 inch of sealant.

Seal around penetrations of fire rated assemblies. Coordinate fire ratings and locations with the architectural drawings. Refer to architectural specifications for fire stoppings. Provide a product schedule for UL listing, location, wall or floor rating and installation drawing for each penetration fire stop system.

Extend pipe insulation for insulated pipe through floor, wall and roof penetrations, including fire rated walls and floors. The vapor barrier shall be maintained. Size sleeve for a minimum of 1 inch annular clear space between inside of sleeve and outside of insulation.

Provide prefabricated roof curbs where pipes and/or ductwork penetrate elevated slabs or the roof to the exterior. Provide cover over curb of weather-resistant material and seal duct or pipe penetrations through the cover. Provide pipe collar of weather-resistant material with stainless steel pipe clamps for piping penetrations.

Provide box frames for rectangular openings welded 12 gauge galvanized steel attached to forms and of a maximum dimension established by the Architect. Notify the General Contractor or Architect before installing any box openings not shown on the Architectural or Structural drawings.

Seal concrete or masonry exterior wall penetrations below grade with "wall pipes" and mechanical sleeve seals. Provide cast iron "wall pipes" with integral waterstop ring manufactured by Jay R. Smith, Josam, Wade, Watts or Zum. Provide modular mechanical sleeve seals, manufactured by Calpico, Metraflex, or Thunderville / Link Seal.

Seal elevated concrete slab with water proof membrane penetrations with "wall pipes" and water proof sealant. Select waterproof membrane flashing between "wall pipe" clamping flange and clamping ring. Provide cast iron "wall pipes" with integral waterstop ring manufactured by Jay R. Smith, Josam, Wade, Watts or Zum.

Provide sleeves for horizontal pipe passing through or under foundation. Sleeves shall be cast iron soil pipe two nominal pipe sizes larger than the pipe served.

Provide Schedule 40 PVC pipe sleeves for vertical pressure pipe passing through concrete slab on grade. Sleeves shall be one nominal pipe size larger than the pipe served and two pipe sizes larger than pipe served for ductile iron pipes with restraining rods. Seal water-tight with silicone caulk.

Provide 12 inch thick cellular foam insulation around perimeter of non-pressure pipe passing thru concrete slab on grade. Insulation shall extend to 2 inches above and below the concrete slab.

**J. FIRESTOPPING**

Sealants and accessories shall have fire-resistance ratings indicated, as established by testing identical assemblies in accordance with UL 2079 or ASTM E 814, or other NRTL acceptable to AHJ.

Manufacturers: Hilli, RectorSeal, Specified Technologies Inc., United States Gypsum Company, or 3M corp.

Through and Membrane Penetration Firestopping Systems Product Schedule: Provide UL listing, location, wall or floor rating, and installation drawing for each penetration fire stop system.

Where project conditions require modification to qualified testing and inspecting agency's illustrations for a particular firestopping condition, submit illustration, with modifications marked, approved by penetration firestopping manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly, include qualifications data for testing agency.

**K. ELECTRICAL WIRING**

High voltage wiring is defined as 50 Volts or higher. Low voltage wiring is defined as less than 50 Volts. Line voltage wiring shall be provided by Division 26. Line voltage control and interlock wiring for mechanical systems shall also be provided by Division 26. Low voltage control wiring shall be provided by Division 23. For Division 23, provide wiring diagrams to Division 26 as required for proper equipment hookup. Coordinate with Division 26 the actual wire sizing amps for mechanical equipment (from the equipment nameplate) to ensure proper installation.

Provide power and communication wiring with transient protection in accordance with IEEE C62.41.2. All control and interlock wiring shall comply with the NEC. Control wiring shall be sized to accommodate the voltage drop associated with the distance between the control device and the controlled device and the control installation. All NEC Class 1 (High Voltage) wiring (other than Class 1, low voltage) wiring shall be UL listed in approved raceway according to the NEC and Division 26 requirements. Maximum allowable voltage for control wiring shall be 120 V. All low-voltage wiring shall meet NEC Class 2 requirements. Low-voltage power circuits shall be sub-fused when required to meet Class 2 current limit.

Conduit for Control Wiring: EMT with compression fittings, cold rolled steel, zinc coated or zinc-coated rigid steel with threaded connections.

Pull and Junction Boxes: Size according to number, size, and position of entering raceway as required by National Electrical Codes. Enclosure type shall be suited to location.

Install wiring parallel to building lines wherever possible. Conceal all control wiring in finished rooms. Do not install Class 2 wiring in raceway containing Class 1 wiring. Boxes and panels containing high voltage wiring and equipment may not be used for low-voltage wiring except for the purpose of interfacing the two wires (e.g., relays and transformers). All wire-to-device and wire-to-wire connections shall be made at a terminal block or terminal strip. All runs of communication wiring shall be unspliced length when that length is commercially available. Verify the integrity of the entire network following the cable installation. Use appropriate test measures for each particular cable. Label all wiring and cabling at each end within 2 inches of termination with the controller termination number. Label control devices used in the system with permanent labels using the identifiers that match the record documents.

**L. EQUIPMENT FURNISHED BY OTHERS**

Provide equipment furnished and accessories that are not provided by the equipment supplier or Owner to complete installation of equipment furnished by others in locations as indicated on the drawings, specified herein, or both. Equipment and accessories not provided by the equipment supplier may include, but not be limited to fuses, vents, intakes, associated roof jacks and caps to outdoors, dampers, in-line fans, roof fans, and control interlocks, etc. as required for proper operation of the complete system in accordance with the manufacturer's instructions.

Contractor shall be responsible for correct rough-in dimensions and shall verify them with Architect and/or equipment supplier prior to service installations.

**M. SYSTEM TESTING, ADJUSTING, AND BALANCING**

Upon completion of each phase of the installation, test each system in conformance with local code requirements and as noted below. Furnish labor and equipment equal to that of the equipment supplier for system installed under this contract. Assume all costs involved in the tests and repairing and/or replacing any damages resulting therefrom.

Final system testing, balancing and adjustments (TAB) shall be performed by a Contractor certified by the National Environmental Performance Bureau (NEBB), Associated Air Balance Council (AABC), or Testing, Adjusting and Balancing Bureau (TABB). TAB shall be performed in accordance with the most current edition of the certified agencies procedural standard for testing, adjusting and balancing and shall comply with the strictest interpretation of that standard for execution and reporting of all TAB work.

Test, adjust, and balance equipment and systems included in the scope of work. Prepare testing and balancing report log using forms equivalent with the standard forms available from the TAB certification standard being followed. Adjust equipment and systems to




- 11. Terminal Units
  - a. Include all applicable "Start-Up Checks Common to All Systems".
  - b. Start-Up Checks: Perform the following inspections/checks during start-up:
    - i. After construction is completed, including painting if applicable, clean unit exposed surfaces.
    - ii. Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
    - iii. Verify adequate access for maintenance.
    - iv. Check power and control voltages.
    - v. Check rotation of fan where applicable.
    - vi. Check operation of water leak sensors.
    - vii. Check calibration and operation of the controlling elements.
    - viii. Check control valves for required close-off and fail position.
    - ix. Install new filter units for terminals requiring same.
- 12. Fans and ESPs
  - a. Include all applicable "Start-Up Checks Common to All Systems".
  - b. General: Provide the services of a factory-authorized service representative to test and inspect ESP installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
  - c. Start-Up Checks: Perform the following inspections/checks during start-up:
    - i. Inspect the field assembly of components and installation of the units, piping, ductwork, and electrical connections.
    - ii. Clean unit cabinet interiors to remove foreign material and construction dirt and dust. Vacuum clean fan wheel, fan cabinet, coils entering air face. Ensure volatile irritants are contained and kept out of occupied spaces.
    - iii. Adjust and lubricate dampers and linkages for proper damper operation.
    - iv. Verify the unit is secure on mountings and supporting devices and connections for ductwork, and electrical are complete. Verify proper thermal overload protection is installed in motors, starters, and disconnects.
    - v. Ensure vibration isolation integrity is maintained with the fan installation and associated connections.
    - vi. Lubricate bearings, pulleys, belts, and other moving parts with factory-recommended lubricants.
    - vii. Stroke all dampers to ensure free and full travel.
- 13. Ductwork Accessories
  - a. Include all applicable "Start-Up Checks Common to All Systems".
  - b. Start-Up Checks: Perform the following checks during start-up and as specified:
    - i. Cleaning: Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
  - c. Start-Up Tests: In addition to specifications, perform the following as a minimum:
    - i. Operate installed ductwork accessories to demonstrate compliance with requirements. Test for air leakage while system is operating. Repair or replace faulty accessories, as required to obtain proper operation and leak proof performance.
    - ii. Label access doors in accordance with Division 21 Section "Mechanical Identification"
    - iii. Adjusting: Adjust ductwork accessories for proper settings, install fusible links in-fire dampers and adjust for proper action.

8. ALTERNATES

A. DESCRIPTION

Refer to the architectural portion of the specification for list of alternates. Applicable sections of the base specifications shall apply to all work required by the alternate unless otherwise specified. Determine whether or not and how each alternate affects work. Include labor, materials, equipment, and transportation services necessary for and incidental to the completion of work under each particular alternate. Furnish separate bid for each alternate applicable to work, stating the amount to be added or deducted from the base bid.

END OF SECTION 23



800 South Figueroa St.  
 Los Angeles, CA 90017  
 213.337.1090  
 www.bergmeyer.com

875 N High St.  
 Columbus, OH 43215  
 380.900.8867

Shepley St.  
 Boston, MA 02210  
 617.542.1025

CONSULTANTS:



**HNY**  
 CONSULTING  
 ENGINEERS  
 240 WEST 37TH STREET, 3RD FLOOR  
 NEW YORK, NY 10018  
 TEL: 212 413 8400  
 www.hny-eng.com  
 245002084  
 NC CORPORATE NO. P-2451  
 EXPIRES 6/30/2026


SEAL SIGNATURE:



10/13/2025

1	HNY	2025-10-13	IFC SET
A	HNY	2025-04-15	ADDENDUM A
	HNY	2025-02-03	PERMIT SET
	HNY	2025-01-13	75% SET

NO.	BY	DATE	DESCRIPTION
-----	----	------	-------------



SHAKE SHACK CONCORD MILLS

8031 CONCORD MILLS BLVD  
 CONCORD, NC 28027, SUITE 103  
 SHACK #1630

IFC SET

MECHANICAL SPECIFICATIONS

DRAWN BY: Author  
 CHECKED BY: Checker  
 JOB NO: 20240321.00

M-592

## ROOFTOP UNIT CONTROL MATRIX

CONTROL FEATURE	UNITS	(E) RTU-1 SETPOINT OR Y/N	(E) RTU-2 SETPOINT OR Y/N	NOTES
SETPOINTS				
COOLING - OCCUPIED SETPOINT	'F	75	75	
COOLING - UNOCCUPIED SETPOINT	'F	80	80	
DEAD BAND - MINIMUM HEATING AND COOLING TEMPERATURE SETPOINT DIFFERENCE	'F	5	5	
HEATING - OCCUPIED SETPOINT	'F	70	70	
HEATING - UNOCCUPIED SETPOINT	'F	60	60	
DEHUMIDIFICATION SETPOINT - HUMIDITY SENSOR FEEDBACK	% RH	50%	50%	B
PROGRAMMED CONTROL FEATURES				
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT		Y	Y	B
REMOTE COMBINATION TEMPERATURE AND HUMIDITY SENSOR		Y	Y	
EQUIPMENT ACCESSORIES AND CONTROL MODULES				
OUTSIDE AIR DAMPER - MOTOR OPERATED (MODULATING)		Y	Y	L
OUTSIDE AIR FLOW MONITORING STATION		Y	Y	F
INTEGRATED ECONOMIZER - DIFFERENTIAL ENTHALPY ENABLE (OA ENTHALPY < RA ENTHALPY)	BTULB	Y	Y	E
ECONOMIZER FAULT DETECTION AND DIAGNOSTICS (FDD) SYSTEM		Y	Y	F, G
RELIEF - BAROMETRIC DAMPER		Y	N	
RELIEF - VARIABLE VOLUME POWERED EXHAUST FAN	IN, W.C.	N	Y	H
COOLING COIL (DX - VARIABLE SPEED)		Y	Y	M
DEHUMIDIFICATION - HOT GAS REHEAT		Y	Y	O
HEATING COIL (NATURAL GAS)		Y	Y	M
SUPPLY FAN CONTROL METHODS		Y	Y	
ON DURING OCCUPIED HOURS		Y	Y	
CYCLE WITH LOADS DURING UNOCCUPIED HOURS		Y	Y	
OPTIMUM START SEQUENCE		Y	Y	T
VARIABLE VOLUME - STAGED FAN CONTROL IN RESPONSE TO ACTIVE COOLING COIL STAGES		Y	Y	M, Q
SAFETIES, INTERLOCKS, AND ALARMS				
GAS VALVE SAFETY		Y	Y	F
RETURN AIR SMOKE DETECTOR - SAFETY SHUTDOWN		Y	Y	B
LOW LIMIT FREEZE/STAT - FREEZE PROTECTION SAFETY SHUTDOWN		Y	Y	F
DIFFERENTIAL PRESSURE SWITCH - FILTER CHANGE ALARM		Y	Y	F
FIRE ALARM CONTROL PANEL - SAFETY SHUTDOWN INTERLOCK		Y	Y	F
KITCHEN EXHAUST SYSTEM INTERLOCK		Y	Y	S

DIV. 23 CONTRACTOR SHALL PROVIDE CONTROL PANEL(S), WIRING, THERMOSTAT(S), TEMPERATURE SENSOR(S), HUMIDISTAT(S), AND/OR CO2 SENSOR(S) WHERE SHOWN ON THE DRAWINGS AND AS REQUIRED TO FACILITATE THE SCHEDULE CONTROL MODES AND SEQUENCES OF OPERATION. EACH UNIT SHALL CONTROL BASED ON ITS OWN INTERNAL SAFETIES, TIME DELAYS, AND SEQUENCES UNLESS NOTED OTHERWISE. COORDINATE WITH OWNER FINAL BUILDING AND EQUIPMENT SCHEDULES DURING STARTUP. REFERENCE DIVISION SPECIFICATIONS FOR INDIVIDUAL DEVICE REQUIREMENTS.

- NOTES:
- B. DIVISION 23 CONTRACTOR SHALL PROVIDE DEVICE.
  - E. IF SETPOINT VALUE IS LISTED, IT INDICATES ECONOMIZER HIGH-LIMIT SHUTOFF. UNIT SHALL BE IN ECONOMIZER IF CONDITIONS ARE LESS THAN SETPOINT. THE FOLLOWING SENSORS SHALL DETERMINE ECONOMIZER ON POINT:
    - OUTSIDE AIR TEMPERATURE: DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
    - RETURN AIR TEMPERATURE: DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
    - OUTSIDE AIR HUMIDITY: DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
    - RETURN AIR HUMIDITY: DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
  - F. DEVICE SHALL BE FACTORY MOUNTED AND PRE-WIRED FOR OPERATION SUBJECT TO THE ONBOARD CONTROLLER.
  - G. PROVIDE UNIT WITH AN FDD SYSTEM CONSISTING OF PERMANENTLY INSTALLED OUTSIDE AIR, SUPPLY AIR, AND RETURN AIR TEMPERATURE SENSORS. THE UNIT CONTROLLER SHALL AT A MINIMUM BE CAPABLE OF PROVIDING SYSTEM STATUS OF ECONOMIZER, COMPRESSOR, HEATING, MIXED AIR LOW LIMIT ALARM, AND SENSOR VALUES. EACH OPERATING MODE SHALL BE CAPABLE OF INDEPENDENTLY OPERATING FOR TESTING. THE SYSTEM SHALL REPORT FAULTS TO AN APPLICATION ACCESSIBLE BY SERVICE PERSONNEL. THE FOLLOWING FAULTS SHALL BE DETECTED: AIR TEMPERATURE SENSOR FAILURE, ECONOMIZER ENABLE/DISABLED WHEN ECONOMIZER SHOULD BE OFF/ON, RESPECTIVELY, DAMPER NOT MODULATING, AND EXCESS OUTSIDE AIR.
  - H. POWERED EXHAUST FAN SHALL STAGE ON AND OFF ACCORDING TO DAMPER POSITION.
  - L. EQUIPMENT MANUFACTURER SHALL PROVIDE MODULATING DAMPER AND CONTROLS CAPABLE OF ADJUSTING THE DAMPER POSITION TO MAINTAIN THE SCHEDULED OUTSIDE AIR ON THE DRAWINGS ACROSS ALL FAN SPEEDS. DIV. 23 CONTRACTOR SHALL PROGRAM MULTIPLE DAMPER POSITION SETPOINTS IN THE FIELD DURING TESTING AND BALANCING TO MAINTAIN MINIMUM VENTILATION WHEN NOT IN ECONOMIZER. DAMPER SHALL BE CLOSED DURING UNOCCUPIED HOURS.
  - M. UNITARY CONTROLLER SHALL MODULATE AND/OR CYCLE SUPPLY FAN SPEED SETTING AND COIL CAPACITY STAGES SUBJECT TO THE INTERNAL SAFETIES AND SEQUENCES TO MAINTAIN SCHEDULED SETPOINTS.
  - O. DEHUMIDIFICATION SEQUENCE SHALL BE BASED ON RETURN AIR HUMIDITY.
  - S. INTERLOCK RTU WITH KITCHEN EXHAUST HOOD SYSTEM(S) TO SHUT DOWN UPON SIGNAL FROM HOOD FIRE EXTINGUISHING SYSTEM. INTERLOCK RTU WITH KITCHEN EXHAUST FAN TO ENERGIZE WHEN HOOD SYSTEM IS ENERGIZED FOR PRESSURIZATION.

## GRILLE, REGISTER AND DIFFUSER SCHEDULE

MARK	MANUFACTURER	SERVICE	MODEL	CONSTRUCTION	FACE TYPE	MOUNTING LOCATION	FACE SIZE (IN)	MAX NC	MAX PRESS DROP (IN W.C.)	NOTES
CEG	E.H. PRICE	EXHAUST GRILLE W/ DAMPER	80D	STEEL	EGGCRATE	SURFACE	12"x12"	30	0.06	A C D G H I
CRG	E.H. PRICE	RETURN GRILLE	80	STEEL	EGGCRATE	LAY-IN	24"x24"	30	0.06	A C D G I
CSD1	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	SURFACE	12"x12"	30	0.08	A B C D G I J
CSO2	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	LAY-IN	24"x24"	30	0.08	A B C D G I
CSO3	E.H. PRICE	SUPPLY DIFFUSER	P3DR	STEEL	PERFORATED	LAY-IN	24"x24"	30	0.08	A C D G I
WSR	E.H. PRICE	SUPPLY REGISTER W/ DAMPER	520D	STEEL	LOUVERED FACE	WALL OR DUCT	<varies>	30	0.08	A C D E F G I

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

- NOTES:
- A. EQUIPMENT FURNISHED AND INSTALLED PER THE EQUIPMENT RESPONSIBILITY SCHEDULE.
  - B. 4-WAY THROW PATTERN UNLESS OTHERWISE INDICATED BY FLOW ARROWS ON DRAWINGS.
  - C. NECK SIZE SHOWN ON DRAWINGS. PROVIDE BRANCH DUCT TO MATCH NECK SIZE UNLESS OTHERWISE SHOWN ON DRAWINGS.
  - D. BAKED ENAMEL FINISH, WHITE TO MATCH CEILING COLOR.
  - E. FRONT BLADES PARALLEL TO LONG DIMENSION.
  - F. DOUBLE DEFLECTION BARS SHALL BE ADJUSTABLE.
  - G. FRAME TYPE TO MATCH CEILING/WALL CONSTRUCTION, COORDINATE WITH ARCHITECTURAL REFLECTED CEILING/WALL PLAN.
  - H. PROVIDE OPPOSED BLADE DAMPER ADJUSTABLE FROM FACE OF DEVICE.
  - I. PROVIDE DIFFUSERS, LINEAR SLOTS, AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.
  - J. PROVIDE WITH RAPID MOUNT FRAMING OPTION FOR LAY-IN TYPE DIFFUSERS INSTALLED IN A HARD CEILING.

## PROJECT DESIGN CONDITIONS

CLIMATE CONDITIONS				BUILDING OPERATING HOURS:			
WEATHER STATION: CHARLOTTE DOUGLAS, NC, USA				MONDAY - FRIDAY TBD BY OWNER			
CLIMATE ZONE: 3A				SATURDAY TBD BY OWNER			
HEATING (DB): 99.6% 21.0 'F				SUNDAY TBD BY OWNER			
COOLING (DB/MCWB): 0.4% 94.2 'F/ 74.6 'F/				HOLIDAY TBD BY OWNER			

SPACE / UNIT DESCRIPTION	SETPOINTS										SPACE OPERATING HOURS OCCUPIED / UNOCCUPIED			NOTES	
	COOLING / DEHUMIDIFICATION					HEATING					M-F	SAT	SUN		
	OCC	UNOCC	MAX RH %	MIN RH %	MAX RH %	OCC	UNOCC	MIN RH %	MAX RH %	CONTROL METHOD					BASE PPM
DINING AREAS	75	80	50%	NA	70	60	NA	NA	NA	NA	NA	TBD	TBD	TBD	A, B, C
OFFICES	75	80	50%	NA	70	60	NA	NA	NA	NA	NA	TBD	TBD	TBD	A, B, C
KITCHEN/BOH	75	80	50%	NA	70	60	NA	NA	NA	NA	NA	TBD	TBD	TBD	A, B, C

- NOTES:
- A. ZONE LEVEL SET POINT CONDITIONS SHALL BE AS SCHEDULED UNLESS OTHERWISE SCHEDULED OR NOTED ON THE DRAWINGS FOR ROOM SPECIFIC SPACE CONDITIONS.
  - B. ZONE LEVEL OCCUPANCY HOUR SCHEDULE SHALL BE PER BUILDING OPERATING HOURS UNLESS OTHERWISE SCHEDULED.
  - C. ZONE LEVEL CONTROLS SHALL BE CAPABLE OF OPERATING WITH INDEPENDENT OCCUPANCY SCHEDULES.

BUILDING AIR BALANCE SUMMARY NORMAL OPERATION				
UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/S
(E) RTU-1	2,100	900	--	43%
(E) RTU-2	4,100	1,100	--	27%
(E) FCU-1	420	40	--	10%
KEF-1	--	--	750	--
KEF-2	--	--	700	--
EF-1	--	--	150	--
TOTALS	6,620	2,040	1,600	--
<b>TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)</b>				<b>440</b>
<b>PERCENT POSITIVE PRESSURIZATION</b>				<b>21.6%</b>

BUILDING AIR BALANCE SUMMARY ECONOMIZER MODE				
UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/S
(E) RTU-1	2,100	2,100	--	100%
(E) RTU-2	4,100	4,100	--	100%
(E) FCU-1	420	40	--	10%
KEF-1	--	--	750	--
KEF-2	--	--	700	--
EF-1	--	--	150	--
RELIEF (E) RTU-1	--	--	1,200	--
RELIEF (E) RTU-2	--	--	3,000	--
TOTALS	6,620	6,240	5,800	--
<b>TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)</b>				<b>440</b>
<b>PERCENT POSITIVE PRESSURIZATION</b>				<b>7.1%</b>

OUTSIDE AIR REQUIREMENTS, IMC-2015 (IP)																
SYSTEM DESIGNATION	SYSTEM TAB NAME OR LIST 'SINGLE'	SINGLE-ZONE SYSTEMS ONLY			MULTI-ZONE SYSTEMS ONLY			FLOOR AREA SERVED BY SYSTEM [A4] (SF)	SYSTEM AVERAGED AREA-BASED OUTDOOR AIR RATE (CFM/SF)	SYSTEM POPULATION (PEOPLE)	SYSTEM AVERAGED PEOPLE-BASED OUTDOOR AIR RATE (CFM/PP)	REQUIRED OA INTAKE FLOW [V4] (CFM)	REQUIRED DCV OA INTAKE FLOW [V4] (CFM)	DESIGN OA INTAKE FLOW [V4] (CFM)	NOTES	
		ASSOCIATED VENTILATION ZONE	SINGLE ZONE WORST CASE EFFECTIVENESS [E2]	SYSTEM VENTILATION EFFICIENCY [EV]	ASSOCIATED VENTILATION ZONE	SINGLE ZONE WORST CASE EFFECTIVENESS [E2]										
(E) RTU-1	MULTIZONE (E) RTU-1	KITCHEN + BOH	0.80	0.93	1,230	0.145	38	7.50	497	NA	900	ALL				
(E) RTU-2	SINGLE ZONE	OFFICE	0.80	-	1,360	0.090	0	0.80	0	NA	1,100	ALL				
(E) FCU-1	SINGLE ZONE	OFFICE	0.80	0.80	71	0.090	2	5.00	18	NA	40	ALL				
											TOTALS	515	0	2,040		

GENERAL NOTES:

- VENTILATION CALCULATIONS BASED ON IMC-2015.
- SYSTEM POPULATIONS BASED ON MAX SEATING AND/OR CODE MAXIMUM VALUES.
- SINGLE ZONE SYSTEMS (Vol + Voz). SYSTEM VENTILATION EFFICIENCY CALCULATION IS NOT REQUIRED FOR SINGLE ZONE SYSTEMS. WORST CASE AIR DISTRIBUTION EFFECTIVENESS BETWEEN HEATING AND COOLING MODES OF OPERATION IS SHOWN IN TABLE.
- 100% OA SYSTEMS (Vol + Voz). WHEN ONE AIR HANDLER SUPPLIES ONLY OUTDOOR AIR TO ONE OR MORE ZONES. EACH ZONE IS INDIVIDUALLY CALCULATED WITH ITS WORST CASE ZONE AIR DISTRIBUTION EFFECTIVENESS (HEATING/COOLING).
- MULTI-ZONE RECIRCULATING SYSTEMS. CALCULATOR USED TO DETERMINE VENTILATION AIRFLOW IN COMPLIANCE WITH IMC-2015 VRP AND ASHRAE 62-1 2013 APPENDIX A. VENTILATION RATE SHOWN IS ACTUAL CALCULATED WITH CORRECTION FACTORS INCLUDED. EACH ZONE IS CALCULATED WITH ITS WORST CASE ZONE AIR DISTRIBUTION EFFECTIVENESS (HEATING/COOLING) AS PART OF CALCULATIONS TO FIND EV.

JOSHUA N. HOWER

10/13/2025 11:42:14 AM Autodesk Docs/20240210\_05\_Shake\_Shack\_Concord Mills\_NCS24501002061\_RFP\_2024

## ROOFTOP UNIT SCHEDULE (DX COOLING, NATURAL GAS HEAT)

LANDLORD PROVIDED EQUIPMENT. SCHEDULE FOR REFERENCE ONLY																															
MARK	MANUFACTURER	MODEL	NOMINAL TONS	UNIT TYPE	SUPPLY FAN					COOLING COIL					GAS FIRED HEAT EXCHANGER					ELECTRICAL											
					CFM	ESP (IN)	NOM HP	VFD (Y/N)	TH	SH (MBH)	EAT (°F DB)	LAT (°F WB)	REFR TYPE	MIN EFF (EER)	(IEER)	MIN NO STAGES	MIN OUT (MBH)	NOM INPUT (MBH)	MIN EFF (%)	EAT (°F DB)	LAT (°F WB)	MIN NO STAGES	MIN OA (CFM)	V/PH	MCA	MOC/P	DISC TYPE	WEIGHT (LBS)	NOTES		
(E) RTU 1	CAPTIVEAIRE	CAS-HVAC-1.125-18-10T	10.0	SINGLE ZONE	2100	0.8	2.00	Yes	114.5	73.6	83.3	68.1	51.5	50.0	R454B	11	13.8	3	93.9	122.4	81	49.0	90.4	2	900	208 / 3	55	60	FUSED	1496	A-O
(E) RTU 2	CAPTIVEAIRE	CAS-HVAC-3.250-24-15T	15.0	SINGLE ZONE	4100	0.8	5.00	Yes	150.0	110.9	80.2	66.1	55.6	54.1	R454B	12	18.8	3	124.6	213.9	81	56.9	85.0	2	1100	208 / 3	74	80	FUSED	2654	A-O

\*EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS. EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFERENCE RESPONSIBILITY MATRIX ON SHEET M-001. MODEL NUMBERS AND NOMINAL TONS LISTED SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER, MODEL NUMBERS, OR NOMINAL TONS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:

- A. REFER TO ROOFTOP UNIT CONTROL MATRIX FOR ADDITIONAL UNIT FEATURES, COMPONENTS, MODULES, ACCESSORIES, AND CONTROLS THAT SHALL BE PROVIDED WITH THE EQUIPMENT.
- B. EQUIPMENT SIZED FOR 100°F AMBIENT TEMPERATURE.
- C. PROVIDE 2" MERV 13, EFFICIENT PLEATED THROWAWAY AIR FILTERS.
- D. PROVIDE FACTORY MOUNTED DISCONNECT INSTALLED ON SERVICE SIDE OF UNIT.
- E. STARTERS FOR ALL MOTORS SHALL BE FURNISHED INTEGRAL WITH UNIT.
- F. PROVIDE FACTORY MOUNTED VARIABLE FREQUENCY DRIVE TO FACILITATE MODULATING FAN SPEED CONTROL.
- G. COORDINATE SIZE OF CONDUCTOR TERMINATION LUGS WITH CONDUCTOR SIZES SHOWN ON ELECTRICAL DRAWINGS.
- H. PROVIDE 125 VAC, 20 AMP DUPLEX CONVENIENCE RECEPTACLE MOUNTED TO UNIT READY FOR FIELD WIRING WITH A COVER UL LISTED FOR WET AND DAMPER LOCATIONS WHEN IN USE.
- I. SPECIFIED FAN ESP ACCOUNTS FOR DUCT LOSSES EXTERNAL TO UNIT.
- J. PROVIDE MOTOR HORSEPOWER TO OVERCOME INTERNAL UNIT STATIC PRESSURE DROP PLUS SPECIFIED EXTERNAL STATIC PRESSURE DROP. NOMINAL MOTOR HP SHALL BE NO LARGER THAN THE FIRST AVAILABLE NOMINAL MOTOR SIZE GREATER THAN THE REQUIRED BHP.
- K. PROVIDE INSULATED ROOF CURB WITH MINIMUM HEIGHT REQUIRED TO MAINTAIN BOTTOM OF EQUIPMENT A MINIMUM OF 14 INCHES ABOVE FINISHED ROOF SURFACE. PROVIDE SLOPED CURB IF NEEDED TO MATCH ROOF SLOPE. COORDINATE WITH ROOF INSULATION THICKNESS AND ROOF TAPER AT INSTALLED LOCATION. COORDINATE CURB TYPE WITH DRAWINGS.
- L. SCHEDULED WEIGHT IS THE MAXIMUM ALLOWABLE OPERATING WEIGHT OF THE EQUIPMENT AND CURB.
- M. COOLING COIL LAT IS LEAVING AIR TEMPERATURE OF COIL.
- N. PROVIDE GUARDS TO PROTECT CONDENSER COIL FROM HAIL OR OTHER DAMAGE.
- O. PROVIDE HEATER TO MEET OR EXCEED SCHEDULED MINIMUM MBH OUTPUT. NOMINAL KW IS BASED ON LISTED MANUFACTURER'S STANDARD PRODUCT. COORDINATE EQUIPMENT POWER SUPPLY WITH ELECTRICAL CONTRACTOR IF DIFFERENT FROM THAT SCHEDULED.
- P. SELECT EQUIPMENT FOR ELEVATION OF 0 FEET ABOVE SEA LEVEL.

SEQUENCE OF OPERATION	
A. FAN COIL UNIT CONTROL	During occupied hours, operate fan coil unit supply fan continuously and open outdoor air damper to maintain minimum ventilation. Cycle stages of DX cooling and electric heating to maintain room thermostat set point (75 degrees Fahrenheit cooling, 70 degrees Fahrenheit heating). Unit shall be shutdown upon alarm signal from FACP.
B. RESTROOM EXHAUST FAN (EF-1) CONTROL	During unoccupied hours, cycle the fan coil unit supply fan and cooling or heating system to maintain unoccupied setback temperature set points. Outdoor air damper shall be closed during unoccupied hours.
C. KITCHEN EXHAUST FAN CONTROL	Kitchen exhaust fan shall be interlocked to operate with cooking appliances, make-up air and other air-handling equipment providing fresh air to the kitchen area as noted or scheduled on the drawings.
D. ROOFTOP UNIT CONTROL	Refer to ROOFTOP UNIT CONTROL MATRIX on Sheet M001 for required rooftop unit control options.
E. AIR CURTAIN CONTROL	Interlock air curtain with door limit switch to energize when the door opens.

## FAN COIL UNIT SCHEDULE (HEAT PUMP)

LANDLORD PROVIDED EQUIPMENT. SCHEDULE FOR REFERENCE ONLY																								
MARK	MANUFACTURER	MODEL	SUPPLY FAN				COOLING COIL				HEAT PUMP HEATING COIL				ELECTRICAL									
			CFM	ESP (IN)	NOM HP	VFD (Y/N)	TH	SH (MBH)	EAT (°F DB)	LAT (°F WB)	REFR TYPE	MIN EFF (EER)	MIN OUT (MBH)	NOM INPUT (MBH)	MIN EFF (%)	EAT (°F DB)	LAT (°F WB)	MIN OA (CFM)	V/PH	MCA	MOC/P	DISC TYPE	WEIGHT (LBS)	NOTES
(E) FCU 1	CARRIER	40MBCO18	420	0.03	0.06	11.4	99.5	76.8	63.8	55.3	54.8	R410A	8.9	21	65	85	40	248 / 1	0	0	NF	N/A	45	A-G

\*EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION. MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:

- A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS.
- B. ASSOCIATED CONDENSING UNIT SHALL BE BY THE SAME MANUFACTURER.
- C. FOR COOLING, EQUIPMENT SIZES FOR 100°F AMBIENT TEMPERATURE. HEAT PUMP HEATING CAPACITY BASED ON AMBIENT TEMPERATURE LISTED.
- D. PROVIDE UNIT WITH CLEANABLE AIR FILTERS.
- E. PROVIDE WITH 7-DAY PROGRAMMABLE THERMOSTAT WITH STAGED HEATING AND COOLING CAPABILITY AS REQUIRED FOR OPERATION OF AUXILIARY HEATING AND COOLING CONTROLS.
- F. DISCONNECT SWITCH PROVIDED BY DIVISION 26 CONTRACTOR.
- G. DISCONNECT SWITCH PROVIDED BY DIVISION 26 CONTRACTOR.
- H. PROVIDE SINGLE POINT POWER CONNECTION.

## CONDENSING UNIT SCHEDULE (HEAT PUMP)

LANDLORD PROVIDED EQUIPMENT. SCHEDULE FOR REFERENCE ONLY																	
MARK	SERVICE	MANUFACTURER	MODEL	REFR TYPE	TH	COOLING CAPACITY				HEATING CAPACITY				ELECTRICAL			
						MIN EFF (EER)	(SEER)	CAP (MBH)	AMBIENT (DB °F)	COP 47°F	(HSPF)	MIN EFF (EER)	(SEER)	CAP (MBH)	AMBIENT (DB °F)	MCA	MOC/P
(E) CU 1	(E) FCU 1	CARRIER	38MARBQ18AA3	R410A	11.4	12.5	20	99.5	21.0	3.43	10.5	18	25	208/1	NF	118	A-1

\*EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION. MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:

- A. EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE. REF ARCHITECTURAL DRAWINGS.
- B. EQUIPMENT CAPACITY SCHEDULED IS MINIMUM CAPACITY THAT MUST BE PROVIDED AT AMBIENT TEMPERATURE INDICATED.
- C. CONTRACTOR SHALL VERIFY WITH EQUIPMENT SUPPLIER EXACT QUANTITY AND SIZE OF REFRIGERANT PIPING.
- D. PROVIDE LEAD LINE AND FILTER DRYER AND SIGHT GLASS.
- E. PROVIDE PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS WITH MINIMUM HEIGHT REQUIRED TO MAINTAIN BOTTOM OF EQUIPMENT A MINIMUM OF 16 INCHES ABOVE FINISHED ROOF SURFACE.
- F. COORDINATE WITH ROOF INSULATION THICKNESS AND ROOF TAPER AT INSTALLED LOCATION.
- G. DISCONNECT SWITCH PROVIDED BY DIVISION 26 CONTRACTOR.
- H. STARTERS FOR ALL MOTORS SHALL BE PROVIDED INTEGRAL WITH UNIT.
- I. COORDINATE SIZE OF CONDUCTOR TERMINATION LUGS WITH CONDUCTOR SIZES SHOWN ON ELECTRICAL DRAWINGS.
- J. EQUIPMENT SIZED FOR 100 °F AMBIENT TEMPERATURE.

## AIR CURTAIN SCHEDULE

MARK	AREA SERVED	MANUFACTURER	MODEL	UNIT SPECS				ELECTRICAL				
				LENGTH (IN)	MAX AIRFLOW (CFM)	FAN QUANTITY	MOTOR HP	V/PH	DISC TYPE	WEIGHT (LBS)	NOTES	
AC 1	SERVED ENTRY	BERNER	CLC08-1042A	42"	1176	1	0.20	120/1				A



COMcheck Software Version COMcheckWeb  
Mechanical Compliance Certificate

Project Information

Energy Code: 2015 IECC  
Project Title: Shake Shack - Concord Mills  
Location: Concord (Cabarrus), North Carolina  
Climate Zone: 3a  
Project Type: Alteration

Construction Site: Owner/Agent: Bergmeyer  
51 Sleeper Street, 6th Floor  
Boston, Massachusetts 02210  
617.542.1025  
Designer/Contractor: HNY Consulting Engineers  
240 West 37th Street, 3rd Floor  
New York, New York 10018  
212.413.8400

Efficiency Packages

Description: Credit

Mechanical Systems List

Quantity System Type & Description  
3 WH-1, WH-2, WH-3  
Gas Instantaneous Water Heater, Capacity: 0 gallons, Input Rating: 199 kBtu/h w/ Circulation Pump  
Proposed Efficiency: 95.00 EF, Required Efficiency: 0.62 EF

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical alteration project represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2015 IECC requirements in COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Eion Hindsman-Curry  
Name - Title Signature Date 01/10/2025

Project Title: Shake Shack - Concord Mills Report date: 01/10/25  
Data filename: Page 1 of 5

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C404.3 [F111]	Heat traps installed on supply and discharge piping of non-circulating systems.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.4 [F125]	All piping insulated in accordance with section details and Table C403.2.10.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.6.1 [F112]	Controls are installed that limit the operation of a recirculation pump installed to maintain temperature of a storage tank. System return pipe is a dedicated return pipe or a cold water supply pipe.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C406.7.1 [F133]	Enhanced Service Water Heat System efficiency package. One of the following SWH system enhancements must satisfy 60 percent of hot water requirements, or 100 percent of the building otherwise complies with heat recovery per Section C403.4.5: Waste heat recovery from SWH, process equipment, or combined heat and power system), OR solar water-heating.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

Project Title: Shake Shack - Concord Mills Report date: 01/10/25  
Data filename: Page 5 of 5



COMcheck Software Version COMcheckWeb  
Inspection Checklist

Energy Code: 2015 IECC

Requirements: 100.0% were addressed directly in the COMcheck software

Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Plan Review	Complies?	Comments/Assumptions
C103.2 [PR3]	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the service water heating systems and equipment and document where exceptions to the standard are claimed. Hot water system sized per manufacturer's sizing guide.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

Project Title: Shake Shack - Concord Mills Report date: 01/10/25  
Data filename: Page 2 of 5

Section # & Req.ID	Plumbing Rough-In Inspection	Complies?	Comments/Assumptions
C404.5, C404.5.1, C404.5.2 [PL6]	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.6.1, C404.6.2 [PL3]	Automatic time switches installed to automatically switch off the recirculating hot-water system or heat trace.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.6.3 [PL7]	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.7 [PL8]	Water distribution system that pumps water from a heated-water supply pipe back to the heated-water source through a cold-water supply pipe is a demand recirculation water system. Pumps within this system have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

Project Title: Shake Shack - Concord Mills Report date: 01/10/25  
Data filename: Page 3 of 5

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C402.2.6 [ME41]	Thermally ineffective panel surfaces of sensible heating panels have insulation >= R-3.5.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.6 [ME115]	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.8 [ME126]	Kitchen exhaust systems comply with replacement air and conditioned supply air limitations, and satisfy hood rating requirements and maximum exhaust rate criteria.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.2.1 [MES3]	Air outlets and zone terminal devices have means for air balancing.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.1 [ME123]	Refrigerated display cases, walk-in coolers or walk-in freezers served by remote compressors and remote condensers not located in a condensing unit, have fan-powered condensers that comply with Sections C403.5.1 and refrigeration compressor systems that comply with C403.5.2.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

Project Title: Shake Shack - Concord Mills Report date: 01/10/25  
Data filename: Page 4 of 5



800 South Figueroa St.  
Los Angeles, CA 90017  
213.337.1090  
www.bergmeyer.com

CONSULTANTS:  
**HNY**  
CONSULTING ENGINEERS  
240 WEST 37TH STREET, 3RD FLOOR  
NEW YORK, NY 10018  
TEL: 212.413.8400  
www.hnyeng.com  
245002084  
NC CORPORATE NO. P-2451  
EXPIRES 6/30/2026

SEAL SIGNATURE:  
  
10/13/2025

NO.	BY	DATE	DESCRIPTION
1	HNY	2025-10-13	IFC SET
A	HNY	2025-04-15	ADDENDUM A
	HNY	2025-02-03	PERMIT SET
	HNY	2025-01-13	75% SET



SHAKE SHACK CONCORD MILLS


8031 CONCORD MILLS BLVD  
CONCORD, NC 28027, SUITE 103  
SHACK #1630

IFC SET

MECHANICAL ENERGY CODE COMPLIANCE

DRAWN BY: Author  
CHECKED BY: Checker  
JOB NO: 20240321.00

M-630



HANGING ANGLE DETAILS			
HOOD STYLE / MODEL	450 DEGREES cfm/ft.	600 DEGREES cfm/ft.	700 DEGREES cfm/ft.
CANOPY ND-2	150	200	250
CANOPY ND-2 w/ END PANELS	105	140	175
SLOPED SHD-2	228	294	-
ISLAND ND-2MI	269	300	350
ISLAND ND-2I	346	422	475

ETL HOOD LISTING DETAIL			
EXHAUST CFM = LENGTH OF HOOD X CFM/IN/FT. (LOAD)			
SUPPLY CFM = EXHAUST CFM X PERCENTAGE REQUIRED			
TOTAL DUCT AREA (sq. in.) = 144 X _____ CFM			
DUCT LENGTH = _____ TOTAL DUCT AREA			
DUCT WIDTH = _____			

40°F TO 180°F VENTILATION SET POINTS ARE CALCULATED USING AN EXHAUST VELOCITY OF 1500-1800 FPM AND A SUPPLY VELOCITY OF 1000 FPM.

**CAPTIVE-AIRE HOODS BUILT IN COMPLIANCE WITH:**

ETL LISTED UNDER ETL File number 3054804-001/002

BUILDING CODES	
CAPTIVE-AIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:	
MATERIAL	CLEARANCE REDUCTION SYSTEM
NON-COMBUSTIBLE	NONE REQUIRED
LIMITED-COMBUSTIBLE	3" UNINSULATED STANDOFF
COMBUSTIBLE	1" INSULATED STANDOFF



CLEARANCE TO COMBUSTIBLES	
HOODS #	SURFACE *CLEARANCE
1	TOP 18"
	FRONT 0"
	BACK 0"
	LEFT 18"
2	RIGHT 18"
	TOP 18"
	FRONT 0"
	BACK 0"
	LEFT 0"
	RIGHT 18"

- INSTALLATION**
- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
  - ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
  - HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGING MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
  - ALL CONNECTIONS FROM CAPTIVE-AIRE HOOD PER MECHANICAL CONTRACTOR'S PLANS.
  - COOKING EQUIPMENT TO SHUT OFF IN EVENT OF FIRE. EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
  - ALL LIGHT FIXTURES SHOWN INSTALLED BY CAPTIVE-AIRE ARE FACTORY PROVIDED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES ARE BY ELECTRICAL CONTRACTOR. LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
  - SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
  - INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTERPRETATION AND ADMINISTRATION OF FIELD REQUIREMENTS IN FIELD PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.

**GENERAL NOTES**

1. WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.

2. SIZES AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE USED BY THE FACTORY PRIOR TO PRODUCTION.



**FILTER DETAIL**

FOR QUESTIONS, CALL THE  
Eastern PA Mechanical  
REGION 108  
PHONE: (267) 504 - 4126  
EMAIL: reg108@captiveaire.com



HOOD INFORMATION - JOB#7210583																		
HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST PLENUM FILTER(S)				HOOD CONSTRUCTION	HOOD CONFIG END TO END	ROW		
										WIDTH	LENG	HEIGHT	DIA				CFM	VEL
1	Hood (Grill)	S430 ND-2	CAPTIVEAIRE	5' 0"	450 DEG	I	MEDIUM	150	750	9'	8'	4'	750	1500	-0.330"	430 SS WHERE EXPOSED	ALONE	ALONE
2	Hood (Fryer)	S430 ND-2	CAPTIVEAIRE	4' 0"	600 DEG	I	HEAVY	175	700	8'	8'	4'	700	1575	-0.375"	430 SS WHERE EXPOSED	ALONE	ALONE

HOOD INFORMATION															
HOOD NO	TAG	TYPE	QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE	UTILITY CABINET(S)		FIRE SYSTEM	HOOD HANGING WEIGHT
												FIRE SYSTEM	SIZE		
1	Hood (Grill)	CAPTRATE SOLD FILTER	3	20"	16"	85% SEE FILTER SPEC	2	RECESSED ROUND	ND						441 LBS
2	Hood (Fryer)	CAPTRATE SOLD FILTER	2	20"	20"	85% SEE FILTER SPEC	1	RECESSED ROUND	ND	LEFT	12"x54"x30"	TANK FS	4.0/4.0	SC-320110MA 1 LIGHT 1 FAN	622 LBS

HOOD OPTIONS		OPTION
1	Hood (Grill)	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT. INSULATION FOR BACK OF HOOD. RISER SENSOR INSTALL 6IN PLEN. LEFT VERTICAL END PANEL 27" TOP WIDTH, 21" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS. RIGHT WIDE VERTICAL END PANEL 42" TOP WIDTH, 36" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS. FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT. RIGHT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. LEFT QUARTER END PANEL 23" TOP WIDTH, 0" BOTTOM WIDTH, 23" HIGH 430 SS. INSULATION FOR BACK OF HOOD. RISER SENSOR INSTALL 6IN PLEN.
2	Hood (Fryer)	FIELD WRAPPER 18.00" HIGH FRONT, LEFT, RIGHT. INSULATION FOR BACK OF HOOD. RISER SENSOR INSTALL 6IN PLEN.

CLEARANCE TO COMBUSTIBLES		
HOODS #	SURFACE	*CLEARANCE
1	TOP	18"
	FRONT	0"
	BACK	0"
	LEFT	18"
2	RIGHT	18"
	TOP	18"
	FRONT	0"
	BACK	0"
	LEFT	0"
	RIGHT	18"

- \*0" CLEARANCE TO COMBUSTIBLES CONFORMS TO UL710 STANDARD.  
- HOOD MOUNTED UTILITY CABINETS REQUIRE 36" SERVICE CLEARANCE.



REVISIONS	
DESCRIPTION	DATE

Eastern PA Mechanical  
225 E City Line Avenue, Suite #103, Bala Cynwyd, PA 19004  
PHONE: (267) 504 - 4126  
EMAIL: reg108@captiveaire.com

Shake Shack-1630-Concord Mills (CKitchen)

DATE: 12/6/2024  
DWG.#: 7210583  
DRAWN BY: Joe.shilba  
SCALE: 3/4" = 1'-0"  
MASTER DRAWING  
SHEET NO. 1

**Bergmeyer**  
CONSULTANTS:  
SEAL SIGNATURE:  
FOR REFERENCE ONLY

8031 CONCORD MILLS BLVD  
CONCORD, NC 28027, SUITE 103  
SHACK #1630

IFC SET


CAPTIVEAIRE DRAWINGS

DRAWN BY: Author  
CHECKED BY: Checker  
JOB NO: 20240321.00

**M-701**

THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.


1" LAYER OF INSULATION FACTORY  
INSTALLED IN INTERNAL BACK STANDOFF.  
MEETS 0 INCH REQUIREMENTS FOR  
CLEARANCE TO COMBUSTIBLE SURFACES.




PLAN VIEW - HOOD #1 (Hood (Grill))  
5'-0 0/8" LONG 5430ND-2

⊕ ⊖ DUPLEX OUTLET


1" LAYER OF INSULATION FACTORY  
INSTALLED IN INTERNAL BACK STANDOFF.  
MEETS 0 INCH REQUIREMENTS FOR  
CLEARANCE TO COMBUSTIBLE SURFACES.



PLAN VIEW - HOOD #2 (Hood (Fryer))  
4'-0 0/8" LONG 5430ND-2



SECTION VIEW - MODEL 5430ND-2  
HOOD - #1 (Hood (Grill))



SECTION VIEW - MODEL 5430ND-2  
HOOD - #2 (Hood (Fryer))

REVISIONS	
DESCRIPTION	DATE

**CAPTIVEAIRE**  
www.captiveaire.com  
Eastern PA Mechanical  
225 E City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004 PHONE: (267) 504-4128 EMAIL: reg108@captiveaire.com


Shake Shack-1630-Concord Mills (CKKitchen)

DATE:	12/6/2024
DWG.#:	7210583
DRAWN BY:	Joe.shilba
SCALE:	3/4" = 1'-0"
MASTER DRAWING	
SHEET NO.	2


**Bergmeyer**

CONSULTANTS:

SEAL SIGNATURE:



NO.	BY	DATE	DESCRIPTION
1	HNY	2025-10-13	IFC SET
A	HNY	2025-04-15	ADDENDUM A
	HNY	2025-02-03	PERMIT SET
	HNY	2025-01-13	75% SET



SHAKE SHACK CONCORD MILLS

8031 CONCORD MILLS BLVD  
CONCORD, NC 28027, SUITE 103  
SHACK #1630

IFC SET

CAPTIVEAIRE DRAWINGS

DRAWN BY:	Author
CHECKED BY:	Checker
JOB NO.:	20240321.00

M-702

THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

**FIRE SYSTEM INFORMATION - JOB#7210583**

FIRE SYSTEM NO	TAG	TYPE	SIZE	MAX FP	DESIGN FP	INSTALLATION	
						SYSTEM	LOCATION ON HOOD
1		TANK FS	4.0/4.0	40	36	FIRE CABINET LEFT	LEFT, HOOD 2

**GAS VALVE(S)**

FIRE SYSTEM NO	TAG	TYPE	SIZE	SUPPLIED BY
1		SC ELECTRICAL	1.000	CAPTIVEAIRE SYSTEMS

**NOTES**

- FIELD PIPE DROPS AS SHOWN
- PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS
- FIELD INSTALLED DROP: FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
- SHIP LOOSE DROP: FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
- RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVEING, SALAMANDERS, ETC.
- OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
- IF APPLICABLE EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
- FACTORY PIPING EXTENDS A MAXIMUM OF 6' ABOVE THE TOP OF THE HOOD.

- APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.
- THIS FIRE SYSTEM COMPLIES WITH U.L. 300 REQUIREMENTS.

- DL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS

JOB #: 7210583  
 JOB NAME: SHAKE SHACK-1630-CONCORD MILLS, NC(KITCHEN).

SYSTEM SIZE: TANK-SP-2 DESIGN FP: 36, MAXIMUM FP: 40.  
 HOOD # 1 5' 0.00" LONG x 54" WIDE x 30" HIGH.  
 RISER # 1 SIZE: 9" x 8".  
 HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.  
 HOOD # 2 4' 0.00" LONG x 54" WIDE x 30" HIGH.  
 RISER # 1 SIZE: 8" x 8".  
 HOOD # 2 METAL BLOW-OFF CAPS INCLUDED.



- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

AGENT DISTRIBUTION PIPING LIMITATIONS	
PIPE SECTION	MAX PIPE LENGTH (FT)
MAX SUPPLY LINE TO FIRST OVERLAPPING NOZZLE	42
OVERLAPPING NOZZLE APPLIANCE BRANCH	10
DEDICATED NOZZLE APPLIANCE BRANCH	10


**LEGEND - FIRE CABINET TANK SYSTEM**

- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.

- SYSTEM REQUIRES A MINIMUM OF 7 FT OF EQUIVALENT PIPE LENGTH BETWEEN TANK AND NEAREST APPLIANCE NOZZLE FOR MOST APPLIANCES. EACH 90 DEGREE ELBOW ADDS 1.3 FT OF EQUIVALENT LENGTH. SEE MANUAL FOR DETAILS



REVISIONS	
DESCRIPTION	DATE



**CAPTIVEAIRE**  
 Eastern PA Mechanical  
 225 E City Line Avenue, Suite #103, Bala Cynwyd, PA, 19004  
 PHONE: (267) 804-4126 EMAIL: reg.08@captiveaire.com

Shake Shack-1630-Concord Mills, NC(Kitchen)

DATE: 12/6/2024  
 DWG.#: 7210583  
 DRAWN BY: joe.shilba  
 SCALE: 3/4" = 1'-0"  
 MASTER DRAWING

SHEET NO. 3

THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

**Bergmeyer**

CONSULTANTS:  
 SEAL SIGNATURE:  
 FOR REFERENCE ONLY

NO.	BY	DATE	DESCRIPTION
1	HNY	2025-10-13	IFC SET
A	HNY	2025-04-15	ADDENDUM A
	HNY	2025-02-03	PERMIT SET
	HNY	2025-01-13	75% SET



SHAKE SHACK CONCORD MILLS

8031 CONCORD MILLS BLVD  
 CONCORD, NC 28027, SUITE 103  
 SHACK #1630

IFC SET

CAPTIVEAIRE DRAWINGS

DRAWN BY:	Author
CHECKED BY:	Checker
JOB NO:	20240321.00

M-703

**EXHAUST FAN INFORMATION - JOB#7210583**

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	MANUFACTURER	CFM	ESP	RPM	MOTOR ENCL	HP	BHP	PHASE	VOLT	FLA	DISCHARGE VELOCITY	WEIGHT (LBS)	SINES
1	KEF(GRILL)	1	DU50HFA	CAPTIVEAIRE	750	1000	1423	TEAD-ECM	0.500	0.2980	1	208	3.8	285 FPM	79	14
2	KEF(FRYER)	1	DU50HFA	CAPTIVEAIRE	700	1000	1408	TEAD-ECM	0.500	0.2890	1	208	3.8	266 FPM	79	13.6

**FAN OPTIONS**

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	KEF(GRILL)	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - DU/DR50HFA - INSTALLED AT PLANT - FDR GREASE DUCTS
		1	ECM WIRING PACKAGE - EXHAUST - MODBUS CONTROL -MSC- (TELCD), CCW ROTATION
		1	2 YEAR PARTS WARRANTY
2	KEF(FRYER)	1	GREASE BOX
		1	ECM WIRING PACKAGE - EXHAUST - MODBUS CONTROL -MSC- (TELCD), CCW ROTATION
		1	FAN BASE CERAMIC SEAL - DU/DR50HFA - INSTALLED AT PLANT - FDR GREASE DUCTS
		1	2 YEAR PARTS WARRANTY


**FAN ACCESSORIES**

FAN UNIT NO	TAG	EXHAUST				SUPPLY		
		GREASE CUP	GRAVITY DAMPER	WALL MOUNT	SIDE DISCHARGE	GRAVITY DAMPER	MOTORIZED DAMPER	WALL MOUNT
1	KEF(GRILL)	YES						
2	KEF(FRYER)	YES						

**CURB ASSEMBLIES**

NO	IN FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	KEF(FRYER)	31 LBS	CURB	19.500"W X 19.500"L X 20.000"H HINGED.
2	# 2	KEF(FRYER)	31 LBS	CURB	19.500"W X 19.500"L X 20.000"H HINGED.

FANS #1 (KEF(GRILL)), #2 (KEF(FRYER)) - DU50HFA EXHAUST FAN



TOP VIEW

**FEATURES:**

- DIRECT DRIVE CONSTRUCTION (NO BELTS/PULLEYS).
- ROOF MOUNTED FANS.
- RESTAURANT MODEL.
- UL705 AND UL768 AND UL6-S645
- VARIABLE SPEED CONTROL.
- INTERNAL WIRING.
- THERMAL OVERLOAD PROTECTION (SINGLE PHASE).
- HIGH HEAT OPERATION 309°F (149°C).
- GREASE CLASSIFICATION TESTING.
- NEMA 3R SAFETY DISCONNECT SWITCH.




**NORMAL TEMPERATURE TEST**  
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING AIR AT 300°F (149°C) UNTIL ALL FAN PARTS HAVE REACHED THERMAL EQUILIBRIUM AND WITHOUT ANY DETERIORATING EFFECTS TO THE FAN WHICH WOULD CAUSE UNSAFE OPERATION.

**ABNORMAL FLARE-UP TEST**  
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING BURNING GREASE VAPORS AT 600°F (316°C) FOR A PERIOD OF 15 MINUTES WITHOUT THE FAN BECOMING DAMAGED TO ANY EXTENT THAT COULD CAUSE AN UNSAFE CONDITION.

**OPTIONS:**


- GREASE BOX
- FAN BASE CERAMIC SEAL - DU/DR50HFA - INSTALLED AT PLANT - FDR GREASE DUCTS.
- ECM WIRING PACKAGE - EXHAUST - MODBUS CONTROL -MSC- (TELCD), CCW ROTATION.
- 2 YEAR PARTS WARRANTY.

DUCTWORK BETWEEN EXHAUST RISER ON HOOD AND FAN (BY OTHERS).



**REVISIONS**

NO.	DESCRIPTION	DATE
1		
2		
3		
4		



Shake Shack-1630-Concord Mills (Kitchen)

DATE: 12/6/2024  
 DWG.#: 7210583  
 DRAWN BY: Joe.shilba  
 SCALE: 3/4" = 1'-0"  
 MASTER DRAWING  
 SHEET NO. 4

THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.

**Bergmeyer**

CONSULTANTS:

SEAL SIGNATURE:

FOR REFERENCE ONLY

1 HNY 2025-10-13 IFC SET  
 A HNY 2025-04-15 ADDENDUM A  
 HNY 2025-02-03 PERMIT SET  
 HNY 2025-01-13 75% SET

NO. BY DATE DESCRIPTION

**SHAKE SHACK**

SHAKE SHACK CONCORD MILLS

8031 CONCORD MILLS BLVD  
 CONCORD, NC 28027, SUITE 103  
 SHACK #1630

IFC SET

CAPTIVEAIRE DRAWINGS



DRAWN BY: Author  
 CHECKED BY: Checker  
 JOB NO: 20240321.00

**M-704**

800 South Figueroa St.  
 Los Angeles, CA 90017  
 213.337.1090  
 www.bergmeyer.com

3800 N High St.  
 Columbus, OH 43210  
 617.542.1025  
 380.900.8887









Instructions below outline single, or dual, one gallon grease cup installation for ND-2 hood models.

The one gallon grease cup comes as an assembly of stainless steel wall mounting bracket and one gallon cup. The mounting bracket should be installed 2" from the edge of the containment plenum and 3"-4" below the bottom of the hood.

Piping from the hood grease drain should route to the opening of the grease cup, but not into the cup, otherwise the cup will not be able to be removed and emptied.



REVISIONS	
DESCRIPTION	DATE



Shake Shack-1630-Concord Mills, NC(Kitchen)

DATE:	12/6/2024
DWG.#:	7210583
DRAWN BY:	Joe.shilba
SCALE:	3/4" = 1'-0"
MASTER DRAWING	
SHEET NO.	6

**Bergmeyer**

BCS  
Shelton St.  
Boston, MA 02210  
617.542.1025

CO  
875 N High St.  
Columbus, OH 43215  
380.900.8867

LA  
800 South Figueroa St.  
Los Angeles, CA 90017  
213.337.1090

www.bergmeyer.com


CONSULTANTS:

SEAL SIGNATURE:

FOR REFERENCE ONLY

NO.	BY	DATE	DESCRIPTION
1	HNY	2025-10-13	IFC SET
A	HNY	2025-04-15	ADDENDUM A
	HNY	2025-02-03	PERMIT SET
	HNY	2025-01-13	75% SET

DATE:	12/6/2024
DWG.#:	7210583
DRAWN BY:	Joe.shilba
SCALE:	3/4" = 1'-0"
MASTER DRAWING	
SHEET NO.	6



SHAKE SHACK CONCORD MILLS

8031 CONCORD MILLS BLVD  
CONCORD, NC 28027, SUITE 103  
SHACK #1630

IFC SET

CAPTIVEAIR DRAWINGS

DRAWN BY: Author  
CHECKED BY: Checker  
JOB NO: 20240321.00

M-706

THE DOCUMENTATION CONTAINED ON THIS SHEET WAS NOT PREPARED BY HENDERSON ENGINEERS AND IS INCLUDED IN THIS SET FOR REFERENCE ONLY. HENDERSON ENGINEERS REVIEWED THE DOCUMENTATION ON THIS SHEET FOR GENERAL COMPLIANCE WITH DESIGN INTENT. SUPPLIER IS RESPONSIBLE THAT ALL FURNISHED EQUIPMENT ON THIS SHEET COMPLIES WITH APPLICABLE LOCAL, STATE, AND FEDERAL LAWS, CODES, AND REGULATIONS.