

MECHANICAL GENERAL NOTES:

- PRIOR TO SUBMITTING BID, VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH THE EXISTING CONDITIONS OF THE PROJECT. REVIEW THE GENERAL NOTES, SPECIFICATIONS AND OTHER DOCUMENTS. NOTIFY ARCHITECT, ENGINEER OR OWNER OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
- EXISTING CONDITIONS WERE TAKEN FROM ORIGINAL DRAWINGS AND SITE VISITS AND MAY NOT REFLECT EXACT "AS-BUILT" CONDITIONS. FIELD VERIFY EXISTING CONDITIONS PRIOR TO SUBMITTING FINAL BIDS. COORDINATE NEW WORK AND DEMOLITION WITH OTHER DISCIPLINES AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION.
- COORDINATE THE INSTALLATION OF THE MECHANICAL SYSTEMS WITH OTHER TRADES TO ENSURE A NEAT AND ORDERLY INSTALLATION. INSTALL DUCTWORK AND PIPING AS CLOSE TO STRUCTURE AS POSSIBLE. COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS. COORDINATE INSTALLATION OF DUCTWORK AND PIPING TO AVOID CONFLICTS WITH ELECTRICAL PANELS, LIGHTING FIXTURES, ETC. ANY MODIFICATIONS REQUIRED DUE TO LACK OF COORDINATION WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AT NO EXTRA COST TO THE OWNER.
- WHERE SHUTDOWN OF EXISTING SYSTEMS IS REQUIRED DURING NEW WORK, COORDINATE SHUTDOWN TIME AND DURATION WITH THE OWNER TO MINIMIZE DOWNTIME. NOTIFY OWNER SEVEN (7) DAYS PRIOR TO INTERRUPTION OF SERVICE.
- DURING INSTALLATION OF NEW WORK, AVOID DAMAGING EXISTING SURFACES AND EQUIPMENT TO REMAIN. REPAIR DAMAGE CAUSED DURING CONSTRUCTION AT NO EXTRA COST TO THE OWNER.
- PROVIDE TEMPORARY BARRIERS TO CONTAIN DUST AND DEBRIS RESULTING FROM THE PERFORMANCE OF THE WORK TO THE AREA WHERE WORK IS BEING PERFORMED.
- ALL MECHANICAL EQUIPMENT SHOWN ON THE MECHANICAL PLANS SHALL BE PROVIDED BY DIVISION 23 UNLESS OTHERWISE NOTED. PROVIDE APPROXIMATE LOCATIONS. FIELD MEASURE FINAL DUCTWORK AND PIPING LOCATIONS PRIOR TO CONSTRUCTION AND MAKE ADJUSTMENTS AS REQUIRED TO FIT THE DUCTWORK AND PIPING WITHIN THE AVAILABLE SPACE. VERIFY THAT FINAL EQUIPMENT LOCATIONS MEET MANUFACTURER'S RECOMMENDATIONS REGARDING SERVICE CLEARANCE AND PROPER AIRFLOW CLEARANCE AROUND EQUIPMENT.
- REFER TO ARCHITECTURAL DRAWINGS FOR RELATED CONSTRUCTION DETAILS AS APPLICABLE TO THE HVAC SYSTEM. VERIFY CHASES AND PENETRATIONS SHOWN ON ARCHITECTURAL DRAWINGS THAT ARE INTENDED FOR DUCTWORK AND PIPING MEET REQUIREMENTS.
- COORDINATE LOCATION OF ROOF MOUNTED HVAC EQUIPMENT AND ROOF PENETRATIONS WITH THE ARCHITECTURAL AND STRUCTURAL DRAWINGS.
- INDOOR AIR QUALITY MEASURES: PROTECT INSIDE OF (INSTALLED AND DELIVERED) DUCTWORK AND HVAC UNITS FROM EXPOSURE TO DUST, DIRT, PAINT AND MOISTURE. REPLACE INSULATION THAT HAS BECOME WET AT ANY TIME DURING CONSTRUCTION. DRYING THE INSULATION IS NOT ACCEPTABLE. SEAL ANY TEARS OR JOINTS OF INTERNAL FIBERGLASS INSULATION. REMOVE DEBRIS FROM CEILING/RETURN AIR PLENUM INCLUDING DUST. AN INDEPENDENT, PROFESSIONAL DUCT CLEANING COMPANY SHALL VACUUM CLEAN ANY DUCTWORK CONNECTED TO HVAC UNITS THAT WERE OPERATED DURING THE CONSTRUCTION PERIOD AFTER NEW FILTERS ARE INSTALLED AND PRIOR TO BLDG. OCCUPANCY. OVER TO THE OWNER. THE INTERNAL SURFACES AND ASSOCIATED COILS OF ANY HVAC UNITS THAT WERE OPERATED SHALL ALSO BE CLEANED.
- INSTALL DUCTWORK AND BUILDING COLUMN LINES UNLESS OTHERWISE SHOWN OR NOTED.
- OVERHEAD HANGERS AND SUPPORTS FOR EQUIPMENT, DUCTWORK AND PIPING SHALL BE FASTENED TO BUILDING JOISTS OR BEAMS. DO NOT ATTACH HANGERS AND SUPPORTS TO THE ABOVE FLOOR SLAB OR ROOF EXCEPT WHERE CONCRETE INSERTS IN CONCRETE SLABS ARE ALLOWED BY THE SPECIFICATIONS.
- COORDINATE LOCATION OF EQUIPMENT SUPPORTS WITH LOCATION OF EQUIPMENT ACCESS PANELS/DOORS TO ENABLE SERVICE OF EQUIPMENT AND/OR FILTER CLEANING.
- SEAL PENETRATIONS THROUGH THE BUILDING COMPONENTS IN ACCORDANCE WITH THE CONTRACT SPECIFICATIONS. FIREPROOF PENETRATIONS THROUGH FIRE RATED COMPONENTS IN ACCORDANCE WITH U.L. REQUIREMENTS.
- COORDINATE THE EXACT MOUNTING SIZE AND FRAME TYPE OF DIFFUSERS, REGISTERS AND GRILLES WITH THE SUPPLIER TO MEET THE CEILING, WALL AND DUCT INSTALLATION REQUIREMENTS.
- ADJUST LOCATION OF CEILING DIFFUSERS, REGISTERS AND GRILLES AS REQUIRED TO ACCOMMODATE FINAL CEILING GRID AND LIGHTING LOCATIONS.
- LOCATE AND SET THERMOSTATS AT LOCATIONS SHOWN ON PLANS. VERIFY EXACT LOCATIONS WITH ARCHITECT PRIOR TO BEAM/CEILING INSTALLATION. INSTALL DEVICES WITH TOP OF DEVICE AT MAXIMUM 48" AFF TO MEET ADA REQUIREMENTS UNLESS NOTED OTHERWISE ON PLANS. PROVIDE INSULATED BACKING FOR THERMOSTATS MOUNTED ON EXTERIOR BUILDING WALLS. INSTALL WIRING IN CONDUIT PROVIDED BY DIVISION 26. AT A MINIMUM, PROVIDE CONDUIT IN THE WALL FROM THE JUNCTION BOX TO 8" ABOVE THE CEILING.
- COORDINATE THE LOCATION AND ELEVATION OF WALL-MOUNTED DEVICES WITH PRESENTATION BOARDS, DISPLAY CABINETS, SHELVES OR OTHER COMPONENTS SHOWN ON THE ARCHITECTURAL DRAWINGS THAT ARE TO BE INSTALLED UNDER OTHER DIVISIONS. CONTRACTOR WILL NOT BE REIMBURSED FOR RELOCATION OF WALL-MOUNTED DEVICES CAUSED BY A LACK OF COORDINATION.
- PROVIDE A MANUAL BALANCING DAMPER IN EACH DUCT TAKEOFF FROM SUPPLY, RETURN, OUTDOOR, AND EXHAUST AIR DUCTS.
- PROVIDE A PREFABRICATED 45 DEGREE, HIGH EFFICIENCY, RECTANGULAR/ROUND BRANCH DUCT TAKEOFF FITTING FOR BRANCH DUCT CONNECTIONS AND TAKE-OFFS TO INDIVIDUAL DIFFUSERS, REGISTERS AND GRILLES. PROVIDE WITH INTEGRAL MANUAL BALANCING DAMPER AND LOCKING QUADRANT WHERE INDICATED ON PLANS.
- BRANCH DUCTWORK TO AIR OUTLETS SHALL BE SAME SIZE AS OUTLET NECK SIZE UNLESS OTHERWISE NOTED.
- REFER TO SPECIFICATIONS FOR DUCTWORK AND PIPING INSULATION REQUIREMENTS. DUCT SIZES ON MECHANICAL PLANS INDICATE CLEAR INSIDE AIRFLOW DIMENSIONS. INCREASE SHEET METAL SIZES ACCORDINGLY TO ACCOUNT FOR THICKNESS OF DUCT LINER.
- FLEXIBLE DUCTWORK SHALL NOT EXCEED 5'-0" IN LENGTH AND SHALL BE INSTALLED AND SUPPORTED TO AVOID SHARP BENDS AND SAGGING. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- PROVIDE WALL MOUNTED LOUVERS AND DAMPERS WITH SUITABLE MOUNTING FRAME TO MATCH WALL CONSTRUCTION. COORDINATE WITH ARCHITECTURAL DRAWINGS.
- PROVIDE A NEW SET OF AIR FILTERS IN UNITS PRIOR TO TESTING, ADJUSTING AND BALANCING AND BEFORE TURNING SYSTEM(S) OVER TO OWNER.
- FIELD VERIFY THAT THE EXISTING EQUIPMENT INCLUDING ACCESSORIES BEING REUSED FOR THIS PROJECT IS NOT DAMAGED AND IS IN GOOD WORKING ORDER. REPORT ANY DEFICIENCIES TO THE OWNER OR ARCHITECT. SUBMIT TO THE OWNER AND ARCHITECT A WRITTEN REPORT DESCRIBING TESTS PERFORMED TO VERIFY OPERATION AND RESULTS OF THE TESTS.
- CLEAN EXISTING EQUIPMENT AND EQUIPMENT COMPONENTS BEING REUSED FOR THIS PROJECT. PROVIDE NEW FILTERS FOR EXISTING AIR HANDLING EQUIPMENT PRIOR TO STARTUP OF EQUIPMENT. NEW FILTERS SHALL BE COMPATIBLE WITH THE EXISTING EQUIPMENT AND EQUAL IN PERFORMANCE TO THE EXISTING FILTERS AT NEW CONDITION UNLESS OTHERWISE NOTED. CLEAN STRAINERS IN PIPING SYSTEMS PRIOR TO STARTING PUMPS.
- LUBRICATE EXISTING EQUIPMENT BEING REUSED FOR THIS PROJECT IN ACCORDANCE WITH MANUFACTURER'S WRITTEN INSTRUCTIONS. OBTAIN INSTRUCTIONS FROM MANUFACTURER IF THEY ARE NOT AVAILABLE AT THE SITE.
- FULLY CHARGE EXISTING REFRIGERANT SYSTEMS BEING REUSED FOR THIS PROJECT IN ACCORDANCE WITH MANUFACTURER'S WRITTEN INSTRUCTIONS. CHARGE SYSTEMS WITH NEW REFRIGERANT MATCHING EXISTING.

MECHANICAL SYMBOLS

THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS OR ABBREVIATIONS ARE USED.

STANDARD MOUNTING HEIGHT		HVAC DUCTWORK AND ACCESSORIES	
THERMOSTATS (USER ADJUSTABLE)(TOP OF DEVICE)	48"	LINEAR SLOT DIFFUSER	
CONTROLS (TOP OF DEVICE)	48"	INSULATED FLEXIBLE DUCT (MAX. 5'-0" LONG)	
USE THE DEFAULT MOUNTING HEIGHTS SHOWN ABOVE UNLESS NOTED OTHERWISE IN THE SPECIFICATIONS OR ELSEWHERE. MOUNTING HEIGHTS LISTED ARE ABOVE FINISHED FLOOR (AFF) OR ABOVE FINISHED GRADE (AFG) TO TOP OF DEVICE. ALL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH CURRENT ADA AND LOCAL REQUIREMENTS.		ELBOW WITH TURNING VANES	
ANNOTATION		BRANCH DUCT WITH BELL-MOUTH FITTING & MANUAL VOLUME CONTROL DAMPER	
	MECHANICAL PLAN NOTE CALLOUT	RETURN, EXHAUST, OR OUTSIDE AIR DUCT UP	
	MECHANICAL EQUIPMENT DESIGNATION (CONTRACTOR FURNISHED AND INSTALLED UNLESS NOTED OTHERWISE)	RETURN, EXHAUST, OR OUTSIDE AIR DUCT DOWN	
	CONNECTION POINT OF NEW WORK TO EXISTING	SUPPLY AIR DUCT UP	
	DETAIL REFERENCE. UPPER NUMBER INDICATES DETAIL NUMBER LOWER NUMBER INDICATES SHEET NUMBER	SUPPLY AIR DUCT DOWN	
	SECTION CUT DESIGNATION	EQUIPMENT WITH FLEXIBLE DUCT CONNECTION	
ABBREVIATIONS		10" (NECK SIZE) CSD-1 (TYPE) 300 CFM (CFM OF SUPPLY DIFFUSER OR REGISTER)	
A/C	AIR CONDITIONING	HWP	HEATING WATER PUMP
ACC	AIR COOLED CHILLER	IW/WC	INCHES OF WATER COLUMN
ACCU	AIR COOLED CONDENSING UNIT	L	LOUVER
AFC	ABOVE FINISHED CEILING	LAT	LEAVING AIR TEMPERATURE
AFF	ABOVE FINISHED FLOOR	LDB	LEAVING DRY BULB
AFG	ABOVE FINISHED GRADE	LP	LOW PRESSURE
AHJ	AUTHORITY HAVING JURISDICTION	LWB	LEAVING WET BULB
AHU	AIR HANDLING UNIT	LWT	LEAVING WATER
AI	ANALOG INPUT	MAU	MAKE-UP AIR UNIT
AO	ANALOG OUTPUT	MAX	MAXIMUM
AP	ACCESS PANEL	MIBH	1000 BTU PER HOUR
APP	AIR PRESSURE DROP	MD	MOTORIZED DAMPER
AWG	AMERICAN WIRE GAUGE	MFR	MANUFACTURER
B	BOILER	MIN	MINIMUM
BAS	BUILDING AUTOMATION SYSTEM	N/A	NOT APPLICABLE
BB	BACKBONE	NC	NORMALLY CLOSED
BD	BACKDRAFT DAMPER	N/O	NORMALLY OPEN
BD	BLOWDOWN	NOM	NOMINAL
BFC	BELOW FINISHED CEILING	NC	NOISE CRITERIA
BFF	BELOW FINISHED FLOOR	NF	NOT IN CONTRACT
BFG	BELOW FINISHED GRADE	NIC	NOT IN CONTRACT
BFP	BOILER FEED PUMP	OA	OUTSIDE AIR
BHP	BRAKE HORSEPOWER	PCV	PRESSURE INDEP. CONTROL VALVE
BI	BINARY INPUT	PROVIDE	FURNISH AND INSTALL
BO	BINARY OUTPUT	RA	RETURN AIR
BOD	BOTTOM OF DUCT	RC	ROOM CRITERIA
BOS	BOTTOM OF STRUCTURE	RD	RETURN DUCT
BTU	BRITISH THERMAL UNIT	RE	RELIEF AIR
CFM	CUBIC FEET PER MINUTE	REA	RELIEF AIR
CH	CHILLER	RF	RETURN FAN
CLG	COOLING	RFR	REFRIGERANT
CP	CONDENSATE PUMP	RH	RELATIVE HUMIDITY
CPT	CONTROL POWER TRANSFORMER	RI	ROOM INCHES PER MINUTE
CRAC	COMPUTER ROOM AIR CONDITIONING UNIT	RTU	ROOFTOP UNIT
CRU	COMPUTER ROOM UNIT	SA	SUPPLY AIR
CU	CONDENSING UNIT	SC	STEAM CONDENSATE PUMP
CHWP	CHILLED WATER PUMP	SD	SMOKE DUCT DETECTOR
DB	DECIBELS	SD	SUPPLY DUCT
DBA	DECIBEL AVERAGE	SH	SENSIBLE HEAT CAPACITY
DDC	DIRECT DIGITAL CONTROL	SOW	SCOPE OF WORK
DDC	DIRECT DIGITAL CONTROL	ST	STATIC PRESSURE
DISC	DISCONNECT	ST	STEAM TRAP
DN	DOWN	STM	STEAM
DX	DIRECT EXPANSION	TD	TO BE DETERMINED
(E)	EXISTING	TC/C	TEMPERATURE CONTROLS
EAT	ENTERING AIR	TCP	TEMPERATURE CONTROL PANEL
EAT	ENTERING	TF	TRANSFER FAN
ED	AIR TEMPERATURE	TFA	TO FLOOR ABOVE
EDB	EXHAUST DUCT	TFB	TO FLOOR BELOW
ED	EXHAUST FAN	TH	TOTAL HEAT CAPACITY
EF	EFFICIENCY	TSP	TOTAL STATIC PRESSURE
EMS	ENERGY MANAGEMENT SYSTEM	TT	TEMPERATURE TRANSMITTAL
ESP	INTERNAL STATIC PRESSURE	U/F	UNDERFLOOR
ETR	EXISTING TO REMAIN	U/G	UNDERGROUND
EWB	ENTERING WATER TEMPERATURE	U/S	UNIT HEATER
EWB	ENTERING WATER TEMPERATURE	UH	UNIT HEATER
FF	FEET PER MINUTE	UNO	UNLESS NOTED OTHERWISE
FF	FEET PER MINUTE	U/V	UNDER FLOOR VOLUME
FF	FEET PER MINUTE	VEL	VELOCITY
FPI	FINS PER INCH	VFD	VARIABLE FREQUENCY DRIVE
FPM	FEET PER MINUTE	VRF	VARIABLE REFRIGERANT FLOW
GC	GENERAL CONTRACTOR	VRV	VARIABLE REFRIGERANT VOLUME
GPM	GALLONS PER MINUTE	W/	WITH
HOA	HAND-OFF-AUTOMATIC	W/O	WITHOUT
HP	HORSEPOWER	WB	WET BULB
HTG	HEATING	WC	WATER COLUMN
		WPD	WATER PRESSURE DROP
		XP	EXPLOSION PROOF

ALL DUCT DIMENSIONS SHOWN ON DRAWINGS ARE INSIDE DIMENSIONS. REFER TO DUCTWORK SPECIFICATIONS FOR DUCTWORK INSULATION AND LINER INFORMATION.

HVAC CONTROL DEVICES	
	HUMIDISTAT
	THERMOSTAT
	STATIC PRESSURE SENSOR
	TEMPERATURE SENSOR
	VELOCITY
	CARBON MONOXIDE SENSOR
	CARBON DIOXIDE SENSOR
	DIFFERENTIAL PRESSURE SENSOR
	FLOW SWITCH
	HUMIDITY SENSOR
	PULL STATION

PIPING SYMBOLS		PIPING LINETYPES	
	DIRECTION OF FLOW		CONDENSATE DRAIN (CD)
	CONTROL VALVE		AUXILIARY CONDENSATE DRAIN (ACD)
	THREE-WAY CONTROL VALVE		NON-POTABLE WATER (NPW)
	SHUTOFF VALVE		NATURAL GAS (G)
	CHECK VALVE		NATURAL GAS ON ROOF (G)
	BALANCING VALVE WITH PRESSURE PORTS		MEDIUM PRESSURE NATURAL GAS (MPG)
	TRIPLE DUTY VALVE WITH PRESSURE PORTS		MEDIUM PRESSURE NATURAL GAS ON ROOF (MPG)
	STRAINER		FUEL OIL SUPPLY (FOS)
	STRAINER WITH BLOWDOWN VALVE		FUEL OIL RETURN (FOR)
	RELIEF / SAFETY VALVE		FUEL OIL VENT (FOV)
	SOLENOID VALVE		LIQUEFIED PETROLEUM GAS (LPG)
	PRESSURE REDUCING VALVE		BOILER FEED WATER (BFW)
	GAS PRESSURE REGULATOR		HIGH PRESSURE STEAM SUPPLY (HPS)
	THERMOSTATIC MIXING VALVE		HIGH PRESSURE STEAM CONDENSATE (HPC)
	PIPE ANCHOR		MEDIUM PRESSURE STEAM SUPPLY (MPS)
	EXPANSION JOINT		MEDIUM PRESSURE STEAM CONDENSATE (MPC)
	PIPE GUIDE		LOW PRESSURE STEAM SUPPLY (LPS)
	PIPING SUPPORT		LOW PRESSURE STEAM CONDENSATE (LPC)
	F & T TRAP		CONDENSATE PUMP DISCHARGE (PD)
	BUCKET TRAP		HEATING HOT WATER SUPPLY (HWS)
	THERMOSTATIC TRAP		HEATING HOT WATER RETURN (HWR)
	BACKFLOW PREVENTER		CHILLED WATER SUPPLY (CHWS)
	PRESSURE GAUGE		CHILLED WATER RETURN (CHR)
	THERMOMETER		HOT / CHILLED WATER SUPPLY (HCS)
	PRESSURE AND TEMPERATURE TEST PLUG		HOT / CHILLED WATER SUPPLY (HCR)
	UNION		CONDENSER WATER SUPPLY (CWS)
	FLANGE CONNECTION		CONDENSER WATER RETURN (CWR)
	VACUUM RELIEF VALVE		HEAT PUMP WATER SUPPLY (HPWS)
	AUTOMATIC AIR VENT		HEAT PUMP WATER RETURN (HPWR)
	MANUAL AIR VENT		REFRIGERANT LIQUID (RL)
	PRESSURE / VACUUM SWITCH		REFRIGERANT DISCHARGE (HOT GAS) (RD)
	CLEANOUT		REFRIGERANT SUCTION (RS)
	CAP		REFRIGERANT DISCHARGE BYPASS (RDB)
	ELBOW UP		REFRIGERANT VENT (RV)
	ELBOW DOWN		
	TEE UP		
	TEE DOWN		
	ELBOW UP WITH SHUT-OFF VALVE (SOV)		
	ELBOW DOWN WITH SHUT-OFF VALVE (SOV)		
	TEE UP WITH SHUT-OFF VALVE (SOV)		
	TEE DOWN WITH SHUT-OFF VALVE (SOV)		
	REDUCER		
	RECIRCULATION PUMP		
	P-TRAP		
	GAS COCK		
	TOP BEAM CLAMP		
	TRAPEZE HANGER		

LINETYPE LEGEND	
	EXISTING
	DEMOLISH
	NEW
	FUTURE

MECHANICAL DEMOLITION GENERAL NOTES:


- COORDINATE ALL DEMOLITION WITH WHAT IS SHOWN ON ARCHITECTURAL PLANS. NOTIFY ARCHITECT OF ANY DISCREPANCIES.
- PRIOR TO SUBMITTING BID, VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH THE EXISTING CONDITIONS OF THE PROJECT. REVIEW GENERAL NOTES, SPECIFICATIONS AND OTHER DRAWINGS FOR ADDITIONAL REQUIREMENTS THAT MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY ARCHITECT, ENGINEER OR OWNER, AS DEFINED IN BID DOCUMENTS, OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
- OWNER RETAINS RIGHTS OF SALVAGE FOR EQUIPMENT AND FIXTURES TO BE REMOVED. COORDINATE WITH OWNER THE EQUIPMENT AND FIXTURES TO BE SALVAGED AND THE LOCATION FOR STORAGE. AVOID DAMAGE TO SALVAGED EQUIPMENT, FIXTURES AND DEVICES DURING DEMOLITION WORK AND DURING TRANSPORT TO OWNER'S DESIGNATED STORAGE LOCATION.
- AVOID DAMAGING EXISTING SURFACES AND EQUIPMENT TO REMAIN FOR NEW INSTALLATION. REPAIR DAMAGE CAUSED DURING WORK AT NO EXTRA COST TO THE OWNER.
- SEAL PENETRATIONS THROUGH FLOORS, WALLS, CEILINGS AND ROOFS WHERE MECHANICAL COMPONENTS ARE REMOVED AND WHERE THE EXISTING PENETRATION IS NOT USED FOR THE NEW INSTALLATION. REPAIR DAMAGED SURFACES TO MATCH ADJACENT AREAS OR AS INDICATED ON THE ARCHITECTURAL DRAWINGS.
- REMOVE HANGERS AND SUPPORTS WHERE DUCTWORK, PIPING AND/OR EQUIPMENT ARE REMOVED AND THE EXISTING HANGERS AND SUPPORTS ARE NOT USED FOR THE NEW INSTALLATION.
- INSTALL PERMANENT CAPS WHERE DUCTWORK AND PIPING IS REMOVED AND THE EXISTING TAPS ARE NOT USED FOR THE NEW INSTALLATION. WHERE DUCTWORK AND PIPING ARE REMOVED AND THE EXISTING TAPS WILL BE USED FOR THE NEW INSTALLATION, INSTALL TEMPORARY CAPS TO PROTECT THE EXTERIOR SURFACES UNTIL NEW DUCTWORK AND PIPING ARE INSTALLED.
- INSPECT EXISTING EQUIPMENT TO REMAIN TO VERIFY THAT EQUIPMENT IS OPERATING PROPERLY. NOTIFY OWNER OF DAMAGED AND/OR MALFUNCTIONING COMPONENTS.
- WHERE SHUTDOWN OF EXISTING SYSTEMS IS REQUIRED DURING DEMOLITION, COORDINATE SHUTDOWN TIME AND DURATION WITH OWNER TO MINIMIZE DOWNTIME. NOTIFY OWNER SEVEN (7) DAYS PRIOR TO INTERRUPTION OF SERVICE.
- CEASE WORK AND IMMEDIATELY NOTIFY THE OWNER SHOULD ANY HAZARDOUS MATERIALS BE ENCOUNTERED DURING THE PERFORMANCE OF THE WORK.
- REMOVAL, RECOVERY, RECYCLING, AND DISPOSAL OF REFRIGERANT, CONTAINED IN ANY EQUIPMENT TO BE REMOVED, SHALL BE PERFORMED IN STRICT ACCORDANCE WITH CURRENT EPA GUIDELINES.

MECHANICAL EMS NOTES:

- COORDINATE ALL CONTROLS, EQUIPMENT ACCESSORIES, AND ASSOCIATED WORK WITH EMS VENDOR PRIOR TO ALL EQUIPMENT PURCHASES AND INSTALLATION.
- GENERAL CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH EMS VENDOR TO PROVIDE A FULLY FUNCTIONAL SYSTEM AT START-UP. FAILURE TO COORDINATE CONTROLS AND REQUIRED EQUIPMENT ACCESSORIES RESULTING IN MODIFICATION SHALL BE RESPONSIBILITY OF THE CONTRACTOR AT NO EXTRA COST TO THE OWNER.
- PROVIDE ALL VARIABLE FREQUENCY DRIVES ON PLAN, AS APPLICABLE, TO BE ABLE TO ACCEPT A 0-10VDC SPEED SIGNAL AND START/STOP SIGNAL FROM THE EMS. VARIABLE FREQUENCY DRIVES SHALL BE FACTORY PROVIDED AND WALL MOUNTED.
- THERMOSTATS AND SENSORS SHALL BE FURNISHED BY EMS VENDOR AND INSTALLED BY DIVISION 26 CONTRACTOR UNLESS NOTED OTHERWISE.

MECHANICAL LANDLORD NOTES:

- LANDLORD WILL INSTALL ALL NECESSARY CONDENSERS AND AIR HANDLERS IN POSITION WITH TENANTS APPROVAL. THE SYSTEM WILL BE A "FREE BLOW" SYSTEM WITH NO DUCTWORK. TENANT TO SUPPLE DUCTWORK FOR PARTITIONED SPACE.
- COORDINATE ALTERATIONS TO BUILDING FACADE WITH LANDLORD REQUIRED CONTRACTORS, INCLUDING ROOF WORK, LOUVERS, STOREFRONT, AND ALL PENETRATIONS.



NIKE INC.
ONE BOWERMAN DRIVE
BEAVERTON, OR 97005




Don M. Docomos, Architect
960 Atlantic Avenue
Alameda, CA 94501
Tel 510 865 6663

MBH PROJECT: 55398



8345 LENEXA DRIVE, SUITE 300
LENEXA, KS 66214
TEL 913.742.2000 FAX 913.742.5001
WWW.HENDERSONENGINEERS.COM
2150001893
TX. CORPORATE NO. F-001236
EXPIRES 9/30/2022

Date	No.	Description
09/13/21		75% SET
10/04/21		90% SET
11/18/21		LL APPROVAL SET
11/19/2021		PERMIT SET
12/15/2021	1	PERMIT SET REVISION 1
01/07/2022	2	PERMIT SET REVISION 2
03/07/2022	3	PERMIT SET REVISION 3
04/10/2022	4	BID SET
05/23/2022	5	ISSUE FOR CONSTRUCTION



05/20/2022


NIKE BY SOUTHLAKE

167 GRAND AVE.
SOUTHLAKE, TX 76092

Project Number	
Config:	R/L
Drawn By	HENDERSON
Checked By	HENDERSON

MECHANICAL LEGENDS AND GENERAL NOTES

M-000



NIKE INC.
ONE BOWERMAN DRIVE
BEAVERTON, OR 97005




Don M. Decomos, Architect
960 Atlantic Avenue
Alameda, CA 94501
Tel 510 865 6663

MBH PROJECT: 55398



8345 LENEXA DRIVE, SUITE 300
LENEXA, KS 66214
TEL 913.742.2000 FAX 913.742.5001
WWW.HENDERSONENGINEERS.COM

Date	No.	Description
09/13/21		75% SET
10/04/21		90% SET
10/18/21		LL APPROVAL SET
11/19/2021		PERMIT SET
12/15/2021	1	PERMIT SET REVISION 1
01/07/2022	2	PERMIT SET REVISION 2
03/07/2022	3	PERMIT SET REVISION 3
04/01/2022	4	BID SET
05/23/2022	5	ISSUE FOR CONSTRUCTION



05/20/2022

NIKE BY SOUTHLAKE
167 GRAND AVE.
SOUTHLAKE, TX 76092

Project Number: _____
Config: R/L
Drawn By: HENDERSON
Checked By: HENDERSON

MECHANICAL HVAC PLAN

M-100

KEYNOTES ARE PROTOTYPICAL. MISSING KEYNOTE NUMBERS INDICATE A PROTOTYPICAL NOTE IS NOT USED OR REMOVED.

MECHANICAL PLAN NOTES

- M01 ALL THERMOSTATS AND SENSORS FURNISHED BY EMS VENDOR AND INSTALLED BY DIVISION 26, UNLESS NOTED OTHERWISE.
- M02 DO NOT INSTALL SENSORS ON WALL GRAPHICS. CONFIRM LOCATIONS OF SENSORS WITH FM PRIOR TO INSTALL.
- M03 INSTALL DAMPER AND ACTUATOR IN LOCATION INDICATED. DAMPER FURNISHED BY DIVISION 23. ACTUATOR FURNISHED BY EMS VENDOR.
- M05 DIVISION 23 CONTRACTOR SHALL PROVIDE NEW REMOTE TEMPERATURE SENSOR FOR CONTROL OF UNIT HEATER. CONTRACTOR SHALL WIRE SENSOR BACK TO INTEGRAL UNIT-MOUNTED THERMOSTAT. REFER TO MECHANICAL SCHEDULES AND CONTROLS FOR MORE INFORMATION.
- M10 EXISTING DX SPLIT SYSTEM FAN COIL UNIT WITH NEW CONNECTIONS FOR DUCTWORK AND CONTROLS AS SCHEDULED SUPPORTED FROM STRUCTURE ABOVE. PROVIDE A NEW SET OF MERV 13 AIR FILTERS IN UNIT BEFORE TURNING SYSTEM OVER TO OWNER. COORDINATE CONDENSATE PIPING WITH DIVISION 22.
- M11 LANDLORD SHALL CONFIRM ADEQUATE ACCESS AND CLEARANCES ARE PROVIDED FOR EACH EXISTING CONDENSING UNIT.
- M13 PROVIDE NEW ELECTRIC UNIT HEATER AS SCHEDULED. SUPPORT FROM STRUCTURE ABOVE AT 10'-0" AFF. DIVISION 23 TO PROVIDE TEMPERATURE SENSOR WIRED BACK TO UNIT. UNIT HEATER SHALL NOT BE INTERLOCKED WITH EMS.
- M16 ACCESS TO EXISTING HVAC EQUIPMENT SHALL BE FROM LAY-IN CEILING. NO CEILING DEVICES SHALL BE PLACED IN THIS LOCATION. COORDINATE FINAL INSTALLED LOCATION SUCH THAT THE HVAC EQUIPMENT REMAINS ACCESSIBLE. VERIFY NO OTHER PIPING, ELECTRICAL CONDUIT, STRUCTURE, AND/OR CEILING SUPPORTS IMPEDE ACCESS IN ANY WAY. INSTALL HVAC EQUIPMENT WITHIN 24" ABOVE CEILING FOR SERVICEABILITY.
- M18 PROVIDE NEW IN-LINE EXHAUST FAN AS SCHEDULED FOR GENERAL RESTROOM EXHAUST.
- M19 EXHAUST FAN SERVES TO PROVIDE TRANSFER AIR ONLY AND SHALL DISCHARGE AIR INTO THE STOCKROOM.
- M20 INSTALL VAV POWER MODULE FOR CONTROL OF OFFICE VAV DIFFUSERS IN AN ACCESSIBLE LOCATION ABOVE THE CEILING. DIVISION 26 CONTRACTOR SHALL PROVIDE 120V POWER TO MODULE. REFER TO ELECTRICAL DRAWINGS FOR DETAILS.
- M23 SERVICE AREA FOR FAN COIL UNIT SHALL NOT BE LOCATED ABOVE PIPING SHELVE. FINAL LOCATION TO BE DETERMINED ON FINAL CONSTRUCTION DOCUMENTS.
- M24 EXISTING LOUVER INSTALLED BY LANDLORD. COORDINATE EXACT LOCATION WITH LANDLORD AND ARCHITECT PRIOR TO DUCT INSTALLATION.
- M25 PROVIDE NEW VAV BOX IN SUPPLY AIR DUCT SERVING FITTING ROOMS. INSTALL VAV BOX IN ACCESSIBLE LOCATION AND COORDINATE CONTROLS WITH EMS VENDOR PRIOR TO ORDERING.
- M26 PROVIDE NEW VAV BOX IN SUPPLY AIR DUCT SERVING SOLAR ZONE. INSTALL VAV BOX IN ACCESSIBLE LOCATION AND COORDINATE CONTROLS WITH EMS VENDOR PRIOR TO ORDERING.
- M27 BALANCING DAMPER IS IN VERTICAL RUN OF DUCT
- M30 ROUTE SHEET METAL RETURN AIR DUCT AS SHOWN WITH TERMINATION DIRECTED DOWNWARD. SIZE PLENUM FULL SIZE OF RETURN AIR INLET. CONNECT RETURN DUCT TO NEW CEILING RETURN GRILLES.
- M32 EXHAUST AIR DAMPERS SHALL BE ACCESSIBLE FROM LAY-IN CEILING. COORDINATE FINAL INSTALLED LOCATION SUCH THAT THE DAMPERS REMAIN ACCESSIBLE.
- M33 DO NOT ROUTE DUCTWORK OVER ELECTRICAL EQUIPMENT. NOTIFY ENGINEER OF CONFLICTS IN FIELD.
- M34 ROUTE DUCTWORK TIGHT TO STRUCTURE.
- M41 COORDINATE DUCT ROUTING WITH LIGHTS AND STRUCTURE. ROUTE ALL SALES DUCTWORK AT SAME ELEVATION (12" BELOW UNDERSIDE OF DECK.
- M65 LOUVERED DOOR FOR MAKEUP AIR BY GENERAL CONTRACTOR. REFER TO ARCHITECTURAL DRAWINGS FOR MORE INFORMATION.
- M67 COORDINATE LOCATION OF FITTING ROOM DIFFUSERS WITH LIGHTS, SPRINKLERS, SPEAKERS, AND OTHER CEILING DEVICES FOR A NEAT AND ORDERLY INSTALLATION. INSTALL CEILING DEVICES IN-LINE WITH EACH OTHER WHERE POSSIBLE.
- M69 INSTALL DUCT-MOUNTED DIFFUSERS WITH BLADES ANGLED AT 22.5° TOWARDS THE SALES FLOOR. DUCT-MOUNTED DIFFUSERS SHALL HAVE INTEGRAL DAMPER ADJUSTABLE FROM FACE OF DEVICE.
- M70 PROVIDE 1" UNDERCUT ON DOOR TO ALLOW FOR RETURN AIR TRANSFER.

INSTALL DUCTWORK AND PIPING AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS. COORDINATE INSTALLATION OF DUCTWORK AND PIPING TO AVOID CONFLICTS WITH ELECTRICAL PANELS, LIGHTING FIXTURES, ETC. NOTIFY CONSTRUCTION PROJECT MANAGER OF CONFLICTS.

THE DUCTWORK LAYOUT INDICATED ON THE DRAWINGS IS SCHEMATIC AND SHOWS DESIGNED INTENT ONLY. PRIOR TO FABRICATION AND INSTALLATION OF DUCTWORK, DIVISION 23 SHALL HAVE A QUALIFIED, EXPERIENCED SKETCHER PREPARE AND SUBMIT SHEET METAL SHOP DRAWINGS. SHOP DRAWINGS SHALL TAKE INTO ACCOUNT ALL EXISTING CONDITIONS, INCLUDING BUT NOT LIMITED TO, STRUCTURAL MEMBERS, PIPING, CEILINGS, SOFFIT HEIGHTS, AND LIGHT FIXTURES.

SHOP DRAWINGS SHALL INDICATE ALL REVISIONS TO THE LAYOUT REQUIRED TO ACCOMMODATE THE EXISTING CONDITIONS AND/OR MAINTAIN THE CEILING HEIGHTS AND CLEARANCES REQUIRED. NOTIFY THE ARCHITECT AND ENGINEER OF ANY LOCATION WHERE THE DESIGN INTENT CANNOT BE MET PRIOR TO FABRICATION AND INSTALLATION OF DUCTWORK. REVISIONS TO DUCTWORK, EQUIPMENT, CONDUIT AND/OR PIPING REQUIRED BY CONTRACTOR'S FAILURE TO SUBMIT PROPERLY PREPARED SHOP DRAWINGS SHALL BE THE RESPONSIBILITY OF DIVISION 23 AT NO ADDITIONAL COST TO THE CLIENT OR DELAY TO THE PROJECT SCHEDULE.


GENERAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING TO ARCHITECT, ENGINEER, LANDLORD, AND BUILDING OFFICIAL/INSPECTOR A FINAL TEST AND BALANCE REPORT PER THE SPECIFICATIONS. PROVIDE TEST AND BALANCE REPORT TO ARCHITECT, ENGINEER, AND LANDLORD PRIOR TO THE FINAL BUILDING INSPECTION.

LANDLORD REQUIREMENTS:
LANDLORD APPROVED ROOFING CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING ALL CUTS THROUGH THE EXISTING ROOF, MODIFYING EXISTING OPENINGS, AND/OR ALTERING CURB FLASHING AT GENERAL CONTRACTOR'S EXPENSE. COORDINATE WITH GENERAL CONTRACTOR.


EMS CONTROLS:
CONTRACTORS ARE RESPONSIBLE FOR COORDINATING ALL EQUIPMENT CONTROLS WITH EMS VENDOR PRIOR TO PURCHASE AND INSTALLATION. CONTRACTORS SHALL COORDINATE WITH EMS VENDOR TO PROVIDE ALL NECESSARY EQUIPMENT AND ACCESSORIES FOR A FULLY FUNCTIONING SYSTEM.

TEMPERATURE CONTROLS:
EMS VENDOR SHALL FURNISH SENSORS AND CONTROL COMPONENTS AS INDICATED ON PLANS AND AS NECESSARY TO ACCOMPLISH THE INTENT OF THE DRAWINGS. ALL CONTROLS SHALL BE TIED INTO THE EMS SYSTEM UNLESS NOTED OTHERWISE.


PROVIDE RFID DUCTWORK MESH OVER TRANSFER GRILLES BELOW 15'-0" AFF BETWEEN THE STOCKROOM AND THE SALES FLOOR, IF APPLICABLE.




1 HVAC PLAN
3/16" = 1'-0"




2 ENLARGED BACK OF HOUSE HVAC PLAN
1/4" = 1'-0"




3 LOUVER INSTALLATION DETAIL NTS




2 CONDENSATE OVERFLOW DRAIN PAN NTS




1 HORIZONTAL FAN COIL UNIT DETAIL NTS




6 RETURN/TRANSFER AIR DUCT DETAIL NTS




5 SINGLE DUCT VAV TERMINAL UNIT - COOLING ONLY DETAIL NTS




4 IN-LINE DUCT-MOUNTED FAN DETAIL NTS




9 REGISTER MOUNTING TO RECTANGULAR DUCT DETAIL NTS




8 DAMPER AND FLEX DUCTWORK CONNECTION DETAIL NTS



7 DUCT HANGER - LOWER ATTACHMENT DETAILS NTS




11 LAY-IN CEILING DIFFUSER DETAIL NTS



10 HARD CEILING DIFFUSER DETAIL NTS



Date	No.	Description
09/13/21		75% SET
10/04/21		90% SET
10/18/21		LL APPROVAL SET
11/19/2021		PERMIT SET
12/15/2021	1	PERMIT SET REVISION 1
01/07/2022	2	PERMIT SET REVISION 2
03/07/2022	3	PERMIT SET REVISION 3
04/01/2022	4	BID SET
05/23/2022	5	ISSUE FOR CONSTRUCTION



NIKE BY SOUTHLAKE
167 GRAND AVE.
SOUTHLAKE, TX 76092

Project Number	
Config:	R/L
Drawn By	HENDERSON
Checked By	HENDERSON

MECHANICAL
DETAILS

M-200

PROJECT DESIGN CONDITIONS

CLIMATE CONDITIONS				BUILDING OPERATING HOURS:			
WEATHER STATION: NIKE SOUTHLAKE, TX, USA				MONDAY - FRIDAY			
CLIMATE ZONE: 3A				SATURDAY			
HEATING (DB): 99.6% 23.3 °F				SUNDAY			
DESIGN HEATING CONDITIONS (DB): 15 °F				HOLIDAY			
HUMIDIFICATION (DP/HR MCB): 99.6% 9.3 °F/ 9.0 g/bt 30.8 °F				TBD BY OWNER			
COOLING (DB/MCB): 0.4% 101.4 °F/ 74.2 °F				TBD BY OWNER			
DESIGN COOLING CONDITIONS (DB/MCB): 0.4% 101.4 °F/ 74.2 °F				TBD BY OWNER			
DEHUMIDIFICATION (DP/HR MCB): 0.4% 75.4 °F/ 135.7 g/bt 83.7 °F				TBD BY OWNER			

SPACE / UNIT DESCRIPTION	SET POINTS												SPACE OPERATING HOURS OCCUPIED / UNOCCUPIED			NOTES	
	COOLING / DEHUMIDIFICATION				HEATING				HUMIDIFICATION				ZONE VENTILATION RESET				
	OC	UNOC	MAX	MIN	OC	UNOC	MIN	MAX	CONTROL METHOD	BASE PPM	MAXIMUM PPM	M/F	SAT	SUN			
FCU-1 BACK OF HOUSE	72	77	80%	NA	70	60	NA	NA	CO2	400	750	TBD	TBD	TBD	A-D		
FCU-2 STOCKROOM	72	77	80%	NA	70	60	NA	NA	CO2	400	750	TBD	TBD	TBD	A-D		
FCU-3 SALES	72	77	80%	NA	70	60	NA	NA	CO2	400	750	TBD	TBD	TBD	A-D		
FCU-4 SALES	72	77	80%	NA	70	60	NA	NA	CO2	400	750	TBD	TBD	TBD	A-D		
FCU-5 SOLAR ZONE	72	77	80%	NA	70	60	NA	NA	CO2	400	750	TBD	TBD	TBD	A-D		

- NOTES:
- ZONE LEVEL VENTILATION RESET / DEMAND CONTROL VENTILATION (DCV) CONTROL METHOD: CARBON DIOXIDE SENSOR (CO2).
 - ZONE LEVEL SET POINT CONDITIONS SHALL BE AS SCHEDULED UNLESS OTHERWISE SCHEDULED OR NOTED ON THE DRAWINGS FOR ROOM SPECIFIC SPACE CONDITIONS.
 - ZONE LEVEL OCCUPANCY HOUR SCHEDULE SHALL BE PER BUILDING OPERATING HOURS UNLESS OTHERWISE SCHEDULED.
 - ZONE LEVEL CONTROLS SHALL BE CAPABLE OF OPERATING WITH INDEPENDENT OCCUPANCY SCHEDULES.

SPLIT SYSTEM CONTROL MATRIX

CONTROL FEATURE	UNITS	FCU-1 SETPOINT OR Y/N	FCU-2 SETPOINT OR Y/N	FCU-3,4 SETPOINT OR Y/N	FCU-5 SETPOINT OR Y/N	POINT TYPE INTERFACE WITH DDC (READ/WRITE)	NOTES
BUILDING AUTOMATION SYSTEM (BAS)							
ENERGY MANAGEMENT SYSTEM INTERFACE							
SETPOINTS							
COOLING - OCCUPIED SETPOINT		Y	Y	Y	Y	READ	B
COOLING - UNOCCUPIED SETPOINT		Y	Y	Y	Y	READ	B
DEAD BAND - MINIMUM HEATING AND COOLING TEMPERATURE SETPOINT DIFFERENCE		Y	Y	Y	Y	READ	B
HEATING - OCCUPIED SETPOINT		Y	Y	Y	Y	READ	B
HEATING - UNOCCUPIED SETPOINT		Y	Y	Y	Y	READ	B
HEATING - SUPPLY AIR TEMPERATURE SETPOINT		Y	Y	Y	Y	READ	B
PROGRAMMED CONTROL FEATURES							
REMOTE TEMPERATURE SENSOR		Y	Y	Y	Y	READ	B
DEMAND CONTROL VENTILATION - CO2 SENSOR FEEDBACK		PPM	750	750	750	750	READ/WRITE
EQUIPMENT ACCESSORIES AND CONTROL MODULES							
OUTSIDE AIR DAMPER - MOTOR OPERATED (MODULATING)		Y	Y	Y	Y	READ POSITION	L
HEATING COIL (ELECTRIC)		Y	Y	Y	Y	READ STATUS	J
COOLING COIL - (3) STAGES		Y	Y	Y	Y	READ STATUS	N
SUPPLY FAN CONTROL METHODS							
ON DURING OCCUPIED HOURS		Y	Y	Y	Y		
CYCLE WITH LOADS DURING UNOCCUPIED HOURS		Y	Y	Y	Y		
OPTIMUM START SEQUENCE		Y	Y	Y	Y		R
CONSTANT VOLUME FAN CONTROL		Y	Y	Y	Y	READ STATUS	
SAFETIES, INTERLOCKS, AND ALARMS							
RETURN AIR SMOKE DETECTOR - UNIT SHUTDOWN		Y	Y	Y	Y	READ	D
AUXILIARY DRAIN PAN FLOOD DETECTOR - UNIT SHUTDOWN		Y	Y	Y	Y	READ	B
DIFFERENTIAL PRESSURE SWITCH - FILTER CHANGE ALARM		Y	Y	Y	Y	READ	G

DIV. 23 CONTRACTOR SHALL PROVIDE CONTROL PANEL(S), WIRING, THERMOSTAT(S), TEMPERATURE SENSOR(S), HUMIDISTAT(S), AND/OR CO2 SENSOR(S) WHERE SHOWN ON THE DRAWINGS AND AS REQUIRED TO FACILITATE THE SCHEDULED CONTROL MODULES AND SEQUENCES OF OPERATION. EACH UNIT SHALL CONTROL BASED ON ITS OWN INTERNAL SAFETIES, TIME DELAYS, AND SEQUENCES UNLESS NOTED OTHERWISE. COORDINATE WITH OWNER FINAL BUILDING AND EQUIPMENT SCHEDULES DURING STARTUP. REFERENCE DIVISION SPECIFICATIONS FOR INDIVIDUAL DEVICE REQUIREMENTS.

- NOTES:
- PROVIDE UNIT WITH TERMINAL STRIP TO RECEIVE CONTROL INPUT(S) COMMUNICATED FROM A CENTRAL DDC CONTROLLER. EMS SHALL PROVIDE REMOTE SETPOINT ADJUSTMENT, SCHEDULING, AND MONITORING OF THE POINTS LISTED IN THE SCHEDULE FOR EACH UNIT. LISTED IN THE SCHEDULE FOR EACH UNIT.
 - DIVISION 23 CONTRACTOR SHALL PROVIDE DEVICE.
 - DIVISION 28 CONTRACTOR SHALL PROVIDE DEVICE.
 - DEVICE SHALL BE FACTORY MOUNTED AND PRE-WIRED FOR OPERATION SUBJECT TO THE ONBOARD CONTROLLER.
 - MODULATE AND/OR CYCLE SUPPLY FAN SPEED SETTING AND COIL CAPACITY STAGES SUBJECT TO THE INTERNAL SAFETIES AND SEQUENCES TO MAINTAIN SCHEDULED SETPOINTS.
 - DIVISION 23 SHALL PROVIDE MODULATING DAMPER AND EMS CONTRACTOR SHALL PROVIDE CONTROLS CAPABLE OF ADJUSTING THE DAMPER POSITION TO MAINTAIN THE SCHEDULED OUTSIDE AIR ON THE DRAWINGS. EMS CONTRACTOR SHALL PROGRAM MULTIPLE DAMPER POSITION SETPOINTS IN THE FIELD DURING TESTING AND BALANCING TO MAINTAIN MINIMUM PROGRAM MULTIPLE DAMPER POSITION SETPOINTS IN THE FIELD DURING TESTING. DAMPER SHALL ADJUST BASED ON DEMAND CONTROL VENTILATION.
 - CYCLE COIL CAPACITY STAGES TO MAINTAIN SCHEDULED SETPOINTS.
 - DURING OPTIMUM START SEQUENCE, THE UNIT SHALL SUPPLY THE LESSER OF THE MINIMUM RATE OF OUTDOOR AIR OR SUPPLY 3 COMPLETE AIR CHANGES DURING THE 1-HOUR PERIOD BEFORE NORMAL OCCUPIED MODE.

CARRIER UNIT STARTUP REQUIREMENTS

INSTALLING CONTRACTOR SHALL COMPLETE THE PRE-START CHECKLIST AND EMAIL DENNY.LAWRENCE@COMFORTSYSTEMSUSA.COM TWO WEEKS PRIOR TO SCHEDULING EQUIPMENT STARTUP.

COORDINATE EQUIPMENT STARTUP WORK WITH COMFORT SYSTEMS USA. EMAIL: DENNY.LAWRENCE@COMFORTSYSTEMSUSA.COM OFFICE: (317) 246-4644

DEPARTMENT MANAGER
EMAIL: KLORI.KARAMDAD@COMFORTSYSTEMSUSA.COM OFFICE: 317-246-4656

TECHNICAL SUPPORT
EMAIL: RICK.FARRIS@COMFORTSYSTEMSUSA.COM MOBILE: 317-638-5363 X4454

PRE-START CHECKLIST (VERIFY FOR ALL UNITS)

- VERIFY ALL ITEMS ON THE EQUIPMENT ORDER RECEIVED.
- VERIFY ALL PACKAGING MATERIAL REMOVED FROM THE UNIT.
- VERIFY CURB GASKETS PROPERLY INSTALLED.
- VERIFY ROOFTOP UNIT INSTALLED LEVEL AND PROPERLY ALIGNED WITH CURB.
- VERIFY DUCTWORK/FABRIC DUCT COMPLETELY INSTALLED PER MECHANICAL PLANS.
- VERIFY OA HOOD INSTALLED, AIR INLET SCREEN INSTALLED.
- VERIFY POWER EXHAUST ACCESSORY INSTALLED, (IF APPLICABLE).
- VERIFY CLEAN PLEATED FILTERS INSTALLED, MINIMUM MERV 8 RATING.
- VERIFY CONDENSATE DRAIN LINE INSTALLED, MINIMUM 2" DEEP TRAP, DRAIN PAN CHECK/LEVEL.
- VERIFY SUPPLY FAN ROTATES FREELY IN THE HOUSING.
- VERIFY PULLEYS ALIGNED AND BELT TENSION CORRECT.
- VERIFY SMOKE DETECTORS INSTALLED IN DUCTWORK, CLEANED AND TESTED.
- VERIFY GAS METER INSTALLED AND GAS AVAILABLE FROM THE UTILITY, GAS PIPING COMPLETED, CHECKED FOR LEAKS AND PURGED (IF APPLICABLE).
- VERIFY GAS PIPING DRIP LEG INSTALLED PROPERLY, (DOWNSTREAM OF SHUTOFF VALVE AND NO INTERFERENCE WITH ACCESS DOOR)
- VERIFY FLUE HOOD INSTALLED.
- VERIFY JOBSITE POWER SUPPLY MATCHES THE VOLTAGE ON THE UNIT DATA PLATE.
- VERIFY ELECTRIC POWER CONNECTED TO UNIT VIA THE ACCESS PROVIDED, IF NOT, DATE POWER WILL BE AVAILABLE.
- VERIFY NO WIRES TOUCHING REFRIGERANT LINES OR SHARP EDGES.
- VERIFY ELECTRIC CONNECTORS AND TERMINALS TIGHT.
- VERIFY THRU-THE-CURB UTILITY CONNECTIONS COMPLETE.
- VERIFY UNIT TRANSFORMER PRIMARY TAPPED FOR JOBSITE VOLTAGE.
- VERIFY VENSTAR THERMOSTAT INSTALLED IN THE RETURN AIR DUCT DROP AND WIRED FOR TEMPORARY UNIT OPERATION.

EMS INSTALLATION CHECKLIST

ITEMS ON EMS CHECK-OFF LIST MUST BE COMPLETED PRIOR TO EMS AND GBS COMMISSIONING AT THE END OF THE JOB. SOME ITEMS LISTED BELOW MAY NOT BE APPLICABLE.

COORDINATE EQUIPMENT STARTUP WORK WITH COMFORT SYSTEMS USA. EMAIL: PAUL_SAWYER@COMFORTSYSTEMSUSA.COM OFFICE: 317-246-5170

EMS CHECKLIST

- REVIEW EMS PRINT SET AND INSTALL EMS OPUS PANEL AND LCP AS DESCRIBED IN THE EMS PRINT SET.
- REVIEW EMS PRINT SET AND PULL ALL WIRE AND TERMINATE ON DEVICES AS DESCRIBED IN THE EMS PRINT SET.
- REVIEW EMS PRINT SET AND INSTALL ALL EMS HVAC CONTROLS AS DESCRIBED IN THE EMS PRINT SET.
- REVIEW EMS PRINT SET AND INSTALL ALL EMS LIGHTING CONTROLS AS DESCRIBED IN THE EMS PRINT SET.
- REVIEW EMS PRINT SET AND WATTSOPPER SUBMITTAL AND INSTALL THE WATTSOPPER LIGHTING SYSTEM AND PULL ALL WIRE AS DESCRIBED IN THE EMS PRINT SET AND WATTSOPPER SUBMITTAL.

EMS CONTROLS:

CONTRACTORS ARE RESPONSIBLE FOR COORDINATING ALL EQUIPMENT CONTROLS WITH EMS VENDOR PRIOR TO PURCHASE AND INSTALLATION. CONTRACTORS SHALL COORDINATE WITH EMS VENDOR TO PROVIDE ALL NECESSARY EQUIPMENT AND ACCESSORIES FOR A FULLY FUNCTIONING SYSTEM.

OUTSIDE AIR REQUIREMENTS, IMC-2018 (IP)

SYSTEM DESIGNATION	SYSTEM TYPE	SINGLE-ZONE SYSTEMS			MULTI-ZONE SYSTEMS			FLOOR AREA SERVED BY SYSTEM [A] (SF)	SYSTEM AVERAGED AREA-BASED OUTDOOR AIR RATE (CFM/SF)	SYSTEM POPULATION [P] (PEOPLE)	SYSTEM AVERAGED PEOPLE-BASED OUTDOOR AIR RATE (CFM/P)	REQUIRED OA INTAKE FLOW [V] (CFM)	REQUIRED DCV OA INTAKE FLOW [V] (CFM)	DESIGN OA INTAKE FLOW [V] (CFM)	NOTES
		VENTILATION ZONE ASSOCIATED WITH SYSTEM	WORST CASE ZONE AIR DISTRIBUTION EFFECTIVENESS [E]	SYSTEM VENTILATION EFFICIENCY [EV]	SYSTEM VENTILATION EFFICIENCY [EV]										
FCU-1	MULTIZONE	-	-	0.71	580	0.042	12.00				5.0	118	34	120	35 ALL
FCU-2	MULTIZONE	-	-	0.59	1,095	0.120	10.0				10.0	234	222	235	1225 ALL
FCU-3,4,5	MULTIZONE	-	-	0.80	3,742	0.116	44.07				7.5	954	542	960	1555 ALL
TOTALS											1,306	798	1315	1515	

- NOTES:
- VENTILATION CALCULATIONS BASED ON 2018 INTERNATIONAL MECHANICAL CODE.
 - SYSTEM POPULATIONS BASED ON MAX SEATING AND/OR CODE MAXIMUM VALUES.
 - VENTILATION RE-CIRCULATING SYSTEMS: CALCULATOR TAKES THE MAXIMUM OUTSIDE AIRFLOW REQUIRED BY IMC ON A SYSTEM LEVEL. THE CALCULATION USED TO DETERMINE VENTILATION AIRFLOW IN COMPLIANCE WITH VPP AND SECTION 404.0.
- MULTI-ZONE RATE SHOWN IS ACTUAL CALCULATED WITH CORRECTION FACTORS INCLUDED. EACH ZONE IS CALCULATED WITH ITS WORST CASE ZONE AIR DISTRIBUTION EFFECTIVENESS (HEATING/COOLING) AS PART OF CALCULATIONS TO FIND EV.

FAN COIL UNIT SCHEDULE (DX COOLING, ELECTRIC HEATING) (EXISTING BY LANDLORD)

MARK	MANUFACTURER	MODEL	SUPPLY FAN				COOLING COIL				HEATING COIL				MIN O/A (CFM)	ABS MIN O/A (CFM)	ELECTRICAL V/PH	MCA	MOCP	WEIGHT (LBS)	NOTES			
			CFM	ESP (IN)	NOM HP	TH (MBH)	SH (MBH)	EAT (°F DB)	(°F WB)	REFR TYPE	MIN OUT (MBH)	NOM (KW)	EAT (°F DB)	(°F WB)								MIN NO OF STAGES		
FCU-1	CARRIER	FV4CNB005	1,475	0.7	0.5	35.4	31.3	75.2	60.7	55.9	52.2	R-410A	40.0	15	65.5	90	2	120	35	480/3	8.4	15	213	ALL
FCU-2	CARRIER	FV4CNB005	1,050	0.7	0.5	32.0	27.7	60.7	56.3	56.7	R-410A	36.6	15	57.7	90	2	235	225	480/3	7.6	15	184	ALL	
FCU-3	CARRIER	FV4CNB006	1,840	1.0	0.75	49.8	40.5	77.5	64.2	56.9	55.2	R-410A	58.8	20	60.4	90	2	320	185	480/3	9.7	15	245	ALL
FCU-4	CARRIER	FV4CNB006	1,840	1.0	0.75	49.8	40.5	77.5	64.2	56.9	55.2	R-410A	58.8	20	60.4	90	2	320	185	480/3	9.7	15	245	ALL
FCU-5	CARRIER	FV4CNB006	1,400	1.0	0.75	41.2	33.4	79.2	65.0	55.8	54.8	R-410A	49.3	20	57.4	90	2	320	185	480/3	9.7	15	207	ALL

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

CARRIER NATIONAL ACCOUNT CONTACT
MATT MURPHY
STRATEGIC ACCOUNT MANAGER
CARRIER CORPORATION
MOBILE: 630 235-1615
EMAIL: MATT.MURPHY@CARRIER.COM

- NOTES:
- FAN COIL UNIT AND ASSOCIATED CONDENSING UNIT ARE EXISTING TO REMAIN. CONTRACTOR SHALL REFURBISH FAN COIL TO "LIKE NEW" CONDITIONS.
 - PROVIDE NEW 2 INCH MERV 13, EFFICIENT PLEATED THROWAWAY AIR FILTERS.
 - PROVIDE WITH 7-DAY PROGRAMMABLE THERMOSTAT WITH STAGED HEATING AND COOLING CAPABILITY AS REQUIRED FOR OPERATION OF AUXILIARY HEATING AND COOLING CONTROLS. COORDINATE CONTROLS WITH EMS PRIOR TO CONSTRUCTION.
 - SPECIFIED FAN ESP ACCOUNTS FOR DUCT LOSSES EXTERNAL TO UNIT. FILTER LOSS IS AT A MAXIMUM OF 400 FPM FACE VELOCITY.
 - DIVISION 23 CONTRACTOR SHALL PROVIDE SMOKE DETECTORS IN RETURN AIR DUCT(S).
 - VERIFY UNIT IS INSTALLED WITH ELECTRIC HEAT KIT POWERED AT 480V AS SCHEDULED. IF NECESSARY, PROVIDE WARREN TECHNOLOGIES MODEL NUMBER WPK9WJ5A, OR EQUIVALENT. HEATER SHALL MEET OR EXCEED SCHEDULED MINIMUM MBH OUTPUT.
 - NOMINAL RV IS BASED ON LISTED MANUFACTURERS STANDARD PRODUCT. COORDINATE EQUIPMENT POWER SUPPLY WITH ELECTRICAL CONTRACTOR IF DIFFERENT FROM THAT SCHEDULED.
 - PROVIDE AUXILIARY DRAIN PAN WITH FLOOD DETECTOR SWITCH TO SHUT OFF UNIT WHEN WATER IS PRESENT IN DRAIN PAN.

CONDENSING UNIT SCHEDULE (EXISTING BY LANDLORD)

MARK	SERVICE	MANUFACTURER	MODEL	REFR	TH (MBH)	MIN NO OF STAGES	NO OF CIRCUITS	MIN EFF (EER)	(IEER)	ELECTRICAL V/PH	MCA	MOCP	WEIGHT (LBS)	NOTES
CU-1	FCU-1	CARRIER	24AH44A0A006	R-410A	35.4	1	1	12	15	480/3	8.4	15	213	ALL
CU-2	FCU-2	CARRIER	24AH44A0A006	R-410A	32.0	1	1	13	16	480/3	7.6	15	184	ALL
CU-3	FCU-3	CARRIER	24AH46A0A006	R-410A	49.6	1	1	12	14.5	480/3	9.7	15	245	ALL
CU-4	FCU-4	CARRIER	24AH46A0A006	R-410A	49.6	1	1	12	14.5	480/3	9.7	15	245	ALL
CU-5	FCU-5	CARRIER	24AH44A0A006	R-410A	41.2	1	1	12.5	15.5	480/3	8.4	15	213	ALL

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.


- NOTES:
- CONDENSING UNIT AND ASSOCIATED FAN COIL UNIT ARE EXISTING TO REMAIN. CONTRACTOR SHALL CLEAN EXTERIOR COILS AND REPAIR TO "LIKE NEW" CONDITIONS.
 - EQUIPMENT SIZES FOR EXISTING TYPICAL BRANCH DUCT TO MATCH NECK SIZE UNLESS OTHERWISE SHOWN ON DRAWINGS.
 - VERIFY EXISTING UNITS ARE PROVIDED WITH GUARDS TO PROTECT CONDENSER COIL FROM HAIL OR OTHER DAMAGE. PROVIDE NEW OR REPLACE IF NECESSARY.

GRILLE, REGISTER, AND DIFFUSER SCHEDULE

MARK	MANUFACTURER	SERVICE	MODEL	CONSTRUCTION TYPE	FACE TYPE	MOUNTING LOCATION	BORDER TYPE	FACE SIZE (IN)	MAX. NC	MAX. PRESS. DROP (IN. W.C.)	NOTES
CEG1	TITUS	EXHAUST	OMNI	STEEL	PLAQUE	CEILING	--	12x12	25	0.1	B,C,F,H
CRG1	TITUS	RETURN	PAR	STEEL	PERFORATED	CEILING	--	24x24	25	0.1	B,C,F,H
CRG2	TITUS	RETURN	PAR	STEEL	PERFORATED	CEILING	--	12x24	25	0.1	B,C,F,H
CS1	PRICE	SUPPLY	PRODIGY	STEEL	PLAQUE	CEILING	--	24x24	25	0.1	A,C,F,H,K
CS2	TITUS	SUPPLY	OMNI	STEEL	PLAQUE	CEILING	--	24x24	25	0.1	A,C,F,H
CS3	TITUS	SUPPLY	OMNI	STEEL	PLAQUE	CEILING	--	12x12	25	0.1	A,C,F,J
CS4	ARIA	SUPPLY	DRYWALL PRO	DRYWALL	PLAQUE	CEILING	--	6"x10"	25	0.1	A,C,F,M
DSG1	TITUS	SUPPLY	301RL	STEEL	LOUVERED	DUCT SIDEWALL	--	REFER TO PLANS	25	0.1	B,C,E,H
WTG1	TITUS	TRANSFER	350RL	STEEL	LOUVERED	WALL	--	REFER TO PLANS	25	0.1	B-D,G,H

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

- NOTES:
- 4-WAY THROW PATTERN UNLESS OTHERWISE INDICATED BY FLOW ARROWS ON DRAWINGS.
 - NECK SIZE SHOWN ON DRAWINGS. PROVIDE BRANCH DUCT TO MATCH NECK SIZE UNLESS OTHERWISE SHOWN ON DRAWINGS.
 - BAKED ENAMEL FINISH. COLOR TO MATCH WALL, DUCT, AND/OR CEILING COLOR. COORDINATE WITH ARCHITECT PRIOR TO ORDERING.
 - FRONT BLADES PARALLEL TO LONG DIMENSION. INSTALL WALL GRILLE HIGH ON WALL WITH AIR BLADES POINTED UPWARD. COORDINATE EXACT LOCATIONS PRIOR TO INSTALLATION.
 - FRONT BLADES PARALLEL TO LONG DIMENSION. PROVIDE OPPOSED BLADE DAMPER ADJUSTABLE FROM FACE OF DEVICE. AIR BLADES SHALL BE DIRECTED AT 45° TOWARDS THE FINISHED FLOOR.
 - PROVIDE WITH RAPID MOUNT FRAMING OPTION FOR LAY-IN TYPE DIFFUSERS INSTALLED IN A HARD CEILING.
 - FRAME TYPE TO MATCH CEILING/WALL CONSTRUCTION. COORDINATE WITH ARCHITECTURAL, REFLECTED CEILING/WALL PLAN.
 - H. PROVIDE DIFFUSERS AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.
 - CONTRACTOR SHALL PROVIDE REMOTE CABLE-OPERATED VOLUME DAMPER WITH METROPOLITAN AIR TECHNOLOGIES MODEL RT-250 WITH EXTERNAL WORM GEAR OPERATOR OR EQUIVALENT YOUNG REGULATOR BUTTERFLY DAMPER WITH 270-275 CONTROLLER. OPERATOR SHALL HAVE A SQUARE DRIVE FOR 1/4" NUT DRIVER. DAMPER ASSEMBLY SHALL INCLUDE GALVANIZED STEEL DUCT WITH ROLLED BEAD STAINLESS STEEL BLADES, LUBRICATING SELF-BEARING AND WORM GEAR MOUNTING PLATE. DAMPER SHALL BE INSTALLED IN BRANCH DUCT NOT INLET OF PLENUM DIFFUSER.
 - VARIABLE VOLUME DIFFUSER TO BE INTERLOCKED WITH SPACE MOUNTED THERMOSTAT. MAXIMUM AIRFLOW SHALL BE AS NOTED ON PLANS. MINIMUM AIRFLOW SHALL BE 30% OF MAXIMUM AIRFLOW.
 - PROVIDE PRESSURE RELIEF COLLAR WITH DIFFUSER. DIFFUSER SHALL BE FURNISHED BY EMS VENDOR. INSTALLED BY MECHANICAL CONTRACTOR.
 - COORDINATE ARIA DRYWALL PRO INSTALLATION WITH ARCHITECT PRIOR TO INSTALLATION. COORDINATE EXACT LOCATION WITH OTHER CEILING DEVICES FOR AN ORDERLY CEILING CON



NIKE INC.
ONE BOWERMAN DRIVE
BEAVERTON, OR 97005




Don M. Documans, Architect
960 Atlantic Avenue
Alameda, CA 94501
Tel 510 865 8663

MBH PROJECT: 55398



8345 LEXENA DRIVE, SUITE 300
LEXENA, KS 66214
TEL 913.742.5000 FAX 913.742.5001
WWW.HENDERSONENGINEERS.COM
2150001893
TX, CORPORATE NO. F-001236
EXPIRES 9/30/2022

Date	No.	Description
09/13/21		75% SET
10/04/21		90% SET
10/18/21		LL APPROVAL SET
11/19/2021		PERMIT SET
12/15/2021	1	PERMIT SET REVISION 1
01/07/2022	2	PERMIT SET REVISION 2
03/07/2022	3	PERMIT SET REVISION 3
04/01/2022	4	BID SET
05/23/2022	5	ISSUE FOR CONSTRUCTION



05/20/2022

NIKE BY SOUTHLAKE

167 GRAND AVE.
SOUTHLAKE, TX 76092

Project Number:
Config: R/L
Drawn By: HENDERSON
Checked By: HENDERSON

MECHANICAL
ENERGY CODE
COMPLIANCE

M-500

COMcheck Software Version 4.1.5.3 Mechanical Compliance Certificate

Project Information

Energy Code: 2018 IECC
Project Title: Nike Live - Southlake
Location: Southlake, Texas
Climate Zone: 3a
Project Type: Alteration

Construction Site: Southlake Town Square
1560 E Southlake Blvd
Southlake, TX 76092
Owner/Agent: Nike
1 Bowerman Dr
Beaverton, OR 97005
503-971-6453
Designer/Contractor: Henderson Engineers
8345 Lenexa Dr
Suite 300
Lenexa, KS 66214
913-742-5000

Mechanical Systems List

Quantity System Type & Description

- EHU-1 (Single Zone):
Heating: 1 each - Unit Heater, Electric, Capacity = 34 kBtu/h
No minimum efficiency requirement applies.
Fan System: EHU-1 - Compliance (Motor nameplate HP method) - Passes
Fans:
EHU1 Supply, Constant Volume, 600 CFM, 0.0 motor nameplate hp, 0.0 fan efficiency grade
- Water Heater 1:
Electric Storage Water Heater, Capacity: 20 gallons w/ Circulation Pump
Proposed Efficiency: 1.65 SL, %/h (f = 12 kW), Required Efficiency: 1.65 SL, %/h (f = 12 kW)

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical alteration project represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2018 IECC requirements in COMcheck Version 4.1.5.3 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Jared Bennett: Mechanical Designer
Name - Title: Signature: Date: 09/23/2021

Project Title: Nike Live - Southlake Report date: 09/23/21
Data filename: J:\Programs\NikeLive\2150001893 Nike Live - Southlake, TX\0000\Energy\2150001893 COMChk Page 1 of 10
-2018IECC.cck

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C402.2.6 [ME41]	Thermally ineffective panel surfaces of sensible heating panels have insulation >= R-3.5.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.11.3 [ME61]	HVAC piping insulation installed in accordance with Table C403.11.3. Insulation exposed to weather is protected from damage and is provided with shielding from solar radiation.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.8.4 [ME42]	Motors for fans that are not less than 1/2 hp and less than 1 hp are electrically controlled motors or have a minimum motor efficiency of 70 percent. These motors have the means to adjust motor speed.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.8.5 [ME43]	Each DX cooling system > 65 kBtu/h and chiller water/evaporative cooling system with fans > 1/4 hp are designed to vary the indoor fan airflow as a function of load and comply with detailed requirements of this section.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.12.1 [ME71]	Systems that heat outside the building envelope are radiant heat systems controlled by an occupancy sensing device or timer switch.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.2.3 [ME55]	HVAC equipment efficiency verified.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	See the Mechanical Systems list for values.
C403.2.2 [ME57]	Natural or mechanical ventilation is provided in accordance with International Mechanical Code Chapter 4. Mechanical ventilation has capability to reduce outdoor air supply to minimum per IMC Chapter 4.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.7.1 [ME59]	Demand control ventilation provided for spaces >500 ft2 and >25 people/1000 ft2 occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow >3,000 cfm.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.7.2 [ME115]	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.7.6 [ME141]	HVAC systems serving guestrooms in Group R-1 buildings with > 50 guestrooms. Each guestroom is provided with controls that automatically manage temperature setpoint and ventilation (see sections C403.7.6.1 and C403.7.6.2).	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.7.4 [ME57]	Exhaust air energy recovery on systems meeting Table C403.7.4(1) and C403.7.4(2).	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Where the largest exhaust source is less than 75% of the design outdoor airflow.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Nike Live - Southlake Report date: 09/23/21
Data filename: J:\Programs\NikeLive\2150001893 Nike Live - Southlake, TX\0000\Energy\2150001893 COMChk Page 5 of 10
-2018IECC.cck

COMcheck Software Version 4.1.5.3 Inspection Checklist

Energy Code: 2018 IECC

Requirements: 100.0% were addressed directly in the COMcheck software

Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Plan Review	Complies?	Comments/Assumptions
C103.2 [PK2]	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical systems and equipment and document where exceptions to the standard are claimed. Load calculations per acceptable engineering standards and handbooks.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C103.2 [PK3]	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the service water heating systems and equipment and document where exceptions to the standard are claimed. Hot water system sized per manufacturer's sizing guide.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Nike Live - Southlake Report date: 09/23/21
Data filename: J:\Programs\NikeLive\2150001893 Nike Live - Southlake, TX\0000\Energy\2150001893 COMChk Page 2 of 10
-2018IECC.cck

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C403.7.5 [ME116]	Kitchen exhaust systems comply with replacement air and conditioned supply air limitations, and satisfy hood rating requirements and maximum exhaust rate criteria.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C403.11.1 [ME60]	HVAC ducts and plenums insulated in accordance with C403.11.1 and C403.11.2, verification may need to occur during Foundation Inspection.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.4.1 [ME63]	Heating for vestibules and air curtains with integral heating include automatic controls that shut off the heating system when outdoor air temperatures > 45F. Vestibule heating and cooling systems controlled by a thermostat in the vestibule with heating setpoint <= 60F and cooling setpoint <= 60F.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C408.2.2 [ME53]	Air outlets and zone terminal devices have means for air balancing.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.1 [ME123]	Refrigerated display cases, walk-in coolers or walk-in freezers served by remote compressors and remote condensers not located in a condensing unit, have fan-powered condensers that comply with Sections C403.5.1 and refrigeration compressor systems that comply with C403.5.2.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Nike Live - Southlake Report date: 09/23/21
Data filename: J:\Programs\NikeLive\2150001893 Nike Live - Southlake, TX\0000\Energy\2150001893 COMChk Page 6 of 10
-2018IECC.cck

Section # & Req.ID	Footing / Foundation Inspection	Complies?	Comments/Assumptions
C403.12.2 [F09]	Snowmelt melting system and freeze protection systems have sensors and controls configured to limit service for pavement temperature and outdoor temperature, future connection to controls.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Nike Live - Southlake Report date: 09/23/21
Data filename: J:\Programs\NikeLive\2150001893 Nike Live - Southlake, TX\0000\Energy\2150001893 COMChk Page 3 of 10
-2018IECC.cck

Section # & Req.ID	Rough-In Electrical Inspection	Complies?	Comments/Assumptions
C405.6 [EL26]	Low-voltage dry-type distribution electric transformers meet the minimum efficiency requirements of Table C405.6.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C405.7 [EL27]	Electric motors meet the minimum efficiency requirements of Tables C405.7(1) through C405.7(4). Efficiency verified through certification under an approved certification program or the equipment efficiency ratings shall be provided by motor manufacturer (where certification programs do not exist).	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C405.8.2 [EL28]	Escalators and moving walks comply with ASME A17.1/CSA B44 and have automatic controls configured to reduce speed to the minimum permitted speed in accordance with ASME A17.1/CSA B44 or applicable local code when not conveying passengers.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C405.9 [EL29]	Total voltage drop across the combination of feeders and branch circuits <= 5%.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Nike Live - Southlake Report date: 09/23/21
Data filename: J:\Programs\NikeLive\2150001893 Nike Live - Southlake, TX\0000\Energy\2150001893 COMChk Page 7 of 10
-2018IECC.cck

Section # & Req.ID	Plumbing Rough-In Inspection	Complies?	Comments/Assumptions
C404.5.1 [PL6]	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.5.2 [PL6]	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.6.1 [PL7]	Automatic time switches installed to automatically switch off the recirculating hot-water system or heat trace.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.6.2 [PL7]	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.6.3 [PL7]	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.7 [PL8]	Demand recirculation water systems have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Exception: Requirement does not apply.
C404.7 [PL8]	Demand recirculation water systems have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Nike Live - Southlake Report date: 09/23/21
Data filename: J:\Programs\NikeLive\2150001893 Nike Live - Southlake, TX\0000\Energy\2150001893 COMChk Page 4 of 10
-2018IECC.cck

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C303.3 [F18]	Furnished O&M manuals for HVAC systems within 90 days of system acceptance.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.2 [F17]	HVAC systems and equipment capacity does not exceed calculated loads.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4 [F14]	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per zone. Humidification/dehumidification system.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.4.1 [F13]	Thermostatic controls have a 5 °F deadband.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1 [F13]	Temperature controls have setpoint overlap restrictions.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.2 [F13]	Each zone equipped with setback controls using automatic time clock or programmable control system.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.3 [F14]	Automatic Controls: Setback to 55°F (heat) and 55°F (cool), 7-day clock, 2-hour occupant override, 10-hour backup.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.4 [F14]	Systems include optimum start controls.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.3 [F11]	Heat traps installed on supply and discharge piping of non-circulating systems.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.4 [F12]	All piping insulated in accordance with section details and Table C403.11.3.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C404.6.1 [F12]	Controls are installed that limit the operation of a recirculation pump installed to maintain temperature of a storage tank. System return pipe is a dedicated return pipe or a cold water supply pipe.	<input type="checkbox"/> Complies <input checked="" type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Nike Live - Southlake Report date: 09/23/21
Data filename: J:\Programs\NikeLive\2150001893 Nike Live - Southlake, TX\0000\Energy\2150001893 COMChk Page 8 of 10
-2018IECC.cck

