

SECTION 23 00 00 - MECHANICAL GENERAL REQUIREMENTS

- PART 1 - GENERAL
1. THE TERM "TENANT," "TENANT'S CONSTRUCTION MANAGER," "OWNER," OR "OWNER'S CONSTRUCTION MANAGER" SHALL REFER TO SWEETGREEN.
2. THE GENERAL CONTRACTOR SHALL PROVIDE ALL MATERIALS AND LABOR AS REQUIRED TO PROVIDE A COMPLETE WORKING SYSTEM AND AS DESCRIBED IN THESE DRAWINGS.
3. THE GENERAL CONTRACTOR SHALL REVIEW A COMPLETE SET OF THE CONSTRUCTION DOCUMENTS. EACH SUB-CONTRACTOR SHALL MAINTAIN A COMPLETE SET OF DRAWINGS ON SITE DURING THE CONSTRUCTION PROCESS.
4. COORDINATE WORK AS REQUIRED WITH THE LANDLORD. THE GENERAL CONTRACTOR SHALL UTILIZE LANDLORD-REQUIRED CONTRACTORS AT THE GENERAL CONTRACTOR'S EXPENSE.
PART 2 - PRODUCTS
1. PRODUCTS SHALL BE AS DESCRIBED IN THE DRAWINGS AND AS REQUIRED FOR A COMPLETE AND FUNCTIONING SYSTEM.
PART 3 - EXECUTION
UNLESS DIMENSIONS HAVE BEEN PROVIDED, THE DRAWINGS ARE DIAGRAMMATIC IN NATURE, SHOWING THE GENERAL LOCATION, TYPE, LAYOUT AND REQUIRED EQUIPMENT. THEY SHALL NOT BE SCALED. COORDINATE WITH THE ARCHITECTURAL DRAWINGS, TENANT VENDORS AND MANUFACTURER'S INSTALLATION INSTRUCTIONS AND CUTSHEETS AS REQUIRED.
2. COMPLETE ALL WORK IN COMPLIANCE WITH THE CODES LISTED ON SHEET G-001 INCLUDING ALL LOCAL AMENDMENTS, ALL RELEVANT NFPA CODES AND STANDARDS AND SMACNA STANDARDS.
A. VERIFY ALL CODE REQUIREMENTS AND LOCAL AMENDMENTS WITH THE AUTHORITY HAVING JURISDICTION PRIOR TO BID.
B. WHEN THERE IS A DISCREPANCY BETWEEN THE ADOPTED CODES AND THESE DRAWINGS, THE MORE STRINGENT REQUIREMENT SHALL APPLY.
3. COORDINATE WITH THE LOCAL AUTHORITY HAVING JURISDICTION AND ARRANGE ALL INSPECTIONS AS REQUIRED.
4. MAINTAIN A CLEAN CONSTRUCTION SITE DURING CONSTRUCTION. CLEAN SCRAP MATERIAL AND REMOVE FROM SITE DAILY AND MAINTAIN WORKING AREA IN AN ORDERLY FASHION.
5. PROVIDE SUBMITTALS AS NOTED IN THESE SPECIFICATIONS AND AS REQUESTED BY THE TENANT'S CONSTRUCTION MANAGER.
A. ALL SHOP DRAWINGS SHALL BE REVIEWED AND STAMPED BY THE GENERAL CONTRACTOR PRIOR TO SUBMITTING TO THE TENANT'S CONSTRUCTION MANAGER.
B. SHOP DRAWINGS SHALL BE SUBMITTED TO ALLOW FOR FIVE BUSINESS DAYS OF REVIEW TIME.
6. PROVIDE REQUESTS FOR INFORMATION TO THE TENANT'S CONSTRUCTION MANAGER.
A. ALL SHOP DRAWINGS SHALL PROVIDE A DETAILED DESCRIPTION OF THE SITE CONDITION OR DISCREPANCY AND THE CONTRACTORS PROPOSED REMEDY.
B. REQUESTS FOR INFORMATION SHALL BE SUBMITTED TO ALLOW FOR FIVE BUSINESS DAYS OF REVIEW TIME.
7. UPON COMPLETION OF WORK, THE GENERAL CONTRACTOR SHALL PROVIDE THE TENANT'S CONSTRUCTION MANAGER WITH A BOUND RECORD OF ALL MECHANICAL EQUIPMENT UTILIZED IN THE JOB. THE GENERAL CONTRACTOR SHALL PROVIDE THE SAME INFORMATION ON A COMPACT DISC. THE BINDER SHALL CONTAIN:
A. COVER SHEET INDICATING THE PROJECT NAME, ADDRESS AND TURNOVER DATE.
B. COMPANY NAME AND CONTACT INFORMATION OF THE CONTRACTORS UTILIZED FOR THE MECHANICAL SCOPE OF WORK.
C. CUTSHEETS, INSTALLATION MANUALS AND MAINTENANCE REQUIREMENTS FOR ALL MECHANICAL EQUIPMENT.
8. UPON COMPLETION OF WORK, THE GENERAL CONTRACTOR SHALL PROVIDE THE TENANT'S CONSTRUCTION MANAGER A FULL SET OF DRAWINGS WITH ANY DEVIATIONS FROM THE DRAWINGS INDICATED IN RED INK.

(END OF SECTION 23 00 00)

SECTION 23 05 93 - TESTING, ADJUSTING AND BALANCING FOR HVAC

- PART 1 - GENERAL
1. QUALITY ASSURANCE- ALL TESTING AND BALANCING WORK SHALL BE COMPLETED BY AN INDEPENDENT CONTRACTOR, CERTIFIED BY NEBB OR TABB AS A TAB TECHNICIAN. BALANCE THE SYSTEM IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING STANDARDS.
PART 2 - PRODUCTS: NA
PART 3 - EXECUTION
1. AIR SYSTEMS
A. PROVIDE ALL LABOR AND MATERIALS REQUIRED TO BALANCE THE SYSTEM AS NOTED ON THE PLANS.
B. FAN SYSTEMS SHALL BE ADJUSTED SUCH THAT THE LOWEST FAN SPEED IS UTILIZED TO DELIVER THE REQUIRED CFM TO THE AIR TERMINALS.
C. ADJUST DAMPERS AS REQUIRED TO BALANCE THE SUPPLY, RETURN AND EXHAUST SYSTEMS TO 10% OF THE DESIGN RATES. ADJUST THE OUTSIDE AIR DAMPER AS REQUIRED TO OBTAIN THE MINIMUM OUTSIDE AIR REQUIREMENTS AS NOTED IN THE SCHEDULES.
D. RECORD THE OPERATING VOLTAGE, AMPACITY, SUPPLY/RETURN SYSTEM STATIC PRESSURES, SUPPLY/MIXED AIR TEMPERATURES (BOTH HEATING AND COOLING) AND FINAL FAN RPM.
E. VERIFY SYSTEM CONTROLS ARE FUNCTIONING AS INTENDED.
2. REPORTING
A. THE TEST AND BALANCE AGENT SHALL PREPARE A REPORT INCLUDING THE FINAL VALUES OF THE AIR AND WATER SYSTEM BALANCING, SYSTEM DIAGRAMS, AND SYSTEM NOTES.
B. THE GENERAL CONTRACTOR SHALL REVIEW THE FINAL BALANCE REPORT PRIOR TO SENDING TO THE TENANT'S CONSTRUCTION MANAGER.
C. PROVIDE TAB REPORT TO THE LANDLORD AND THE AUTHORITY HAVING JURISDICTION AS REQUIRED.

(END OF SECTION 23 05 93)

SECTION 23 07 13 - DUCT INSULATION

- PART 1 - GENERAL
1. INSULATION SHALL BE PROVIDED ON THE FOLLOWING DUCT SERVICES:
A. INDOOR, CONCEALED SUPPLY AND OUTDOOR AIR.
B. INDOOR, CONCEALED RETURN.
C. INDOOR, CONCEALED OVEN AND WAREWASH EXHAUST FROM AIR TERMINAL TO PENETRATION OF BUILDING EXTERIOR.
D. INDOOR, CONCEALED GENERAL EXHAUST FROM AIR TERMINAL TO PENETRATION OF BUILDING EXTERIOR.
E. OUTDOOR, SUPPLY AND RETURN.
2. QUALITY ASSURANCE
A. INSULATION INSTALLED INDOORS SHALL HAVE A FLAME-SPREAD INDEX OF 25 OR LESS, AND SMOKE-DEVELOPED INDEX OF 50 OR LESS.
B. INSULATION INSTALLED OUTDOORS SHALL HAVE A FLAME-SPREAD INDEX OF 75 OR LESS, AND SMOKE-DEVELOPED INDEX OF 150 OR LESS.
PART 2 - PRODUCTS
1. INTERIOR DUCTWORK SHALL HAVE FLEXIBLE FIBERGLASS DUCT WRAP LAMINATED TO FOIL, REINFORCED KRAFT VAPOR BARRIER FACINGS WITH 2" STAPLING FLANGE AND AN INSTALLED THICKNESS OF 1-1/2" WITH AN R-VALUE OF 6.0.
2. EXTERIOR DUCTWORK SHALL BE INSULATED WITH 2" THICK RIGID INSULATION WITH A MINIMUM R-VALUE OF 12.0, PROTECTED WITH ROOFING MEMBRANE.
PART 3 - EXECUTION
1. PREPARATION: CLEAN AND DRY SURFACES. REMOVE MATERIALS THAT WILL ADVERSELY AFFECT INSULATION APPLICATION.
2. GENERAL INSTALLATION REQUIREMENTS:
A. INSTALL INSULATION ACCORDING TO MANUFACTURER'S INSTALLATION INSTRUCTIONS.
B. INSTALL INSULATION AND ACCESSORIES AND FINISHES WITH SMOOTH, STRAIGHT AND EVEN SURFACES, FREE OF VOIDS THROUGHOUT THE LENGTH OF DUCT AND FITTINGS.
C. INSTALL ACCESSORIES COMPATIBLE WITH INSULATION MATERIALS AND SUITABLE FOR THE SERVICE. ACCESSORIES SHALL NOT CORRODE, SOFTEN OR OTHERWISE ATTACK INSULATION OR JACKETS IN EITHER WET OR DRY STATE.
D. INSTALL INSULATION WITH LONGITUDINAL SEAMS AT TOP OF HORIZONTAL RUNS. LONGITUDINAL SEAMS AND END JOINTS SHALL BE TIGHT. BOND SEAMS AND JOINTS WITH ADHESIVE RECOMMENDED BY INSULATION MANUFACTURER TO MAINTAIN VAPOR BARRIER INTEGRITY.
E. APPLY ADHESIVES, MASTICS AND SEALANTS AT MANUFACTURER'S RECOMMENDED COVERAGE RATE.
F. CUT INSULATION IN A MANNER TO AVOID COMPRESSING INSULATION MORE THAN 75 PERCENT OF ITS NOMINAL THICKNESS.
3. PENETRATIONS
A. ROOF PENETRATIONS: INSTALL INSULATION CONTINUOUSLY THROUGH ROOF PENETRATIONS. FOR APPLICATIONS REQUIRING ONLY INDOOR INSULATION, TERMINATE INSULATION ABOVE ROOF SURFACE AND SEAL WITH JOINT SEALANT. FOR APPLICATIONS REQUIRING INDOOR AND OUTDOOR INSULATION, INSTALL INSULATION FOR OUTDOOR APPLICATIONS TIGHTLY JOINED TO INDOOR INSULATION ENDS. SEAL JOINT WITH JOINT SEALANT.
B. WALL PENETRATIONS: INSTALL INSULATION CONTINUOUSLY THROUGH WALL PENETRATIONS. FOR APPLICATIONS REQUIRING ONLY INDOOR INSULATION, TERMINATE INSULATION ABOVE ROOF SURFACE AND SEAL WITH JOINT SEALANT. FOR APPLICATIONS REQUIRING INDOOR AND OUTDOOR INSULATION, INSTALL INSULATION FOR OUTDOOR APPLICATIONS TIGHTLY JOINED TO INDOOR INSULATION ENDS. SEAL JOINT WITH JOINT SEALANT.
C. INTERIOR WALLS: INSTALL INSULATION CONTINUOUSLY THROUGH WALLS AND PARTITIONS THAT ARE NOT FIRE RATED. TERMINATE INSULATION AT FIRE DAMPER SLEEVES FOR FIRE-RATED WALL AND PARTITION PENETRATIONS. EXTERNALLY INSULATE THE DAMPER SLEEVES TO MATCH ADJACENT INSULATION AND OVERLAP DUCT INSULATION AT LEAST 2 INCHES.

(END OF SECTION 23 07 13)

SECTION 23 31 13 - METAL DUCTS

- PART 1 - GENERAL
1. SECTION INCLUDES
A. RECTANGULAR DUCTS AND FITTINGS
B. ROUND DUCTS AND FITTINGS
C. DOUBLE-WALL DUCTWORK AND FITTINGS
D. FLAT OVAL DUCTS AND FITTINGS
E. SHEET METAL MATERIALS
F. SEALANTS AND GASKETS
G. HANGERS AND SUPPORTS
2. PERFORMANCE REQUIREMENTS
A. DUCT CONSTRUCTION, INCLUDING SHEET METAL THICKNESS, SEAM AND JOINT CONSTRUCTION, REINFORCEMENTS AND HANGERS/SUPPORTS SHALL COMPLY WITH THE LATEST VERSION OF SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE."
B. DUCT HANGERS AND SUPPORTS SHALL WITHSTAND THE EFFECTS OF GRAVITY LOADS AND STRESSES WITHIN LIMITS UNDER CONDITIONS DESCRIBED IN SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE."
C. SURFACES IN CONTACT WITH THE AIRSTREAM SHALL COMPLY WITH REQUIREMENTS IN ANSI/ASHRAE 62.1.
3. SECTION REQUIREMENTS
A. SUBMITTALS: NONE REQUIRED.
PART 2 - PRODUCTS
1. RECTANGULAR DUCTS AND FITTINGS:
A. COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE" BASED ON INDICATED STATIC-PRESSURE CLASS UNLESS NOTED OTHERWISE.
B. TRANSVERSE JOINTS: SELECT JOINT TYPES AND FABRICATE ACCORDING TO SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE," FIGURE 2-1 FOR STATIC PRESSURE CLASS, APPLICABLE SEALING REQUIREMENTS, MATERIALS INVOLVED, DUCT SUPPORT INTERVALS AND OTHER PROVISIONS AS REQUIRED.
C. LONGITUDINAL SEAMS: SELECT SEAM TYPES AND FABRICATE ACCORDING TO SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE," FIGURE 2-2 FOR STATIC PRESSURE CLASS, APPLICABLE SEALING REQUIREMENTS, MATERIALS INVOLVED, DUCT SUPPORT INTERVALS AND OTHER PROVISIONS AS REQUIRED.
D. ELBOWS, TRANSITIONS, BRANCH CONNECTIONS AND OTHER DUCT CONSTRUCTION: SELECT TYPES AND FABRICATE ACCORDING TO SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE," CHAPTER 4 FOR STATIC-PRESSURE CLASS, APPLICABLE SEALING REQUIREMENTS, MATERIALS INVOLVED, DUCT SUPPORT INTERVALS AND OTHER PROVISIONS AS REQUIRED.
2. ROUND DUCTS AND FITTINGS:
A. SPIRAL LOCK SEAM, WITHOUT INSULATION.
B. BASIS OF DESIGN: LINDAB SAFE SINGLE WALL DUCTS AND FITTINGS. ALTERNATES BY MCGILL AIRFLOW. ALL DUCTWORK SHALL BE PREPPED AND READY TO RECEIVE PAINT.
3. FLAT OVAL DUCTS AND FITTINGS:
A. SPIRAL LOCK SEAM, WITHOUT INSULATION.
B. BASIS OF DESIGN: LINDAB FOHR FLAT-OVAL SPIRAL DUCTS AND FITTINGS. ALTERNATES BY MCGILL AIRFLOW. ALL DUCTWORK SHALL BE PREPPED AND READY TO RECEIVE PAINT.
4. DOUBLE-WALL DUCTWORK AND FITTINGS:
A. SPIRAL LOCK SEAM, WITH 1" INSULATION THICKNESS.
B. BASIS OF DESIGN: LINDAB SAFE DOUBLE WALL DUCTS AND FITTINGS. ALTERNATES BY MCGILL AIRFLOW.
5. MATERIALS: GALVANIZED SHEET STEEL, COMPLY WITH ASTM A 653A 653M, G90 COATING DESIGNATION.
6. SEALANTS AND GASKETS:
A. MAXIMUM FLAME-SPREAD INDEX: 25 (WHEN TESTED ACCORDING TO UL 723).
B. MAXIMUM SMOKE-DEVELOPED INDEX: 50 (WHEN TESTED ACCORDING TO UL 723).
C. TWO-PART TAPE SEALING SYSTEM: PROVIDE 3" TAPE CONSTRUCTED OF WOVEN COTTON FIBER IMPREGNATED WITH MINERAL GYPSUM AND MODIFIED ACRYLSILICONE TO FORM A HARD, DURABLE, AIR/TIGHT SEAL. SEALANT SHALL BE A MODIFIED STYRENE ACRYLIC, COMPATIBLE WITH GALVANIZED SHEET STEEL, WATER, MOLD AND MILDEW RESISTANT. VOC CONTENT OF 250% OR LESS.
D. WATER BASED JOINT AND SEAM SEALANT: BRUSH ON WITH MINIMUM OF 65% SOLIDS CONTENT, MINIMUM SHORE A HARDNESS OF 20. COMPATIBLE WITH GALVANIZED SHEET STEEL, WATER, MOLD AND MILDEW RESISTANT. VOC CONTENT OF 75% (LESS WATER).
7. HANGERS AND SUPPORT:
A. RECTANGULAR DUCTWORK: HANGER RODS SHALL BE CADMIUM-PLATED STEEL RODS AND NUTS. STRAP AND ROD SIZE SHALL COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE," TABLE 5-1. SECURE TO DUCT WITH SHEET METAL SCREWS COMPATIBLE WITH DUCT MATERIALS.
B. ROUND DUCTWORK: SUPPORT WITH AIRCRAFT CABLE COMPLYING WITH ASTM A 603. CONNECT ENDS WITH CADMIUM-PLATED STEEL ASSEMBLIES WITH BRACKETS, SWIVEL AND BOLTS DESIGNED FOR DUCT HANGER SERVICE.
C. EXTERIOR DUCTWORK SHALL BE PROVIDED WITH DUCT SUPPORTS, SPACED PER THE MANUFACTURER'S RECOMMENDATIONS.
PART 3 - EXECUTION
1. INSTALLATION
A. DRAWING PLANS, SCHEMATICS AND DIAGRAMS INDICATE GENERAL LOCATION AND ARRANGEMENT OF DUCTWORK ROUTING. COORDINATE INSTALLATION WITH WORK OF ALL OTHER TRADES AND EXISTING CONDITIONS. ACCOMMODATE DUCT HANGER, RODS, INSULATION AND OTHER REQUIREMENTS AS REQUIRED.
B. INSTALL DUCTS ACCORDING TO SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE" IN THEIR MAXIMUM PRACTICAL LENGTHS WITH FEWEST POSSIBLE JOINTS.
C. UNLESS NOTED OTHERWISE, INSTALL DUCTS PARALLEL TO BUILDING LINES.
D. INSTALL DUCTS WITH CLEARANCES AS REQUIRED TO ACCOMMODATE THE INSTALLATION OF INSULATION.
E. INSTALLATION OF EXPOSED DUCTWORK: PROTECT DUCTWORK FROM DAMAGE. REPAIR/REPLACE ALL DAMAGED SECTIONS AND FINISHED WORK. TRIM SEALANTS FLUSH WITH METAL. CREATE A SMOOTH AND UNIFORM EXPOSED BEAD. DO NOT USE TWO-PART TAPING SYSTEM. MAINTAIN CONSISTENCY, SYMMETRY AND UNIFORMITY IN THE INSTALLATION.
2. DUCT SEALING: CONSTRUCT DUCTS WITH 2 INCH POSITIVE AND NEGATIVE DUCT PRESSURE CLASSIFICATIONS.
3. HANGER AND SUPPORT INSTALLATION: COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE," CHAPTER 5. HANGERS EXPOSED TO VIEW SHALL BE AIRCRAFT IN ACCORDANCE WITH THE MECHANICAL DETAILS.
4. CONNECTIONS: MAKE CONNECTIONS TO EQUIPMENT WITH FLEXIBLE CONNECTORS COMPLYING WITH SECTION 23 33 00 "AIR DUCT ACCESSORIES." COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE" FOR BRANCH, OUTLET AND INLET, AND TERMINAL UNIT CONNECTIONS.
5. CLEANING: CLEAN ALL EXISTING DUCTWORK TO REMAIN PRIOR TO TESTING, ADJUSTING AND BALANCING. REMOVE ALL SURFACE CONTAMINANTS AND DEPOSITS ON AIR OUTLETS AND INLETS PRIOR TO PUNCH.
6. PROVIDE AIR BALANCE IN ACCORDANCE WITH SECTION 23 05 93 "TESTING, ADJUSTING, AND BALANCING FOR HVAC."
7. DUCT ELBOWS
A. RECTANGULAR: PROVIDE HOLLOW-FORMED, DOUBLE-THICKNESS TURNING VANES OR RADIIUSED ELBOWS WITH INSIDE RADIUS NO SMALLER THAN 1/2 OF THE DUCT WIDTH.
B. ROUND DUCT ELBOWS: PROVIDE RADIIUSED ELBOWS WITH AN INSIDE RADIUS NO SMALLER THAN 1.2 OF THE DUCT WIDTH.
8. BRANCH CONNECTIONS
A. RECTANGULAR: COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE," FIGURE 4.6. RECTANGULAR MAIN TO RECTANGULAR BRANCH SHALL BE 45-DEGREE ENTRY. RECTANGULAR MAIN TO ROUND BRANCH SHALL BE A SPIN-IN FITTING.
B. ROUND: COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE," FIGURE 3.5 AND FIGURE 3.6. PROVIDE 90 DEGREE TAP.

(END OF SECTION 23 31 13)

SECTION 23 33 00 - AIR DUCT ACCESSORIES

- PART 1 - GENERAL
1. SECTION INCLUDES
A. BACKDRAFT AND PRESSURE RELIEF DAMPERS
B. MANUAL VOLUME DAMPERS
C. CONTROL DAMPERS
D. FIRE DAMPERS
E. TURNING VANES
F. FLEXIBLE CONNECTORS
G. DUCT HARDWARE: HARDWARE
2. SECTION REQUIREMENTS
A. SUBMITTALS: NONE REQUIRED.
PART 2 - PRODUCTS
1. COMPLY WITH NFPA 90A AND WITH NFPA 90B.
2. COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS-METAL AND FLEXIBLE" FOR ACCEPTABLE MATERIALS, THICKNESS AND DUCT CONSTRUCTION METHODS UNLESS NOTED OTHERWISE. SHEET METAL MATERIALS SHALL BE FREE FROM PITTING, SEAM MARKS, ROLLER MARKS, STAIN, DISCOLORATIONS AND OTHER IMPERFECTIONS.
3. GALVANIZED SHEET STEEL: COMPLY WITH ASTM A 653A 653M, G90 COATING DESIGNATION.
4. BACKDRAFT AND PRESSURE RELIEF DAMPERS: GRAVITY BALANCED, AS SPECIFIED ON THE PLANS.
5. MANUAL VOLUME DAMPERS: STANDARD LEAKAGE RATING WITH LINKAGE OUTSIDE OF AIRFRAME, SUITABLE FOR HORIZONTAL OR VERTICAL APPLICATIONS
A. FRAME: HAT SHAPED WITH MITERED AND WELDED CORNERS, FLANGELESS FRAMES FOR INSTALLING IN DUCTS.
B. BLADES: RECTANGULAR DAMPERS SHALL MULTIPLE BLADES WITH OPPOSED BLADE DESIGN. ROUND DAMPERS SHALL BE SINGLE BLADE.
C. BLADE AXLES: GALVANIZED STEEL.
D. BEARINGS: MOLDED SYNTHETIC.
E. TIE BARS AND BRACKETS: GALVANIZED STEEL.
F. JACKSHAFT: 1/2" DIAMETER CONSTRUCTED OF GALVANIZED STEEL, WITHIN PIPE-BEARING ASSEMBLY WITH SUPPORTS. LENGTH AND NUMBER OF MOUNTINGS AS REQUIRED.
G. HARDWARE: ZINC-PLATED, DIE CAST CORE WITH DIAL HANDLE AND A LOCKING NUT.
6. CONTROL DAMPERS
A. FRAME: HAT SHAPED WITH MITERED AND WELDED CORNERS. FLANGELESS FRAMES FOR INSTALLING IN DUCTS.
B. BLADES: RECTANGULAR DAMPERS SHALL BE MULTIPLE BLADES WITH OPPOSED-BLADE DESIGN. ROUND DAMPERS SHALL BE SINGLE BLADE. BLADE EDGING SHALL BE REPLACEABLE RUBBER SEALS.
C. BLADE AXLES: 1/2" DIAMETER. BLADE LINKAGE HARDWARE OF ZINC-PLATED STEEL AND BRASS; ENDS SEALED AGAINST BLADE BEARING.
D. BEARINGS: MOLDED SYNTHETIC.
7. FIRE DAMPERS
A. TYPE: STATIC, RATED AND LABELED ACCORDING TO UL 555.
B. CLOSING RATINGS IN DUCTS UP TO 4" STATIC PRESSURE CLASS AND MAXIMUM 2,000 FPM VELOCITY.
C. FIRE RATINGS: 1-1/2 HOURS, OR AS NOTED IN THE SCHEDULES.
D. FRAME: CURTAIN TYPE WITH BLADES INSIDE AIRSTREAM. CONSTRUCTED OF GALVANIZED STEEL.
E. MOUNTING SLEEVE: FACTORY FURNISHED.
F. MOUNTING ORIENTATION: AS NOTED ON PLANS.
G. BLADES: INTERLOCKING, CONSTRUCTED OF GALVANIZED STEEL.
H. HEAT RESPONSIVE DEVICE: 165 DEGREE F RATED FIBRILE LINK OR AS NOTED IN THE SCHEDULES.
8. TURNING VANES: CURVED BLADES OF GALVANIZED SHEET STEEL, PROVIDED WITH SUPPORT BARS PERPENDICULAR TO BLADE SET. SUITABLE FOR DUCT MOUNTING. COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE," SINGLE WALL CONSTRUCTION.
9. FLEXIBLE CONNECTORS: CONSTRUCTED OF FLAME-RETARDANT OR NONCOMBUSTIBLE FABRIC. FABRIC SHALL BE A GLASS FABRIC, DOUBLE COATED WITH NEOPRENE. COMPLY WITH UL 181 CLASS 1. FACTORY-FABRICATED WITH A FABRIC STRIP 3-1/2 INCHES WIDE ATTACHED TO TWO STRIPS OF 2-3/4 INCH THICK GALVANIZED SHEET STEEL.
PART 3 - EXECUTION
1. INSTALLATION
A. INSTALL DUCT ACCESSORIES ACCORDING TO APPLICABLE DETAILS IN SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS-METAL AND FLEXIBLE."
B. INSTALL VOLUME DAMPERS WITH POINTS NOTED ON PLANS AND AS REQUIRED FOR SYSTEM BALANCING. WHERE DAMPERS ARE INSTALLED IN DUCTS WITH DUCT LINER, INSTALL DAMPERS WITH HAT CHANNELS OF SAME DEPTH AS LINER AND TERMINATE LINER WITH NOSING AT HAT CHANNEL.
C. SET DAMPERS TO FULLY OPEN POSITION BEFORE TESTING, ADJUSTING AND BALANCING.
D. INSTALL TEST HOLES IN FAN INLETS AND OUTLETS AND WHERE REQUIRED FOR TESTING AND BALANCING PURPOSES.
E. INSTALL FIRE DAMPERS ACCORDING TO UL LISTING.
F. INSTALL FLEXIBLE CONNECTORS TO CONNECT DUCTS TO EQUIPMENT.
2. TESTS AND INSPECTIONS
A. OPERATE DAMPERS TO VERIFY FULL RANGE OF MOVEMENT.
B. OPERATE FIRE DAMPERS TO VERIFY FULL RANGE OF MOVEMENT AND VERIFY THAT PROPER HEAT-RESPONSE DEVICE IS INSTALLED.
C. INSPECT TURNING VANES FOR PROPER AND SECURE INSTALLATION.

(END OF SECTION 23 33 00)

SECTION 23 33 46 - FLEXIBLE DUCTS

- PART 1 - GENERAL
1. SECTION REQUIREMENTS
A. SUBMITTALS: NONE REQUIRED.
PART 2 - PRODUCTS
1. COMPLY WITH NFPA 90A AND NFPA 90B.
2. COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE" FOR ACCEPTABLE MATERIALS, MATERIAL THICKNESS AND DUCT CONSTRUCTION METHODS UNLESS NOTED OTHERWISE.
3. COMPLY WITH ASTM F 4009 FPM.
4. INSULATED, FLEXIBLE DUCT UL 181, CLASS 1, FACTORY FABRICATED AND INSULATED. PROVIDED WITH INTERIOR LINER, FIBROUS-GLASS INSULATION AND VAPOR-BARRIER FILM.
A. PRESSURE RATING: 10" W.G. POSITIVE.
B. MAXIMUM VELOCITY: 4,000 FPM.
C. INSULATION R-VALUE: R-6.0.
5. FLEXIBLE DUCT CONNECTIONS SHALL BE NYLON STRAPS IN SIZES 3 THROUGH 18 INCHES TO SUIT DUCT SIZE.
PART 3 - EXECUTION
1. INSTALLATION
A. INSTALL FLEXIBLE DUCTS ACCORDING TO APPLICABLE DETAILS IN SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS - METAL AND FLEXIBLE."
B. INSTALL IN INDOOR APPLICATIONS ONLY. FLEXIBLE DUCTWORK IS ONLY PERMITTED TO CONNECT TO SUPPLY-AIR GRILLES, REGISTERS AND DIFFUSERS. MAXIMUM LENGTH SHALL BE 60 INCHES.
C. CONNECT FLEXIBLE DUCTS TO METAL DUCTS WITH DRAW BANDS AND TAPE.
D. INSTALL DUCTS FULLY EXTENDED.
E. DO NOT BEND DUCTS ACROSS SHARP CORNERS.
F. BENDS OF FLEXIBLE DUCTING SHALL NOT EXCEED A MINIMUM OF ONE DUCT DIAMETER.
G. AVOID CONTACT WITH METAL FIXTURES, WATER LINES, PIPES, ADJACENT DUCTWORK OR CONDUIT.
H. INSTALL FLEXIBLE DUCTS IN A DIRECT LINE, WITHOUT SAGS, TWISTS OR TURNS.
I. SUSPEND FLEXIBLE DUCTS WITH BANDS 1-1/2 INCHES WIDE AND SPACED A MAXIMUM OF 48 INCHES APART. PROVIDE ADDITIONAL SUPPORT AT BENDS. DUCTS MAY REST ON CEILING JOISTS OR TRUSS SUPPORTS. SPACING BETWEEN THESE ELEMENTS SHALL NOT EXCEED 48 INCHES.

(END OF SECTION 23 33 46)

SECTION 23 34 00 - SQUARE INLINE FANS

- PART 1 - GENERAL
1. SECTION REQUIREMENTS
A. SUBMITTALS: PROVIDE SHOP DRAWINGS INDICATING THE DIMENSIONS, WEIGHTS, REQUIRED CLEARANCES, COMPONENTS, ELECTRICAL CHARACTERISTICS, CFM, STATIC PRESSURE AND FAN CURVE.
B. WARRANTY: SUBMIT A WRITTEN WARRANTY, SIGNED BY THE MANUFACTURER AGREEING TO REPAIR OR REPLACE COMPONENTS OF FANS THAT FAIL IN MATERIALS OR WORKMANSHIP WITHIN THE MANUFACTURER'S STANDARD WARRANTY PERIOD.
PART 2 - PRODUCTS
1. DESCRIPTION
A. INLINE TYPE FAN WITH SQUARE INLET AND OUTLET DESIGNED FOR FLOOR-MOUNTING OR HUNG INSTALLATIONS IN-LINE WITH DUCTWORK WITH CENTRIFUGAL OR MIXED-FLOW WHEEL.
2. MANUFACTURERS: AS NOTED IN THE MECHANICAL SCHEDULES. NO SUBSTITUTIONS SHALL BE PERMITTED.
3. CHARACTERISTICS: PROVIDED WITH:
A. FAN: CONSTRUCTED OF CORROSION RESISTANT STEEL, DIRECT DRIVEN, SQUARE INLINE BLOWER.
B. HOUSING: CONSTRUCTED OF HEAVY-GAUGE GALVANIZED STEEL OR STAINLESS STEEL FOR UL726 LISTED FANS. SIDE PANELS SHALL BE REMOVEABLE FOR SERVICE ACCESS.
C. WHEEL: BACKWARD INCLINED, NON-OVERLOADING, ALL-ALUMINUM WHEEL, BALANCED IN ACCORDANCE WITH AMCA STANDARD 204-96.
D. MOTOR: VOLTAGE AS NOTED IN THE MECHANICAL SCHEDULES. MOTOR SHALL HAVE PERMANENTLY LUBRICATED BALL BEARINGS, SUPPLIED WITH A MOTOR COVER.
E. ACCESSORIES: AS NOTED ON THE MECHANICAL SCHEDULES.
PART 3 - EXECUTION
1. INSTALLATION
A. SUSPEND THE INLINE FAN FROM STRUCTURE WITH NEOPRENE-TYPE VIBRATION ISOLATORS, AS NOTED IN THE STRUCTURAL DRAWINGS.
2. CONNECTIONS
A. COMPLY WITH DUCT INSTALLATION REQUIREMENTS SPECIFIED IN OTHER HVAC SECTIONS. DRAWINGS INDICATE GENERAL ARRANGEMENTS OF DUCTS.
B. WHERE INSTALLING ADJACENT TO OTHER BUILDING SYSTEMS, ALLOW SPACE FOR SERVICE AND MAINTENANCE.
C. CONNECT DUCTWORK TO FAN WITH FLEXIBLE DUCT CONNECTORS.
D. CONNECT ELECTRICAL WIRING IN ACCORDANCE WITH THE ELECTRICAL SPECIFICATIONS.
E. GROUND EQUIPMENT IN ACCORDANCE WITH THE ELECTRICAL SPECIFICATIONS.
3. FIELD QUALITY CONTROL
A. AFTER INSTALLING FANS, TEST UNITS FOR COMPLIANCE WITH REQUIREMENTS.
B. CONFIRM PROPER MOTOR ROTATION AND UNIT OPERATIONS.
C. OPERATIONAL TEST: AFTER ELECTRICAL CIRCUITRY HAS BEEN ENERGIZED, START UNITS TO CONFIRM PROPER MOTOR ROTATION AND UNIT OPERATION.

(END OF SECTION 23 34 00)

SECTION 23 34 03 - UTILITY SET POWER VENTILATORS

- PART 1 - GENERAL
1. SECTION REQUIREMENTS
A. SUBMITTALS: PROVIDE SHOP DRAWINGS INDICATING THE DIMENSIONS, WEIGHTS, REQUIRED CLEARANCES, COMPONENTS, ELECTRICAL CHARACTERISTICS, CFM, STATIC PRESSURE AND FAN CURVE.
B. WARRANTY: SUBMIT A WRITTEN WARRANTY, SIGNED BY THE MANUFACTURER AGREEING TO REPAIR OR REPLACE COMPONENTS OF RVTS THAT FAIL IN MATERIALS OR WORKMANSHIP WITHIN THE MANUFACTURER'S STANDARD WARRANTY PERIOD.
PART 2 - PRODUCTS
1. DESCRIPTION
A. CENTRIFUGAL UPBLAST UTILITY EXHAUST VENTILATOR.
2. MANUFACTURERS: AS NOTED IN THE MECHANICAL SCHEDULES. NO SUBSTITUTIONS SHALL BE PERMITTED.
3. CHARACTERISTICS: PROVIDED WITH:
A. BASE: CONSTRUCTED OF GALVANIZED STEEL.
B. HOUSING: CONSTRUCTED OF ALUMINIZED AND GALVANIZED STEEL. FAN SCROLL SHALL BE CONTINUOUSLY SEALED AND TACK WELDED.
C. WHEEL: CENTRIFUGAL, BACKWARD INCLINED AND NON-OVERLOADING, BALANCED IN TWO PLANES IN ACCORDANCE WITH AMCA STANDARDS. WHEEL BLADES SHALL BE AERODYNAMICALLY DESIGNED TO MINIMIZE TURBULENCE AND REDUCE NOISE. WHEEL SHALL BE CONSTRUCTED OF HEAVY GAUGE WELDED ALUMINUM. ANY BALANCING WEIGHTS SHALL BE WELDED OR RIVETED TO THE BLADES OR WHEEL. WHEEL SHALL BE FIRMLY ATTACHED TO THE MOTOR SHAFT WITH SET SCREWS.
D. MOTOR: HEAVY DUTY BALL BEARING TYPE MOUNTED OUT OF THE AIRSTREAM AT THE VOLTAGE AND PHASE NOTED IN THE SCHEDULES. MOTOR COMPARTMENT SHALL BE COOLED BY OUTSIDE AIR. MOTOR COMPARTMENT SHALL BE COMPLETELY REMOVABLE WITH THE MOTOR COVER ASSEMBLY HAVING WING BOLTS TO SECURE THE ASSEMBLY TO THE HOUSING.
E. BELTS AND DRIVERS: BELTS SHALL BE HEAT AND OIL RESISTANT, NON-STATIC TYPE. DRIVERS SHALL BE CAST TYPE AND SIZED FOR A MINIMUM OF 50% OF THE INSTALLED MOTOR HORSEPOWER. FAN OPERATING SPEED SHALL BE FACTORY SET USING ADJUSTABLE PITCH PULLEYS. MOTORS OVER 2 HP TO BE FURNISHED WITH DOUBLE-GROOVE PULLEYS.
F. ACCESSORIES: AS NOTED ON THE MECHANICAL SCHEDULES.
PART 3 - EXECUTION
1. INSTALLATION
A. UNIT SUPPORT: INSTALL ON ROOF RAILS ON ROOF STRUCTURE, LEVEL, SECURE, PER STRUCTURAL DETAILS AND PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
2. CONNECTIONS
A. COMPLY WITH DUCT INSTALLATION REQUIREMENTS SPECIFIED IN OTHER HVAC SECTIONS. DRAWINGS INDICATE GENERAL ARRANGEMENTS OF DUCTS.
B. CONNECT TO FANS WITH FLEXIBLE DUCT CONNECTORS.
C. WHERE INSTALLING PIPING ADJACENT TO FANS, ALLOW SPACE FOR SERVICE AND MAINTENANCE.
D. CONNECT ELECTRICAL WIRING IN ACCORDANCE WITH THE ELECTRICAL SPECIFICATIONS.
E. GROUND EQUIPMENT IN ACCORDANCE WITH THE ELECTRICAL SPECIFICATIONS.
3. FIELD QUALITY CONTROL
A. AFTER INSTALLING FANS, TEST UNITS FOR COMPLIANCE WITH REQUIREMENTS.
B. INSPECT AND REMOVE SHIPPING BOLTS, BLOCKS AND TIE-DOWN STRAPS.
C. CONFIRM PROPER MOTOR ROTATION AND UNIT OPERATIONS.
D. TEST AND ADJUST CONTROLS AND SAFETIES. REPLACE DAMAGED AND MALFUNCTIONING CONTROLS AND EQUIPMENT.
E. OPERATIONAL TEST: AFTER ELECTRICAL CIRCUITRY HAS BEEN ENERGIZED, START UNITS TO CONFIRM PROPER MOTOR ROTATION AND UNIT OPERATION.

(END OF SECTION 23 34 03)

HVAC GENERAL NOTES

- A GENERAL NOTES APPLY TO ALL HVAC SHEETS.
B WORK SHALL COMPLY WITH STATE AND LOCAL CODE REQUIREMENTS AS APPROVED AND AMENDED BY THE AUTHORITY HAVING JURISDICTION, INCLUDING APPLICABLE SECTIONS OF NFPA, THE MECHANICAL CODE, AND ANY INTERIM AMENDMENTS AT THE TIME OF THE PROPOSAL. PURCHASE PERMITS ASSOCIATED WITH THE WORK, OBTAIN INSPECTIONS REQUIRED BY CODE. SEE SHEET G-001 FOR THE PREVAILING CODES.
C CONTRACTOR AND SUBCONTRACTORS SHALL REVIEW A COMPLETE SET OF THE CONSTRUCTION DOCUMENTS.
D COORDINATE WORK WITH THE WORK OF OTHER TRADES, EQUIPMENT FURNISHED BY OTHERS, REQUIREMENTS OF THE OWNER, AND OF THE EXISTING CONDITIONS AT THE PROJECT SITE.
E DRAWINGS FOR THE MECHANICAL WORK ARE DIAGRAMMATIC, SHOWING THE GENERAL LOCATION, TYPE, LAYOUT, AND EQUIPMENT REQUIRED. THE DRAWING SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. REFER TO ARCHITECTURAL DRAWINGS FOR DIMENSIONS. REFER TO MANUFACTURER'S STANDARD INSTALLATION DRAWINGS FOR EQUIPMENT CONNECTIONS AND INSTALLATION REQUIREMENTS. PROVIDE DUCTWORK, CONNECTIONS, OFFSETS, ACCESSORIES, AND MATERIALS NECESSARY FOR A COMPLETE SYSTEM.
F DUCT DIMENSIONS ON PLANS INDICATE DIMENSIONS OF INTERNAL FREE AREA.
G PERFORATED CEILING DIFFUSERS SHALL BE 4-WAY UNLESS NOTED OTHERWISE.
H COORDINATE ROOF WORK WITH THE LANDLORD AND THE OWNER'S CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION. UTILIZE THE LANDLORD'S ROOFING CONTRACTOR AT THE GENERAL CONTRACTOR'S EXPENSE WHEN REQUIRED.
I UNLESS NOTED OTHERWISE RECTANGULAR DUCT ELBOWS SHALL BE MITERED ELBOWS WITH DOUBLE-THICKNESS TURNING VANES. J REPLACE AIR FILTERS WITH NEW, CLEAN MERV8 FILTERS AT TURNOVER.
K THE TERM "FURNISH" OR "SUPPLY" MEANS SUPPLY AND DELIVER TO THE PROJECT SITE, READY FOR UNLOADING, UNPACKING, ASSEMBLY, INSTALLATION, AND SIMILAR OPERATIONS. THE TERM "INSTALL" DESCRIBES THE OPERATIONS AT THE PROJECT SITE INCLUDING THE ACTUAL UNLOADING, UNPACKING, ASSEMBLY, ERECTING, PLACING, ANCHORING, APPLYING, WORKING TO DIMENSION, FINISHING, CURING, PROTECTING, CLEANING, AND SIMILAR OPERATIONS. THE TERM "PROVIDE" MEANS TO FURNISH AND INSTALL, COMPLETE AND READY FOR THE INTENDED USE.
L A FINAL REPORT FOR THE TESTING AND ADJUSTMENTS OF ALL NEW SYSTEMS FROM ALL DISCIPLINES SHALL BE COMPLETED WITH FINAL APPROVAL BY THE FIELD INSPECTOR. THIS REPORT SHALL BE SIGNED BY THE INDIVIDUAL RESPONSIBLE FOR PERFORMING THESE SERVICES.
M TESTING AND BALANCING OF THE MECHANICAL SYSTEMS TO BE COMPLETED BY NATIONALTAB AT THE GENERAL CONTRACTOR'S EXPENSE. THE CONTRACTOR SHALL CONTRACT WITH, SCHEDULE AND SUPERVISE/ASSIST NATIONALTAB AS REQUIRED. REFER TO THE COVER SHEET, OR CONTACT SWEETGREEN'S CONSTRUCTION MANAGER FOR CONTACT INFORMATION.
N ALL DUCT AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED WITH TAPE, PLASTIC, OR SHEET METAL UNTIL THE FINAL START UP OF THE HEATING, COOLING, AND VENTILATION EQUIPMENT.
O REFER TO THE TRANE AND CAPTIVE-AIRE NATIONAL ACCOUNT INFORMATION BLOCKS ON SHEET M-300 FOR REPRESENTATIVE CONTACT INFORMATION.
P CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY UNIT CONFIGURATIONS, COORDINATE DELIVERY WITH TRANE, RECEIVE AND UNLOAD EQUIPMENT, INSPECT EQUIPMENT AND PROPERLY INSTALL EQUIPMENT INCLUDING FIELD-INSTALLED ITEMS. PROVIDE EQUIPMENT STARTUP AND 1ST YEAR LABOR WARRANTY AND ADMINISTRATION.
Q PROVIDE ALL REQUIRED FIRESTOPPING AND SLEEVES AS REQUIRED FOR ALL LINESET PIPING, CONTROL AND POWER WIRING AND ALL OTHER SYSTEMS PENETRATING FIRE-RATED PARTITIONS.

sg logo
sweetgreen
3101 W. EXPOSITION BLVD.
LOS ANGELES, CALIFORNIA 90018

THESE DRAWINGS & SPECIFICATIONS ARE CONFIDENTIAL AND SHALL REMAIN THE SOLE PROPERTY OF SWEETGREEN CORPORATION. THEY SHALL NOT BE REPRODUCED IN WHOLE OR IN PART, SHARED WITH THIRD PARTIES OR USED IN ANY MANNER ON OTHER PROJECTS OF ANY TYPE AND MAY NOT BE REPRODUCED WITHOUT THE PRIOR WRITTEN CONSENT OF SWEETGREEN CORPORATION. THESE DRAWINGS & SPECIFICATIONS ARE INTENDED TO EXPRESS DESIGN INTENT FOR A PROTOTYPICAL SWEETGREEN STORE WHICH IS SUBJECT TO CHANGE AT ANY TIME AND MAY NOT REFLECT ACTUAL SITE CONDITIONS. NEITHER PARTY SHALL HAVE ANY OBLIGATION NOR LIABILITY TO THE OTHER EXCEPT AS STATED ABOVE UNTIL A WRITTEN AGREEMENT IS FULLY EXECUTED.

ENGINEER OF RECORD:
EVERJ ENGINEERING, INC.
1509 BUCK TRAIL LANE
WORTHINGTON, OH 43085
240-319-0822
www.everjengineering.com

STAMP:

CONSTRUCTION ISSUE SET

PROJECT INFORMATION: THE YARD AT FISHERS DISTRICT
PROJECT INFORMATION: 9711 E. 116TH ST, SUITE 310 FISHERS, IN 46037
08/15/2022

Table with 2 columns: Field Name, Value. Includes DRAWN BY: JAE, CHECKED BY: MK, PROJECT MANAGER: JAE, SG DESIGN MANAGER: LK, SG CONSTR. MANAGER: JB, PROJECT NO: 210023, TEMPLATE VERSION: 12/21/2021

Table with 3 columns: REVISIONS, REV., DATE, DESCRIPTION

MECHANICAL SPECIFICATIONS

M-010




sweetgreen

3101 W. EXPOSITION BLVD.
LOS ANGELES, CALIFORNIA 90018

THESE DRAWINGS & SPECIFICATIONS ARE CONFIDENTIAL AND SHALL REMAIN THE SOLE PROPERTY OF SWEETGREEN CORPORATION. THEY SHALL NOT BE REPRODUCED (IN WHOLE OR IN PART), SHARED WITH THIRD PARTIES OR USED IN ANY MANNER ON OTHER PROJECTS OR EXTENSIONS TO THIS PROJECT WITHOUT THE PRIOR WRITTEN CONSENT OF SWEETGREEN CORPORATION. THESE DRAWINGS & SPECIFICATIONS ARE INTENDED TO EXPRESS DESIGN INTENT FOR A PROTOTYPICAL SWEETGREEN STORE WHICH IS SUBJECT TO CHANGE AT ANY TIME AND MAY NOT REFLECT ACTUAL SITE CONDITIONS. NEITHER PARTY SHALL HAVE ANY OBLIGATION OR LIABILITY TO THE OTHER EXCEPT AS STATED ABOVE UNLESS A WRITTEN AGREEMENT IS FULLY EXECUTED.

ENGINEER OF RECORD:



EVERJ ENGINEERING, INC.
1509 BUCK TRAIL LANE
WORTHINGTON, OH 43085
240-319-0822
www.everjengineering.com

STAMP:

CONSTRUCTION
ISSUE SET

08/15/2022

PROJECT INFORMATION:
**THE YARD AT FISHERS
DISTRICT**
PROJECT INFORMATION:
**9711 E. 116TH ST, SUITE 310
FISHERS, IN 46037**

DRAWN BY: JAE
CHECKED BY: MK
PROJECT MANAGER: JAE
SG DESIGN MANAGER: LK
SG CONSTR. MANAGER: JB
PROJECT NO: 210023
TEMPLATE VERSION: 12/21/2021

REVISIONS
REV. DATE DESCRIPTION

MECHANICAL
SPECIFICATIONS

M-011

SECTION 23 37 13 - GRILLES, REGISTERS & DIFFUSERS

PART 1 - GENERAL

- 1. SECTION REQUIREMENTS
A. SUBMITTALS: NONE REQUIRED.

PART 2 - PRODUCTS

- 1. GRILLES: MANUFACTURER, MODEL, MATERIAL, FINISH, MOUNTING AND ACCESSORIES SHALL BE AS NOTED IN THE MECHANICAL SCHEDULES. NO SUBSTITUTIONS SHALL BE PERMITTED.
2. REGISTERS: MANUFACTURER, MODEL, MATERIAL, FINISH, MOUNTING AND ACCESSORIES SHALL BE AS NOTED IN THE MECHANICAL SCHEDULES. NO SUBSTITUTIONS SHALL BE PERMITTED.
3. DIFFUSERS: MANUFACTURER, MODEL, MATERIAL, FINISH, MOUNTING AND ACCESSORIES SHALL BE AS NOTED IN THE MECHANICAL SCHEDULES. NO SUBSTITUTIONS SHALL BE PERMITTED.

PART 3 - EXECUTION

- 1. INSTALLATION
A. INSTALL GRILLES, REGISTERS & DIFFUSERS LEVEL AND PLUMB.
B. INSTALL GRILLES, REGISTERS & DIFFUSERS AS INDICATED. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN FOR EXACT LOCATION.
C. INSTALL GRILLES, REGISTERS & DIFFUSERS WITH AIRTIGHT CONNECTIONS TO DUCTS AND TO ALLOW SERVICE AND MAINTENANCE OF DAMPERS, EXTRACTORS AND OTHER ACCESSORIES.
D. AFTER INSTALLATION, ADJUST REGISTERS & DIFFUSERS TO AIR PATTERNS (IF NOTED) OR AS DIRECTED BY THE TENANT'S CONSTRUCTION MANAGER PRIOR TO STARTING AIR BALANCING.

(END OF SECTION 23 37 13)

SECTION 23 81 29 - VARIABLE REFRIGERANT FLOW SYSTEMS

PART 1 - GENERAL

- 1. SECTION REQUIREMENTS
A. SUBMITTALS: PROVIDE SHOP DRAWINGS INDICATING THE DIMENSIONS, WEIGHTS, REQUIRED CLEARANCES, COMPONENTS, EFFICIENCIES, CAPACITIES, ELECTRICAL CHARACTERISTICS AND LOCATION AND SIZE OF EACH FIELD CONNECTION FOR EACH INDOOR AND OUTDOOR UNIT.
B. WARRANTY: SUBMIT A WRITTEN WARRANTY, SIGNED BY THE MANUFACTURER AGREEING TO REPAIR OR REPLACE COMPONENTS OF THE SYSTEM FOR A PERIOD OF ONE YEAR. COMPRESSORS SHALL HAVE A WARRANTY OF SEVEN YEARS.

PART 2 - PRODUCTS

- 1. DESCRIPTION
A. A VARIABLE CAPACITY, HEAT PUMP HEAT RECOVERY AIR CONDITIONING SYSTEM CAPABLE OF SIMULTANEOUS HEATING AND COOLING.
B. SYSTEM SHALL CONSIST OF AN OUTDOOR UNIT, BRANCH CIRCUIT CONTROLLER, MULTIPLE INDOOR UNITS AND AN INTEGRAL DIRECT DIGITAL CONTROLS SYSTEM.
C. EACH INDOOR UNIT, OR GROUP THEREOF SHALL BE ABLE TO OPERATE IN EITHER COOLING OR HEATING MODE, INDEPENDENTLY OF OTHER UNITS/GROUPS AND SHALL BE CAPABLE OF CHANGING MODE WITH NO INTERRUPTION TO SYSTEM FUNCTION.
D. ENERGY COMPLIANCE: COMPLY WITH THE APPLICABLE REQUIREMENTS OF THE ENERGY CODE LISTED ON THE COVER SHEET.
E. ELECTRICAL COMPONENTS, DEVICES AND ACCESSORIES SHALL BE LABELED AND LISTED AS DEFINED IN NFPA 70 BY A QUALIFIED TESTING AGENCY.
2. MANUFACTURERS: AS NOTED IN THE MECHANICAL SCHEDULES. ALTERNATES BY DAIKIN OR PANASONIC. THIS CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL STRUCTURAL, ELECTRICAL AND OTHER REQUIREMENTS RESULTING FROM THE SUBSTITUTION. ALL CHANGE ORDERS RESULTING IN THE USE OF AN ALTERNATE SHALL BE PAID FOR BY THIS CONTRACTOR.
3. OUTDOOR UNIT CHARACTERISTICS:
A. AN AIR-COOLED, DIRECT EXPANSION MULTI-ZONE UNIT SPECIFICALLY FOR USE WITH VRF COMPONENTS.
B. UNITS SHALL BE EQUIPPED WITH A SINGLE, INVERTER-DRIVEN SCROLL TYPE, HERMETIC, MULTI-PORT COMPRESSOR. THE CAPACITY OF THE COMPRESSOR SHALL BE VARIABLE, WITH A MINIMUM TURNDOWN NOT GREATER THAN 15%.
C. UNIT SHALL BE FACTORY ASSEMBLED, PIPED AND WIRED AND RUN TESTED AT THE FACTORY.
D. OUTDOOR UNITS MAY BE COMPRISED OF MULTIPLE MODULES, CONNECTED VIA A TWINNING KIT INSTALLED IN THE FIELD.
E. ALL LINESETS TO THE INDOOR UNITS SHALL BE INSULATED IN ACCORDANCE WITH THE MANUFACTURERS INSTALLATION INSTRUCTIONS.
F. THE OUTDOOR UNIT SHALL HAVE AN ACCUMULATOR WITH REFRIGERANT LEVEL SENSORS AND CONTROLS. UNITS SHALL ACTIVELY CONTROL LIQUID LEVEL VIA LINEAR EXPANSION VALVES.
G. THE OUTDOOR UNIT SHALL HAVE A HIGH-EFFICIENCY OIL SEPARATOR.
H. UNIT SHALL DEFROST ALL CIRCUITS SIMULTANEOUSLY DURING LOW-AMBIENT TEMPERATURES (BELOW 23 DEGREES F.), WHILE IN HOT GAS DEFROST, THE SYSTEM SHALL SLOW THE INDOOR UNIT FAN SPEED TO MAINTAIN A HIGH DISCHARGE AIR TEMPERATURE.
I. THE OUTDOOR UNIT SHALL BE FURNISHED WITH A 20 GAUGE HOT DIPPED GALVANIZED SNOW/HAIL GUARD.
J. THE OUTDOOR UNIT SHALL BE FURNISHED WITH A FOUR-LEGGED OUTDOOR MOUNTING SYSTEM FROM THE MANUFACTURER.
K. UNIT CASING SHALL BE GALVANIZED STEEL, BONDERIZED AND FINISHED.
L. OUTDOOR UNIT FAN SHALL BE DIRECT DRIVE WITH A VARIABLE SPEED PROPELLER, FAN SHALL HAVE INHERENT PROTECTION WITH PERMANENTLY LUBRICATED BEARINGS. FANS SHALL BE PROVIDED WITH A RAISED GUARD TO PREVENT CONTACT WITH MOVING PARTS.
M. OUTDOOR COIL SHALL BE A 4-SIDED COIL, ELEVATED AT LEAST 12" FROM THE BASE OF THE UNIT. COIL SHALL BE CORRUGATED PLATE FINS ON COPPER TUBING WITH FACTORY-APPLIED CORROSION RESISTANT FINISH. UNCOATED ALUMINUM COIL/FINS ARE NOT ALLOWED.
N. UNIT SHALL HAVE PREWIRED PLUGS FOR OPTIONAL PANEL HEATERS.
O. UNIT POWER SHALL BE AS NOTED IN THE EQUIPMENT SCHEDULES.
P. CONTROL CIRCUITING BETWEEN THE INDOOR UNITS, BRANCH CIRCUIT CONTROLLER AND THE OUTDOOR UNIT SHALL BE 24V DC COMPLETED USING 2-CONDUCTOR, TWISTED PAIR SHIELDED CABLE.
4. REFRIGERANT AND REFRIGERANT PIPING
A. R410A REFRIGERANT SHALL BE REQUIRED FOR SYSTEMS.
B. POLYESTER (POE) OIL SHALL BE REQUIRED FOR SYSTEMS.
C. REFRIGERANT PIPING SHALL BE PHOSPHORUS DEOXYDIZED COPPER WITH A THICKNESS AS DEFINED BY THE MANUFACTURERS RECOMMENDATIONS.
D. ALL PIPING SHALL BE INSULATED WITH 1/2" CLOSED-CELL INSULATION WITH A FLAME-SPREAD INDEX OF LESS THAN 25, AND A SMOKE-DEVELOPMENT INDEX OF LESS THAN 50. R-VALUE SHALL BE 3.0 OR GREATER.
E. ALL REFRIGERANT PIPING CONNECTIONS SHALL BE BRAZED.
5. BRANCH CIRCUIT (BC) CONTROLLERS
A. BC CONTROLLERS SHALL INCLUDE MULTIPLE BRANCHES TO ALLOW SIMULTANEOUS HEATING AND COOLING.
B. BC CONTROLLERS SHALL BE EQUIPPED WITH A CIRCUIT BOARD THAT INTERFACES TO THE CONTROLS SYSTEM AND SHALL PERFORM ALL FUNCTIONS NECESSARY FOR OPERATION.
C. THE UNIT CASING SHALL BE FABRICATED OF GALVANIZED STEEL.
D. EACH CABINET SHALL HOUSE A LIQUID-GAS SEPARATOR AND MULTIPLE REFRIGERATION CONTROL VALVES AND TWO TUBE-IN-TUBE HEAT EXCHANGERS.
E. REFRIGERANT SERVICE SHUT OFF VALVES SHALL BE FIELD-PROVIDED FOR EACH BRANCH TO ALLOW SERVICE TO INDOOR UNITS WITHOUT OPERATION TO OVERALL SYSTEM.
F. BC CONTROLLERS SHALL HAVE INTEGRAL RESIN DRAIN PAN.
G. UNIT POWER SHALL BE AS NOTED IN THE EQUIPMENT SCHEDULES.
H. CONTROL CIRCUITING BETWEEN THE INDOOR UNITS, BRANCH CIRCUIT CONTROLLER AND THE OUTDOOR UNIT SHALL BE 24V DC COMPLETED USING 2-CONDUCTOR, TWISTED PAIR SHIELDED CABLE.
6. HIGH-STATIC, CEILING-CONCEALED, DUCTED INDOOR UNITS
A. FACTORY-ASSEMBLED, WIRED AND RUN TESTED, CONTAINING FACTORY WIRING, PIPING, ELECTRONIC MODULATING LINEAR EXPANSION DEVICE, CONTROL CIRCUIT BOARD AND MOTOR.
G. UNIT CABINET SHALL BE CEILING-CONCEALED, DUCTED WITH A FIXED REAR RETURN.
C. FAN SHALL BE DYNAMICALLY BALANCED, DIRECT DRIVEN BY A SINGLE MOTOR WITH PERMANENTLY LUBRICATED BEARINGS.
D. FILTER BOX SHALL BE FURNISHED WITH ALL UNITS.
E. COIL SHALL BE CONSTRUCTED OF SMOOTH PLATE FINS ON COPPER TUBING WITH INNER GROOVES.
F. UNIT POWER SHALL BE AS NOTED IN THE EQUIPMENT SCHEDULES.
G. CONTROL CIRCUITING BETWEEN THE INDOOR UNITS, BRANCH CIRCUIT CONTROLLER AND THE OUTDOOR UNIT SHALL BE 24V DC COMPLETED USING 2-CONDUCTOR, TWISTED PAIR SHIELDED CABLE.

PART 3 - EXECUTION

- 1. INSTALLATION
A. OUTDOOR UNITS: INSTALL OUTDOOR UNITS ON MANUFACTURERS FURNISHED STANDS.
B. INDOOR UNITS: INSTALL UNITS LEVEL FROM STRUCTURE, ON NEOPRENE TYPE VIBRATION ISOLATORS AS NOTED ON THE STRUCTURAL DRAWINGS.
2. CONNECTIONS
A. COMPLY WITH DUCT INSTALLATION REQUIREMENTS SPECIFIED IN OTHER HVAC SECTIONS. DRAWINGS INDICATE GENERAL ARRANGEMENTS OF DUCTS.
B. CONNECT SUPPLY AND RETURN AIR DUCTS WITH FLEXIBLE DUCT CONNECTORS AS NOTED IN SECTION 23 33 00.
C. INSTALL CONDENSATE DRAIN WITH TRAP AND INDIRECT CONNECTION AS NOTED ON THE PLANS AND PER THE MANUFACTURERS INSTALLATION INSTRUCTIONS.
D. CONNECT REFRIGERANT PIPING PER THE MANUFACTURERS INSTALLATION INSTRUCTIONS.
E. INSTALL PIPING AND DUCTWORK ADJACENT TO EQUIPMENT TO ALLOW SPACE FOR SERVICE AND MAINTENANCE.
F. CONNECT CONTROLS WIRING TO THE THERMOSTAT, TEMPERATURE SENSOR AND UNIT AS DESCRIBED IN THE MANUFACTURERS INSTALLATION INSTRUCTIONS.
G. CONNECT ELECTRICAL WIRING IN ACCORDANCE WITH THE ELECTRICAL SPECIFICATIONS.
3. FIELD QUALITY CONTROL
A. AFTER INSTALLING ALL EQUIPMENT, TEST UNITS FOR COMPLIANCE WITH REQUIREMENTS.
B. INSPECT AND REMOVE SHIPPING BOLTS, BLOCKS AND THE DOWN STRAPS.
C. CONFIRM PROPER MOTOR ROTATION AND UNIT OPERATIONS.
D. TEST AND ADJUST CONTROLS AND SAFETIES: REPLACE DAMAGED AND MALFUNCTIONING CONTROLS AND EQUIPMENT.
E. OPERATIONAL TEST: AFTER ELECTRICAL CIRCUITRY HAS BEEN ENERGIZED, START UNITS TO CONFIRM PROPER MOTOR ROTATION AND UNIT OPERATION.
F. CLEAN FILTER HOUSINGS AND CHANGE FILTERS PRIOR TO AIR BALANCE AND IMMEDIATELY PRIOR TO TURNOVER.

(END OF SECTION 23 81 29)

SECTION 23 90 00 - LOUVERS

PART 1 - GENERAL

- 1. SECTION INCLUDES
A. EXTRUDED ALUMINUM LOUVERS
2. PERFORMANCE REQUIREMENTS
A. UL CLASSIFIED FOR WIND RESISTANT BUILDING COMPONENTS IN ACCORDANCE WITH ASTM E330-02 FOR +- F5F WINDLOAD.
B. LOUVERS SHALL BEAR THE AMCA CERTIFIED RATINGS SEAL, LISTED FOR BASE PROTECTION.
3. SECTION REQUIREMENTS
A. SUBMITTALS: PROVIDE SHOP DRAWINGS INDICATING SIZE, FACE AREA, FREE AREA, AIRFLOW, PRESSURE DROP, MATERIAL, FINISH AND FURNISHED ACCESSORIES.
4. WARRANTY: SUBMIT A WRITTEN WARRANTY, SIGNED BY THE MANUFACTURER INDICATING THAT THE PRODUCT WILL BE FREE FROM DEFECTS IN MATERIAL AND WORKMANSHIP FOR A PERIOD OF 5-YEARS AS OF THE DATE OF DELIVERY TO THE DELIVERY LOCATION.

PART 2 - PRODUCTS

- 1. DESCRIPTION
A. LOUVERS SHALL BE STATIONARY DRAINABLE TYPE WITH DRAIN GUTTERS IN EACH BLADE AND DOWNSPOUTS IN JAMBS AND MULLIONS.
B. STATIONARY DRAINABLE BLADES SHALL BE CONTAINED WITHIN A FRAME.
C. LOUVER COMPONENTS (HEADS, JAMBS, SILLS, BLADES & MULLIONS) SHALL BE FACTORY ASSEMBLED BY THE MANUFACTURER.
D. LOUVER SIZES TOO LARGE FOR SHIPPING SHALL BE BUILT-UP BY THE CONTRACTOR FROM FACTORY-ASSEMBLED SECTIONS.
E. LOUVERS SHALL BE FURNISHED WITH A FLATTENED ALUMINUM BIRD SCREEN IN REMOVEABLE FRAME.
F. FINISH SHALL BE AS NOTED IN THE MATERIAL SCHEDULES.
2. MANUFACTURERS: AS NOTED IN THE MECHANICAL SCHEDULES. ALTERNATES BY GREENHECK AND NAILOR.

PART 3 - EXECUTION

- 1. INSTALLATION
A. INSPECT AREAS TO RECEIVE LOUVERS. NOTIFY THE ARCHITECT OF CONDITIONS THAT WOULD ADVERSELY AFFECT THE INSTALLATION OR UTILIZATION OF THE LOUVERS.
B. CLEAN OPENINGS THOROUGHLY PRIOR TO INSTALLATION AND PREPARE SURFACES USING THE METHODS RECOMMENDED BY THE MANUFACTURER.
C. INSTALL LOUVERS AT LOCATIONS INDICATED AND IN ACCORDANCE WITH THE STRUCTURAL DETAILS AND MANUFACTURERS INSTRUCTIONS.
D. INSTALL LOUVERS LEVEL, PLUMB, IN PLANE OF WALL AND IN ALIGNMENT WITH ANY ADJACENT WORK.
E. INSTALL JOINT SEALANTS AS REQUIRED.
2. FIELD QUALITY CONTROL
A. CLEAN LOUVER SURFACES IN ACCORDANCE WITH THE MANUFACTURERS INSTRUCTIONS.
B. TOUCH-UP, REPAIR OR REPLACE DAMAGED PRODUCTS.

(END OF SECTION 23 90 00)




sweetgreen

3101 W. EXPOSITION BLVD.
LOS ANGELES, CALIFORNIA 90018

THESE DRAWINGS & SPECIFICATIONS ARE CONFIDENTIAL AND SHALL REMAIN THE SOLE PROPERTY OF SWEETGREEN CORPORATION. THEY SHALL NOT BE REPRODUCED (IN WHOLE OR IN PART), SHARED WITH THIRD PARTIES OR USED IN ANY MANNER ON OTHER PROJECTS OR EXTENSIONS TO THIS PROJECT WITHOUT THE PRIOR WRITTEN CONSENT OF SWEETGREEN CORPORATION. THESE DRAWINGS & SPECIFICATIONS ARE INTENDED TO EXPRESS DESIGN INTENT FOR A PROTOTYPICAL SWEETGREEN STORE WHICH IS SUBJECT TO CHANGE AT ANY TIME AND MAY NOT REFLECT ACTUAL SITE CONDITIONS. NEITHER PARTY SHALL HAVE ANY OBLIGATION OR LIABILITY TO THE OTHER EXCEPT AS STATED ABOVE UNTIL A WRITTEN AGREEMENT IS FULLY EXECUTED.

ENGINEER OF RECORD:



EVERJ ENGINEERING, INC.
1509 BUCK TRAIL LANE
WORTHINGTON, OH 43085
240-319-0822
www.everjengineering.com

STAMP:

CONSTRUCTION
ISSUE SET

08/15/2022

PROJECT INFORMATION:
THE YARD AT FISHERS DISTRICT
PROJECT INFORMATION:
**9711 E. 116TH ST, SUITE 310
FISHERS, IN 46037**

DRAWN BY: JAE
CHECKED BY: MK
PROJECT MANAGER: JAE
SG DESIGN MANAGER: LK
SG CONSTR. MANAGER: JB
PROJECT NO: 210023
TEMPLATE VERSION: 12/21/2021

REVISIONS
REV. 1 DATE 08/15/2022 DESCRIPTION CLIENT CHANGES

HVAC PLAN


M-100

CODED NOTES

1. INSTALL THE EQUIPMENT PER MANUFACTURER'S INSTALLATION INSTRUCTION AND PER THE STRUCTURAL DETAILS.
2. COORDINATE MOUNTING LOCATION FOR WALK-IN COOLER CONDENSING UNIT, CU-1 ON TOP OF THE WALK-IN COOLER WITH THE KITCHEN EQUIPMENT SUPPLIER PRIOR TO ROUGH-IN. ENSURE ALL CLEARANCE REQUIREMENTS FOR THE UNIT ARE MAINTAINED THROUGH CONSTRUCTION. KITCHEN EQUIPMENT SUPPLIER SHALL PROVIDE LINESET, SPECIALTIES AND MAKE ALL FINAL CONNECTIONS BETWEEN THE CONDENSING UNIT AND EVAPORATOR COIL.
3. PROVIDE SUPPLY DIFFUSER CONNECTION PER DETAIL 1/SHEET M-400.
4. REFER TO THE ARCHITECTURAL RCP FOR CEILING MOUNTED EQUIPMENT LOCATION, TYPICAL.
5. PROVIDE AUDIO/VISUAL REMOTE SMOKE DETECTOR ANNUNCIATOR WITH REMOTE KEY OPERATED RESET. WIRE A UNIT BACK TO EACH SMOKE DETECTOR. MOUNT UNIT 80" AFF. TYPICAL.
6. INSTALL THE OWNER-FURNISHED MAIN CONTROLLER FOR THE HVAC EQUIPMENT NOTED AT THIS LOCATION AT 48" AFF. COORDINATE WITH ELECTRICAL SWITCHING IN THE AREA AND EXTEND CONTROLS WIRING AS NOTED IN THE TRANE SHOP DRAWINGS. COORDINATE CONTROLLER LOCATION WITH WALL-MOUNTED EQUIPMENT SO THAT THE THERMOSTATS ARE NOT BLOCKED BY SHELVING, COAT RACKS OR DOORS.
7. INSTALL THE TEMPERATURE SENSOR FOR THE HVAC EQUIPMENT NOTED AT THIS LOCATION AT 5'-0" AFF. COORDINATE LOCATION WITH EQUIPMENT AND WALL-MOUNTED FIXTURES AS REQUIRED SUCH THAT THE SENSOR IS NOT BLOCKED.
8. REFER TO DETAIL 3/SHEET M-400 FOR AIR HANDLER INSTALLATION DETAILS.
9. PROVIDE EXPOSED DUCTWORK AS SHOWN, PER THE SPECIFICATIONS AND PER DETAIL 2/SHEET M-400.
10. THE GENERAL CONTRACTOR SHALL FURNISH A REME HALO AIR PURIFICATION SYSTEM AND REQUIRED TRANSFORMER, PURCHASED THROUGH SWEETGREEN'S VENDOR (NATIONAL TAB) AND INSTALL SYSTEM IN THE SUPPLY AIR DUCTWORK AND PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. ADJUST AS REQUIRED FOR THE SUPPLY AIRFLOW.
11. THE GENERAL CONTRACTOR SHALL PROVIDE A DUCT-MOUNTED SMOKE DETECTOR IN THE RETURN AIR STREAM, UPON DETECTION OF SMOKE, THE SUPPLY AIR FAN SHALL DE-ENERGIZE. COORDINATE ALL REQUIREMENTS WITH THE LANDLORD AND ALARM PROVIDER.
12. MAINTAIN MANUFACTURER'S RECOMMENDED CLEARANCE ZONES. NO DUCTWORK, PIPING, CONDUIT OR OTHER SYSTEMS SHALL BE PERMITTED IN THIS AREA. COORDINATE WITH SITE CONDITIONS AND WORK OF OTHER TRADES AS REQUIRED. TYPICAL.
13. INSTALL THE OWNER-FURNISHED REFRIGERANT PIPING BETWEEN THE ROOF-MOUNTED CONDENSING UNIT AND THE BRANCH CONTROLLER. REFER TO SHEET M-101 AND SHEET M-401 FOR MORE INFORMATION. COORDINATE LINESET PATHWAY WITH THE LANDLORD AND SITE CONDITIONS AS REQUIRED. COORDINATE LINESET LENGTH AND QUANTITIES REQUIRED WITH THE OWNER'S NATIONAL ACCOUNT REPRESENTATIVE PRIOR TO EQUIPMENT SHIPPING.
14. APPROXIMATE LOCATION OF CHASE TO ROOF. PROVIDE SUPPORTS WITHIN THE CHASE AS REQUIRED FOR REFRIGERANT PIPING. PROVIDE SUPPORTS WITHIN THE CHASE PER SMACNA GUIDELINES FOR DUCTWORK. REFER TO SHEET M-101 FOR CONTINUATION.
15. INSTALL THE OWNER-FURNISHED REFRIGERANT PIPING BETWEEN THE BRANCH CONTROLLER AND THE AIR HANDLING UNITS. REFER TO SHEET M-401 FOR MORE INFORMATION. COORDINATE LINESET LENGTH AND QUANTITIES REQUIRED WITH THE OWNER'S NATIONAL ACCOUNT REPRESENTATIVE PRIOR TO EQUIPMENT SHIPPING.
16. INSTALL THE OWNER-FURNISHED FILTER BOX FOR THE AIR HANDLING UNIT PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
17. PROVIDE A DUCT HEATER IN THE SUPPLY-AIR STREAM IN LOCATION SHOWN. ENSURE THAT THERE IS A MINIMUM OF 4'-0" OF STRAIGHT DUCT AT THE INLET AND OUTLET OF THE HEATER. INSTALL PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
18. PROVIDE A RUSKIN CBD2 COUNTERBALANCED BACKDRAFT DAMPER IN THE SPACE PRESSURE RELIEF DUCTWORK AS SHOWN. DAMPER SHALL BE BALANCED TO PERMIT THE REQUIRED AIRFLOW TO EXIT DURING ECONOMIZER OPERATION AND SHALL BE FULLY CLOSED DURING MINIMUM OUTSIDE AIRFLOW CONDITIONS. INSTALL PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
19. INSTALL THE TYPE II HOOD, HD-2 IN LOCATION SHOWN. SUPPORT PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. INSTALL HOOD ACCORDING TO THE REQUIREMENTS OF ITS LISTING, THE BUILDING CODE, ALL NFPA REQUIREMENTS AND THE LOCAL AUTHORITY HAVING JURISDICTIONS REQUIREMENTS.
20. TRANSITION FROM ROUND DUCTWORK TO RECTANGULAR DUCTWORK AS REQUIRED TO INSTALL THE BACKDRAFT DAMPER. PROVIDE SUFFICIENT SPACE TO ALLOW FOR PROPER BLADE OPERATION.
21. TRANSFER GRILLE FOR PRESSURE RELIEF FROM THE KITCHEN. INSTALL WITH GRILLE BLADES TOWARDS THE WALL TO PREVENT LINE OF SIGHT INTO THE DUCTWORK.
22. PROVIDE A BELIMO ZIP ECONOMIZER FOR MECHANICAL EQUIPMENT. PROVIDE 24V FULLY-MODULATING DAMPERS, SENSORS AND WIRING AS REQUIRED FOR A FULLY FUNCTIONING ENTHALPY ECONOMIZER SYSTEM. INSTALL PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
23. INSTALL THE EQUIPMENT PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
24. DUCTWORK SHALL BE ROUTED OVER THE CLEARANCE ZONE FOR AHU-2.
25. NOT USED.

SYMBOLS & ABBREVIATIONS

HVAC SYMBOLS




- MITERED CORNER WITH TURNING VANES
- DUCTWORK INTERNAL FREE DIMENSIONS (WIDTHxHEIGHT)
- RECTANGULAR TO ROUND DUCT TRANSITION
- DUCT-MOUNTED SMOKE DETECTOR
- MOTOR-OPERATED DAMPER
- MANUAL VOLUME DAMPER
- GREASE DUCT CLEANOUT
- MITERED CORNER WITHOUT TURNING VANES
- CEILING DIFFUSER
- CEILING-MOUNTED RETURN OR EXHAUST REGISTER
- SUPPLY REGISTER
- RETURN REGISTER
- FLEXIBLE DUCT
- THERMOSTAT
- REMOTE TEMPERATURE SENSOR
- PLAN NOTE: SEE PLAN NOTES LISTED ON THE SAME SHEET FOR NOTE MEANING
- CONNECT TO EXISTING
- EQUIPMENT TAG: SEE EQUIPMENT SCHEDULE ON SHEET M-300 FOR EQUIPMENT INFORMATION
- AUDIO/VISUAL REMOTE SMOKE DETECTOR ANNUNCIATOR WITH REMOTE KEY OPERATED RESET
- TAG
- NECK SIZE
- AIRFLOW [CFM]


HVAC ABBREVIATIONS

- (E) EXISTING
- (R) RELOCATED
- AFF ABOVE FINISHED FLOOR
- AFG ABOVE FINISHED GRADE
- AHU AIR HANDLING UNIT
- BC BLOWER COIL
- CD CEILING DIFFUSER
- CU CONDENSING UNIT
- EF EXHAUST FAN
- ER EXHAUST REGISTER
- EXTG EXISTING
- GC GENERAL CONTRACTOR
- HES TENANT'S HVAC EQUIPMENT SUPPLIER
- KES TENANT'S KITCHEN EQUIPMENT SUPPLIER
- OBD BLADE DAMPER
- PL PLENUM
- RG RETURN GRILLE
- RTU ROOFTOP UNIT
- SD SLOT DIFFUSER
- SR SUPPLY REGISTER
- VSC VARIABLE SPEED CONTROL
- WSHP WATER SOURCE HEAT PUMP

REVISED EXHAUST AND SPACE PRESSURE RELIEF DUCTWORK THROUGHOUT



HVAC PLAN
1/4" = 1'-0"
NORTH



1 HVAC ROOF PLAN
1/4" = 1'-0"
NORTH

CODED NOTES

- 1 INSTALL EQUIPMENT MOUNTED ON OWNER-FURNISHED STANDS PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- 2 INSTALL THE OWNER-FURNISHED TWINNING KIT PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- 3 INSTALL THE OWNER-FURNISHED REFRIGERANT PIPING BETWEEN THE ROOF-MOUNTED CONDENSING UNIT AND THE BRANCH CONTROLLER. REFER TO SHEET M-100 AND SHEET M-401 FOR MORE INFORMATION. COORDINATE LINESET PATHWAY WITH THE LANDLORD AND EXISTING CONDITIONS AS REQUIRED. COORDINATE LINESET LENGTH AND QUANTITIES REQUIRED WITH THE OWNER'S NATIONAL ACCOUNT REPRESENTATIVE PRIOR TO EQUIPMENT SHIPPING.
- 4 APPROXIMATE LOCATION OF CHASE TO ROOF. PROVIDE SUPPORTS WITHIN THE CHASE AS REQUIRED FOR REFRIGERANT PIPING. PROVIDE SUPPORTS WITHIN THE CHASE PER SMACNA GUIDELINES FOR DUCTWORK. REFER TO SHEET M-101 FOR CONTINUATION.
- 5 EXISTING MECHANICAL EQUIPMENT ON THE ROOF TO REMAIN. TYPICAL.
- 6 NOT USED.
- 7 LOCATION OF EXISTING FRESH-AIR INTAKE. NO EXHAUST SYSTEM SHALL BE INSTALLED WITHIN 10'-0" OF THIS POINT.
- 8 NOT USED.
- 9 NOT USED.

SYMBOLS & ABBREVIATIONS

HVAC SYMBOLS		HVAC ABBREVIATIONS	
	MITERED CORNER WITH TURNING VANES	(E)	EXISTING
	DUCTWORK INTERNAL FREE DIMENSIONS (WIDTHxHEIGHT)	(R)	RELOCATED
	RECTANGULAR TO ROUND DUCT TRANSITION	AFF	ABOVE FINISHED FLOOR
	DUCT-MOUNTED SMOKE DETECTOR	AFG	ABOVE FINISHED GRADE
	MOTOR-OPERATED DAMPER	AHU	AIR HANDLING UNIT
	MANUAL VOLUME DAMPER	BC	BLOWER COIL
	GREASE DUCT CLEANOUT	CD	CEILING DIFFUSER
	MITERED CORNER WITHOUT TURNING VANES	CU	CONDENSING UNIT
	CEILING DIFFUSER	EF	EXHAUST FAN
	CEILING-MOUNTED RETURN OR EXHAUST REGISTER	ER	EXHAUST REGISTER
	SUPPLY REGISTER	EXTG	EXISTING
	RETURN REGISTER	GC	GENERAL CONTRACTOR
	FLEXIBLE DUCT	HES	TENANT'S HVAC EQUIPMENT SUPPLIER
	THERMOSTAT	KES	TENANT'S KITCHEN EQUIPMENT SUPPLIER
	REMOTE TEMPERATURE SENSOR	OBD	BLADE DAMPER
	PLAN NOTE: SEE PLAN NOTES LISTED ON THE SAME SHEET FOR NOTE MEANING	PL	PLENUM
	CONNECT TO EXISTING	RG	RETURN GRILLE
	EQUIPMENT TAG: SEE EQUIPMENT SCHEDULE ON SHEET M-300 FOR EQUIPMENT INFORMATION	RTU	ROOFTOP UNIT
	AUDIO/VISUAL REMOTE SMOKE DETECTOR ANNUNCIATOR WITH REMOTE KEY OPERATED RESET	SD	SLOT DIFFUSER
	TAG	SR	SUPPLY REGISTER
	NECK SIZE	VSC	VARIABLE SPEED CONTROL
	AIRFLOW (CFM)	WSHP	WATER SOURCE HEAT PUMP



sweetgreen

3101 W. EXPOSITION BLVD.
LOS ANGELES, CALIFORNIA 90018

THESE DRAWINGS & SPECIFICATIONS ARE CONFIDENTIAL AND SHALL REMAIN THE SOLE PROPERTY OF SWEETGREEN CORPORATION. THEY SHALL NOT BE REPRODUCED (IN WHOLE OR IN PART), SHARED WITH THIRD PARTIES OR USED IN ANY MANNER ON OTHER PROJECTS OR EXTENSIONS TO THIS PROJECT WITHOUT THE PRIOR WRITTEN CONSENT OF SWEETGREEN CORPORATION. THESE DRAWINGS & SPECIFICATIONS ARE INTENDED TO EXPRESS DESIGN INTENT FOR A PROTOTYPICAL SWEETGREEN STORE WHICH IS SUBJECT TO CHANGE AT ANY TIME AND MAY NOT REFLECT ACTUAL SITE CONDITIONS. NEITHER PARTY SHALL HAVE ANY OBLIGATION OR LIABILITY TO THE OTHER EXCEPT AS STATED ABOVE UNTIL A WRITTEN AGREEMENT IS FULLY EXECUTED.

ENGINEER OF RECORD:



EVERJ ENGINEERING, INC.
1509 BUCK TRAIL LANE
WORTHINGTON, OH 43085
240-319-0822
www.everjengineering.com

STAMP:

**CONSTRUCTION
ISSUE SET**

08/15/2022

PROJECT INFORMATION:
**THE YARD AT FISHERS
DISTRICT**
PROJECT INFORMATION:
**9711 E. 116TH ST, SUITE 310
FISHERS, IN 46037**

DRAWN BY: JAE
CHECKED BY: MK
PROJECT MANAGER: JAE
SG DESIGN MANAGER: LK
SG CONSTR. MANAGER: JB
PROJECT NO: 210023
TEMPLATE VERSION: 12/21/2021

REVISIONS
REV. DATE DESCRIPTION
1 08/15/2022 CLIENT CHANGES

HVAC ROOF PLAN

M-101




sweetgreen

3101 W. EXPOSITION BLVD.
LOS ANGELES, CALIFORNIA 90018

THESE DRAWINGS & SPECIFICATIONS ARE CONFIDENTIAL AND SHALL REMAIN THE SOLE PROPERTY OF SWEETGREEN CORPORATION. THEY SHALL NOT BE REPRODUCED (IN WHOLE OR IN PART), SHARED WITH THIRD PARTIES OR USED IN ANY MANNER ON OTHER PROJECTS OR EXTENSIONS TO THIS PROJECT WITHOUT THE PRIOR WRITTEN CONSENT OF SWEETGREEN CORPORATION. THESE DRAWINGS & SPECIFICATIONS ARE INTENDED TO EXPRESS DESIGN INTENT FOR A PROTOTYPICAL SWEETGREEN STORE WHICH IS SUBJECT TO CHANGE AT ANY TIME AND MAY NOT REFLECT ACTUAL SITE CONDITIONS. NEITHER PARTY SHALL HAVE ANY OBLIGATION OR LIABILITY TO THE OTHER EXCEPT AS STATED ABOVE UNTIL A WRITTEN AGREEMENT IS FULLY EXECUTED.

ENGINEER OF RECORD:



EVERJ ENGINEERING, INC.
1509 BUCK TRAIL LANE
WORTHINGTON, OH 43085
240-319-0822
www.everjengineering.com

STAMP:

CONSTRUCTION
ISSUE SET

08/15/2022

PROJECT INFORMATION:
THE YARD AT FISHERS DISTRICT
PROJECT INFORMATION:
**9711 E. 116TH ST, SUITE 310
FISHERS, IN 46037**

DRAWN BY: JAE
CHECKED BY: MK
PROJECT MANAGER: JAE
SG DESIGN MANAGER: LK
SG CONSTR. MANAGER: JB
PROJECT NO: 210023
TEMPLATE VERSION: 12/21/2021

REVISIONS
REV. DATE DESCRIPTION

HVAC PIPING PLAN

M-200

CODED NOTES

- 1 PROVIDE CONDENSATE DRAIN FROM THE MECHANICAL EQUIPMENT AS SHOWN, PER DETAIL 3/SHEET M-400 AND PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. PROVIDE INDIRECT DRAIN PER DETAIL 5/SHEET P-400. ALL DRAIN PIPING SHALL BE CONCEALED ABOVE CEILINGS AND WITHIN FRAMED WALLS UNLESS OTHERWISE NOTED.
- 2 REFER TO SANITARY WASTE AND VENT PLAN FOR WALK-IN COOLER CONDENSATE DRAIN ROUTING.
- 3 MECHANICAL EQUIPMENT UNIT SHALL BE FURNISHED WITH A CONDENSATE PUMP. INSTALL PUMP PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. CONTRACTOR SHALL PROVIDE PIPING UP TO A HEIGHT SUFFICIENT ENOUGH TO DRAIN THE CONDENSATE VIA GRAVITY AND PROVIDE PIPING TO THE INDIRECT WASTE RECEPTOR PER THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. TERMINATE PER DETAIL 5/SHEET P-400. ALL DRAIN PIPING SHALL BE CONCEALED ABOVE CEILINGS AND WITHIN FRAMED WALLS UNLESS OTHERWISE NOTED. COORDINATE WITH FIELD CONDITIONS AS REQUIRED.
- 4 PROVIDE CLEANOUTS IN CONDENSATE PIPING AS SHOWN AND AS REQUIRED TO CLEAR BLOCKAGES IN THE CONDENSATE DRAIN SYSTEM. TYPICAL FOR EACH UNIT.


SYMBOLS & ABBREVIATIONS

HVAC PIPING SYMBOLS

- ELBOW UP
- ELBOW DOWN
- CWS— CONDENSER WATER SUPPLY
- CWR— CONDENSER WATER RETURN
- CHWS— CHILLED WATER SUPPLY
- CHWR— CHILLED WATER RETURN
- HWS— HOT WATER SUPPLY
- HWR— HOT WATER RETURN
- - - CD - - - CONDENSATE DRAIN
- (X) PLAN NOTE: SEE KEYNOTES LISTED ON THE SAME SHEET FOR NOTE MEANING
- CONNECT TO EXISTING
- ⊘ REDUCED PRESSURE ZONE BACKFLOW PREVENTER
- ⊘-# EQUIPMENT TAG: SEE EQUIPMENT SCHEDULE ON SHEET M-300 FOR EQUIPMENT INFORMATION
- ⊘ VALVE
- ⊘ SOLENOID-OPERATED VALVE
- ⊘ CHECK VALVE
- ⊘ CIRCUIT-SETTER BALANCE VALVE RATED FOR POTABLE WATER
- (BTU) BTU METER

HVAC PIPING ABBREVIATIONS

- AFF ABOVE FINISHED FLOOR
- AFG ABOVE FINISHED GRADE
- AHU AIR HANDLING UNIT
- BC BLOWER COIL
- CD CONDENSATE DRAIN
- CHWR CHILLED WATER RETURN
- CHWS CHILLED WATER SUPPLY
- CWR CONDENSER WATER RETURN
- CWS CONDENSER WATER SUPPLY
- EXTG EXISTING
- GC GENERAL CONTRACTOR
- HES TENANT'S HVAC EQUIPMENT SUPPLIER
- HWR HOT WATER RETURN
- HWS HOT WATER SUPPLY
- KES TENANT'S KITCHEN EQUIPMENT SUPPLIER
- RTU ROOFTOP UNIT
- WSHP WATER SOURCE HEAT PUMP



1 HVAC PIPING PLAN
1/4" = 1'-0"
NORTH

REMOVED FIRE DAMPER SCHEDULE




sweetgreen

3101 W. EXPOSITION BLVD.
LOS ANGELES, CALIFORNIA 90018

THESE DRAWINGS & SPECIFICATIONS ARE CONFIDENTIAL AND SHALL REMAIN THE SOLE PROPERTY OF SWEETGREEN CORPORATION. THEY SHALL NOT BE REPRODUCED OR USED IN ANY MANNER ON OTHER PROJECTS OR EXTENSIONS TO THIS PROJECT WITHOUT THE PRIOR WRITTEN CONSENT OF SWEETGREEN CORPORATION. THESE DRAWINGS & SPECIFICATIONS ARE INTENDED TO EXPRESS DESIGN INTENT FOR A PROTOTYPICAL SWEETGREEN STORE WHICH IS SUBJECT TO CHANGE AT ANY TIME AND MAY NOT REFLECT ACTUAL SITE CONDITIONS. NEITHER PARTY SHALL HAVE ANY OBLIGATION OR LIABILITY TO THE OTHER EXCEPT AS STATED ABOVE UNTIL A WRITTEN AGREEMENT IS FULLY EXECUTED.

ENGINEER OF RECORD:



EVERJ ENGINEERING, INC.
1509 BUCK TRAIL LANE
WORTHINGTON, OH 43085
240-319-0822
www.everjengineering.com

STAMP:

CONSTRUCTION
ISSUE SET

08/15/2022

PROJECT INFORMATION:
THE YARD AT FISHERS DISTRICT
PROJECT INFORMATION:
9711 E. 116TH ST., SUITE 310 FISHERS, IN 46037

DRAWN BY: JAE
CHECKED BY: MK
PROJECT MANAGER: JAE
SG DESIGN MANAGER: LK
SG CONSTR. MANAGER: JB
PROJECT NO: 210023
TEMPLATE VERSION: 12/21/2021

REVISIONS
REV. 1 DATE 08/15/2022 DESCRIPTION CLIENT CHANGES

HVAC SCHEDULES

M-300

LOUVER SCHEDULE

TAG	DESCRIPTION	SIZE			AIRFLOW		MATERIAL	FINISH	SUPPLIER	INSTALLER	MANUFACTURER	MODEL	SPECIAL REMARKS
		FACE SIZE (W" x H")	FACE AREA (SF)	FREE AREA (SF)	TOTAL AIRFLOW (CFM)	PRESSURE DROP (IN W.C.)							
LV-1	VENTILATION AIR LOUVER	49"x24"	8.17	4.03	2500	0.06	ALUMINUM	TO MATCH EXISTING	GC	GC	RUSKIN	ELF6375DX	FURNISHED WITH BIRD SCREEN AND MOUNTING SYSTEM COMPATIBLE WITH THE BUILDING CONSTRUCTION.
LV-2	VENTILATION AIR LOUVER	49"x24"	8.17	4.03	2950	0.09	ALUMINUM	TO MATCH EXISTING	GC	GC	RUSKIN	ELF6375DX	FURNISHED WITH BIRD SCREEN AND MOUNTING SYSTEM COMPATIBLE WITH THE BUILDING CONSTRUCTION.
LV-3	EXHAUST LOUVER	78"x60"	32.50	19.24	1190	0.01	ALUMINUM	TO MATCH EXISTING	GC	GC	RUSKIN	ELF6375DX	FURNISHED WITH BIRD SCREEN AND MOUNTING SYSTEM COMPATIBLE WITH THE BUILDING CONSTRUCTION.
LV-4	SPACE PRESSURE RELIEF LOUVER	47"x44"	14.36	8.13	4260	0.04	ALUMINUM	TO MATCH EXISTING	GC	GC	RUSKIN	ELF6375DX	FURNISHED WITH BIRD SCREEN AND MOUNTING SYSTEM COMPATIBLE WITH THE BUILDING CONSTRUCTION.

GRILLS, REGISTERS, AND DIFFUSERS SCHEDULE

TAG	DESCRIPTION	FACE SIZE	MATERIAL	FINISH	MOUNTING	SUPPLIER	INSTALLER	MANUFACTURER	MODEL	REMARKS
CD1	PERFORATED CEILING DIFFUSER	24" x 24"	ALUMINUM	WHITE	LAY-IN	GC	GC	TITUS	PCS-AA	PROVIDE INTEGRAL OBD
CD2	PERFORATED CEILING DIFFUSER	24" x 24"	ALUMINUM	WHITE	GYPSUM BOARD	GC	GC	TITUS	PCS-AA	PROVIDE INTEGRAL OBD
CD4	PERFORATED CEILING DIFFUSER	12" x 12"	ALUMINUM	WHITE	GYPSUM BOARD	GC	GC	TITUS	PCS-AA	PROVIDE INTEGRAL OBD
ER1	0° FIXED BLADE EXHAUST GRILL	8" x 8"	ALUMINUM	WHITE	GYPSUM BOARD	GC	GC	TITUS	355ZFL	PROVIDE INTEGRAL OBD
ER2	PERFORATED CEILING EXHAUST	24" x 24"	ALUMINUM	WHITE	LAY-IN	GC	GC	TITUS	PAR-AA	PROVIDE INTEGRAL OBD
RG1	PERFORATED CEILING RETURN	24" x 24"	ALUMINUM	WHITE	LAY-IN	GC	GC	TITUS	PAR-AA	
RG2	PERFORATED CEILING RETURN	48" x 24"	ALUMINUM	WHITE	LAY-IN	GC	GC	TITUS	PAR-AA	
RG3	3/4" SPACING, 35° DEGREE DEFLECTION RETURN GRILLE	26"x26"	STEEL	WHITE	GYPSUM BOARD	GC	GC	TITUS	350RL	PROVIDE INTEGRAL OBD
SR1	DOUBLE DIRECTIONAL SUPPLY REGISTER	16" x 8"	STEEL	WHITE	SURFACE	GC	GC	TITUS	300RL	PROVIDE INTEGRAL OBD
SR2	DOUBLE DIRECTIONAL SUPPLY REGISTER	8" x 8"	ALUMINUM	WHITE	SURFACE	GC	GC	TITUS	300FL	PROVIDE INTEGRAL OBD
TG1	3/4" SPACING, 35° DEGREE DEFLECTION TRANSFER GRILLE	38"x26"	STEEL	WHITE	GYPSUM BOARD	GC	GC	TITUS	350RL	PROVIDE INTEGRAL OBD

BRANCH CONTROLLER SCHEDULE

TAG	DESCRIPTION	NUMBER OF PORTS	MCOCP (A)	MCA (A)	V/PH	SUPPLIER	INSTALLER	MANUFACTURER	MODEL	REMARKS
BC-1	VRF BRANCH CONTROLLER	8	15	1.0	208/1/60	OWNER	GC	TRANE	TCMBM0108JA114N4	

RECIRCULATING HOOD SCHEDULE

TAG	DESCRIPTION	MAX COOKING TEMP.	EXHAUST PLENUM AIRFLOW [CFM]	APPROXIMATE WEIGHT [lbs]	SUPPLIER	INSTALLER	ELECTRICAL DATA		MANUFACTURER	MODEL	REMARKS
							WATTS	V/PH			
HD-1	VENTLESS CANOPY RECIRCULATING HOOD	N/A	415	175	OWNER	OWNER	170 W	120/1/60	RATIONAL	60.76.177	UL 710B APPROVED APPLIANCE INSTALLED IN ACCORDANCE WITH ITS LISTING.

FAN SCHEDULE

TAG	EXHAUST AIRFLOW (CFM)	E.S.P. (IN. W.C.)	DRIVE TYPE	MOTOR POWER (HP)	WEIGHT (LB)	V/PH	SUPPLIER	INSTALLER	MANUFACTURER	MODEL	REMARKS
EF-1	990	1.0	DIRECT	0.50	175	120/1/60	GC	GC	CAPTIVE-AIRE	SIF13DD-HE	WITH VIBRATION ISOLATORS. MOTORIZED BACKDRAFT DAMPER AND SPEED CONTROLLER.
EF-2	200	0.8	DIRECT	1.00	175	120/1/60	GC	GC	CAPTIVE-AIRE	SIF11DD	WITH VIBRATION ISOLATORS. MOTORIZED BACKDRAFT DAMPER AND SPEED CONTROLLER.

AIR DOOR SCHEDULE

TAG	DESCRIPTION	OPENING WIDTH	MAX VELOCITY (FPM)	AIRFLOW (CFM)	MCOCP (A)	FLA (A)	V/PH	SUPPLIER	INSTALLER	MANUFACTURER	MODEL	REMARKS
AD-1	AIR DOOR	36"	3600	2118	1036	20	3.4	120/1/60	GC	GC	BERNER	MAX1036A FURNISHED WITH DOOR-ACTIVATED SWITCH

TYPE II HOOD SCHEDULE

TAG	DESCRIPTION	WIDTH	DEPTH	MATERIAL	MAXIMUM COOKING TEMPERATURE (DEG. F)	AIRFLOW (CFM)	DIAMETER (IN)	PRESSURE DROP (IN. W.G.)	WEIGHT (LB)	SUPPLIER	INSTALLER	MANUFACTURER	MODEL	REMARKS
HD-2	TYPE II CANOPY HOOD	58"	60"	430 STAINLESS STEEL	700	990	12"	0.09	200	GC	GC	CAPTIVEAIRE	6012 VHB	

DUCT HEATER SCHEDULE

TAG	DESCRIPTION	AIRFLOW (CFM)	NUMBER OF STEPS	HEATING OUTPUT (BTU/H)	EAT (DEG. F)	LAT (DEG. F)	ELECTRICAL KW	V/PH	SUPPLIER	INSTALLER	BASIS OF DESIGN		REMARKS
											MANUFACTURER	MODEL	
DH-1	AHU-3 DUCT HEATER	2500	1	54624	72.6	92.5	16.0	208/3/60	GC	GC	INDEECO	QUA	PROVIDE WITH DISCONNECT SWITCH, THERMAL CUTOUTS, AIRFLOW PROVING SWITCH, CONTACTORS, CONTROL TRANSFORMER AND FUSES AS REQUIRED.

CONDENSING UNIT SCHEDULE

TAG	DESCRIPTION	PAIRED WITH	NOMINAL CAPACITY (TONS)	NUMBER OF COMPRESSORS	REFRIGERANT TYPE	WEIGHT (LBS)	ELECTRICAL				V/PH	SUPPLIER	INSTALLER	MANUFACTURER	MODEL	REMARKS
							MCOCP, CKT 1 (A)	MCA, CKT 1 (A)	MCOCP, CKT 2 (A)	MCA, CKT 2 (A)						
CU-1	WALK-IN COOLER REMOTE CONDENSING UNIT	N/A	0	1	R448A	260	25	16.3			208/1/60	KES	KES	BY KES	BY KES	FURNISHED WITH THE WALK-IN COOLER.
CU-2	VRF SYSTEM CONDENSING UNIT	AHU-1 THRU AHU-3	20	2	R410A	1,600	70	47.0	70	47.0	208/3/60	OWNER	GC	TRANE	TURYH2403BN40AN	FURNISHED WITH TWINNING KIT, PANEL HEATER, SNOW/HAIL GUARDS, SNOW HOOD AND 24" TALL STANDS.

AIR BALANCE SCHEDULE

TAG	SUPPLY AIRFLOW (CFM)	RETURN AIRFLOW (CFM)	OUTSIDE AIRFLOW (CFM)	EXHAUST AIRFLOW (CFM)	SUBTOTAL (CFM)
AHU-1	2950	2750	200	0	200
AHU-2	1050	1050	0	0	0
AHU-3	2500	1710	790	0	790
EF-1	0	0	0	990	-990
EF-2	0	0	0	200	-200
Net Pressurization (CFM)					-200

EXHAUST SCHEDULE

PER TABLE 403.3 OF THE 2014 IN MECHANICAL CODE

CATEGORY	AREA (SF)	NUMBER OF FIXTURES	AIR RATE		EXHAUST REQUIRED (CFM)		VENTILATION REQUIRED (CFM)	VENTILATION PROVIDED (CFM)
			CFM / FIXTURE	CFM / SF	FIXTURES	FLOOR AREA		
KITCHEN	1154.0	0	0.00	-0.70	0.0	-807.8	-807.8	-1040.0
RESTROOMS	102.3	2	-50.00	0.00	-100.0	0.0	-100.0	-150.0
TOTAL						-907.8	-907.8	-1190.0

VENTILATION SCHEDULE

PER TABLE 403.3 OF THE 2014 IN MECHANICAL CODE

CATEGORY	OCCUPANT DENSITY (# / 1000 SF)	AREA (SF)	OCCUPANCY BY AREA (PEOPLE)	AIR RATE (CFM)		VENTILATION REQUIRED (CFM)		EFFECTIVENESS	VENTILATION REQUIRED (CFM)	VENTILATION PROVIDED (CFM)
				CFM / PERSON	CFM / SF	OCCUPANCY	FLOOR AREA			
CORRIDOR	0	127.4	0	0.00	0.06	0.0	7.6	0.8	9.6	10.0
DINING ROOM	70	883.5	62	7.50	0.18	465.0	159.0	0.8	780.0	780.0
OFFICE	5	35.8	1	5.00	0.06	5.0	2.1	0.8	8.9	10.2
STORAGE AREAS	0	150.0	0	0.00	0.12	0.0	18.0	0.8	22.5	189.8
TOTAL									821.0	990.0

TRANE NATIONAL ACCOUNT - HVAC SYSTEM INFORMATION

CONTACT THE TRANE NATIONAL ACCOUNT TEAM FOR HVAC SYSTEM INFORMATION AT:
EMAIL - SOCIALNA@TRANE.COM
PHONE - (714)983-0505 OPTION 4 (NATIONAL ACCOUNTS TEAM)
OR ANY OF THE BELOW SOUTHERN CALIFORNIA NATIONAL ACCOUNTS TEAM MEMBERS:
DEREK VAN RIPPER (714)227-9366 MARIA G. GARCIA (714)983-0464 JEFF SWANSON (626)945-6049
DEREK.VANRIPPER@TRANE.COM MGGARCIA@TRANE.COM JSWANSON@TRANE.COM

SWEETGREEN SHALL FURNISH THE MECHANICAL SYSTEM AND ASSOCIATED ACCESSORIES THROUGH THEIR NATIONAL ACCOUNTS REPRESENTATIVES NOTED ABOVE. THE GENERAL CONTRACTOR SHALL INSTALL THE SYSTEM AND ACCESSORIES AS NOTED IN THESE DRAWINGS AND AS REQUIRED FOR A COMPLETE AND FUNCTIONING SYSTEM. COORDINATE WITH SWEETGREEN AND THE REPRESENTATIVES AS REQUIRED AND NOTED ON THE PLANS.

ANY CHANGES OR VARIATION TO THE EQUIPMENT PACKAGE THAT WOULD AFFECT THE HVAC EQUIPMENT PACKAGE SHOULD BE BROUGHT TO THE ATTENTION OF THE TRANE NATIONAL ACCOUNT TEAM AND THE ARCHITECT/ENGINEER OF RECORD AT THE TIME OF QUOTATION.

MATERIAL SCHEDULE


CATEGORY	APPLICATION	ALLOWABLE MATERIAL
DUCT	EXPOSED, SUPPLY	DOUBLE-WALL INSULATED ROUND AS SHOWN. PAINTED TO MATCH ROOF DECK.
	EXPOSED, RETURN	ROUND AS SHOWN. PAINTED TO MATCH ROOF DECK.
	EXPOSED, GEN. EXHAUST & PRESSURE RELIEF	DOUBLE-WALL INSULATED ROUND OR RECTANGULAR AS SHOWN. PAINTED TO MATCH ROOF DECK.
	EXPOSED, VENTILATION AIR	DOUBLE-WALL INSULATED ROUND AS SHOWN. PAINTED TO MATCH ROOF DECK.
	CONCEALED, SUPPLY	RECTANGULAR OR ROUND AS SHOWN. INSULATED.
	CONCEALED, RETURN	RECTANGULAR OR ROUND AS SHOWN. INSULATED.
CONCEALED, GEN. EXHAUST	RECTANGULAR OR ROUND AS SHOWN. INSULATED.	
	RECTANGULAR OR ROUND AS SHOWN. INSULATED.	
	RECTANGULAR OR ROUND AS SHOWN. INSULATED.	
CONCEALED, VENTILATION AIR	RECTANGULAR OR ROUND AS SHOWN. INSULATED.	
	RECTANGULAR OR ROUND AS SHOWN. INSULATED.	
PIPING	CONDENSATE DRAINS	SCHEDULE 40 PVC PIPE AND FITTINGS.

AIR HANDLING UNIT SCHEDULE

TAG	DESCRIPTION	COOLING CAPACITY (TONS)	EER	AIRFLOW			COOLING				HEATING				ELECTRICAL				REMARKS				
				TOTAL (CFM)	RETURN (CFM)	OA (CFM)	E.S.P. (IN. W.C.)	NET TOTAL (MBH)	NET SENSIBLE (MBH)	EAT (DEG. F)		EAT (DEG. F)	TOTAL (MBH)	LAT (DEG. F)	WEIGHT (LB)	MCOCP (A)	MCA (A)	V/PH	SUPPLIER	INSTALLER	MANUFACTURER	MODEL	
							DB	WB															
AHU-1	KITCHEN AIR HANDLING UNIT	3	0	2950	2750	200	0.8	94.2	60.0	73.5	64.8	66.3	84.5	92.5	300	15	8.2	208/1/60	OWNER	GC	TRANE	TPEFYP096MH140A	FURNISHED WITH FILTER BOX, FLUSH-MOUNT REMOTE SENSOR, JOINT PIPE AND MAXIBLUE CONDENSATE PUMP.
AHU-2	KITCHEN AIR HANDLING UNIT	3	0	1050	1050	0	0.8	35.3	23.1	73.5	64.8	66.3	31.3	87.8	225	15	4.2	208/1/60	OWNER	GC	TRANE	TPEFYP036MH142A	FURNISHED WITH FILTER BOX, FLUSH-MOUNT REMOTE SENSOR AND JOINT PIPE.
AHU-3	DINING ROOM AIR HANDLING UNIT	8	0	2500	1710	790	0.8	100.8	64.9	78.8	68.3	46.4	87.8	72.6	300	15	8.2	208/1/60	OWNER	GC	TRANE	TPEFYP096MH140A	FURNISHED WITH FILTER BOX, FLUSH-MOUNT REMOTE SENSOR, JOINT PIPE, MAXIBLUE CONDENSATE PUMP AND EXTERNAL HEATER ADAPTOR.

THESE DRAWINGS & SPECIFICATIONS ARE CONFIDENTIAL AND SHALL REMAIN THE SOLE PROPERTY OF SWEETGREEN CORPORATION. THEY SHALL NOT BE REPRODUCED IN WHOLE OR IN PART, SHARED WITH THIRD PARTIES OR USED IN ANY MANNER ON OTHER PROJECTS OR EXTENSIONS TO THIS PROJECT WITHOUT THE PRIOR WRITTEN CONSENT OF SWEETGREEN CORPORATION. THESE DRAWINGS & SPECIFICATIONS ARE INTENDED TO EXPRESS DESIGN INTENT FOR A PROTOTYPICAL SWEETGREEN STORE WHICH IS SUBJECT TO CHANGE AT ANY TIME AND MAY NOT REFLECT ACTUAL SITE CONDITIONS. NEITHER PARTY SHALL HAVE ANY OBLIGATION OR LIABILITY TO THE OTHER EXCEPT AS STATED ABOVE UNTIL A WRITTEN AGREEMENT IS FULLY EXECUTED.

ENGINEER OF RECORD:



EVERJ ENGINEERING, INC.
1509 BUCK TRAIL LANE
WORTHINGTON, OH 43085
240-319-0822
www.everjengineering.com

STAMP:

CONSTRUCTION
ISSUE SET

08/15/2022


PROJECT INFORMATION:
THE YARD AT FISHERS DISTRICT
PROJECT INFORMATION:
9711 E. 116TH ST, SUITE 310 FISHERS, IN 46037

DRAWN BY: JAE
CHECKED BY: MK
PROJECT MANAGER: JAE
SG DESIGN MANAGER: LK
SG CONSTR. MANAGER: JB
PROJECT NO: 210023
TEMPLATE VERSION: 12/21/2021


REVISIONS	REV.	DATE	DESCRIPTION

HVAC DETAILS


M-400




9 HVAC SECTION
N.T.S.




8 KITCHEN HVAC SECTION
N.T.S.




7 ROOF-MOUNTED DUCTWORK DETAIL
N.T.S.




6 FIRE DAMPER DETAIL
N.T.S.




5 DUCT HEATER INSTALLATION DETAIL
N.T.S.




4 LOUVER INSTALLATION DETAIL
N.T.S.



3 AIR HANDLING UNIT INSTALLATION DETAIL
N.T.S.



2 EXPOSED DUCTWORK SUPPORT
N.T.S.



1 DIFFUSER CONNECTION
N.T.S.




sweetgreen

3101 W. EXPOSITION BLVD.
LOS ANGELES, CALIFORNIA 90018

THESE DRAWINGS & SPECIFICATIONS ARE CONFIDENTIAL AND SHALL REMAIN THE SOLE PROPERTY OF SWEETGREEN CORPORATION. THEY SHALL NOT BE REPRODUCED OR USED IN ANY MANNER ON OTHER PROJECTS OR EXTENSIONS TO THIS PROJECT WITHOUT THE PRIOR WRITTEN CONSENT OF SWEETGREEN CORPORATION. THESE DRAWINGS & SPECIFICATIONS ARE INTENDED TO EXPRESS DESIGN INTENT FOR A PROTOTYPICAL SWEETGREEN STORE WHICH IS SUBJECT TO CHANGE AT ANY TIME AND MAY NOT REFLECT ACTUAL SITE CONDITIONS. NEITHER PARTY SHALL HAVE ANY OBLIGATION OR LIABILITY TO THE OTHER EXCEPT AS STATED ABOVE UNTIL A WRITTEN AGREEMENT IS FULLY EXECUTED.

ENGINEER OF RECORD:



EVERJ ENGINEERING, INC.
1509 BUCK TRAIL LANE
WORTHINGTON, OH 43085
240-319-0822
www.everjengineering.com

STAMP:

CONSTRUCTION
ISSUE SET

08/15/2022


PROJECT INFORMATION:
THE YARD AT FISHERS DISTRICT
PROJECT INFORMATION:
**9711 E. 116TH ST., SUITE 310
FISHERS, IN 46037**

DRAWN BY: JAE
CHECKED BY: MK
PROJECT MANAGER: JAE
SG DESIGN MANAGER: LK
SG CONSTR. MANAGER: JB
PROJECT NO: 210023
TEMPLATE VERSION: 12/21/2021

REVISIONS
REV. DATE DESCRIPTION
1 08/15/2022 CLIENT CHANGES

VRF DIAGRAMS &
SEQUENCE OF
OPERATIONS

M-401



This drawing is schematic in nature. Final routing of piping & wiring shall be determined by the installing contractor and/or designer of record. Additional refrigerant charge is needed depending on the size and length of extended piping. Please refer the amount of pre-charge and the formula of calculation which is mentioned on the data book.

1.25mm(1/8 AWG) : 1.25mm(1/8 AWG) or more. 0.75mm(20 AWG) : between 0.5mm(24 AWG) and 0.75mm(20 AWG).

Code Notes:
NOTE 1: Install hwinning 'Y's within 15 degrees of level and with 20 inches of straight pipe on converging connection - reference installation manual for additional details including but not limited to special trapping requirements when wiring, and pipe slope requirements

SEQUENCE OF OPERATIONS VRF GENERAL

GENERAL:
THE VRF SYSTEM SHALL BE A HEAT PUMP, HEAT RECOVERY SYSTEM CAPABLE OF SIMULTANEOUS HEATING AND COOLING. THE CONDENSING UNIT SHALL MODULATE CAPACITY AS REQUIRED TO SATISFY THE AIR HANDLING UNIT DEMAND. THE BRANCH CIRCUIT CONTROLLER SHALL PROVIDE CONTROL TO THE SYSTEM AS REQUIRED.

SEQUENCE OF OPERATIONS EF-1 & EF-2

OCCUPIED MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: WHEN SCHEDULED BY THE TIME CLOCK TO BE IN OCCUPIED MODE, THE FANS ARE TO START AND RUN CONTINUOUSLY.

UNOCCUPIED MODE:
FAN OPERATION: WHEN SCHEDULED BY THE TIME CLOCK TO BE IN UNOCCUPIED MODE, THE FANS SHALL REMAIN OFF.

EMERGENCY MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: UPON A SIGNAL FROM THE FIRE ALARM SYSTEM, THE FANS SHALL STOP.

SEQUENCE OF OPERATIONS AHU-1

OCCUPIED MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: WHEN SCHEDULED BY THE TIME CLOCK TO BE IN OCCUPIED MODE, THE AIR HANDLER FANS ARE TO START AND RUN CONTINUOUSLY AND THE OUTSIDE AIR DAMPER SHALL MODULATE TO THE MINIMUM POSITION.

HEATING: ON A FALL IN SPACE TEMPERATURE BELOW THE SETPOINT OF 70 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT SHALL BE SWITCHED TO HEATING MODE AND THE HEATING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

COOLING: ON A RISE IN SPACE TEMPERATURE ABOVE THE SETPOINT OF 72 DEGREES (ADJUSTABLE), WHEN THE ENTHALPY OF THE OUTSIDE AIR IS FAVORABLE, THE OUTSIDE AIR DAMPER SHALL MODULATE OPEN UP TO 100% AND THE RETURN AIR DAMPER SHALL MODULATE CLOSED AS REQUIRED TO MAINTAIN THE SUPPLY AIRFLOW. IF THE ENTHALPY OF THE OUTSIDE AIR IS NOT FAVORABLE, OR UPON A SUDDEN RISE IN SPACE TEMPERATURE THE DAMPERS SHALL RETURN TO THEIR OCCUPIED SET POSITIONS. THE AIR HANDLING UNIT SHALL BE SWITCHED TO COOLING MODE AND THE COOLING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

UNOCCUPIED MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: WHEN SCHEDULED BY THE TIME CLOCK TO BE IN UNOCCUPIED MODE, THE AIR HANDLER FANS ARE TO BE OFF AND THE OUTSIDE AIR DAMPER SHALL REMAIN CLOSED.

HEATING: ON A FALL IN SPACE TEMPERATURE BELOW THE SETPOINT OF 65 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT FAN SHALL START, THE UNIT SHALL BE SWITCHED TO HEATING MODE AND THE HEATING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

COOLING: ON A RISE IN SPACE TEMPERATURE ABOVE THE SETPOINT OF 85 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT FAN SHALL START. WHEN THE ENTHALPY OF THE OUTSIDE AIR IS FAVORABLE, THE OUTSIDE AIR DAMPER SHALL MODULATE OPEN UP TO 100 AND THE RETURN AIR DAMPER SHALL MODULATE CLOSED AS REQUIRED TO MAINTAIN THE SUPPLY AIRFLOW. IF THE ENTHALPY OF THE OUTSIDE AIR IS NOT FAVORABLE, OR UPON A SUDDEN RISE IN SPACE TEMPERATURE THE DAMPERS SHALL RETURN TO THEIR UNOCCUPIED SET POSITIONS. THE AIR HANDLING UNIT SHALL BE SWITCHED TO COOLING MODE AND THE COOLING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

EMERGENCY MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: UPON A SIGNAL FROM THE FIRE ALARM SYSTEM, THE FAN SHALL STOP AND THE OUTSIDE AIR DAMPER SHALL CLOSE.

SEQUENCE OF OPERATIONS AHU-2

OCCUPIED MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: WHEN SCHEDULED BY THE TIME CLOCK TO BE IN OCCUPIED MODE, THE AIR HANDLER FANS ARE TO START AND RUN CONTINUOUSLY.

HEATING: ON A FALL IN SPACE TEMPERATURE BELOW THE SETPOINT OF 70 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT SHALL BE SWITCHED TO HEATING MODE AND THE HEATING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

COOLING: ON A RISE IN SPACE TEMPERATURE ABOVE THE SETPOINT OF 72 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT SHALL BE SWITCHED TO COOLING MODE AND THE COOLING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

UNOCCUPIED MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: WHEN SCHEDULED BY THE TIME CLOCK TO BE IN UNOCCUPIED MODE, THE AIR HANDLER FANS ARE TO BE OFF AND THE OUTSIDE AIR DAMPER SHALL REMAIN CLOSED.

HEATING: ON A FALL IN SPACE TEMPERATURE BELOW THE SETPOINT OF 65 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT FAN SHALL START AND THE UNIT SHALL BE SWITCHED TO HEATING MODE AND THE HEATING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

COOLING: ON A RISE IN SPACE TEMPERATURE ABOVE THE SETPOINT OF 85 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT FAN SHALL START AND THE UNIT SHALL BE SWITCHED TO COOLING MODE AND THE COOLING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

EMERGENCY MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: UPON A SIGNAL FROM THE FIRE ALARM SYSTEM, THE FAN SHALL STOP.

SEQUENCE OF OPERATIONS AHU-3

OCCUPIED MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: WHEN SCHEDULED BY THE TIME CLOCK TO BE IN OCCUPIED MODE, THE AIR HANDLER FANS ARE TO START AND RUN CONTINUOUSLY AND THE OUTSIDE AIR DAMPER SHALL MODULATE TO THE MINIMUM POSITION.

HEATING: ON A FALL IN SPACE TEMPERATURE BELOW THE SETPOINT OF 70 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT SHALL BE SWITCHED TO HEATING MODE AND THE HEATING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

COOLING: ON A RISE IN SPACE TEMPERATURE ABOVE THE SETPOINT OF 72 DEGREES (ADJUSTABLE), WHEN THE ENTHALPY OF THE OUTSIDE AIR IS FAVORABLE, THE OUTSIDE AIR DAMPER SHALL MODULATE OPEN UP TO 100% AND THE RETURN AIR DAMPER SHALL MODULATE CLOSED AS REQUIRED TO MAINTAIN THE SUPPLY AIRFLOW. IF THE ENTHALPY OF THE OUTSIDE AIR IS NOT FAVORABLE, OR UPON A SUDDEN RISE IN SPACE TEMPERATURE THE DAMPERS SHALL RETURN TO THEIR OCCUPIED SET POSITIONS. THE AIR HANDLING UNIT SHALL BE SWITCHED TO COOLING MODE AND THE COOLING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

UNOCCUPIED MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: WHEN SCHEDULED BY THE TIME CLOCK TO BE IN UNOCCUPIED MODE, THE AIR HANDLER FANS ARE TO BE OFF AND THE OUTSIDE AIR DAMPER SHALL REMAIN CLOSED.

HEATING: ON A FALL IN SPACE TEMPERATURE BELOW THE SETPOINT OF 65 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT FAN SHALL START, THE UNIT SHALL BE SWITCHED TO HEATING MODE AND THE HEATING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.


COOLING: ON A RISE IN SPACE TEMPERATURE ABOVE THE SETPOINT OF 85 DEGREES (ADJUSTABLE) THE AIR HANDLING UNIT FAN SHALL START. WHEN THE ENTHALPY OF THE OUTSIDE AIR IS FAVORABLE, THE OUTSIDE AIR DAMPER SHALL MODULATE OPEN UP TO 100 AND THE RETURN AIR DAMPER SHALL MODULATE CLOSED AS REQUIRED TO MAINTAIN THE SUPPLY AIRFLOW. IF THE ENTHALPY OF THE OUTSIDE AIR IS NOT FAVORABLE, OR UPON A SUDDEN RISE IN SPACE TEMPERATURE THE DAMPERS SHALL RETURN TO THEIR UNOCCUPIED SET POSITIONS. THE AIR HANDLING UNIT SHALL BE SWITCHED TO COOLING MODE AND THE COOLING CAPACITY SHALL MODULATE UP TO MAXIMUM TO MAINTAIN THE TEMPERATURE SETPOINT.

EMERGENCY MODE:
FAN OPERATION/OUTSIDE AIR DAMPER: UPON A SIGNAL FROM THE FIRE ALARM SYSTEM, THE FAN SHALL STOP AND THE OUTSIDE AIR DAMPER SHALL CLOSE.

SEQUENCE OF OPERATIONS N.T.S.


DIAGRAM SYMBOL	DESCRIPTION	CONT.No	PAGE
---	POWER WIRE		
---	CONTROL WIRE		
---	REF. PIPE		

PIPING AND CONTROLS	SYMBOL	BRANCH PIPE MODEL NAME
J1	CMV-R200NCBK	
J2	CMV-R300CS-G1	
J3	CMV-R160-J1	
SYMBOL LIQUID PIPE GAS PIPE SIZE		
P1	3/4	
P2	1-1/8	
P3	3/8	7/8
P4	3/8	1/2
P5	1/8	1-3/8



Diamond System Builder
sw: 4.3.2.35
db: 4.3.2.31
2/4/2022
3:46 PM

CITY MULTI SYSTEM SCHEMATIC DWG.



NOTE: DIAGRAM IS FOR REFERENCE ONLY. REFER TO THE TRANE SHOP DRAWING AND REVIEWED SUBMITTAL FOR MORE INFORMATION.

VRF WIRING/PIPING DIAGRAMS N.T.S.