

CERTIFICATE OF COMPLIANCE
Project Name: Chipotle - Morro Rd. Report Page: (Page 1 of 9)
Project Address: Date Prepared: 2023-02-21T11:00:09-05:00

A. GENERAL INFORMATION
Table with 4 columns: 01-04. Rows include Project Location (Atascadero), Climate Zone (4), Occupancy Types (Retail), and High-Rise Residential (Retail).

B. PROJECT SCOPE
Table with 3 columns: 01-03. Rows include Heating Air System, Cooling Air System, Mechanical Controls, and Mechanical Controls (existing to remain, altered or new).

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469

CERTIFICATE OF COMPLIANCE
Project Name: Chipotle - Morro Rd. Report Page: (Page 4 of 9)
Project Address: Date Prepared: 2023-02-21T11:00:09-05:00

F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)
Table with 9 columns: 01-09. Rows include RTU-1 and RTU-2 with equipment category, type, and performance metrics.

G. PUMPS
This section does not apply to this project.

H. FAN SYSTEMS & AIR ECONOMIZERS
This table is used to demonstrate compliance with prescriptive requirements found in §140.4(c), §140.4(e) and §140.4(m) for fan systems.

Table with 8 columns: System Name, RTU's, Economizer, Differential Enthalpy, Economizer Controls, Design per §140.4(e) and (m), System Fan Type, Constant Volume. Rows include RTU-1 and RTU-2.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469

CERTIFICATE OF COMPLIANCE
Project Name: Chipotle - Morro Rd. Report Page: (Page 2 of 9)
Project Address: Date Prepared: 2023-02-21T11:00:09-05:00

C. COMPLIANCE RESULTS
Table with 9 columns: 01-09. Rows include System Summary, Fans/Economizers, System Controls, Ventilation, Terminal Box Controls, Distribution, and Cooling Towers.

D. EXCEPTIONAL CONDITIONS
This table is auto-filled with uneditable comments because of selections made or data entered in tables throughout the form.

E. ADDITIONAL REMARKS
This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469

CERTIFICATE OF COMPLIANCE
Project Name: Chipotle - Morro Rd. Report Page: (Page 5 of 9)
Project Address: Date Prepared: 2023-02-21T11:00:09-05:00

H. FAN SYSTEMS & AIR ECONOMIZERS
FOOTNOTES: Computer room economizers must meet requirements of §140.9(a) and will be documented on the NRC-PRC-E document.

I. SYSTEM CONTROLS
Table with 9 columns: 01-09. Rows include System Name, System Zoning, Conditioned Floor Area, Thermostats, Shut-Off Controls, Isolation Zone Controls, Demand Response, Supply Air Temp, and Window Interlocks.

J. VENTILATION AND INDOOR AIR QUALITY
This table is used to demonstrate compliance with mandatory ventilation requirements in §120.1 and §120.2(c)3B for all nonresidential, high-rise residential and hotel/motel occupancies.

Table with 3 columns: 01-03. Rows include RTU-1 and RTU-2 with checkboxes for ventilation requirements.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469

CERTIFICATE OF COMPLIANCE
Project Name: Chipotle - Morro Rd. Report Page: (Page 3 of 9)
Project Address: Date Prepared: 2023-02-21T11:00:09-05:00

F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)
Table with 11 columns: 01-11. Rows include RTU-1 and RTU-2 with equipment category, type, and performance metrics.

FOOTNOTES: Equipment shall be the smallest size, within the available options of the desired equipment line, necessary to meet the design heating and cooling loads of the building per §140.4(a). Healthcare facilities are exempt.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469

CERTIFICATE OF COMPLIANCE
Project Name: Chipotle - Morro Rd. Report Page: (Page 6 of 9)
Project Address: Date Prepared: 2023-02-21T11:00:09-05:00

K. TERMINAL BOX CONTROLS
This section does not apply to this project.

L. DISTRIBUTION (DUCTWORK and PIPING)
This table is used to show compliance with mandatory pipe insulation requirements found in §120.3 and prescriptive requirements found in §140.4(i) for duct leakage testing.

Table with 3 columns: Question, Yes, No. Rows include duct leakage testing for M100, duct system providing conditioned air, and duct system serving less than 5,000 ft² of conditioned floor area.

M. COOLING TOWERS
This section does not apply to this project.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469

Consultant:



1425 WAKARUSA DR. STE B
LAWRENCE, KS 66049
PH: 785.993.0300
AEGROUP@BAE.GROUP



COPYRIGHT 2023
THIS DRAWING IS AN INSTRUMENT OF SERVICE AND AS SUCH REMAINS THE PROPERTY OF CHIPOTLE MEXICAN GRILL, INC. PERMISSION FOR USE OF THIS DOCUMENT IS LIMITED AND CAN BE EXTENDED ONLY BY WRITTEN AGREEMENT WITH CHIPOTLE MEXICAN GRILL, INC.



CHIPOTLE MEXICAN GRILL, INC.
PO BOX 182566
COLUMBUS, OH 43218-2566
TELEPHONE: (614) 318-2400
INTERNET: WWW.CHIPOTLE.COM

STORE NO.: 4642
MORRO RD & HWY 101 - ATASCADERO
6435 Morro Rd.
Atascadero, CA 93422

Issue Record:
02/28/2023 PERMIT ISSUE

Revisions table with columns for revision number, description, and date.

Drawn: Checked:
JJD AJD

Project No:
221125

Contents:

MECHANICAL TITLE
24 COMPLIANCE

M020

CERTIFICATE OF COMPLIANCE NRCC-PLB-E
This document is used to demonstrate compliance for nonresidential occupancies with requirements in §110.1, §110.3, §120.3, and §140.5, and with requirements in §141.0 for additions and alterations, for domestic water heating scopes using the prescriptive path. For high-rise residential and hotel/motel occupancies compliance is demonstrated with requirements in §110.1, §110.3, §120.3, §150.2, and §150.1(c)(8), and with requirements §150.2 for additions.
Project Name: Chipotle - Morro Rd Report Page: (Page 1 of 4)
Project Address: Date Prepared: 2023-02-21T11:10:22-05:00

A. GENERAL INFORMATION
01 Project Location (city) Atascadero 02 Climate Zone 4
03 Occupancy Types Within Project (select all that apply):
 Nonresidential High-Rise Residential Hotel/Motel
 State Building Healthcare Facility Other (Write In)

B. PROJECT SCOPE
This table includes domestic water heating systems that are within the scope of the permit application and are demonstrating compliance using the prescriptive paths outlined in §140.5, §150.1(c)(8), and §141.0(a), or §141.0(b)(2) for additions or alterations. Solar water heating systems are documented on the NRCC-SRA compliance document. Combined hydronic water heating systems are documented on the NRCC-MCH compliance document.
01 My project consists of (check all that apply):
 New system (DHW system being installed for the first time in newly constructed building) System Alteration (equipment, distribution or controls)
02 System Type^{1,2} Central System (serving nonresidential spaces)
03 System Components
 Equipment Distribution Controls
 Equipment Distribution Controls

¹FOOTNOTES: Point of use water heaters, or other non-central systems used to serve nonresidential spaces, are considered individual systems.
² Dwelling units refers to hotel/motel guest rooms and units in a high-rise residential occupancy.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469
Schema Version: rev 20200601 Report Generated: 2023-02-21 08:10:24

CERTIFICATE OF COMPLIANCE NRCC-PLB-E
Project Name: Chipotle - Morro Rd Report Page: (Page 4 of 6)
Project Address: Date Prepared: 2023-02-21T11:10:22-05:00

G. DOMESTIC HOT WATER DISTRIBUTION SYSTEM
This table is used to demonstrate compliance for nonresidential occupancies with distribution requirements in §120.3 and §140.5. For high-rise residential and hotel/motel occupancies, compliance is demonstrated with requirements §110.3(c), §120.3, §150.0, §150.1
Recirculation Loops in Central Systems Serving Dwelling Units or Nonresidential Spaces

	Yes	No	Not Applicable	Requirement
01	<input type="radio"/>	<input type="radio"/>	<input checked="" type="radio"/>	Air release valve or vertical pump installation per §110.3(c)(4A)
02	<input checked="" type="radio"/>	<input type="radio"/>	<input type="radio"/>	Check valve or similar located between recirculation pump and water heating equipment to prevent backflow per §110.3(c)(4B)
03	<input checked="" type="radio"/>	<input type="radio"/>	<input type="radio"/>	Hose bibb installed between pump and equipment and isolation valve between hose bibb and equipment per §110.3(c)(4C)
04	<input checked="" type="radio"/>	<input type="radio"/>	<input type="radio"/>	Isolation valves on both sides of the pump per §110.3(c)(4D)
05	<input type="radio"/>	<input type="radio"/>	<input checked="" type="radio"/>	Cold water and recirculation loop piping shall not be connected to the hot water storage tank drain port per §110.3(c)(4E)
06	<input checked="" type="radio"/>	<input type="radio"/>	<input type="radio"/>	Check valve installed on cold water supply between hot water system and next closest tee on cold water supply per §110.3(c)(4F)
07	<input type="radio"/>	<input type="radio"/>	<input checked="" type="radio"/>	For central systems serving multiple dwelling units, design includes two or more recirculation loops serving separate dwelling units per §150.1(c)(8)(ii) unless building has <=8 dwelling units.

Mandatory Pipe Insulation All Occupancies
For systems serving nonresidential spaces, pipe insulation for the following applications is specified to comply with Table 120.3-A (see below) per §120.3:
• Recirculating system piping, including supply and return piping of the water heater
• The first 8 ft of hot and cold outlet piping, including between storage tank and heat trap, for a nonrecirculating storage system
• Pipes that are externally heated
Insulation shall be protected from damage, including that due to sunlight, moisture, equipment maintenance, and wind. Insulation exposed to weather shall be installed with a cover suitable for outdoor service per §120.3(b) and §150.0(l)(3)

TABLE 120.3-A PIPE INSULATION THICKNESS

Fluid Temperature Range (°F)	Conductivity Range (Btu-in per hour per ft² per °F)	Insulation Mean Rating Temp (°F)	Nominal Pipe Diameter (in)		
			< 1	1 to < 1.5	1.5 to < 4
105-140	0.22 - 0.28	100	Minimum Insulation Required		
			1.0 in or R-7.7	1.5 in or R-12.5	1.5 in or R-11

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469
Schema Version: rev 20200601 Report Generated: 2023-02-21 08:10:24

CERTIFICATE OF COMPLIANCE NRCC-PLB-E
Project Name: Chipotle - Morro Rd Report Page: (Page 2 of 6)
Project Address: Date Prepared: 2023-02-21T11:10:22-05:00

C. COMPLIANCE RESULTS
Table C will indicate if the project data input into the compliance document is compliant with water heating requirements. If this table says "DOES NOT COMPLY" or "COMPLIES with Exceptional Conditions" refer to Table D. or the table indicated as not compliant for guidance.
01 Domestic Hot Water Equipment 02 Distribution Systems 03 Controls 04 Compliance Results
Table F Table G Table H
Yes Yes Yes COMPLIES

D. EXCEPTIONAL CONDITIONS
This table is auto-filled with unedited comments because of selections made or data entered in tables throughout the form.

E. ADDITIONAL REMARKS
This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469
Schema Version: rev 20200601 Report Generated: 2023-02-21 08:10:24

CERTIFICATE OF COMPLIANCE NRCC-PLB-E
Project Name: Chipotle - Morro Rd Report Page: (Page 5 of 6)
Project Address: Date Prepared: 2023-02-21T11:10:22-05:00

H. DOMESTIC HOT WATER CONTROLS
This table is used to demonstrate compliance with control requirements in §110.3 for all occupancies. For high-rise residential and hotel/motel occupancies, compliance is also demonstrated with requirements in §150.1(c)(8).

	Yes	No	Not Applicable	Requirement
01	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Construction documents require manufacturer certification that service water-heating systems are equipped with automatic temperature controls capable of adjusting temperature settings per §110.3(a)
02	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Systems with capacity >167,000 BTUH equipped with outlet temperature controls per §110.3(c)(1) unless covered by California Plumbing Code 613.0.
03	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Controls for circulating pumps or electrical heat trace systems are capable of automatically turning off the system per §110.3(c)(2) unless systems serves healthcare facility.
04	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	For recirculation systems serving multiple dwelling units, design includes automatic pump controls per §150.1(c)(8)(ii), or §150.2 for additions or alterations.
05	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	For recirculation systems serving individual dwelling units, design includes manual on/off controls as specified in Reference Appendix RAA.4.9 per §150.1(c)(8).
06	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	For replacement single heat pump water heaters serving individual dwelling units in climate zone 1-15, design includes communication interface that meets demand responsive control requirements of §110.12(a) per §150.2(b)(1)(iii).

I. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION
Selections have been made based on information provided in this document. If any selection have been changed by permit applicant, an explanation should be included in Table E.
Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/Nonresidential_Documents/NRCC/

Form/Title
NRCC-PLB-01-E - Must be submitted for all buildings

J. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE
There are no Certificates of Acceptance applicable to service water heating requirements.

K. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION
There are no NRCV forms required for this project.

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469
Schema Version: rev 20200601 Report Generated: 2023-02-21 08:10:24

CERTIFICATE OF COMPLIANCE NRCC-PLB-E
Project Name: Chipotle - Morro Rd Report Page: (Page 3 of 6)
Project Address: Date Prepared: 2023-02-21T11:10:22-05:00

F. DOMESTIC HOT WATER EQUIPMENT
This table is used to demonstrate compliance with mandatory equipment requirements in §110.1 and §110.3. For high-rise residential and hotel/motel occupancies, compliance with prescriptive requirements in §150.1(c)(8) must also be demonstrated and with §150.2 for addition and alteration scopes.
Equipment Schedule: Central Systems
07 Name or Item Tag 08 Equipment Type 09 Volume (gal) 10 Rated Input Capacity (Btu/h) 11 Rated Efficiency (%) 12 Minimum Efficiency Required (%) 13 Efficiency Unit 14 Designed Standby Loss¹ 15 Maximum Standby Loss¹
DWH-1/2 Gas Instantaneous Water Heater 0.5 0.96 0.8 Et

¹FOOTNOTE: For gas water heaters/boilers, standby loss is in BTUH. For electric storage water heaters, standby loss is in %/hr.

Water Heating Equipment All Occupancies
18 19 20
Requirement
Unfired storage tank insulation shall have Internal + External >=R-16 OR External >=R-12. Label required per §110.3(c)(3)
New state buildings 60% of energy for service water heating from site solar energy or recovered energy per §110.3(c)(5)
Isolation valves for instantaneous water heater with input rating >6.8 kBtu/h or 2 kW has been specified per §110.3(c)(6)

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469
Schema Version: rev 20200601 Report Generated: 2023-02-21 08:10:24

CERTIFICATE OF COMPLIANCE NRCC-PLB-E
Project Name: Chipotle - Morro Rd Report Page: (Page 6 of 6)
Project Address: Date Prepared: 2023-02-21T11:10:22-05:00

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT

I certify that this Certificate of Compliance documentation is accurate and complete.
Documentation Author Name: Isaac Dunn
Company: BAE Group
Address: 1425 Wakarusa Dr.
City/State/Zip: Lawrence/KS/66049
Phone: 785-993-0300
Signature Date: 21FEB23
CEA/ HERS Certification Identification (if applicable):
Phone: 785-993-0300

RESPONSIBLE PERSON'S DECLARATION STATEMENT
I certify the following under penalty of perjury under the laws of the State of California:
1. The information provided on this Certificate of Compliance is true and correct.
2. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer).
3. The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.
4. The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application.
5. I will ensure that a completed signed copy of this Certificate of Compliance shall be made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable inspections. I understand that a completed signed copy of this Certificate of Compliance is required to be included with the documentation the builder provides to the building owner at occupancy.
Responsible Designer Name: Laura Blanchard, PE
Company: BAE Group
Address: 1425 Wakarusa Dr.
City/State/Zip: Lawrence/KS/66049
Date Signed: 21FEB23
License: M34017
Phone: 785-993-0300

Registration Number: Generated Date/Time: Documentation Software: Energy Code Ace
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Compliance ID: 90469
Schema Version: rev 20200601 Report Generated: 2023-02-21 08:10:24

Consultant:



1425 WAKARUSA DR. STE B
LAWRENCE, KS 66049
PH: 785.993.0300
AEGROUP@BAE.GROUP



COPYRIGHT 2023
THIS DRAWING IS AN INSTRUMENT OF SERVICE AND AS SUCH REMAINS THE PROPERTY OF CHIPOTLE MEXICAN GRILL, INC. PERMISSION FOR USE OF THIS DOCUMENT IS LIMITED AND CAN BE EXTENDED ONLY BY WRITTEN AGREEMENT WITH CHIPOTLE MEXICAN GRILL, INC.



CHIPOTLE MEXICAN GRILL, INC.
PO BOX 182566
COLUMBUS, OH 43218-2566
TELEPHONE: (614) 318-2400
INTERNET: WWW.CHIPOTLE.COM

STORE NO.: 4642
MORRO RD & HWY 101 - ATASCADERO
6435 Morro Rd.
Atascadero, CA 93422

Issue Record:
02/28/2023 PERMIT ISSUE

Revisions:

Drawn: JJD Checked: AJD

Project No.: 221125

Contents:

MECHANICAL TITLE
24 COMPLIANCE


M022

HVAC PLAN NOTES


- SEE ARCHITECTURAL REFLECTED CEILING PLAN FOR CEILING MOUNTED EQUIPMENT LOCATION. TYPICAL.
- PAINT DUCTWORK VISIBLE THROUGH DINING ROOM SUPPLY REGISTERS BLACK. TYPICAL.
- PENETRATIONS THROUGH SHEAR WALL SHALL BE LIMITED TO 10" DIAMETER (OR A GROUP OF PENETRATIONS ALL CONTAINED WITHIN 10" DIAMETER). IF LARGER PENETRATIONS OR GROUPS OF PENETRATIONS ARE REQUIRED COORDINATE WITH STRUCTURAL ENGINEER FOR APPROPRIATE BRACING. SEE STRUCTURAL DRAWINGS FOR SHEAR WALL LOCATION.
- 16/16 DUCT UP FOR TRANSITION TO RTU-1 RETURN CONNECTION IN ROOF CURB. RTU-1 SHALL HAVE AN INTEGRAL SMOKE DETECTOR MOUNTED IN THE RETURN AIR STREAM. INTERLOCK SMOKE DETECTOR TO RTU-1 OPERATION.
- 16/16 DUCT UP FOR TRANSITION TO RTU-2 RETURN CONNECTION IN ROOF CURB. RTU-2 SHALL HAVE AN INTEGRAL SMOKE DETECTOR MOUNTED IN THE RETURN AIR STREAM. INTERLOCK SMOKE DETECTOR TO RTU-2 OPERATION.
- 20/16 DUCT UP FROM BUILDING SUPPLY THROUGH ROOF. TRANSITION TO RTU-1 SUPPLY CONNECTION IN ROOF CURB.
- 26/18 DUCT UP FROM BUILDING SUPPLY TO RTU-2 SUPPLY CONNECTION. TRANSITION IN ROOF CURB.
- 14/14 DUCT UP THROUGH ROOF. TRANSITION TO MAU-1 SUPPLY CONNECTION IN ROOF CURB.
- 24/10 DUCT UP FROM HOOD THROUGH ROOF TO EF-1 COMPLIANT WITH NFPA 96. PROVIDE RADIUS ELBOWS WITH AN INSIDE RADIUS OF 0.5W AT ELBOWS IN GREASE DUCT.
- 28/6 DUCT DOWN TO MAKEUP AIR PSP DUCT CONNECTION. TRANSITION TO SUPPLY PLENUM OPENING SIZE. TYPICAL FOR 3.
- 8" DIA. DUCT DOWN TO AC PSP DUCT CONNECTION. TRANSITION TO SUPPLY PLENUM OPENING SIZE. TYPICAL. CAP UNUSED DUCT CONNECTIONS.
- INSTALL GRIDPOINT THERMOSTATS FURNISHED BY TEMS FOR RTU-1 AND RTU-2 AT THIS LOCATION AT 48" AFF. COORDINATE WITH ELECTRICAL SWITCHING IN THIS AREA. PROVIDE WIRING AS SHOWN IN DETAIL 8/E710.
- INSTALL GRIDPOINT ZONE SENSOR MODULE FURNISHED BY TEMS FOR RTU-1 AT THIS LOCATION 60" AFF DIRECTLY TO WALL (NO JUNCTION BOX). COORDINATE LOCATION WITH EQUIPMENT. PROVIDE WIRING AS SHOWN IN DETAIL 8/E710.
- INSTALL GRIDPOINT ZONE SENSOR MODULE FURNISHED BY TEMS FOR RTU-2 AT THIS LOCATION 66" AFF DIRECTLY TO WALL (NO JUNCTION BOX). COORDINATE LOCATION WITH EQUIPMENT. PROVIDE WIRING AS SHOWN IN DETAIL 8/E710.
- INSTALL GRIDPOINT SUPPLY PROBE FURNISHED BY TEMS FOR RTU-1 IN THE SUPPLY DUCTWORK UPSTREAM FROM THE FIRST BRANCH CONNECTION. PROVIDE WIRING AS SHOWN IN DETAIL 8/E710.
- INSTALL GRIDPOINT SUPPLY PROBE FURNISHED BY TEMS FOR RTU-2 IN THE SUPPLY DUCTWORK UPSTREAM FROM THE FIRST BRANCH CONNECTION. PROVIDE WIRING AS SHOWN IN DETAIL 8/E710.
- INSTALL REMOTE TEMPERATURE SENSOR FOR HOOD HD-1 AT THIS LOCATION 66" AFF. COORDINATE LOCATION WITH EQUIPMENT. PROVIDE (2) #18 G. THERMISTOR CABLE FROM TEMPERATURE SENSOR TO HOOD CONTROL PANEL.
- INSTALL KITCHEN HOOD, HD-1. SUPPORT HOOD PER MANUFACTURER'S INSTALLATION INSTRUCTIONS AND AS DETAILED IN THE ARCHITECTURAL AND STRUCTURAL DRAWINGS. INSTALL HOOD ACCORDING TO THE REQUIREMENTS OF ITS LISTING, IN COMPLIANCE WITH NFPA 96, THE BUILDING CODE, AND AUTHORITIES HAVING JURISDICTION. HOOD SHALL HAVE AN INTEGRAL DUCT COLLAR TEMPERATURE SENSOR TO AUTOMATICALLY ENERGIZE THE EXHAUST AND MAKEUP AIR FANS IF COOKING TEMPERATURES ARE DETECTED. EXHAUST DUCT SYSTEM TO BE WELDED OR FACTORY-MANUFACTURED WATER AND AIR TIGHT. INSTALL CLEANOUTS PER CODE AND AS SHOWN. INSTALL HOOD PER DETAILS 2 AND 4/M700. CHIPOTLE WILL PROVIDE AN INDEPENDENT TESTING AGENCY FOR TESTING THE INTEGRITY OF THE GREASE DUCT SYSTEM.

HVAC PLAN NOTES


- INSTALL REMOTE CONDENSING UNIT FOR WALK-IN COOLER ON ROOF AS DETAILED IN THE ARCHITECTURAL AND STRUCTURAL DRAWINGS. INSTALL REFRIGERANT LINE SET, THERMOSTATIC EXPANSION VALVE, SOLENOID VALVE, TEMPERATURE CONTROL, SIGHT GLASS, FILTER DRIER, PRESSURE CONTROL, LOW AMBIENT CONTROLS, AND WEATHERPROOF HOUSING. TRAP AND SLOPE REFRIGERANT LINES PER MANUFACTURER'S RECOMMENDATIONS. INSTALLATION SHALL COMPLY WITH ASHRAE/ANSI STANDARD 15. INSTALL THE REFRIGERANT LINE SET UNDER THE ROOF DECK TO WITHIN 3' OF THE CONDENSING UNIT. CUT 2-1/2" HOLE IN WALK-IN COOLER ROOF FOR REFRIGERANT LINE SET AND SEAL PER THE COOLER MANUFACTURER'S INSTALLATION INSTRUCTIONS AFTER LINE SET IS INSTALLED.
- INSTALL REMOTE CONDENSER FOR ICE MACHINE ON ROOF AS DETAILED IN THE ARCHITECTURAL AND STRUCTURAL DRAWINGS. INSTALL REFRIGERANT LINE SET, THERMOSTATIC EXPANSION VALVE, SOLENOID VALVE, TEMPERATURE CONTROL, SIGHT GLASS, FILTER DRIER, PRESSURE CONTROL, LOW AMBIENT CONTROLS, AND WEATHERPROOF HOUSING. TRAP AND SLOPE REFRIGERANT LINES PER MANUFACTURER'S RECOMMENDATIONS. SEAL PIPING PENETRATIONS THROUGH ROOF. INSTALLATION SHALL COMPLY WITH ASHRAE/ANSI STANDARD 15. INSTALL THE REFRIGERANT LINE SET UNDER THE ROOF DECK TO WITHIN 3' OF THE REMOTE CONDENSER. IF REFRIGERANT PIPING TO ICE MAKER IS EXPOSED TO PUBLIC VIEW CONCEAL WITHIN A STAINLESS STEEL SHROUD AS SHOWN IN THE ARCHITECTURAL DRAWINGS.
- INSTALL ROOFTOP EQUIPMENT PER MANUFACTURER'S INSTALLATION INSTRUCTIONS AND AS DETAILED IN THE ARCHITECTURAL AND STRUCTURAL DRAWINGS.
- INSTALL EXHAUST FAN EF-1 PER DETAIL 5/M700 AND AS DETAILED IN THE ARCHITECTURAL AND STRUCTURAL DRAWINGS. INSTALL GREASE VIROGUARD SYSTEM FURNISHED BY CHIPOTLE ON EXHAUST FAN, EF-1.
- PROVIDE SUPPLY DIFFUSER CONNECTION TO SUPPLY SYSTEM PER DETAIL 1/M700. TYPICAL.
- PROVIDE AUDIO/VISUAL REMOTE SMOKE DETECTOR ANNUNCIATOR WITH REMOTE KEY OPERATED RESET. WIRE A UNIT BACK TO EACH SMOKE DETECTOR. MOUNT UNIT 60" AFF. TYPICAL.
- INSTALL REME HALO AIR PURIFIER FURNISHED BY TUV IN RTU PER DETAIL 6/M700. SEE ELECTRICAL DRAWINGS FOR POWER CONNECTION INFORMATION. INSTALL UV WARNING STICKERS ON FACE OF ENCLOSURE PER DETAIL AND ON ANY RTU ACCESS DOOR(S) THROUGH WHICH THE REME HALO WOULD BE VISIBLE IF OPENED.
- MAINTAIN 10' CLEARANCE BETWEEN WATER HEATER FLUE TERMINATION AND OUTSIDE AIR INTAKES. MAINTAIN 10' CLEARANCE BETWEEN WATER HEATER COMBUSTION AIR INTAKE AND EXHAUST FAN EF-1 DISCHARGE. SEE PLUMBING DRAWINGS FOR MORE INFORMATION ON WATER HEATER FLUE AND COMBUSTION AIR TERMINATIONS.
- ADJUST SUPPLY REGISTERS SO THAT SUPPLY AIR HITS WALL ON OPPOSITE SIDE OF ROOM AT APPROXIMATELY 7' AFF WITH NO DRAFTS FELT IN THE DINING ROOM.
- PROVIDE RESTROOM EXHAUST FAN MOUNTED PER MANUFACTURER'S RECOMMENDATIONS. TERMINATE DUCT OUT OF THE TOP OF THE SOFFIT WITH THE MANUFACTURER'S STANDARD ROOF CAP. SEE SCHEDULE, SHEET M600, FOR MORE INFORMATION.
- ROUTE DUCTWORK THROUGH STRUCTURE AS NECESSARY.



HVAC ROOF PLAN
1/8" = 1'-0"



HVAC DINING ROOM SECTION
1/4" = 1'-0"



HVAC FLOOR PLAN
1/4" = 1'-0"


CHIPOTLE 4246

Consultant:



Blanchard AE Group

1425 WAKARUSA DR. STE B
LAWRENCE, KS 66049
PH: 785.993.0300
AEGROUP@BAE.GROUP



COPYRIGHT 2023
THIS DRAWING IS AN INSTRUMENT OF SERVICE AND AS SUCH REMAINS THE PROPERTY OF CHIPOTLE MEXICAN GRILL, INC. PERMISSION FOR USE OF THIS DOCUMENT IS LIMITED AND CAN BE EXTENDED ONLY BY WRITTEN AGREEMENT WITH CHIPOTLE MEXICAN GRILL, INC.



CHIPOTLE MEXICAN GRILL, INC.
PO BOX 182566
COLUMBUS, OH 43218-2566
TELEPHONE: (614) 318-2400
INTERNET: WWW.CHIPOTLE.COM

STORE NO.: 4642
MORRO RD & HWY 101 - ATASCADERO
6435 Morro Rd.
Atascadero, CA 93422

Issue Record:
02/28/2023 PERMIT ISSUE

Revisions:


Drawn: JJD
Checked: AJD

Project No:
221125


Contents:

HVAC PLAN


M100




9 HVAC DINING ROOM SECTION
M700 NOT TO SCALE




8 HOOD EXHAUST ISOMETRIC
M700 NOT TO SCALE




7 DUCT SECTION AT HOOD
M700 1/4" = 1'-0"




6 UV AIR PURIFIER INSTALLATION
M700 NOT TO SCALE




5 GREASE EXHAUST FAN
M700 NOT TO SCALE




4 FIRE SUPPRESSION SYSTEM SCHEMATIC
M700 NOT TO SCALE



3 FIREMASTER DUCT WRAP - UL HNKT-G18
M700 NOT TO SCALE



2 HOOD SECTION VIEW
M700 NOT TO SCALE



1 DIFFUSER CONNECTION
M700 NOT TO SCALE



COPYRIGHT 2023
THIS DRAWING IS AN INSTRUMENT OF SERVICE AND AS SUCH REMAINS THE PROPERTY OF CHIPOTLE MEXICAN GRILL, INC. PERMISSION FOR USE OF THIS DOCUMENT IS LIMITED AND CAN BE EXTENDED ONLY BY WRITTEN AGREEMENT WITH CHIPOTLE MEXICAN GRILL, INC.



CHIPOTLE MEXICAN GRILL, INC.
PO BOX 182566
COLUMBUS, OH 43218-2566
TELEPHONE: (614) 318-2400
INTERNET: WWW.CHIPOTLE.COM

STORE NO.: 4642
MORRO RD & HWY 101 - ATASCADERO
6435 Morro Rd.
Atascadero, CA 93422

Issue Record:

Issue No.	Date	Description
02/28/2023	PERMIT ISSUE	

Revisions:

No.	Date	Description

Drawn: JJD
Checked: AJD

Project No.: 221125

Contents:
HVAC DETAILS