


**EQUIPMENT ROUGH-IN FLOOR PLAN**

SCALE 1/4" = 1'-0"



**EQUIPMENT SCHEDULE**

EQUIPMENT		ELECTRICAL				PLUMBING		DRAIN				GAS		SEE						
ITEM	QTY	DESCRIPTION	VOLT	K.W.	AMP.	H.P.	LOC.	A.F.F.	CONN.	H.W.	C.W.	LOC.	A.F.F.	IND.	DIR.	LOC.	A.F.F.	CONN.	kBTU	NOTE
1	1	UNDERCOUNTER REFRIG	120/1		7.2	1/5	PROV	12"	PL											B,C
2	1	UNDERCOUNTER FREEZER	120/1		7.5	1/5	PROV	12"	PL											B,C
4*	1	BURRITO STEAMER	120/1		15.0		PROV	48"	PL											A, B
5	1	BASE REFRIGERATOR	120/1		5.0	1/4	PROV	18"	PL											B
7	1	HOT FOOD WELL	120/1		15.0		PROV	42"	PL											B
8*	1	SINGLE DR FREEZER	120/1		15.0				PL											A

**ROUGH-IN LEGEND**

QTY.	QUANTITY	○	DUPLEX RECEPTACLE
VOLT.	VOLTAGE	○	PROVIDE ELECTRICAL ROUGH IN AS PER SPEC
K.W.	KILOWATTS	○	PROVIDE PLUMBING (WATER\GAS) ROUGH IN AS PER SPEC
AMP.	AMPERAGE	○	PROVIDE DRAIN
H.P.	HORSE POWER	○	FLOOR DRAIN
C.W.	COLD WATER	○	FLOOR SINK
H.W.	HOT WATER	○	PHONE JACK
DIR.	DIRECT	○	TELEVISION
R.O.W.	ROUGH OUT WALL	○	COORDINATE LOCATIONS WITH OWNER
R.U.	ROUGH UP	○	120/1 DUPLEX RECEPTACLE MOUNTED AS NOTED ON PLAN, EC TO FLUSH MOUNT EMPTY 4X4 BOX WITH GROMMETTED COVER PLATE AND EMPTY CONDUIT WITH PULL STRING TO OFFICE FOR CABLE (BY OTHERS)
PROV.	PROVIDE	○	
LOC.	LOCATION	○	
A.F.F.	ABOVE FINISHED FLOOR (DIMENSION TO CENTER OF J-BOX)	○	
CONN.	CONNECTION	○	
PL.	PLUG	○	

**EQUIPMENT ROUGH-IN NOTES**

- A. \*\* EXISTING EQUIPMENT RELOCATED, GC/SUB TO FIELD VERIFY EXISTING CONDITIONS AND PROVIDE NEW TO MATCH
- B. COORDINATE INSTALLATION, ELECTRICAL, COMMUNICATION REQUIREMENTS WITH OWNER AND PRODUCT VENDOR
- C. EC TO ROUGH-IN ELECTRICAL RECEPTACLE WITHIN EXISTING STEAM TABLE, VERIFY SPEC SHEET FOR REQUIREMENTS

**GENERAL ROUGH-IN NOTES**

- ALL CONTRACTORS ARE RESPONSIBLE FOR FINAL EQUIPMENT CONNECTIONS AFTER EQUIPMENT IS ROUGH SET IN PLACE.
- 1. PLUMBER TO PROVIDE ALL REQUIRED GAS AND WATER SHUT OFFS AT EQUIPMENT LOCATIONS AS NEEDED.
- 2. ALL DIMENSIONS ON ROUGH IN DWGS ARE FROM FINISHED WALL.
- 3. THE TERM "BY OWNER" INDICATES EQUIPMENT FURNISHED AND/OR COORDINATED BY PIZZA HOUSE OWNER. IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR (GC) AND EACH TRADE TO ACQUIRE THIS SPECIFIC INFORMATION AS NEEDED.
- 4. GC SHALL SILICONE SEAL ALL FABRICATIONS, SINKS, AND OPEN JOINTS AS REQUIRED BY THE BOARD OF HEALTH.
- 5. ELECTRICAL AND PLUMBING CONTRACTORS TO COORDINATE WITH GENERAL CONTRACTOR FOR LOCATIONS OF CONCEALED CONDUITS, FLOOR DRAINS/SINKS, PVC CHASES AND PLUMBING PRIOR TOP FINAL INSTALLATION OF CONCRETE SLAB.
- 6. ALL CONTRACTORS SHALL COORDINATE WITH EACH OTHER/GC AND BETWEEN ARCHITECTURAL/ENGINEERING, AND INTERIOR FINISH DRAWINGS.
- 7. GC SHALL PROVIDE COPIES OF THE ENTIRE DRAWING PACKAGE TO ALL ELECTRICAL, PLUMBING, AND MECHANICAL TRADES.
- 8. IT IS THE RESPONSIBILITY OF EACH TRADE TO IDENTIFY AND DISCREPANCIES BETWEEN THESE "ROUGH-IN" DRAWINGS AND THE ACTUAL PLUMBING, ELECTRICAL, AND MECHANICAL DRAWINGS/SPECIFICATIONS. DISCREPANCIES MUST BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO WORK BE COMPLETED, TO ALLOW FOR DRAWING CORRECTIONS AND ANY SUBSEQUENT COST ADJUSTMENTS DUE TO DISCREPANCIES. FAILURE TO NOTIFY MAKES ALL ADDITIONAL EXPENSES THE RESPONSIBILITY OF THE SUB-CONTRACTOR. ALL ADDITIONAL WORK AND ASSOCIATED COSTS MUST BE SUBMITTED TO THE OWNER FOR WRITTEN APPROVAL.
- 9. PLUMBING AND ELECTRICAL CONTRACTORS SHALL COORDINATE WITH KITCHEN EQUIPMENT SHEETS WITH PLUMBING, MECHANICAL, AND ELECTRICAL DRAWINGS.
- 10. SOUND SYSTEM, TELEVISION, INTERCOM, SECURITY, FIRE ALARM, SUPERVISORY AND PHONE SYSTEMS ARE FURNISHED BY OWNER. GC TO COORDINATE ALL SYSTEM RE-INSTALL WITH OWNER AND SUB-CONTRACTORS AS REQUIRED.
- 11. ALL FINAL CONNECTIONS TO BE DONE BY THE SUB-CONTRACTORS IN ACCORDANCE WITH ALL LOCAL AND STATE CODES. EQUIPMENT WILL BE SET IN APPROXIMATE LOCATION PRIOR TO FINAL HOOK UP BY GC.
- 12. GC TO FURNISH LABOR TO UNLOAD, UNCRATE, INSPECT, SET IN PLACE ALL EQUIPMENT AND FURNITURE AND FABRICATIONS UNLESS OTHERWISE SPECIFIED BY OWNER.
- 13. GC AND SUB-CONTRACTORS TO CONCEAL ALL CONDUITS AND PVC SLEEVES IN FLOOR/WALL PRIOR TO FINAL FINISH INSTALL.
- 14. ELECTRICAL CONTRACTOR TO PROVIDE MIN. CAT-5 CABLE FROM ALL P.O.S. TERMINALS AND PRINTERS BACK TO MAIN OFFICE LOCATION AS DIRECTED BY OWNER. ELECTRICAL CONTRACTOR TO VERIFY REQUIREMENTS WITH OWNER PRIOR TO INSTALLATION.
- 15. ALL PHONE JACKS TO HAVE 4x4 J-BOX WITH EMPTY 3/4" CONDUIT WITH BUSHING TO CEILING CAVITY WITH PULL STRING.
- 16. ELECTRICAL CONTRACTOR TO INSTALL ALL COMPUTER RECEPTACLES AS DEDICATED LINES. PROVIDE HUBBELL #165262 ORANGE DEVICE, COORDINATE REQUIREMENTS WITH OWNER.
- 17. ALL HAND WASHING SINKS TO HAVE SOAP, PAPER TOWEL DISPENSER, AND A HAND WASH REMINDER SIGN - PROVIDED BY GC.

THIS DOCUMENT IS THE PRODUCT AND PROPERTY OF D. R. BROOKS ARCHITECT, LLC. NEITHER THE DOCUMENT NOR THE INFORMATION IT CONTAINS MAY BE COPIED OR USED FOR PURPOSES OTHER THAN THE SPECIFIC PROJECT FOR WHICH IT WAS PREPARED WITHOUT THE WRITTEN CONSENT OF D. R. BROOKS ARCHITECT

ARCHITECTS ■ PLANNERS ■ INTERIORS  
**D.R. Brooks Architect, LLC**  
 100 South Dixie Highway  
 Columbus, KY 40201  
 PH: 606-334-8822  
 FAX: 606-334-8811  
 DANIEL R. BROOKS, R.A.  
 M.C.A.R.B.  
 REGISTERED ARCHITECT  
 LICENSE NO. 4229

**Design Lines**  
 Interior Planners  
 & Kitchen Design  
 100 South Dixie Highway  
 Columbus, KY 40201  
 Phone: 513.314.3428

INTERIOR RENOVATION FOR:  
**SKYLINE CHILI**  
 FT. WRIGHT, KY 40111  
 1730 DIXIE HIGHWAY  
**EQUIPMENT ROUGH-IN FLOOR PLAN**

D.R. BROOKS ARCH., LLC. 2010  
 STATE OF KENTUCKY  
 DANIEL BROOKS  
 2747  
 REGISTERED ARCHITECT  
 All Rights Reserved  
 DANIEL BROOKS, LIC #2747  
 EXPIRATION DATE JUNE 30 2017

SHEET NO.  
**KE-1**  
 JULY 29, 2016  
 16-012 16-012 KE1