

SHEET NUMBER	SHEET NAME
M001	MECHANICAL ABBREVIATIONS AND SYMBOLS
M101	MECHANICAL FLOOR PLAN
M102	MECHANICAL REFRIGERANT PIPING LAYOUT PLAN
M150	MECHANICAL ROOF PLAN
M501	MECHANICAL DETAILS
M502	MECHANICAL DETAILS
M590	MECHANICAL SPECIFICATIONS
M591	MECHANICAL SPECIFICATIONS
M592	MECHANICAL SPECIFICATIONS
M601	MECHANICAL SCHEDULES
M701	CAPTIVEAIRE DRAWINGS
M702	CAPTIVEAIRE DRAWINGS
M703	CAPTIVEAIRE DRAWINGS
M704	CAPTIVEAIRE DRAWINGS
M705	CAPTIVEAIRE DRAWINGS
M706	CAPTIVEAIRE DRAWINGS
M707	CAPTIVEAIRE DRAWINGS
M708	CAPTIVEAIRE DRAWINGS
M709	CAPTIVEAIRE DRAWINGS

RESPONSIBILITY MATRIX

THIS SCHEDULE IS PROVIDED FOR QUICK REFERENCE ONLY.
THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ALL WORK DESCRIBED IN THE CONSTRUCTION DOCUMENTS.
CONFLICTS BETWEEN THIS SCHEDULE AND THE REST OF THE CONTRACT DOCUMENTS SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION PRIOR TO BEGINNING WORK.

DESCRIPTION	FURNISHED			INSTALLED			REMARKS
	GENERAL CONTRACTOR	OWNER	LANDLORD	GENERAL CONTRACTOR	OWNER	LANDLORD	
DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING							
23.1 HVAC DUCTWORK AND PIPING IDENTIFICATION							
23.1.1 HVAC DUCTWORK SYSTEM IDENTIFICATION	X			X			
23.1.2 PIPING SYSTEM IDENTIFICATION	X			X			
23.1.3 UTILITY SHUT OFF IDENTIFICATION IN KITCHEN	X			X			
23.1.4 VALVE TAGS AND CHART	X			X			
23.1.5 HVAC DAMPER IDENTIFICATION	X			X			
23.2 ROOF CURBS							
23.2.1 EXHAUST FAN CURBS			X		X		SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.2 ROOFTOP UNIT CURBS			X		X		SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.3 CONDENSING UNIT CURBS	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.4 MAKE UP AIR UNIT CURBS			X		X		SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.2.5 KITCHEN EXHAUST FAN CURBS			X		X		SCOPE OF WORK TO INCLUDE RIGGING, CURBS, AND ACCESSORIES
23.3 HVAC DUCTWORK SYSTEM COMPONENTS							
23.3.1 HVAC DUCTWORK	X			X			
23.3.2 INSULATION AND FIRE WRAP	X			X			GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE TENANT FIT OUT FROM LANDLORD POINT OF CONNECTION
23.3.3 DAMPERS	X			X			
23.3.4 SMOKE DETECTORS	X			X			
23.3.5 SUPPLY, RETURN, AND EXHAUST GRILLS AND REGISTERS	X			X			
23.4 MECHANICAL PIPING SYSTEM COMPONENTS							
23.4.1 WALK-IN COOLER AND FREEZER REFRIGERATION			X	X			WALK-IN COOLER AND FREEZER SUPPLIED BY VENDOR NO. 103 GENERAL CONTRACTOR SCOPE OF WORK TO INCLUDE PIPING INSTALLATION AND FINAL CONNECTION
23.4.2 REFRIGERATION FOR OTHER HVAC EQUIPMENT	X			X			
23.4.3 CHILLED WATER	X			X			
23.4.4 CONDENSER WATER	X			X			
23.4.5 HEATING HOT WATER	X			X			
23.4.6 VALVES AND ACCESSORIES (E.G. AIR VENTS)	X			X			
23.5 HVAC EQUIPMENT							
23.5.1 SUPPLY FAN	X			X			
23.5.2 TOILET EXHAUST FAN	X			X			
23.5.3 KITCHEN EXHAUST FAN	X			X			
23.5.4 DUCTED AND NON-DUCTED HEATING AND COOLING UNITS			X	X			SUPPLIED BY VENDOR NO. 102
23.5.5 MAKE UP AIR UNITS	X			X			SUPPLIED BY VENDOR NO. 102
23.5.6 ELECTRIC PATIO HEATERS	X			X			
23.5.7 CONDENSING UNITS	X			X			
23.5.8 RGF PHI SYSTEM	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 7 VENDOR SUBSTITUTION IS NOT PERMITTED
23.6 KITCHEN EXHAUST WITH FIRE SUPPRESSION SYSTEM							
23.6.1 HOOD CONTROL PANEL			X	X			SUPPLIED BY VENDOR NO. 102
23.6.2 KITCHEN EXHAUST HOOD			X	X			SUPPLIED BY VENDOR NO. 102
23.6.3 STRUCTURAL SUPPORT	X			X			
23.6.4 ELECTRICAL AND CONTROL WIRING	X			X			
23.6.5 TANK SYSTEM			X	X			SUPPLIED BY VENDOR NO. 102 GENERAL CONTRACTOR TO COORDINATE AND FACILITATE SYSTEM SIGN-OFF
23.6.6 TANK WIRING AND UTILITIES CONNECTION	X			X			
23.6.7 TANK GAS VALVE			X	X			SUPPLIED BY VENDOR NO. 102
23.7 COMMISSIONING ACTIVITIES							
23.7.1 GREASE EXHAUST WATER LEAKAGE TEST	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 6 VENDOR SUBSTITUTION IS NOT PERMITTED
23.7.2 TESTING AIR BALANCE (TAB) REPORT	X			X			GENERAL CONTRACTOR TO PURCHASE FROM VENDOR NO. 7 VENDOR SUBSTITUTION IS NOT PERMITTED

SUBMITTAL MATRIX

GENERAL CONTRACTORS TO ALSO REVIEW ARCHITECTURAL SPECIFICATIONS AS NOTED IN PLANS IN PLAN SECTION 700 OF THE ARCHITECTURAL PACKAGE FOR REQUIRED SUBMITTALS THAT MIGHT NOT BE LISTED BELOW.

SUBMITTAL DESCRIPTION	Required Review Time (Business Days)	Architect of Record	Shop Drawings	Samples Required	Physical Submittals Required	Submit for Record	Submit for Record Only
Anchor Bolts Shops	5	X				X	
ATAS-Detailed Shop DWGS(Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X					X
Concrete Mix Design	5	X					X
Construction Prefunctional Checklists	5	X					X
Decorative Metal Shop Drawings	5	X					
Difusers, Grills & Registers	5	X				X	
Doors, Frames & Hardware	7	X				X	
Ductwork Layout (if there are significant changes in field)	5	X				X	
Electrical Distribution Equipment	5	X					
Elevator & Vertical Transportation Shop Drawings	5	X					X
Epoxy Floor	5	X					
Fire Alarm Shop Drawings & Device Cut Sheets	5	X				X	
Fire Sprinkler Shop Drawings, Hydraulic Calculations & Device Cut Sheets	5	X					X
HVAC Equipment(if Carrier - Submitted by Owner Vendor to Owner/AOR prior to const.)	5	X				X	
Light Fixtures(Submitted by Owner Vendor to Owner/AOR prior to construction)	5	X				X	
MEP Tests, Start-Up, and Programming Reports	5	X				X	
Millwork - Material Submittals (if differs from spec)	5	X		X	X		
Millwork - Shop Drawings (custom items & design features only)	5	X					
Restroom Partitions	5	X				X	
Plumbing Fixtures	5	X				X	
Railing Shop Drawings	5	X					X
Rebar	5	X				X	
Stair Shop Drawings	5	X					X
Structural Steel Shop Drawings	7	X				X	
Storefront - product data Submittal (if different from specified)	5	X					
Storefront - Shop Drawings	5	X					
Tile (if differs from spec)	5	X				X	
Window Film	5	X					

SYMBOLS

HEATING-VENTILATING-AIR CONDITIONING	
SYMBOL	DESCRIPTION
	THERMOSTAT
	REMOTE SENSOR
	SUPPLY DIFFUSER
	RETURN OR EXHAUST GRILLE
	SUPPLY OR FRESH AIR DUCT (SA OR FA)
	RETURN OR EXHAUST AIR DUCT (RA OR EA)
	RECTANGULAR DUCT (FIRST FIGURE IS SIDE SHOWN)
	ROUND DUCT
	VOLUME DAMPER (ELEV AND PLAN)
	TURNING VANES
	SUPPLY REGISTER OR GRILLE (R OR G)
	RETURN REGISTER OR GRILLE (R OR G)
	FRESH AIR INTAKE (FA)
	SQUARE CEILING DIFFUSER (SUPPLY)
	FAN COIL UNIT AND MARK
	MOTORIZED DAMPER
	REFRIGERANT LIQUID LINE
	REFRIGERANT SUCTION LINE

Bergmeyer


800 South Figueroa St.
 Los Angeles, CA 90017
 213.337.1090
 www.bergmeyer.com
 875 N High St.
 Columbus, OH 43215
 617.542.1025
 390.900.8887
 51 Shaffer St.
 Braintree, MA 02210
 617.542.1025



New York • Miami • Orlando • Los Angeles • Dallas • Houston
952.921.0020 www.schnackel.com

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL/ SIGNATURE:



NO.	BY	DATE	DESCRIPTION
1	AJ	2024-01-22	IFC SET
B	AJ	2024-04-15	ADDENDUM B
A	SG/AJ	2024-02-23	ADDENDUM A
SI/AJ		2023-12-04	PERMIT / BID SET
SI/AJ		2023-11-06	75% SET
RD		2023-04-01	DD SET



SHAKE SHACK - TOWN & COUNTRY

700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET

MECHANICAL
ABBREVIATIONS &
SYMBOLS



DRAWN BY: RAS

CHECKED BY: GRS

JOB NO: 20230037.00

M001

1 MECHANICAL FLOOR PLAN
SCALE: 1/4" = 1'-0"



- GENERAL NOTES:**
- A. EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - B. CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - C. ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - D. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - E. MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - F. ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - G. ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - H. COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - I. THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - J. ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - K. DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E., BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - L. ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACoustical DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOGA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACoustical DUCT LINER.
 - M. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK WITHIN 10 FEET OF THE UNIT SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - N. ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE.
 - O. PROVIDE REMOTE VOLUME DAMPER MANUFACTURED BY YOUNG REGULATOR OR LIMITED CLEARANCE DAMPERS LOCATED IN ACCESSIBLE CEILING.
 - P. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - Q. REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE AS REQUIRED FOR COMPLETELY FOR COMPLETELY FOR COMPLETELY WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - R. TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITIES RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITIES RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - S. ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE. IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - T. ROOF MOUNTED EQUIPMENT SHALL BE LABELED WITH THE TENANT NAME AND SPACE NUMBER WITH 3" FINISH WEATHER PROTECTIVE TIES.
 - U. ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E-2336 REQUIREMENTS.
 - V. GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - W. MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) MONTHS SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - X. AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCE AND COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURGH AT WILLTURNBOURGH.COM OR 514-884-6244.
 - Y. PARTS OF THE BASE BUILDING SYSTEMS THAT FALL INTO LEASE LINE SHALL REMAIN UNDISTURBED UNLESS NOTED OTHERWISE.
 - Z. PROVIDE ALL NECESSARY WIRING, RELAYS, DETECTORS, COMPONENTS, ETC., FOR FIRE ALARM OR CONTROL SYSTEM INTERLOCK IF APPLICABLE. VERIFY WITH BUILDING PERSONNEL BEFORE BID.
- HVAC NOTES:**
1. RETURN GRILLE TO BE MOUNTED AS HIGH AS EXISTING CONDITIONS ALLOW. COORDINATE WITH FINISH AND INSTALLATION LOCATION WITH THE ARCHITECT.
 2. CONTRACTOR SHALL UNDERCUT DOOR 3/4".
 3. PROVIDE 8/8 EXHAUST AIR DUCT UP TO EF-3 ON ROOF.
 4. NEW CAPTIVEIRE EXHAUST HOOD TO BE FURNISHED BY OWNER FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. SEE CAPTIVEIRE SHEETS FOR ADDITIONAL INFORMATION. BALANCE HOOD EXHAUST AS NOTED ON CAPTIVEIRE SHEETS. VERIFY ALL MANUFACTURER AND CODE REQUIRED CLEARANCES ARE MAINTAINED. NOTIFY ARCHITECT IF ANY CONFLICTS OCCUR.
 5. TRANSITION FROM HOOD EXHAUST COLLAR AS INDICATED ON PLANS AND EXTEND KITCHEN HOOD GREASE EXHAUST DUCTWORK UP TO CORRESPONDING GREASE EXHAUST FAN ON ROOF AS INDICATED ON THE PLANS. SEE SHEET M100 FOR CONTINUATION. GREASE DUCT SHALL BE WRAPPED WITH TWO (2) LAYERS OF THERMAL CERAMICS FAST WRAP XL, 1 1/2" THICK WITH 3" PERIMETER AND LONGITUDINAL OVERLAPS OR EQUIVALENT U.L. LISTED GREASE DUCT WRAP FOR ZERO CLEARANCE TO COMBUSTIBLES. REFER TO SHEET M501, DETAIL 2, FOR ADDITIONAL INFORMATION. TYPICAL.
 6. PROVIDE CLEARANCES ON GREASE DUCTWORK AS REQUIRED BY CODE. REFERENCE SHEET M501, DETAIL 1 FOR ADDITIONAL INFORMATION. TYPICAL OF GREASE EXHAUST DUCTWORK.
 7. DUCTWORK TO BE TO BE INSTALLED AS HIGH AS CONDITIONS ALLOW. COORDINATE ROUTING AND MOUNTING HEIGHT WITH LIGHTING FIXTURES. NOTIFY THE ARCHITECTS OF ANY CONFLICTS AND COORDINATE WITH THE CONSTRUCTION MANAGER.
 8. PROVIDE REMOTE VOLUME DAMPER AS INDICATED ON PLANS. REFERENCE SHEET M501, DETAIL 3, FOR ADDITIONAL INFORMATION. TYPICAL OF DIFFUSERS/GRILLES INSTALLED IN GYP. BOARD CEILING.
 9. PROVIDE NEW FC UNIT AS NOTED ON PLANS AND AS SCHEDULED ON SHEET M501.
 10. PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 11. HOOD MANUFACTURER TO PROVIDE A "KIT" TO FASTEN THE BOTTOM FLANGE OF THE HOOD TO THE WALL, WITH ONE FASTENER PER STUD WALL. SIL-BOND RTV 4500 ALUMINUM SILICONE SEALANT OR APPROVED SIMILAR, TO BE APPLIED BY GENERAL CONTRACTOR/HOOD INSTALLER FOR ANY REMAINING SMALL GAPS. HOOD FASTENING "KIT" DETAIL TO BE INCLUDED IN MANUFACTURER DRAWINGS. REFERENCE SHEET M501, DETAIL 11, FOR ADDITIONAL INFORMATION.
 12. BALANCE DAMPER TO PROVIDE 30 CFM.
 13. COORDINATE WITH CAPTIVEIRE ON REMOTE SENSORS AND COMFORT CONTROLS PACKAGE THAT IS TO BE INSTALLED IN THE OFFICE. VERIFY CONTROLS ARE A FULLY DIGITAL 7 DAY PROGRAMMABLE TYPE THERMOSTAT WITH REMOTE SENSING CAPABILITIES, AUTO CHANGE OVER AND AUTO SET BACK. MOUNT SENSOR AND CONTROLS AT 48" ABOVE FINISHED FLOOR. UNITS SERVING THE SAME TEMPERATURE ZONE SHALL BE INTERLOCKED TO PREVENT SIMULTANEOUS HEATING AND COOLING. LOCATE REMOTE TEMPERATURE SENSORS AS INDICATED ON PLAN. COORDINATE LOCATION WITH CONSTRUCTION MANAGER AND WALL GRAPHICS LAYOUT. REFERENCE CAPTIVEIRE SHEETS FOR ADDITIONAL INFORMATION.
 14. PROVIDE WITH INSULATED BACK PAN.
 15. VERIFY WITH ALL TRADES THAT TRANSFORMER CLEARANCES ARE MAINTAINED. DIFFUSER TO BE MOUNTED IN FACE OF TRANSFORMER SOFFIT.

Bergmeyer


800 South Figueroa St.
Los Angeles, CA 90017
213.337.1000

51 Slinger St.
Billerica, MA 02021
980.900.8887
617.542.1025

Schnackel
engineers

New York • Miami • Orlando • Los Angeles • Dallas • Houston
800.621.0200

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680



NO.	BY	DATE	DESCRIPTION
1	AJ	2024-01-22	IFC SET
B	ASGAJ	2024-04-15	ADDENDUM B
A	ASGAJ	2024-02-23	ADDENDUM A
	ASGAJ	2023-12-04	PERMIT / BID SET
	ASGAJ	2023-11-06	75% SET
	RAS	2023-04-01	DD SET

SHAKE SHACK

SHAKE SHACK - TOWN & COUNTRY

700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502


IFC SET

MECHANICAL FLOOR PLAN

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 20230037.00

M101

SEAL SIGNATURE:



- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E., BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOGA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERIALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR LIMITED EXTERIOR PER DAMPERS LOCATED ABOVE INACCESSIBLE CEILING. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OF ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE. IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ROOF MOUNTED EQUIPMENT SHALL BE LABELED WITH THE TENANT NAME AND SPACE NUMBER WITH 3" HIGH WEATHER PROOF LETTERS.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURGH AT WILLTURNBOURGH@TAB.COM OR 514-894-6244.
 - PARTS OF THE BASE BUILDING SYSTEMS THAT FALL INTO LEASE LINE SHALL REMAIN UNDISTURBED UNLESS NOTED OTHERWISE.
 - PROVIDE ALL NECESSARY WIRING, RELAYS, DETECTORS, COMPONENTS, ETC., FOR FIRE ALARM OR CONTROL SYSTEM INTERLOCK IF APPLICABLE. VERIFY WITH BUILDING PERSONNEL BEFORE BID.

- HVAC NOTES:**
- PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.
 - PROVIDE REFRIGERANT LINES FROM CONDENSING UNIT ON ROOF TO KITCHEN EQUIPMENT AS NOTED ON PLANS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE. ADJUST ROUTING AS NECESSARY IN FIELD FOR ANY OBSTACLES. COORDINATE EXACT LOCATION AND ROUTING WITH CONSTRUCTION MANAGER.

1	AJ	2024-01-22	IFC SET
B	AJ	2024-04-15	ADDENDUM B
A	SG/AJ	2024-02-23	ADDENDUM A
SR/AJ		2023-12-04	PERMIT / BID SET
SR/AJ		2023-11-06	75% SET
RS		2023-04-01	DD SET
NO.	BY	DATE	DESCRIPTION



SHAKE SHACK - TOWN & COUNTRY


700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET


MECHANICAL
REFRIGERANT PIPING
LAYOUT PLAN


DRAWN BY:	RAS
CHECKED BY:	GRS
JOB NO.:	20230037.00

M102



1 MECHANICAL REFRIGERANT PIPING LAYOUT PLAN
SCALE: 1/4" = 1'-0"





- GENERAL NOTES:**
- EXISTING CONDITIONS ARE BASED ON RECORD DRAWINGS PROVIDED BY THE OWNER. CONTRACTOR SHALL ADJUST TO ACTUAL FIELD CONDITIONS AT NO ADDITIONAL EXPENSE TO THE PROJECT.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING THE BID. NO ADDITIONAL COMPENSATION WILL BE PROVIDED FOR ANY EXTRAS DUE TO THE CONTRACTOR'S FAILURE TO VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER FOR RESOLUTION.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS. CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH DEMOLITION WORK PRIOR TO BIDDING AND START OF WORK. CONTRACTOR IS RESPONSIBLE TO DEMOLISH ALL EXISTING AS REQUIRED FOR INSTALLATION/CONSTRUCTION OF NEW WORK.
 - ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE GOVERNMENT AND LOCAL CODES.
 - MECHANICAL CONTRACTOR SHALL FIELD COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL POWER REQUIREMENTS.
 - ALL CONTRACTORS SHALL REVIEW A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF ALL EQUIPMENT MAY BE PROPERLY COORDINATED.
 - ALL EQUIPMENT FURNISHED SHALL FIT THE SPACE AVAILABLE WITH CONNECTIONS IN THE REQUIRED LOCATIONS AND WITH ADEQUATE SPACE FOR OPERATING AND SERVICING. THE DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATE THE INTENT OF THE INSTALLATION WHILE THE SPECIFICATIONS AND EQUIPMENT LIST DENOTE THE TYPE AND QUALITY OF MATERIAL AND WORKMANSHIP TO BE USED. THE DRAWINGS SHALL NOT BE SCALED FOR EXACT MEASUREMENTS. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER AND/OR MORE COSTLY STANDARD WILL APPLY. THE CONTRACTOR SHALL PROMPTLY NOTIFY THE ENGINEER WHOSE DECISION SHALL BE FINAL. NO ALLOWANCE WILL BE MADE SUBSEQUENTLY IN THIS REGARD ON BEHALF OF THE CONTRACTOR AFTER AWARD OF THE CONTRACT.
 - COORDINATE DUCT ROUTING AND HEIGHTS WITH GENERAL CONTRACTOR. VERIFY ALL CLEARANCES BEFORE STARTING WORK.
 - THE CONTRACTOR SHALL INSTALL ALL PIPING, DUCTWORK AND EQUIPMENT AS REQUIRED TO CONFORM TO THE STRUCTURE, AVOID OBSTRUCTIONS, PRESERVE CEILING HEIGHTS AND HEADROOM AND MAKE ALL EQUIPMENT REQUIRING MAINTENANCE OR REPAIR ACCESSIBLE.
 - ALL DUCT CONNECTIONS TO HVAC EQUIPMENT MUST BE MADE WITH FLEXIBLE CONNECTORS.
 - DO NOT ATTACH ANYTHING TO DECK ABOVE. ATTACH TO STRUCTURE (I.E., BEAMS, JOISTS) ONLY. DUCT HANGERS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODE. ALL CONNECTIONS TO JOISTS SHALL BE MADE AT THE TOP CORNER.
 - ALL DUCT DIMENSIONS INDICATED ARE CLEAR INSIDE DIMENSIONS. ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER OR WRAPPED WITH 1-1/2" THICK FIRE RETARDANT FIBERGLASS WITH A REINFORCED ALUMINUM FOIL JACKET AND SHALL BE APPROVED FOR USE BY SMOGA AND NAIMA. RETURN AIR TRANSFER DUCTS AND RETURN DUCTWORK WITHIN 10 FEET OF THE UNIT FAN SHALL BE LINED WITH 1" ACOUSTICAL DUCT LINER.
 - ALL SUPPLY AND UNTEMPERED OUTDOOR AIR DUCTWORK VISIBLE TO THE PUBLIC SHALL BE INTERNALLY LINED AND PAINTED TO MATCH THE SURROUNDING AREA. DUCT WRAP INSULATION IS NOT PERMITTED IN THESE AREAS.
 - ALL EXPOSED DUCTWORK SHALL BE INSTALLED TIGHT TO THE BOTTOM OF THE STRUCTURE.
 - PROVIDE REMOTE VOLUME DAMPER CONTROL MANUFACTURED BY YOUNG REGULATOR OR LIMITED ENERGY FOR DAMPERS LOCATED ABOVE INACCESSIBLE CEILINGS. LOCATE CONTROLLER ABOVE ACCESSIBLE CEILING LOCATION.
 - REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - TENANT'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE FIELD VERIFICATION OF ALL UTILITY RUNS AND/OR OTHER IMPROVEMENTS LOCATED ON THE PREMISES PRIOR TO BIDDING. TENANT'S CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ALL COSTS RELATING TO THE RELOCATION OF, DAMAGE TO, REPAIR OR ANY EXISTING UTILITY RUNS AND/OR IMPROVEMENTS WHICH ARE DAMAGED AS A RESULT OF TENANT'S WORK IN OR AROUND THE PREMISES.
 - ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S APPROVED ROOFING CONTRACTOR AT TENANT'S EXPENSE. IF REQUIRED IN LEASE OR TENANT CRITERIA MANUAL.
 - ROOF MOUNTED EQUIPMENT SHALL BE LABELED WITH THE TENANT NAME AND SPACE NUMBER WITH 3" CLEARANCE FROM THE ROOF LETTERS.
 - ALL GREASE EXHAUST DUCTWORK SHALL BE PROVIDED WITH 3" FOIL FACED THERMAL-CERAMIC INSULATION FOR GREASE DUCTS. INSULATION SHALL MEET NFPA 96 AND ASTM E 2336 REQUIREMENTS.
 - GREASE DUCT LEAKAGE TESTING MUST BE PERFORMED PRIOR TO CONCEALMENT OF THE DUCTWORK.
 - MECHANICAL CONTRACTOR SHALL PROVIDE TENANT WITH A WRITTEN ONE (1) YEAR MANUFACTURER'S WARRANTY ON ALL HVAC EQUIPMENT PROVIDED AND / OR INSTALLED. THE WARRANTY SHALL INCLUDE ALL LABOR, MATERIALS AND THREE (3) ROUTINE SERVICES INCLUDING FILTER CHANGES DURING A ONE (1) YEAR PERIOD.
 - AT THE COMPLETION OF CONSTRUCTION AN NEBB, AABC OR TABB CERTIFIED AIR BALANCE REPORT SHALL BE SUBMITTED TO THE ENGINEER AND LANDLORD. PRIOR TO SCHEDULING BALANCING, COORDINATE WITH LANDLORD'S FIELD REPRESENTATIVE FOR THE VENDOR LISTED BELOW. IF APPROVED, THE BALANCING SHALL BE COMPLETED BY NATION TAB. CONTACT WILL TURNBOURH AT WILLTURNBOURH.COM OR 514-894-6244.
 - PARTS OF THE BASE BUILDING SYSTEMS THAT FALL INTO LEASE LINE SHALL REMAIN UNDISTURBED UNLESS NOTED OTHERWISE.
 - PROVIDE ALL NECESSARY WIRING, RELAYS, DETECTORS, COMPONENTS, ETC., FOR FIRE ALARM OR CONTROL SYSTEM INTERLOCK IF APPLICABLE. VERIFY WITH BUILDING PERSONNEL BEFORE BID.

- HVAC NOTES:**
- NEW CAPTIVEAIRE RTU TO BE FURNISHED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE CAPTIVEAIRE SHEETS FOR ADDITIONAL INFORMATION. FIELD VERIFY EXACT LOCATION.
 - NEW CAPTIVEAIRE GREASE EXHAUST FAN TO BE FURNISHED BY OWNER FOR INSTALLATION BY MECHANICAL CONTRACTOR. SEE CAPTIVEAIRE SHEETS FOR ADDITIONAL INFORMATION. CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE. DUCT SMOKE DETECTOR ON RETURN SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.
 - RRR ENVIRONMENTAL GROUP, INC. AIR PURIFICATION SYSTEM TO BE PROVIDED BY NTAB. REFER TO RESPONSIBILITY MATRIX ON SHEET M001 FOR ADDITIONAL INFORMATION, SHEET M601 FOR SCHEDULE, AND SHEET M602 FOR SPECIFICATIONS. PROVIDE NEW EXHAUST FAN AS NOTED ON PLANS AND SCHEDULED ON SHEET M601. THE CONTRACTOR SHALL FIELD VERIFY THAT THE LOCATION SHOWN IS A MINIMUM OF 10'-0" FROM ANY OUTDOOR AIR INTAKE.
 - PROVIDE ASHP AS NOTED ON PLANS AND SCHEDULED ON SHEET M601.
 - PROVIDE REFRIGERANT LINES FROM ASHP-1 ON ROOF TO FC-1 IN KITCHEN OFFICE. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.
 - PROVIDE REFRIGERANT LINES FROM KITCHEN EQUIPMENT CONDENSING UNITS ON ROOF TO UNITS IN THE KITCHEN SPACE AS INDICATED ON THE KITCHEN DRAWINGS. LINES SHALL BE SIZED ACCORDING TO MANUFACTURER'S SPECIFICATIONS. PROVIDE ALL ACCESSORIES AS REQUIRED BY MANUFACTURER FOR COMPLETE WORKING SYSTEM, INCLUDING ANY ACCESSORIES ASSOCIATED WITH LONG LENGTH APPLICATIONS WHERE APPLICABLE.

1	AJ	2024-01-22	IFC SET
B	AJ	2024-04-15	ADDENDUM A
A	SGIAJ	2024-02-23	ADDENDUM A
A	SGIAJ	2023-12-04	PERMIT / BID SET
A	SGIAJ	2023-11-06	75% SET
SS		2023-04-01	DO SET

NO.	BY	DATE	DESCRIPTION
-----	----	------	-------------



SHAKE SHACK - TOWN & COUNTRY


700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET

MECHANICAL ROOF PLAN

DRAWN BY:	RAS
CHECKED BY:	GRS
JOB NO.:	20230037.00

M150



WALK-IN COOLER/FREEZER CONDENSING UNITS. REFER TO KITCHEN EQUIPMENT VENDOR DRAWINGS FOR ADDITIONAL INFORMATION.

NOTE 6

ASHP-1
NOTE 6
NOTE 7

2-500 CFM F.A. MIN.

NOTE 3

RTU-2 (DOAS)
NOTE 2
NOTE 4

NOTE 3

RTU-1 (DOAS)
NOTE 1
NOTE 4


NOTE 3


900 CFM F.A. MIN.

EF-1
EST. WT: 136 LBS.


EF-2
EST. WT: 136 LBS.

1 MECHANICAL ROOF PLAN
SCALE: 1/4" = 1'-0"






8 CURB FLASHING DETAIL
NOT TO SCALE




NOTE:
1. DUCT SMOKE DETECTOR ON RETURN AND/OR SUPPLY SIDE DUCT AND SHUTDOWN RELAY SHALL BE FURNISHED BY THE ELECTRICAL CONTRACTOR FOR INSTALLATION BY THE MECHANICAL CONTRACTOR. ALL WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR.

5 DUCT SMOKE DETECTOR DETAIL
NOT TO SCALE




NOTE:
1. CONTACT MANUFACTURER FOR INFORMATION REGARDING ROUGH-IN SIZES.

1 TYPICAL DRYWALL MOUNTING FRAME DETAIL
NOT TO SCALE




NOTES:
1. PROVIDE THROUGH CURB ELECTRICAL CONNECTIONS. NO ROOF PENETRATIONS OF ELECTRICAL CONDUITS WILL BE ACCEPTABLE.
2. DUCT SMOKE DETECTOR SHALL BE MOUNTED AND INSTALLED PER LOCAL CODES.


6 TYPICAL ROOF TOP UNIT DETAIL
NOT TO SCALE




2 TYPICAL ROOF TOP UNIT TEE CONNECTION
NOT TO SCALE



7 DUCTWORK DETAILS
NOT TO SCALE



3 TYPICAL DIFFUSER CONNECTION
NOT TO SCALE




4 TYPICAL ROUND DUCT FITTINGS
NOT TO SCALE

Bergmeyer
LA 800 South Figueroa St. Los Angeles, CA 90017
CO 875 N High St. Columbus, OH 43215
BOS 51 Sleeper St. Braintree, MA 02210
617.542.1105 980.900.8887
www.bergmeyer.com

Schnackel engineers
New York • Miami • Omaha • Los Angeles • Dallas • Houston
800.621.6262 www.schnackel.com

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEAL SIGNATURE:



1	AJ	2024-01-22	IFC SET
2	AJ	2024-04-15	ADDENDUM B
3	AJ	2024-02-23	ADDENDUM A
4	SG/AJ	2023-12-04	PERMIT / BID SET
5	SG/AJ	2023-11-06	75% SET
6	RAS	2023-04-01	DO SET
NO.	BY	DATE	DESCRIPTION

SHAKE SHACK

SHAKE SHACK - TOWN & COUNTRY

700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET

MECHANICAL DETAILS

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 20230037.00

M502

SPECIFICATIONS TABLE OF CONTENTS

- SECTION 230000 – HVAC GENERAL CONDITIONS
- SECTION 230548 – VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT
- SECTION 230583 – TESTING, ADJUSTING, AND BALANCING FOR HVAC
- SECTION 230713 – DUCT INSULATION
- SECTION 230713.1 – GREASE DUCT FIREPROOFING
- SECTION 230719 – HVAC PIPING INSULATION
- SECTION 230800 – COMMISSIONING FOR HVAC SYSTEMS
- SECTION 230983 – SEQUENCE OF OPERATIONS FOR HVAC CONTROLS
- SECTION 231200 – REFRIGERANT PIPING
- SECTION 233100 – HVAC DUCTS AND CASINGS
- SECTION 233300 – AIR DUCT ACCESSORIES to existing HVAC systems
- SECTION 233423 – HVAC POWER VENTILATORS
- SECTION 233700 – FAN DUCTS AND ACCESSORIES
- SECTION 2337413 – PACKAGED OUTDOOR ROOF TOP UNITS – GAS FIRED
- SECTION 2338127 – SMALL SPLIT-SYSTEM HEATING AND COOLING

SECTION 230000 – HVAC GENERAL CONDITIONS

PART 1 GENERAL

- 1.01 APPLICABILITY
- 1.02 DEFINITIONS
- 1.03 CODES AND STANDARDS
- 1.04 PERMITS AND FEES
- 1.05 CONTRACT DRAWINGS
- 1.06 EXISTING CONDITIONS
- 1.07 SUBMITTALS
- 1.08 QUALITY ASSURANCE
- 1.09 DELIVERY, STORAGE, AND HANDLING
- 1.10 WARRANTY AND GUARANTEE

PART 2 PRODUCTS

- 2.01 SUBSTITUTIONS
- 2.02 MANUFACTURERS

PART 3 EXECUTION

- 3.01 INSTALLATION
- 3.02 SCHEDULES
- 3.03 EXECUTION
- 3.04 WARRANTY

PART 4 EXECUTION

- 4.01 SECTION INCLUDES
- 4.02 SUBMITTALS
- 4.03 EXECUTION
- 4.04 WARRANTY

- 4.05 EXAMINATION
- 4.06 INTERFACE WITH OTHER PRODUCTS
- 4.07 FIELD QUALITY CONTROL
- 4.08 SCOPE
- 4.09 MINIMUM DATA
- 4.10 PROJECT RECORD DOCUMENTS
- 4.11 ELECTRIC MATERIALS AND DEVICES
- 4.12 COOLING AND HEATING EQUIPMENT
- 4.13 AIR DISTRIBUTION TESTS

END OF SECTION

SECTION 230548 – VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT

PART 1 GENERAL

- 1.01 SECTION INCLUDES
- 1.02 SUBMITTALS
- 1.03 EXECUTION

PART 2 PRODUCTS

- 2.01 MANUFACTURERS
- 2.02 VIBRATION ISOLATORS
- 2.03 GLASS FIBER, FLEXIBLE ELASTOMER, CELLULAR INSULATION

PART 3 EXECUTION

- 3.01 INSTALLATION
- 3.02 SCHEDULES
- 3.03 EXECUTION

END OF SECTION

SECTION 230583 – TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 GENERAL

- 1.01 SECTION INCLUDES
- 1.02 SUBMITTALS
- 1.03 EXECUTION

PART 2 PRODUCTS

- 2.01 SUBSTITUTIONS
- 2.02 MANUFACTURERS

PART 3 EXECUTION

- 3.01 INSTALLATION
- 3.02 SCHEDULES
- 3.03 EXECUTION

- 3.04 WARRANTY
- 3.05 EXAMINATION
- 3.06 INTERFERENCE WITH OTHER PRODUCTS
- 3.07 FIELD QUALITY CONTROL
- 3.08 SCOPE
- 3.09 MINIMUM DATA
- 3.10 PROJECT RECORD DOCUMENTS
- 3.11 ELECTRIC MATERIALS AND DEVICES
- 3.12 COOLING AND HEATING EQUIPMENT
- 3.13 AIR DISTRIBUTION TESTS

END OF SECTION

SECTION 230713 – DUCT INSULATION

PART 1 GENERAL

- 1.01 SECTION INCLUDES
- 1.02 SUBMITTALS
- 1.03 EXECUTION

PART 2 PRODUCTS

- 2.01 MANUFACTURERS
- 2.02 VIBRATION ISOLATORS
- 2.03 GLASS FIBER, FLEXIBLE ELASTOMER, CELLULAR INSULATION

PART 3 EXECUTION

- 3.01 INSTALLATION
- 3.02 SCHEDULES
- 3.03 EXECUTION

END OF SECTION

- 3.04 WARRANTY
- 3.05 EXAMINATION
- 3.06 INTERFERENCE WITH OTHER PRODUCTS
- 3.07 FIELD QUALITY CONTROL
- 3.08 SCOPE
- 3.09 MINIMUM DATA
- 3.10 PROJECT RECORD DOCUMENTS
- 3.11 ELECTRIC MATERIALS AND DEVICES
- 3.12 COOLING AND HEATING EQUIPMENT
- 3.13 AIR DISTRIBUTION TESTS

END OF SECTION

SECTION 230719 – HVAC PIPING INSULATION

PART 1 GENERAL

- 1.01 SECTION INCLUDES
- 1.02 SUBMITTALS
- 1.03 EXECUTION

PART 2 PRODUCTS

- 2.01 MANUFACTURERS
- 2.02 VIBRATION ISOLATORS
- 2.03 GLASS FIBER, FLEXIBLE ELASTOMER, CELLULAR INSULATION

PART 3 EXECUTION

- 3.01 INSTALLATION
- 3.02 SCHEDULES
- 3.03 EXECUTION

END OF SECTION

Bergmeyer
860 South Figueroa St.,
Columbus, OH 43215
380.900.8887
www.bergmeyer.com

Schnackel engineers
New York, New York • Columbus, Ohio • Los Angeles • Dallas • Houston
9505 Old Katy Rd.
MEFF Engineering
3035 S 72nd St.
OMAHA NE 68124
TEL. 402.391.7680

SEALED SIGNATURE:

NO.	BY	DATE	DESCRIPTION
1	AJ	2024-02-20	IFC SET
B	AJ	2024-04-16	ADDENDUM B
A	SGAJ	2024-02-23	ADDENDUM A
SNAJ		2023-11-06	PERMIT / BID SET
MSJ		2023-07-01	DO SET

SHAKE SHACK

SHAKE SHACK - TOWN & COUNTRY

700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET

MECHANICAL SPECIFICATIONS

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 2023037.00

M590

- E. Locate ducts with sufficient space around equipment to allow normal operating and maintenance activities.
- F. Use crimp joints with or without bead for joining round duct sizes 8 inch and smaller with crimp in direction of air flow.
- G. Use duct nuts and lock washers on threaded rod supports.
- H. Connect flexible ducts to metal ducts with draw bands.
- I. Support flexible duct runs every 4 feet in the horizontal direction to avoid dips and sags.
- J. Connect terminal units to supply ducts with one foot maximum length of flexible duct. Do not use flexible duct to change direction.
- K. Connect diffusers to low pressure ducts directly or with 5 feet maximum length of flexible duct held in place with strap or clamp. Longer duct lengths are acceptable if depicted on the design drawings and allowed per local code. A maximum of one 90 degree bend, or equivalent, will be allowed in flexible duct runs.
- L. During construction provide temporary closures of metal or taped polyethylene on open ductwork to prevent construction dust from entering ductwork system.
- M. All exposed ducts in finished areas must be completely free from all dents or imperfections in the galvanized coating and shall be sealed CAREFULLY AND NEATLY with duct sealer completely contained within the joint. Duct wrap will not be acceptable if exposed locations in finished areas are indicated in exposed locations, it must be spiral. No exposed duct sealer, tape or longitudinal joints will be accepted in exposed finished areas. Line all exposed supply air ductwork.
- N. Kitchen hood exhaust, Type 1: Use stainless steel for ductwork exposed to view and stainless steel or carbon steel for ducts where concealed.
- O. For all hood systems, perform all required regulatory duct leakage and weld tests in the presence of the code official, including but not limited to light tests and smoke tests, to demonstrate the integrity of the duct construction prior to the installation of any insulation that prevents visual inspection of the ductwork on all sides.
- P. Provide residue traps in kitchen hood exhaust ducts at base of vertical risers with provisions for clean out.
- Q. All roofing penetrations shall be flashed and weather sealed by the roofing manufacturer's authorized roofing contractor at this Contractor's expense. This contract shall contract with the factory authorized roofing contractor for the specific roofing system applicable to this Project. The use of an unauthorized roofing contractor may result in removal and replacement of the penetration systems at this Contractor's expense.

3.03 CLEANING

- A. Clean duct system and force air at high velocity through duct to remove accumulated dust or clean with high power vacuum machines. To obtain sufficient air, clean half the system at a time. Protect equipment which may be harmed by excessive dirt with temporary filters, or bypass during cleaning.

3.04 SCHEDULES

- A. Ductwork Material: The Contractor may use any of the following ductwork materials, at his option, provided the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected piping material is the sole responsibility of the installing Contractor.
 1. Low Velocity Supply (Heating Systems): Galvanized Steel, Aluminum, Galvanized Supply (System with Cooling Coils): Galvanized Steel, Aluminum.
 2. Return and Relief: Galvanized Steel, Aluminum.
 3. General Exhaust: Galvanized Steel, Aluminum.
 4. Outside Air Intake: Galvanized Steel.
 5. Kitchen Hood Exhaust, Type 1: Carbon Steel, Stainless Steel, Constructed per NFPA 96.
- C. Ductwork Pressure Class:
 1. Low Velocity Supply (Heating Systems): Scheduled System ESP+0.25", round up to next higher pressure class.
 2. Low Velocity Supply (Systems with Cooling): Scheduled System ESP +0.5", round up to next higher pressure class.
 3. Return and Relief: 1 inch.
 4. General Exhaust: Scheduled System ESP +1.0", round up to next higher pressure class.
 5. Outside Air Intake: 1 inch.
 6. Kitchen Hood Exhaust: See drawings for maximum fan static pressure plus 50% additional.

END OF SECTION

SECTION 233300 – AIR DUCT ACCESSORIES

PART 1 GENERAL

- 1.01 SECTION INCLUDES
 - A. Air turning devices/extractors.
 - B. Volume control dampers.
 - C. Flexible duct connections.
 - D. Duct access doors.

PART 2 PRODUCTS

- 2.01 AIR TURNING DEVICES/EXTRACTORS
 - A. Manufacturers: Kraeger; Ruskin Company; Tilus.
 - B. Multi-blade device with blades aligned in short dimension; steel or aluminum construction; with individually adjustable blades, mounting straps.
- 2.02 VOLUME CONTROL DAMPERS
 - A. Manufacturers: Louvers & Dampers, Inc.; Nalor Industries Inc.; Ruskin Company; Prefo Inc.
 - B. Fabricate in accordance with SMACNA HVAC Duct Construction Standards – Metal and Flexible, and as indicated.
 - C. Single Blade Dampers: Fabricate for duct sizes up to 6 x 30 inch.
 - D. Multi-Blade Damper: Fabricate of opposed blade pattern with maximum blade sizes 8 x 72 inch. Assemble center and edge crimped blades in prime coated or galvanized channel frame with suitable hardware.
 - E. End Bearings: Except in round ducts 12 inches and smaller, provide end bearings. On multiple blade dampers, provide oil-impregnated nylon or sintered bronze bearings.
 - F. The contractor shall provide either a mechanical or electrical cable operated system wherever dampers are located in non-accessible areas.
 1. Mechanical cable operator system shall be similar and equal to Young Regulator Company, "Bowden Cable Control" system including damper, flexible cable with casing and concealed ceiling register control.
 2. Electrically operated damper control system shall be similar and equal to United Erectek Corporation, "Power Balance" system including motor operated damper, RJ-11 plenum rated cabling and flush ceiling or wall mounted RJ-11 jack in remote plate. Include one hand held battery pack operator pack to be controlled by the Owner upon completion of the balancing.

PART 3 EXECUTION

- 3.01 INSTALLATION
 - A. Install accessories in accordance with manufacturer's instructions, NFPA 90A, and follow SMACNA HVAC Duct Construction Standards – Metal and Flexible. Duct construction and pressure class.
 - B. Provide duct access doors for inspection and cleaning before and after filters, coils, fans, automatic dampers, at fire dampers, combination fire and smoke dampers, and elsewhere as indicated. Provide minimum 8 x 8 inch size for hand access, 18 x 18 inch size for shoulder access, and as indicated. Provide 4 x 4 inch for balancing dampers only. Review locations prior to fabrication.
 - C. Location of dampers and control elements in accessible areas wherever possible to avoid access doors. Provide ceiling access doors for access to all dampers and control elements located above ceiling areas. Provide minimum 12 x 12 inch size for hand access, 18 x 18 inch size for shoulder access, and as indicated. Provide 4 x 4 inch for balancing dampers only. Review locations prior to fabrication.
 - D. Provide balancing dampers at points on supply, return, and exhaust systems where branches are taken from larger ducts as required for air balancing. Install minimum 2 duct widths from duct take-off.
 - E. Provide balancing dampers on duct take-off to diffusers, grilles, and registers, regardless of whether dampers are specified as part of the diffuser, grille, or register assembly. Do not locate dampers closer than 3 feet or 10 duct diameters from the air terminal device.
 - F. At fans and motorized equipment associated with ducts, provide flexible duct connections immediately adjacent to the equipment.

AIR PURIFICATION DEVICES

Model: PHI-PKG14-24V Specifications

LISTING: UL 1598-2008 (3rd Edition)

FACTORY UV-PHI CELL

INSTALLATION: RTU PACKAGED UNIT / BLOWER CABINET

PART 1 GENERAL

1.01 SUMMARY

- A. This section includes hydro-peroxide, Super-Oxide Ions, & Hydroxide Ions delivered via PHI technology through packaged heating and cooling units capable of supplying 100 to 3,000 CFM of supply air to the indoor space.

1.02 QUALITY ASSURANCE

- A. All models shall be UL listed and comply with safety standards UL 1598-2008 (3rd Edition) and CSA Standard C22.2 No. 250.0:2008.

1.03 WARRANTY

- A. All units shall be provided with the following standard warranties:
 1. 2-year or 18,000 hours from initial start-up. National TAB provided service plan, all parts and all UV light replacement. 18,000 hour replacement are provided/installed at no cost if National TAB is providing Renew-Cx Service after initial installation.
 2. This warranty shall not apply if:
 1. The equipment is not installed by a qualified installer per the manufacturer's installation instructions shipped with the product.
 2. The equipment is misused or neglected, or not maintained per the manufacturer's maintenance instructions.
 3. The equipment is not operated within its published capacity.

PART 2 PRODUCTS

2.01 GENERAL

2.02 HOUSING

- A. Unit(s) shall be constructed of aluminum structural pop-rivets. All metal shall be CNC bent for precise assembly.
 1. Quat Metallic Topnet
 2. UV-C bulb enclosure (24VAC input power pack)
 3. All thermostat, humidifier (if required), damper interlock and other low voltage control wiring shall be installed by the Mechanical Contractor. The Electrical Contractor will furnish only the power system connections shown on the Electrical Drawings. All other control and interlock wiring is the responsibility of the Mechanical Contractor.

END OF SECTION

SECTION 234243 – HVAC POWER VENTILATORS

PART 1 GENERAL

- 1.01 SECTION INCLUDES
 - A. Roof exhausters.
 - B. Kitchen range hood exhausters.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Greenheck, Loren Cook Company, PennBarry; CaptiveAir.

2.02 POWER VENTILATORS- GENERAL

- A. Performance Ratings: Determined in accordance with AMCA 210 and bearing the AMCA Certified Seal.
- B. Sound Ratings: AMCA 301, tested to AMCA 300, and bearing AMCA Certified Sound Rating Seal.
- C. Fabrication: Conform to AMCA 99.
- D. UL Compliance: UL listed and labeled, designed, manufactured, and tested as suitable for the purpose specified and indicated.

2.03 ROOF EXHAUSTERS AND VENTILATORS

- A. Fan Unit: Vessel or direct driven as indicated, with spun aluminum housing; resilient mounted motor; 1/2 inch mesh, 0.62 inch thick aluminum wire birdscreen; square hose to suit roof curb with continuous curb gaskets.
- B. Roof Curb: 20 inch high above the finished roof surface (compensate for roof insulation thickness as indicated) with continuous curb gaskets and aluminum construction with continuously welded seams, built-in cant strips, insulation and curb bottom, and factory installed nailer strip.
- C. Disconnect Switch: Factory wired, non-fusible, in housing for thermal overload protection.
- D. Backdraft Damper: Motor actuated (or gravity damper if depicted on design drawings), aluminum multiple blade construction, felt edged with offset hinge pin, nylon bearings, blades linked, and live voltage motor drive, power open, spring return.
- E. Shafts: Cast iron or steel, dynamically balanced, bored to fit shafts and keyed; variable and adjustable pitch motor sheave selected so required rpm is obtained with shafts set at mid-position; fan shaft with self-aligning pre-lubricated ball bearings.
- F. Kitchen hood exhausters shall conform with grease tray, ventilated double wall curb and hinged curb adapter base for cleaning. Hood exhausters shall comply with requirements of NFPA 96.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Provide shafts required for final air balance at no additional expense to the project.
- C. Secure roof and wall exhausters with minimum plated steel lag screws to roof curb or structure.
- D. Extend ducts to roof and wall exhausters into roof curb or wall structure.
- E. Counterflash curb to roof or wall opening.
- F. Install backdraft dampers (gravity or motorized as depicted on design drawings) on inlet to roof and wall exhausters.
- G. All roofing penetrations shall be flashed and weather sealed by the roofing manufacturer's authorized roofing contractor at this Contractor's expense. This contract shall contract with the factory authorized roofing contractor for the specific roofing system applicable to this project. The use of an unauthorized roofing contractor may result in removal and replacement of the penetration systems at this Contractor's expense.

END OF SECTION

SECTION 233700 – AIR OUTLETS AND INLETS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Rectangular ceiling diffusers.
- B. Perforated face ceiling diffusers.
- C. Grid core exhaust and return grilles.
- D. Wall registers and grilles.

1.02 SUBMITTALS

- A. Product Data: Provide data for equipment required for this project. Review outlets and inlets as to size, finish, and type of mounting prior to submission. Submit schedule of outlets and inlets showing type, size, location, application, accessories, and note file.

1.03 QUALITY ASSURANCE

- A. Test and rate air outlet and inlet performance in accordance with ASHRAE Std 70.
- B. Test and rate lower performance in accordance with AMCA 500-L.
- C. Code requirements shall supersede any conflicting requirements of this Section.

1.04 QUALIFICATIONS

- A. Manufacturer Specifications: Company specializing in manufacturing the type of products specified in this Section, with minimum five years of documented experience.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Tilus; Kraeger; Price Industries; Nalor Industries Inc.; Hart & Cooley; Ruskin; Greenheck.

2.02 RECTANGULAR CEILING DIFFUSERS

- A. Type: Square, adjustable pattern, stamped, multi-core, or architectural plaque diffuser to discharge air in 360 degree pattern with sectorizing baffles where indicated.
- B. Frame: Inverted T-bar type. In plaster ceilings, provide plaster frame and ceiling frame. (To allow lift-out removal of the diffuser without removal of the plaster frame.)
- C. Fabrication: Steel with baked enamel off-white finish.
- D. Accessories: Opposed blade damper and multi-louvered equalizing grid with damper adjustable from diffuser face.

2.03 PERFORATED FACE CEILING DIFFUSERS

- A. Type: Perforated face with removable face.
- B. Frame: Inverted T-bar type. In plaster ceilings, provide plaster frame and ceiling frame. (To allow lift-out removal of the diffuser without removal of the plaster frame.)
- C. Fabrication: Steel with steel frame and baked enamel off-white finish.
- D. Accessories: Opposed blade damper and multi-louvered equalizing grid with damper adjustable from diffuser face.

2.04 GRID CORE EXHAUST AND RETURN GRILLES

- A. Type: Fixed grille 1/2" x 1/2" x 1 inch louvers.
- B. Fabrication: Aluminum with factory off-white enamel finish.
- C. Frame: 1-1/4 inch margin with countersunk screw mounting.
- D. Frame: Channel type in frame for suspended grid ceiling where face size exceeds 18 x 18 inch.
- E. Damper (if specified on drawings): Integral, gang-operated, opposed blade type with removable key operator, operable from face.

2.05 WALL SUPPLY REGISTERS/GRILLES

- A. Type: Streamlined and individually adjustable blades, 3/4 inch minimum depth, 3/4 inch maximum spacing with spring or other device to set blades, horizontal face, double deflection.
- B. Frame: 1-1/4 inch margin with countersunk screw mounting and gasket.
- C. Fabrication: Steel with 20 gage minimum frames and 22 gage minimum blades, steel and aluminum with 20 gage minimum frame, or aluminum extrusions, with factory off-white enamel finish.
- D. Damper: Integral, gang-operated opposed blade type with removable key operator, operable from face.
- E. Rough Service: Provide front pivoted or welded in place blades, securely fastened to be immobile. PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Check location of outlets and inlets and make necessary adjustments in position to conform with architectural features, symmetry, and lighting arrangement.
- C. Install diffusers to ductwork with air tight connection.
- D. Provide balancing dampers on duct take-off to diffusers, and grilles and registers, despite whether dampers are specified as part of the diffuser, or grille or register assembly.
- E. Point ductwork visibly behind air outlets and inlets matte black.

END OF SECTION

SECTION 237413 – PACKAGED OUTDOOR ROOF TOP UNITS – GAS FUELED

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Packaged roof top units.
- B. Thermostat controls.
- C. Roof mounting curb and base.
- D. Economizer.
- E. Power exhaust.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Carrier Corporation; Trane Inc.; Lennox Industries; York; AAOI Incorporated.

2.02 AIR CONDITIONING UNITS

- A. General: Roof mounted units having gas burner and electric refrigeration.
- B. Description: Self-contained, packaged, factory assembled and prewired, consisting of cabinet and frame, supply fan, heat exchanger and burner, controls, air filters, refrigerant cooling coil and compressor, dry bulb economizer and power exhaust fan where indicated on the Drawings, condenser coil and condenser fan.
- C. Electrical Characteristics: As scheduled on the Drawings.
- D. Disconnect Switch: Factory mount disconnect switch on equipment.

FABRICATION

- A. Cabinet: Steel with baked enamel finish, including access panels with screwdriver operated flush cam type fasteners or doors with piano hinges with locking handles. Structural members shall be minimum 18 gage, with access doors or panels of minimum 20 gage.
- B. Insulation: One inch thick neoprene coated glass fiber with edges protected from erosion.
- C. Heat Exchangers: Aluminumized steel or stainless steel where indicated on the Drawings, of welded construction.
- D. Supply Fan: Forward curved centrifugal type, resiliently mounted with V-belt drive, adjustable variable pitch motor pulley, and rubber isolated hinge mounted motor or direct drive as indicated. Isolate complete fan assembly.
 1. Fans for units with a mechanical cooling capacity greater than or equal to 85,000 Btu/h shall have not fewer than two stages of fan control.
- E. Air Filters: 2 inch thick disposable media in metal frame.
- F. Roof Mounting Curb: Galvanized steel, channel form, insulated with gaskets, nailer strips. Provide roof curb of adequate height to provide a unit mounting height of 12" or greater above the top of the roof surface with the curb mounted to the building structure. Roof curb height must compensate for the roof insulation thickness to meet this requirement.
- G. Vibration Isolation Curb: Only when indicated on the Drawings.

2.04 BURNER

- A. Gas Burner: Induced draft or forced draft type burner with adjustable combustion air supply, pressure regulator, gas valves, manual shut-off, intermittent spark or glow coil ignition, flame sensing device, and automatic 100 percent shut-off pilot.
- B. Gas Burner Safety Controls: Energize ignition, limit time for establishment of flame, prevent opening of gas valve until pilot flame is proven, stop gas flow on ignition failure, energize blower motor, and after air flow proven and slight delay, allow gas valve to open.
- C. High Limit Control: Temperature sensor with fixed stop at maximum permissible setting, de-energize burner on excessive bonnet temperature and energize burner when temperature drops to lower safe value.
- D. Supply Fan Control: Temperature sensor sensing bonnet temperatures and independent of burner controls, with provisions for continuous fan operation.

2.05 EVAPORATOR COIL

- A. Provide copper tube aluminum fin coil assembly with galvanized drain pan and connection.
- B. Provide capillary tubes or thermostatic expansion valves for units of 6 tons capacity and less and thermostatic expansion valves and alternate row circuiting for units 7.5 tons cooling capacity and larger.

2.06 COMPRESSOR

- A. Provide hermetic or semi-hermetic compressors, 3600 rpm maximum, resiliently mounted with positive lubrication, crankcase heater, high and low pressure safety controls, motor overload protection, suction and discharge service valves and gage ports, and filter drier.
- B. Five minute timed off circuit to delay compressor start.
- C. Outdoor thermostat to energize compressor above 35 degrees F ambient.

2.07 CONDENSER COIL

- A. Provide copper tube aluminum fin coil assembly with subcooling rows and coil guard.
- B. Provide direct drive propeller fans, resiliently mounted with fan guard, motor overload protection, wired to operate with compressor.

2.08 MIXED AIR CASING

- A. Dampers: Provide outside, return, and relief dampers with damper operator and control package to automatically vary outside air quantity. Outside air damper to fail to closed position. Relief dampers may be gravity balanced.
- B. Gaskets: Provide light fitting dampers with edge gaskets maximum leakage 5 percent at 2 inches pressure differential.
- C. Damper Operator: 24 volt with gear train sealed in oil.
- D. Damper Operator, Units 7.5 Ton Cooling Capacity and Larger: 24 volt with gear train sealed in oil with spring return on.
- E. Mixed Air Control: Maintain selected supply air temperature and return dampers to minimum position on call to heating and above 75 degrees F ambient, or when ambient air temperature exceeds return air temperature.

2.09 INTEGRATED ECONOMIZER

- A. Economizer shall be furnished and installed complete with outside air and relief dampers and controls.
 1. Meet all leakage requirements of applicable energy code.
- B. Economizer shall be capable of introducing up to 100% outdoor air for minimum ventilation as well as free cooling.
- C. Damper actuator shall be electric, fully modulating design.
- D. Economizer outdoor hood shall be pre-painted and fully integrated with the unit.
- E. Dry Bulb Control: Provide dry bulb sensor capable of measuring temperature of outdoor air and controlling economizer cut-in point at the most economical level. High level cutoff shall be set per applicable energy code.
 1. Provide economizer Fault Detection and Diagnostics (FDD).

2.10 POWER EXHAUST

- A. Package shall include exhaust fan(s) and damper for units with economizer to control over-pressurization of building including integral pressure controls.

2.11 WATER LEVEL MONITORING DEVICE

- A. A water-level monitoring device shall be installed inside the primary drain pan. This device shall shut off the equipment served in the event that the primary drain becomes restricted. Devices installed in the drain line shall not be permitted.

2.12 OPERATING CONTROLS

- A. Provide low voltage, adjustable thermostat to control heater stages in sequence with delay between stages, compressor and condenser fan, and supply fan to maintain temperature setting.
 1. Include system selector switch (off-heat-auto-cool) and fan control switch (auto-on).
 2. The Mechanical Contractor shall provide all control wiring between thermostat and unit control panel and any required remote sensors.
 3. Locate thermostat in room as shown.
 - a. Electric solid state microcomputer based room thermostat, located as indicated. Provide remote sensors when indicated on the Drawings.
 1. Room thermostat shall incorporate:
 1. Automatic switching from heating to cooling.
 2. Preferential rate control to minimize overshoot and deviation from set point.
 2. Automatic Start Capabilities: Controls shall be capable of automatically adjusting the daily start time of the HVAC system in order to bring each space to the desired occupied temperature immediately prior to scheduled occupancy.
 4. Set-up for four separate temperatures per day.
 5. Instant override of set point for continuous or timed period from one hour to 31 days.
 6. Short cycle protection.
 7. Programming based on weekdays, Saturday and Sunday.
 8. Switch selection features including imperial or metric display, 12 or 24 hour clock, keypad disable, remote sensor, fan on-out, fan off.
- B. Room thermostat display shall include:
 1. Time of day.
 2. Actual room temperature.
 3. Programmed temperature.
 4. Day of week.
 5. System mode indication: heating, cooling, auto, off, fan auto, fan on.
 6. Stage (heating or cooling) operation.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with manufacturer's instructions and NFPA 90A.
- B. Mount units on factory built roof mounting curb providing watertight enclosure to protect ductwork and utility services. Install roof mounting curb level. Install roof mounting curb so that it lies near to the building structure, not on top of the roof deck or roofing materials. Provide restraints where required by local codes. Provide cooling condensate drain piping (and overflow piping if required) to approved location. Condensate piping shall be Schedule 40 galvanized steel pipe, Type L copper tube, or PVC. Contractor shall verify the selected material meets with the approval of all State, local authorities and utility company requirements. Verification of compliance of the selected piping material is the sole responsibility of the installing Contractor.
 1. Condensate piping located within the building shall be insulated with 1/2 inch thick glass fiber or flexible elastomeric cellular foam insulation. Only metallic piping systems will be allowed in return air plenum ceiling space.

END OF SECTION

SECTION 238127 – SMALL SPLIT-SYSTEM HEATING AND COOLING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Air-source heat pumps.
- B. Indoor ductless fan & coil units.
- C. Controls.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Carrier Corporation; Trane Inc.; YORK; Lennox Industries

2.02 SYSTEMS

- A. Split-System Heating and Cooling Units: Self-contained, packaged, matched factory-engineered and assembled, pre-wired indoor and outdoor units; UL listed.
 1. Size as recommended by the manufacturer. All refrigerant line sizes indicated on the Drawings are approximate and shall be adjusted as required based on the actual equipment provided to meet the manufacturer's recommended line sizing at no additional expense.
 2. Performance Requirements:
 1. Equipment performance, efficiency and accessories shall be as scheduled on the Drawings and specified herein. Inclusion in both locations is not a prerequisite to inclusion in the Contract. Equipment and accessories specified in either location shall be included in the Contract. Provide all necessary accessories and connections as required for a complete, functional system. Efficiency shall not be less than requirements of the units specified or indicated on the drawings, or the applicable local energy code.

2.03 INDOOR UNITS FOR DUCTLESS SYSTEMS

- A. Indoor Units: Self-contained, packaged, factory assembled, pre-wired unit consisting of cabinet, supply fan, evaporator coil, and controls; wired for single power connection with control transformer.
- B. Evaporator Coils: Copper tube aluminum fin assembly, galvanized or polymer drain pan sloped in all directions to drain, drain connection, refrigerant piping connections, restricted distributor or thermostatic expansion valve.
 1. Construction and Ratings: In accordance with ARI 210/240 and UL listed.

2.04 OUTDOOR UNITS

- A. Outdoor Units: Self-contained, packaged, factory assembled, pre-wired unit consisting of cabinet, with compressor and condenser.
 1. Cabinet: Steel with baked enamel finish, easily removed and secured access doors with safety interlock switches, glass fiber insulation with reflective lining.
 2. Construction and Ratings: In accordance with ARI 210/240 with testing in accordance with ASHRAE Std 23 and UL listed.
- B. Compressor: ARI 520; hermetic, 3600 rpm. (multi-speed when indicated on the Drawings) resiliently mounted integral with condenser fan with positive lubrication crankcase heater, motor overload protection, service valves and drier. Provide time delay circuit to prevent short cycling.
- C. Air Cooled Condenser: ARI 520; Aluminum fin and copper tube coil, with direct drive axial propeller fan resiliently mounted, galvanized fan guard.
- D

SYSTEM 1 FGH		TABLE 403.3.1.1 R _p PEOPLE OA (CFM/PERSON)		TABLE 403.3.1.1 R _a AREA OA (CFM/FT ²)		TABLE 403.3.1.1 OCCUPANT DENSITY (#/1000 FT ²)		TABLE 403.3.1.1.2 E _z		TABLE 403.3.1.2.3.2 E _v		
ROOM #	NAME	A _z (FT ²)	R _p	R _a	OCCUPANT DENSITY	P _z (#)	R _p P _z	R _a A _z	V _z (CFM)	V _z MAX SUPPLY (CFM)	V _z MIN SUPPLY (CFM)	Z _o
101	QUEUING AREA	184	7.5	0.12	15	4	30	22	52	86	250	0.260
102	DINING ROOM	352	7.5	0.18	20	67	503	121	874	862	2500	0.307
109	CORRIDOR	55	0.0	0.06	0	0	0	3	3	4	50	0.083
110	MENS RESTROOM	113	0.0	0.00	0	0	0	0	0	0	100	0.000
111	WOMENS RESTROOM	150	0.0	0.00	0	0	0	0	0	0	100	0.000
		1,583				71	533	197	729	912	3000	0.307

OUTDOOR AIR CALCULATIONS PER EQUATION 4-1:

SYMBOL	VALUE	DESCRIPTION
P _s	71	SYSTEM POPULATION
S _{Pz}	71	ZONE POPULATION
D	1.00	OCCUPANT DIVERSITY
V _{ou}	729	UNCORRECTED OUTDOOR AIR INTAKE
Z _p (max)	0.337	ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)
E _v	0.81	SYSTEM VENTILATION EFFICIENCY
S _{Vpz}	3000	ZONE PRIMARY AIRFLOW
V _{ot}	807	CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM
V _{at}	800	DESIGN OUTDOOR AIRFLOW RATE, CFM

SYSTEM 2 BOH		TABLE 403.3.1.1 R _p PEOPLE OA (CFM/PERSON)		TABLE 403.3.1.1 R _a AREA OA (CFM/FT ²)		TABLE 403.3.1.1 OCCUPANT DENSITY (#/1000 FT ²)		TABLE 403.3.1.1.2 E _z		TABLE 403.3.1.2.3.2 E _v		
ROOM #	NAME	A _z (FT ²)	R _p	R _a	OCCUPANT DENSITY	P _z (#)	R _p P _z	R _a A _z	V _z (CFM)	V _z MAX SUPPLY (CFM)	V _z MIN SUPPLY (CFM)	Z _o
103	FRONT OF HOUSE	293	7.5	0.12	15	5	38	35	73	91	250	0.260
104	COLDLINE	232	5.0	0.06	5	3	15	14	29	36	675	0.054
106	COLDLINE	314	7.5	0.12	20	7	53	36	90	113	1500	0.075
107	BOH	385	7.5	0.12	20	8	60	46	108	132	675	0.198
108	DISHWASH AREA	256	7.5	0.12	20	8	46	31	76	95	1400	0.088
108	MANAGERS OFFICE	78	5.0	0.06	5	2	10	5	15	18	350	0.052
		1,583				31	220	168	388	485	4850	0.383

OUTDOOR AIR CALCULATIONS PER EQUATION 4-1:

SYMBOL	VALUE	DESCRIPTION
P _s	31	SYSTEM POPULATION
S _{Pz}	31	ZONE POPULATION
D	1.00	OCCUPANT DIVERSITY
V _{ou}	388	UNCORRECTED OUTDOOR AIR INTAKE
Z _p (max)	0.363	ZONE PRIMARY OUTDOOR AIR FRACTION (MAXIMUM)
E _v	0.79	SYSTEM VENTILATION EFFICIENCY
S _{Vpz}	4850	ZONE PRIMARY AIRFLOW
V _{ot}	483	CODE REQUIRED OUTDOOR AIRFLOW RATE, CFM
V _{at}	2,500	DESIGN OUTDOOR AIRFLOW RATE, CFM

1 OUTSIDE AIR CALCULATIONS

RTU/ACU CONTROL MATRIX			
SETPOINT/CONTROL	RTU-1 DINING	RTU-2 KITCHEN	FC-1 OFFICE
SETPOINTS			
COOLING - OCCUPIED SETPOINT	75 F	75 F	75 F
COOLING - UNOCCUPIED SETPOINT	80 F	80 F	80 F
HEATING - OCCUPIED SETPOINT	70 F	70 F	70 F
HEATING - UNOCCUPIED SETPOINT	60 F	60 F	60 F
ECONOMIZER UPPER LIMIT SETPOINT	65 F	65 F	NA
ACCESSORIES			
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT	YES	YES	YES
REMOTE TEMPERATURE SENSOR	YES	YES	NO
MOTORIZED OUTDOOR AIR DAMPER	YES	YES	YES
INTEGRATED ECONOMIZER	YES	YES	NO
ECONOMIZER FAULT DETECTION	YES	YES	NO
BAROMETRIC RELIEF	YES	NO	NO
POWERED EXHAUST RELIEF	NO	YES	NO
DEHUMIDIFICATION (HOT GAS REHEAT)	YES	YES	NO
SUPPLY FAN			
ON DURING OCCUPIED MODE	YES	YES	YES
VARIABLE VOLUME - MODULATE FAN SPEED	YES	YES	YES
SAFETIES AND INTERLOCKS			
RETURN AIR SMOKE DETECTOR	YES	YES	NO
LOW LIMIT FREEZESTAT	YES	YES	YES
FIRE ALARM CONTROL PANEL INTERLOCK	YES	YES	YES
KITCHEN EXHAUST SYSTEM INTERLOCK	YES	YES	YES

AIR BALANCE SCHEDULE						
EQUIPMENT TAG	SUPPLY AIRFLOW (CFM)	OUTDOOR AIRFLOW (CFM)	RETURN AIRFLOW (CFM)	EXHAUST AIRFLOW (CFM)	OA/SA (%)	REMARKS
RTU-1	3,500	900	2,600		26%	
RTU-2	4,000	2,500	1,500		63%	
FC-1	350	0	350		0%	
EF-1				1,430		Hood-1
EF-2				1,415		Hood-2
EF-3				300		
TOTAL	7,850	3,400	4,450	3,145		
RESULTING BUILDING PRESSURIZATION = 255 CFM						
PRESSURIZATION PERCENTAGE = 3.2 %						

CARRIER EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. CONTACT CARRIER CORPORATION FOR PROPOSALS: KEN REVILLA, CARRIER RETAIL STRATEGIC ACCOUNTS, EMAIL: KEN.REVILLA@CARRIER.COM, PHONE: (954) 218-0070

- COOLER VOLUME: 700 CUBIC FT
- FREEZER VOLUME: 240 CUBIC FT
- REFRIGERANT TYPE - R404
- POUNDS OF REF. IN SYSTEM:
 - 20 POUNDS TOTAL / NOT TO EXCEED, FINAL EXACT AMOUNT TO BE DETERMINED BY REFRIGERATION INSTALLER
 - (APPROX.)
 - #1A COIL 1.34
 - #1B CONDENSER 2.90
 - #1C COIL 1.06
 - #1D 2.10
 - #1E LINES - 3.70 TYP.
- HP OF CONDENSERS:
 - COOLER 0.75 HP
 - FREEZER 1.5 HP
- LOCATION OF CONDENSERS: PER MEP & STRUCTURAL ROOF PLANS

2 COOLER/FREEZER INFORMATION

UV SYSTEMS												
UNIT NO.	PLACEMENT	PHI CELL MODEL #	UV/CELL SIZE	RANGE	INDOOR PPM TARGET	SIZE	TRANSFORMER	POWER	IN-VOLT	OUT-VOLT	MCA	WEIGHT (LBS.)
RTU-B4	BLOWER CABINET	PHI-PKG14-24V	14"	3,000-8000 CFM	< 0.02 PPM	2.25"W x 19.5"L x 1.75"D	SHIP LOOSE	11W	115 VAC	24 VAC	0.50A	2 LBS
RTU-B5	BLOWER CABINET	PHI-PKG14-24V	14"	3,000-8000 CFM	< 0.02 PPM	2.25"W x 19.5"L x 1.75"D	SHIP LOOSE	11W	115 VAC	24 VAC	0.50A	2 LBS

DIFFUSERS, GRILLES AND REGISTERS							
MARK	SERVICE	LOCATION	CEILING TYPE	MOUNTING TYPE	MANUFACTURER	MODEL NUMBER	REMARKS
D-1	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	TMSA XX 24x24 3 26	[1,2,6]
D-2	SUPPLY	CEILING	AC TILE	LAY-IN	TITUS	PAR XX 24x24 3 26	[1,2,6]
D-3	SUPPLY	CEILING	GYP. BOARD	LAY-IN	TITUS	OMNI XX 12x12 3 26	[1,2,4,6]
D-4	SUPPLY	VARIABLE	NA	SURFACE	TITUS	300RL X X 1 26	[1,5-7]
G-1	EXHAUST	CEILING	GYP. BOARD	SURFACE	TITUS	50F X X 3 26	[1,3,5-7]
G-2	RETURN	CEILING	AC TILE	LAY-IN	TITUS	50F X X 3 26	[1,3,5,6]

REMARKS:
 1. TITUS IS THE BASE OF DESIGN. KRUEGER, PRICE, NAILOR, CARNES ARE EQUAL. NO EXCEPTIONS.
 2. SEE PLAN FOR NECK SIZE.
 3. PROVIDE 1/2" X 1/2" X 1" CORE.
 4. PROVIDE WITH MODEL TRM FRAME.
 5. SEE PLAN FOR SIZE.
 6. DIFFUSERS SHALL BE FINISHED TO MATCH CEILING/WALL/EXPOSED DUCT COLOR. COORDINATE WITH ARCHITECT.
 7. PROVIDE DIFFUSERS AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.

ROOF TOP UNITS															
MARK	COOLING		HEATING		SUPPLY AIR (CFM)	EXT. S.P. (IN)	ELECTRICAL				WEIGHT (LBS)	SEER /EER	MODEL NUMBER	REMARKS	
	SEN (MBH)	TOT (MBH)	IN (MBH)	OUT (MBH)			FAN BHP	VOLT	PH	MCA					MOCOP
RTU-1	-	-	-	-	-	-	-	-	-	-	-	-	-	CAPTIVEAIRE	[1-2]
RTU-2	-	-	-	-	-	-	-	-	-	-	-	-	-	CAPTIVEAIRE	[1-2]

COOLING CAPACITIES ARE BASED ON AHRI STANDARD 210/240 OR 340/360: 80F DB/ 67F WB INDOOR ENTERING AIR TEMPERATURE, 95F DB AIR ENTERING OUTDOOR FAN. SCHEDULED UNIT MAY DIFFER FROM AHRI STANDARD CFM.

REMARKS:
 1. PROVIDE EQUIPMENT WITH SCOR GREATER THAN THE AVAILABLE FAULT CURRENT AT THE EQUIPMENT OR UPSTREAM PANELBOARD. REFER TO THE ELECTRICAL ONE LINE DIAGRAM AND PANEL SCHEDULES FOR AVAILABLE FAULT CURRENT AT UPSTREAM PANELBOARD.
 2. REFERENCE CAPTIVEAIRE DRAWINGS FOR ADDITIONAL INFORMATION.

AIR SOURCE HEAT PUMPS													
MARK	LOCATION	SERVES	NOMINAL COOL (TONS)	HEATING AT 47F (MBH)	ELECTRICAL				HSPF /COP	MANUFACTURER	MODEL NUMBER	REMARKS	
					VOLT	PH	MCA	MOCOP					
ASHP-1	ROOF	FC-1	3/4	10.0	208	1	15.0	15	205/130	108/283	CARRIER	38MAR009	[1]

REMARKS:
 1. PROVIDE EQUIPMENT WITH SCOR GREATER THAN THE AVAILABLE FAULT CURRENT AT THE EQUIPMENT OR UPSTREAM PANELBOARD. REFER TO THE ELECTRICAL ONE LINE DIAGRAM AND PANEL SCHEDULES FOR AVAILABLE FAULT CURRENT AT UPSTREAM PANELBOARD.

DUCTLESS SPLIT SYSTEMS														
MARK	COOLING		HEATING		SUPPLY AIR (CFM)	FAN (WATT)	ELECTRICAL				SEER /EER	HSPF /COP	CARRIER MODEL NUMBER	REMARKS
	NOMINAL (TONS)	TOT (MBH)	SEN (MBH)	OUT (MBH)			VOLT	PH	MCA	MOCOP				
FC-1	3/4	11.73	8.79	10.00	350	45	208	1	0.2	N/A	20.5/13.0	40MBC009	[1,2]	




REMARKS:
 1. PROVIDE CONDENSATE PUMP.
 2. INDOOR UNIT POWER PROVIDED FROM OUTDOOR UNIT.

EXHAUST FANS													
MARK	LOCATION	SERVICE	AIRFLOW (CFM)	EXTERNAL STATIC (IN H2O)	MOTOR DATA				RPM	MANUFACTURER	MODEL NUMBER	REMARKS	
					SONES	FAN (HP)	VOLT	PH					
EF-1	ROOF	-	-	-	-	-	-	-	-	-	-	CAPTIVEAIRE	[4]
EF-2	ROOF	-	-	-	-	-	-	-	-	-	-	CAPTIVEAIRE	[1-3]
EF-3	ROOF	RESTROOMS	300	0.50	7.1	1/8	115	1	1,550	GREENHECK	G-095-D	[1-3]	

REMARKS:
 1. PROVIDE SOLID STATE SPEED CONTROL.
 2. PROVIDE MOTORIZED BACKDRAFT DAMPER.
 3. PROVIDE MINIMUM 12 INCH HEIGHT ROOF CURB.
 4. REFERENCE CAPTIVEAIRE SHEETS FOR ADDITIONAL INFORMATION.

AIR CURTAINS													
MARK	LENGTH (IN)	AIRFLOW (CFM)	HEATER		FANS		ELECTRICAL		MANUFACTURER	MODEL NUMBER	REMARKS		
			IN (kW)	OUT (MBH)	QTY	HP	CIRCUIT (QTY)	VOLT				PH	
AC-1	36.0	1,379	NA	NA	NA	1	1/2	1	115	1	MARS	STD236	[1-3]

REMARKS:
 1. PROVIDE AUTOMATIC DOOR SWITCH.
 2. PROVIDE UNIT MOUNTED CONTROL PANEL.
 3. VERIFY FINAL COLOR/FINISH WITH ARCHITECT.



NO.	BY	DATE	DESCRIPTION
1	AJ	2024-01-22	IFC SET
2	AJ	2024-04-15	ADDENDUM B
3	SG/AJ	2024-02-23	ADDENDUM A
4	SG/AJ	2023-12-04	PERMIT / BID SET
5	SG/AJ	2023-11-06	75% SET
6	SG/AJ	2023-04-07	DD SET



SHAKE SHACK - TOWN & COUNTRY


700 TOWN AND COUNTRY BLVD #2400
 HOUSTON, TX 77024
 SHACK #1502

IFC SET

MECHANICAL SCHEDULES

DRAWN BY: RAS
 CHECKED BY: GRS
 JOB NO: 20230037.00

M601



ETL HOOD LISTING DETAIL

EXHAUST CFM = LENGTH OF HOOD X CFM/LIN.FT. (LOAD)

SUPPLY CFM = EXHAUST CFM X PERCENTAGE REQUIRED

TOTAL DUCT AREA (sq. in.) = 144 X (CFM)²

DUCT LENGTH = DUCT WIDTH

• CAPTIVEAIRE HOODS FOR DUCT SIZES ARE CALCULATED USING AN EXHAUST VELOCITY OF 1500 FPM AND A SUPPLY VELOCITY OF 1000 FPM.

CAPTIVEAIRE HOODS BUILT IN COMPLIANCE WITH:

UL TYPE 1 TYPE III LISTED UNDER ETL File number 3054804-001/002

UL TYPE 1 TYPE III LISTED UNDER ETL File number 3054804-001/002

CALCULATIONS UTILIZED

CAPTIVEAIRE HOODS BUILT IN COMPLIANCE WITH:

UL TYPE 1 TYPE III LISTED UNDER ETL File number 3054804-001/002

BUILDING CODES

CAPTIVEAIRE HOODS HAVE OPTIONAL CLEARANCE REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:

MATERIAL CLEARANCE REDUCTION SYSTEM

NON-COMBUSTIBLE NONE REQUIRED

LIMITED-COMBUSTIBLE 3" UNINSULATED STANDOFF

COMBUSTIBLE 1" INSULATED STANDOFF

CLEARANCE TO COMBUSTIBLES

INSTALLATION

- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTORS.
- ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
- HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
- ALL CONNECTIONS FROM CAPTIVEAIRE HOOD PER MECHANICAL CONTRACTOR'S PLANS.
- COOKING EQUIPMENT TO SHUT OFF IN EVENT OF FIRE.
- EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
- ALL LIGHT FIXTURES SHOWN INSTALLED BY CAPTIVEAIRE ARE FACTORY PREWIRED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES ARE BY ELECTRICAL CONTRACTOR.
- LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
- SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
- INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY, INTEGRATION, AND ADMINISTRATION OF CODE REQUIREMENTS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.

BALANCE

- KITCHEN HOODS MUST BE BALANCED WITH KITCHEN.
- KITCHEN SHALL BE NEGATIVE WITH RESPECT TO DINING AREA.
- RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.

ADDITIONAL



- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
- SIGNED AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE RECEIVED BY THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

GENERAL NOTES

FILTER COLLECTION EFFICIENCY

CapriveAir Captrate Solo Filter

ETL Listed Grease Extracting Filters Made From 430 Stainless Steel



FOR QUESTIONS, CALL THE
Eastern PA Mechanical
REGION 108
PHONE: (267) 504-4126
EMAIL: reg108@captiveaire.com

HOOD INFORMATION - JOB#5963893






HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST PLENUM RISER(S)				HOOD CONSTRUCTION	HOOD CONFIG		
										WIDTH	LENG	HEIGHT	DIA		CFM	VEL	SP
1	Hood-Right	5430 ND-2	CAPTIVEAIRE	8' 2"	450 DEG	I	MEDIUM	175	1429	10'	13'	4'	1429	1583	-0.530'	430 SS WHERE EXPOSED	RIGHT ALDNE
2	Hood-Left	5430 ND-2	CAPTIVEAIRE	8' 1"	450 DEG	I	MEDIUM	175	1415	10'	13'	4'	1415	1567	-0.519'	430 SS WHERE EXPOSED	LEFT ALDNE

HOOD INFORMATION

HOOD NO	TAG	FILTER(S)				LIGHT(S)				UTILITY CABINET(S)				FIRE SYSTEM PIPING	HOOD HANGING WEIGHT		
		TYPE	QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE	TYPE	SIZE			ELECTRICAL MODEL #	SWITCHES QUANTITY
1	Hood-Right	CAPTRATE SOLO FILTER	6	20"	16"	85% SEE FILTER SPEC	3	RECESSED ROUND	NO	RIGHT	12"x54"x30"	TANK FS	4.0/4.0/4.0			YES	891 LBS
2	Hood-Left	CAPTRATE SOLO FILTER	6	20"	16"	85% SEE FILTER SPEC	3	RECESSED ROUND	NO							YES	410 LBS


HOOD OPTIONS

HOOD NO	TAG	OPTION
1	Hood-Right	FIELD WRAPPER 12.00' HIGH FRONT, RIGHT. RISER SENSOR INSTALL 6IN PLEN. RIGHT WIDE VERTICAL END PANEL 42" TOP WIDTH, 36" BOTTOM WIDTH, 80" HIGH INSULATED 430 SS.
2	Hood-Left	FIELD WRAPPER 12.00' HIGH FRONT. LEFT END STANDOFF (FINISHED) 1" WIDE 54" LONG INSULATED. RISER SENSOR INSTALL 6IN PLEN. LEFT WALL AS END PANEL.



REVISIONS



NO.	DESCRIPTION	DATE
1		
2		
3		
4		



Eastern PA Mechanical
PO Box 2500, Union Ave, Belle Cymrud, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg108@captiveaire.com


Shake Shack - Town and Country Houston, TX
HOUSTON, TX, 77024

DATE: 4/20/2023
DWG #: 5963893
DRAWN BY: joe.shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING
SHEET NO. 1



SEAL SIGNATURE:

NO.	BY	DATE	DESCRIPTION
1	AJ	2024-01-22	IFC SET
2	AJ	2024-04-15	ADDENDUM B
3	ASG/AJ	2024-02-23	ADDENDUM A
4	SR/AJ	2023-12-04	PERMIT / BID SET
5	SR/AJ	2023-11-06	75% SET
6	RAS	2023-04-07	DO SET



SHAKE SHACK - TOWN & COUNTRY
700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502


IFC SET
CAPTIVEAIRE DRAWINGS

DRAWN BY:	RAS
CHECKED BY:	GRS
JOB NO:	2023037.00

M701


1" LAYER OF INSULATION FACTORY INSTALLED IN 100' END STANDOFF MEETS 0' REQUIREMENTS CLEARANCE TO COMBUSTIBLE SURFACES.

INSTALLER MUST CONFIRM HOOD IS INSTALLED SUCH THAT THE SPECIFIED WALL, ACTING AS AN END PANEL, IS MATED TIGHT TO THE CORRECT END OF HOOD TO ACHIEVE A REDUCED MINIMUM EXHAUST CFM LISTING. NON-COMPLIANCE WILL NULLIFY THE ETL LISTING, VOID THE MANUFACTURER'S WARRANTY, AND HOLD THE CONTRACTOR LIABLE FOR ANY AND ALL LOSSES, COSTS, AND EXPENSES RELATED TO THE NON-COMFORMANCE OF THE MANUFACTURER'S SPECIFIED INSTRUCTION. THE WALL, ACTING AS AN END PANEL, MUST EXTEND NO LESS THAN 20" FROM THE INTERSECTING WALL ON WHICH HOOD IS MOUNTED AND MUST EXTEND NO LESS THAN 20" UNDER BOTTOM OF HOOD TO BE ELIGIBLE FOR REDUCED MINIMUM EXHAUST CFM LISTING.




PLAN VIEW - HOOD #2 (Hood-Left)
8' 1.00" LONG 5430ND-2

PLAN VIEW - HOOD #1 (Hood-Right)
8' 2.00" LONG 5430ND-2




SECTION VIEW - MODEL 5430ND-2
HOOD - #2 (Hood-Left)



SECTION VIEW - MODEL 5430ND-2
HOOD - #1 (Hood-Right)

REVISIONS	
DESCRIPTION	DATE



Eastern, P.A. Mechanical
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 504-4126 EMAIL: reg108@captiveme.com

Shake Shack-Town and Country Houston, TX
HOUSTON, TX, 77024

DATE: 4/20/2023
DWG.#: 5963893
DRAWN BY: Joe.shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING
SHEET NO. 2

Bergmeyer

LA 800 South Figueroa St. Los Angeles, CA 90017
CO 875 N High St. Columbus, OH 43215
BOS 51 Shilpa St. Boston, MA 02210
617.542.1025 980.900.8887 www.bergmeyer.com

Schnackel engineers

MEPE ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.361.7680

SEAL SIGNATURE

NO.	BY	DATE	DESCRIPTION
1	AJ	2024-01-22	IFC SET
2	AJ	2024-04-15	ADDENDUM A
3	SG/AJ	2024-02-23	ADDENDUM B
4	SG/AJ	2023-12-04	PERMIT / BID SET
5	SG/AJ	2023-11-06	75% SET
6	RAS	2023-04-07	DD SET

SHAKE SHACK

SHAKE SHACK - TOWN & COUNTRY

700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET

CAPTIVEAIRE DRAWINGS

DRAWN BY:	RAS
CHECKED BY:	GRS
JOB NO:	20230037.00

M702

FIRE SYSTEM INFORMATION - JOB#5963893

FIRE SYSTEM NO	TAG	TYPE	SIZE	FLOW POINTS	INSTALLATION	
					SYSTEM	LOCATION ON HOOD
1		TANK FS	4.0/4.0/4.0	51	FIRE CABINET RIGHT	RIGHT, HOOD 1

GAS VALVE(S)

FIRE SYSTEM NO	TAG	TYPE	SIZE	SUPPLIED BY
1		SC ELECTRICAL	2,000	CAPTIVEAIRE SYSTEMS

NOTES

- FIELD PIPE DROPS AS SHOWN PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
- FIELD INSTALLED DROP: FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
- SHIP LOOSE DROP: FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
- RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVING, SALAMANDERS, ETC.
- OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
- IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
- FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.

- APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.

- THIS FIRE SYSTEM COMPLIES WITH U.L. 300 REQUIREMENTS.

- QL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS



JOB #: 5963893.
JOB NAME: SHAKE SHACK-1502-TOWN AND COUNTRY HOUSTON, TX.

SYSTEM SIZE: TANK-SP-3 TOTAL FP REQUIRED: 51.
HOOD # 1 8' 2.00' LONG x 54" WIDE x 30" HIGH.
RISER # 1 SIZE: 10' x 13'.
HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.
HOOD # 2 8' 1.00' LONG x 54" WIDE x 30" HIGH.
RISER # 1 SIZE: 10' x 13'.
HOOD # 2 METAL BLOW-OFF CAPS INCLUDED.

- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

LEGEND - FIRE CABINET TANK SYSTEM

- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.



REVISIONS	
DESCRIPTION	DATE

CAPTIVEAIRE

Eastern, PA Mechanical
PO Box 2350, 1 Union Ave, Erie Cymyrd, PA 16504 PHONE: (814) 504-4178 EMAIL: rsg108@captiveaire.com

Shake Shack-1502-Town and Country Houston, TX
HOUSTON, TX, 77024

DATE: 4/20/2023
DWG.#: 5963893
DRAWN BY: Joe.shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING
SHEET NO. 3

Bergmeyer

800 South Figueroa St.
Los Angeles, CA 90017
213.337.1090

51 Shilpa St.
Boston, MA 02210
617.542.1025
980.900.8887

Schnackel engineers

MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.361.7680

SEAL SIGNATURE

GREGORY ROY SCHNACKEL
84119
Date: 07/19/24
CSA # F-095125

NO.	BY	DATE	DESCRIPTION
1	AJ	2024-01-22	IFC SET
2	AJ	2024-04-15	ADDENDUM A
3	AS/AJ	2024-02-23	ADDENDUM B
4	AS/AJ	2023-12-04	PERMIT / BID SET
5	SR/AS	2023-11-06	75% SET
6	RAS	2023-04-07	DO SET

SHAKE SHACK

SHAKE SHACK - TOWN & COUNTRY

700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET

CAPTIVEAIRE DRAWINGS

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 2023037.00

M703

EXHAUST FAN INFORMATION - JOB#5963893

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	MANUFACTURER	CFM	ESP	RPM	MOTOR ENCL.	HP	BHP	PHASE	VOLT	FLA	DISCHARGE VELOCITY	WEIGHT (LBS)	SDNES
1	KEF-1	1	DUB5HFA	CAPTIVEAIRE	1429	1.000	1255	DDP	0.750	0.3570	3	460	1.3	452 FPM	100	9.8
2	KEF-2	1	DUB5HFA	CAPTIVEAIRE	1415	1.000	1251	DDP	0.750	0.3540	3	460	1.3	448 FPM	100	9.7

FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	KEF-1	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FOR GREASE DUCTS
		1	LOAD REACTOR MOUNTED IN FAN
		1	2 YEAR PARTS WARRANTY
2	KEF-2	1	GREASE BOX
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FOR GREASE DUCTS
		1	LOAD REACTOR MOUNTED IN FAN
		1	2 YEAR PARTS WARRANTY



FAN ACCESSORIES

FAN UNIT NO	TAG	EXHAUST				SUPPLY		
		GREASE CUP	GRAVITY DAMPER	WALL MOUNT	SIDE DISCHARGE	GRAVITY DAMPER	MOTORIZED DAMPER	WALL MOUNT
1	KEF-1	YES						
2	KEF-2	YES						

CURB ASSEMBLIES

NO	DN FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	KEF-1	36 LBS	CURB	23.000"W X 23.000"L X 20.000"H ALONG LENGTH, RIGHT HINGED.
2	# 2	KEF-1	36 LBS	CURB	23.000"W X 23.000"L X 20.000"H ALONG LENGTH, RIGHT HINGED.

FANS #1 (KEF-1), #2 (KEF-2) - DUB5HFA EXHAUST FAN



TOP VIEW

FEATURES:




- DIRECT DRIVE CONSTRUCTION (NO BELTS/PULLEYS).
- ROOF MOUNTED FANS.
- RESTAURANT MODEL.
- UL705 AND UL762 AND ULC-5645
- VARIABLE SPEED CONTROL.
- INTERNAL WIRING.
- THERMAL OVERLOAD PROTECTION (SINGLE PHASE).
- HIGH HEAT OPERATION 300°F (149°C).
- GREASE CLASSIFICATION TESTING.
- NEMA 3R SAFETY DISCONNECT SWITCH.

NORMAL TEMPERATURE TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING AIR AT 300°F (149°C) UNTIL ALL FAN PARTS HAVE REACHED THERMAL EQUILIBRIUM, AND WITHOUT ANY DETERIORATING EFFECTS TO THE FAN WHICH WOULD CAUSE UNSAFE OPERATION.

ABNORMAL FLARE-UP TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING BURNING GREASE VAPORS AT 600°F (316°C) FOR A PERIOD OF 15 MINUTES WITHOUT THE FAN BECOMING DAMAGED TO ANY EXTENT THAT COULD CAUSE AN UNSAFE CONDITION.

OPTIONS:

- GREASE BOX.
- FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FOR GREASE DUCTS.
- LOAD REACTOR MOUNTED IN FAN.
- 2 YEAR PARTS WARRANTY.



REVISIONS	
NO.	DESCRIPTION

CAPTIVEAIRE

Shake Shack-Town and Country Houston, TX
HOUSTON, TX, 77024

DATE: 4/20/2023
DWG.#: 5963893
DRAWN BY: Joe.shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING
SHEET NO. 4

Eastern, PA. Mechanical
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA. 19004 PHONE: (267) 504-4126 EMAIL: mg108@captiveaire.com

Bergmeyer
800 South Figueroa St.
Los Angeles, CA 90017
213.337.1000
51 Shilpa St.
Boston, MA 02210
617.542.1025
380.900.8887

Schnackel engineers
MEPE ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.391.7680

SEALED SIGNATURE:
GREGORY ROY SCHNACKEL
84119
Date: 07/19/24
CSA # F-05125

NO.	BY	DATE	DESCRIPTION
1	AJ	2024-07-22	IFC SET
B	AJ	2024-04-15	ADDENDUM B
A	SG/AJ	2024-02-23	ADDENDUM A
SR/AJ		2023-12-04	PERMIT / BID SET
SR/AJ		2023-11-06	75% SET
RSB		2023-04-07	DD SET

SHAKE SHACK

SHAKE SHACK - TOWN & COUNTRY

700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502


IFC SET

CAPTIVEAIRE DRAWINGS

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 2023037.00

M704

NO	TAG	PACKAGE #	LOCATION	SWITCHES		OPTION	FANS CONTROLLED					
				LOCATION	QUANTITY		FAN TAG	TYPE	Φ	HP	VOLT	FLA
1		SC-32010MA	WALL MOUNT IN SS BDX	SS WALL MOUNT BOX	1 LIGHT 1 FAN	SMART CONTROLS THERMOSTATIC CONTROL V/ RELAY ON/OFF WITH SUPPLY	KEF-1	EXHAUST	3	0.750	460	1.3
							KEF-2	EXHAUST	3	0.750	460	1.3







CAslink Monitor and Control

- Hood control panel to support communications to cloud-based Building Management System.
- Hood Control Panel to allow cloud-based Building Management System to monitor real time parameters outlined as MONITOR in the points list.
- Hood Control Panel to allow cloud-based Building Management System to control parameters outlined as CONTROL in the points list.
- Hood Control Panel to allow cloud-based Building Management System to implement SYSTEM ECONOMIZER control strategies for fully integrated Building Management.

MONITORING AND CONTROL POINTS LIST

DCV Package	Function	SC Packages	Function
Room Temperature	MONITOR	Room Temperature(s)	MONITOR
duct Temperature(s)	MONITOR	duct Temperature(s)	MONITOR
MHA Discharge Temperature	MONITOR	MHA Discharge Temperature	MONITOR
Atmospheric RTU Discharge Temperature	MONITOR	Atmospheric RTU Discharge Temperature	MONITOR
Fan Speed	MONITOR	Controler Faults	MONITOR
Fan Amperage	MONITOR	Fan Faults	MONITOR
Fan Power	MONITOR	Fan Status	MONITOR
TPF Faults	MONITOR	PCU Faults	MONITOR
Controler Faults	MONITOR	PCU Filter Chg Percentages	MONITOR
Fan Faults	MONITOR	Fire Condition	MONITOR
Fan Status	MONITOR	COSE Fwy System	MONITOR
PCU Faults	MONITOR	Building Presence	MONITOR
PCU Filter Chg Percentages	MONITOR	Fans Bulletin(s)	MONITOR & CONTROL
Fire Condition	MONITOR	Alarms Bulletin(s)	MONITOR & CONTROL
COSE Fwy System	MONITOR	Wash Button	MONITOR & CONTROL
Building Presence	MONITOR		
Fan Power Button	MONITOR & CONTROL		
Fans Bulletin	MONITOR & CONTROL		
Alarms Bulletin	MONITOR & CONTROL		
Wash Button	MONITOR & CONTROL		



REVISIONS

NO	DESCRIPTION	DATE
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		

Eastern, P.A. Mechanical
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA, 19004 PHONE: (607) 504-4128 EMAIL: info@capmech.com

Shake Shack-1502-Town and Country Houston, TX
HOUSTON, TX, 77024

DATE: 4/20/2023
DWG.#: 5963893
DRAWN BY: Joe.Shilba
SCALE: 3/4" = 1'-0"
MASTER DRAWING

SHEET NO. 5

Bergmeyer

800 South Figueroa St.
Los Angeles, CA 90017
213.337.1090

875 N High St.
Columbus, OH 43215
617.542.1025
380.900.8887

51 Shilpa St.
Bala Cynwyd, PA 19004
617.542.1025
380.900.8887

Schnackel engineers

New York • Miami • Columbus • Los Angeles • Dallas • Houston
800.621.0323 www.schnackel.com

MEPP ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402.361.7680

SEALED SIGNATURE

STATE OF TEXAS
COURT REPORTERS & VIDEO
GREGORY ROY SCHNACKEL
84119
I hereby certify that the above-named individual is duly qualified and licensed as a Professional Engineer in the State of Texas.
Date: 07/19/24
CSA # F-005125

1	AJ	2024-01-22	IFC SET
2	AJ	2024-04-15	ADDENDUM B
3	ASJA	2024-02-23	ADDENDUM A
4	SHAK	2023-12-04	PERMIT / BID SET
5	SHAK	2023-11-06	75K SET
6	SHAK	2023-04-01	DO SET

SHAKE SHACK

SHAKE SHACK - TOWN & COUNTRY




700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET

CAPTIVEAIRE DRAWINGS

DRAWN BY: RAS
CHECKED BY: GRS
JOB NO: 20230307.00

M705




One Gallon Grease Cup Installation

Instructions below outline single, or dual, one gallon grease cup installation for ND-2 hood models.

The one gallon grease cup comes as an assembly of stainless steel wall mounting bracket and one gallon cup. The mounting bracket should be installed 2" from the edge of the containment plenum and 3"-4" below the bottom of the hood.

Piping from the hood grease drain should route to the opening of the grease cup, but not into the cup, otherwise the cup will not be able to be removed and emptied.



REVISIONS		
NO.	DESCRIPTION	DATE

CAPTIVE

Eastern, PA Mechanical
 PO Box 2520, 1 Union Ave, Bala Cynwyd, PA 19004 PHONE: (267) 504-4126 EMAIL: reg108@captiveme.com

Shake Shack-Town and Country Houston, TX
 HOUSTON, TX, 77024

DATE:	4/20/2023
DWG.#:	5963893
DRAWN BY:	joe.shilba
SCALE:	3/4" = 1'-0"
MASTER DRAWING	
SHEET NO.	6

Bergmeyer

800 South Figueroa St.
 Los Angeles, CA 90017
 213.337.1090

875 N High St.
 Columbus, OH 43215
 617.542.1025
 980.900.8887

51 Shilpa St.
 Braintree, MA 02210
 617.542.1025

Schnackel
 engineers

New York • Miami • Orlando • Los Angeles • Dallas • Houston
 800-221-1025 www.schnackel.com

MEPF ENGINEER
 3035 S 72ND ST
 OMAHA NE 68124
 TEL 402.391.7680

SEAL SIGNATURE:

Gregory R. Schnackel
 84119
 Date: 07/19/24
 CCA # F-095125

1	AJ	2024-01-22	IFC SET
B	AJ	2024-04-15	ADDENDUM B
A	SG/AJ	2024-02-23	ADDENDUM A
SHAK		2023-12-04	PERMIT / BID SET
SHAK		2023-11-06	75% SET
SHAK		2023-04-07	DD SET

SHAKE SHACK

SHAKE SHACK - TOWN & COUNTRY

700 TOWN AND COUNTRY BLVD #2400
 HOUSTON, TX 77024
 SHACK #1502

IFC SET

CAPTIVEAIRE
 DRAWINGS

DRAWN BY: RAS
 CHECKED BY: GRS
 JOB NO: 20230037.00

M706



DOAS/RTU FAN SCHEDULE - JOB#5974802

FAN UNIT NO	TAG	QTY	DOAS/RTU MODEL #	FAN INFORMATION										ELECTRICAL INFORMATION										COOLING INFORMATION										REHEAT INFORMATION										GAS HEAT INFORMATION										NOTES
				MANUFACTURER	BLOWER	RETURN AIR CFM	MAX OUTSIDE AIR CFM	TOTAL CFM	WEIGHT (LBS)	ESP	HP	PHASE	VOLT	MCA	MDCP	DB	WB	DB	WB	DB	WB	DP	TOTAL	SENS.	IEER	ISMRE	DB	WB	DESIRED	MAX	MOISTURE REMOVAL RATE	GAS TYPE	INPUT BTUs	OUTPUT BTUs	TEMP RISE	REQUIRED INPUT GAS PRESSURE																		
1	RTU-1	1	CASRTU2-1300-18-10T	CAPTIVEAIRE	18MF-2-RTU	2000	1000	3000	2012	1.000	3.00	3	460	29.7A	30A	93.0°F	78.0°F	80.9°F	67.9°F	53.5°F	53.5°F	53.6°F	129.7 MBH	88.1 MBH	18.6	4.3	75.0°F	62.5°F	72.4 MBH	96 MBH	38.2 LBS/HR	NATURAL	161775	131038	40°F	7 IN. W.C. - 14 IN. W.C.	1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17																	
2	RTU-2	1	CASRTU3-1250-24-20T	CAPTIVEAIRE	24MF-3-RTU	2000	2500	4500	2826	1.000	5.00	3	460	57.1A	60A	93.0°F	78.0°F	85.1°F	71.6°F	53.2°F	53.2°F	53.3°F	263.5 MBH	155.9 MBH	18.2	6.0	75.0°F	62.5°F	110.2 MBH	129.6 MBH	95.5 LBS/HR	NATURAL	246875	199969	40°F	7 IN. W.C. - 14 IN. W.C.	1,2,3,4,5,6,7,8,9,10,11,12,13,14,16,17,18,19																	


FOR QUESTIONS, CALL THE
 Eastern Mechanical
 REGION 108
 PHONE: (267) 504-4126
 EMAIL: reg108@cpiveaire.com

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	RTU-1	1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE
		1	RTU TOTAL CFM MONITORING
		1	SHIP LODGE GAS STRAINER 3/4"
		1	SINGLE POINT ELECTRICAL CONNECTION FOR RTU, 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #28, #47, #M, OR #E2 PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE
		1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED
		1	RTU2 DOWN DISCHARGE
		1	2" NERV 13 FILTERS FOR RTU2 (QTY. 4)
		1	2" NERV 8 FILTERS FOR RTU2 (QTY. 4)
		1	DVERHEAT STAT
		1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE
		1	10 TON MODULATING COOLING OPTION, 460/480V, R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS
		1	10 TON MODULATING REHEAT OPTION - SPACE DEWPOINT CONTROL
		1	REMOTE TEMPERATURE AND HUMIDITY SPACE SENSOR
		1	RTU2 CURB DUCT HANGER
		1	VAV PACKAGE W/ MANUAL/DDC CONTROL (571 VFD INCLUDED)
		1	LOAD REACTOR MOUNTED IN FAN
		1	RTU2 DOWN RETURN
		1	RTU2 HAIL GUARD
		2	RTU-2
1	RTU ECONOMIZER - DIFFERENTIAL ENTHALPY CONTROL		
1	RTU2 ECONOMIZER BAROMETRIC RELIEF		
1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI		
1	RTU2 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX		
1	OCCUPIED SCHEDULING		
1	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS		
1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS)		
1	INLET PRESSURE GAUGE, 0-35"		
1	MANIFOLD PRESSURE GAUGE, 0 TO 10" WC, 1 FURNACE		
1	SHIP LODGE GAS STRAINER 1"		
1	SINGLE POINT ELECTRICAL CONNECTION FOR RTU, 750VA TRANSFORMER USED. IF A NON-DCV PREWIRE CONTROLS THIS UNIT, THE #28, #47, #M, OR #E2 PREWIRE OPTION MUST BE SELECTED. DOES NOT PROVIDE SUPPLY STARTER IN PREWIRE		
1	CASLINK BUILDING MONITORING SYSTEM - INTERNET OR CELLULAR CONNECTION REQUIRED		
1	LOW AMBIENT COOLING OPERATION - DOWN TO OF AMBIENT		
1	RTU3 DOWN DISCHARGE		
1	2" NERV 13 FILTERS FOR RTU3 (QTY. 4)		
1	2" NERV 8 FILTERS FOR RTU3 (QTY. 4)		
1	DVERHEAT STAT		
1	VFD FACTORY MOUNTED AND WIRED IN RTU COMMERCIAL CONTROL VESTIBULE		
1	REMOTE TEMPERATURE AND HUMIDITY SPACE SENSOR		
1	RTU3 CURB DUCT HANGER		
1	OCCUPIED SCHEDULING		
1	COMMERCIAL SMOKE DETECTOR/ALARM INTERLOCK - ALARM SUPPLIED BY OTHERS		
1	CLOGGED FILTER SWITCH - NOTIFICATION ON HMI		
1	RTU3 CONVENIENCE OUTLET (GFCI), 15 AMP - REQUIRES SEPARATE 120V CONNECTION. INCLUDES RECEPTACLE, COVER AND J-BOX		
1	HIGH AMBIENT - 20 TON MODULATING COOLING OPTION, 460/480V, R410A REFRIGERANT, VARIABLE SPEED COMPRESSOR, ECM CONDENSING FANS, USED FOR SUMMER CONDITIONS ABOVE 110F DEGREES		
1	20 TON MODULATING REHEAT OPTION - DISCHARGE DEWPOINT CONTROL		
1	RTU ECONOMIZER - DIFFERENTIAL DRY BULB CONTROL		
1	RTU3 ECONOMIZER BAROMETRIC RELIEF		
1	RTU INTAKE/RETURN DAMPER - MANUAL CONTROL VIA HMI		
1	POWERED EXHAUST FOR RTU3 - MANUAL CONTROL		
1	RTU3 DOWN RETURN		
1	RTU3 HAIL GUARD		
1	VAV PACKAGE W/ MANUAL/DDC CONTROL (571 VFD INCLUDED)		
1	LOAD REACTOR MOUNTED IN FAN		
1	5 YEAR ENTIRE UNIT PARTS WARRANTY, 10 YEAR ENTIRE UNIT PARTS WARRANTY WITH REMOTE MONITORING AND CAPTIVEAIRE SERVICE CONTRACT, 25 YEAR STAINLESS STEEL FURNACE PARTS WARRANTY (SEE ADDITIONAL DETAILS)		

NO	ON FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	RTU-1	90 LBS	CURB	49.500"W X 75.000"L X 14.000"H ALONG WIDTH, RIGHT INSULATED.
2	# 2	RTU-2	96 LBS	CURB	59.500"W X 91.000"L X 12.000"H ALONG WIDTH, RIGHT INSULATED.



REVISIONS	DESCRIPTION	DATE




Eastern PA. Mechanical
 PO Box 2520, 1 Union Ave. Bala Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg108@cpiveaire.com


Shake Shack - Town and Country Houston, TX (HVAC)
 HOUSTON, TX, 77024

DATE: 5/4/2023
 DWG.#: 5974802
 DRAWN BY: Joe.Shilba
 SCALE: 1/2" = 1'-0"
 MASTER DRAWING

SHEET NO. 1



MEPF ENGINEER
 3035 S 72ND ST
 OMAHA NE 68124
 TEL 402.391.7680



NO.	BY	DATE	DESCRIPTION
1	AJ	2024-01-22	IFC SET
2	AJ	2024-04-15	ADDENDUM B
3	AS	2024-02-23	ADDENDUM A
4	AS	2023-12-04	PERMIT / BID SET
5	AS	2023-11-06	75% SET
6	AS	2023-04-07	DO SET



SHAKE SHACK - TOWN & COUNTRY









700 TOWN AND COUNTRY BLVD #2400
 HOUSTON, TX 77024
 SHACK #1502

IFC SET


CAPTIVEAIRE DRAWINGS

DRAWN BY: RAS
 CHECKED BY: GRS
 JOB NO: 2023037.00

M707



REVISIONS	
DESCRIPTION	DATE



Shake Shack-1502-Town and Country Houston, TX(HVAC)
 HOUSTON, TX, 77024


DATE: 5/4/2023
 DWG. #: 5974802
 DRAWN BY: joe.shilba
 SCALE: 1/2" = 1'-0"
 MASTER DRAWING
 SHEET NO. 2

FAN #1 CASRTU2-I.300-18MF-10T - HEATER (RTU-1)

- NOTES:
- DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
 - DENOTES CORNER WEIGHT.
 - ROOF OPENING MUST BE 2" SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.

Bergmeyer
 LA 800 South Figueroa St. Los Angeles, CA 90017
 CO 875 N High St. Columbus, OH 43215
 BOS 51 Sleeper St. Boston, MA 02210
 980.900.8887 617.542.1025
 www.bergmeyer.com

Schnackel engineers
 New York • Miami • Orlando • Los Angeles • Dallas • Houston
 800.621.0428 www.schnackel.com
 MEPF ENGINEER
 3035 S 72ND ST
 OMAHA NE 68124
 TEL 402.361.7680



1	AJ	2024-01-22	IFC SET
B	AJ	2024-04-15	ADDENDUM B
A	SGM/AJ	2024-02-23	ADDENDUM A
SGM/AJ		2023-12-04	PERMIT / BID SET
SGM/AJ		2023-11-06	75% SET
END		2023-04-07	DD SET



SHAKE SHACK - TOWN & COUNTRY









700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET

CAPTIVEAIRE DRAWINGS

DRAWN BY: RAS
 CHECKED BY: GRS
 JOB NO: 20230037.00

M708



FAN #2 CASRTU3-1,250-24MF-20T - HEATER (RTU-2)

NOTES:

- DO NOT OBSTRUCT OUTSIDE AIR INLET, OUTSIDE AIR COIL OR OUTSIDE AIR FAN.
- DENOTES CORNER WEIGHT.
- ROOF OPENING MUST BE 2" SMALLER THAN CURB DIMENSIONS IN BOTH DIRECTIONS.

REVISIONS

NO.	BY	DATE	DESCRIPTION
1	AJ	2024-01-22	IFC SET
2	AJ	2024-04-15	ADDENDUM B
3	SGM/AJ	2024-02-23	ADDENDUM A
4	SGM/AJ	2023-12-04	PERMIT / BID SET
5	SGM/AJ	2023-11-06	75% SET
6	RAS	2023-04-07	DO SET

DATE: 5/4/2023

DWC.#: 5974802

DRAWN BY: joe.shilbo

SCALE: 1/2" = 1'-0"

MASTER DRAWING

SHEET NO. 3

Shake Shack-Town and Country Houston, TX(HVAC)
HOUSTON, TX, 77024

DATE: 5/4/2023


DWC.#: 5974802

DRAWN BY: joe.shilbo

SCALE: 1/2" = 1'-0"

MASTER DRAWING

SHEET NO. 3




Eastern PA. Mechanical
PO Box 2520, 1 Union Ave, Bala Cynwyd, PA, 19004 PHONE: (267) 504-4126 EMAIL: reg.08@captiveme.com

Bergmeyer



MEPF ENGINEER
3035 S 72ND ST
OMAHA NE 68124
TEL 402 361 7680



NO.	BY	DATE	DESCRIPTION
1	AJ	2024-01-22	IFC SET
2	AJ	2024-04-15	ADDENDUM B
3	SGM/AJ	2024-02-23	ADDENDUM A
4	SGM/AJ	2023-12-04	PERMIT / BID SET
5	SGM/AJ	2023-11-06	75% SET
6	RAS	2023-04-07	DO SET



SHAKE SHACK - TOWN & COUNTRY

700 TOWN AND COUNTRY BLVD #2400
HOUSTON, TX 77024
SHACK #1502

IFC SET

CAPTIVEAIRE DRAWINGS

DRAWN BY:	RAS
CHECKED BY:	GRS
JOB NO:	20230037.00

M709