

MECHANICAL SHEET INDEX

M001	MECHANICAL GENERAL INFORMATION
M101	MECHANICAL FLOOR PLAN
M150	MECHANICAL ROOF PLAN
M501	MECHANICAL DETAILS
M502	MECHANICAL DETAILS
M590	MECHANICAL SPECIFICATIONS
M591	MECHANICAL SPECIFICATIONS
M592	MECHANICAL SPECIFICATIONS
M601	MECHANICAL SCHEDULES
M630	MECHANICAL ENERGY CODE COMPLIANCE
M631	MECHANICAL ENERGY CODE COMPLIANCE
M701	HALTON DRAWINGS
M702	HALTON DRAWINGS
M703	HALTON DRAWINGS
M704	HALTON DRAWINGS
M705	HALTON DRAWINGS

RESPONSIBILITY MATRIX

DESCRIPTION	FURNISHED			INSTALLED			REMARKS
	GC	OWNER	LL	GC	OWNER	LL	
DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING							
23.1 HVAC DUCTWORK AND PIPING IDENTIFICATION							
HVAC DUCTWORK SYSTEM IDENTIFICATION	•			•			
PIPING SYSTEM IDENTIFICATION	•			•			
UTILITY SHUT OFF IDENTIFICATION IN KITCHEN	•			•			
VALVE TAGS AND CHART	•			•			
HVAC DAMPER IDENTIFICATION	•			•			
23.2 ROOF CURBS							
EXHAUST FAN CURBS	•			•			
ROOFTOP UNIT CURBS	•			•			
CONDENSING UNIT RAILS	•			•			
MAKE UP AIR UNIT CURBS	•			•			
KITCHEN EXHAUST FAN CURBS	•			•			
KITCHEN EXHAUST FAN CURB EXTENSIONS	•			•			
23.3 HVAC DUCTWORK SYSTEM COMPONENTS							
HVAC DUCTWORK	•			•			
GREASE DUCTWORK INSIDE TENANT SPACE	•			•			
MAKEUP AIR DUCTWORK INSIDE TENANT SPACE	•			•			
OUTSIDE AIR DUCTWORK INSIDE TENANT SPACE	•			•			
GENERAL EXHAUST AIR DUCTWORK INSIDE TENANT SPACE	•			•			
INSULATION AND FIRE WRAP	•			•			
DAMPERS	•			•			
SMOKE DETECTORS	•			•			
SUPPLY, RETURN, AND EXHAUST GRILLS AND REGISTERS	•			•			
23.4 MECHANICAL PIPING SYSTEM COMPONENTS							
WALK-IN COOLER AND FREEZER WATER COOLED CONDENSERS	•			•			1
REFRIGERANT PIPING FOR HVAC EQUIPMENT	•			•			
VALVES AND ACCESSORIES (E.G. AIR VENTS)	•			•			
23.5 HVAC EQUIPMENT							
SUPPLY FAN	•			•			
RESTROOM EXHAUST FAN	•			•			
RELIEF EXHAUST FAN	•			•			
KITCHEN EXHAUST FAN	•			•			
DUCTED AND NON-DUCTED HEATING AND COOLING UNITS	•			•			
MAKEUP AIR UNITS	•			•			
CONDENSING UNITS	•			•			
23.6 KITCHEN EXHAUST WITH FIRE SUPPRESSION SYSTEM							
HOOD CONTROL PANEL	•			•			
KITCHEN EXHAUST HOOD	•			•			
STRUCTURAL SUPPORT	•			•			
ELECTRICAL AND CONTROL WIRING	•			•			
ANSUL SYSTEM	•			•			
ANSUL WIRING AND UTILITIES CONNECTION	•			•			2
ANSUL GAS VALVE	•			•			
23.7 COMMISSIONING ACTIVITIES							
GREASE EXHAUST WATER LEAKAGE TEST	•			•			
TEST AND BALANCE (TAB) REPORT	•			•			
GENERAL NOTES:							
1. INFORMATION CONTAINED WITHIN IS BASED ON THE EXECUTED WORK LETTER DATE...							
2. REFER TO FINAL WORK LETTER FOR ALL LANDLORD / TENANT SCOPE OF WORK...							
REMARKS:							
1. WALK-IN COOLER AND FREEZER SUPPLIED BY VENDOR NO. 27. GENERAL... INSTALLATION AND FINAL CONNECTION.							
2. GENERAL CONTRACTOR TO COORDINATE AND FACILITATE SYSTEM SIGN-OFF.							

SUBMITTAL MATRIX

SUBMITTAL DESCRIPTION	Required Review Time (Business Days)		Shake Shack	Physical Sample Required	Submit for Record	Submit for Record Only
	5	X				
Diffusers, Grills & Registers	5	X		X		
Ductwork Layout (if there are significant changes in field)	5	X		X		
HVAC Equipment (if Carrier - Submitted by Owner/Vendor directly to Owner/AOR prior to construction)	5	X		X		
MEP Tests, Start-up, and Programming Reports	5	X		X		

GENERAL NEW NOTES:

- PRIOR TO SUBMITTING BID, VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH THE EXISTING CONDITIONS OF THE PROJECT. REVIEW THE GENERAL NOTES, SPECIFICATIONS AND OTHER DRAWINGS FOR ADDITIONAL REQUIREMENTS WHICH MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY ARCHITECT, ENGINEER AND/OR OWNER OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
- EXISTING CONDITIONS WERE TAKEN FROM ORIGINAL DRAWINGS AND SITE VISITS AND MAY NOT REFLECT EXACT "AS-BUILT" CONDITIONS. FIELD VERIFY EXISTING CONDITIONS PRIOR TO SUBMITTING FINAL BIDS. COORDINATE NEW WORK AND DEMOLITION WITH OTHER DISCIPLINES AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION.
- COORDINATE THE INSTALLATION OF THE MECHANICAL SYSTEMS WITH OTHER TRADES TO ENSURE A NEAT AND ORDERLY INSTALLATION. INSTALL DUCTWORK AND PIPING AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS. COORDINATE INSTALLATION OF DUCTWORK AND PIPING TO AVOID CONFLICTS WITH ELECTRICAL PANELS, LIGHTING FIXTURES, ETC. ANY MODIFICATIONS REQUIRED DUE TO LACK OF COORDINATION WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AT NO EXTRA COST TO THE OWNER.
- WHERE SHUTDOWN OF EXISTING SYSTEMS IS REQUIRED DURING NEW WORK, COORDINATE SHUTDOWN TIME AND DURATION WITH THE OWNER TO MINIMIZE DOWNTIME. NOTIFY OWNER SEVEN (7) DAYS PRIOR TO INTERRUPTION OF SERVICE.
- DURING INSTALLATION OF NEW WORK, AVOID DAMAGING EXISTING SURFACES AND EQUIPMENT TO REMAIN. REPAIR DAMAGE CAUSED DURING CONSTRUCTION AT NO EXTRA COST TO THE OWNER.
- PROVIDE TEMPORARY BARRIERS TO CONTAIN DUST AND DEBRIS RESULTING FROM THE PERFORMANCE OF THE WORK TO THE AREA WHERE WORK IS BEING PERFORMED.
- ALL MECHANICAL EQUIPMENT SHOWN ON THE MECHANICAL PLANS SHALL BE PROVIDED BY DIVISION 23 UNLESS OTHERWISE NOTED.
- NEW MECHANICAL EQUIPMENT, DUCTWORK AND PIPING ARE SHOWN AT APPROXIMATE LOCATIONS. FIELD MEASURE FINAL DUCTWORK AND PIPING LOCATIONS PRIOR TO FABRICATION AND MAKE ADJUSTMENTS AS REQUIRED TO FIT THE DUCTWORK AND PIPING WITHIN THE AVAILABLE SPACE. VERIFY THAT FINAL EQUIPMENT LOCATIONS MEET MANUFACTURER'S RECOMMENDATIONS REGARDING SERVICE CLEARANCE AND PROPER AIRFLOW CLEARANCE AROUND EQUIPMENT.
- REFER TO ARCHITECTURAL DRAWINGS FOR RELATED CONSTRUCTION DETAILS AS APPLICABLE TO THE HVAC SYSTEM. VERIFY CHASES AND PENETRATIONS SHOWN ON ARCHITECTURAL DRAWINGS THAT ARE INTENDED FOR DUCTWORK AND PIPING MEET REQUIREMENTS.
- COORDINATE LOCATION OF ROOF MOUNTED HVAC EQUIPMENT AND ROOF PENETRATIONS WITH THE ARCHITECTURAL AND STRUCTURAL DRAWINGS.
- INDOOR AIR QUALITY MEASURES. PROTECT INSIDE OF (INSTALLED AND DELIVERED) DUCTWORK AND HVAC UNITS FROM EXPOSURE TO DUST, DIRT, PAINT AND MOISTURE. REPLACE INSULATION THAT HAS BECOME WET AT ANY TIME DURING CONSTRUCTION. DRYING THE INSULATION IS NOT ACCEPTABLE. SEAL ANY TEARS OR JOINTS OF INTERNAL FIBERGLASS INSULATION. REMOVE DEBRIS FROM CEILING/RETURN AIR FLEES INCLUDING DUST. AN INDEPENDENT, PROFESSIONAL DUCT CLEANING COMPANY SHALL VACUUM CLEAN ANY DUCTWORK AND HVAC UNITS THAT WERE OPERATED DURING THE CONSTRUCTION PERIOD AFTER NEW FILTERS ARE INSTALLED AND PRIOR TO TURNING SYSTEM OVER TO THE OWNER. THE INTERNAL SURFACES AND ASSOCIATED COILS OF ANY HVAC UNITS THAT WERE OPERATED SHALL ALSO BE CLEANED.
- INSTALL DUCTWORK AND PIPING PARALLEL TO BUILDING COLUMN LINES UNLESS OTHERWISE SHOWN OR NOTED.
- OVERHEAD HANGERS AND SUPPORTS FOR EQUIPMENT, DUCTWORK AND PIPING SHALL BE FASTENED TO BUILDING JOISTS OR BEAMS. DO NOT ATTACH HANGERS AND SUPPORTS TO THE ABOVE FLOOR SLAB OR ROOF EXCEPT WHERE CONCRETE INSERTS IN CONCRETE SLABS ARE ALLOWED BY THE SPECIFICATIONS.
- COORDINATE LOCATION OF EQUIPMENT SUPPORTS WITH LOCATION OF EQUIPMENT ACCESS PANELS/DOORS TO ENABLE SERVICE OF EQUIPMENT AND/OR FILTER REPLACEMENT.
- SEAL PENETRATIONS THROUGH THE BUILDING COMPONENTS IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS. FIREPROOF PENETRATIONS THROUGH FIRE RATED COMPONENTS IN ACCORDANCE WITH U.L. REQUIREMENTS.
- COORDINATE THE EXACT MOUNTING SIZE AND FRAME TYPE OF DIFFUSERS, REGISTERS AND GRILLES WITH THE SUPPLIER TO MEET THE CEILING, WALL AND DUCT INSTALLATION REQUIREMENTS.
- ADJUST LOCATION OF CEILING DIFFUSERS, REGISTERS AND GRILLES AS REQUIRED TO ACCOMMODATE FINAL CEILING GRID AND LIGHTING LOCATIONS.
- PAINT PORTIONS OF DUCTWORK AND INSULATION THAT ARE EXPOSED TO VIEW BY THE INSTALLATION OF DIFFUSERS, REGISTERS, AND GRILLES IN CEILINGS OR WALLS FLAT BLACK. PORTIONS INCLUDE BOTH THE INTERIOR OF UNLINED DUCTWORK AND THE EXTERIOR OF DUCTWORK AND INSULATION.
- LOCATE AND SET THERMOSTATS AND TEMPERATURE SENSORS AT LOCATIONS SHOWN ON PLANS. VERIFY EXACT LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION. INSTALL DEVICES WITH TOP OF DEVICE AT MAXIMUM 48" AFF TO MEET ADA REQUIREMENTS UNLESS NOTED OTHERWISE ON PLANS. PROVIDE INSULATED BACKING FOR THERMOSTATS MOUNTED ON EXTERIOR BUILDING WALLS. INSTALL WIRING IN CONDUIT PROVIDED BY DIVISION 26. AT A MINIMUM, PROVIDE CONDUIT IN THE WALL FROM THE JUNCTION BOX TO 6" ABOVE THE CEILING.
- COORDINATE THE LOCATION AND ELEVATION OF WALL-MOUNTED DEVICES WITH PRESENTATION CABINETS, DISPLAY CABINETS, SHELVES OR OTHER COMPONENTS SHOWN ON THE ARCHITECTURAL DRAWINGS THAT ARE TO BE INSTALLED UNDER OTHER DIVISIONS. CONTRACTOR WILL NOT BE REIMBURSED FOR RELOCATION OF WALL-MOUNTED DEVICES CAUSED BY A LACK OF COORDINATION.
- PROVIDE A MANUAL BALANCING DAMPER IN EACH DUCT TAKEOFF FROM SUPPLY, RETURN, OUTDOOR AND EXHAUST AIR DUCTS.
- PROVIDE A PREFABRICATED 45 DEGREE, HIGH EFFICIENCY, RECTANGULAR/ROUND BRANCH DUCT TAKEOFF FITTING FOR BRANCH DUCT CONNECTIONS AND TAKE-OFFS TO INDIVIDUAL DIFFUSERS, REGISTERS AND GRILLES. PROVIDE WITH INTEGRAL MANUAL BALANCING DAMPER AND LOCKING QUADRANT WHERE INDICATED ON PLANS.
- BRANCH DUCTWORK TO AIR OUTLETS SHALL BE SAME SIZE AS OUTLET NECK SIZE UNLESS OTHERWISE NOTED.
- REFER TO SPECIFICATIONS FOR DUCTWORK AND PIPING INSULATION REQUIREMENTS. DUCT SIZES ON MECHANICAL PLANS INDICATE CLEAR INSIDE AIRFLOW DIMENSIONS. INCREASE SHEET METAL SIZES ACCORDINGLY TO ACCOUNT FOR THICKNESS OF DUCT LINER.
- FLEXIBLE DUCTWORK SHALL NOT EXCEED 5'-0" IN LENGTH AND SHALL BE INSTALLED AND SUPPORTED TO AVOID SHARP BENDS AND SAGGING. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- PROVIDE EQUIPMENT VENTS AND FLUES PER EQUIPMENT MANUFACTURERS RECOMMENDATIONS AND EQUIPMENT SPECIFICATIONS. KEEP PENETRATIONS THROUGH ROOF A MINIMUM OF 10'-0" FROM HVAC EQUIPMENT FRESH AIR INLETS AND 2'-0" FROM ROOF PARAPETS.
- PROVIDE TYPE I GREASE HOOD EXHAUST DUCTWORK OF MINIMUM 16 GAUGE BLACK IRON WITH LIQUID TIGHT WELDS, WITH ACCESS PANELS FOR GREASE CLEANING AS REQUIRED BY NFPA 96 AND LOCAL CODES. SLOPE DUCT BACK TOWARDS HOOD AT MINIMUM OF 1/4" PER LINEAL FOOT MAINTAINING 18" CLEARANCE TO COMBUSTIBLE MATERIALS. INSTALL GREASE DUCTS IN AN APPROVED FIRE-RATED ENCLOSURE SEPARATED FROM THE EXHAUST DUCT BY A MINIMUM OF 6" AND MAXIMUM OF 12". VENTILATE ENCLOSURE TO THE OUTSIDE AIR IF REQUIRED BY CODE. AS AN OPTION, IF APPROVED BY LOCAL CODES, PROVIDE AN APPROVED WRAP SYSTEM IN LIEU OF THE RATED DUCT ENCLOSURE SYSTEM. DUCT WRAP SYSTEM SHALL MEET UL REQUIREMENTS FOR GREASE DUCT ENCLOSURES.
- PROVIDE A NEW SET OF AIR FILTERS IN UNITS PRIOR TO TESTING, ADJUSTING AND BALANCING AND BEFORE TURNING SYSTEM(S) OVER TO OWNER.
- TEMPORARY INSTALLATIONS OF INFECTION CONTROL MEASURES DURING CONSTRUCTION SHALL BE COORDINATED WITH THE FACILITY'S INFECTION CONTROL STAFF. PRIOR TO CONSTRUCTION PROVIDE ALL REQUIRED TEMPORARY INSTALLATIONS, INCLUDING DETAILS OF THE INFECTION CONTROL MEASURES SUCH AS TEMPORARY BARRIERS AND MEMBRANES, PORTABLE EXHAUST FANS AND TEMPORARY DUCTWORK. TEMPORARY INSTALLATIONS MUST NOT HAVE A NEGATIVE IMPACT ON EXISTING SYSTEMS NOR CAUSE UNSAFE CONDITIONS. TEMPORARY INSTALLATIONS SHALL MAINTAIN ADEQUATE EGRESS AND SHALL NOT OBSTRUCT EXISTING EXITS. CREATE A FIRE HAZARD OR REDUCE REQUIRED FIRE RESISTANCE. TEMPORARY VENTILATION SYSTEMS SHALL NOT CAUSE THE AIR BALANCE OF ADJACENT ROOMS OR SPACES TO BE IMPACTED OR ALTER THE PERFORMANCE OF PERMANENT BUILDING VENTILATION SYSTEMS. AIRFLOW MEASUREMENTS SHALL BE TAKEN TO VERIFY ADJACENT ROOMS OR SPACES ARE NOT IMPACTED.

MECHANICAL SYMBOLS

STANDARD MOUNTING HEIGHT		HVAC DUCTWORK AND ACCESSORIES		PIPING SYMBOLS	
<p>48" 48"</p> <p>THERMOSTATS (USER ADJUSTABLE)/TOP OF DEVICE CONTROLS (TOP OF DEVICE)</p>		<p>LINEAR SLOT DIFFUSER</p>		<p>DIRECTION OF FLOW</p>	
<p>48" 48"</p> <p>INSULATED FLEXIBLE DUCT (MAX. 5'-0" LONG)</p>		<p>BRANCH DUCT WITH 45° RECTANGLE-ROUND BRANCH FITTING AND MANUAL VOLUME DAMPER</p>		<p>CONTROL VALVE</p>	
<p>ELBOW WITH TURNING VANES</p>		<p>BRANCH DUCT WITH BELL-MOUTH FITTING & MANUAL VOLUME CONTROL DAMPER</p>		<p>THREE-WAY CONTROL VALVE</p>	
<p>RETURN, EXHAUST, OR OUTSIDE AIR DUCT UP</p>		<p>RETURN, EXHAUST, OR OUTSIDE AIR DUCT DOWN</p>		<p>SHUTOFF VALVE</p>	
<p>SUPPLY AIR DUCT UP</p>		<p>SUPPLY AIR DUCT DOWN</p>		<p>CHECK VALVE</p>	
<p>EQUIPMENT WITH FLEXIBLE DUCT CONNECTION</p>		<p>10" (NECK SIZE) CSD-1 (TYPE) 300 CFM (CFM OF SUPPLY DIFFUSER OR REGISTER)</p>		<p>BALANCING VALVE WITH PRESSURE PORTS</p>	
<p>24x24 (NECK SIZE) CEG-1 (TYPE) 800 CFM (CFM OF EXHAUST GRILLE)</p>		<p>MANUAL VOLUME DAMPER</p>		<p>TRIPLE DUTY VALVE WITH PRESSURE PORTS</p>	
<p>DUCT MOUNTED SMOKE DETECTOR (SD=SUPPLY/RD=RETURN)</p>		<p>SQUARE TO ROUND TRANSITION</p>		<p>STRAINER</p>	
<p>ROUND DUCT TAG INDICATING DIAMETER</p>		<p>RECTANGULAR DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS.</p>		<p>STRAINER WITH BLOWDOWN VALVE</p>	
<p>FLAT OVAL DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS</p>		<p>RISER DESIGNATION</p>		<p>RELIEF / SAFETY VALVE</p>	
<p>MANUAL AIR VENT</p>		<p>MANUAL AIR VENT</p>		<p>SOLENOID VALVE</p>	
<p>PRESSURE / VACUUM SWITCH</p>		<p>PIPING SUPPORT</p>		<p>PRESSURE REDUCING VALVE</p>	
<p>CLEANOUT</p>		<p>CAP</p>		<p>GAS PRESSURE REGULATOR</p>	
<p>ELBOW UP</p>		<p>ELBOW DOWN</p>		<p>THERMOSTATIC MIXING VALVE</p>	
<p>TEE UP</p>		<p>TEE DOWN</p>		<p>PIPE ANCHOR</p>	
<p>ELBOW DOWN WITH SHUT-OFF VALVE (SOV)</p>		<p>TEE DOWN WITH SHUT-OFF VALVE (SOV)</p>		<p>EXPANSION JOINT</p>	
<p>TEE UP WITH SHUT-OFF VALVE (SOV)</p>		<p>REDUCER</p>		<p>PIPE GUIDE</p>	
<p>TEE DOWN WITH SHUT-OFF VALVE (SOV)</p>		<p>RECIRCULATION PUMP</p>		<p>F & T TRAP</p>	
<p>GAS COCK</p>		<p>P-TRAP</p>		<p>BUCKET TRAP</p>	
<p>TOP BEAM CLAMP</p>		<p>GAS COCK</p>		<p>BACKFLOW PREVENTER</p>	
<p>TRAPEZE HANGER</p>		<p>ELBOW UP</p>		<p>PRESSURE GAUGE</p>	
<p>FLEXIBLE CONNECTION</p>		<p>ELBOW DOWN</p>		<p>THERMOMETER</p>	
<p>REDUCER</p>		<p>TEE UP</p>		<p>PRESSURE AND TEMPERATURE TEST PLUG</p>	
<p>RECIRCULATION PUMP</p>		<p>TEE DOWN</p>		<p>UNION</p>	
<p>P-TRAP</p>		<p>ELBOW DOWN WITH SHUT-OFF VALVE (SOV)</p>		<p>FLANGE CONNECTION</p>	
<p>GAS COCK</p>		<p>TEE UP WITH SHUT-OFF VALVE (SOV)</p>		<p>VACUUM RELIEF VALVE</p>	
<p>TOP BEAM CLAMP</p>		<p>TEE DOWN WITH SHUT-OFF VALVE (SOV)</p>		<p>AUTOMATIC AIR VENT</p>	
<p>TRAPEZE HANGER</p>		<p>REDUCER</p>		<p>MANUAL AIR VENT</p>	
<p>FLEXIBLE CONNECTION</p>		<p>RECIRCULATION PUMP</p>		<p>PRESSURE / VACUUM SWITCH</p>	


ALL DUCT DIMENSIONS SHOWN ON DRAWINGS ARE INSIDE DIMENSIONS. REFER TO DUCTWORK SPECIFICATIONS FOR DUCTWORK INSULATION AND LINER INFORMATION.

HVAC CONTROL DEVICES

Ⓜ	HUMIDISTAT
Ⓣ	THERMOSTAT
CO	CARBON MONOXIDE SENSOR
CO2	CARBON DIOXIDE SENSOR
DP	DIFFERENTIAL PRESSURE SENSOR
FS	FLOW SWITCH
HS	HUMIDITY SENSOR
PS	PULL STATION
RT	REMOTE TESTING STATION WITH INDICATING LIGHT
SP	STATIC PRESSURE
TS	TEMPERATURE SENSOR



ZEBRA PROJECTS, INC.
14814 N KIERLAND BLVD, SUITE N 300
SCOTTSDALE, ARIZONA 85254
PHONE: 480.912.1169 zbr.global



STORE NO:
CA #1399



REVISION

Δ	DATE	DESCRIPTION
1	12/20/21	PERMIT/IBID SET
A	02/10/22	REVISION A
B	04/26/22	REVISION B
C	05/27/22	REVISION C
1	06/24/22	IFC SET
2	08/03/22	REVISION 2

STATUS:
IFC SET



08/10/2022
FIELD VERIFICATION:
The contractor shall verify all signed dimensions and location at the project site and notify Zebra Projects, Inc. of any dimensional errors, omissions or discrepancies within 48 hours of beginning of installation of any work. Do not scale these drawings.

COPYRIGHT © 2021:
Zebra Projects, Inc. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, altered or otherwise used without the written consent of Zebra Projects, Inc.


SHEET NAME:
MECHANICAL GENERAL INFORMATION

DATE: 12/18/20 PROJECT NO: 34285
DRAWN: MJW SCALE:

SHEET NO:
M001

REVISION	
DATE	DESCRIPTION
12/20/21	PERMIT/IFC SET
A 02/10/22	REVISION A
B 04/26/22	REVISION B
C 05/27/22	REVISION C
1 06/24/22	IFC SET
2 08/03/22	REVISION 2

STATUS:
IFC SET



08/10/2022
 FIELD VERIFICATION:
 The contractor shall verify all signed dimensions and location of the project site and notify Zebra Projects, INC. of any dimensional errors, or omissions or discrepancies before beginning or resuming any work. Do not scale these drawings.

COPYRIGHT © 2021:
 Zebra Projects, INC. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, disclosed or otherwise used without the written consent of Zebra Projects, INC.

SHEET NAME:
MECHANICAL FLOOR PLAN

DATE: 12/18/20 PROJECT NO: 34285
 DRAWN: MLJ SCALE: 1/4" = 1'-0"

SHEET NO:
M101

- MECHANICAL GENERAL NOTES:**
- DO NOT ROUTE ANY DUCTWORK OR PIPING ABOVE ELECTRICAL PANELS. REFER TO SHEET M001 FOR ADDITIONAL GENERAL NOTES AND REQUIREMENTS.
 - REFER TO DETAILS AND SCHEDULES SHEETS FOR FURTHER INFORMATION. MOUNT ALL THERMOSTATS AND SENSORS CONTROLLING HVAC EQUIPMENT AT 48" AFF UNLESS OTHERWISE NOTED.

- MECHANICAL PLAN NOTES:**
- TYPE I HOODS SHALL BE FURNISHED COMPLETE WITH INTERNALLY PIPED FIRE SUPPRESSION SYSTEM AND EXTERNAL FOAM SUPPLY BOTTLES WITH REMOTE PULL CONTROLS AND IN COMPLIANCE WITH NFPA 96. DIVISION 23 SHALL COORDINATE COMPLETE INSTALLATION WITH FIRE PROTECTION CONTRACTOR TO MEET APPROVAL OF LOCAL INSPECTOR AND CODE COMPLIANCE INCLUDING TESTING.
 - TYPE I GREASE HOOD EXHAUST DUCTWORK SHALL BE MINIMUM 16 GAUGE STEEL OR MINIMUM 18 GAUGE STAINLESS STEEL WITH LEAD TIGHT WELDS. INSTALL ACCESS PANELS FOR CLEANING AS REQUIRED BY NFPA 96 AND LOCAL CODES. TRANSITION GREASE DUCTWORK AS REQUIRED TO HOOD AND FAN CONNECTIONS. PROVIDE 45° MAX OFFSETS AS REQUIRED TO COORDINATE WITH STRUCTURE. PROVIDE RADIUS ELBOWS WITHOUT TURNING VANES. SLOPE HORIZONTAL GREASE DUCT BACK TOWARDS HOOD AT MINIMUM OF 1/4" PER LINEAL FOOT. GREASE DUCTS SHALL BE CONTAINED IN A UL APPROVED GREASE DUCT WRAP SYSTEM.
 - REFER TO HALTON SHEETS FOR INFORMATION ON HOOD MAKEUP AIR PLENUM.
 - MOUNT THERMOSTATS AND TEMPERATURE SENSORS ON WALL. THERMOSTATS AND SENSOR(S) SHALL BE LABELED TO MATCH THE UNIT TAG AND CORRESPOND TO THE ELECTRICAL LEGEND IN THE ELECTRICAL PANELBOARD SERVING THE EQUIPMENT. COORDINATE COLOR WITH ARCHITECT.
 - 12"X12" GREASE EXHAUST DUCT UP TO KEF-1 ON ROOF.
 - 8"X8" GREASE EXHAUST DUCT UP TO KEF-2 ON ROOF.
 - COMBINATION TEMPERATURE SENSOR AND HUMIDITY SENSOR.
 - PROVIDE SA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING. AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.
 - PROVIDE RA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING. AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.
 - INSTALL HOOD FIRE SUPPRESSION MANUAL PULL STATION. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH FIRE SUPPRESSION SYSTEM INSTALLER AND THE AUTHORITY HAVING JURISDICTION.
 - PROVIDE ANALOX AX60 OR APPROVED EQUAL CARBON DIOXIDE SENSOR WITH REMOTE ALARM REPEATER TO BE MOUNTED AT 18" AFF. PROVIDE CARBON DIOXIDE SENSOR WITH RELAY. RELAY SHALL BE INTERLOCKED WITH THE BUILDING FIRE ALARM SYSTEM. THE SENSOR SHALL BE EQUIPPED WITH A LOCAL AUDIBLE AND VISUAL ALARM. THE LOW LEVEL ALARM SHALL ACTIVATE THE LOCAL AUDIBLE AND VISUAL ALARM. THE HIGH LEVEL ALARM SHALL ACTIVATE RELAY. INSTALL SENSOR PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
 - INSTALL "DUCTMATE ULTIMATE DOOR" GREASE DUCT ACCESS PANELS FOR CLEANING IN LOCATION SHOWN AT A MINIMUM AND AS REQUIRED BY NFPA 96 AND LOCAL CODES.
 - INSTALL DUCT SMOKE DETECTOR IN SUPPLY AIR DUCT.
 - 12"X12" EXHAUST DUCT UP TO EF-1 ON ROOF.
 - CARBON MONOXIDE DETECTOR FURNISHED BY OWNER. INSTALL AT 5'-0" AFF. COORDINATE FINAL LOCATION WITH OWNER REPRESENTATIVE.
 - PROVIDE SUPPLY PLENUM BOX WITH DAMPER AND WORM GEAR OPERATOR.
 - REFRIGERANT PIPING UP TO CU-1 ON ROOF. REF 1/1M50.
 - PROVIDE COMBUSTION AIR AND EXHAUST PIPE AND ROUTE TO CONCENTRIC VENT THROUGH ROOF.
 - PROVIDE CONCENTRIC VENT MODEL NUMBER 397006.
 - MOUNT RETURN AIR DUCTWORK TIGHT TO BOTTOM OF ROOF DECK AT 17'-0" A.F.F. TERMINATE DUCT AT WALL IN DINING AREA WITH WRG1.
 - MOUNT WRG1 IN WALL CENTERED ABOVE DOOR AT 9'-0" A.F.F.
 - MOUNT BOTTOM OF DUCT 14'-2" A.F.F.
 - MOUNT BOTTOM OF DUCT 12'-8" A.F.F.
 - ROUTE DUCTWORK LEVEL, TIGHT TO STRUCTURE, AND ABOVE LIGHTS. COORDINATE WITH STORM DRAINAGE, STRUCTURAL, AND ELECTRICAL.
 - INSTALL REMOTE MOUNTED HOOD MONITORING PANEL PER MANUFACTURER'S INSTRUCTIONS.
 - INSTALL KITCHEN HOODS CENTERED OVER THE COOKLINE SO THAT THE HOOD OVERHANGS THE COOKING SURFACES BY AT LEAST 6" ON BOTH SIDES.
 - INSTALL STATIC PRESSURE SENSOR ON WALL 48" AFF.
 - LOCATE BUILDING DP SENSOR ON WALL 48" AFF.
 - INSTALL OUTDOOR STATIC PRESSURE SENSOR 10'-0" ABOVE FINISHED FLOOR. COORDINATE FINAL LOCATION WITH LANDLORD.
 - PROVIDE EA DUCT THROUGH ROOF. FULL SIZE OF UNIT OPENING. AND CONNECT TO UNIT WITH FLEXIBLE CONNECTOR. TRANSITION 45 DEGREES THROUGH ROOF CURB.

SEAL PERMANENT HVAC DUCT/EQUIPMENT STORED ONSITE BEFORE INSTALLATION PER CALGREEN 5.504.1-3.


THE USE OF HALONS OR CFCs IN THE HVAC IS PROHIBITED PER CALGREEN 5.508.1.

ALL GREASE DUCT TO BE WATER TESTED BY ENVIROMATIC AT MECHANICAL CONTRACTOR'S EXPENSE. CONTACT OWNER'S NATIONAL ACCOUNT VENDOR:

ENVIROMATIC
 DON PFLEDERER
 1.800.325.8478
 inspections@enviromatic.com

THE BUILDINGS HVAC SYSTEMS SHALL BE BALANCED BY NATIONAL TAB (NO EXCEPTIONS) AND CONTRACTED BY THE GENERAL CONTRACTOR.

CONTACT:
 WILL TURNBOUGH
 will@natatab.com
 855-682-6822 ext1704




MECHANICAL GENERAL NOTES:

- ALL VENT STACKS SHALL BE NO LESS THAN 12" FROM PARAPET, AT LEAST 10 FEET FROM OUTSIDE AIR INTAKES, AND ABOVE ROOF SURFACE 6" MINIMUM TO FULL HEIGHT OF PARAPET, WHICHEVER IS GREATER. CONTRACTOR SHALL PROVIDE BRACING AS SPECIFIED.
- COORDINATE EXACT EQUIPMENT LOCATIONS WITH OTHER TRADES PRIOR TO INSTALLATION.
- REFER TO SHEET M001 FOR ADDITIONAL GENERAL NOTES.
- REFER TO DETAILS AND SCHEDULES SHEETS FOR FURTHER INFORMATION.

MECHANICAL PLAN NOTES:

- AREA RESERVED FOR REFRIGERATION CONDENSER(S) PROVIDED BY KITCHEN EQUIPMENT CONTRACTOR. COORDINATE EQUIPMENT LOCATION AND CONDENSER INSTALLATION WITH KITCHEN EQUIPMENT CONTRACTOR.
- MAINTAIN ALL OUTSIDE AIR INTAKES A MINIMUM OF 10'-0" RADIUS FROM EXHAUST, TYPICAL.
- TURN DOWN 6"Ø INTAKE AND END OPEN OVER ROOF (MIN. 24") WITH INSECT SCREEN.
- REFERENCE PLUMBING DRAWINGS FOR CONDENSATE DRAIN ROUTING AND TERMINATION REQUIREMENTS.
- CONTRACTOR SHALL COORDINATE WITH NATIONAL TAB AND PROVIDE UV-FH INDOOR AIR PURIFICATION SYSTEM, MODEL PHI-PKG-24V. INSTALL IN UNIT BLOWER COMPARTMENT PER MANUFACTURER'S INSTRUCTIONS.
- CONTRACTOR SHALL VERIFY WITH EQUIPMENT SUPPLIER EXACT ROUTING AND SIZE OF INSULATED REFRIGERANT PIPING. SINGLE LINE SHOWN FOR CLARITY. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.




1 MECHANICAL ROOF PLAN
1/4" = 1'-0"

STORE NO:
CA #1399

SHAKE SHACK
STONETOWN GALLERIA
SAN FRANCISCO, CA

REVISION	DATE	DESCRIPTION
Δ	12/20/21	PERMIT/IFC SET
A	02/10/22	REVISION A
B	04/26/22	REVISION B
C	05/27/22	REVISION C
T	06/24/22	IFC SET
Z	08/03/22	REVISION 2

STATUS:
IFC SET




FIELD VERIFICATION:
The contractor shall verify all signed dimensions and location at the project site and notify Zebra Projects, INC. of any dimensional errors, or omissions or discrepancies online beginning or immediately any work. Do not scale these drawings.
COPYRIGHT © 2021:
Zebra Projects, INC. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, disclosed or otherwise without the written consent of Zebra Projects, INC.

SHEET NAME:
MECHANICAL ROOF PLAN


DATE: 12/18/20 PROJECT NO: 34285
DRAWN: MLJ SCALE: 1/4" = 1'-0"

SHEET NO:
M150




NOTES:
1. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR EQUIPMENT SUPPORTS, ANCHORING AND SEISMIC/WIND RESISTANCE.

16 ROOF EQUIPMENT SUPPORT RAIL DETAIL NTS




NOTES:
1. SUPPORT AND ANCHOR OUTDOOR UNITS IN COMPLIANCE WITH LOCAL SEISMIC AND WIND RESTRAINT REQUIREMENTS.
2. SEE MECHANICAL EQUIPMENT ANCHORS AND SUPPORT SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
3. REFER TO THE EQUIPMENT SCHEDULE AND MANUFACTURER'S REQUIREMENTS FOR UNIT MOUNTING HEIGHT.

15 CONDENSING UNIT SUPPORT DETAIL NTS




NOTES:
1. CUT METAL DECKING TO ALLOW CURB INSTALLATION ON STEEL FRAMING. AFTER CURB IS SET IN PLACE, TRIM REMAINING METAL DECKING AND INSTALL WITHIN CURB. TACK WELD DECKING TO SUPPORT STEEL. DO NOT WELD INTERIOR DECKING TO ROOF CURB. PROVIDE ADDITIONAL CROSS FRAMING TO SUPPORT INTERIOR DECKING AND FILL MATERIAL AS REQUIRED.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR ROOF CURBS, ANCHORING AND SEISMIC/WIND RESISTANCE.

14 ROOF CURB DETAIL NTS




NOTES:
1. EXTEND HARD METAL DUCT SO THAT MAXIMUM FLEXIBLE DUCT LENGTH DOES NOT EXCEED 5'-0". PROVIDE RIGID 90° ELBOW WHERE REQUIRED TO KEEP FLEXIBLE DUCT WITHIN 5'-0" LENGTH LIMITATION.
2. COORDINATE EXACT LENGTH AND LOCATION OF SLOT DIFFUSER WITH ARCHITECT'S REFLECTED CEILING PLAN.
3. REFER TO DIFFUSER MANUFACTURER'S INSTALLATION INSTRUCTIONS FOR EACH SCHEDULED BORDER TYPE.
4. REFER TO SPECIFICATIONS FOR FLEXIBLE DUCTWORK INSTALLATION REQUIREMENTS.

13 LINEAR SLOT DIFFUSER IN LAY-IN CEILING DETAIL NTS




NOTES:
1. ARRANGEMENT SHOWN IS SCHEMATIC, ADJUST TO SUIT FIELD CONDITIONS AND MEET LOCAL CODE.
2. PROVIDE CURB EXTENSION OF HEIGHT REQUIRED TO MOUNT FAN BASE A MINIMUM 18 INCHES ABOVE ROOF SURFACE AND DISCHARGE GREASE OUTLET A MINIMUM OF 40 INCHES ABOVE ROOF SURFACE OR ANY ADJACENT BUILDING STRUCTURE WITHIN 10 FEET OF OUTLET, WHICHEVER IS HIGHER.
3. PREFABRICATED INSULATED ROOF CURB WITH TREATED WOOD NAILER, CANT, AND STEP AS REQUIRED TO ACCOMMODATE ROOF INSULATION. FRAME AND SECURE CURB TO ROOF WITH METHOD CONSISTENT WITH ROOF CONSTRUCTION. ROOF CURBS SHALL BEAR ON ROOF STRUCTURE. REFER TO ARCHITECTURAL DRAWINGS AND CURB MANUFACTURER'S DETAILS FOR MORE INFORMATION.
4. FOR SLOPED ROOFS, PROVIDE CURB WITH DIMENSIONS CAPABLE OF COMPENSATING ROOF SLOPE TO ENSURE FAN IS INSTALLED LEVEL.
5. VENTED CURB EXTENSION. IF DOUBLE-WALL U.L. LISTED ZERO CLEARANCE GREASE DUCT IS USED, PROVIDE BLANK OFF PANELS ON INTERIOR OF CURB OPENINGS AND SEAL AIRTIGHT.


12 UPBLAST GREASE EXHAUST FAN DETAIL NTS



11 DOWNBLAST EXHAUST FAN DETAIL NTS




10 ROUND AIR DUCT OR PIPE PENETRATION THROUGH ROOF DETAIL NTS




NOTES:
1. ALL ATTACHMENTS SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS AND SHALL BE APPROVED FOR THE SPECIFIC APPLICATION.
2. COORDINATE ALL ATTACHMENTS WITH ARCHITECT AND STRUCTURAL ENGINEER.
3. REFER TO SPECIFICATIONS FOR MORE INFORMATION ON APPROVED ATTACHMENT METHODS.
4. REFER TO SPECIFICATIONS FOR REQUIREMENTS RELATING TO SEISMIC INSTALLATIONS.
5. FOR OPEN WEB JOIST STRUCTURE, CONTRACTOR MAY HANG FROM TOP CHORD AND RUN DUCT AND PIPING THROUGH WEB JOIST WHEN APPROPRIATE. ANY CONCENTRATED LOADS NOT OCCURRING AT JOIST PANEL POINTS MUST BE REVIEWED BY A STRUCTURAL ENGINEER FOR FIELD INSTALLED PANEL BRACE REQUIREMENTS.

9 HANGER UPPER ATTACHMENT DETAILS NTS




NOTES:
1. FOR REFERENCE ONLY. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
2. AT CONTRACTOR'S OPTION, A LISTED UL 1979 GREASE ACCESS DOOR PRODUCT MAY BE SUBSTITUTED FOR THE ACCESS DOOR PICTURED IN THIS DETAIL. DOOR SHALL BE RATED FOR UP TO 2,300F AND MEET NFPA98 STANDARDS. BOLTS SHALL BE LONG ENOUGH FOR DUCT WRAP SYSTEM (WHEN USED). INSTALL IN ACCORDANCE WITH MANUFACTURER'S LITERATURE.

8 GREASE DUCT CLEANOUT ACCESS DOOR DETAIL NTS




NOTES:
1. INSTALL GREASE EXHAUST AND FIRE RATED DUCT WRAP IN ACCORDANCE WITH THE MANUFACTURER'S APPROVED INSTRUCTIONS AND UL LISTED INSTALLATION DETAILS. TECHNIQUES THAT DIFFER FROM THE ABOVE METHOD ARE ACCEPTABLE IF THEY ARE UL TESTED AND APPROVED.

7 GREASE DUCT FIRE WRAP INSULATION INSTALLATION DETAIL NTS




NOTES:
1. USE THREADED ROD FOR RECTANGULAR DUCTS LARGER THAN 60" WIDE.
2. OMIT SHEET METAL SCREWS IF HANGER STRAP IS CONTINUOUS AND LOOPS UNDER ENTIRE RECTANGULAR DUCT.
3. FOR ROUND DUCTS LARGER THAN 36"x36", USE TWO HANGER RODS TO SUPPORT DUCT FROM EACH SIDE.
4. HANGERS MUST NOT DEFORM DUCT SHAPE.

6 DUCT HANGER LOWER ATTACHMENT DETAILS NTS




NOTES:
1. SUBMIT SHOP DRAWINGS OF ALL HOOD SYSTEMS TO CITY FOR APPROVAL PRIOR TO INSTALLATION.
2. TOTAL HOOD SYSTEM TO BE IN COMPLETE CONFORMANCE WITH NFPA, AND ALL LOCAL CODES AND REGULATIONS.
3. COORDINATE ALL FIRE PROTECTION SYSTEMS WITH FIRE PROTECTION CONTRACTOR WHO SHALL ALSO BE RESPONSIBLE FOR ALL PERMITS AND TESTING REQUIRED.
4. PROVIDE WRAP SYSTEM WHERE APPROVED BY LOCAL CODES IN LIEU OF RATED ENCLOSURE.
5. PROVIDE ACCESS PANELS AS REQUIRED BY LOCAL CODE AND PER PLAN.
6. HOODS SHALL EXTEND MINIMUM 6" BEYOND ALL OPEN SIDES AND FRONT EDGE OF FOOD COOKING EQUIPMENT BEING SERVED.

5 KITCHEN EXHAUST HOOD ELEVATION DETAIL NTS




NOTES:
1. ARRANGEMENT SHOWN IS SCHEMATIC, ADJUST TO SUIT FIELD CONDITIONS AND MEET LOCAL CODE REQUIREMENTS.
2. SET DAMPER TO DELIVER SCHEDULED OUTSIDE AIR FLOW.
3. REFER TO MANUFACTURER'S RECOMMENDATIONS FOR MAXIMUM CONDENSATE DRAIN LIFT HEIGHTS.
4. REFER TO MANUFACTURER'S RECOMMENDATIONS FOR HORIZONTAL CONDENSATE DRAIN LIFT CONNECTION FROM THE UNIT.

4 CEILING CASSETTE DETAIL NTS




3 DUCT MOUNTED REGISTER DETAIL NTS



NOTES:
1. FLEXIBLE DUCT LENGTH MAY NOT EXCEED 5'-0". EXTEND RIGID DUCT AS REQUIRED.
2. REFER TO SPECIFICATIONS FOR FLEXIBLE DUCTWORK INSTALLATION REQUIREMENTS.

2 HARD CEILING DIFFUSER DETAIL NTS




NOTES:
1. FLEXIBLE DUCT LENGTH MAY NOT EXCEED 5'-0". EXTEND RIGID DUCT AS REQUIRED.
2. REFER TO SPECIFICATIONS FOR FLEXIBLE DUCTWORK INSTALLATION REQUIREMENTS.

1 LAY-IN CEILING DIFFUSER DETAIL NTS

DATE	DESCRIPTION
12/20/21	PERMIT/FBID SET
A 02/10/22	REVISION A
B 04/26/22	REVISION B
C 05/27/22	REVISION C
1 06/24/22	IFC SET
2 08/03/22	REVISION 2

STATUS: IFC SET



08/10/2022

FIELD VERIFICATION:
The contractor shall verify all signed dimensions and location at the project site and notify Zebra Projects, INC. of any dimensional errors, omissions or discrepancies. (Indicate on drawings or photographs any work. Do not scale these drawings.)
COPYRIGHT © 2021:
Zebra Projects, INC. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, modified or otherwise used without the written consent of Zebra Projects, INC.

SHEET NAME: MECHANICAL DETAILS

DATE: 12/18/20 PROJECT NO: 34285
DRAWN: MLW SCALE: AS NOTED


SHEET NO: M501

STORE NO:
CA #1399

SHAKE SHACK
STONETOWN GALLERIA
SAN FRANCISCO, CA

REVISION	
DATE	DESCRIPTION
12/20/21	PERMIT/IFC SET
A 02/10/22	REVISION A
B 04/26/22	REVISION B
C 05/27/22	REVISION C
1 06/24/22	IFC SET
2 08/03/22	REVISION 2

STATUS:
IFC SET




08/10/2022
FIELD VERIFICATION:
The contractor shall verify all signed dimensions and conditions at the project site and notify Zebra Projects, Inc. of any dimensional errors, or omissions or discrepancies before beginning or fabricating any work. Do not scale these drawings.
COPYRIGHT © 2021:
Zebra Projects, Inc. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, disclosed or otherwise used without the written consent of Zebra Projects, Inc.


SHEET NAME:
MECHANICAL DETAILS

DATE: 12/18/20 PROJECT NO: 34285
DRAWN: MJW SCALE: AS NOTED


SHEET NO:
M502




① RTU-1 ONE-LINE DIAGRAM
NTS




② RTU-2 ONE-LINE DIAGRAM
NTS



③ MAU-1 ONE-LINE DIAGRAM
NTS



④ KEF-1 & KEF-2 ONE-LINE DIAGRAM
NTS



⑤ EF-1 ONE-LINE DIAGRAM
NTS

GENERAL MECHANICAL REQUIREMENTS

1. GENERAL INSTRUCTIONS

- A. GENERAL REQUIREMENTS
B. DEFINITIONS
C. PRE-BID SITE VISIT
D. MATERIAL AND WORKMANSHIP
E. MANUFACTURERS
F. COORDINATION
G. ORDINANCES AND CODES
H. PROTECTION OF EQUIPMENT AND MATERIALS
I. SUBSTITUTIONS
J. SUBMITTALS
K. ELECTRONIC DRAWINGS FILES
L. EQUIPMENT FURNISHED BY OTHERS
M. OPERATION AND MAINTENANCE INSTRUCTIONS
N. SPARE PARTS
O. TRAINING
P. WARRANTIES

2. GENERAL MATERIALS AND INSTALLATION

- A. BUILDING OPERATION
B. EXISTING EQUIPMENT REUSE AND REMOVAL
C. INCIDENTAL DAMAGE
D. CUTTING AND PATCHING
E. ROUGH-IN
F. STRUCTURAL SUPPORT SYSTEMS
G. PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS AND CURBS
H. ACCESS PANELS AND DOORS
I. PENETRATIONS
J. FIRESTOPPING
K. MOTORS AND STARTERS
L. VARIABLE FREQUENCY DRIVES
M. ELECTRICAL WIRING
N. EQUIPMENT FURNISHED BY OTHERS
O. SYSTEM TESTING, ADJUSTING, AND BALANCING
P. VIBRATION ISOLATION
Q. SEISMIC CONTROLS FOR MEFP SYSTEMS
R. AIR FILTERS
S. REFRIGERANT AND OIL IDENTIFICATION

3. DUCT INSULATION, DUCTWORK, ACCESSORIES, FLUES AND FANS

- A. DUCT INSULATION
B. DUCTWORK
C. FLEXIBLE DUCT
D. PLASTIC FLUE GAS VENTS
E. AIR DEVICES
F. CONTROL DAMPERS
G. EXHAUST AIR SYSTEMS
H. KITCHEN EXHAUST AIR SYSTEMS

4. HVAC EQUIPMENT

- A. ROOFTOP UNITS (3-25 TONS)
B. SPLIT DUCTLESS AIR-CONDITIONING SYSTEMS

5. PIPING AND PIPING SPECIALTIES

- A. REFRIGERANT PIPING AND INSULATION
B. SYSTEM EVACUATION AND CHARGING

6. TEMPERATURE CONTROLS

- A. GENERAL REQUIREMENTS
B. WIRING
C. THERMOSTAT CONTROL EQUIPMENT
D. SENSORS AND RELAYS

7. SEQUENCE OF OPERATION

- A. FAN COIL UNIT CONTROL
B. KITCHEN EXHAUST FAN CONTROL
C. MAKE-UP AIR UNIT CONTROL
D. ROOFTOP UNIT CONTROL
E. RESTROOM EXHAUST FAN (EF-1) CONTROL

8. ALTERNATIVES

- A. DESCRIPTION

9. COMMISSIONING OF MECHANICAL SYSTEM

- A. GENERAL
B. EXECUTION

Division 23: HEATING, VENTILATING AND AIR CONDITIONING

1. GENERAL INSTRUCTIONS

A. GENERAL REQUIREMENTS

Articles under Division 01 and the general and supplementary conditions of these specifications apply to this section and division. Where the requirements of this section and division exceed those of Division 01, this section and division take precedence. Become thoroughly familiar with all contents as to requirements that affect this division, section, or both. Work required under this division includes all material, equipment, appliances, transportation, services, and labor required to complete the entire system as required by the drawings and specifications, or reasonably inferred to be necessary to facilitate the function of each system as implied by the design and the equipment specified.

B. DEFINITIONS

Division: References contained in this specification follow the numbering system defined in the Construction Specifications Institute (CSI) MasterFormat 2004 Edition. Specification Divisions 01 through 33 provided with this project may reference the CSI MasterFormat 1995 Edition. The corresponding division references between the 2004 Edition and 1995 Edition are as follows:
2004 Edition 1995 Edition
1. Division 21 - Fire Suppression Division 15
2. Division 22 - Plumbing Division 15
3. Division 23 - HVAC Division 15
4. Division 24 - Electrical Division 15
5. Division 27 - Communications Division 16
6. Division 28 - Electronic Safety and Security Division 16

Furnish: "to supply and deliver to the project site, ready for unloading, unpacking, assembly, installation and similar operations."

Install: "to perform all operations at the project site including, but not limited to, the actual unloading, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, testing, commissioning, start-up and similar operations, complete, and ready for the intended use."

Provide: "to furnish and install."

Furnished by Owner (or Owner-Furnished) or Furnished by Others: "an item furnished by the Owner or under other divisions or contracts, and installed under the requirements of this division, complete and ready for intended use, including all items and services incidental to the work necessary for proper installation and operation. Include the installation under the warranty required by this division."

Engineer: Where referenced in this division, "Engineer" is the Engineer of Record and the Design Professional for the work under this division, and is a consultant to, and an authorized representative of the Architect, as defined in the General and/or Supplementary Conditions. When used in this division, Engineer means increased involvement by and obligations to the Engineer, in addition to involvement by and obligations to the Architect.

AHJ: The local code and/or inspection agency (Authority) Having Jurisdiction over the work.

NRTL: Nationally recognized testing laboratory, as defined and listed by OSHA in 29 CFR 1910.7 (e.g., UL, ETL, CSA), and acceptable to the AHJ over this project. Nationally recognized testing laboratories and standards listed are used only to represent the characteristics required and are not intended to restrict the use of other NRTLs that are acceptable to the AHJ and standards that meet the specified criteria.

Substitution: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor. Substitutions include Value Engineering proposals.

- 1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required in order to meet other Project requirements but may offer advantage to Contractor or Owner.

The terms "approved equal," "equivalent," or "equal" are used synonymously and shall mean "accepted by or acceptable to the Engineer as equivalent to the item or manufacturer specified." The term "approved" shall mean labeled, listed, or, by an NRTL, and acceptable to the AHJ over this project.

C. PRE-BID SITE VISIT

Prior to submitting bid, visit the site of the proposed work and become fully informed as to the conditions under which the work is to be done. Failure to comply with this requirement shall not be considered sufficient justification to request or obtain extra compensation over and above the contract price.

D. MATERIAL AND WORKMANSHIP

Provide new material, equipment, and apparatus under this contract unless otherwise stated herein, of best quality normally used for the purpose in good commercial practice, and free from defects. Install material and equipment in accordance with the manufacturer's installation instructions. Model numbers listed in the specifications or shown on the drawings are not necessarily intended to designate the required item, written descriptions of the item govern model numbers.

Pipe, pipe fittings, pipe specialties and valves shall be manufactured in plants located in the United States or certified to meet the specified ASTM and ANSI standards.

Work performed under this contract shall provide a neat and "workmanlike" appearance when completed, to the satisfaction of the Architect and Engineer. Workmanship shall be the finest possible by experienced mechanics. Installations shall comply with applicable codes and laws.

The complete installation shall function as designed and intended with respect to efficiency, capacity, noise level, etc. Abnormal noise caused by rattling equipment, piping, ducts, air devices, and squeaks in rotating components shall not be acceptable. Materials and equipment shall be of commercial specification grade in quality. Light duty and residential grade equipment shall not be accepted unless otherwise indicated.

Remove from the premises waste material present as a result of work, including cartons, crating, paper, stickers, and/or excavation material used in building, etc. Clean equipment installed under this contract to present a neat and clean installation at the termination of the work.

Repair or replace public and private property provided as a result of work performed under this contract to the satisfaction of authorities and regulations having jurisdiction. Provide all safety lights, guards, and warning signs required for the performance of the work and for the safety of the public.

E. MANUFACTURERS

In other articles where lists of manufacturers are introduced, subject to compliance with requirements, provide products by one of the manufacturers specified.

Where a list is provided, manufacturers are listed alphabetically and not in accordance with any ranking or preference.

Where manufacturers are not listed, provide products subject to compliance with requirements from manufacturers that have been actively involved in manufacturing the specified product for no less than 5 years.

F. COORDINATION

Coordinate work with that of other trades so that the various components of the systems are installed at the proper time, will fit the available space, and will allow proper service access to those items requiring maintenance. Components which are installed without regard to above shall be relocated at no additional cost to the Owner.

Unless otherwise indicated, the General Contractor shall provide chases and openings in building construction required for installation of the systems specified herein. Contractor shall furnish the General Contractor with information where chases and openings are required. Contractor shall keep informed as to the work of other trades engaged in the construction of the project and shall execute work in a manner as to not interfere with or delay the work of other trades.

Figured dimensions shall be taken in preference to scale dimensions. Contractor shall take his own measurements at the building, as variations may occur. Contractor shall be held responsible for errors that could have been avoided by proper checking and inspection.

Provide materials with trim that will properly fit the types of ceiling, wall, or floor finishes actually installed. Model numbers listed in the specifications or shown on the drawings are not intended to designate the required trim.

G. ORDINANCES AND CODES

Work performed under this contract shall, at a minimum, be in conformance with applicable national, state and local codes having jurisdiction. Equipment furnished and associated installation work performed under this contract shall be in strict compliance with current applicable codes adopted by the local AHJ, including any amendments and standards as set forth by the following:

- 1. National Electrical Code (NEC)
2. National Fire Protection Association (NFPA)
3. Underwriters Laboratories (UL)
4. Occupational Safety and Health Administration (OSHA)
5. American Society of Mechanical Engineers (ASME)
6. American Society of Heating, Refrigerating, and Air Conditioning Engineers (ASHRAE)
7. American National Standards Institute (ANSI)
8. American Society of Testing and Materials (ASTM)
9. California Code of Regulations, Title 24
10. Other national standards and codes where applicable.

Where the contract documents exceed the requirements of the referenced codes, standards, etc., the contract documents shall take precedence. Where conflicts between various codes, ordinances, rules, and regulations exist, comply with the most stringent.

Promptly bring all conflicts observed between codes, ordinances, rules, regulations, referenced standards, and these documents to the attention of the Architect and Engineer for final resolution. Contractor will be held responsible for any violation of the law.

Procure and pay for permits and licenses required for the accomplishment of the work herein described. Where required, obtain, pay for, and furnish certificates of inspection to Owner.

H. PROTECTION OF EQUIPMENT AND MATERIALS

Store and protect from damage equipment and materials delivered to job site. For materials and equipment susceptible to changing weather conditions, dampness, or temperature variations, store inside in conditioned spaces. For materials and equipment not susceptible to these conditions, cover with waterproof, tear-resistant, heavy tarp or polyethylene plastic as required to protect from plaster, dust, dirt, paint, water, or physical damage. Replace insulation that has become wet at any time during construction. Drying the insulation is not acceptable. Seal any tears or joints of internal fiberglass insulation. Equipment and material damaged by construction activities shall be rejected. Seal Contractor shall furnish new equipment and material of a like kind at his own expense.

Keep premises broom clean of foreign material created during work performed under this contract. Piping, equipment, etc. shall have a neat and clean appearance at the termination of the work. Remove debris from ceiling/return air plenum, including dust.

Plug, seal, or cap open ends of ductwork and piping systems while stored and installed during construction when not in use to prevent the entrance of debris into the systems. Remove temporary protection prior to starting equipment and turning the system over to the owner.

I. SUBSTITUTIONS

Materials, products, equipment, and systems described in the Bidding Documents establish a standard of required function, dimension, appearance and quality to be met by the proposed substitution. The base bid shall include only the products from manufacturers specifically named in the Bidding Documents. To request a substitution, request the Substitution Request Form from the Architect or Engineer. Complete and send the Substitution Request Form for each material, product, equipment, or system that is proposed to be substituted. The burden of proof of the merit of the proposed substitution is upon the proposer.

Unless stated otherwise in writing to the Engineer by the Contractor, Contractor warrants to the Engineer, Architect, and Owner the following:

- 1. Proposed substitution has been fully investigated and determined to meet or exceed the specified Work in all respects unless stated otherwise in the substitution request.
2. Proposed substitution is consistent with the Contract Documents and will produce indicated results, including functional clearances, maintenance service, and source of replacement materials.
3. Proposed substitution has received necessary approvals of authorities having jurisdiction.

- 4. Same warranty will be furnished for proposed substitution as for specified Work.
5. If accepted substitution fails to perform as required, Contractor shall replace substitute material or system with that originally specified and bear costs incurred thereby.
6. Coordination, installation and changes in the Work as necessary for accepted substitution will be complete in all respects.

No substitutions will be considered unless the Substitution Request Form is completed and attached with the appropriate substitution documentation. No substitution will be considered prior to receipt of bids unless written request for approval is bid has been received by the Engineer at least ten (10) calendar days prior to the date of receipt of bids.

If the proposed substitution is approved prior to the date of bids, such approval will be stated in an addendum. Bidders shall not rely upon approvals made in any other way. Verbal approval will not be given. No substitutions will be considered after the contract is awarded unless specifically provided in the contract documents.

J. SUBMITTALS

Assemble and submit for review shop drawings, material lists, manufacturer product literature for equipment to be furnished, and items requiring coordination between contractors under this contract. Provide submittals in sufficient detail so as to demonstrate compliance with these contract documents and the design concept. Prior to submitting submittals, verify that the equipment submitted is mutually compatible and suitable for the intended use, will fit the available space, and maintain manufacturer recommended service clearances. If the size of equipment furnished makes necessary any change in location or configuration, submit a shop drawing showing the proposed layout.

Transmit submittals as early as required to support the project schedule. Allow for two weeks Engineer review time, plus to/from mailing time via the Architect, plus a duplication of this time for resubmittal, if required. Only resubmit those sections requested for resubmittal.

Submittals shall contain the project name, applicable specification section, submittal date, equipment identification acronym as used on the drawings, and the Contractor's stamp. The stamp shall certify that the submittal has been checked by the Contractor, complies with the drawings and specifications, and is coordinated with other trades. Manufacturer product literature shall include shop drawings, product data, performance sheets, samples and other submittals required by this division. Highlight, mark, list, or indicate the materials, performance criteria, and accessories that are being proposed. General product catalog data not specifically noted to be part of the specified product will be rejected and returned without review.

Submittals and shop drawings shall not contain the firm name, logo, seal, or signature of the Engineer. They shall not be copies of the work product of the Engineer. If the Contractor desires to use elements of such product, refer to paragraph "Electronic Drawing Files" for procedures to be used.

Separate submittals according to individual specification sections. Illegible submittals will be rejected and returned without review. Catalog data shall be properly bound, identified, indexed and tabbed in a 3-ring binder. Each item or model number shall be clearly marked and accessories indicated. Label the catalog data with the equipment identification acronym or number as used on the drawings and include performance curves, capacities, sizes, weights, materials, finishes, wiring diagrams, electrical requirements and deviations from specified equipment or materials. For equipment with motor starters or VFDs, include short circuit current ratings. Mark out inapplicable items. Shop drawings will be returned without review if the above mentioned requirements are not met.

Provide the quantity of submittals required by Division 01. If not indicated and hard-copy sets are provided, submit a minimum of six (6) copies. Refer to Division 01 for acceptance of electronic submittals for this project. For electronic submittals, Contractor shall submit the documents in accordance with the procedures specified in Division 01. Contractor shall notify the Architect and Engineer that the submittals have been posted. If electronic submittal procedures are not defined in Division 01, Contractor shall include the website, user name, and password information to access the submittals. For submittals sent by e-mail, Contractor shall copy the designated representatives of the Architect and Engineer. Contractor shall allow for the Engineer review time as specified above in the construction schedule. Contractor shall submit only the documents required to purchase the materials and/or equipment in the electronic submittal.

The checking and subsequent acceptance of submittals by the Engineer and/or Architect shall not relieve the Contractor from responsibility for deviations from the drawings and specifications, errors in dimensions, details, size of members, or quantities, omissions of components or fittings, coordination of electrical requirements; and not coordinating items with actual building conditions and adjacent work. Proceed with the procurement and installation of equipment only after receiving approved shop drawings relative to each item.

K. ELECTRONIC DRAWING FILES

In preparation of shop drawings or record drawings, Contractor may, at his option, obtain electronic drawing files in AutoCAD or DXF format on CD-ROM disk, DVD disk, flash drive or direct download, as desired, from the Engineer for a shipping and handling fee of \$200 for a drawing set up to 12 sheets and \$15 per sheet for each additional sheet. Contact the Architect for written authorization and Engineer for the necessary release agreement form and to specify shipping method and drawing format. In addition to payment, the written authorization from the Architect and release agreement form from the Engineer must be received before electronic drawing files will be sent.

L. RECORD DRAWINGS (AS-BUILT DRAWINGS)

During progress of the work in this division, Contractor shall maintain an accurate record of all changes made during the installation of the system. Upon completion of the work, accurately transfer all record information to three identical sets of the approved shop drawings. Insert one set into each copy of the manual described below.

See Division 01 and General Conditions for additional information.

M. OPERATION AND MAINTENANCE INSTRUCTIONS

During the course of construction, collect and compile a complete brochure of equipment furnished and installed on this project. Include operational and maintenance instructions, manufacturer's catalog sheets, wiring diagrams, parts lists, approved submittals and shop drawings, warranties, and descriptive literature as furnished by the equipment manufacturer. Include an inside cover sheet that lists the project name, date, Owner, Architect, Engineer, General Contractor, Sub-Contractor, and an index of contents.

Submit three copies of literature bound in approved binders with index and tabs separating equipment types to the Architect, for Engineer's review, at the termination of the work. Pages, staples, rubber bands, loose-leaf binding, and mailing envelopes are not considered approved binders. Final approval of systems installed under this contract shall be withheld until this equipment brochure is received and deemed complete by the Architect and Engineer. Instruct workmen to save required literature shipped with the equipment itself for inclusion in this brochure.

Include Record Drawings as described above.

Refer to Division 01 for acceptance of electronic manuals for this project. For electronic manuals, refer to paragraph "Submittals" for requirements.

N. SPARE PARTS

Furnish to Owner, with receipt, the following spare parts for the equipment furnished for this project:
1. One set of spare filters of each type required for each unit. In addition to the spare set of filters, install new filters prior to testing, adjusting, and balancing work and before turning system over to Owner.
2. Furnish one complete set of belts for each fan.
3. Furnish three operating keys for each type of air outlet and inlet that require them.

O. TRAINING

At a time mutually agreed upon between the Owner and Contractor, provide the services of a factory trained and authorized representative to train Owner's designated personnel on the operation and maintenance of the equipment provided for this project.

Provide training to include, but not be limited to, an overview of the system and/or equipment as it relates to the facility as a whole; operation and maintenance procedures and schedules related to startup and shutdown, troubleshooting, servicing, preventive maintenance and appropriate operator intervention; and review of data included in the operation and maintenance manuals.

Submit a certification letter to the Architect stating that the Owner's designated representative has been trained as specified herein. Letter shall include date, time, attendees and subject of training. The Contractor and the Owner's representative shall sign the certification letter indicating agreement that the training has been provided.

Schedule training with Owner with at least 7 days advance notice.

WARRANTIES
Provide each system and each element thereof against all defects due to faulty workmanship, design, or material for a period of 12 months from date of Substantial Completion, unless specific items are noted to carry a longer warranty in the construction documents or manufacturer's standard warranty exceeds 12 months. Remedy all defects, occurring within the warranty period(s), as stated in the General Conditions and Division 01.

Warranties shall include labor and material, including travel expenses. Make repairs or replacements without any additional costs to the Owner, and to the satisfaction of the Owner, Architect, and Engineer.

Perform the remedial work promptly, upon written notice from the Engineer or Owner.

At the time of Substantial Completion, deliver to the Owner all warranties, in writing and properly executed, including term limits for warranties extending beyond the one year period and any actions the Owner must take in order to maintain warranty status. Each warranty instrument shall be addressed to the Owner and state the commencement date and term.

2. GENERAL MATERIALS AND INSTALLATION

A. BUILDING OPERATION

Comply with the schedule of operations as outlined in the architectural portions of this specification. Accomplish work requiring interruption of building operation at a time when the building is not in operation and only with written approval of building Owner and tenant. Coordinate interruption of building operation with the Owner and/or tenant a minimum of seven (7) days in advance of work.

B. EXISTING EQUIPMENT REUSE AND REMOVAL

Remove all unused equipment, ductwork, piping, and associated supports. Cap ductwork and piping at drains and seal air and water tight.

Provide items of HVAC systems modification required because of building remodeling, as noted on the drawings or necessary for proper operation. Match existing materials and construction techniques when modifying existing systems unless specified otherwise. Coordinate additional requirements with General Contractor and Architect.

Seal airtight existing ductwork required to be abandoned in place or not in use at the termination of the work.

Cap and seal weathertight existing roof curbs and roof openings to be abandoned in place as a result of equipment removal.

Clean and rebalance existing ductwork, diffusers, registers, and grilles intended for reuse as required or as indicated on drawings.

Clean and refurbish existing HVAC equipment intended for reuse as required for proper operation including replacement of filters, belts, motors, remote controls, and safety interlocks.

C. INCIDENTAL DAMAGE

Repair streets, sidewalks, drives, paving, walls, finishes, and other facilities damaged in the course of the work. Repair materials shall match existing construction. Repair work shall meet all requirements of the Owner, local authorities having jurisdiction, and meet the satisfaction of the Architect.

D. CUTTING AND PATCHING

Conform to the requirements in Division 01. Cut walls, floors, ceilings, and other portions of the facility as required to install work under this division. Obtain permission from the Architect prior to cutting. Do not cut or disturb structural members without prior approval from the Architect and Structural Engineer. For post-tensioned slabs, x-ray slab and closely coordinate all core drill locations with Architect and Structural Engineer prior to performing any work. Obtain approval from Architect and Structural Engineer for all core drills and penetrations at least four days prior to performing work. Penetrations shall be made as small as possible while maintaining required clearances between the building element penetrated and the system component. Patch around openings to match the adjacent construction including fire ratings, if applicable. Repair and refinish areas disturbed by work to the condition of adjoining surfaces in a manner satisfactory to the Architect.

E. ROUGH-IN

Coordinate without delay all roughing-in with other divisions. Conceal piping, conduit, and rough-in except in unfinished areas and where otherwise shown.

F. STRUCTURALSUPPORT SYSTEMS

Structural steel used for support of equipment, ductwork and piping shall be new, clean, and conform to ASTM Designation A-36. Support mechanical components from the building structure. Do not support mechanical components from ceilings, other mechanical or electrical components, and other non-structural elements.

G. PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS AND CURBS

Provide prefabricated equipment support rails and roof curbs manufactured by AES Industries, Custom Curb, Inc., Pace Company, Thybar or approved equal. Provide with fully reinforced raised cant and step to match roof insulation thickness, welded, minimum 18 gauge galvanized steel shell, internally reinforced to load bearing factors of equipment being supported, minimum 1-1/2 inch thick, 3 pound rigid insulation internal to shell with exterior of insulation where required, factory installed wood nailer, and minimum 18 gauge jacket with counterflashing where equipment does not fully cover the equipment support. Provide sloped roof equipment supports to enable level installation. Provide rigid backing material behind cant to maintain cant slope. Provide multiple support rails to uniformly support the equipment. Attach to roof structure according to manufacturer's installation instructions.

- 1. Attach equipment directly to pre-engineered roof equipment support using one of the following methods:
a. Rail Equipment Supports: Secure each equipment support leg to the rail with a minimum of 4 points of connection per leg.
b. Roof Curbs: Secure each corner of the equipment to the curb nailer using a minimum of 4 lag screws, located along the length of the equipment. Alternatively, secure equipment to the curb using hold-down brackets. Provide minimum 6 inch long, 14 gauge galvanized steel support rail with minimum 1/2 inch diameter top curb and under equipment base rail with sufficient horizontal offset to cover overlap gap between equipment rail and curb. Secure bracket to equipment rail and curb nailer using a minimum of 8 points of connection per bracket. Provide one bracket at each corner along the length of the rail.
c. Hold-Down Brackets: Provide a minimum of 4 hold-down brackets per equipment support to determine the quantity and size of hold-down brackets and fasteners, with installation instructions for each unit to meet a Building Design Risk Category III or IV and a Design Wind Speed of 115 mph.
d. Submit signed and sealed drawings that indicate the design and installation requirements of pre-engineered roof supports can withstand the design criteria listed. Include installation requirements for anchoring to the roof structure. The Engineer is not responsible and will not provide the seal and signature. Deliver submittal to the local AHJ for approval prior to installation of the contractor provided, pre-engineered roof supports.
e. Provide seismic restraints in accordance with Article "Seismic Controls for MEFP Systems."

H. ACCESS PANELS AND DOORS

Refer to Architectural documents for specification of access panels and doors.

Provide access doors for all concealed equipment and duct and piping accessories that require service where indicated or as required, except where above lay-in ceilings. Access doors shall be adequately sized for the devices served with a minimum size of 18 inches x 18 inches. Access doors must be of the proper construction for type of construction in which it is installed. Obtain Architect's approval of type, size, location and color before ordering. Provide factory-fabricated and assembled units, complete with attachment devices and fasteners ready for installation, concealed hinges, flush screwdriver-operated cam lock, and anchor straps. Provide access doors manufactured by Greenheck, Milcor, Tius, Zum, or equal.

I. PENETRATIONS

Provide sleeves for pipes passing through above grade concrete or masonry walls, concrete floor or roof slabs. Sleeves are not required for core drilled holes in existing masonry walls, concrete floors or roofs. Provide 10 gauge galvanized steel sleeves for sleeves 6 inches and smaller. Provide galvanized steel metal sleeves for larger than 6 inches. Schedule 40 PVC sleeves are acceptable for installation in areas without return air plenums.

Seal elevated floor, exterior wall and roof penetrations weathertight and weathertight with non-shrink, non-hardening commercial sealant. Pack with mineral wool and seal both ends with minimum of 1/2 inch of sealant.

Seal around penetrations of fire rated assemblies. Coordinate fire ratings and locations with the architectural drawings. Refer to architectural specifications for fire stoppings. Provide a product schedule for UL listing, location, wall or floor rating and installation drawing for each penetration fire stop system.

Extend pipe insulation for insulated pipe through floor, wall and roof penetrations, including fire rated walls and floors. The vapor barrier shall be maintained. Size sleeve for a minimum of 1/8 inch annular clear space between inside of sleeve and outside of insulation.

Provide prefabricated roof curbs where pipes and/or ductwork penetrate elevated slabs or of the roof to the exterior. Provide cover curb of weather-resistant material and seal duct or pipe penetrations through the curb. Provide pipe collar of weather-resistant material with stainless steel pipe clamps for pipe penetrations.

Provide box frames for rectangular openings welded 12 gauge galvanized steel attached to forms and of a maximum dimension established by the Architect. Notify the General Contractor or Architect before installing any box openings not shown on the Architectural or Structural drawings.

Seal concrete or masonry exterior wall penetrations below grade with "wall pipes" and mechanical sleeve seals. Provide cast iron "wall pipes" with integral waterproof ring manufactured by Jay R. Smith, Josam, Wade, Watts or Zum. Provide modular mechanical sleeve seals, manufactured by Galpco, Metraflex, or Thunderline / Link Seal.

Seal elevated concrete slab with water proof membrane penetrations with "wall pipes" and water proof sealant. Secure waterproof membrane flashing between "wall pipe" clamping flange and clamping ring. Provide cast iron "wall pipes" with integral waterproof ring manufactured by Jay R. Smith, Josam, Wade, Watts or Zum.

Provide sleeves for horizontal pipe passing through or under foundation. Sleeves shall be cast iron soil pipe two nominal pipe sizes larger than the pipe served.

Provide Schedule 40 PVC pipe sleeves for vertical pressure pipe passing through concrete slab on grade. Sleeves shall be one nominal pipe size larger than the pipe served and two pipe sizes larger than pipe served for ductile iron pipe with restraining rods. Seal water-tight with silicone caulk.

Provide 1/2 inch thick cellular foam insulation around perimeter of non-pressure pipe passing thru concrete slab on grade. Insulation shall extend to 2 inches above and below the concrete slab.

J. FIRESTOPPING

Sealants and accessories shall have fire-resistance ratings indicated, as established by testing identical assemblies in accordance with UL 2079 or ASTM E 814, or other NRTL acceptable to AHJ. Manufacturers: Hilli, RectolSeal, Specified Technologies Inc., United States Gypsum Company, or 3M corp.

Through and Membrane Penetration Firestopping Systems Product Schedule: Provide UL listing, location, wall or floor rating, and installation drawing for each penetration fire stop system.

Where project conditions require modification to qualified testing and inspecting agency's illustrations for a particular firestopping condition, submit illustration, with modifications marked, approved by penetration firestopping manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly, include qualifications data for testing agency.

K. MOTORS AND STARTERS

Provide motors and starting equipment where not furnished with the equipment package. Motors shall have copper windings, Class B insulation, and standard squirrel cage with starting torque characteristics suitable for the equipment served. Motors controlled by variable frequency drives shall be rated for minimum rise times in accordance with NEMA MG1, Part 31. Motors 5 horsepower and larger controlled by variable frequency drives shall be provided with a shaft grounding system equal to Aegis SGR Bearing Protection Ring, InproSeal Current Divertor Ring (CDR) or approved equal. Motors for air handling equipment shall be selected for quiet operation. Each motor shall be checked for proper rotation before electrical connection has been completed. Provide drip-proof enclosure for locations protected from weather and not in air stream of fan, and totally enclosed fan cooled enclosure for motors exposed to weather. Motors shall be manufactured by Century, General Electric, Louis Allis, Westinghouse, or approved equal.

L. VARIABLE FREQUENCY DRIVES

Provide PWM variable frequency drives (VFD) to control fan or pump motors as indicated on the drawings. Provide VFD as manufactured by AC Technology, Asea Brown Boveri, Danloss, Reliance Electric, or Yaskawa. Include an integral, door-locked interlock input circuit breaker or fused disconnect which may be padlocked in the "OFF" position.

Provide a magnetic contactor manual bypass integral to each drive. Provide two magnetic contactors, mechanically and electrically interlocked, to isolate the inverter output from line voltage. The inverter input shall be isolated by either a third magnetic contactor or a second disconnect switch to allow manual power to the inverter for service while still operating the motor across the line. Bypass shall include a 120/180 control transformer, fused on both the primary and secondary, and bi-metallic thermal motor overload relays with adjustable trip settings.

Provide input AC line reactors without exception. Reactors shall be minimum 3 percent impedance, and "K" rated per IEEE C57-110 for harmonic current content. Reactors shall be integral to the drive enclosure without need for field wiring.

O. SYSTEM TESTING, ADJUSTING, AND BALANCING

Upon completion of each phase of the installation, test each system in conformance with local code requirements and as noted below. Furnish labor and equipment required to test each system installed under this contract. Assume all costs involved in making the tests and repairing and/or replacing any damages resulting therefrom.

The final test and balance of the building HVAC systems shall be completed by National TAB (no exceptions) and contracted by the General Contractor. The representative from National TAB shall be certified by the National Environmental Balancing Bureau (NEBB), Associated Air Balance Council (AABC), or Testing, Adjusting and Balancing Bureau (TABB). TAB shall be performed in accordance with the most current edition of the certified agencies procedural standard for testing, adjusting and balancing and shall comply with the strictest interpretation of that standard for execution and reporting of all TAB work.

Work shall include but not be limited to: Perform test readings on fans, coils, pumps, etc. and adjust equipment to deliver specified amounts of air. Prepare testing and balancing report log showing air supply quantities, air entering and leaving temperature and air flow, and submit six copies of the final report to the Architect for evaluation and approval before final inspection of the project. Balance air systems to within plus or minus 10 percent for terminal devices and branch lines and plus or minus 5 percent for main ducts and air handling equipment that does not require ductwork. Adjust dampers and make adjustments to make adjustments in airflow. Adjust diffuser to obtain uniform temperature (no greater than +/- 3) in spaces. Document temperatures and adjustments in lab report. Adjust equipment to operate as intended by the specification. TAB report shall include a report summary/remarks section in accordance with the procedural standard that provides both system set up and a summary of deficiencies as defined by the procedural standard.

TAB Contractor shall be responsible to calibrate, set, and adjust automatic temperature control sensors, actuators and control devices. Coordinate with the manufacturer's installation instructions and provide engineering support designed to meet the wind resistance and seismic design criteria. Reference Section, "PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS."

Division 23 contractor shall align bearings and replace bearings that have dirt or foreign material in them with new bearings without additional cost to the Owner.

P. VIBRATION ISOLATION

Provide vibration isolation equipment and materials by a single manufacturer. If type and deflection for specific equipment is not specified within the contract, ASHRAE Handbook "HVAC Applications" or provide per manufacturer's recommendations. Approved manufacturers include Calkdy, Kinetics Noise Control, Mason Industries, Inc., Vibration Eliminator Co., Inc., Vibration Mounting and Control, and Vibro-Acoustics, provided their systems are in compliance with the specified design and performance requirements.

General Requirements: Select vibration isolators by the weight distribution to produce uniform deflection. Vibration isolators shall have equal or unequal deflection heights or calibration markings so that, after adjustment, the static deflection can be verified. Thus, determining that the load is within the proper range of the isolator. Isolators shall operate in the linear portion of their load versus deflection curves. Spring isolators shall have 50 percent excess capacity without becoming coil bound. Coils shall be protected with factory-applied corrosion resistance protection. Install and adjust vibration isolators in accordance with manufacturer's written instructions.

Pipe connections: Provide flexible connectors for piping system connections on equipment side of shutoff valves for all pumps, mechanical equipment supported or suspended by spring isolators, and where indicated on drawings. Fabricate flexible piping connectors from stainless steel or rubber materials as suitable for system fluid. Flexible piping connectors shall be bellows, spherical or braided hose type as recommended by the manufacturer for the application.

Isolator Types:

1. Type WP (Waffle Pads): Provide 5/16 inch thick neoprene pads ribbed or waffled on both sides. Manufacture pads with bridge bearing quality neoprene and select for a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of 0.05 inches. Insulate between the equipment and the neoprene pad to provide selected deflection. If the isolator is bolted to the structure, install a neoprene mounting sleeve under the bolt head between the steel washer and the base plate to prevent metal to metal contact. Provide Mason Industries Type W or equal.

2. Type SPNH (Spring and Neoprene Hangers): Provide a steel hanger bar containing a laterally stable, double-deflecting neoprene pad. The neoprene pad shall be attached to the vertical spring so that, after adjustment, the static deflection is between one and two. The spring diameter shall be not less than 80 percent of the compressed height of the spring at rated load. Loaded springs shall operate within the linear portion of their load versus deflection curve over a deflection range of not less than 50 percent above and below the rated load. The spring diameter shall be large enough to permit the hanger rod to swing through a 30 degree arc. Include a neoprene bushing to prevent contact between the lower hanger rod and hanger box and short-circuiting the isolating function. The neoprene element shall have a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of not less than 0.05 inches. Unless otherwise specified, the static deflection of SPNH hangers shall be 2 inches. Provide SPNH hangers with 1 inch static deflection for water source heat pumps and fan-powered VAV terminal units. When installed, do not cock the spring element and do not allow the hanger box to rotate through a full 360 degree arc without encountering obstructions. Provide Mason Industries Type 30N or equal.

3. Type NR (Neoprene Bushing): Provide neoprene, rubber-in-shear bushings for lightweight (less than 100 pounds), suspended equipment supported from structure with threaded rod and angle iron or linear rod for a maximum diameter of 50 and designed for 15 percent strain, with a static deflection of 0.15 inches. Provide Mason Industries Type HMB or equal.

Q. SEISMIC CONTROLS FOR MEPP SYSTEMS

Seismic Protection Criteria: Risk/Occupancy Category: II, III or IIII/V; Site Soil Category: Contractor's Seismic Engineer to Determine; Seismic Design Category: Contractor's Seismic Engineer to Determine; Component Importance Factor: Determined from ASCE 7, most recent version.

The Contractor shall be responsible for determining the requirements for seismic bracing of mechanical, electrical, and plumbing systems. Seismic protection criteria used to determine seismic bracing requirements of all mechanical, electrical, and plumbing systems shall be determined by the applicable code adopted in the project jurisdiction. Where not already determined within the contract documents, the Contractor shall be responsible for contracting a licensed professional engineer to establish building site class, seismic design category, seismic zone, or any other criteria necessary to determine the requirements for seismic bracing on mechanical, electrical, and/or plumbing systems.

Seismic bracing of fire protection systems shall be installed in strict accordance with the provisions of NFPA 13 (2010 or later edition).

The Contractor shall determine the type and location of seismic bracing required for the mechanical, electrical, and plumbing elements shown on the drawings based on the established seismic criteria, the size and weight of the supported element, and the distance from structure of the supported element.

The Contractor shall submit the following shop drawing information to the AHJ and the Engineer for review and approval: 1. Seismic analysis listing all applicable seismic design criteria. 2. Descriptive catalog data of seismic bracing materials. 3. Shop drawings showing bracing type and location. 4. Installation details of all bracing used. 5. Calculations showing that the seismic restraints meet the seismic requirements. Shop drawings and calculations shall be signed and sealed by a registered professional engineer, licensed in the state of the project and employed by the manufacturer of the seismic bracing products. Calculations shall include dead loads, static seismic loads, and capacity of materials utilized for connections.

Seismic bracing, restraints, isolators, and isolation materials shall be of the same manufacturer and shall be certified by the manufacturer. Approved manufacturers are AmberBooth Company, Inc., B-Line/Totco, SAT, Kinetics Noise Control, Inc., Loox & Company, Inc., Mason Industries, Inc., Uni-Strut, or Vibro-Acoustics. Each device shall have a pre-approval number from California OSHPD or other recognized government agency showing maximum restraint ratings.

Seismic bracing measures to be applied to mechanical, electrical, and plumbing equipment/systems shall be installed in strict accordance with all applicable local, state, and/or federal codes as well as manufacturer's requirements. The most stringent criteria shall apply. All anchor connections to structure for mechanical and electrical equipment, regardless of the type for seismic restraints, shall be shown on shop drawings.

R. AIR FILTERS

Provide AAF/Flanders Perfect Pleat HC MB, Camfil Fair 30/30, pleated, throwaway type filters, minimum MERV 8, or similar as manufactured by Air Filter, Inc., Bicimatic, Columbus, Koch, or approved equal, unless otherwise indicated.

Temporary filters used to protect openings in ductwork and minimum equipment when permanent HVAC equipment is used during the construction period shall be pleated, throwaway type filters, minimum MERV 8.

S. REFRIGERANT AND OIL

Provide full refrigerant and oil charge in new air conditioning refrigeration systems, and maintain it for full term of the guarantee.

T. IDENTIFICATION

Provide manufacturer's standard pre-printed, semi-rigid snap-on or permanent adhesive, pressure-sensitive vinyl pipe markers. Color code pipe markers to comply with ANSI A13.1.

Install pipe markers on each HVAC piping system and include arrows to show normal direction of flow.

Locate pipe markers and color bands wherever piping is exposed to view in occupied spaces, machine rooms, accessible maintenance spaces (shafts, tunnels, plenums) and exterior non-enclosed locations.

Provide plastic laminate or brass valve tag on every valve, cock and control device in each HVAC piping system; exclude check valves, valves within factory-fabricated equipment units, and shut-off valves at HVAC terminal devices and similar rough-in connections of end-use fixtures and units.

Provide manufacturer's standard laminated plastic, color coded equipment markers. Conform to the following color code: Green for Cooling, Yellow/Green for Heating, Yellow/Red for Heating and Cooling, Blue for Emergency Readaction, Blue for other equipment types. Conform to ANSI A13.1 for Hazardous Equipment.

Provide stenciled signs for equipment identification at Contractor's option or where distance of required identification requires lettering larger than 1 inch height. Stencil paint shall be exterior type, oil-based, alkyl amine, minimum 1/4 inch height or greater as required for long distance identification, white or black color for best contrast.

Provide duct markers or provide stenciled signs and arrows indicating ductwork service and flow direction in black or white lettering for best contrast with duct or insulation color. Locate markers maximum 50 feet along each duct side and within 5 feet of all control and balancing dampers or branch ducts more than 26 feet length and within 5 feet on each side of wall, floor, and ceiling penetrations. Provide additional markers in congested areas or on multiple duct runs as required for clarity.

3. DUCT INSULATION, DUCTWORK, ACCESSORIES, FLUES AND FANS

A. DUCT INSULATION

Provide fiberglass duct liner with fibers firmly bonded together with a thermosetting resin. Liner surface shall serve as a barrier against infiltration of dust and dirt; shall meet ASTM C1338 for fungi resistance, and shall be cleanable using duct cleaning methods and equipment outlined by North American Insulation Manufacturers Association (NAIMA) duct cleaning guide. Install with liner adhesive and mechanical fasteners in accordance with manufacturer's instructions and recommendations. Ductwork sizes shown on drawings are inside clear dimensions. Increasing sheet metal by liner thickness in both directions where liner is installed.

Provide rectangular liner conforming to ASTM C1071, Type I or II that is 1-1/2 inch thick, 1-1/2 pound density, minimum R-6.0 Certainteed Corp. "Toughguard" or equivalent, Johns Manville, Owens-Corning, or Knaflex.

Provide round liner that is 1-1/2 inch thick, 4 pound density, minimum R-6.0 Johns Manville "Spiracoustic Plus" or equivalent, Certainteed or Owens-Corning.

Provide liner on the following interior air ducts and where specified on the drawings:

- 1. Exposed round and rectangular supply ductwork.
2. Exposed round and rectangular return ductwork.

At interface of lined and wrapped ductwork, overlap lined ductwork at least 2 feet beyond wrapped insulation.

Cover concealed, rigid ductwork with ASTM C563, Type II flexible fiberglass insulation. Installed insulation shall be 2 inch thick, 3/4 pound density, minimum R-6.0 duct wrap, Certainteed or equivalent Johns Manville, Owens-Corning, or Knaflex with heavy-duty foil-scrim-kraft facing, and with joints taped with 3 inch wide foil tape as follows:

- 1. Round and rectangular supply and return air ductwork.
2. Unlined Round and rectangular outside air ductwork.
3. Round and rectangular exhaust and relief air ductwork within 10 feet of exterior discharge.

Cover Outdoor air, Exhaust air and Relief air plenums connected to exterior louvers with 1-1/2 inch thick, 1.5 pound density, rigid fiberglass insulation conforming to ASTM C612, Class 2.

Insulating materials, adhesives, coatings, etc., shall not exceed flame spread rating of 25 and smoke developed rating of 50 per ASTM E84. Containers for mastics and adhesives shall have U.L. Label.

B. DUCTWORK

Provide galvanized steel ductwork and housings as shown on drawings. Construct ductwork including fittings and transitions in conformance with current SMACNA standards relative to gauge, bracing, joints, etc. Minimum thickness of duct shall be 26-gauge sheet metal. Reinforce housings and ductwork over 30 inches with 1-1/4 inch angles not less than 5/8" on centers, and close if required. Provide sufficient rigidity to prevent vibration. Support horizontal runs of duct from strap iron hangers on centers not to exceed 6'-0". Do not support ceiling grid, conduits, pipes, equipment, etc., from ductwork. Coordinate routing of ductwork with other contractors such that piping, electrical conduit, and associated supports are not routed through the ductwork.

Provide pre-engineered roof duct supports by Cooper B-Line, Elite Components, ERICO, FNN, Mio, PHD Manufacturing, PMP Systems, Roof Top Box, UniStrut (Akroak), Zia Foster, or approved equal. Support ductwork on the roof with pre-engineered roof duct supports that rest on top of the roofing membrane, not requiring any attachment to the roof structure and shall contain the roofing assembly, with embedded support fixtures as required to support the duct. Provide steel pedestal type supports with minimum 1x8x18 inch thermoplastic or rubber base or 4 inch wide closed-cell polyethylene block with length as required. Maintain minimum 6 inches clearance under duct to finished roof surface.

Coordinate with the pre-engineered roof duct manufacturer to anchor the roof supports directly to the roof structure in accordance with the manufacturer's installation instructions and provide engineering support designed to meet the wind resistance and seismic design criteria. Reference Section, "PRE-ENGINEERED ROOF EQUIPMENT SUPPORTS."

Construct non-VAV supply ducts to meet SMACNA positive pressure of 2 inches w.g. Construct Return, Outdoor and Exhaust ductwork upstream of fans to meet SMACNA negative pressure of 1 inch w.g. Construct exhaust ductwork downstream of fans to meet SMACNA positive pressure of 1 inch w.g.

Provide mill phosphatized or galvanized finish for exposed ductwork to be field painted. Shop treated sheet metal shall have galvanized metal primer applied in the shop after fabrication and prior to shipping.

Seal ductwork with heavy liquid sealant, Hardcast Irongrip 601, Design Polymer DP 1010, United McGill duct sealer or approved equal, applied according to sealant manufacturer's instructions. Seal all longitudinal and transverse ductwork joints airtight to meet SMACNA Seal Class A. Tapes and mastics shall be listed and labeled in accordance with UL 181A.

Provide radius elbows, turns, and offsets with a minimum centerline radius of 1-1/2 times the duct width. Where space does not permit full radius elbows, provide 90 degree turns with a minimum of two continuous 90 degree turns. Vanes shall be the entire length of the bend. Provide mitered elbows where space does not permit radius elbows, where shown on the drawings, or at the option of the contractor with the engineer's approval. Mitered elbows less than 45 degrees shall not require turning vanes. Mitered elbows 45 degrees and greater shall require turning vanes of same gauge as ductwork, rigidly fastened with guide strips in accordance with drawings. Vanes for mitered elbows shall be provided in all supply and exhaust ductwork and in return and outside air ductwork that has an air velocity exceeding 1000 fpm. Do not install vanes in grease ductwork. The use of square throat, radius heel elbows is prohibited. Remove and replace all installed elbows of this type with an approved elbow at no additional cost to the owner.

Connect ducts to vibrating equipment and when transitioning between two different metallic duct materials (e.g., aluminum to galvanized steel) by means of flexible connectors. Flexible connectors shall have a flame spread of 25 or less and smoke developed rating not higher than 50. Make airtight joints and install with minimum 1-1/2 inches slack.

Provide balanced dampers, manufactured by Cresco, Greenheck, Louvers & Dampers, Nalor Industries, Pottoff, Ruskin, Tamco, or approved equal, where shown on drawings and wherever necessary for complete control of air flow. Splitter dampers shall be controlled by kicking dampers; provide Young Regulator or Ventok or equivalent fan. Rectangular volume dampers shall be opposed blade interlocking type. Round volume dampers shall be single-blade type consisting of circular blade mounted to a shaft. Provide Flexmaster model STO or equal 45 degree rectangular/round side takeoff fitting with model B03 damper with locking gasket and insulation built out for round ductwork branch takeoffs to individual air devices. Omit damper at takeoff fitting when damper is located downstream of takeoff.

Where access to dampers through a hard ceiling is required, provide a concealed, remote cable-operated, butterfly-type volume damper assembly with external worm gear operator. Damper assembly shall include duct casing with rolled bead stiffeners, reinforced blade, self-lubricating bearing, and remote operator mounting plate. External operator shall attach to damper as a single piece which shall be factory assembled to the damper frame with standard 1/4 inch longitudinal and transverse ductwork joints.

Provide split ductless system consisting of evaporator section for wall or ceiling mounting as indicated and remote condensing section similar to Carrier, Comfort Star, Dakin, Friedrich, Fujitsu, Lennox, LG, Mitsubishi, Samsung, Sanyo, Trane, or York. Evaporator cabinet shall be factory assembled to the damper frame with standard 1/4 inch longitudinal and transverse ductwork joints. Centrifugal fans, 2-speed motor, and cleanable foam filter. Evaporator coil shall be direct-expansion cooling coil of seamless copper tubes expanded into aluminum fins, with thermal-expansion valve with external equalizer. Air-cooled condenser shall be of corrosion-resistant cabinet containing compressor and condenser coils, direct-drive propeller fans with motors with internal overload protection; capacity control to 2 degrees Fahrenheit.

Provide concrete base for units located on grade. Provide pre-engineered roof equipment support rails for units located on roof. Securely attach units to rail.

Provide refrigerant piping sized as recommended by equipment manufacturer with foamed plastic insulation on the suction line as specified in this section.

Control System: Unit-mounted panel with controls, control transformer with circuit breaker, adjustable static temperature- and humidity-control modules. Provide solid-state, unit-mounted control panel with start-stop switch, adjustable humidity set point, and adjustable temperature set point. Refer to sequence of operation.

5. PIPING AND PIPING SPECIALTIES

A. REFRIGERANT PIPING AND INSULATION

Copper Tubing: ASTM B280, Type ACR, hard-drawn straight lengths, and soft-annealed coils, seamless copper tubing. Tubing shall be factory cleaned, ready for installation. Provide full length of pipe diameters as recommended by the manufacturer and of length as required for the installation. Tubing shall be factory or field insulated with flexible urethane insulation with thickness as specified below.

Fittings: wrought-copper fittings: ANSI B16.22, streamlined pattern.

Solder filler metals: ASTM B32, 95.5 Tin-Antimony.

Brazing filler metals: 1. AWS A5.8, Classification BAg-5; Silver (Ag) 44.0-46.0 percent, Zinc (Zn) 23.0-27.0 percent, and Copper (Cu) 29.0-31.0 percent. 2. AWS A5.8, Classification BCuP-5; Phosphorus (P) 4.5-5.2 percent, Silver (Ag) 14.5-15.5 percent, and Copper (Cu) remainder.

Brace mechanical joints. Solder joints connecting to refrigerant valves and specialties. Continuously purge the pipe and fittings during brazing with an inert gas per manufacturer's recommendation (e.g., dry nitrogen) to prevent formation of scale. Maintain purge until the joint is cool to the touch. Provide temporary cap or cover on completed joints with open ends to prevent entry of contaminating materials.

Insulate refrigerant lines with flexible elastomeric insulation, Armaflex or equal. Insulate suction and liquid lines between the expansion valve, evaporator, and compressor with 1/2 inch thick insulation on pipes less than 1 inch in size and 3/4 inch thick for pipes 1 inch and larger. Insulate hot gas and liquid lines between the compressor condenser, and expansion valve with 1 inch thick insulation on pipes less than 1-1/2 inch and 1-1/2 inch thick for pipes 1-1/2 inch and larger. Piping insulation shall have a flame spread of 25 or less, and a smoke developed rating of 50 or less when tested in accordance with ASTM E84. Coat insulation that is exposed to the elements with a protective sealer. Install and support piping to keep noise and vibration to a minimum. Support and secure piping to UniStrut type supports so that no vibration passes to the building structure. Pipe attachments shall be copper-plated or have nonmetallic coating for electrolytic protection where attachments are in direct contact with copper tubing. Install a support within one foot of each change of direction. Mount pipe hangers around the outside of the insulation with saddles to prevent hangers from rupturing the insulation. Replace insulation that is cut or broken by the hangers.

Refrigerant lines parallel and perpendicular to wall and floor lines and to appear straight and in good order. Pitch suction lines down slightly (1 inch in 20 feet) towards the compressor. Provide oil traps at the base of vertical suction risers over 6 feet high. Install liquid line sight glasses in liquid lines near the expansion valve. Factory mount expansion valves with the sensing bulbs shipped loose. Field mount expansion valve bulb after refrigerant piping is complete (damage may occur if bulbs come in contact with heat).

For systems of 5 ton capacity and smaller, the contractor shall have the option to provide copper refrigerant tubing line sized as recommended by equipment manufacturer and of length as required for the installation. Provide quick-connect flare tubing connecting fittings, solder connections, or brazed connections as recommended by the manufacturer to match the connections of the condensing unit and evaporator coil.

Repeat the proper amount of refrigerant charge per the manufacturer's recommendations. Record the amount of refrigerant by weight charged into the system for each circuit. The minimum 14 pound on tags and attach tags to the liquid line near the condensing unit. Refrigerant shall be supplied by the HVAC Contractor.

Provide refrigerant lines parallel and perpendicular to wall and floor lines and to appear straight and in good order. Pitch suction lines down slightly (1 inch in 20 feet) towards the compressor. Provide oil traps at the base of vertical suction risers over 6 feet high. Install liquid line sight glasses in liquid lines near the expansion valve. Factory mount expansion valves with the sensing bulbs shipped loose. Field mount expansion valve bulb after refrigerant piping is complete (damage may occur if bulbs come in contact with heat).

For systems of 5 ton capacity and smaller, the contractor shall have the option to provide copper refrigerant tubing line sized as recommended by equipment manufacturer and of length as required for the installation. Provide quick-connect flare tubing connecting fittings, solder connections, or brazed connections as recommended by the manufacturer to match the connections of the condensing unit and evaporator coil.

Repeat the proper amount of refrigerant charge per the manufacturer's recommendations. Record the amount of refrigerant by weight charged into the system for each circuit. The minimum 14 pound on tags and attach tags to the liquid line near the condensing unit. Refrigerant shall be supplied by the HVAC Contractor.

Provide ceiling mounted air devices of lay-in or surface mounted type as required to be compatible with ceiling construction. Provide ceiling diffusers and grilles with white enamel finish unless noted otherwise.

Provide linear slot diffusers of standard one-piece lengths up to 6-feet and furnish in multiple sections greater than 6-feet. Join multiple sections together end-to-end with alignment pins to form a continuous slot appearance. For installations in a hard ceiling, install diffuser per manufacturer's installation instructions prior to installation of drywall. Contractor shall use manufacturer's hard ceiling clips for mounting to ceiling framing. Screws through face of linear slot diffuser are not acceptable. Provide alignment components by the manufacturer. Provide plenums by the slot diffuser manufacturer. Plenums shall be internally insulated by the manufacturer with minimum 1/4 inch thick, fiberglass insulation.

Provide modulating dampers with linear flow characteristics. Size modulating dampers based on the smaller of 1,500 FPM through the damper or full open air pressure drop of 0.1 inches W.C. Size two-position dampers full size and select to minimize pressure drop.

Motorized dampers used for ventilation air intake, exhaust air, or relief air shall have leakage rates not to exceed 4.0 CFM/square foot in full closed position at 1 inch W.G. pressure differential across the damper.

Provide dampers as manufactured by Greenheck, CESCO, Pottoff, Nalor, or Ruskin. Reference manufacturer with model number for outside air dampers is Ruskin CD-50 constructed of aluminum, and all other applications is Ruskin CD-35 constructed of galvanized steel.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

Provide damper operator for each automatic damper with sufficient capacity to operate the damper under all conditions and to guarantee the damper is closed or open in the event of power encountered. Each operator shall be provided with spring-return for normally closed or normally open position for fail safe operation to account for fire, low temperatures, or power interruptions as required by the control systems manufacturer on the drawings. Damper operators shall be manufactured by Belimo, Johnson Controls or approved equal. Provide transformer for damper motors if different voltages are required.

G. EXHAUST AIR SYSTEMS

Roof mounted exhaust fans as scheduled on the drawings, or equal ACME, Cames, Cook, Greenheck, Pennbray, or Twin City Fans complete with aluminum housing, aluminum centrifugal wheel, motor with integral thermal overload protection, disconnect switch mounted inside the housing, birdscreen, backdraft damper, and pale prefabricated roof curb. Three phase fans shall be furnished with magnetic starters with push button station.

H. KITCHEN EXHAUST AIR SYSTEMS

Install kitchen grease exhaust package furnished by the owner. System includes kitchen hood, grease exhaust fan, filtered makeup air unit and a mechanical or electrical gas shutoff valve provided with the kitchen exhaust system to shutoff fuel or power source to cooking equipment upon detection of fire. Valve shall have a clearly marked open/closed indicator.

Provide ducts connecting Type 1 exhaust hoods to exhaust fans made of #16 gauge black iron with continuously welded joints and clean-out doors. Provide transition to fan with opening size equal to or greater than the venturi opening of the fan inlet. Provide gasket at flanged connection to fan rated for 1500 degrees Fahrenheit and grease applications. Enclose duct in fireproof enclosure per locally adopted mechanical code or, if approved by the local code official, in fire rated wrap insulation. Insulation shall be minimum two-hour rated duct wrap meeting the fire type I hood grease exhaust duct applications and shall conform to ASTM E2336 where required to comply with IMC. Insulation shall be flexible wrap enclosure rated for minimum 200 degrees Fahrenheit and for zero clearance to combustibles. Insulation shall be non-mineral wool, passive, low bio-persistent fiber totally encapsulated on all sides with aluminum foil. Insulation shall be installed in accordance with the manufacturer's instructions and shall comply with UL 1818 standard for grease ducts may be used in lieu of the welded black iron duct for connecting hood to exhaust fan. Ductwork package shall be mechanically tight, double-brake, silver-to-steel type protected by arcing contacts. Provide manufacturer's UL listing number and certification as a part of the shop drawing submittal. The installed duct package in strict conformance with manufacturer's instructions and recommendations.

All portions of grease duct systems shall be tested for leakage in accordance with the "Grease Duct Test" paragraph of the IMC. Leakage tests shall be by water leakage type or equivalent test methods as approved by the local code official to determine that all joints are airtight tight. Water leakage test shall be performed by Environmental Corporation of America or owner approved testing contractor. Tests shall be performed in the presence of the local code official. Any joints found defective shall be repaired and retested until satisfactory results are obtained. The contractor shall submit a copy of the grease duct leakage test report to the architect/engineer complete with the approval signature of the local code official.

Provide electric cooling, gas heating rooftop units as scheduled on the drawings, manufactured by Aeon, Carrier, Dakin, Lennox, Johnson Controls, Trane, or York, with features as noted in the RTU schedule and in the RTU Control Matrix. Control panel and factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater, and low pressure switches; direct expansion cooling and condensing coils with 1 inch factory installed flexible elastomers; insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating (as required by the applicable energy code or greater if mandated by local code), minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code.

Provide electric cooling, gas heating rooftop units as scheduled on the drawings, manufactured by Aeon, Carrier, Dakin, Lennox, Johnson Controls, Trane, or York, with features as noted in the RTU schedule and in the RTU Control Matrix. Control panel and factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater, and low pressure switches; direct expansion cooling and condensing coils with 1 inch factory installed flexible elastomers; insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating (as required by the applicable energy code or greater if mandated by local code), minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code.

Provide electric cooling, gas heating rooftop units as scheduled on the drawings, manufactured by Aeon, Carrier, Dakin, Lennox, Johnson Controls, Trane, or York, with features as noted in the RTU schedule and in the RTU Control Matrix. Control panel and factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater, and low pressure switches; direct expansion cooling and condensing coils with 1 inch factory installed flexible elastomers; insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating (as required by the applicable energy code or greater if mandated by local code), minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code.

Provide electric cooling, gas heating rooftop units as scheduled on the drawings, manufactured by Aeon, Carrier, Dakin, Lennox, Johnson Controls, Trane, or York, with features as noted in the RTU schedule and in the RTU Control Matrix. Control panel and factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater, and low pressure switches; direct expansion cooling and condensing coils with 1 inch factory installed flexible elastomers; insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating (as required by the applicable energy code or greater if mandated by local code), minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code.

Provide electric cooling, gas heating rooftop units as scheduled on the drawings, manufactured by Aeon, Carrier, Dakin, Lennox, Johnson Controls, Trane, or York, with features as noted in the RTU schedule and in the RTU Control Matrix. Control panel and factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater, and low pressure switches; direct expansion cooling and condensing coils with 1 inch factory installed flexible elastomers; insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating (as required by the applicable energy code or greater if mandated by local code), minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code.

Provide electric cooling, gas heating rooftop units as scheduled on the drawings, manufactured by Aeon, Carrier, Dakin, Lennox, Johnson Controls, Trane, or York, with features as noted in the RTU schedule and in the RTU Control Matrix. Control panel and factory installed direct-drive hermetic compressors with internal spring vibration isolation, built-in motor thermal overload protection, crankcase heater, and low pressure switches; direct expansion cooling and condensing coils with 1 inch factory installed flexible elastomers; insulation around the suction and liquid lines not directly located above a condensate drain pan and protective UV coating on any insulation exposed to sunlight, minimum SEER or EER rating (as required by the applicable energy code or greater if mandated by local code), minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code, minimum AFUE rating (heating) as required by the applicable energy code or greater if mandated by local code.

Provide electric cooling, gas heating rooftop units as scheduled on the drawings

6

5

4

3

2

1

E

D

C

B

A

3.6 MECHANICAL IDENTIFICATION

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Perform the following checks:
 1. Verify all valve tags, piping, duct, and equipment labeling corresponds with drawings and indexes and meets requirements specified. Correct any deficiencies for all piping and duct system.
 2. Adjusting: Relocate any mechanical identification device which has become visually blocked by work of this division or other divisions.
 3. Cleaning: Clean face of identification devices, and glass frames of valve charts.

3.7 MECHANICAL INSULATION

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Examine all piping, systems and equipment specified to be insulated.
 1. Ensure quality of insulation. Patch and repair all insulation damaged after installation.
 2. Ensure the integrity of vapor barrier around all cold surfaces.

3.8 PIPING GENERAL

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: These procedures apply to all installed piping systems, including underground site utilities.
 1. Inspect all piping for proper installation, adequate support (with appropriate vibration isolation where applicable) and adequate isolation valves for required service.
 2. Provide notifications of pipe cleaning and flushing activities.
 3. Flush and clean all piping and clean all strainers. Provide documentation of all related procedures.
 4. Ensure adequate drainage is provided at low points and venting is provided at high points.
 5. Ensure facilities to effectively drain and fill the system are in place.
 6. Ensure air is thoroughly removed from the system as applicable.
 7. Provide notification of pressure testing.
 8. Pressure and/or leak test all applicable systems in accordance with the requirements in the applicable Division 23 specification.
 9. Sterilize applicable piping systems as specified in the individual sections and as required by regulatory authorities.
 10. Submit pressure test reports that document the pressure testing results with certification of the results. Include drawings/diagrams indicating sections of pipe that are tested with the corresponding report.
 11. Set and adjust fill, pressure, or level controls to the required setting.

3.9 AC MOTORS

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Perform the following checks during start-up and as specified in manufacturer's instructions:
 1. Verify proper alignment, installation, and rotation.
 2. Verify properly sized overloads are in place.
- c. Start-Up Tests: Perform the following tests, measurements, or procedures during start-up and as specified in the manufacturer's instruction:
 1. Measure voltage available to all phases. Measure amps and RPM after motor has been placed in operation and is under load.
 2. Record all motor nameplate data.

3.10 PACKAGED HEATING AND COOLING UNITS

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Refer to AC Motors in this section.
- c. General: Provide the services of a factory-authorized service representative to test and inspect unit installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
- b. Start-Up Checks: Perform the following inspections/checks during start-up:
 1. Test controls and demonstrate compliance with requirements. Replace damaged or malfunctioning controls and equipment.
 2. Install new filters after start-up.

3.11 TERMINAL UNITS

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Perform the following inspections/checks during start-up:
 1. After construction is completed, including painting if applicable, clean unit exposed surfaces.
 2. Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
 3. Verify adequate access for maintenance.
 4. Check power and control voltages.
 5. Check rotation of fan where applicable.
 6. Check operation of water leak sensors.
 7. Check calibration and operation of the controlling elements.
 8. Check control valves for required close-off and full position.
 9. Install new filter units for terminals requiring same.

3.12 FANS

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. General: Provide the services of a factory-authorized service representative to test and inspect exhaust fan installation, provide startup service, and to demonstrate and train Owner's maintenance personnel is required by the Owner.
- c. Start-Up Checks: Perform the following inspections/checks during start-up:
 1. Inspect the field assembly of components and installation of the units, piping, ductwork, and electrical connections.
 2. Clean unit cabinet interiors to remove foreign material and construction dirt and dust. Vacuum clean fan wheel, fan cabinet, coils entering air face. Ensure volatile irritants are contained and kept out of occupied spaces.
 3. Adjust and lubricate dampers and linkages for proper damper operation.
 4. Verify the unit is secure on mountings and supporting devices and connections for ductwork, and electrical are complete. Verify proper thermal overload protection is installed in motors, starters, and disconnects.
 5. Ensure vibration isolation integrity is maintained with the fan installation and associated connections.
 6. Lubricate bearings, pulleys, belts, and other moving parts with factory-recommended lubricants.
 7. Stroke all dampers to ensure free and full travel.

3.13 DUCTWORK ACCESSORIES

- a. Include all applicable "Start-Up Checks Common to All Systems".
- b. Start-Up Checks: Perform the following checks during start-up and as specified:
 1. Cleaning: Clean factory-finished surfaces. Repair any marred or scratches surfaces with manufacturer's touch-up paint.
- c. Start-Up Tests: In addition to specifications, perform the following as a minimum:
 1. Operate installed ductwork accessories to demonstrate compliance with requirements. Test for air leakage while system is operating. Repair or replace faulty accessories, as required to obtain proper operation and leak proof performance.
 2. Label access doors in accordance with Division 21 Section "Mechanical Identification"
 3. Adjusting: Adjust ductwork accessories for proper settings, install fusible links in-fire dampers and adjust for proper action.

END OF SECTION 23



ZEBRA PROJECTS, INC. 14814 N KIERLAND BLVD, SUITE N 300 SCOTTSDALE, ARIZONA 85254

PHONE: 480.912.1169 zbr.global

HENDERSON ENGINEERS 8345 LENEXA DRIVE, SUITE 300 LENEXA, KS 66214 TEL 913.342.5000 FAX 913.742.5001 WWW.HENDERSONENGINEERS.COM 2150003768

STORE NO: CA #1399



REVISION	
Δ	DESCRIPTION
1	12/20/21 PERMIT/IBID SET
A	02/10/22 REVISION A
B	04/26/22 REVISION B
C	05/27/22 REVISION C
1	06/24/22 IFC SET
2	08/03/22 REVISION 2

STATUS: IFC SET



08/10/2022

FIELD VERIFICATION: The contractor shall verify all signed dimensions and condition at the project site and notify Zebra Projects, INC. of any dimensional errors, or omissions or discrepancies, within beginning of fabricating any work. Do not scale these drawings.

COPYRIGHT © 2021: Zebra Projects, INC. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, disclosed or otherwise without the written consent of Zebra Projects, INC.

SHEET NAME: MECHANICAL SPECIFICATIONS

DATE: 12/17/20 PROJECT NO: 34285

DRAWN: MJW SCALE:

SHEET NO: M592

ROOFTOP UNIT CONTROL MATRIX

CONTROL FEATURE	UNITS	RTU-1	RTU-2	NOTES
		DNING SETPOINT OR Y/N	KITCHEN SETPOINT OR Y/N	
COOLING - OCCUPIED SETPOINT		75	75	
COOLING - UNOCCUPIED SETPOINT		80	80	
HEATING - OCCUPIED SETPOINT		70	70	
HEATING - UNOCCUPIED SETPOINT		60	60	
DEHUMIDIFICATION SETPOINT - HUMIDITY SENSOR FEEDBACK		% RH	50%	N B
PROGRAMMED CONTROL FEATURES				
HVAC SYSTEM OCCUPIED/UNOCCUPIED MODE - PROGRAMMABLE THERMOSTAT		Y	Y	B
REMOTE TEMPERATURE SENSOR		N	Y	B
REMOTE COMBINATION TEMPERATURE AND HUMIDITY SENSOR		Y	N	B
EQUIPMENT ACCESSORIES AND CONTROL MODULES				
OUTSIDE AIR DAMPER - MOTOR OPERATED (MODULATING)		Y	Y	L
INTEGRATED ECONOMIZER - DIFFERENTIAL TEMPERATURE ENABLE (OA TEMP < RA TEMP)		Y	Y	E
ECONOMIZER FAULT DETECTION AND DIAGNOSTICS (FDD) SYSTEM		BTULB	Y	F, G
RELIEF - BAROMETRIC DAMPER		Y	N	
RELIEF - VARIABLE VOLUME REVERSE EXHAUST FAN		N	Y	H
COOLING COIL (DX - STAGED)		Y	Y	M
DEHUMIDIFICATION - HOT GAS REHEAT		Y	N	O
HEAT PUMP COIL WITH REVERSING VALVE		Y	Y	M
SUPPLY FAN CONTROL METHODS				
ON DURING OCCUPIED HOURS		Y	Y	
CYCLE WITH LOADS DURING UNOCCUPIED HOURS		Y	Y	
VARIABLE VOLUME - STAGED FAN CONTROL IN RESPONSE TO ACTIVE COOLING COIL STAGES		Y	Y	M, Q
SAFETIES, INTERLOCKS, AND ALARMS				
SUPPLY AIR SMOKE DETECTOR - SAFETY SHUTDOWN		Y	Y	U
FIRE ALARM CONTROL PANEL - SAFETY SHUTDOWN INTERLOCK		Y	Y	
KITCHEN EXHAUST SYSTEM INTERLOCK		Y	Y	S

DIV. 23 CONTRACTOR SHALL PROVIDE CONTROL PANEL(S), WIRING, THERMOSTAT(S), TEMPERATURE SENSOR(S), HUMIDISTAT(S), AND/OR CO2 SENSOR(S) WHERE SHOWN ON THE DRAWINGS AND AS REQUIRED TO FACILITATE THE SCHEDULED CONTROL MODULES AND SEQUENCES OF OPERATION. EACH UNIT SHALL CONTROL BASED ON ITS OWN INTERNAL SAFETIES, TIME DELAYS, AND SEQUENCES UNLESS NOTED OTHERWISE. COORDINATE WITH OWNER FINAL BUILDING AND EQUIPMENT SCHEDULES DURING STARTUP. REFERENCE DIVISION SPECIFICATIONS FOR INDIVIDUAL DEVICE REQUIREMENTS.

- NOTES:
- DIVISION 23 CONTRACTOR SHALL PROVIDE DEVICE.
 - IF SETPOINT VALUE IS LISTED, IT INDICATES ECONOMIZER HIGH-LIMIT SHUTOFF. UNIT SHALL BE IN ECONOMIZER IF CONDITIONS ARE LESS THAN SETPOINT. THE FOLLOWING SENSORS SHALL DETERMINE ECONOMIZER ON POINT: OUTSIDE AIR TEMPERATURE, DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE. RETURN AIR TEMPERATURE, DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE. OUTSIDE AIR HUMIDITY, DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE. RETURN AIR HUMIDITY, DIVISION 23 PROVIDED AS PART OF ECONOMIZER CONTROL MODULE.
 - DEVICE SHALL BE FACTORY MOUNTED AND PRE-WIRED FOR SERVICE SUBJECT TO THE ONBOARD CONTROLLER.
 - PROVIDE UNIT WITH AN FDD SYSTEM CONSISTING OF PERMANENTLY INSTALLED OUTSIDE AIR, SUPPLY AIR, AND RETURN AIR TEMPERATURE SENSORS. THE UNIT CONTROLLER SHALL AT A MINIMUM BE CAPABLE OF PROVIDING SYSTEM STATUS OF ECONOMIZER, COMPRESSOR, HEATING, MIXED AIR LOW LIMIT ALARM, AND SENSOR VALUES. EACH OPERATING MODE SHALL BE CAPABLE OF INDEPENDENTLY OPERATING FOR TESTING. THE SYSTEM SHALL REPORT FAULTS TO AN APPLICATION ACCESSIBLE BY SERVICE PERSONNEL. THE FOLLOWING FAULTS SHALL BE DETECTED: AIR TEMPERATURE SENSOR FAILURE, ECONOMIZER ENABLED/DISABLED WHEN ECONOMIZER SHOULD BE OFF, RESPECTIVELY, DAMPER NOT MODULATING, AND EXCESS OUTSIDE AIR.
 - POWERED EXHAUST FAN SHALL STAGE ON AND OFF ACCORDING TO DAMPER POSITION.
 - EQUIPMENT MANUFACTURER SHALL PROVIDE MODULATING DAMPER AND CONTROLS CAPABLE OF ADJUSTING THE DAMPER POSITION TO MAINTAIN THE SCHEDULED OUTSIDE AIR ON THE DRAWINGS ACROSS ALL FAN SPEEDS. DIV. 23 CONTRACTOR SHALL PROGRAM MULTIPLE DAMPER POSITION SETPOINTS IN THE FIELD DURING TESTING AND BALANCING TO MAINTAIN MINIMUM VENTILATION WHEN NOT IN ECONOMIZER. DAMPER SHALL BE CLOSED DURING UNOCCUPIED HOURS.
 - UNITARY CONTROLLER SHALL MODULATE AND/OR CYCLE SUPPLY FAN SPEED SETTING AND COIL CAPACITY STAGES SUBJECT TO THE INTERNAL SAFETIES AND SEQUENCES TO MAINTAIN SCHEDULED SETPOINTS.
 - PROGRAM DEHUMIDIFICATION SEQUENCE BASED ON ZONE AIR HUMIDITY.
 - PROVIDE STAGED FAN CONTROL WITH MINIMUM 2 FAN SPEEDS. LOW SPEED SHALL NOT EXCEED 66% OF FULL SPEED AND SHALL DRAW NO MORE THAN 40% OF FAN POWER AT FULL SPEED. COMPRESSORS SHALL BE CONTROLLED TO MATCH CAPACITY OF 2-STAGE SUPPLY FAN SUCH THAT LEAVING AIR TEMPERATURE REMAINS CONSTANT.
 - INTERLOCK RTU WITH KITCHEN EXHAUST HOOD SYSTEM(S), TO SHUT DOWN UPON SIGNAL FROM HOOD FIRE EXTINGUISHING SYSTEM. INTERLOCK RTU WITH KITCHEN EXHAUST FAN TO EMERGENCY WHEN HOOD SYSTEM IS ENERGIZED FOR PRESSURIZATION.
 - DIVISION 28 CONTRACTOR SHALL PROVIDE DEVICE.

HEAT PUMP ROOFTOP UNIT SCHEDULE

MARK	MANUFACTURER	MODEL	NOMINAL TONS	UNIT TYPE	SUPPLY FAN										COOLING COIL										HEAT PUMP HEATING COIL										AUXILIARY HEATING COIL										MIN VPH	ELECTRICAL	DISC TYPE	WEIGHT (LBS)	NOTES
					CFM	ESP (IN)	BHP (HP)	VFD (Y/N)	TH (IN/SH)	SH (IN/SH)	EAT (°F DB)	REFR (R410A)	MIN EFF (SEER)	MIN NO (STAGES)	MIN CAP (MBH)	AMBIENT (°F DB)	EAT (°F DB)	LAT (°F DB)	REFR (R410A)	MIN EFF (SEER)	MIN NO (STAGES)	MIN CAP (MBH)	AMBIENT (°F DB)	EAT (°F DB)	LAT (°F DB)	REFR (R410A)	MIN EFF (SEER)	MIN NO (STAGES)	MIN CAP (MBH)	AMBIENT (°F DB)	EAT (°F DB)	LAT (°F DB)	REFR (R410A)																
RTU-1	CAPTIVEAIRE	CASRTU2-18-BT-DOAS	8	SINGLE ZONE	3,200	0.75	1.8	3.0	N	88.3	75.5	77.8	64.0	35.3	34.8	R410A	20.2	2	99.5	35	29.2	85	3.6	47.77	14	1	1280	4603	24.4	25	NF	1849	A-R																
RTU-2	CAPTIVEAIRE	CASRTU2-18-10T-DOAS	10	SINGLE ZONE	4,050	0.75	3.6	5.0	N	114.2	97.5	75.5	61.8	53.6	51.9	R410A	18.6	2	113.4	35	67.3	93.2	3.2	44.36	13	1	310	4603	32.5	35	NF	1901	A-R																

*EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION. MODEL NUMBERS AND NOMINAL TONS LISTED SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER, MODEL NUMBERS, OR NOMINAL TONS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:

- REFER TO ROOFTOP UNIT CONTROL MATRIX FOR ADDITIONAL UNIT FEATURES, COMPONENTS, MODULES, ACCESSORIES, AND CONTROLS THAT SHALL BE PROVIDED WITH THE EQUIPMENT.
- EQUIPMENT SIZED FOR 95°F AMBIENT TEMPERATURE.
- PROVIDE 2" MERV 13, EFFICIENT PLEATED THROWAWAY AIR FILTERS.
- PROVIDE FACTORY MOUNTED DISCONNECT INSTALLED ON SERVICE SIDE OF UNIT.
- STARTERS FOR ALL MOTORS SHALL BE FURNISHED INTEGRAL WITH UNIT.
- PROVIDE 2-SPEED MOTOR TO FACILITATE STAGED FAN SPEED CONTROL.
- PROVIDE SINGLE POINT POWER CONNECTION.
- COORDINATE SIZE OF CONDUCTOR TERMINATION LUGS WITH CONDUCTOR SIZES SHOWN ON ELECTRICAL DRAWINGS.
- PROVIDE 125 VAC, 20 AMP DUPLEX CONVENIENCE RECEPTACLE MOUNTED TO UNIT READY FOR FIELD WIRING WITH A COVER UL LISTED FOR WET AND DAMPER LOCATIONS WHEN IN USE.
- SPECIFIED FAN ESP ACCOUNTS FOR DUCT LOSSES EXTERNAL TO UNIT.
- PROVIDE MOTOR HORSEPOWER TO OVERCOME INTERNAL UNIT STATIC PRESSURE DROP PLUS SPECIFIED EXTERNAL STATIC PRESSURE DROP. NOMINAL MOTOR HP SHALL BE NO LARGER THAN THE FIRST AVAILABLE NOMINAL MOTOR SIZE GREATER THAN THE REQUIRED BHP.
- PROVIDE INSULATED ROOF CURB WITH MINIMUM HEIGHT REQUIRED TO MAINTAIN BOTTOM OF EQUIPMENT A MINIMUM OF 8 INCHES ABOVE FINISHED ROOF SURFACE. PROVIDE SLOPED CURB IF NEEDED TO MATCH ROOF SLOPE.
- COORDINATE WITH ROOF INSULATION THICKNESS AND ROOF TAPER AT INSTALLED LOCATION. COORDINATE CURB TYPE WITH DRAWINGS.
- SCHEDULED WEIGHT IS THE MAXIMUM ALLOWABLE OPERATING WEIGHT OF THE EQUIPMENT AND CURB.
- COOLING COIL LAT IS LEAVING AIR TEMPERATURE OF COIL.
- PROVIDE GUARDS TO PROTECT CONDENSER COIL FROM HAIL OR OTHER DAMAGE.
- TOTAL HEATING CAPACITY INCLUDES THE HEAT PUMP HEATING COIL CAPACITY AT THE AMBIENT DRY BULB TEMPERATURE LISTED. HEAT PUMP HEATING COIL MINIMUM EFFICIENCY IS CALCULATED AT 47°F.
- CONTRACTOR TO COORDINATE WITH NATIONAL TAB TO PROVIDE UV-PHI INDOOR AIR PURIFICATION SYSTEM, PHI CELL MODEL NO. PHI-PKG14-24V IN BLOWER CABINET.
- PROVIDE A FACTORY APPLIED COIL CORROSION COATING TO CONDENSER COIL WHICH IS CAPABLE OF WITHSTANDING GREATER THAN 6,000 HOURS OF THE ASTM B117 SALT SPRAY TEST.

BUILDING AIR BALANCE SUMMARY NORMAL OPERATION

UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/S
MAU-1	1,700	1,700	--	100%
RTU-1	3,200	1,260	--	39%
RTU-2	4,050	310	--	8%
FCU-1	420	40	--	10%
KEF-1	--	--	1,714	--
KEF-2	--	--	733	--
EF-1	--	--	450	--
TOTALS	9,370	3,310	2,897	--
TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)				413
PERCENT POSITIVE PRESSURIZATION				12.5%

BUILDING AIR BALANCE SUMMARY ECONOMIZER MODE

UNIT NO.	SUPPLY (CFM)	OUTDOOR (CFM)	EXHAUST (CFM)	PERCENT O/A/S
MAU-1	1,700	1,700	--	100%
RTU-1	3,200	3,200	--	100%
RTU-2	4,050	4,050	--	100%
FCU-1	420	40	--	10%
KEF-1	--	--	1,714	--
KEF-2	--	--	733	--
EF-1	--	--	450	--
BAROMETRIC RELIEF RTU-1	--	--	1,940	--
REF-1	--	--	3,740	--
TOTALS	9,370	8,990	8,577	--
TOTAL AIRFLOW AVAILABLE FOR PRESSURIZATION (CFM)				413
PERCENT POSITIVE PRESSURIZATION				4.6%

FAN COIL UNIT SCHEDULE (HEAT PUMP)

MARK	MANUFACTURER	MODEL	SUPPLY FAN					COOLING COIL					HEAT PUMP HEATING COIL					MIN VPH	ELECTRICAL	DISC TYPE	WEIGHT (LBS)	NOTES	
			CFM	ESP (IN)	NOM HP	TH (IN)	SH (IN)	EAT (°F DB)	REFR (R410A)	MIN EFF (SEER)	MIN NO (STAGES)	MIN CAP (MBH)	AMBIENT (°F DB)	EAT (°F DB)	LAT (°F DB)	REFR (R410A)	MIN EFF (SEER)						MIN NO (STAGES)
FCU-1	CARRIER	40MBC018-3	420	0.025	0.06	9.6	9.1	75.5	62.0	55.9	54.3	R410A	12.2	35.0	66.6	90	40	2081	N/A	N/A	NF	45	A-1

*EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION. MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:

- EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE, REF ARCHITECTURAL DRAWINGS.
- ASSOCIATED CONDENSING UNIT SHALL BE BY THE SAME MANUFACTURER.
- FOR COOLING, EQUIPMENT SIZED FOR 95°F AMBIENT TEMPERATURE. HEAT PUMP HEATING CAPACITY BASED ON AMBIENT TEMPERATURE LISTED.
- PROVIDE UNIT WITH CLEANABLE AIR FILTERS.
- PROVIDE FACTORY MOUNTED STARTER AND DISCONNECT SWITCH INSTALLED ON SERVICE SIDE OF UNIT.
- PROVIDE SINGLE POINT POWER CONNECTION.
- PROVIDE WITH SPRING VIBRATION ISOLATION AND ALL-THREAD HANGING RODS.
- REFERENCE PLUMBING PLANS FOR CONDENSATE DRAIN PIPING FROM UNIT.

HEAT PUMP CONDENSING UNIT SCHEDULE

MARK	SERVICE	MANUFACTURER	MODEL	REFR TYPE	COOLING CAPACITY					HEATING CAPACITY					MIN VPH	ELECTRICAL	WEIGHT (LBS)	NOTES
					TH (IN)	SH (IN)	EAT (°F DB)	REFR (R410A)	MIN EFF (SEER)	MIN NO (STAGES)	MIN CAP (MBH)	AMBIENT (°F DB)	EAT (°F DB)	LAT (°F DB)				
CU-1	FCU-1	CARRIER	38MAR901AA3	R410A	9.6	82.0	19.0	12.2	35.0	3.3	18	25	2081	102.5	A-1			

*EQUIPMENT SHALL BE OBTAINED THROUGH SHAKE SHACK NATIONAL ACCOUNT. REFER TO T002 / VENDOR LIST FOR MORE INFORMATION. MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:

- EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE, REF ARCHITECTURAL DRAWINGS.
- EQUIPMENT CAPACITY SCHEDULED IS MINIMUM CAPACITY THAT MUST BE PROVIDED AT AMBIENT TEMPERATURE INDICATED.
- CONTRACTOR SHALL VERIFY WITH EQUIPMENT SUPPLIER EXACT QUANTITY AND SIZE OF REFRIGERANT PIPING.
- PROVIDE LIQUID LINE FILTER DRYER AND SIGHT GLASS.
- PROVIDE PREFABRICATED EQUIPMENT SUPPORT RAILS.
- PROVIDE FACTORY MOUNTED DISCONNECT INSTALLED ON SERVICE SIDE OF UNIT.
- STARTERS FOR ALL MOTORS SHALL BE FURNISHED INTEGRAL WITH UNIT.
- COORDINATE SIZE OF CONDUCTOR TERMINATION LUGS WITH CONDUCTOR SIZES SHOWN ON ELECTRICAL DRAWINGS.
- PROVIDE A FACTORY APPLIED COIL CORROSION COATING TO CONDENSER COIL WHICH IS CAPABLE OF WITHSTANDING GREATER THAN 6,000 HOURS OF THE ASTM B117 SALT SPRAY TEST.

GRILLE, REGISTER, AND DIFFUSER SCHEDULE

MARK	MANUFACTURER	SERVICE	MODEL	CONSTRUCTION MATERIAL	FACE TYPE	MOUNTING LOCATION	FACE SIZE (IN)	MAX. NO.	NOTES
CEG1	E.H. PRICE	EXHAUST GRILLE W/ DAMPER	80	STEEL	ECCGRATE	SURFACE	12x12	30	A B C D E F G H
CEG2	E.H. PRICE	EXHAUST GRILLE	80	STEEL	ECCGRATE	LAY-IN	24x24	30	A B C D E F G H
CRG1	E.H. PRICE	RETURN GRILLE	30	STEEL	ECCGRATE	LAY-IN	24x24	30	A B C D E F H
CS01	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	LAY-IN	24x24	30	A B C F H K
CS02	E.H. PRICE	SUPPLY DIFFUSER	PDOR	STEEL	PERFORATED	LAY-IN	24x24	30	A B C F H
CS03	E.H. PRICE	SUPPLY DIFFUSER	SCD	STEEL	SQUARE CONE	SURFACE	12x12	30	A B C F H J K L
WRG1	E.H. PRICE	RETURN GRILLE W/DAMPER	S30D	STEEL	LOUVERED FACE	WALL OR DUCT	(SEE PLANS)	30	A B C D F H
WSR1	E.H. PRICE	SUPPLY REGISTER W/DAMPER	S20D	STEEL	LOUVERED FACE	WALL OR DUCT	(SEE PLANS)	30	A B C D E F G H
LS01	E.H. PRICE	LINEAR SLOT DIFFUSER	S05180	ALUMINUM	LINEAR SLOT	CEILING	(9") SLOT 48" LENGTH	30	A B C F H
PSD1	E.H. PRICE	LINEAR SLOT DIFFUSER	SDB	ALUMINUM	TO FACE		48"	30	A B C F H N

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:

- EQUIPMENT FURNISHED AND INSTALLED PER THE EQUIPMENT RESPONSIBILITY SCHEDULE.
- NECK SIZE SHOWN ON DRAWINGS. PROVIDE BRANCH DUCT TO MATCH NECK SIZE UNLESS OTHERWISE SHOWN ON DRAWINGS.
- DIFFUSERS SHALL BE PREFINISHED TO MATCH CEILING/WALL EXPOSED DUCT COLOR (COORDINATE WITH ARCHITECT).
- FRONT BLADES PARALLEL TO LONG DIMENSION.
- DOUBLE DEFLECTION BARS SHALL BE ADJUSTABLE.
- FRAME TYPE TO MATCH CEILING/WALL CONSTRUCTION. COORDINATE WITH ARCHITECTURAL, REFLECTED CEILING/WALL PLAN.
- PROVIDE OPPOSED BLADE DAMPER ADJUSTABLE FROM FACE OF DEVICE.
- PROVIDE DIFFUSERS, LINEAR SLOTS, AND GRILLES WITH NO EXPOSED MOUNTING SCREWS.
- CONTRACTOR SHALL PROVIDE REMOTE CABLE-OPERATED VOLUME DAMPER BY METROPOLITAN AIR TECHNOLOGIES MODEL RT-250 WITH EXTERNAL WORM GEAR OPERATOR OR EQUIVALENT YOUNG REGULATOR BUTTERFLY DAMPER WITH 270-275 CONTROLLER. OPERATOR SHALL HAVE A SQUARE DRIVE FOR 1/4" NUT DRIVER. DAMPER ASSEMBLY SHALL INCLUDE A SQUARE DRIVE FOR 1/4" NUT DRIVER. DAMPER SHALL BE INSTALLED IN BRANCH DUCT NOT INLET OF PLENUM DIFFUSER.
- 4-WAY THROW PATTERN UNLESS OTHERWISE INDICATED BY FLOW ARROWS ON DRAWINGS.
- PROVIDE RAPID MOUNT FRAME FOR INSTALLATION IN HARD CEILING.
- PROVIDE E.H. PRICE MODEL VORBEK CABLE OPERATED DAMPER.
- SUPPLY PLENUMS SHALL BE FIELD FABRICATED BASED ON DETAIL (RE: 13M501). PROVIDE 1/4" CLOSED CELL INSULATION ON THE INTERIOR OF THE SUPPLY PLENUM.

FAN SCHEDULE

MARK	SERVICE	MANUFACTURER	MOUNTING	MODEL	CFM	ESP (IN)	BHP (HP)	NOM FAN RPM	DRIVE (BELT/DIRECT)	VFD (Y/N)	ELECTRICAL	WEIGHT (LBS)	NOTES			
														TH (IN)	SH (IN)	EAT (°F DB)
EF-1	TAILFAN	GREENHECK	ROOF	GA-80-1	390	0.0	0.1	18	1000	DIRECT	N/A	N/A	A-E			
EF-2	TAILFAN	GREENHECK	ROOF	GA-80-1	390	0.0	0.1	18	1000	DIRECT	N/A	N/A	A-E			

MODEL NUMBERS SHALL NOT BE CONSIDERED COMPLETE AND MATERIAL SHALL NOT BE ORDERED BY MANUFACTURER AND MODEL NUMBERS ONLY. REVIEW THE COMPLETE DESCRIPTION, NOTES AND SPECIFICATIONS TO DETERMINE THE EXACT MATERIAL AND ACCESSORIES TO BE ORDERED. THE MANUFACTURERS LISTED ARE THE BASIS FOR THE DESIGN.

NOTES:

- EQUIPMENT FURNISHED AND INSTALLED PER THE RESPONSIBILITY SCHEDULE, REF ARCHITECTURAL DRAWINGS.
- PROVIDE WITH MINIMUM 12" HIGH ROOF CURB, BIRDSCREEN AND BACKDRAFT DAMPER.
- PROVIDE FACTORY MOUNTED DISCONNECT SWITCH.
- INTERLOCK FAN OPERATION WITH TIME CLOCK.
- PROVIDE WITH MANUFACTURER'S CONVEYOR CONTROLLER FOR BALANCING PURPOSES.
- PROVIDE WITH MANUFACTURER'S CONVEYOR CONTROLLER FOR BALANCING PURPOSES.
- PROVIDE WITH MANUFACTURER'S CONVEYOR CONTROLLER FOR BALANCING PURPOSES.
- PROVIDE WITH MANUFACTURER'S CONVEYOR CONTROLLER FOR BALANCING PURPOSES.

PROJECT DESIGN CONDITIONS

CLIMATE CONDITIONS				BUILDING OPERATING HOURS:			
WEATHER STATION: C.E.C. REGION 3 (NTC200)				MONDAY - FRIDAY: TBD BY OWNER			
CLIMATE ZONE: 3C				SATURDAY: TBD BY OWNER			
HEATING (DB): 99.6% 35.0 °F				SUNDAY: TBD BY OWNER			
COOLING (DB/KNWB): 0.4% 82.0 °F 64.0 °F				HOLIDAY: TBD BY OWNER			

SPACE / UNIT DESCRIPTION	COOLING / DE-HUMIDIFICATION				HEATING				HUMIDIFICATION				ZONE VENTILATION				SPACE OPERATING HOURS OCCUPIED / UNOCCUPIED				NOTES
	OCC	UNOCC	MAX	MIN RH %	OCC	UNOCC	MAX	MIN RH %	MIN	MAX	CONTROL METHOD	BASE	MAXIMUM	M:F	SAT	SUN	A,B,C				
DINING AREAS	75	80	50%	NA	70	60	NA	NA	NA	NA	NA	NA	NA	TBD	TBD	TBD	A,B,C				
OFFICES	75	80	NA	NA	70	60	NA	NA	NA	NA	NA	NA	NA	TBD	TBD	TBD	A,B,C				
STOCKROOMS/STORAGE	75	80	NA	NA	70	60	NA	NA	NA	NA	NA	NA	NA	TBD	TBD	TBD	A,B,C				
FOOD PREP AREAS	75	80	NA	NA	70	60	NA	NA	NA	NA	NA	NA	NA	TBD	TBD	TBD	A,B,C				

NOT

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA
 Report Page: Page 1 of 13
 Date Prepared: 2022-07-26

A. GENERAL INFORMATION

01 Project Location (city)	San Francisco	04 Total Conditioned Floor Area	3,100
02 Climate Zone	3	05 Total Unconditioned Floor Area	0
03 Occupancy Types Within Project:	<input type="checkbox"/> Office (B) <input type="checkbox"/> Retail (M) <input type="checkbox"/> Non-refrigerated Warehouse (S) <input type="checkbox"/> Hotel/ Motel Guest Rooms (R-1) <input type="checkbox"/> School (E) <input type="checkbox"/> Healthcare Facility (I) <input type="checkbox"/> High-Rise Residential (R-2/R-3) <input type="checkbox"/> Relocatable Class Bldg (E) <input checked="" type="checkbox"/> Other (Write In):		

B. PROJECT SCOPE

Table Instructions: Complete the following equipment schedules to show compliance with mandatory requirements found in §110.1 and §110.2(a) and prescriptive requirements found in §140.4(a), §140.4(b) and §140.4(c) or §141.0(b) for alterations.

My project consists of (check all that apply)

01 Heating Air System	<input checked="" type="checkbox"/>	02 Cooling Air System	<input checked="" type="checkbox"/>
03 Mechanical Controls	<input checked="" type="checkbox"/>	04 Fans/Economizers	<input checked="" type="checkbox"/>
05 Mechanical Controls (existing to remain, altered or new)	<input checked="" type="checkbox"/>	06 Chillers	<input type="checkbox"/>
07 Zonal Systems/ Terminal Boxes	<input type="checkbox"/>	08 Boilers	<input type="checkbox"/>

C. COMPLIANCE RESULTS

Table Instructions: If any cell on this table says "DOES NOT COMPLY" or "COMPLIES with Exceptional Conditions" refer to Table D. For guidance.

01 System Summary §110.1, §110.2, §140.4 (See Table F)	02 Pumps §140.4(k) (See Table G)	03 Fans/Economizers §140.4(c), §140.4(e) (See Table H)	04 System Controls §110.2, §120.2, §140.4(f) (See Table I)	05 Ventilation §120.1 (See Table J)	06 Terminal Box Controls §140.4(d) (See Table K)	07 Distribution §120.3, §130.2(e)(2) (See Table L)	08 Cooling Towers §130.2(e)(2) (See Table M)	09 Compliance Results
Yes	AND	AND	AND	AND	AND	AND	AND	COMPLIES
Mandatory Measures Compliance (See Table Q for Details)								COMPLIES

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards/> September 2020

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA
 Report Page: Page 4 of 13
 Date Prepared: 2022-07-26

D. FAN SYSTEMS & AIR ECONOMIZERS

Table Instructions: Complete the following Table to demonstrate compliance with mandatory controls in §110.2 and §120.2 and prescriptive controls in §140.4(i) and (j) or requirements in §141.0(b) for altered space conditioning systems.

Table Continued

01 Fan Name or Item Tag	02 Fan Function	03 Qty	04 Maximum Design Supply Airflow (CFM)	05 HP Unit ¹	06 Design HP	07 Fan Power Pressure Drop Adjustment - Table 140.4-B	08 Design Airflow through Device (CFM)	
RTU-1 Fan	Supply	1	3,200	BHP	1.86	Fully ducted return/ exhaust	3,200	
Total System Design Supply Airflow (CFM):			3,200	Total System Design (BHP):		1.86	Maximum System Fan Power (BHP):	
System Name:		RTU-2	Economizer ¹	Differential Temperature	Economizer Controls:	Designed per §140.4(e) and (m)	System Fan Type:	Constant Volume
01 Fan Name or Item Tag	02 Fan Function	03 Qty	04 Maximum Design Supply Airflow (CFM)	05 HP Unit ¹	06 Design HP	07 Fan Power Pressure Drop Adjustment - Table 140.4-B	08 Design Airflow through Device (CFM)	
RTU-2 Fan	Supply	1	4,050	BHP	3.92	Fully ducted return/ exhaust	4,050	
Total System Design Supply Airflow (CFM):			4,050	Total System Design (BHP):		3.92	Maximum System Fan Power (BHP):	

E. SYSTEM CONTROLS

Table Instructions: Complete the following Table to demonstrate compliance with mandatory controls in §110.2 and §120.2 and prescriptive controls in §140.4(i) and (j) or requirements in §141.0(b) for altered space conditioning systems.

Table Continued

17	Yes	Duct system shall be sealed in accordance with the California Mechanical Code.
The answers to the questions below apply to the following duct system(s):		
11	No	The scope of the project includes only duct systems serving healthcare facilities.
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft ² of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system:
<input type="checkbox"/> Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the U-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)(1) or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawlspace <input type="checkbox"/> In other unconditioned spaces		
15	No	The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.
16	No	The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.
Duct system shall be sealed in accordance with the California Mechanical Code.		
The answers to the questions below apply to the following duct system(s):		
11	No	The scope of the project includes only duct systems serving healthcare facilities.
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft ² of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system:
<input type="checkbox"/> Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the U-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)(1) or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawlspace <input type="checkbox"/> In other unconditioned spaces		
15	No	The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.
16	No	The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.
Duct system shall be sealed in accordance with the California Mechanical Code.		
The answers to the questions below apply to the following duct system(s):		
11	No	The scope of the project includes only duct systems serving healthcare facilities.

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards/> September 2020

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA
 Report Page: Page 7 of 13
 Date Prepared: 2022-07-26

F. COOLING TOWERS

Table Instructions: Complete the following Table to demonstrate compliance with mandatory controls in §110.2 and §120.2 and prescriptive controls in §140.4(i) and (j) or requirements in §141.0(b) for altered space conditioning systems.

Table Continued

17	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft ² of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system:
<input type="checkbox"/> Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the U-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)(1) or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawlspace <input type="checkbox"/> In other unconditioned spaces		
15	No	The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.
16	No	The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.
Duct system shall be sealed in accordance with the California Mechanical Code.		
The answers to the questions below apply to the following duct system(s):		
11	No	The scope of the project includes only duct systems serving healthcare facilities.
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.
13	Yes	The space conditioning system serves less than 5,000 ft ² of conditioned floor area.
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system:
<input type="checkbox"/> Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the U-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)(1) or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawlspace <input type="checkbox"/> In other unconditioned spaces		
15	No	The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.
16	No	The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.
Duct system shall be sealed in accordance with the California Mechanical Code.		
The answers to the questions below apply to the following duct system(s):		
11	No	The scope of the project includes only duct systems serving healthcare facilities.

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards/> September 2020

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA
 Report Page: Page 2 of 13
 Date Prepared: 2022-07-26

D. EXCEPTIONAL CONDITIONS

This table is auto-filled with uneditable comments because of selections made or data entered in tables throughout the form.

Table H indicates a Fan Power System Index that exceeds the maximum allowed per §140.4(c). Please revise to demonstrate compliance. Selections made in Table O have been changed by the permit applicant. See Table E. Additional Remarks for permit applicant's explanation.

E. ADDITIONAL REMARKS

This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.

F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)

Table Instructions: Complete the following equipment schedules to show compliance with mandatory requirements found in §110.1 and §110.2(a) and prescriptive requirements found in §140.4(a), §140.4(b) and §140.4(c) or §141.0(b) for alterations.

Dry System Equipment Sizing (includes air conditioners, condensers, heat pumps, VRF, furnaces and unit heaters)

01 Name or Item Tag	02 Equipment Category per Tables 110.2	03 Equipment Type per Tables 110.2 & Title 20	04 Smallest Size Available ¹ §140.4(a)	05 Per Design (kBtu/h)	06 Rated (kBtu/h)	07 Supp. Heating Output (kBtu/h)	08 Sensible Per Design (kBtu/h)	09 Rated (kBtu/h)	10 Total Heating Load (kBtu/h)	11 Total Sensible Cooling Load (kBtu/h)
RTU-1	Unitary heat pumps	Air cooled, package (3 phase)	Yes	99.5	72.6	47.8	75.5	84.3	88.3	101.4
RTU-2	Unitary heat pumps	Air cooled, package (3 phase)	Yes	113.4	96.2	44.4	97.5	99.5	114.2	104.1
FCU-1/CU	Unitary heat pumps	Air cooled, split (1 phase)	Yes	11.6	18	0	9	15.6	11.6	9.6

Table Continued

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards/> September 2020

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA
 Report Page: Page 5 of 13
 Date Prepared: 2022-07-26

G. PUMPS

This Section Does Not Apply

H. FAN SYSTEMS & AIR ECONOMIZERS

Table Instructions: Complete the following Table for fan systems to demonstrate compliance with prescriptive requirements found in §140.4(c), §140.4(e) and §140.4(m). First document the system details, then add fans within that system to document compliance with fan power requirements. Fan systems serving only process loads are exempt from these requirements and do not need to be included in Table H.

System Name: RTU-1 Economizer¹ Differential Temperature Economizer Controls. Designed per §140.4(e) and (m) System Fan Type: Constant Volume

Table Continued

I. VENTILATION AND INDOOR AIR QUALITY

Table Instructions: Complete the following Table to demonstrate compliance with mandatory ventilation requirements in §120.1 and §120.2(c)(3) for all nonresidential, high-rise residential and hotel/motel occupancies. For alterations, only ventilation systems being altered within the scope of the permit application need to be documented in this table. In lieu of this table, the required outdoor ventilation rates and airflow may be shown on the plans or the calculations can be presented in a spreadsheet.

01	<input checked="" type="checkbox"/>	Check the box if the project is showing ventilation calculations on the plans, or attaching the calculations instead of completing this table.
02	<input type="checkbox"/>	Check this box if the project includes Nonresidential or Hotel/Motel spaces.
03	<input type="checkbox"/>	Check this box if the project includes new or altered high-rise residential dwelling units.
03	<input type="checkbox"/>	Check the box if the project is using natural ventilation in any spaces to meet required ventilation rates per §120.2(c)(2).

J. TERMINAL BOX CONTROLS

This Section Does Not Apply

K. DISTRIBUTION (DUCTWORK AND PIPING)

Table Instructions: Complete the following tables to show compliance with mandatory pipe insulation requirements found in §120.3 and prescriptive requirements found in §140.4(i) for duct leakage testing.

Duct Leakage Sealing

The answers to the questions below apply to the following duct system(s):

11	No	The scope of the project includes only duct systems serving healthcare facilities.	RTU-1 Supply Air Ductwork	Duct leakage testing triggered for these systems?	No
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.			
13	Yes	This space conditioning system serves less than 5,000 ft ² of conditioned floor area.			
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system:			
<input type="checkbox"/> Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the U-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)(1) or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawlspace <input type="checkbox"/> In other unconditioned spaces					
15	No	The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.			
16	No	The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.			

Table Continued

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards/> September 2020

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA
 Report Page: Page 8 of 13
 Date Prepared: 2022-07-26

M. COOLING TOWERS

This Section Does Not Apply

N. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION

Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/Nonresidential_Documents/NRCC/

YES	NO	Form/Title	Systems To Be Field Verified	Field Inspector	Pass	Fail
<input checked="" type="checkbox"/>	<input type="checkbox"/>	NRCC-MCH-01-E - Must be submitted for all buildings.			<input type="checkbox"/>	<input type="checkbox"/>

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards/> September 2020

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA
 Report Page: Page 3 of 13
 Date Prepared: 2022-07-26

O. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE

Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/Nonresidential_Documents/NRCC/

YES	NO	Form/Title	Systems To Be Field Verified	Field Inspector	Pass	Fail
<input checked="" type="checkbox"/>	<input type="checkbox"/>	NRCC-MCH-02-A Outdoor Air must be submitted for all newly installed HVAC units. Note: MCH02-A can be performed in conjunction with MCH-07-A Supply Fan VFD Acceptance (if applicable) since testing activities overlap.	RTU-1; RTU-2		<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input checked="" type="checkbox"/>	NRCC-MCH-03-A Constant Volume Single Zone HVAC NOTE: This form does not automatically move to "Yes". If Constant Volume Single Zone HVAC Systems are included in the scope, permit applicant should move this form to "Yes".			<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input checked="" type="checkbox"/>	NRCC-MCH-04-A Air Distribution Duct Leakage			<input type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	<input type="checkbox"/>	NRCC-MCH-05-A Air Economizer Controls	RTU-1; RTU-2		<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input checked="" type="checkbox"/>	NRCC-MCH-06-A Demand Control Ventilation Systems Acceptance must be submitted for all systems required to employ demand controlled ventilation (refer to §120.1(c)(3) can vary outdoor ventilation flow rates based on maintaining interior carbon dioxide (CO2) concentration setpoints.			<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input checked="" type="checkbox"/>	NRCC-MCH-07-A Supply Fan Variable Flow Controls			<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input checked="" type="checkbox"/>	NRCC-MCH-08-A Valve Leakage Test			<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input checked="" type="checkbox"/>	NRCC-MCH-09-A Supply Water Temperature Reset Controls			<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input checked="" type="checkbox"/>	NRCC-MCH-10-A Hydronic System Variable Flow Controls			<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input checked="" type="checkbox"/>	NRCC-MCH-11-A Automatic Demand Shed Controls			<input type="checkbox"/>	<input type="checkbox"/>

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards/> September 2020

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA
 Report Page: Page 6 of 13
 Date Prepared: 2022-07-26

P. TERMINAL BOX CONTROLS

This Section Does Not Apply

Q. TERMINAL BOX CONTROLS

This Section Does Not Apply

R. DISTRIBUTION (DUCTWORK AND PIPING)

Table Instructions: Complete the following tables to show compliance with mandatory pipe insulation requirements found in §120.3 and prescriptive requirements found in §140.4(i) for duct leakage testing.

Duct Leakage Sealing

The answers to the questions below apply to the following duct system(s):

11	No	The scope of the project includes only duct systems serving healthcare facilities.	RTU-1 Supply Air Ductwork	Duct leakage testing triggered for these systems?	No
12	Yes	Duct system provides conditioned air to an occupiable space for a constant volume, single zone, space-conditioning system.			
13	Yes	This space conditioning system serves less than 5,000 ft ² of conditioned floor area.			
14	No	The combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system:			
<input type="checkbox"/> Outdoors <input type="checkbox"/> In a space directly under a roof that has a U-factor greater than the U-factor of the ceiling, or if the roof does not meet the requirements of §140.3(a)(1) or if the roof has fixed vents or openings to the outside/unconditioned spaces <input type="checkbox"/> In an unconditioned crawlspace <input type="checkbox"/> In other unconditioned spaces					
15	No	The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.			
16	No	The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verification and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.			

Table Continued

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards/> September 2020

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA
 Report Page: Page 9 of 13
 Date Prepared: 2022-07-26

S. REVISIONS

DATE	DESCRIPTION
12/20/21	PERMIT/FBD SET
02/10/22	REVISION A
04/26/22	REVISION B
05/27/22	REVISION C
10/24/22	IFC SET
10/03/22	REVISION 2

STATUS: IFC SET

08/10/2022

FIELD VERIFICATION: The contractor shall verify all signed dimensions and location at the project site and notify Zebra Projects, Inc. of any dimensional errors, or omissions or discrepancies, within 48 hours of beginning any work. Do not scale these drawings.

COPYRIGHT © 2021: Zebra Projects, Inc. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, disclosed or otherwise used without the written consent of Zebra Projects, Inc.


SHEET NAME: MECHANICAL ENERGY CODE COMPLIANCE

DATE: 12/18/20 PROJECT NO: 34285

DRAWN: MLW SCALE:

SHEET NO: M630

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards/> September 2020



STORE NO: CA #1399



REVISION

DATE	DESCRIPTION
12/20/21	PERMIT/FBD SET
02/10/22	REVISION A
04/26/22	REVISION B
05/27/22	REVISION C
10/24/22	IFC SET
10/03/22	REVISION 2



FIELD VERIFICATION: The contractor shall verify all signed dimensions and location at the project site and notify Zebra Projects, Inc. of any dimensional errors, or omissions or discrepancies, within 48 hours of beginning any work. Do not scale these drawings.

COPYRIGHT © 2021: Zebra Projects, Inc. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, disclosed or otherwise used without the written consent of Zebra Projects, Inc.

SHEET NAME: MECHANICAL ENERGY CODE COMPLIANCE

DATE: 12/18/20 PROJECT NO: 34285

DRAWN: MLW SCALE:

SHEET NO: M630

M630

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA Report Page: NRCC-MCH-E Page 13 of 13
 Project Address: Report Date Prepared: 2022-07-26

<input type="radio"/>	<input checked="" type="radio"/>	NRCA-MCH-12-A FDD for Packaged Direct Expansion Units		<input type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="radio"/>	<input type="radio"/>	NRCA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance	RTU-1 ; RTU-2 ; FCU-1/CU-1	<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCA-MCH-14-A Distributed Energy Storage DX AC Systems Acceptance NOTE: This form does not automatically move to "Yes". If Distributed Energy Storage DX AC Systems are included in the scope, permit applicant should move this form to "Yes".		<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCA-MCH-15-A Thermal Energy Storage (TES) System Acceptance NOTE: This form does not automatically move to "Yes". If Chilled Water Storage, Ice-on-Coil Internal Melt, Ice-on-Coil External Melt, Ice Harvester, Brine, Ice Slurry, Eutectic Salt, Clathrate Hydrate Slurry (CHS), Cryogenic or Encapsulated (Ice Ball) Systems are included in the scope, permit applicant should move this form to "Yes".		<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCA-MCH-16-A Supply Air Temperature Reset Controls		<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCA-MCH-17-A Condenser Water Temperature Reset Controls		<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCA-MCH-18 Energy Management Control Systems		<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCA-MCH-19 Occupancy Sensor Controls		<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCA-MCH-20 Multi-Family Ventilation		<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCA-MCH-21 Multi-Family Envelope Leakage		<input type="checkbox"/>	<input type="checkbox"/>

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards> September 2020

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA Report Page: NRCC-MCH-E Page 13 of 13
 Project Address: Report Date Prepared: 2022-07-26

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT
 I, I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Dalton Jueneemann Documentation Author Signature: *Dalton Jueneemann*
 Company: Henderson Engineers Signature Date: 07/28/2022
 Address: 8345 Lenexa Drive CEA/HERS Certification Identification (if applicable): NA
 City/State/Zip: Lenexa, KS 66214 Phone: 913-742-5000

RESPONSIBLE PERSON'S DECLARATION STATEMENT
 I certify the following under penalty of perjury, under the laws of the State of California:
 1. The information provided on this Certificate of Compliance is true and correct.
 2. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer).
 3. The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.
 4. The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application.
 5. I will ensure that a completed signed copy of this Certificate of Compliance shall be made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable inspections. I understand that a completed signed copy of this Certificate of Compliance is required to be included with the documentation the builder provides to the building owner at occupancy.

Responsible Designer Name: Joshua N. Hover Responsible Designer Signature: *J. Hover*
 Company: Henderson Engineers Date Signed: 08/10/2022
 Address: 8345 Lenexa Drive License: 38635
 City/State/Zip: Lenexa, KS 66214 Phone: 913-742-5000

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards>

STATE OF CALIFORNIA
Process Systems
 NRCC-PRC-E CALIFORNIA ENERGY COMMISSION
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA Report Page: NRCC-PRC-E Page 3 of 5
 Project Address: Report Date Prepared: 2021-12-07T15:33:41-05:00

K. ELEVATOR LIGHTING AND VENTILATION
 This section does not apply to this project.

L. ESCALATORS AND MOVING WALKWAYS SPEED CONTROLS
 This section does not apply to this project.

M. COMPUTER ROOM SYSTEM SUMMARY
 This section does not apply to this project.

N. COMMERCIAL KITCHEN EXHAUST AND VENTILATION
 This table contains all new and replacement hoods being installed within the scope of the permit application. Table N is used to demonstrate compliance with prescriptive requirements found in §140.9(b).
Kitchen Ventilation §140.9(b)2

01	<input type="checkbox"/>	Existing kitchen hoods not being replaced as part of an addition or alteration (do not need to meet requirements)
Requirements		
02	<input type="checkbox"/>	Replacement Air to Hood Compliance Method §140.9(b)1A Not providing replacement air directly to the hood(s)
03	<input type="checkbox"/>	Mechanically cooled or heated makeup air delivered to any space with a kitchen hood is designed per 140.9(b)2A to not exceed the greater of: The supply flow required to meet the space heating and cooling load
04	<input type="checkbox"/>	Location that is supplying transfer air
05	<input type="checkbox"/>	The kitchen/dining facility has a total Type I and Type II kitchen hood exhaust airflow > 5000 cfm and is designed to have one of the following per 140.9(b)2B: A minimum of 75% of makeup air volume having a total of no more than 60 °F and uncooled or cooled without the use of mechanical cooling

Registration Number: Registration Date/Time: Registration Provider: Energy Code Ace
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2021-12-07 12:33:47

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA Report Page: NRCC-MCH-E Page 11 of 13
 Project Address: Report Date Prepared: 2022-07-26

P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION
 Table Instructions: Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E. Additional Remarks: These documents must be provided to the building inspector during construction. The final documents must be created by a HERS Providers registry, but drafts can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/Nonresidential_Documents/NRCV/

YES	NO	Form/Title	Field Inspector	
			Pass	Fail
<input type="radio"/>	<input checked="" type="radio"/>	NRCC-MCH-04-H Duct Leakage Test NOTE: Must be completed by a HERS Rater	<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCC-MCH-24 Enclosure Air Leakage Worksheet NOTE: Must be completed by a HERS Rater	<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCC-MCH-27 High-rise Residential NOTE: Must be completed by a HERS Rater	<input type="checkbox"/>	<input type="checkbox"/>
<input type="radio"/>	<input checked="" type="radio"/>	NRCC-MCH-32 Local Mechanical Exhaust NOTE: Must be completed by a HERS Rater	<input type="checkbox"/>	<input type="checkbox"/>

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards> September 2020

STATE OF CALIFORNIA
Process Systems
 NRCC-PRC-E CALIFORNIA ENERGY COMMISSION
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA Report Page: NRCC-PRC-E Page 4 of 5
 Project Address: Report Date Prepared: 2021-12-07T15:33:41-05:00

A. GENERAL INFORMATION

01 Project Location (city)	San Francisco	04 Total Conditioned Floor Area	3100
02 Climate Zone	3	05 Total Unconditioned Floor Area	0
03 Occupancy Types Within Project:		06 # of Stories (Habitable Above Grade)	1
<input type="checkbox"/> Office	<input type="checkbox"/> Retail	<input type="checkbox"/> Non-refrigerated Warehouse	
<input type="checkbox"/> Hotel/ Motel	<input type="checkbox"/> School	<input type="checkbox"/> Healthcare Facility	
<input type="checkbox"/> High-Rise Residential	<input type="checkbox"/> Relocatable Class Bldg	<input checked="" type="checkbox"/> Other (write in)	

B. PROJECT SCOPE
 This table includes process systems that are within the scope of the permit application and are demonstrating compliance with mandatory requirements in §120.6 or prescriptive requirements in §140.5.
 My project consists of: (check all that apply):

01	02
<input type="checkbox"/> Refrigerated Spaces <3,000 ft² Total (no Title 24, P16 requirements)	<input type="checkbox"/> Elevator Lighting & Ventilation Controls (mandatory §120.6(f))
<input type="checkbox"/> Refrigerated Spaces >=3,000 ft² Total (mandatory §120.6(a))	<input type="checkbox"/> Escalator & Moving Walkway Speed Controls (mandatory §120.6(g))
<input type="checkbox"/> Food Stores >=8,000 ft² cfa (mandatory §120.6(b))	<input type="checkbox"/> Computer Rooms >20 WJ/ft² Power Density (prescriptive §140.9(a)) ¹
<input type="checkbox"/> Enclosed Parking Garage Exhaust >=10,000 cfm (mandatory §120.6(c))	<input checked="" type="checkbox"/> Commercial Kitchen Ventilation/Exhaust (prescriptive §140.9(b)) ¹
<input type="checkbox"/> Newly Installed Process Boilers (mandatory §120.6(d))	<input type="checkbox"/> Laboratory Exhaust/Factory Exhaust & Fume Hood (prescriptive §140.9(c)) ¹
<input type="checkbox"/> Compressed Air Systems Combined HP >= 25 (mandatory §120.6(e))	

¹ FOOTNOTES: These building features can comply using the performance method. If using the performance method for these features, compliance should be demonstrated on the NRCC-PRF-E.

Registration Number: Registration Date/Time: Registration Provider: Energy Code Ace
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2021-12-07 12:33:47

STATE OF CALIFORNIA
Process Systems
 NRCC-PRC-E CALIFORNIA ENERGY COMMISSION
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA Report Page: NRCC-PRC-E Page 4 of 5
 Project Address: Report Date Prepared: 2021-12-07T15:33:41-05:00

N. COMMERCIAL KITCHEN EXHAUST AND VENTILATION
Kitchen Exhaust: Airflow Rate §140.9(b)1B

01	02	03	04	05	06	07	08
Kit Name or Item Tag	Kitchen	Compliance Method per §140.9(b)1B	NA: Kitchen/dining facility has a total Type I and Type II kitchen hood exhaust airflow rate <= 5,000 cfm				
Name or Item Tag	Hood Type ¹	Hood Style	Hood Length (ft)	Equipment Duty	Design Hood Exhaust Rate CFM	Max Hood Exhaust Rate Allowed CFM	
Hood 1-1	Type I				1714		
Hood 1-2	Type I				733		

¹ FOOTNOTES: Type II hoods do not have a max hood exhaust air rate per §140.9(b)1B

O. LABORATORY AND FACTORY EXHAUST AND FUME HOODS
 This section does not apply to this project.

P. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION
 Selections have been made based on information provided in this document. If any selection have been changed by permit applicant, an explanation should be included in Table E. Additional Remarks: These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/Nonresidential_Documents/NRCV/

Form/Title	Field Inspector	
	Pass	Fail
NRCC-PRC-01-E - Covered Process	<input type="checkbox"/>	<input type="checkbox"/>

Q. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE
 Selections have been made based on information provided in this document. If any selection have been changed by permit applicant, an explanation should be included in Table E. Additional Remarks: These documents must be provided to the building inspector during construction and must be completed through an Acceptance Test Technician Certification Provider (ATTCP). For more information visit: <http://www.energy.ca.gov/title24/attcp/providers.html>

Form/Title	Systems/Spaces To Be Field Verified	Field Inspector	
		Pass	Fail
NRCC-PRC-02-F Kitchen Exhaust	Kitchen	<input type="checkbox"/>	<input type="checkbox"/>

Registration Number: Registration Date/Time: Registration Provider: Energy Code Ace
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2021-12-07 12:33:47

STATE OF CALIFORNIA
Mechanical Systems
 NRCC-MCH-E (Created 09/2020)
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA Report Page: NRCC-MCH-E Page 12 of 13
 Project Address: Report Date Prepared: 2022-07-26

R. MANDATORY MEASURES DOCUMENTATION LOCATION
 Table Instructions: Indicate where mandatory measures are documented in the plan set or construction documentation. For any mandatory measures that do not apply, mark the plan sheet or construction document location as "N/A", any active cells that are left blank will result in non-compliance in Table C.

01	02
Compliance with Mandatory Measures documented through MCH Mandatory Measures Note Block:	Plan sheet or construction document location
Yes	M601

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance: <http://www.energy.ca.gov/title24/2019standards> September 2020

STATE OF CALIFORNIA
Process Systems
 NRCC-PRC-E CALIFORNIA ENERGY COMMISSION
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA Report Page: NRCC-PRC-E Page 2 of 5
 Project Address: Report Date Prepared: 2021-12-07T15:33:41-05:00

C. COMPLIANCE RESULTS
 Results in this table are automatically calculated from data input and calculations in Tables F through O. Note: If any cell on this table says "COMPLIES with Exceptional Conditions" refer to Table D. Exceptional Conditions for guidance or see applicable Table referenced below.

01	02	03	04	05	06	07	08	09	10	11	Compliance Results
Refrigerated Warehouse/Space §120.6(a) (See Table F)	Commercial Refrigeration Space §120.6(b) (See Table G)	Parking Garage Exhaust §120.6(c) (See Table H)	Process Boilers §120.6(d) (See Table I)	Compressed Air Systems §120.6(e) (See Table J)	Elevators §120.6(f) (See Table K)	Escalators & Moving Walkways §120.6(g) (See Table L)	Computer Rooms §140.9(a) (See Table M)	Commercial Kitchens §140.9(b) (See Table N)	Laboratory/Factory Exhaust §140.9(c) (See Table O)		COMPLIES

D. EXCEPTIONAL CONDITIONS
 This table is auto-filled with uneditable comments because of selections made or data entered in tables throughout the form.

E. ADDITIONAL REMARKS
 This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.

F. REFRIGERATED WAREHOUSES/SPACES
 This section does not apply to this project.

G. COMMERCIAL REFRIGERATION
 This section does not apply to this project.

H. ENCLOSED PARKING GARAGE EXHAUST
 This section does not apply to this project.

I. PROCESS BOILER
 This section does not apply to this project.

J. COMPRESSED AIR SYSTEMS
 This section does not apply to this project.

Registration Number: Registration Date/Time: Registration Provider: Energy Code Ace
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2021-12-07 12:33:47

STATE OF CALIFORNIA
Process Systems
 NRCC-PRC-E CALIFORNIA ENERGY COMMISSION
 CERTIFICATE OF COMPLIANCE
 Project Name: Shake Shack Stonestown San Francisco, CA Report Page: NRCC-PRC-E Page 5 of 5
 Project Address: Report Date Prepared: 2021-12-07T15:33:41-05:00

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT
 I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Malvin Warrick Documentation Author Signature: *Malvin Warrick*
 Company: Henderson Engineers Signature Date: 12/07/2021
 Address: 8345 Lenexa Drive CEA/HERS Certification Identification (if applicable): NA
 City/State/Zip: Lenexa, KS 66214 Phone: 913-742-5000

RESPONSIBLE PERSON'S DECLARATION STATEMENT
 I certify the following under penalty of perjury, under the laws of the State of California:
 1. The information provided on this Certificate of Compliance is true and correct.
 2. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer).
 3. The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.
 4. The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application.
 5. I will ensure that a completed signed copy of this Certificate of Compliance shall be made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable inspections. I understand that a completed signed copy of this Certificate of Compliance is required to be included with the documentation the builder provides to the building owner at occupancy.


Responsible Designer Name: Joshua N. Hover Responsible Designer Signature: *J. Hover*
 Company: Henderson Engineers Date Signed: 08/10/2022
 Address: 8345 Lenexa Drive License: 38635
 City/State/Zip: Lenexa, KS 66214 Phone: 913-742-5000

Registration Number: Registration Date/Time: Registration Provider: Energy Code Ace
 CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601 Report Generated: 2021-12-07 12:33:47

REVISION

DATE	DESCRIPTION
12/20/21	PERMIT/FBD SET
02/10/22	REVISION A
04/28/22	REVISION B
05/27/22	REVISION C
06/24/22	IFC SET
08/03/22	REVISION 2

SATUS:
 IFC SET



08/10/2022
 FIELD VERIFICATION:
 The contractor shall verify all signed dimensions and location of the project site and verify Zebra Projects, INC. of any dimensional errors, or omissions or discrepancies before beginning or resuming any work. Do not scale these drawings.
 COPYRIGHT © 2021:
 Zebra Projects, INC. shall retain all common law, statutory and all other reserved rights. Neither the documents nor the information herein is to be reproduced, distributed, photocopied or otherwise without the written consent of Zebra Projects, INC.

SHEET NAME:
 MECHANICAL ENERGY CODE COMPLIANCE

DATE: 12/18/20 PROJECT NO: 34285
 DRAWN: MLW SCALE:

SHEET NO:
 M631